TestAmerica

THE LEADER IN ENVIRONMENTAL TESTING

ANALYTICAL REPORT

TestAmerica Laboratories, Inc.
TestAmerica Richland
2800 George Washington Way
Richland, WA 99352
Tel: (509)375-3131

TestAmerica Job ID: 300-1728-1
TestAmerica Sample Delivery Group: WC0654
Client Project/Site: CHPRC Chemical Hanford

For:
CH2M Hill Plateau Remediation Company
PO BOX 1600
Mail Stop R3-50
Richland, Washington 99352

Attn: CPP Sample Management

Authorized for release by:
12/8/2015 10:31:20 AM
Steven Campbell, Quality Assurance Assistant
steven.campbell@testamericainc.com

Designee for

Whitney Ritari, Project Manager I
(509)375-3131 ext164
whitney.ritari@testamericainc.com

LINKS

Review your project results through TotalAccess

Have a Question? Ask The Expert

Visit us at: www.testamericainc.com

I certify that this Certificate of Analysis is in compliance with the SOW, both technically and for completeness, for other than the conditions detailed in this package. Release of the data contained in this hard copy data package has been authorized by the Laboratory Manager, or a desingee as verified by the attached signature.

The laboratory is accredited to EPA 7196A in Solid and Chemical Materials, per Washington State Department of Ecology this is approved for non-discharge water samples. The sample/ sample duplicate RPD agreement is not applicable if one or both results are elss than five times the MDL.

Table of Contents

Cover Page 1
Table of Contents 2
Definitions/Glossary 3
Case Narrative 4
Chain of Custody 5
Detection Summary 10
Client Sample Results 11
QC Sample Results 13
QC Association Summary 15
Lab Chronicle 16
Method Summary 19
Sample Summary 20
Receipt Checklists 21

Definitions/Glossary

Client: CH2M Hill Plateau Remediation Company
Project/Site: CHPRC Chemical Hanford

TestAmerica Job ID: 300-1728-1
SDG: WC0654

Qualifiers

HPLC/IC

Qualifier	Qualifier Description
U	Analyzed for but not detected.
N	MS, MSD: Spike recovery is outside acceptance limits.
D	The reported value is from a dilution.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
¤	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CNF	Contains no Free Liquid
DER	Duplicate error ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision level concentration
MDA	Minimum detectable activity
EDL	Estimated Detection Limit
MDC	Minimum detectable concentration
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
NC	Not Calculated
ND	Not detected at the reporting limit (or MDL or EDL if shown)
PQL	Practical Quantitation Limit
QC	Quality Control
RER	Relative error ratio
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)

Case Narrative

Job ID: 300-1728-1

Laboratory: TestAmerica Richland

Narrative

Job Narrative
300-1728-1

Comments
No additional comments.

Receipt
The samples were received on 12/2/2015 12:10 PM; the samples arrived in good condition, properly preserved and, where required, on ice. The temperature of the cooler at receipt was 9.6º C.

HPLC/IC
Method 300.0: The matrix spike (MS) recoveries for analytical batch 300-2203 were outside control limits for Orthophosphate as P. Sample matrix interference is suspected because the associated laboratory control sample (LCS) recovery was within acceptance limits.

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

CH2MHill Plateau Remediation Company	CHAIN OF CUSTODY/SAMPLE ANALYSIS REQUEST	C.O.C. # X15-068-051 Page 1 of 1

Collector	J.R. Aguilar/CHPRC	Contact/Requester	WHITLEY, KM	Telephone No.	373-4929
SAF No.	X15-068	Sampling Origin	Hanford Site	Purchase Order/Charge Code	300205
Project Title	300 Area Uranium Sequestration Post Inj	Logbook No.	HNF-N-506 80 / 45	Ice Chest No.	N/A
Shipped To (Lab)	TestAmerica Incorporated, Richland	Method of Shipment	GOVERNMENT VEHICLE	Bill of Lading/Air Bill No.	N/A
Protocol	CERCLA	Priority:	30 Days **PRIORITY**	Offsite Property No.	N/A

POSSIBLE SAMPLE HAZARDS/REMARKS

*Contains Radioactive Material at concentrations that are not be regulated for transportation per 49 CFR/IATA Dangerous Goods Regulations but are not releasable per DOE Order 458.1.

SPECIAL INSTRUCTIONS **Hold Time** Total Activity Exemption: Yes ☑ No ☐

Sample No.	Filter	*	Date	Time	No/Type Container	Sample Analysis	Holding Time	Preservative
B33900	N	W	12-2-15	1151	1x500-mL P	300.0_ANIONS_IC: COMMON; 300.0_ANIONS_IC: GW 01	48 Hours	Cool <=6C

300-1728 COC

#1728
WC0654

Relinquished By	Print	Sign	Date/Time	Received By	Print	Sign	Date/Time
J.R. Aguilar/CHPRC			DEC 0 2 2015 1200	F.M. Hall/CHPRC			DEC 0 2 2015 1200
F.M. Hall/CHPRC			DEC 0 2 2015 1210	J. Friesz, TARL			DEC 0 2 2015 1210
Relinquished By			Date/Time	Received By JF 12/2/15			Date/Time
Relinquished By			Date/Time	Received By			Date/Time

Matrix *

S	= Soil		DS	= Drum Solids	
SE	= Sediment		DL	= Drum Liquids	
SO	= Solid		T	= Tissue	
SL	= Sludge		WI	= Wipe	
W	= Water		L	= Liquid	
O	= Oil		V	= Vegetation	
A	= Air		X	= Other	

FINAL SAMPLE DISPOSITION	Disposal Method (e.g., Return to customer, per lab procedure, used in process)	Disposed By	Date/Time

PRINTED ON 9/30/2015 FSR ID = FSR7345 A-6004-842 (REV 2)

December 08, 2015

CH2MHill Plateau Remediation Company	CHAIN OF CUSTODY/SAMPLE ANALYSIS REQUEST	C.O.C. # X15-068-046 Page 1 of 1

Collector	J.R. Aguilar/CHPRC	Contact/Requester	WHITLEY, KM	Telephone No.	373-4929
SAF No.	X15-068	Sampling Origin	Hanford Site	Purchase Order/Charge Code	300205
Project Title	300 Area Uranium Sequestration Post Inj	Logbook No.	HNF-N-506 80 / 45	Ice Chest No.	N/A
Shipped To (Lab)	TestAmerica Incorporated, Richland	Method of Shipment	GOVERNMENT VEHICLE	Bill of Lading/Air Bill No.	N/A
Protocol	CERCLA	Priority:	30 Days PRIORITY	Offsite Property No.	N/A

POSSIBLE SAMPLE HAZARDS/REMARKS

*Contains Radioactive Material at concentrations that are not be regulated for transportation per 49 CFR/IATA Dangerous Goods Regulations but are not releasable per DOE Order 458.1.

SPECIAL INSTRUCTIONS **Hold Time** Total Activity Exemption: Yes ☑ No ☐

Sample No.	Filter	*	Date	Time	No/Type Container	Sample Analysis	Holding Time	Preservative
B338Y6	N	W	12-2-15	1052	1x500-mL P	300.0_ANIONS_IC: COMMON; 300.0_ANIONS_IC: GW 01	48 Hours	Cool <=6C

#1728
WC0654

Relinquished By	Print	Sign	Date/Time	Received By	Print	Sign	Date/Time
J.R. Aguilar/CHPRC			DEC 0 2 2015 1200	F.M. Hall/CHPRC			DEC 0 2 2015 1200
F.M. Hall/CHPRC			DEC 0 2 2015 1210	J. Friesz, TARL			DEC 0 2 2015 1210

Matrix *

S	= Soil	DS	= Drum Solids		
SE	= Sediment	DL	= Drum Liquids		
SO	= Solid	T	= Tissue		
SL	= Sludge	WI	= Wipe		
W	= Water	L	= Liquid		
O	= Oil	V	= Vegetation		
A	= Air	X	= Other		

FINAL SAMPLE DISPOSITION	Disposal Method (e.g., Return to customer, per lab procedure, used in process)	Disposed By	Date/Time

PRINTED ON 9/30/2015 FSR ID = FSR7344 A-6004-842 (REV 2)

December 08, 2015

CH2MHill Plateau Remediation Company	CHAIN OF CUSTODY/SAMPLE ANALYSIS REQUEST	C.O.C. # X15-068-053 Page 1 of 1

Collector	J.R. Aguilar/CHPRC	Contact/Requester	WHITLEY, KM	Telephone No.	373-4929
SAF No.	X15-068	Sampling Origin	Hanford Site	Purchase Order/Charge Code	300205
Project Title	300 Area Uranium Sequestration Post Inj	Logbook No.	HNF-N-506 80 / 45	Ice Chest No.	N/A
Shipped To (Lab)	TestAmerica Incorporated, Richland	Method of Shipment	GOVERNMENT VEHICLE	Bill of Lading/Air Bill No.	N/A
Protocol	CERCLA	Priority:	30 Days **PRIORITY**	Offsite Property No.	N/A

POSSIBLE SAMPLE HAZARDS/REMARKS

*Contains Radioactive Material at concentrations that are not be regulated for transportation per 49 CFR/IATA Dangerous Goods Regulations but are not releasable per DOE Order 458.1.

SPECIAL INSTRUCTIONS **Hold Time** Total Activity Exemption: Yes ☑ No ☐

Sample No.	Filter	*	Date	Time	No/Type Container	Sample Analysis	Holding Time	Preservative
B338Y2	N	W	12-2-15	1026	1x500-mL P	300.0_ANIONS_IC: COMMON; 300.0_ANIONS_IC: GW 01	48 Hours	Cool <=6C

#1728
WC0654

Relinquished By	Print	Sign	Date/Time	Received By	Print	Sign	Date/Time
J.R. Aguilar/CHPRC			DEC 0 2 2015 1200	F.M. Hall/CHPRC			DEC 0 2 2015 1200
F.M. Hall/CHPRC			DEC 0 2 2015 1210	J. Friesz, TARL			DEC 0 2 2015 1210

Matrix *

S	= Soil		DS	= Drum Solids	
SE	= Sediment		DL	= Drum Liquids	
SO	= Solid		T	= Tissue	
SL	= Sludge		WI	= Wipe	
W	= Water		L	= Liquid	
O	= Oil		V	= Vegetation	
A	= Air		X	= Other	

FINAL SAMPLE DISPOSITION	Disposal Method (e.g., Return to customer, per lab procedure, used in process)	Disposed By	Date/Time

December 08, 2015
7 of 21
12/8/2015
Page 7 of 21

CH2MHill Plateau Remediation Company	CHAIN OF CUSTODY/SAMPLE ANALYSIS REQUEST	C.O.C. # X15-068-041 Page 1 of 1

Collector	S.W. King/CHPRC	Contact/Requester	WHITLEY, KM	Telephone No.	373-4929
SAF No.	X15-068	Sampling Origin	Hanford Site	Purchase Order/Charge Code	300205
Project Title	300 Area Uranium Sequestration Post Inj	Logbook No.	HNF-N-506 81 / 51	Ice Chest No.	N/A
Shipped To (Lab)	TestAmerica Incorporated, Richland	Method of Shipment	GOVERNMENT VEHICLE	Bill of Lading/Air Bill No.	N/A
Protocol	CERCLA	Priority:	30 Days PRIORITY	Offsite Property No.	N/A

POSSIBLE SAMPLE HAZARDS/REMARKS

*Contains Radioactive Material at concentrations that are not be regulated for transportation per 49 CFR/IATA Dangerous Goods Regulations but are not releasable per DOE Order 458.1.

SPECIAL INSTRUCTIONS **Hold Time** Total Activity Exemption: Yes ☑ No ☐

Sample No.	Filter	*	Date	Time	No/Type Container	Sample Analysis	Holding Time	Preservative
B338W2	N	W	DEC 02 2015	1105	1x500-mL P	300.0_ANIONS_IC: COMMON; 300.0_ANIONS_IC: GW 01	48 Hours	Cool <=6C

#1728
WC0654

Relinquished By	Print	Sign	Date/Time	Received By	Print	Sign	Date/Time
S.W. King/CHPRC			DEC 02 2015 1150	F.M. Hall/CHPRC			DEC 02 2015 1150
F.M. Hall/CHPRC			DEC 02 2015 1210	J. Friesz, TARL			DEC 02 2015 1210

Matrix *

S	= Soil		DS	= Drum Solids	
SE	= Sediment		DL	= Drum Liquids	
SO	= Solid		T	= Tissue	
SL	= Sludge		WI	= Wipe	
W	= Water		L	= Liquid	
O	= Oil		V	= Vegetation	
A	= Air		X	= Other	

FINAL SAMPLE DISPOSITION	Disposal Method (e.g., Return to customer, per lab procedure, used in process)	Disposed By	Date/Time

December 08, 2015

CH2MHill Plateau Remediation Company	CHAIN OF CUSTODY/SAMPLE ANALYSIS REQUEST	C.O.C. # X15-068-050 Page 1 of 1

Collector	S.W. King/CHPRC	Contact/Requester	WHITLEY, KM	Telephone No.	373-4929
SAF No.	X15-068	Sampling Origin	Hanford Site	Purchase Order/Charge Code	300205
Project Title	300 Area Uranium Sequestration Post Inj	Logbook No.	HNF-N-506 81/51	Ice Chest No.	N/A
Shipped To (Lab)	TestAmerica Incorporated, Richland	Method of Shipment	GOVERNMENT VEHICLE	Bill of Lading/Air Bill No.	N/A
Protocol	CERCLA	Priority:	30 Days PRIORITY	Offsite Property No.	N/A

POSSIBLE SAMPLE HAZARDS/REMARKS

*Contains Radioactive Material at concentrations that are not be regulated for transportation per 49 CFR/IATA Dangerous Goods Regulations but are not releasable per DOE Order 458.1.

SPECIAL INSTRUCTIONS **Hold Time** Total Activity Exemption: Yes ☑ No ☐

Sample No.	Filter	*	Date	Time	No/Type Container	Sample Analysis	Holding Time	Preservative
B338V8	N	W	DEC 02 2015	1018	1x500-mL P	300.0_ANIONS_IC: COMMON; 300.0_ANIONS_IC: GW 01	48 Hours	Cool <=6C

#1728
W0654

Relinquished By	Print	Sign	Date/Time	Received By	Print	Sign	Date/Time
S.W. King/CHPRC			DEC 02 2015 1150	F.M. Hall/CHPRC			DEC 02 2015 1150
F.M. Hall/CHPRC			DEC 02 2015 1210	J. Friesz, TARL			DEC 02 2015 1210

Matrix *

S	= Soil		DS	= Drum Solids	
SE	= Sediment		DL	= Drum Liquids	
SO	= Solid		T	= Tissue	
SL	= Sludge		WI	= Wipe	
W	= Water		L	= Liquid	
O	= Oil		V	= Vegetation	
A	= Air		X	= Other	

FINAL SAMPLE DISPOSITION	Disposal Method (e.g., Return to customer, per lab procedure, used in process)	Disposed By	Date/Time

December 08 2015

Detection Summary

Client: CH2M Hill Plateau Remediation Company
Project/Site: CHPRC Chemical Hanford

TestAmerica Job ID: 300-1728-1
SDG: WC0654

Client Sample ID: B33900 — Lab Sample ID: 300-1728-1

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Chloride	34	D	0.40	0.20	mg/L	2		300.0	Total/NA
Fluoride	0.17	D	0.10	0.050	mg/L	2		300.0	Total/NA
Sulfate	130	D	1.3	0.63	mg/L	5		300.0	Total/NA

Client Sample ID: B338Y6 — Lab Sample ID: 300-1728-2

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Chloride	18	D	0.40	0.20	mg/L	2		300.0	Total/NA
Nitrate as N	6.4	D	0.056	0.028	mg/L	2		300.0	Total/NA
Fluoride	0.26	D	0.10	0.050	mg/L	2		300.0	Total/NA
Orthophosphate as P	49	D	0.41	0.21	mg/L	5		300.0	Total/NA
Sulfate	53	D	0.50	0.25	mg/L	2		300.0	Total/NA

Client Sample ID: B338Y2 — Lab Sample ID: 300-1728-3

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Chloride	13	D	10	5.0	mg/L	50		300.0	Total/NA
Nitrate as N	5.3	D	1.4	0.70	mg/L	50		300.0	Total/NA
Orthophosphate as P	220	D	4.1	2.1	mg/L	50		300.0	Total/NA
Sulfate	36	D	13	6.3	mg/L	50		300.0	Total/NA

Client Sample ID: B338W2 — Lab Sample ID: 300-1728-4

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Chloride	22	D	20	10	mg/L	100		300.0	Total/NA
Nitrate as N	7.2	D	2.8	1.4	mg/L	100		300.0	Total/NA
Orthophosphate as P	480	D	8.2	4.1	mg/L	100		300.0	Total/NA
Sulfate	46	D	25	13	mg/L	100		300.0	Total/NA

Client Sample ID: B338V8 — Lab Sample ID: 300-1728-5

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Chloride	17	D	10	5.0	mg/L	50		300.0	Total/NA
Nitrate as N	4.8	D	1.4	0.70	mg/L	50		300.0	Total/NA
Orthophosphate as P	120	D	4.1	2.1	mg/L	50		300.0	Total/NA
Sulfate	49	D	13	6.3	mg/L	50		300.0	Total/NA

This Detection Summary does not include radiochemical test results.

Client Sample Results

Client: CH2M Hill Plateau Remediation Company
Project/Site: CHPRC Chemical Hanford

TestAmerica Job ID: 300-1728-1
SDG: WC0654

Client Sample ID: B33900

Lab Sample ID: 300-1728-1
Date Collected: 12/02/15 11:51
Matrix: Water
Date Received: 12/02/15 12:10

Method: 300.0 - Anions, Ion Chromatography

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	34	D	0.40	0.20	mg/L			12/02/15 15:05	2
Nitrate as N	0.028	U	0.056	0.028	mg/L			12/02/15 15:05	2
Fluoride	0.17	D	0.10	0.050	mg/L			12/02/15 15:05	2
Nitrite as N	0.038	U	0.076	0.038	mg/L			12/02/15 15:05	2
Orthophosphate as P	0.082	U N	0.16	0.082	mg/L			12/02/15 15:05	2
Sulfate	130	D	1.3	0.63	mg/L			12/02/15 16:53	5

Client Sample ID: B338Y6

Lab Sample ID: 300-1728-2
Date Collected: 12/02/15 10:52
Matrix: Water
Date Received: 12/02/15 12:10

Method: 300.0 - Anions, Ion Chromatography

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	18	D	0.40	0.20	mg/L			12/02/15 15:50	2
Nitrate as N	6.4	D	0.056	0.028	mg/L			12/02/15 15:50	2
Fluoride	0.26	D	0.10	0.050	mg/L			12/02/15 15:50	2
Nitrite as N	0.038	U	0.076	0.038	mg/L			12/02/15 15:50	2
Orthophosphate as P	49	D	0.41	0.21	mg/L			12/02/15 17:38	5
Sulfate	53	D	0.50	0.25	mg/L			12/02/15 15:50	2

Client Sample ID: B338Y2

Lab Sample ID: 300-1728-3
Date Collected: 12/02/15 10:26
Matrix: Water
Date Received: 12/02/15 12:10

Method: 300.0 - Anions, Ion Chromatography

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	13	D	10	5.0	mg/L			12/02/15 18:08	50
Nitrate as N	5.3	D	1.4	0.70	mg/L			12/02/15 18:08	50
Fluoride	1.3	U	2.5	1.3	mg/L			12/02/15 18:08	50
Nitrite as N	0.95	U	1.9	0.95	mg/L			12/02/15 18:08	50
Orthophosphate as P	220	D	4.1	2.1	mg/L			12/02/15 18:08	50
Sulfate	36	D	13	6.3	mg/L			12/02/15 18:08	50

Client Sample ID: B338W2

Lab Sample ID: 300-1728-4
Date Collected: 12/02/15 11:05
Matrix: Water
Date Received: 12/02/15 12:10

Method: 300.0 - Anions, Ion Chromatography

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	22	D	20	10	mg/L			12/02/15 18:23	100
Nitrate as N	7.2	D	2.8	1.4	mg/L			12/02/15 18:23	100
Fluoride	2.5	U	5.0	2.5	mg/L			12/02/15 18:23	100
Nitrite as N	1.9	U	3.8	1.9	mg/L			12/02/15 18:23	100
Orthophosphate as P	480	D	8.2	4.1	mg/L			12/02/15 18:23	100
Sulfate	46	D	25	13	mg/L			12/02/15 18:23	100

Client Sample Results

Client: CH2M Hill Plateau Remediation Company
Project/Site: CHPRC Chemical Hanford

TestAmerica Job ID: 300-1728-1
SDG: WC0654

Client Sample ID: B338V8

Date Collected: 12/02/15 10:18
Date Received: 12/02/15 12:10

Lab Sample ID: 300-1728-5

Matrix: Water

Method: 300.0 - Anions, Ion Chromatography

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	**17**	**D**	10	5.0	mg/L			12/02/15 18:38	50
Nitrate as N	**4.8**	**D**	1.4	0.70	mg/L			12/02/15 18:38	50
Fluoride	1.3	U	2.5	1.3	mg/L			12/02/15 18:38	50
Nitrite as N	0.95	U	1.9	0.95	mg/L			12/02/15 18:38	50
Orthophosphate as P	**120**	**D**	4.1	2.1	mg/L			12/02/15 18:38	50
Sulfate	**49**	**D**	13	6.3	mg/L			12/02/15 18:38	50

QC Sample Results

Client: CH2M Hill Plateau Remediation Company
Project/Site: CHPRC Chemical Hanford

TestAmerica Job ID: 300-1728-1
SDG: WC0654

Method: 300.0 - Anions, Ion Chromatography

Lab Sample ID: MB 300-2203/17 — **Client Sample ID: Method Blank**
Matrix: Water — **Prep Type: Total/NA**
Analysis Batch: 2203

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Nitrate as N	0.014	U	0.028	0.014	mg/L			12/02/15 14:35	1
Nitrite as N	0.019	U	0.038	0.019	mg/L			12/02/15 14:35	1
Orthophosphate as P	0.041	U	0.082	0.041	mg/L			12/02/15 14:35	1

Lab Sample ID: LCS 300-2203/18 — **Client Sample ID: Lab Control Sample**
Matrix: Water — **Prep Type: Total/NA**
Analysis Batch: 2203

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Nitrate as N	2.26	2.35		mg/L		104	80 - 120
Nitrite as N	3.04	3.17		mg/L		104	80 - 120
Orthophosphate as P	6.53	6.76		mg/L		104	80 - 120

Lab Sample ID: 300-1728-1 MS — **Client Sample ID: B33900**
Matrix: Water — **Prep Type: Total/NA**
Analysis Batch: 2203

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits
Nitrate as N	0.028	U	0.452	0.422	D	mg/L		93	75 - 125
Nitrite as N	0.038	U	0.609	0.542	D	mg/L		89	75 - 125
Orthophosphate as P	0.082	U N	1.31	0.575	D N	mg/L		44	75 - 125

Lab Sample ID: 300-1728-1 DU — **Client Sample ID: B33900**
Matrix: Water — **Prep Type: Total/NA**
Analysis Batch: 2203

Analyte	Sample Result	Sample Qualifier	DU Result	DU Qualifier	Unit	D	RPD	RPD Limit
Nitrate as N	0.028	U	0.028	U	mg/L		NC	20
Nitrite as N	0.038	U	0.038	U	mg/L		NC	20
Orthophosphate as P	0.082	U N	0.082	U	mg/L		NC	20

Lab Sample ID: MB 300-2204/17 — **Client Sample ID: Method Blank**
Matrix: Water — **Prep Type: Total/NA**
Analysis Batch: 2204

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Chloride	0.10	U	0.20	0.10	mg/L			12/02/15 14:35	1
Fluoride	0.025	U	0.050	0.025	mg/L			12/02/15 14:35	1
Sulfate	0.13	U	0.25	0.13	mg/L			12/02/15 14:35	1

Lab Sample ID: LCS 300-2204/18 — **Client Sample ID: Lab Control Sample**
Matrix: Water — **Prep Type: Total/NA**
Analysis Batch: 2204

Analyte	Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits
Chloride	16.0	16.4		mg/L		102	80 - 120
Fluoride	4.00	4.13		mg/L		103	80 - 120
Sulfate	20.0	20.7		mg/L		103	80 - 120

QC Sample Results

Client: CH2M Hill Plateau Remediation Company
Project/Site: CHPRC Chemical Hanford

TestAmerica Job ID: 300-1728-1
SDG: WC0654

Method: 300.0 - Anions, Ion Chromatography (Continued)

Lab Sample ID: 300-1728-1 MS — **Client Sample ID: B33900**
Matrix: Water — **Prep Type: Total/NA**
Analysis Batch: 2204

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits		
Chloride	34	D	3.20	37.2	D	mg/L		103	75 - 125		
Fluoride	0.17	D	0.800	0.944	D	mg/L		96	75 - 125		

Lab Sample ID: 300-1728-1 MS — **Client Sample ID: B33900**
Matrix: Water — **Prep Type: Total/NA**
Analysis Batch: 2204

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits		
Sulfate	130	D	10.0	140	D	mg/L		81	75 - 125		

Lab Sample ID: 300-1728-1 DU — **Client Sample ID: B33900**
Matrix: Water — **Prep Type: Total/NA**
Analysis Batch: 2204

Analyte	Sample Result	Sample Qualifier		DU Result	DU Qualifier	Unit	D			RPD	RPD Limit
Chloride	34	D		34.0	D	mg/L				0.2	20
Fluoride	0.17	D		0.173	D	mg/L				0.1	20

Lab Sample ID: 300-1728-1 DU — **Client Sample ID: B33900**
Matrix: Water — **Prep Type: Total/NA**
Analysis Batch: 2204

Analyte	Sample Result	Sample Qualifier		DU Result	DU Qualifier	Unit	D			RPD	RPD Limit
Sulfate	130	D		132	D	mg/L				0.2	20

QC Association Summary

Client: CH2M Hill Plateau Remediation Company
Project/Site: CHPRC Chemical Hanford

TestAmerica Job ID: 300-1728-1
SDG: WC0654

HPLC/IC

Analysis Batch: 2203

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
300-1728-1	B33900	Total/NA	Water	300.0	
300-1728-1 DU	B33900	Total/NA	Water	300.0	
300-1728-1 MS	B33900	Total/NA	Water	300.0	
300-1728-2	B338Y6	Total/NA	Water	300.0	
300-1728-2	B338Y6	Total/NA	Water	300.0	
300-1728-3	B338Y2	Total/NA	Water	300.0	
300-1728-4	B338W2	Total/NA	Water	300.0	
300-1728-5	B338V8	Total/NA	Water	300.0	
LCS 300-2203/18	Lab Control Sample	Total/NA	Water	300.0	
MB 300-2203/17	Method Blank	Total/NA	Water	300.0	

Analysis Batch: 2204

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
300-1728-1	B33900	Total/NA	Water	300.0	
300-1728-1	B33900	Total/NA	Water	300.0	
300-1728-1 DU	B33900	Total/NA	Water	300.0	
300-1728-1 DU	B33900	Total/NA	Water	300.0	
300-1728-1 MS	B33900	Total/NA	Water	300.0	
300-1728-1 MS	B33900	Total/NA	Water	300.0	
300-1728-2	B338Y6	Total/NA	Water	300.0	
300-1728-3	B338Y2	Total/NA	Water	300.0	
300-1728-4	B338W2	Total/NA	Water	300.0	
300-1728-5	B338V8	Total/NA	Water	300.0	
LCS 300-2204/18	Lab Control Sample	Total/NA	Water	300.0	
MB 300-2204/17	Method Blank	Total/NA	Water	300.0	

Lab Chronicle

Client: CH2M Hill Plateau Remediation Company
Project/Site: CHPRC Chemical Hanford

TestAmerica Job ID: 300-1728-1
SDG: WC0654

Client Sample ID: B33900 — Lab Sample ID: 300-1728-1

Date Collected: 12/02/15 11:51 — **Matrix: Water**
Date Received: 12/02/15 12:10

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		2	10 mL		2203	12/02/15 15:05	CPM	TAL RCH
Total/NA	Analysis	300.0		2	10 mL		2204	12/02/15 15:05	CPM	TAL RCH
Total/NA	Analysis	300.0		5	10 mL		2204	12/02/15 16:53	CPM	TAL RCH

Client Sample ID: B338Y6 — Lab Sample ID: 300-1728-2

Date Collected: 12/02/15 10:52 — **Matrix: Water**
Date Received: 12/02/15 12:10

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		2	10 mL		2203	12/02/15 15:50	CPM	TAL RCH
Total/NA	Analysis	300.0		2	10 mL		2204	12/02/15 15:50	CPM	TAL RCH
Total/NA	Analysis	300.0		5	10 mL		2203	12/02/15 17:38	CPM	TAL RCH

Client Sample ID: B338Y2 — Lab Sample ID: 300-1728-3

Date Collected: 12/02/15 10:26 — **Matrix: Water**
Date Received: 12/02/15 12:10

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		50	10 mL		2203	12/02/15 18:08	CPM	TAL RCH
Total/NA	Analysis	300.0		50	10 mL		2204	12/02/15 18:08	CPM	TAL RCH

Client Sample ID: B338W2 — Lab Sample ID: 300-1728-4

Date Collected: 12/02/15 11:05 — **Matrix: Water**
Date Received: 12/02/15 12:10

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		100	10 mL		2203	12/02/15 18:23	CPM	TAL RCH
Total/NA	Analysis	300.0		100	10 mL		2204	12/02/15 18:23	CPM	TAL RCH

Client Sample ID: B338V8 — Lab Sample ID: 300-1728-5

Date Collected: 12/02/15 10:18 — **Matrix: Water**
Date Received: 12/02/15 12:10

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		50	10 mL		2203	12/02/15 18:38	CPM	TAL RCH
Total/NA	Analysis	300.0		50	10 mL		2204	12/02/15 18:38	CPM	TAL RCH

Lab Chronicle

Client: CH2M Hill Plateau Remediation Company
Project/Site: CHPRC Chemical Hanford

TestAmerica Job ID: 300-1728-1
SDG: WC0654

Client Sample ID: B33900 — Lab Sample ID: 300-1728-1 DU

Date Collected: 12/02/15 11:51 — **Matrix: Water**
Date Received: 12/02/15 12:10

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		2	10 mL		2203	12/02/15 15:35	CPM	TAL RCH
Total/NA	Analysis	300.0		2	10 mL		2204	12/02/15 15:35	CPM	TAL RCH
Total/NA	Analysis	300.0		5	10 mL		2204	12/02/15 17:23	CPM	TAL RCH

Client Sample ID: Lab Control Sample — Lab Sample ID: LCS 300-2203/18

Date Collected: N/A — **Matrix: Water**
Date Received: N/A

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		1	10 mL		2203	12/02/15 14:50	CPM	TAL RCH

Client Sample ID: Lab Control Sample — Lab Sample ID: LCS 300-2204/18

Date Collected: N/A — **Matrix: Water**
Date Received: N/A

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		1	10 mL		2204	12/02/15 14:50	CPM	TAL RCH

Client Sample ID: Method Blank — Lab Sample ID: MB 300-2203/17

Date Collected: N/A — **Matrix: Water**
Date Received: N/A

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		1	10 mL		2203	12/02/15 14:35	CPM	TAL RCH

Client Sample ID: Method Blank — Lab Sample ID: MB 300-2204/17

Date Collected: N/A — **Matrix: Water**
Date Received: N/A

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		1	10 mL		2204	12/02/15 14:35	CPM	TAL RCH

Client Sample ID: B33900 — Lab Sample ID: 300-1728-1 MS

Date Collected: 12/02/15 11:51 — **Matrix: Water**
Date Received: 12/02/15 12:10

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		2	10 mL		2203	12/02/15 15:20	CPM	TAL RCH
Total/NA	Analysis	300.0		2	10 mL		2204	12/02/15 15:20	CPM	TAL RCH
Total/NA	Analysis	300.0		5	10 mL		2204	12/02/15 17:08	CPM	TAL RCH

Lab Chronicle

Client: CH2M Hill Plateau Remediation Company
Project/Site: CHPRC Chemical Hanford

TestAmerica Job ID: 300-1728-1
SDG: WC0654

Laboratory References:

TAL RCH = TestAmerica Richland, 2800 George Washington Way, Richland, WA 99352, TEL (509)375-3131

Method Summary

Client: CH2M Hill Plateau Remediation Company
Project/Site: CHPRC Chemical Hanford

TestAmerica Job ID: 300-1728-1
SDG: WC0654

Method	Method Description	Protocol	Laboratory
300.0	Anions, Ion Chromatography	MCAWW	TAL RCH

Protocol References:

MCAWW = "Methods For Chemical Analysis Of Water And Wastes", EPA-600/4-79-020, March 1983 And Subsequent Revisions.

Laboratory References:

TAL RCH = TestAmerica Richland, 2800 George Washington Way, Richland, WA 99352, TEL (509)375-3131

Sample Summary

Client: CH2M Hill Plateau Remediation Company
Project/Site: CHPRC Chemical Hanford

TestAmerica Job ID: 300-1728-1
SDG: WC0654

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
300-1728-1	B33900	Water	12/02/15 11:51	12/02/15 12:10
300-1728-2	B338Y6	Water	12/02/15 10:52	12/02/15 12:10
300-1728-3	B338Y2	Water	12/02/15 10:26	12/02/15 12:10
300-1728-4	B338W2	Water	12/02/15 11:05	12/02/15 12:10
300-1728-5	B338V8	Water	12/02/15 10:18	12/02/15 12:10

Login Sample Receipt Checklist

Client: CH2M Hill Plateau Remediation Company

Job Number: 300-1728-1
SDG Number: WC0654

Login Number: 1728
List Number: 1
Creator: Friesz, Jordan D

List Source: TestAmerica Richland

Question	Answer	Comment
Radioactivity wasn't checked or is </= background as measured by a survey meter.	True	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time.	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	N/A	
Multiphasic samples are not present.	N/A	
Samples do not require splitting or compositing.	N/A	
Residual Chlorine Checked.	N/A	