TestAmerica

THE LEADER IN ENVIRONMENTAL TESTING

ANALYTICAL REPORT

TestAmerica Laboratories, Inc.
TestAmerica Richland
2800 George Washington Way
Richland, WA 99352
Tel: (509)375-3131

TestAmerica Job ID: 300-1589-1
TestAmerica Sample Delivery Group: WC0617
Client Project/Site: X16-014

For:
CH2M Hill Plateau Remediation Company
PO BOX 1600
Mail Stop R3-50
Richland, Washington 99352

Attn: CPP Sample Management

Authorized for release by:
12/8/2015 8:42:51 AM
Steven Campbell, Quality Assurance Assistant
steven.campbell@testamericainc.com

Designee for

Whitney Ritari, Project Manager I
(509)375-3131 ext164
whitney.ritari@testamericainc.com

LINKS

Review your project results through TotalAccess

Have a Question? Ask The Expert

Visit us at: www.testamericainc.com

I certify that this Certificate of Analysis is in compliance with the SOW, both technically and for completeness, for other than the conditions detailed in this package. Release of the data contained in this hard copy data package has been authorized by the Laboratory Manager, or a desingee as verified by the attached signature.

The laboratory is accredited to EPA 7196A in Solid and Chemical Materials, per Washington State Department of Ecology this is approved for non-discharge water samples. The sample/ sample duplicate RPD agreement is not applicable if one or both results are elss than five times the MDL.

Table of Contents

Cover Page 1
Table of Contents 2
Definitions/Glossary 3
Case Narrative 4
Chain of Custody 5
Detection Summary 7
Client Sample Results 8
QC Sample Results 9
QC Association Summary 10
Lab Chronicle 11
Method Summary 12
Sample Summary 13
Receipt Checklists 14

Definitions/Glossary

Client: CH2M Hill Plateau Remediation Company
Project/Site: X16-014

TestAmerica Job ID: 300-1589-1
SDG: WC0617

Qualifiers

HPLC/IC

Qualifier	Qualifier Description
U	Analyzed for but not detected.
D	The reported value is from a dilution.

Glossary

Abbreviation	These commonly used abbreviations may or may not be present in this report.
¤	Listed under the "D" column to designate that the result is reported on a dry weight basis
%R	Percent Recovery
CFL	Contains Free Liquid
CNF	Contains no Free Liquid
DER	Duplicate error ratio (normalized absolute difference)
Dil Fac	Dilution Factor
DL, RA, RE, IN	Indicates a Dilution, Re-analysis, Re-extraction, or additional Initial metals/anion analysis of the sample
DLC	Decision level concentration
MDA	Minimum detectable activity
EDL	Estimated Detection Limit
MDC	Minimum detectable concentration
MDL	Method Detection Limit
ML	Minimum Level (Dioxin)
NC	Not Calculated
ND	Not detected at the reporting limit (or MDL or EDL if shown)
PQL	Practical Quantitation Limit
QC	Quality Control
RER	Relative error ratio
RL	Reporting Limit or Requested Limit (Radiochemistry)
RPD	Relative Percent Difference, a measure of the relative difference between two points
TEF	Toxicity Equivalent Factor (Dioxin)
TEQ	Toxicity Equivalent Quotient (Dioxin)

Case Narrative

Job ID: 300-1589-1

Laboratory: TestAmerica Richland

Narrative

Job Narrative
300-1589-1

Comments
No additional comments.

Receipt
The samples were received on 11/17/2015 1:10 PM; the samples arrived in good condition, properly preserved and, where required, on ice. The temperature of the cooler at receipt was 6.2º C.

HPLC/IC
Method 300.0: Manual integration was performed on the following sample for Orthophosphate as P: B33L33 (300-1589-2).

No additional analytical or quality issues were noted, other than those described above or in the Definitions/Glossary page.

CH2MHill Plateau Remediation Company	CHAIN OF CUSTODY/SAMPLE ANALYSIS REQUEST	C.O.C. # X16-014-014 Page 1 of 1

Collector	S.W. King/CHPRC	Contact/Requester	WHITLEY, KM	Telephone No.	373-4929
SAF No.	X16-014	Sampling Origin	Hanford Site	Purchase Order/Charge Code	300205
Project Title	Uranium Sequestration - Day 11	Logbook No.	HNF-N-506 81/40	Ice Chest No.	N/A
Shipped To (Lab)	TestAmerica Incorporated, Richland	Method of Shipment	GOVERNMENT VEHICLE	Bill of Lading/Air Bill No.	N/A
Protocol	CERCLA	Priority:	30 Days PRIORITY	Offsite Property No.	N/A

POSSIBLE SAMPLE HAZARDS/REMARKS

*Contains Radioactive Material at concentrations that are not be regulated for transportation per 49 CFR/IATA Dangerous Goods Regulations but are not releasable per DOE Order 458.1.

SPECIAL INSTRUCTIONS **Hold Time** Total Activity Exemption: Yes ☑ No ☐

N/A

Sample No.	Filter	*	Date	Time	No/Type Container	Sample Analysis	Holding Time	Preservative
B33L41	N	W	NOV 17 2015	0928	1x500-mL P	300.0_ANIONS_IC: GW 01	48 Hours	Cool <=6C

300-1589 COC

#1589

WC0617

Relinquished By	Print	Sign	Date/Time	Received By	Print	Sign	Date/Time
S.W. King/CHPRC			NOV 17 2015 1030		L.D. Wall CHPRC		NOV 17 2015 1030
L.D. Wall CHPRC			NOV 17 2015 1310		J. Bock, TARL		NOV 17 2015 1310

Matrix *

S	= Soil		DS	= Drum Solids	
SE	= Sediment		DL	= Drum Liquids	
SO	= Solid		T	= Tissue	
SL	= Sludge		WI	= Wipe	
W	= Water		L	= Liquid	
O	= Oil		V	= Vegetation	
A	= Air		X	= Other	

FINAL SAMPLE DISPOSITION	Disposal Method (e.g., Return to customer, per lab procedure, used in process)	Disposed By	Date/Time

December 08, 2015

CH2MHill Plateau Remediation Company	CHAIN OF CUSTODY/SAMPLE ANALYSIS REQUEST	C.O.C. # X16-014-012 Page 1 of 1

Collector	K.C. Patterson CHPRC	Contact/Requester	WHITLEY, KM	Telephone No.	373-4929
SAF No.	X16-014	Sampling Origin	Hanford Site	Purchase Order/Charge Code	300205
Project Title	Uranium Sequestration - Day 11	Logbook No.	HNF-N-506 80/33	Ice Chest No.	N/A
Shipped To (Lab)	TestAmerica Incorporated, Richland	Method of Shipment	GOVERNMENT VEHICLE	Bill of Lading/Air Bill No.	N/A
Protocol	CERCLA	Priority:	30 Days PRIORITY	Offsite Property No.	N/A

POSSIBLE SAMPLE HAZARDS/REMARKS
*Contains Radioactive Material at concentrations that are not be regulated for transportation per 49 CFR/IATA Dangerous Goods Regulations but are not releasable per DOE Order 458.1.

SPECIAL INSTRUCTIONS **Hold Time** Total Activity Exemption: Yes ☑ No ☐
N/A

Sample No.	Filter	*	Date	Time	No/Type Container	Sample Analysis	Holding Time	Preservative
B33L33	N	W	NOV 17 2015	0908	1x500-mL P	300.0_ANIONS_IC: GW 01	48 Hours	Cool <=6C

#1589
WC0617

Relinquished By (Print / Sign)	Date/Time	Received By (Print / Sign)	Date/Time
K.C. Patterson CHPRC	NOV 17 2015 1000	L.D. Wall CHPRC	NOV 17 2015 1000
L.D. Wall CHPRC	NOV 17 2015 1310	J. Bock, TARL	NOV 17 2015 1310

Matrix *

S	= Soil	DS	= Drum Solids
SE	= Sediment	DL	= Drum Liquids
SO	= Solid	T	= Tissue
SL	= Sludge	WI	= Wipe
W	= Water	L	= Liquid
O	= Oil	V	= Vegetation
A	= Air	X	= Other

FINAL SAMPLE DISPOSITION Disposal Method (e.g., Return to customer, per lab procedure, used in process) Disposed By Date/Time

PRINTED ON 10/28/2015 FSR ID = FSR8679 A-6004-842 (REV 2)

December 08, 2015

Detection Summary

Client: CH2M Hill Plateau Remediation Company
Project/Site: X16-014

TestAmerica Job ID: 300-1589-1
SDG: WC0617

Client Sample ID: B33L41 — Lab Sample ID: 300-1589-1

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Orthophosphate as P	2500	D	41	21	mg/L	500		300.0	Total/NA

Client Sample ID: B33L33 — Lab Sample ID: 300-1589-2

Analyte	Result	Qualifier	RL	MDL	Unit	Dil Fac	D	Method	Prep Type
Orthophosphate as P	1300	D	41	21	mg/L	500		300.0	Total/NA

This Detection Summary does not include radiochemical test results.

Client Sample Results

Client: CH2M Hill Plateau Remediation Company
Project/Site: X16-014

TestAmerica Job ID: 300-1589-1
SDG: WC0617

Client Sample ID: B33L41

Lab Sample ID: 300-1589-1
Date Collected: 11/17/15 09:28
Matrix: Water
Date Received: 11/17/15 13:10

Method: 300.0 - Anions, Ion Chromatography

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Orthophosphate as P	2500	D	41	21	mg/L			11/17/15 18:15	500

Client Sample ID: B33L33

Lab Sample ID: 300-1589-2
Date Collected: 11/17/15 09:08
Matrix: Water
Date Received: 11/17/15 13:10

Method: 300.0 - Anions, Ion Chromatography

Analyte	Result	Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Orthophosphate as P	1300	D	41	21	mg/L			11/17/15 18:30	500

QC Sample Results

Client: CH2M Hill Plateau Remediation Company
Project/Site: X16-014

TestAmerica Job ID: 300-1589-1
SDG: WC0617

Method: 300.0 - Anions, Ion Chromatography

Lab Sample ID: MB 300-2028/5
Matrix: Water
Analysis Batch: 2028

Client Sample ID: Method Blank
Prep Type: Total/NA

Analyte	MB Result	MB Qualifier	RL	MDL	Unit	D	Prepared	Analyzed	Dil Fac
Orthophosphate as P	0.041	U	0.082	0.041	mg/L			11/17/15 12:22	1

Lab Sample ID: LCS 300-2028/6
Matrix: Water
Analysis Batch: 2028

Client Sample ID: Lab Control Sample
Prep Type: Total/NA

Analyte			Spike Added	LCS Result	LCS Qualifier	Unit	D	%Rec	%Rec. Limits		
Orthophosphate as P			6.53	6.88		mg/L		105	80 - 120		

Lab Sample ID: 300-1586-A-5 MS
Matrix: Water
Analysis Batch: 2028

Client Sample ID: Matrix Spike
Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier	Spike Added	MS Result	MS Qualifier	Unit	D	%Rec	%Rec. Limits		
Orthophosphate as P	0.082	U	1.31	1.15	D	mg/L		88	75 - 125		

Lab Sample ID: 300-1586-A-5 DU
Matrix: Water
Analysis Batch: 2028

Client Sample ID: Duplicate
Prep Type: Total/NA

Analyte	Sample Result	Sample Qualifier		DU Result	DU Qualifier	Unit	D			RPD	RPD Limit
Orthophosphate as P	0.082	U		0.082	U	mg/L				NC	20

QC Association Summary

Client: CH2M Hill Plateau Remediation Company
Project/Site: X16-014

TestAmerica Job ID: 300-1589-1
SDG: WC0617

HPLC/IC

Analysis Batch: 2028

Lab Sample ID	Client Sample ID	Prep Type	Matrix	Method	Prep Batch
300-1586-A-5 DU	Duplicate	Total/NA	Water	300.0	
300-1586-A-5 MS	Matrix Spike	Total/NA	Water	300.0	
300-1589-1	B33L41	Total/NA	Water	300.0	
300-1589-2	B33L33	Total/NA	Water	300.0	
LCS 300-2028/6	Lab Control Sample	Total/NA	Water	300.0	
MB 300-2028/5	Method Blank	Total/NA	Water	300.0	

Lab Chronicle

Client: CH2M Hill Plateau Remediation Company
Project/Site: X16-014

TestAmerica Job ID: 300-1589-1
SDG: WC0617

Client Sample ID: B33L41
Date Collected: 11/17/15 09:28
Date Received: 11/17/15 13:10

Lab Sample ID: 300-1589-1
Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		500	10 mL		2028	11/17/15 18:15	CPM	TAL RCH

Client Sample ID: B33L33
Date Collected: 11/17/15 09:08
Date Received: 11/17/15 13:10

Lab Sample ID: 300-1589-2
Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		500	10 mL		2028	11/17/15 18:30	CPM	TAL RCH

Client Sample ID: Duplicate
Date Collected: 11/17/15 10:30
Date Received: 11/17/15 13:10

Lab Sample ID: 300-1586-A-5 DU
Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		2	10 mL		2028	11/17/15 16:39	CPM	TAL RCH

Client Sample ID: Lab Control Sample
Date Collected: N/A
Date Received: N/A

Lab Sample ID: LCS 300-2028/6
Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		1	10 mL		2028	11/17/15 12:37	CPM	TAL RCH

Client Sample ID: Method Blank
Date Collected: N/A
Date Received: N/A

Lab Sample ID: MB 300-2028/5
Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		1	10 mL		2028	11/17/15 12:22	CPM	TAL RCH

Client Sample ID: Matrix Spike
Date Collected: 11/17/15 10:30
Date Received: 11/17/15 13:10

Lab Sample ID: 300-1586-A-5 MS
Matrix: Water

Prep Type	Batch Type	Batch Method	Run	Dil Factor	Initial Amount	Final Amount	Batch Number	Prepared or Analyzed	Analyst	Lab
Total/NA	Analysis	300.0		2	10 mL		2028	11/17/15 16:24	CPM	TAL RCH

Laboratory References:

TAL RCH = TestAmerica Richland, 2800 George Washington Way, Richland, WA 99352, TEL (509)375-3131

Method Summary

Client: CH2M Hill Plateau Remediation Company
Project/Site: X16-014

TestAmerica Job ID: 300-1589-1
SDG: WC0617

Method	Method Description	Protocol	Laboratory
300.0	Anions, Ion Chromatography	MCAWW	TAL RCH

Protocol References:

MCAWW = "Methods For Chemical Analysis Of Water And Wastes", EPA-600/4-79-020, March 1983 And Subsequent Revisions.

Laboratory References:

TAL RCH = TestAmerica Richland, 2800 George Washington Way, Richland, WA 99352, TEL (509)375-3131

Sample Summary

Client: CH2M Hill Plateau Remediation Company
Project/Site: X16-014

TestAmerica Job ID: 300-1589-1
SDG: WC0617

Lab Sample ID	Client Sample ID	Matrix	Collected	Received
300-1589-1	B33L41	Water	11/17/15 09:28	11/17/15 13:10
300-1589-2	B33L33	Water	11/17/15 09:08	11/17/15 13:10

Login Sample Receipt Checklist

Client: CH2M Hill Plateau Remediation Company

Job Number: 300-1589-1
SDG Number: WC0617

Login Number: 1589
List Number: 1
Creator: Friesz, Jordan D

List Source: TestAmerica Richland

Question	Answer	Comment
Radioactivity wasn't checked or is </= background as measured by a survey meter.	True	
The cooler's custody seal, if present, is intact.	True	
Sample custody seals, if present, are intact.	True	
The cooler or samples do not appear to have been compromised or tampered with.	True	
Samples were received on ice.	True	
Cooler Temperature is acceptable.	True	
Cooler Temperature is recorded.	True	
COC is present.	True	
COC is filled out in ink and legible.	True	
COC is filled out with all pertinent information.	True	
Is the Field Sampler's name present on COC?	True	
There are no discrepancies between the containers received and the COC.	True	
Samples are received within Holding Time.	True	
Sample containers have legible labels.	True	
Containers are not broken or leaking.	True	
Sample collection date/times are provided.	True	
Appropriate sample containers are used.	True	
Sample bottles are completely filled.	True	
Sample Preservation Verified.	True	
There is sufficient vol. for all requested analyses, incl. any requested MS/MSDs	True	
Containers requiring zero headspace have no headspace or bubble is <6mm (1/4").	N/A	
Multiphasic samples are not present.	N/A	
Samples do not require splitting or compositing.	N/A	
Residual Chlorine Checked.	N/A	