

PO Box 4339 1570 Bear Creek Road Oak Ridge TN 37830 865/482-6497

CERTIFICATE OF ANALYSIS

Stephen Trent Fluor Hanford, Inc. 825 Jadwin Avenue Richland, Washington 99352 October 21, 2004

This is the Certificate of Analysis for the following samples:

Shaw Project ID: Shaw Project Number:

Client Sampling Authorization Form No.

Client Sample Data Group:

Date Received by Lab: Number of Samples:


Sample Type:

Eberline - Hanford 100846.15000000 F04-013-024

H2706

September 10, 2004

One (1) Soil



I. Introduction/Case Narrative

One soil sample was received by the Shaw Geotechnical Laboratory on September 10, 2004. The sample was submitted for determination of bulk density, sieve analysis, calcium carbonate content, hydraulic conductivity, and specific gravity. The sample number received was B19142.

Please see Appendix A, Sample Number Cross Reference List; Appendix B, Analysis Results; and Appendix C, Chain-of-Custody/Sample Receipt Records.

"I certify that this data package is in compliance with the SOW, both technically and for completeness, for other than the conditions detailed above. Release of the data contained in this hardcopy data package has been authorized by the Laboratory Manager or a designee, as verified by the following signature."

Reviewed and Approved:

Ralph Cole

Laboratory Manager, Geotechnical Services

Page 2 of 11 October 21, 2004 Stephen Trent Fluor Hanford, Inc. Shaw Project Name: Eberline Hanford Shaw Project No. 100846.15000000 SAF No. F04-13-024 SDG No. H2706

Shaw Geotechnical Laboratory Oak Ridge TN 865/482-6497

II. Analytical Results/Methodology

REFERENCES: United States Army Corps of Engineers (USACE), Engineer Manual 1110-2-1906, Laboratory Soils Testing, appendix II, 1970; United States Environmental Protection Agency, SW846, Test Methods for Examining Solid Waste, Physical/Chemical Methods, 3rd ed., Nov 1986 (EPA SW-846). Annual Book of ASTM Standards, Section 4, Construction, Volume 04.08, Soil and Rock (I), and Volume 04.09, Soil and Rock (II), 2004. Shaw Environmental and infrastructure, Standard Operating Procedures.

Moisture Content of Soil and Rock	. ASTM D 2216
Bulk Density of Soils	EM 1110-2-1906
Particle-size Analysis of Soils	ASTM D 422
Calcium Carbonate Content	ASTM D 4373
Specific Gravity of Soil	

III. Quality Control

Quality control checks such as duplicates and spikes (QC samples), are not normally applicable to geotechnical testing. This is due largely to the inability of obtaining samples with known characteristics, the heterogenous nature of the samples, and quality control procedures built-in to the analytical method.

QC measures to ensure accuracy and precision of test results include the following:

- 100% verification of all numerical results raw data entries, transcriptions and calculations entered by lab technicians are checked, recalculated and verified. Most data calculations are performed by computer programs.
- Data validation through test reasonableness summaries of all test results for individual reports are reviewed to determine the overall reasonableness of data and to determine the presence of any data that may be considered outliers.
- Quality control procedures are built into most standardized geotechnical procedures. For example, liquid limit and plastic limit analyses call for re-analyses and specify acceptance criteria.
- Routine instrument calibration instruments, gauges and equipment used in testing are calibrated on a routine basis. All instrument calibration follows ASTM or manufacturer guidelines.

Page 3 of 11 October 21, 2004 Stephen Trent Fluor Hanford, Inc. Shaw Project Name: Eberline Hanford Shaw Project No. 100846.15000000 SAF No. F04-13-024 SDG No. H2706

Shaw Geotechnical Laboratory Oak Ridge TN 865/482-6497

- Maintenance of all past calibration records calibration records and certification documents of all instruments, gauges and equipment are updated routinely and maintained in the Quality Control Coordinators Quality/Operations files.
- Certified and trained personnel all technicians are certified by the National Institute for Certification of Engineering Technicians (NICET) in geotechnical soil testing, and are trained in the application of standard laboratory procedures for geotechnical analyses as well as the quality assurance measures implemented by Shaw.
- Quantitative analyses frequently used in geotechnical/physical testing programs do not use
 QC tools common to wet chemistry or radiochemistry laboratories. Measures not employed
 in the analysis of samples reported in this report include: laboratory control samples (LCS),
 blanks, matrix spikes (MS), duplicate analyses, dilutions, digestions, correction factors,
 surrogate sample analyses, detection limit determinations, control charts, and/or tentatively
 identified compounds (TICs).

IV. Data Qualification

None.

Appendix A Sample Cross-Reference List Page 4 of 11 October 21, 2004 Stephen Trent Fluor Hanford, Inc. Shaw Project Name: Eberline Hanford Shaw Project No. 100846.15000000 SAF No. F04-13-024 SDG No. H2706

Shaw Geotechnical Laboratory Oak Ridge TN 865/482-6497

SAMPLE NUMBER CROSS-REFERENCE LIST

LAB SAMPLE NO.	CLIENT SAMPLE NO.	MATRIX
BC0441	B19142	Soil

Appendix B Sample Test Results Page 5 of 11 October 21, 2004 Stephen Trent Fluor Hanford, Inc. Shaw Project Name: Eberline Hanford Shaw Project No. 100846.15000000 SAF No. F04-13-024 SDG No. H2706

Shaw Geotechnical Laboratory Oak Ridge TN 865/482-6497

PARTICLE-SIZE DISTRIBUTION ASTM D 422

Project Name Eberline Hanford

Field Sample No. B19142

Project No.

100846.15000000

Lab Sample No. BC0441


Moisture Content = 17.2% based on dry sample weight

SIEVE ANALYSIS

	Sieve	Diameter	Percent
С	No.	mm	Finer
0	3"	75.000	100.0%
Α	1.5"	37.500	100.0%
R	0.75"	19.000	100.0%
S E	0.375"	9.500	100.0%
-	#4	4.750	100.0%
	#10	2.000	99.9%

	Sieve	Diameter	Percent
	No.	mm	Finer
F	#20	0.850	98.9%
1	#40	0.425	93.5%
N	# #*UU	0.250	46.6%
Е	#100	0.149	16.2%
	#140	0.106	5.5%
	#200	0.075	2.3%

DISTRIBUTION CURVE



0.0% Gravel

97.7% Sand

2.3% Silt/Clay

Page 6 of 11 October 21, 2004 Stephen Trent Fluor Hanford, Inc. Shaw Project Name: Eberline Hanford Shaw Project No. 100846.15000000 SAF No. F04-13-024 SDG No. H2706

Shaw Geotechnical Laboratory Oak Ridge TN 865/482-6497

SPECIFIC GRAVITY ASTM D 854

PROJECT NAME:

Eberline Hanford

PROJECT NUMBER:

100846.15000000

LAB SAMPLE NO.	CLIENT SAMPLE NO.	SPECIFIC GRAVITY
BC0441	B19142	2.6923

Page 7 of 11 October 21, 2004 Stephen Trent Fluor Hanford, Inc. Shaw Project Name: Eberline Hanford Shaw Project No. 100846.15000000 SAF No. F04-13-024 SDG No. H2706

Shaw Geotechnical Laboratory Oak Ridge TN 865/482-6497

BULK DENSITY/DRY DENSITY EM-1110-2-1906, APPENDIX II

PROJECT NAME:

PROJECT NUMBER:

Eberline - Hanford

100846.15000000

LAB SAMPLE NUMBER	CLIENT SAMPLE NUMBER	AVERAGE LENGTH, inches	AVERAGE DIAMETER, inches	WET WEIGHT, grams	MOISTURE CONTENT, %	BULK DENSITY, pcf	DRY DENSITY, pcf
BC0441	B19142	5.9555	3.8795	2350.31	17.2	127.2	108.6

Moisture content calculated by ASTM D 2216 based on sample dry weight.

Bulk density is the weight of wet sample divided by the volume of the wet sample (as-received).

Dry density is the weight of the dry sample solids divided by the volume of the original sample.

Page 8 of 11 October 21, 2004 Stephen Trent Fluor Hanford, Inc. Shaw Project Name: Eberline Hanford Shaw Project No. 100846.15000000 SAF No. F04-13-024 SDG No. H2706

Shaw Geotechnical Laboratory Oak Ridge TN 865/482-6497

Carbonate Content of Soils ASTM D 4373

PROJECT NAME:

Eberline Hanford

PROJECT NUMBER:

100846.15000000

LAB SAMPLE NO.	CLIENT SAMPLE NO.	CO3, %
BC0441	B19142	0

Page 9 of 11 October 21, 2004 Stephen Trent Fluor Hanford, Inc. Shaw Project Name: Eberline Hanford Shaw Project No. 100846.15000000 SAF No. F04-13-024 SDG No. H2706


Shaw Geotechnical Laboratory Oak Ridge TN 865/482-6497

HYDRAULIC CONDUCTIVITY / PERMEABILITY ASTM D 5084

PROJECT NAME: Eberline Hanford CLIENT SAMPLE NO. B19142 PROJECT NO. 100846.15000000 LAB SAMPLE NO. BC0441

	INITIAL	FINAL		
Specimen diameter, cm	6.46			
Specimen length, cm	6.61		Hydraulic gradient	5.3
Wet weight of specimen, g.	427.04		Min. consolidation stress,	, psi 2.0
Specimen cross-sect. area, cm ²	2 32.82		Max. consolidation stress	s, psi 2.5
Water content, %	25.2		Total backpressure, psi	3.5
Wet unit weight, pcf	122.8			
Dry unit weight, pcf	98.1		Permeant Fluid [Deaired DI Water
Degree of saturation, %	95.1			
Specific gravity of solids	2.69			

Coefficient of Permeability, cm/s 1.3E-05



Appendix C Chain-of-Custody and Request-for-Analysis Records SDG# H2706

Eberline Srvces

CHAIN OF CUSTODY

ORD # R4-09-022

RCVD: 09/03/04 DUE: 10/18/04

PAGE 1

09/03/04 15:01:41

WORK ID: SAF# F04-013 SDG H2706

KEEP: 10/18/05 DISP: S

DASH SAMPLE IDENTIFICATION	STORED	TESTS		
01A-S B19142	SHAW	DISPOS E331S	E335S	E342S
		=============	=======	

Fred Jan	DATE 9/40 P	TRANSFERRED TO	<u>DATE</u>	Down hing Sum	<u> </u>
to an area demanded and a second					

BC 0441

- SHAW - sample

FLUOR Hanfor	d Inc.	CE	CENTRAL PLATEAU CHAIN OF CUSTODY/SAMPLE ANALYSIS REQUEST F04-013-024 Page 1							Page <u>1</u>	of <u>1</u>		
Collector Johansen/Alexander/Gent/The	omas		Company Contact Telephone No. Project Coordinate TRENT, SJ					linator	Price Code	8N	Data Tur		
Project Designation 200-UP-1 Remedial Investiga	ation Sampling and Anal		ampling Location Page 9/1/0 200-UP-1, C4299; 305-210 307.5 - 310 + F04-013						Air Quality 45 Day			Days	
Ice Chest No. GAR-	03-018		Logbook No. F-N-3841		COA 119324ES	10		Method of Sh Federal Exp					
Shipped To Shaw Group		Offsit	e Property No. O	e PTA	14	050		Bill of Ladin	g/Air Bill	No. 54	PTK	140	50
POSSIBLE SAMPLE HAZA	ARDS/REMARKS		Preservation	None	None								
			Type of Container	Moistyre Resistant	Split Spoon								
Special Handling and/or S	storage		No. of Container(s)	1	2)							
H2706	(7083)		Volume	100g	1000g								
	SAMPLE ANAL	YSIS		Moisture Content - D2216	See item (1) in Special Instructions.								
Sample No.	Matrix *	Sample Date	Sample Time					•					
B19142	SOIL	9/1/0	1440					BC 044	1				
CHAIN OF POSSESSIC	DN	Sign/Prin	t Names		SPEC	IAL INSTR	UCTIO	ONS			<u> </u>	<u></u>	Matrix *
Relinquished By/Removed From	Date/Time Date/Time Date/Time Date/Time Date/Time Date/Time	5 Received By/Sto	red In Da # Da / A / Da / Da / Da / Da / Da / Da /	ate/Time ate/Time ate/Time ate/Time	(1) B Hydra 24	ulk Density - D)2937; Pa ity; Parti			2; Calcium Carbon 3,0 KG 3,0 KG		nurated	S=Soil SE=Sediment SO=Solid SI=Sludge W = Water O=Oil A=Air DS=Drum Solids DL=Drum Liquids T=Tissue WI=Wipe L=Liquid V=Vegetation X=Other
LABORATORY Received By SECTION		DON H	USKEY	SR. L		ctt			,,,,,	09	-10-04	@ 1100	
FINAL SAMPLE Disposal M. DISPOSITION							sed By				I	Date/Time	