ENGINEERING CHANGE NOTICE

Page 1 of 2

1. ECN 634620 Proj. ECN

	,				T	
2. ECN Category (mark one)	-	me, Organization, MSIN, a		No.	4. Date	
Supplemental []	F. N. Hodges,	PSS/HTS, H6-06, 3	76-4627		12/27/95	
Direct Revision [X] Change ECN []	5. Project Title/No./Work Order No. 6. Interim Status Groundwater		7	s./Fac. No.	7. Impact Level	
Temporary []				DWL	QE	
Standby []		Monitoring Plan for the			4-	
Supersedure [] Cancel/Void []						
	Nonradioactive Dangerous Waste Landfill, Hanford, Washington					
			<u> </u>		40 - 1 - 1 - 1	
	8. Document Number (includes sheet	s Changed by this ECN no. and rev.)	9. Related	ECN NO(S).	10. Related PO No.	
	WHC-SD-EN-	AP-026, Rev. 0	N	/A	N/A	
11a. Modification Work	11b. Work Package No.	11c. Modification Work (Complete		red to Original Condi- . or Standby ECN only)	
[] Yes (fill out Blk.	N/A	N/A		N/A		
[X] No (NA Biks. 11b,				 -		
11c, 11d)		Cog. Engineer Signatu	ire & Date	Cog. Eng	ineer Signature & Date	
12. Description of Change						
See Attached.						
	eria Change []	Design Improvement	[]	Environment	tal [X]	
(mark one) As-Found [7] Facil	itate Const. []	Const. Error/Omissi	on []	Design Erro	or/Omission []	
13b. Justification Details	· · · · · · · · · · · · · · · · · · ·		<u> []</u>	V	<u> </u>	
The changes bring the	a aroundwaten	monitoring plan in	line wit	h changes	in the campline	
and analysis program					in the sampling	
and analysis prograt	u aun ahnarsz (ine groundwater mor	incoring n	CUWUTK.		
		•				
4/ Mina-Shuai /:1 1	-ma MCTN	of acrical			AF: F4AF ATAY	
14. Distribution (include n	ame, MSIN, and no. o	or copies)	r		RELEASE STAMP	
See attached			l.	UG 07	1996,—	
			Į į	ADO VI	1000	
				DATE:	/ 20	
				DATE:	HAMPORD	
			Í	STA:37	RELEASE } ID:	
			İ	"		
			j		-\~\	
. 3000 043 3 404 (00)						
\-7900-013-2 (0 6/92) GEF095			1	Control of the contro	CALL CONTRACTOR OF THE PERSON	

ENGINEERING CHANGE NOTICE

Page 2 of 2

1. ECN (use no. from pg. 1) -172218 634620 3

15. Design	16. Cost Impact					········	17	. Schedule Im	sact (d	avs)
Verification Required	· ·	NEERING		CON	ISTRUCT	ION			\-	•
[] Yes N/A	Additional	[] \$	N/A	Additional	[] \$	Im	provement	[]	N/A
	Savings	- [j \$		Savings	[] \$) De	lay	[]	
18. Change Impact R that will be af	eview: Indicate fected by the ch	the relat	ed docum	ments (other the Block 12. Ente	on the	engineer affected	ing docume document	nts identifie number in Blo	d on \$1 ck 19.	ide 1)
SOD/DD	[]	;	Seismic/	Stress Analysis	1	[]	Tan	k Calibration	Manual	[]
Functional Design C	riteria []	!	Stress/D	esign Report		[]		lth Physics cedure		[]
Operating Specifics	ition []		Interfac	e Control Draw	ing	[]		res Multiple ting	Unit	[]
Criticality Specifi	cation []	4	Calibrat	ion Procedure		[]	T es Pro n	t cedures/Speci	ficatio	, []
Conceptual Design R	eport []		Installa	tion Procedure		[]		ponent Index		.[1]
Equipment Spec.	ii	1	Maintena	nce Procedure		ii	ASM	E Coded Item		ii
Const. Spec.	ij	1	Engineer	ing Procedure		ij		an Factor sideration		ij
Procurement Spec.	[]		Operatir	ng Instruction		[]		puter Softwar	e	[]
Vendor Information	ij	ı	Operatir	ng Procedure				ctric Circuit edule		ij
OH Manual	[]		Operatio Requirem	onal Safety ment		[]		S Procedure		[]
FSAR/SAR	[]		IEFD Dra			[]		cess Control ual/Plan		[]
Safety Equipment Li	st []		Cell Arr	angement Drawin	19	[]		cess Flow Cha	rt	[]
Radiation Work Perm	* * *		Essentia Specific	al Material		[]	Pur	chase Requisi	tion	ij
Environmental Impac Statement	:t []		•	oc. Samp. Sched	ule	[]				[]
Environmental Repor	't []		Inspect i	on Plan		[]				[]
Environmental Permi			inventor Request	y Adjustment		ij				ii
1	Documents: (NOI the signing organ mber/Revision		s been i Docu		er aff	ected doc	uments lis			
20. Approvals	Signature			Date			Signatur	_		Date
OPERATIONS AND ENGI					ARCHI	TECT-ENG!	-	-		valt
Cog Engineer F. N.		odan	_	12/28/95	PE					
Cog. Mgr. J. S. So		horail	5	12/20/05	QA				-	
QA W. R. Thachaber	ry /We Hank	herez	·	2.266	Safet	t v			-	
Safety	V			31-76	Desig	-			-	
Environ. B. W. Fr		, see			Envi	-			-	
Other B. A. Willia	5/01	Mar Well		3-8-96					_	
Other B. A. Wittin				1/3/96	Other	•			_	
									-	
					0000	THEUT AS	FUERA		-	
						RTMENT OF Sture or I	ENERGY Letter No.			
					Jigik	stare VI L	Letter NO.			
					ADDIT	IONAL			-	
									-	
1									-	

Interim Status Groundwater Monitoring Plan for the Nonradioactive Dangerous Waste Landfill, Hanford, Washington

Floyd N. Hodges
Westinghouse Hanford

Westinghouse Hanford Company, Richland, WA 99352 U.S. Department of Energy Contract DE-AC06-87RL10930

EDT/ECN: 634620 UC: 630

Org Code: 8H200 Charge Code: R4069 B&R Code: EW3120100 Total Pages: 118

Key Words: Groundwater, Monitoring, RCRA, NRDWL

Abstract: This replacement brings the groundwater monitoring plan into line with changes in the sampling and analysis program and updates the groundwater monitoring network to reflect new wells.

TRADEMARK DISCLAIMER. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.

Printed in the United States of America. To obtain copies of this document, contact: WHC/BCS Document Control Services, P.O. Box 1970, Mailstop Hó-08, Richland WA 99352, Phone (509) 372-2420; Fax (509) 376-4989.

James Bistroja 8-78-96

Rease Approval

Date

DATE: KANPORD RELEASE ID:

Release Stamp

Approved for Public Release

RECORD OF REVISION

(1) Document Number
WHC-SD-EN-AP-026

Page 1

(2) Title

Interim Status Groundwater Monitoring Plan for the Nonradioactive Dangerous Waste Landfill, Hanford, Washington

			CHANGE CONTROL RECORD				
77	Davisian	(/)		Authorized for Release			
(3)	Revision	(4)	EDT-159220, 1/20/93	(5) Cog. Engr.	(6) Cog. Mgr. Date		
:	0A RS	(7)	Replace pages 29-31, 33-35, 40, 52, 55, A7-A8, and C-9 (Rev. 0) with corrected pages (Rev. 0-A).	Hayn. Hage	(6) cog. Mgr. Date 1 Hortun 7 30 96		
}			ECN - 634620	FN Hodacs	DG Horton		
	·						
		<u> </u>					
				· · · · · · · · · · · · · · · · · · ·			
-		 					
		 					
		}					
<u> </u>							
		-					
		ļ					
		 					
	-	<u> </u>	<u>, , , , , , , , , , , , , , , , , , , </u>				
		ļ					
		ļ					
		ļ					
		ļ					
[]					
	_		· · · · · · · · · · · · · · · · · · ·		<u> </u>		

3.4 DETECTION LEVEL GROUNDWATER MONITORING SYSTEM

This section describes the aquifer that will be monitored, the location and justification of the monitoring wells, the installation of new wells, the hydrogeologic data to be collected, the frequency of sampling, and the groundwater constituents to be analyzed. Drilling, well construction, aquifer testing, and associated activities will be conducted according to the applicable Westinghouse Hanford procedures. Specific environmental investigation instructions (EII) are cited in sections of the plan. Additional EII may also apply.

3.4.1 Uppermost Aquifer

The unconfined aquifer beneath the NRDWL is contained primarily within sediments of the Hanford and Ringold formations and may extend from the water table to the top of basalt. The unconfined aquifer is discussed in more detail in Chapter 2.0. Hydrogeologic characterization activities are designed to obtain additional information on groundwater flow characteristics of the unconfined aquifer.

3.4.2 Background (Upgradient) Wells

Three wells (699-26-35A, 699-26-34, and 699-26-35C) were installed upgradient as background wells to determine the background groundwater chemistry (Weekes et al. 1987, Table 3-2). Wells 699-26-35A and 699-26-34 were completed in the top of the unconfined aquifer in the Hanford formation, and well 699-26-35C was completed in the upper Ringold Formation above the LPU. Well 699-26-35B, designed to monitor potentiometric levels above and below the LPU during and after pump tests still exists; however, it is not in use.

3.4.3 Detection (Downgradient) Wells

Four wells (699-25-34A, 699-26-33, 699-25-34B, and 699-25-33A) were installed as downgradient detection wells (Figure 10). Wells 699-25-34A, 699-25-34B, and 699-25-33 were completed in the top of the unconfined aquifer, in the Hanford formation, and well 699-25-33A was completed in the upper Ringold Formation above the LPU. A fifth well (699-25-33B), designed for monitoring potentiometric levels above and below the LPU during and after pump tests across the LPU and monitoring gradients across the LPU, still exists; however, it is not presently in use. All wells were designed for hydrogeologic characterization. Table 1 summarizes the construction details for the monitoring wells.

3.4.4 New and Proposed RCRA Monitoring Wells

Three additional monitoring wells, Two new wells were completed in the top of the unconfined aquifer in 1992. and A deep groundwater monitoring and characterization is planned for expanding the initial groundwater monitoring network. Estimated coordinates and construction details for this wells are

Table 1. Construction Summary—The Nonradioactive Dangerous Waste Landfill Groundwater Monitoring Network.

Well number	Date completed	Depth drilled ^a	Casing/ Screen ^b	Screened depth ^a	Depth to water	Date measured
699-26-34°	7/86	43.6 (143)	CS/SS 12.7-cm (5-in.)	35.7-41.8 (177-137)	37.63 (123.45)	7/86
699-26-35A°	7/86	46.6 (153)	CS/SS 12.7-cm (5-in.)	36.6-42.7 (120-140)	38.95 (127.79)	7/86
699-26-35c°	1/87	64.3 (211)	\$\$/\$\$ 10.2-cm (4-in.)	58.8-61.9 (193-203)	38.9 (127.73)	1/87
699-26-33	9/86	44.8 (147)	CS/SS 12.7-cm (5-in.)	37.8-43.9 (124-144)	39.99 (131.20)	1/87
699-25-34A	7/86	44.2 (145)	CS/SS 12.7-cm (5-in.)	36.0-42.1 (118-138)	38.25 (125.49)	7/86
699-25-348	9/86	43.0 (141)	CS/SS 12.7-cm (5-in.)	36.0-42.1 (118-138)	38.05 (124.84)	1/87
699-25-33A	1/87	77.7 (255)	SS/SS 10.2-cm (4-in.)	58.2-61.3 (191-201)	37.86 (124.20)	1/87
699+25-340	10/92	\$2.7 (173)	\$5/\$\$ 10.2-cm (4-in.)	38.7-49.6 (127-162)	40.34 (132.35)	10/92
699-26-348	10/92	50.3 (165)	\$8/\$\$ 10.2-cm (4-in.)	36.0-46.9 (118-154)	37.8 (123.95)	10/92

[&]quot;Approximate depths in meters; feet in parentheses.

Upgradient well.

presented in Table 2 and shown in Figure 13. The addition of these wells is not necessarily intended to represent the final groundwater monitoring network. Additional monitoring wells may be required to achieve full compliance with state and federal regulations. The placement of any additional new wells will depend on results of water level measurements, water-quality-analyses, hydrogeologic information, and tracer tests collected from this initial monitoring network.

Table 2. Construction Details--Proposed Nonradioactive Dangerous Waste Landfill Groundwater Monitoring Wells.


Well number	Estimated completion date	Estimated depth	Casing/ Screen	Screen length ^a	Estimated coordinates ^c
NU-1	FY 1992	45.7-(150)	SS/SS 10-2-om (4-in-)	10.7 (35)	H 430,950 E 261,600
NU-2	FY 1992	45.7-(150)	65/65 10.2-om (4-in.)	10.7 (35)	N-430,450 E-261,400
NW-∰	TBD	175.3 (575)	\$\$/\$\$ 10.2-cm (4-in.)	3.0 (10)	N 430,450 E 261,400

In meters, feet in parentheses.

'Lambert Coordinates.

^{*}SS--stainless steel; CS--carbon steel; casing diameter in parentheses.

[&]quot;SS--stainless steel; CS--carbon steel; casing diameter in parentheses.



3.4.5 Justification for Planned Well Locations

Two shallow groundwater monitoring wells and A deep groundwater monitoring well will be installed around the NRDWL, starting in fiscal year 1992 when funding is available. The justification for the location of the three new monitoring wells is based on uncertainties in groundwater flow directions and the need for characterization of the deeper portions of the unconfined aguifer beneath the site.

The hydraulic gradient across the site is low, and there is much uncertainty about groundwater flow directions beneath the site (Section 2.3.3.1). The groundwater flow direction indicated by water level measurements differs by approximately 90° from groundwater flow directions indicated by contaminant plumes, and both differ from the assumed regional flow direction on which the initial detection level monitoring system is based. These uncertainties in groundwater flow direction indicate that the existing detection level monitoring system may not be complete. The groundwater flow direction calculated from water level measurements indicates that contaminants reaching groundwater from the NRDWL may pass north of the present downgradient wells undetected and that contaminants originating in the adjacent SWL may be detected by NRDWL downgradient wells.

Presently, no deep characterization or groundwater monitoring wells exist for the NRDWL. The two deepest wells at the NRDWL were drilled to depths of 70.1 m (230 ft) to 77.7 m (255 ft), penetrating approximately half of the thickness of the unconfined aquifer. The closest deep borehole, drilled as part of the Skagit/Hanford Project and not as a groundwater monitoring well, is approximately 0.8 km (0.5 mi) from the NRDWL. The planned deep well is necessary for the hydrogeologic characterization of the deep unconfined aquifer. A characterization that is important because of the documented disposal of chlorinated hydrocarbon DNAPL's in the NRDWL, the 12-year interval between the initiation of disposal and initiation of groundwater monitoring, and the presence of chlorinated hydrocarbons in the groundwater beneath the SWL which is immediately adjacent to and down dip from the NRDWL.

One shallow well will be installed on the north side of the NRDWL, and two, one deep and one shallow, on the south side of the site (Figure 13). The well on the north side is intended to supplement the NRDWL downgradient detection network. The shallow well located on the south side of the landfill will help in separating potential groundwater impacts from the NRDWL and the SWL. The locations of the shallow groundwater monitoring wells are indicated by MEMO modeling results that indicate a minimum monitoring efficiency of at least 93%, essentially independent of groundwater flow direction (DOE 1990). These wells will ensure that the uncertainties between the regional and local groundwater flow directions will be adequately covered. The deep monitoring well, located adjacent to the shallow monitoring well on the south side of the site, will provide for deep aquifer characterization and for detection of DNAPL contaminants on the down dip side of the NRDWL.

3.4.6 Well Drilling and Installation

The groundwater monitoring wells to be constructed at the NRDWL will be RCRA standard wells constructed to the generic specification for groundwater monitoring wells (WHC 1990). WAC 173-160, Minimum Standards for Construction and Maintenance of Wells, was used to set the basic design requirements. This well will penetrate the top of the basalt at a depth of approximately 183 m (600 ft).

Procedures for controlling the well site activities are given in the *Environmental Investigations and Site Characterization Manual*, WHC-CM-7-7 (WHC 1988) and listed in Table 3.

The new wells will most likely be drilled with an air rotary rig. If another method of drilling is chosen, it will have the same advantages as the air rotary method: (1) drill cuttings can be easily contained (important in potentially contaminated material), (2) representative geologic samples can be collected, (3) moisture samples can be collected from above the water table, (4) disturbance to the borehole wall is minimized, (5) a straight, plumb borehole is produced, and (6) groundwater quality is not affected by drilling fluids other than water or air.

Drill cuttings will be routinely monitored for radiation and hazardous material in accordance with a site-specific Hazardous Waste Operating Permit (HWOP). Contaminated cuttings will be handled, transported, and disposed according to the *Environmental Investigations and Site Characterization Manual*, EII 4.2, "Interim Control of Unknown, Suspected, Hazardous and Mixed Waste." If the level of contamination is significant enough to require changes in well design or well location, Ecology will be notified by Westinghouse Hanford prior to making the changes.

Drill rigs and peripheral equipment (such as drill tools, cables, and temporary casing) will be steam cleaned before arriving on site, moving to a new site, and beginning construction of the next well, in accordance with EII 5.4, Field Cleaning and/or Decontamination of Equipment. The addition of water to the borehole will be kept to a minimum or avoided. This will minimize well development pumping after wells are completed and minimize the chances of driving any vadose zone contaminants into the groundwater.

Temporary carbon steel casing with a minimum diameter of 20 cm (8 in.) will be driven to total depth as each borehole is advanced. A temporary 20-cm- (8-in.-) diameter telescoping screen may be installed for aquifer testing, if necessary. After the borehole has been drilled to its total depth, the final well casing and screen will be installed and the temporary carbon steel casing will be removed as the filter pack and annular seal materials are placed in the annular space. If a temporary screen is used, it will be left in place.

Two of the wells will be drilled approximately 9 m (30 ft) into the saturated sediments. One of the wells will be drilled to the top of the basalt that forms the base of the unconfined aquifer (expected depth is approximately 152 m [500 ft]).

WHC-SD-EN-AP-026, Rev. 0-A

Table 3. Applicable Environmental Investigations Instructions.

	ore 3. Appricable Environmental Investigations instructions.
Number	Title
EII 1.1	Hazardous Waste Site Entry Requirements
EII 1.2	Preparation and Revision of Environmental Investigations Instructions
E11 1.4	Instruction Change Authorizations
EII 1.5	Field Logbooks
EII 1.6	QA Records Processing
EII 1.7	Indoctrination, Training and Qualification
EII 1.9	RI/FS (RFI/CMS) Document Review and Control
EII 1.10	Identifying, Evaluating, and Documenting Suspect Waste Sites
EII 1.11	Technical Data Management
EII 2.1	Preparation of Hazardous Waste Operations Permits
£11 2.2	Occupational Health Monitoring
EII 2.3	Administration of Radiation Surveys to Support Environmental Characterization Work on the Hanford Site
E11 3.2	Calibration and Control of Monitoring Instruments
E11 4.2	Interim Control of Unknown, Suspected Hazardous and Mixed Waste
EII 5.1	Chain of Custody
EII 5.2	Soil and Sediment Sampling
EII 5.4	Field Cleaning and/or Decontamination of Equipment
E11 5.5	1706KE Laboratory Decontamination of RCRA/CERCLA Sampling Equipment
EII 5.7A	Hanford Geotechnical Sample Library Control
E11 5.8	Groundwater Sampling
EII 5.10	Sample Identification and Data Entry into HEIS Database
EII 5.11	Sample Packaging and Shipping
EII 5.12	Air Quality Sampling of Ambient and Downwind air at Waste Sites
EII 5.13	Drum Sampling
EII 5.14	Drum Handling
EII 6.1	Activity Reports of Field Operations
EII 6.6	Ground Water Well Characterization and Evaluation
EII 6.7	Resource Protection Well and Test Borehole Drilling
E11 6.8	Well Completion
EII 9.1	Geologic Logging
EII 10.1	Aquifer Testing
EII 10.2	Measurement of Ground-Water Levels
EII 10.3	Purge Water Management
EII 10.4	Well Development Activities
EII 11.1	Geophysical Logging

Table 4. Groundwater Sampling Parameters, Maximum Level.


Table 4. Groundwater Sampling P	Parameters", Maximum Level.
Interim primary drinking water standards	Maximum level ^b
Arsenie	0.05
Barium	1.0
Cadmi u m	0.01
Chromium	0.04
Fluoride	1.4 to 2.4
Lead	0.05
Mercury	0.002
Nitrate (as NO ₃)	45
Selenium	0.01
Silver	0.05
Endrin	0.0002
Lindane	0:004
Methoxychlor	0.1
Toxaphene	0.005
2,4 D	0.1
2,4,5 TP-Silvex	0.01
Radium	5 pCi/L
Gross Alpha	15 pCi/L
Gross Beta	4 mrem/year
Turbidity (surface water only)	1 NTU
Coliform bacteria	1/100 mL
Groundwater quality parameters	
Chloride	
Iron	
Manganese	
Phenols	
Sodium	
Sulfate	
Groundwater contamination indicat	or parameters
рН	
Specific conductance	
Total organic carbon	
Total organic halogen	
Site specific parameters	
Tritium	
Volatile halogenated hydrocarbons	
*Regulatory requirements for	

^{*}Regulatory requirements for sampling parameters are subject to change because of federal regulations.
**Unless otherwise noted, concentrations are in mg/L.


5.0 REFERENCES

- 29 CFR 1910.120, 1986, "Hazardous Waste Operations and Emergency Response," Code of Federal Regulations, as amended.
- 40 CFR 164.91(a), 1991, "Interim Status Standards for Owners and Operators of New Hazardous Waste Land Disposal Facilities," Code of Federal Regulations, as amended.
- 40 CFR 264, 1980, Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities, Title 40, Code of Federal Regulations, Part 264, as amended, U.S. Environmental Protection Agency, Washington, D.C.
- 40 CFR 265, 1980, Interim Status Standards for Owners and Operators of Hazardous Waste Treatment, Storage and Disposal Facilities, Title 40, Code of Federal Regulations, Part 265, as amended, U.S. Environmental Protection Agency, Washington, D.C.
- Bierschenk, H. W., 1959, Aquifer Characteristics and Ground-Water Movement at Hanford, HW-60601, General Electric Company, Richland, Washington.
- DOE, 1986, Environmental Assessment, Reference Repository Location, Hanford Site, Washington, DOE/RW-0070, U.S. Department of Energy, Office of Civilian Radioactive Waste Management, Washington, D.C.
- DOE, 1988, Consultation Draft, Site Characterization Plan, Reference Repository Location, Hanford Site, Washington, DOE/RW-0164, Vols. 1-9, Office of Civilian Radioactive Waste Management, U.S. Department of Energy, Richland, Washington.
- DOE, 1990, Non-Radioactive Dangerous Waste Landfill Closure/Postclosure Plan, DOE/RL-90-17, U.S. Department of Energy, Richland, Washington.
- Domenico, P. A. and G. A. Robbins, 1985, "A New Method of Contaminant Plume Analysis," *Groundwater*, Vol. 23, No. 4, pp. 476-485.
- Ecology, 1986, Consent Agreement and Compliance Order, DE 86-133, PCHB No. 86-44, Washington State Department of Ecology, Olympia, Washington.
- Ecology, EPA, and DOE, 1989, Hanford Federal Facility Agreement and Consent Order, Washington State Department of Ecology, U.S. Environmental Protection Agency, and the U.S. Department of Energy, Olympia, Washington.
- EPA, 1986, RCRA Groundwater Monitoring Technical Enforcement Guidance Document, OSWER-9950.1, U.S. Environmental Protection Agency, Washington, D.C.
- Evans, J. C., D. I. Dennison, R. W. Bryce, P. J. Mitchell, D. R. Sherwood, K. M. Krupka, N. W. Hinman, E. A. Jacobson, and M. D. Freshley, 1988, Hanford Site Ground-Water Monitoring for July through December 1987, PNL-6315-2, Pacific Northwest Laboratory, Richland, Washington.

- WAC 173-303, 1987, Dangerous Waste Regulations, Washington Administrative Code 173-303, Washington State Department of Ecology, Olympia, Washington.
- Wallace, R. W., 1977, Work Isolation Safety Assessment Program: A Comparison of Evapotranspiration Estimates Using ERDA Hanford Climatological Data, PNL-2698, Pacific Northwest Laboratory, Richland, Washington.
- Weekes, D. C., S. P. Luttrell, and M. R. Fuchs, 1987, Interim Hydrogeologic Characterization Report and Groundwater Monitoring System for the Nonradioactive Dangerous Waste Landfill, Hanford Site, Washington, WHC-EP-0021, Westinghouse Hanford Company, Richland, Washington.
- WHC, 1988, Environmental Investigations and Site Characterization Manual, WHC-CM-7-7, Westinghouse Hanford Company, Richland, Washington.
- WHC, 1990, Generic Specifications--Ground Water Monitoring Wells, WHC-S-014, Rev. 7, Westinghouse Hanford Company, Richland, Washington.
- WHC, 1993, Quality Assurance Project Plan for RCRA Groundwater Monitoring Activities, WHC-SD-EN-QAPP-001, Rev. 3, Westinghouse Hanford Company, Richland, Washington.



WHC-SD-EN-AP-026, Rev. O-A



REFERENCES

- American Public Health Association (APHA), 1985, Standard Methods for the Examination of Water and Wastewater, 16th ed., Washington, D.C.
- ASTM, 1986, 1986 Annual Book of ASTM Standards, American Society for Testing and Materials, Philadelphia, Pennsylvania.
- ASTM, 1988, "Standard Test Method for the Radionuclides of Radium in Water,"

 Annual Book of ASTM Standards, ASTM D2460, American Society of Testing and Materials, Philadelphia, Pennsylvania.
- EPA, 1984, Test Method for Determination of Inorganic Anions in Water by Ion Chromatography, EPA-600/4-84-017, Environmental Monitoring and Support Laboratory, U.S. Environmental Protection Agency, Cincinnati, Ohio.
- EPA, 1986, Test Methods for Evaluating Solid Waste Physical/Chemical Methods, 3rd ed, EPA SW-846, U.S. Environmental Protection Agency, Washington, D.C.
- Krieger, H. L. and E. L. Whittaker, 1980, Prescribed Procedures for Measurement of Radioactivity in Drinking Water, EPA-600/4-80-032, Environmental Monitoring and Support Laboratory, U.S. Environmental Protection Agency, Cincinnati, Ohio.
- PNL, 1989, Procedures for Ground Water Investigations, PNL 6894, Pacific Northwest Laboratory, Richland, Washington.
- WHC, 1989, Westinghouse Hanford Environmental Investigations and Site Characterization Manual, WHC-CM-7-7, Westinghouse Hanford Company, Richland, Washington.
- WHC, 1993, Quality Assurance Project Plan for RCRA Ground Water Monitoring Activities, WHC-SD-EN-QAPP-001, Rev. 3, Westinghouse Hanford Company, Richland, Washington.

	DISTRIBUTIO	N SHE	ET	18			
То	From		Page 1 of 1				
DISTRIBUTION	F. N. Hodges	F. N. Hodges			Date 12/27/1995		
Project Title/Work Order				EDT No.			
Interim Status Groundwater Mor Nonradioactive Dangerous Waste	nitoring Plan for Landfill, Hanfor	the rd, Washing	ıton .	ECN No. 63	4620		
Name	MSI N	Text With All Attac h.	Text Only	Attach. / Append ix Only	EDT/E CN Only		
D. J. Carrell D. W. Fritz D. M. Day A. K. McDowell F. N. Hodges J. S. Schmid D. G. Horton W. R. Thackaberry K. R. Fecht J. Rugg B. A. Williams Central Files EPIC	H6-22 H6-22 H6-06 R1-51 H6-06 H6-32 H4-85 H4-86 H6-06 A3-88 H6-08	X X X (2) X X X X (2) (2)					