

0064987



Geotechnical Laboratory
PO Box 4339
1570 Bear Creek Road
Oak Ridge TN 37830
(865) 482-6497

CERTIFICATE OF ANALYSIS


Stephen Trent
Fluor Hanford, Inc.
825 Jadwin Avenue
Richland, Washington 99352

February 10, 2005

109-023

This is the Certificate of Analysis for the following samples:

Shaw Project ID:	Eberline - Hanford
Shaw Project Number:	100846.50000000
Client Sample Data Group:	H2914
Date Received by Lab:	December 28, 2004
Number of Samples:	One (1)
Sample Type:	Soil



I. Introduction/Case Narrative

One soil sample was received by the Shaw Geotechnical Laboratory on December 28, 2004. The sample was submitted for determination of bulk density, sieve analysis, hydraulic conductivity, specific gravity, and calcium carbonate content. The sample number received was B1BR60.

Please see Appendix A, Sample Number Cross Reference List; Appendix B, Analysis Results; and Appendix C, Chain-of-Custody/Sample Receipt Records.

"I certify that this data package is in compliance with the SOW, both technically and for completeness, for other than the conditions detailed above. Release of the data contained in this hardcopy data package has been authorized by the Laboratory Manager or a designee, as verified by the following signature."

Reviewed and Approved:

Ralph Cole
Laboratory Manager, Geotechnical Services

RECEIVED
MAY 12 2005

EDMC
00000001

II. Analytical Results/Methodology

REFERENCES: United States Army Corps of Engineers (USACE), Engineer Manual 1110-2-1906, *Laboratory Soils Testing*, appendix II, 1970; United States Environmental Protection Agency, SW846, *Test Methods for Examining Solid Waste, Physical/Chemical Methods*, 3rd ed., Nov 1986 (EPA SW-846). Annual Book of ASTM Standards, Section 4, Construction, Volume 04.08, *Soil and Rock (I)*, and Volume 04.09, *Soil and Rock (II)*, 2004. Shaw Environmental and Infrastructure, Standard Operating Procedures.

Moisture Content of Soil and Rock.....	ASTM D 2216
Bulk Density of Soils	EM 1110-2-1906
Particle-size Analysis of Soils	ASTM D 422
Hydraulic Conductivity of Porous Materials Using a Flexible Wall Permeameter.....	ASTM D 5084
Specific Gravity of Soil.....	ASTM D 854
Calcium Carbonate Content.....	ASTM D 4373

III. Quality Control

Quality control checks such as duplicates and spikes (QC samples), are not normally applicable to geotechnical testing. This is due largely to the inability of obtaining samples with known characteristics, the heterogenous nature of the samples, and quality control procedures built-in to the analytical method.

QC measures to ensure accuracy and precision of test results include the following:

- 100% verification of all numerical results - raw data entries, transcriptions and calculations entered by lab technicians are checked, recalculated and verified. Most data calculations are performed by computer programs.
- Data validation through test reasonableness - summaries of all test results for individual reports are reviewed to determine the overall reasonableness of data and to determine the presence of any data that may be considered outliers.
- Quality control procedures are built into most standardized geotechnical procedures. For example, liquid limit and plastic limit analyses call for re-analyses and specify acceptance criteria.
- Routine instrument calibration - Instruments, gauges and equipment used in testing are calibrated on a routine basis. All instrument calibration follows ASTM or manufacturer guidelines.

00000002

- Maintenance of all past calibration records - calibration records and certification documents of all instruments, gauges and equipment are updated routinely and maintained in the Quality Control Coordinators Quality/Operations files.
- Certified and trained personnel - all technicians are certified by the National Institute for Certification of Engineering Technicians (NICET) in geotechnical soil testing, and are trained in the application of standard laboratory procedures for geotechnical analyses as well as the quality assurance measures implemented by Shaw.
- Quantitative analyses frequently used in geotechnical/physical testing programs do not use QC tools common to wet chemistry or radiochemistry laboratories. Measures not employed in the analysis of samples reported in this report include: laboratory control samples (LCS), blanks, matrix spikes (MS), duplicate analyses, dilutions, digestions, correction factors, surrogate sample analyses, detection limit determinations, control charts, and/or tentatively identified compounds (TICs).

IV. Data Qualification

None.

00000003

Appendix A
Sample Cross-Reference List

00000004

Page 4 of 11
February 10, 2005
Stephen Trent
Fluor Hanford, Inc.
Shaw Project Name: Eberline Hanford
Shaw Project No. 100848.50000000
SDG No. H2914

**Shaw Geotechnical
Laboratory
Oak Ridge TN
(865) 482-6497**

SAMPLE NUMBER CROSS-REFERENCE LIST

LAB SAMPLE NO.	CLIENT SAMPLE NO.	MATRIX
----------------	-------------------	--------

BC0518	B1BR60	Soil
--------------	--------------	------

00000005

Appendix B
Sample Test Results

00000006

000000007

**PARTICLE-SIZE DISTRIBUTION
 ASTM D 422**

Project Name Eberline Hanford

Field Sample No. B1BR60

Project No. 100846.50000000

Lab Sample No. BC0518


Moisture Content = 39.2%
 based on dry sample weight

SIEVE ANALYSIS

C O A R S E	Sieve No.	Diameter mm	Percent Finer
	3"	75.000	100.0%
	1.5"	37.500	100.0%
	0.75"	19.000	100.0%
	0.375"	9.500	100.0%
	#4	4.750	100.0%
	#10	2.000	100.0%

F I N E	Sieve No.	Diameter mm	Percent Finer
	#20	0.850	98.7%
	#40	0.425	94.2%
	#60	0.250	87.9%
	#100	0.149	84.3%
	#140	0.106	83.4%
	#200	0.075	82.0%

DISTRIBUTION CURVE



0.0% Gravel

18.0% Sand

82.0% Silt/Clay

00000008


**HYDRAULIC CONDUCTIVITY / PERMEABILITY
 ASTM D 5084**

PROJECT NAME: Eberline Hanford
 PROJECT NO. 100846.50000000

CLIENT SAMPLE NO. B1BR60
 LAB SAMPLE NO. BC0518

	INITIAL	FINAL		
Specimen diameter, cm	6.38		Hydraulic gradient	17.3
Specimen length, cm	8.15		Min. consolidation stress, psi	2.0
Wet weight of specimen, g.	457.79		Max. consolidation stress, psi	4.0
Specimen cross-sect. area, cm ²	32.01		Total backpressure, psi	8.0
Water content, %	39.2			
Wet unit weight, pcf	109.6		Permeant Fluid	Deaired DI Water
Dry unit weight, pcf	78.7			
Degree of saturation, %	94.2			
Specific gravity of solids	2.65			

Coefficient of Permeability, cm/s 3.9E-07



00000009

Page 8 of 11
February 10, 2005
Stephen Trent
Fluor Hanford, Inc.
Shaw Project Name: Eberline Hanford
Shaw Project No. 100846.50000000
SDG No. H2914

**Shaw Geotechnical
Laboratory
Oak Ridge TN
(865) 482-6497**

**SPECIFIC GRAVITY
ASTM D 854**

PROJECT NAME:
Eberline Hanford

PROJECT NUMBER:
100846.50000000

LAB SAMPLE NO.	CLIENT SAMPLE NO.	SPECIFIC GRAVITY
BC0518	B1BR60	2.7638

000000010

PROJECT NAME:
Eberline Hanford

[illegible]

Appendix C
Chain-of-Custody and Request-for-Analysis Records

Fluor Hanford Inc.		CHAIN OF CUSTODY/SAMPLE ANALYSIS REQUEST				F04-033-028	PAGE 1 OF 1	
COLLECTOR Alexander/Gent/Thomas		COMPANY CONTACT TRENT, SJ		TELEPHONE NO. 373-5869		PROJECT COORDINATOR TRENT, SJ		
SAMPLING LOCATION 200-ZP-1/C4301/435-440 ft		PROJECT DESIGNATION 200-ZP-1 Characterization Sampling and Analysis - Soil				SAF NO. F04-033		
ICE CHEST NO. 61RP-03-009		FIELD LOGBOOK NO.		COA 119325E510		METHOD OF SHIPMENT Federal Express		
SHIPPED TO Shaw Group		OFFSITE PROPERTY NO. SU PTK 14598				BILL OF LADING/NO. BILL NO. SU PTK 14598		
MATRIX* A=Air DL=Drum Liquids DS=Drum Solids L=Liquid O=Oil S=Soil SE=Sediment T=Tissue V=Vegetation W=Water WI=Wipe X=Other	POSSIBLE SAMPLE HAZARDS/ REMARKS Rad into B1BR65 SDG# H2914		PRESERVATION	None				
			TYPE OF CONTAINER	Split Spoon Liner				
			NO. OF CONTAINER(S)	2				
			VOLUME	1000g				
	SPECIAL HANDLING AND/OR STORAGE		SAMPLE ANALYSIS	SEE ITEM (1) IN SPECIAL INSTRUCTIONS				
SAMPLE NO.		MATRIX*	SAMPLE DATE	SAMPLE TIME				
B1BR60		SOIL	12/15/04	1645	X			
BC 0518								
CHAIN OF POSSESSION		SIGN/ PRINT NAMES				SPECIAL INSTRUCTIONS		
RELINQUISHED BY/REMOVED FROM		DATE/TIME		RECEIVED BY/STORED IN		DATE/TIME		
PM GENT/AM		12/15/04		REFRIG #1		12/15/04		
RELINQUISHED BY/REMOVED FROM		DATE/TIME		RECEIVED BY/STORED IN		DATE/TIME		
M. G. B. R. L. T.		12/14/04 1016		M. G. B. R. L. T.		12/14/04		
RELINQUISHED BY/REMOVED FROM		DATE/TIME		RECEIVED BY/STORED IN		DATE/TIME		
M. G. B. R. L. T.		12/14/04		M. G. B. R. L. T.		12/14/04		
RELINQUISHED BY/REMOVED FROM		DATE/TIME		RECEIVED BY/STORED IN		DATE/TIME		
F. J. E. C.		12/20/04 10:30		F. J. E. C.		12/20/04 8:30		
RELINQUISHED BY/REMOVED FROM		DATE/TIME		RECEIVED BY/STORED IN		DATE/TIME		
RELINQUISHED BY/REMOVED FROM		DATE/TIME		RECEIVED BY/STORED IN		DATE/TIME		
RELINQUISHED BY/REMOVED FROM		DATE/TIME		RECEIVED BY/STORED IN		DATE/TIME		
LABORATORY SECTION		RECEIVED BY Shaw				DATE/TIME 12/28/04 @ 1030		
FINAL SAMPLE DISPOSITION		DISPOSAL METHOD				DISPOSED BY		

(1) Bulk Density - D2937; Particle Size (Dry Sieve) - D422; Calcium Carbonate Content; Saturated Hydraulic Conductivity; Particle Density - D854;

#1 GW = 2.683 KG
#3 GW = 2.876 KG

TO SHAW LAB

PAGE 1

SDG# H2914

Eberline Svcs

CHAIN OF CUSTODY

ORD # R4-12-219

12/21/04 14:23:47

WORK ID: SAF# F04-033 SDG H2914

RCVD: 12/20/04 DUE: 02/03/05

KEEP: 02/03/06 DISP: S

DASH SAMPLE IDENTIFICATION

STORED

TESTS

01A-S B1BR60

HAW

| DISPOS

E329S

E331S

E335S

E342S

E345S

BC 0518

<u>RELEASED BY</u>	<u>DATE</u>	<u>TRANSFERRED TO</u>	<u>DATE</u>	<u>RECEIVED BY</u>	<u>DATE</u>
<i>Andersen</i>	<i>12/22/04</i>	<i>Shaw</i>	<i>12/22/04</i>	<i>[Signature]</i>	<i>12/23/04</i>
_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____
_____	_____	_____	_____	_____	_____

00000014