

## AR TARGET SHEET

The following document was too large to scan as one unit, therefore, it has been broken down into sections.

EDMC#: 0069233

SECTION: 2 OF 2

DOCUMENT #: DOE/RL-2005-63, Draft A

TITLE: FS for 200-CS-1 Chemical Sewer  
Group OU

1

## 5.0 REMEDIAL ACTION ALTERNATIVES

2 The U.S. Environmental Protection Agency (EPA) guidance for conducting feasibility studies  
3 under the *Comprehensive Environmental Response, Compensation, and Liability Act of 1980*  
4 recommends that a limited number of technologies be carried forward from the technology  
5 identification and screening activity; these technologies then are grouped into remedial  
6 alternatives to address the site-specific conditions. In Chapter 4.0, technologies were identified  
7 and screened based on site-specific characteristics and contaminants of concern. In this chapter,  
8 these technologies are grouped into remedial alternatives to address site contamination problems.  
9 Several remedial alternatives are developed and described in this chapter for the waste sites in  
10 the 200-CS-1 Operable Unit (OU). The applicability of these alternatives to the individual waste  
11 sites also is considered.

### 12 5.1 DEVELOPMENT OF ALTERNATIVES

13 Significant activities and evaluations have contributed to defining applicable technologies and  
14 process options that address the 200-CS-1 OU representative and analogous waste sites.  
15 DOE/RL-98-28, *200 Areas Remedial Investigation/Feasibility Study Implementation Plan –*  
16 *Environmental Restoration Program* (Implementation Plan), Appendix D, provides initial  
17 information on identification and screening of remedial technologies for 200 Area waste sites.  
18 The Implementation Plan, in conjunction with Chapter 4.0 of this feasibility study (FS),  
19 represents a Phase I FS and thus forms the basis for the development of remedial alternatives.  
20 The Implementation Plan also preliminarily develops remedial alternatives based on the results  
21 of the technology screening for the waste sites. Remedial alternatives identified in the  
22 Implementation Plan for the 200-CS-1 OU include the following:

- 23 • No action
- 24 • Monitored natural attenuation/institutional controls
- 25 • Removal, treatment, and disposal (onsite disposal and geologic repository)
- 26 • Containment using surface barriers.

27 Table 5-1 illustrates the process of identifying technology types, combining process options, and  
28 presenting the elements of each alternative. Evaluation of the no-action alternative is a  
29 requirement under the *Comprehensive Environmental Response, Compensation, and Liability*  
30 *Act of 1980*. The monitored natural attenuation/institutional controls alternative is retained and  
31 further developed in this FS for sites where existing remedial actions are in place or where  
32 contamination is expected to reach remedial action objectives (RAO) within a reasonable  
33 institutional controls period. The removal, treatment, and disposal alternative and the  
34 containment using surface barriers alternative also are retained and further developed in this FS.  
35 The in situ grouting or stabilization alternative, as a standalone alternative, is screened out of this  
36 FS because of implementation problems associated with the size and depth of the waste sites and  
37 unproven effectiveness on large-scale sites having radiological and chemical hazards. However,  
38 in situ grouting or stabilization technologies are retained for inclusion as elements of other  
39 remedial actions. The following subsections further develop and describe the alternatives.

1 One important factor in the development of site-specific remedial alternatives is that  
2 radionuclides, heavy metals, and some inorganic compounds cannot be destroyed. As such,  
3 these compounds must be physically immobilized, contained, or chemically converted to a less  
4 mobile or less toxic form to meet the RAOs.

## 5 **5.2 DESCRIPTION OF ALTERNATIVES**

6 This section provides a description of the selected alternatives considered for evaluation in this  
7 FS, including the following:

- 8 • Alternative 1 – No Action
- 9 • Alternative 2 – Maintain Existing Soil Cover, Monitored Natural Attenuation, and  
10 Institutional Controls
- 11 • Alternative 3 – Removal, Treatment, and Disposal
- 12 • Alternative 4 – Engineered Barrier.

### 13 **5.2.1 Alternative 1 – No Action**

14 The “National Oil and Hazardous Substances Pollution Contingency Plan” (40 CFR 300) (NCP)  
15 requires that a no-action alternative be evaluated as a baseline for comparison with other  
16 remedial alternatives. The no-action alternative represents a situation where no legal restrictions,  
17 access controls, or active remedial measures are applied to the site. No action implies “walking  
18 away from the waste site” and allowing the wastes to remain in their current configuration,  
19 affected only by natural processes. No maintenance or other activities are instituted or  
20 continued. Selecting the no-action alternative would require that a waste site pose no  
21 unacceptable threat to human health or the environment.

22 Based on the waste site evaluations and the results of the risk assessment, only one representative  
23 site and its analogous site in this FS may meet the RAOs using the no-action alternative. The  
24 sites are as follows:

- 25 • 216-S-10 Pond
- 26 • 216-S-11 Pond.

27 As stated above, the no-action alternative implies “walking away from the waste site.” However,  
28 before walking away from the site, confirmatory sampling would be performed at the  
29 216-S-11 Pond. The no-action alternative is carried forward in this FS for comparison purposes  
30 and to address analogous waste sites that are expected to meet the RAOs and preliminary  
31 remediation goals (PRG) without any action.

1 **5.2.2 Alternative 2 – Maintain Existing Soil Cover,**  
 2 **Monitored Natural Attenuation, and**  
 3 **Institutional Controls**

4 This alternative takes advantage of existing soil covers and the nature of the contaminants, in  
 5 combination with institutional controls, to provide protection of human health and the  
 6 environment. Monitoring also is an element of this alternative. For most of the waste sites in  
 7 this OU, an existing soil cover is present that is associated with the waste stabilization activities.  
 8 Under this alternative, these existing soil covers would be maintained and/or augmented as  
 9 needed to provide protection from intrusion by human and/or biological receptors. Institutional  
 10 controls, including legal and physical barriers, also would be used to prevent human access to the  
 11 site. The existing soil covers and/or caps would break the pathway between human and  
 12 ecological receptors and the contaminants. *Washington Administrative Code*  
 13 (WAC) 173-340-745(7), "Soil Cleanup Standards for Industrial Properties," "Point of  
 14 Compliance," identifies the points of compliance for different pathways as follows.

- 15 • "For soil cleanup levels based on protection of groundwater, the point of compliance  
 16 shall be established in the soils throughout the site."
- 17 • "For soil cleanup levels based on protection from vapors, the point of compliance shall be  
 18 established in the soils throughout the site from the ground surface to the uppermost  
 19 groundwater saturated zone."
- 20 • "For soil cleanup levels based on human exposure via direct contact or other exposure  
 21 pathways where direct contact with the soil is required to complete the pathway, the point  
 22 of compliance shall be established in the soils throughout the site from the ground surface  
 23 to fifteen feet below the ground surface."

24 WAC 173-340-7490, "Terrestrial Ecological Evaluation Procedures," specifies a standard point  
 25 of compliance at 4.6 m (15 ft) for ecological receptors; institutional control is not required under  
 26 this option. WAC 173-340-7490 also specifies a conditional point of compliance at the  
 27 biologically active soil zone, with a requirement for institutional controls. The regulation  
 28 assumes a 1.8 m (6 ft) below ground surface biologically active zone, but a site-specific zone  
 29 may be established.

30 Based on literature searches regarding the root and burrowing depths of vegetation and animals  
 31 present on the Hanford Site, a sufficient soil thickness to prevent biological intrusion generally  
 32 would be 2.4 to 3.0 m (8 to 10 ft). Most of the 200-CS-1 OU waste sites have a soil cover  
 33 (i.e., surface stabilization, backfill) over the contaminated zone of only a few feet.

34 Institutional controls involve the use of physical barriers (fences) and access restrictions (deed  
 35 restrictions) to reduce or eliminate exposure to contaminants of concern. Institutional controls  
 36 also can include groundwater, vadose zone, surface soil, biotic, and/or air monitoring.  
 37 Institutional controls for this alternative include periodic surveillance of the waste sites for  
 38 evidence of contamination and biologic intrusion; emplacement of vegetation, herbicide  
 39 application, manual removal, or other activities to control deep-rooted plants; control of  
 40 deep-burrowing animals; maintenance of signs and/or fencing; maintenance of the existing soil  
 41 cover (including an assumed periodic addition of soil); administrative controls; and site reviews.

1 For sites having a clean soil cover of less than 4.6 m (15 ft), more stringent institutional controls  
2 (e.g., physical and legal barriers) would need to be implemented to address potential risks from  
3 direct human and ecological contact with the contaminants. Water and land-use restrictions also  
4 would be used to prevent exposure.

5 Contaminants remaining beneath the clean soil cover would be allowed to attenuate naturally  
6 until remediation goals are met. Natural attenuation relies on natural processes to lower  
7 contaminant concentrations until cleanup levels are met. Monitored natural attenuation would  
8 include sampling and/or environmental monitoring, consistent with EPA guidance  
9 (EPA/540/R-99/009, *Use of Monitored Natural Attenuation at Superfund RCRA Corrective*  
10 *Action and Underground Storage Tank Sites November 1997*, OSWER No. 9200.17P), to verify  
11 that contaminants are attenuating as expected. Attenuation monitoring activities could include  
12 monitoring of the vadose zone using geophysical logging methods or groundwater monitoring to  
13 verify that natural attenuation processes are effective.

14 The existing network of groundwater monitoring wells in the Central Plateau is adequate for  
15 monitoring most sites, in coordination with the groundwater OUs 200-BP-5, 200-PO-1, and  
16 200-UP-1. Where the existing network is unsatisfactory, additional monitoring wells are  
17 planned. If remediation activities result in the decommissioning of groundwater monitoring  
18 wells in the area of remediation, an evaluation of future monitoring needs will be conducted.

### 19 **5.2.3 Alternative 3 – Removal, Treatment, and** 20 **Disposal**

21 Under this alternative, contaminated soil would be removed, treated if required to meet waste  
22 acceptance criteria, and disposed of to an appropriate facility. Some soil blending may be  
23 required to meet health and safety standards and waste acceptance criteria. A generalized  
24 cross-section for this alternative is shown in Figure 5-1. The disposal facility chosen depends on  
25 the type of waste to be disposed. The majority of the waste generated under this alternative  
26 would be disposed of at the Environmental Restoration Disposal Facility (ERDF).

27 Soil and associated structures (such as cribs) with contaminant concentrations above the PRGs  
28 would be removed using conventional excavation techniques where appropriate, or specialized  
29 excavation techniques where contamination levels require added protection (these specialized  
30 techniques are discussed in greater detail in Chapter 4.0). Excavated materials would be  
31 disposed of at an approved disposal facility, currently envisioned as the ERDF. Precautions  
32 would be used to minimize the generation of onsite fugitive dust. Depending on the  
33 configuration and depth of the area to be excavated, shoring might be required to comply with  
34 safety requirements and to reduce the quantity of excavated soil. The depth, and therefore the  
35 volume, of soil removed largely depend on the categories of PRGs that are exceeded. For  
36 example, if human health direct contact or ecological PRGs are exceeded, removals generally  
37 would be conducted to a maximum of 4.6 m (15 ft) in line with the points of compliance  
38 identified in WAC 173-340-745(7) and WAC 173-340-7490. If groundwater protection is  
39 required, soils would be removed to meet groundwater protection PRGs. Below-grade structures  
40 extending below 4.6 m (15 ft) would be removed, if practicable, or stabilized in place.  
41 Implementability, short-term risk to workers, and cost need to be evaluated to determine

1 appropriate excavation depths and to drive decisions between removal and other remedial  
2 actions.

3 The remediation of soil and associated structures for this alternative would be guided by the  
4 observational approach. The observational approach is a method of planning, designing, and  
5 implementing a remedial action that relies on information (e.g., samples, field screening)  
6 collected during remediation to guide the direction and scope of the activity. Data are collected  
7 to assess the extent of contamination and to make "real-time" decisions in the field. Targeted (or  
8 hot spot) removals could be considered under this alternative if contamination were localized in  
9 only a portion of a waste site.

10 Based on existing information, soil and/or debris removed from the waste sites may require  
11 treatment to meet ERDF waste acceptance criteria (BHI-00139, *Environmental Restoration*  
12 *Disposal Facility Waste Acceptance Criteria*). Additional activities may be required to meet  
13 health and safety requirements during excavation, handling, transportation, and disposal.  
14 Contaminated soil and structures will be containerized (e.g., containers, burrito wraps, bulk  
15 shipment) on site and transported to the ERDF, located in the 200 West Area.

16 After the PRGs are met, uncontaminated soil would be used to backfill the excavation. The  
17 backfill material could be found at a variety of sources, including local borrow pits and any  
18 remaining excavated material that is determined to be clean (verified as clean by meeting the  
19 PRGs). Following remediation, the site will be recontoured, resurfaced, and/or revegetated to  
20 establish natural site conditions. Maintenance of the site is required until the vegetation is  
21 sufficiently established to prevent intrusion by noxious, non-native plants such as cheatgrass or  
22 Russian thistle.

#### 23 5.2.4 Alternative 4 -- Engineered Barrier

24 The engineered barrier alternative, also known as the capping alternative, consists of  
25 constructing surface barriers over contaminated waste sites to control the amount of water that  
26 infiltrates into contaminated media, in order to reduce or eliminate leaching of contamination to  
27 groundwater. These barriers may include vertical slurry or grout walls to limit intrusion of water  
28 from the sides. In addition to their hydrological performance, barriers also can function as  
29 physical barriers to prevent intrusion by human and ecological receptors, limit wind and water  
30 erosion, and attenuate radiation. Additional elements to the capping alternative include  
31 institutional controls, discussed earlier, and monitored natural attenuation, where contamination  
32 undergoes natural processes in a reasonable amount of time.

33 The preferred capping technology for the Hanford Site is an evapotranspiration (ET) barrier, as  
34 shown in Figure 5-2. The ET surface barriers rely on the water-holding capacity of a soil,  
35 evaporation from the near-surface, and plant transpiration to control water movement through the  
36 barrier. These sites could have a variety of ET barriers; the most appropriate one would be  
37 determined during design.

38 If capping is identified as the preferred alternative, finalization of site-specific designs will occur  
39 as part of the remedial design process and will consider the RAOs and requirements defined in  
40 the record of decision, regulatory design and performance standards, material availability, cost

1 effectiveness, current surface barrier technology information, and site-specific hydrologic and  
2 physical performance requirements to ensure waste containment. Different waste sites likely  
3 will have varying barrier performance requirements, and more than one barrier design  
4 (e.g., monolithic and capillary barrier) may be deployed to address waste site capping needs.

5 When groundwater protection is required, the cap will limit the infiltration of precipitation.  
6 When the prevention of ecological and human intrusion is a performance requirement, then the  
7 physical barrier components to the cap become more important. The capping alternative  
8 includes provisions for groundwater monitoring for those waste sites with contamination  
9 predicted to threaten groundwater maximum concentration levels.

10 The effectiveness of the cap is related to the design, which must be specific to the conditions at  
11 the waste site, and to continued monitoring activities. Some recent preliminary fate and transport  
12 modeling for the BC Cribs and Trenches area has shown that reducing the infiltration rate to  
13 0.1 mm/yr by use of a cap would cause a five-fold reduction in the resulting groundwater  
14 concentration versus that for uncapped sites. Additional modeling will be needed to design an  
15 appropriate cap to achieve the most effective protection of groundwater.

16 Use of a capping alternative would require an assessment of the lateral extent of contamination  
17 during the confirmatory and/or remedial design sampling phases to properly size the cap to  
18 ensure containment. The site-specific extent of contamination can be assessed using a variety of  
19 approaches including, but not limited to, process knowledge, previous site investigations,  
20 geophysical logging, and/or soil sampling. Some degree of oversizing of the barrier beyond the  
21 footprint of the waste zone (referred to as overlap) is expected and is dependent on the barrier  
22 design used and the depth of contamination. For the purposes of this FS, an overlap of 6.1 m  
23 (20 ft) is assumed based on the performance of the Hanford Barrier. The type and availability of  
24 barrier construction materials also is a design consideration. The results of the most recent  
25 investigation (BHI-01551, *Alternative Fine-Grained Soil Borrow Source Study Final Report*)  
26 will be considered during remedial design for selection of the barrier construction materials.


27 Caps require surveillance and maintenance throughout their life to ensure continued protection.  
28 Performance monitoring will be conducted to ensure that the cap is performing as designed.  
29 Performance monitoring for this alternative will be twofold. The first component is groundwater  
30 monitoring. The second component is vadose zone monitoring, if practical. This FS assumes a  
31 robust performance-monitoring activity during the first 5 years after construction, followed by a  
32 more focused activity in subsequent years. The effectiveness of institutional controls to maintain  
33 the cap becomes uncertain past 150 years. For the majority of the sites in this FS, a design life of  
34 500 years is considered sufficient, because the fate and transport modeling indicate the  
35 contaminants do not reach groundwater within 1,000 years. For barriers that use naturally stable  
36 geologic materials, the key factor establishing life expectancy is projected wind-erosion rates,  
37 which will be minimized by maintaining the vegetation cover, adding gravel to the upper portion  
38 of the surface layer, or by using other armoring methods.

1 5.3 REFERENCES

- 2 40 CFR 300, "National Oil and Hazardous Substances Pollution Contingency Plan," Title 40,  
3 *Code of Federal Regulations*, Part 300, as amended.
- 4 BHI-00139, 2002, *Environmental Restoration Disposal Facility Waste Acceptance Criteria*,  
5 Rev. 4, Bechtel Hanford, Inc, Richland, Washington.
- 6 BHI-01551, 2002, *Alternative Fine-Grained Soil Borrow Source Study Final Report*, Rev. 0,  
7 Bechtel Hanford, Inc., Richland, Washington.
- 8 *Comprehensive Environmental Response, Compensation, and Liability Act of 1980*,  
9 42 USC 9601, et seq.
- 10 DOE/RL-98-28, 1999, *200 Areas Remedial Investigation/Feasibility Study Implementation*  
11 *Plan – Environmental Restoration Program*, Rev. 0, U.S. Department of Energy,  
12 Richland Operations Office, Richland, Washington.
- 13 EPA/540/R-99/009, 1999, *Use of Monitored Natural Attenuation at Superfund RCRA Corrective*  
14 *Action and Underground Storage Tank Sites November 1997*, OSWER 9200.4-17P,  
15 Office of Emergency and Remedial Response, U.S. Environmental Protection Agency,  
16 Washington, D.C.
- 17 WAC 173-340-745(7), "Soil Cleanup Standards for Industrial Properties," "Point of  
18 Compliance," *Washington Administrative Code*, as amended, Washington State  
19 Department of Ecology, Olympia, Washington.
- 20 WAC 173-340-7490, "Terrestrial Ecological Evaluation Procedures," *Washington*  
21 *Administrative Code*, as amended, Washington State Department of Ecology, Olympia,  
22 Washington.

1 Figure 5-1. Generalized Removal, Treatment, and Disposal Alternative (Alternative 3).


2



3 PRG = preliminary remediation goal.

1  
2

Figure 5-2. Evapotranspiration Barrier.



UP1-060503A

3

1

Table 5-1. Summary of Remedial Alternatives and Associated Components.

Technology Type	Process Option	Alternative 1 – No Action	Alternative 2 – Maintain Existing Soil Cover, Monitored Natural Attenuation, and Institutional Controls	Alternative 3 – Removal, Treatment, and Disposal	Alternative 4 – Engineered Barrier
No action	No action	X			
Land-use restrictions	Deed restrictions		X		X
Access controls	Signs/fences		X		X
	Entry control		X		X
Monitoring	Groundwater		X	X	X
	Vadose zone		X		X
	Air		X	X	X
Surface barriers	Existing soil cover		X		X
	Evapotranspiration barriers				X
In situ physical treatment	Dynamic compaction				X
	Grout injection				X
In situ thermal treatment	In situ vitrification				
Ex situ physical treatment	Soil mixing			X	
Removal	Conventional excavation			X	
	Excavation in high-concentration areas			X	
Landfill disposal	Onsite landfill			X	
Monitored natural attenuation	Offsite landfill/ repository			X	X
	Monitored natural attenuation	X	X	X	X

2

CHAPTER 6.0 TERMS

1		
2	95%UCL	95th upper confidence level
3	ARAR	applicable or relevant and appropriate requirement
4	bgs	below ground surface
5	CERCLA	<i>Comprehensive Environmental Response, Compensation, and</i>
6		<i>Liability Act of 1980</i>
7	COC	contaminant of concern
8	DOE	U.S. Department of Energy
9	Eco	Ecological
10	Ecology	Washington State Department of Ecology
11	EPA	U.S. Environmental Protection Agency
12	ERDF	Environmental Restoration Disposal Facility
13	FS	feasibility study
14	GW	groundwater
15	HH	human health
16	mrem	millirem
17	N/A	not applicable
18	NEPA	<i>National Environmental Policy Act of 1969</i>
19	OU	operable unit
20	PRG	preliminary remediation goal
21	RAO	remedial action objective
22	RCRA	<i>Resource Conservation and Recovery Act of 1976</i>
23	SESOIL	Seasonal Soil Compartment model
24	Tri-Parties	U.S. Department of Energy, U.S. Environmental Protection
25		Agency, and Washington State Department of Ecology
26	WAC	<i>Washington Administrative Code</i>

1

**This page intentionally left blank.**

2

## 6.0 DETAILED ANALYSIS OF ALTERNATIVES

This chapter presents the detailed analysis of the remedial alternatives described in Chapter 5.0 for the 200-CS-1 Operable Unit (OU) waste sites included in this feasibility study (FS). Figure 6-1 presents the guiding logic for selecting alternatives. The remedial alternatives are evaluated relative to seven of the nine *Comprehensive Environmental Response, Compensation, and Liability Act of 1980* (CERCLA) criteria, described in the next section. The remedial alternatives are evaluated for each site to determine if the CERCLA evaluation criteria are met.

The analogous waste site (216-S-11 Pond) was assigned to the representative site (216-S-10 Pond) based on physical similarities, waste management function (i.e., disposal versus conveyance), and similarities in the expected distribution of contamination using available information and process knowledge. For this reason, the analogous site is assumed to have contaminant distributions and risks similar to the representative site. Therefore, the detailed analysis for the representative site is assumed to be appropriate for the analogous site. The assignment of the analogous site to the representative site is explained in detail in Chapter 2.0.

The detailed analysis is presented by alternative. Within each alternative, each site is compared with each CERCLA evaluation criterion. Tables 6-1 through 6-3 provide a summary of the detailed analyses for the sites and the one analogous site.

The sites analyzed are as follows:

- 216-A-29 Ditch
- 216-B-63 Trench
- 216-S-10 Ditch
- 216-S-10 Pond and analogous site 216-S-11 Pond.

The analysis of the alternatives takes into account the nature of the contaminants at each site and the assumed land use. Currently, the land use for the 200 Areas is industrial in nature, associated with the management of waste. This land use can be reasonably predicted to be the same for the next 50 years, given the U.S. Department of Energy's (DOE) current commitment to vitrify waste in the tank farms. Industrial use is assumed for the foreseeable future.

### 6.1 DESCRIPTION OF EVALUATION CRITERIA

The U.S. Environmental Protection Agency (EPA) has developed nine CERCLA evaluation criteria, defined in EPA/540/G-89/004, *Guidance for Conducting Remedial Investigations and Feasibility Studies under CERCLA, (Interim Final)*, OSWER 9355.3-01, to address the statutory requirements and the technical and policy considerations important for selecting remedial alternatives. These criteria serve as the basis for conducting detailed and comparative analyses and for the subsequent selection of appropriate remedial actions.

1 The nine CERCLA evaluation criteria are as follows:

- 2 • Overall protection of human health and the environment
- 3 • Compliance with applicable or relevant and appropriate requirements (ARAR)
- 4 • Long-term effectiveness and permanence
- 5 • Reduction of toxicity, mobility, or volume through treatment
- 6 • Short-term effectiveness
- 7 • Implementability
- 8 • Cost
- 9 • State acceptance
- 10 • Community acceptance.

11 The first two criteria, overall protection of human health and the environment and compliance  
 12 with ARARs, are threshold criteria. Alternatives that do not protect human health and the  
 13 environment or those that do not comply with ARARs (or do not justify a waiver) do not meet  
 14 statutory requirements and are eliminated from further consideration in this FS.

15 The next five criteria (long-term effectiveness and permanence; reduction of toxicity, mobility,  
 16 or volume through treatment; short-term effectiveness; implementability; and cost) are balancing  
 17 criteria on which the remedy selection is based. The CERCLA guidance for conducting an FS  
 18 lists appropriate questions to be answered when evaluating an alternative against the balancing  
 19 criteria (EPA/540/G-89/004). The detailed analysis process in this chapter addresses these  
 20 questions, providing a consistent basis for the evaluation of each alternative.

21 The final two criteria, state and community acceptance, are modifying criteria. The criterion of  
 22 state acceptance will be addressed in DOE/RL-2005-64, *Proposed Plan for the 200-CS-1*  
 23 *Chemical Sewer Group Operable Unit*, prepared by the DOE, EPA, and Washington State  
 24 Department of Ecology (Ecology) (Tri-Parties). The Proposed Plan will identify the preferred  
 25 remedy (or remedies) accepted by the Tri-Parties. The criterion of community acceptance will  
 26 be evaluated following the issuance of the Proposed Plan for public review and comment.

27 In addition to the CERCLA criteria, *National Environmental Policy Act of 1969* (NEPA) values  
 28 have been incorporated into this document. Assessment of these considerations is important for  
 29 the integration of NEPA values into CERCLA documents, as called for by the *Secretarial Policy*  
 30 *on the National Environmental Policy Act* (DOE 1994) and DOE O 451.1A, *National*  
 31 *Environmental Policy Act Compliance Program*. Potential effects on NEPA values also are  
 32 discussed in this chapter.

### 33 **6.1.1 Overall Protection of Human Health and the** 34 **Environment**

35 This criterion determines whether adequate protection of human health and the environment,  
 36 including preservation of natural systems and biological diversity, is achieved through  
 37 implementation of the remedial alternative. Protection includes reducing risk to acceptable  
 38 levels, either by reducing contaminant concentrations or by eliminating potential routes for  
 39 exposure, and minimizing exposure threats introduced by actions during remediation.  
 40 Environmental protection includes avoiding or minimizing impacts to natural, cultural, and

1 historical resources. This criterion also evaluates the potential for human health risks, the extent  
2 of those risks, and whether a net environmental benefit will result from implementing the  
3 remedial alternative.

4 This first criterion is a threshold requirement and is the primary objective of the remedial action  
5 program. As indicated in EPA guidance, this criterion, and the criteria for compliance with  
6 ARARs, long-term effectiveness and permanence, and short-term effectiveness, overlap  
7 (EPA/540/G-89/004). This FS used the CERCLA risk range of  $1 \times 10^{-4}$  to  $1 \times 10^{-6}$  excess  
8 lifetime cancer risk for human health as the range of protectiveness. Alternatives were measured  
9 against this standard to determine if the alternative meets this criterion. Protection of  
10 groundwater was measured against groundwater protection standards derived from the maximum  
11 contaminant levels identified in 40 CFR 141, "National Primary Drinking Water Regulations,"  
12 and in fate and transport modeling, reported in DOE/RL-2004-17, *Remedial Investigation Report*  
13 *for the 200-CS-1 Chemical Sewer Group Operable Unit*, and Appendix C of this FS. Ecological  
14 compliance was judged using *Washington Administrative Code (WAC) 173-340-900, "Tables,"*  
15 *and DOE/STD-1153-2002, A Graded Approach for Evaluating Radiation Doses to Aquatic and*  
16 *Terrestrial Biota.*

#### 17 6.1.2 Compliance with Applicable or Relevant and 18 Appropriate Requirements

19 The ARARs are any appropriate standards, criteria, or limitations under any Federal  
20 environmental law or more stringent state requirement that must be either met or waived for any  
21 hazardous substance, pollutant, or contaminant that will remain on site during or after  
22 completion of a remedial action. The ARAR identification process is based on CERCLA  
23 guidance (EPA/540/2-88/002, *Technological Approaches to Cleanup of Radiologically*  
24 *Contaminated Superfund Sites*; EPA/540/G-89/004). Potential Federal and state chemical-,  
25 location-, and action-specific ARARs associated with remediation of the waste sites addressed in  
26 this FS are presented in Appendix B, and each alternative is assessed for compliance against  
27 these ARARs. When an ARAR cannot be met, the lead agency can request a waiver if there is a  
28 solid basis for justifying the waiver.

#### 29 6.1.3 Long-Term Effectiveness and Permanence

30 This criterion addresses the results of a remedial action in terms of risks that remain at the site  
31 after remedial action objectives (RAO) are met. The primary focus of this evaluation is the  
32 extent and effectiveness of the controls that could be required to manage the risk posed by  
33 treatment residuals and/or untreated wastes. The following components of the criterion are  
34 considered for each alternative:

- 35 • Magnitude of residual risk to human and ecological receptors. This factor assesses the  
36 residual risk from untreated waste or treatment residue after remedial activities are  
37 completed. The characteristics of the residual waste are considered to the degree that  
38 they remain hazardous, taking into account their volume, toxicity, mobility, and  
39 propensity to bioaccumulate.

- Adequacy and reliability of controls. This factor assesses the adequacy and suitability of controls used to manage treatment residues or untreated wastes that remain at the site. It also assesses the long-term reliability of management controls for providing continued protection from residues, and it includes an assessment of the potential need to replace the alternative's technical components.

A related consideration is the restoration time required to reestablish sustainable environmental conditions, including fish and wildlife habitat and cultural resources, where appropriate. Residual risk to natural and cultural resources after conclusion of remedial activities also is evaluated. Current environmental conditions are assessed against the alternative's long-term and permanent solutions. The assessment considerations are based on whether lasting environmental losses would be incurred for the sake of short-term cleanup gains, including whether environmental restoration and/or mitigation options would be precluded if a remedial alternative were implemented.

#### **6.1.4 Reduction of Toxicity, Mobility, or Volume through Treatment**

This criterion addresses the degree to which a remedial alternative reduces the toxicity, mobility, or volume of a hazardous substance through treatment. Significant overall reduction can be achieved by destroying toxic contaminants or by reducing total mass, contaminant mobility, or total volume of contaminated media.

This criterion focuses on the following factors for each alternative:

- The treatment processes used and the materials treated
- Whether recycling, reuse, and/or waste minimization are used in the treatment process
- The type and quantity of treatment residuals that remain following treatment, and whether any special treatment actions will be needed
- Whether the alternative satisfies the statutory preference for treatment as a principal element.

#### **6.1.5 Short-Term Effectiveness**

This criterion evaluates the potential effects on human health and the environment during the construction and implementation phases of a remedial action. This criterion also considers the speed with which an alternative achieves protection. The following factors are considered for each alternative:

- Health and safety of remediation workers and reliability of protective measures taken. Specifically, this involves any risk resulting from implementation, such as fugitive dust, transportation of hazardous materials, or air quality impacts from offgas emissions.

- 1 • Physical, biological, and cultural impacts that might result from the construction and  
2 implementation of the remedial action, and whether the impacts can be controlled or  
3 mitigated.
- 4 • The amount of time for the RAOs to be met.

5 Short-term human health impacts are closely related to the duration of exposure to hazardous  
6 waste and the risks associated with waste removal. The greater the exposure time, the greater the  
7 risk. Guidelines will be followed during implementation of the remedial action to minimize  
8 worker risks and to maintain radiation exposures as low as reasonably achievable.

9 Short-term environmental impacts are related primarily to the extent of physical disturbance of a  
10 site and its associated habitat. Risks also can be associated with the potential disturbance of  
11 sensitive species (e.g., bald eagles) because of increased human activity in the area.

#### 12 6.1.6 Implementability

13 This criterion addresses the technical and administrative feasibility of implementing an  
14 alternative and the availability of the required services and materials.

15 The following factors are considered for each alternative:

- 16 • Technical feasibility
  - 17 – The likelihood of technical difficulties in constructing and operating the alternative
  - 18 – The likelihood of delays because of technical problems
  - 19 – Uncertainties related to innovative technologies (e.g., failures)
- 20 • Administrative feasibility
  - 21 – Ability to coordinate activities with other offices and agencies
  - 22 – Potential for regulatory constraints to develop (e.g., as a result of uncovering buried  
23 cultural resources or encountering endangered species)
- 24 • Availability of services and materials
  - 25 – Availability of adequate onsite or offsite treatment storage capacity, and disposal  
26 services, if necessary
  - 27 – Availability of necessary equipment, specialists, and provisions to ensure obtaining  
28 any additional resources, if necessary.

#### 29 6.1.7 Cost

30 This criterion considers the cost of implementing a remedial alternative, including capital costs,  
31 operation and maintenance costs, and monitoring costs. The cost evaluation also includes

1 monitoring of any restoration or mitigation measures for natural, cultural, and historical  
2 resources.

3 The cost estimates for the purposes of this study are presented in either 2003 constant dollars or  
4 present-value terms. The cost estimates were prepared from information available at the time of  
5 this study. The actual cost of the project will depend on additional information gained during the  
6 remedial design phase, the final scope and design of the selected remedial action, the schedule of  
7 implementation, the competitive market conditions, and other variables. However, most of these  
8 factors are not expected to significantly affect the relative cost differences of alternatives.

#### 9 **6.1.8 State Acceptance**

10 This criterion evaluates the technical issues and concerns that the EPA and Ecology could have  
11 regarding a remedial alternative. The regulatory acceptance process would involve a review and  
12 concurrence by the EPA and the Ecology. This criterion will be addressed at the time that the  
13 Proposed Plan (DOE/RL-2005-64) is published.

#### 14 **6.1.9 Community Acceptance**

15 This criterion evaluates the issues and concerns that the public may have regarding a remedial  
16 alternative. This criterion will be addressed following public review of the proposed plan.

### 17 **6.2 DETAILED ANALYSIS OF ALTERNATIVES**

18 This section presents the detailed analysis of the alternatives evaluated under an industrial  
19 (exclusive) land-use scenario. This section is followed by a NEPA evaluation. Detailed  
20 evaluations were performed at the 216-A-29 Ditch, 216-B-63 Trench, 216-S-10 Ditch, and  
21 216-S-10 Pond. Data obtained at the representative site were used to evaluate the analogous site.

22 The following detailed evaluations are applicable to the waste sites and the one analogous site.  
23 Unless noted, when a site name is used, it means the representative site plus the associated  
24 analogous site.

#### 25 **6.2.1 Detailed Analysis of Alternative 1 – No Action**

26 Alternative 1 is retained for detailed analysis as a baseline description of the effects of taking no  
27 action and is required by CERCLA regulations.

##### 28 **6.2.1.1 Overall Protection of Human Health and the Environment**

29 For the four waste sites addressed by this FS, the no-action alternative would fail at the  
30 216-A-29 Ditch and 216-S-10 Ditch to provide overall protection of human health and the  
31 environment. These sites fail to meet the overall protection criteria because contaminants at  
32 concentrations above the preliminary remediation goals (PRG) would remain on site with no  
33 measures performed to prevent intrusion to the contaminants or to monitor their migration. At

1 two sites, 216-S-10 Pond and 216-S-11 Pond, the no-action alternative would meet PRGs. The  
 2 No Action alternative meets the threshold criteria for overall protection of human health and the  
 3 environment and compliance with ARARs at the 216-B-63 Trench because contaminants are  
 4 within the 95th upper confidence level (95%UCL) for direct human contact, groundwater  
 5 protection, or ecological receptors

#### 6 **6.2.1.2 Compliance with Applicable or Relevant and Appropriate Requirements**

7 Because no action would be taken to control the exposure pathway, this alternative would not  
 8 meet the ARARs for two of the waste sites mentioned above. For the 216-B-63 Trench,  
 9 216-S-10 Pond, and its analogous site, all ARARs are anticipated to be met under Alternative 1  
 10 because they meet the PRGs or are within the 95%UCL for direct human contact, groundwater  
 11 protection, or ecological receptors.

12 ARARs include risk-based concentrations for soil cleanup that, if exceeded, would result in a  
 13 radiological dose of 15 mrem/yr or greater under an industrial scenario. As shown in Table 2-39,  
 14 the 216-A-29 Ditch, and 216-S-10 Ditch exceed PRGs for ecological protection.

15 Modeling indicates that only the 216-A-29 Ditch is predicted to require groundwater protection.  
 16 EPA's Seasonal Soil compartment model (SESOIL) was used to predict whether contaminants of  
 17 concern (COC) in soil may migrate to groundwater and result in groundwater concentrations that  
 18 exceed Federal maximum contaminant levels. These levels are defined as the average annual  
 19 activity of beta particles and photon radioactivity from manmade radionuclides in drinking water  
 20 that produces an annual dose equivalent to the total body or any internal organ of greater than  
 21 4 mrem/yr (40 CFR 141.66, "National Primary Drinking Water Regulations," "Maximum  
 22 Contaminant Levels for Radionuclides").

23 As summarized in Table 2-39, concentrations of nonradiological constituents at the  
 24 216-A-29 Ditch and 216-S-10 Ditch exceed wildlife-screening values presented in  
 25 WAC 173-340-900, Table 749-3.

26 Because no remedial activities would take place under this alternative, action-specific ARARs  
 27 would not be triggered. No location-specific ARARs have been identified for the waste sites.

#### 28 **6.2.1.3 Long-Term Effectiveness and Permanence**

29 **Long-Term Effectiveness and Permanence for Human Health.** The no-action alternative  
 30 provides long-term effectiveness and permanence for human health, because the COCs are below  
 31 the human health PRGs.

32 **Long-Term Effectiveness and Permanence for Groundwater.** Contaminants are predicted to  
 33 reach the groundwater at the 216-A-29 Ditch. No contaminants are predicted to reach the  
 34 groundwater in excess of maximum contaminant levels at any of the other sites. Therefore,  
 35 Alternative 1 does provide long-term effectiveness for groundwater protection for those sites and  
 36 their analogous site.

37 **Long-Term Effectiveness and Permanence for the Environment.** Two sites, 216-A-29 Ditch,  
 38 and 216-S-10 Ditch, do not meet the standard for protection of the environment in the 0 to 4.6 m

1 (0 to 15 ft) below ground surface (bgs) zone. The other three sites, 216-B-63 Trench,  
2 216-S-10 Pond, and 216-S-11 Pond, meet the standard for protection of the environment.

### 3 **6.2.1.4 Reduction of Toxicity, Mobility, or Volume through Treatment**

4 Reduction of toxicity, mobility, or volume would occur at all the waste sites in the form of  
5 natural attenuation. Natural attenuation is a process that results in a reduction of toxicity,  
6 mobility, or volume through the natural radioactive decay process. Radioactive decay is the only  
7 process currently available to eliminate nuclear particle emissions. The radioactive decay  
8 process would influence some of the contaminants identified during characterization. In  
9 addition, the heavy metals and Aroclor 1254<sup>1</sup> (polychlorinated biphenyl) are persistent in the  
10 environment and require a long period to attenuate naturally.

11 In EPA/540/R-99/009, *Use of Monitored Natural Attenuation at Superfund RCRA Corrective*  
12 *Action and Underground Storage Tank Sites November 1997*, OSWER 9200.4-17P, the EPA  
13 acknowledges that natural attenuation can be an appropriate treatment for contaminated soil.  
14 Because of uncertainties in the science of natural attenuation processes, the EPA considers  
15 source control and performance monitoring to be fundamental components of the remedy. The  
16 no-action alternative does not use any source control or monitoring. Because of the  
17 concentrations of contaminants and the substantial length of time required for natural attenuation  
18 processes to meet PRGs, this alternative fails for waste sites 216-A-29 Ditch and 216-S-10 Ditch  
19 to meet this criterion under CERCLA. The other sites meet the requirements of this criterion  
20 because they meet PRGs or are within the 95%UCL for direct human contact, groundwater  
21 protection, or ecological receptors.

### 22 **6.2.1.5 Short-Term Effectiveness**

23 No short-term risks to humans would be associated with the no-action alternative because  
24 remedial activities would not be conducted. Current risks to workers are not an issue because of  
25 protective soil covers and appropriate safety measures for work activities. Ecological risk  
26 currently exists at two sites (216-A-29 Ditch and 216-S-10 Ditch), and, therefore, this alternative  
27 fails to meet the criterion for short-term effectiveness at two of the sites. These risks would not  
28 be mitigated in the no-action alternative. The other sites meet the requirements of this criterion  
29 because they meet PRGs or are within the 95%UCL for direct human contact, groundwater  
30 protection, or ecological receptors.

### 31 **6.2.1.6 Implementability**

32 The no-action alternative could be implemented immediately and would not present any  
33 technical problems. Radionuclides at the waste sites addressed by this FS are currently  
34 undergoing natural attenuation.

---

<sup>1</sup>Aroclor is an expired trademark.

1 **6.2.1.7 Cost**

2 The no-action alternative would involve no cost, except the confirmatory sampling cost  
3 associated with the one analogous site. The cost associated with this additional work is assumed  
4 minimal.

5 **6.2.2 Detailed Analysis of Alternative 2 – Maintain**  
6 **Existing Soil Cover, Monitored Natural**  
7 **Attenuation, and Institutional Controls**

8 Under this alternative, existing soil covers and/or caps would be maintained to provide protection  
9 from intrusion by human and/or biological receptors. Legal and physical barriers also would be  
10 used to prevent human access to the site. The existing soil covers and/or caps would break the  
11 pathway between human and ecological receptors and the contaminants. Groundwater  
12 monitoring is included in this alternative.

13 The following sections present a detailed analysis of Alternative 2 against the evaluation criteria.  
14 This analysis is summarized in Table 6-1.

15 **6.2.2.1 Overall Protection of Human Health and the Environment**

16 Alternative 2 would provide overall protection of human health and the environment for sites  
17 that show protection of groundwater and achieve human health and environmental protection  
18 within 500 years. Because the viability of institutional controls cannot be ensured past  
19 500 years, this alternative fails to meet this criterion for sites with long-lived contaminants such  
20 as heavy metals because the waste sites would have contamination that would not attenuate to  
21 acceptable levels within 500 years. Risk assessment details are contained in Chapter 2.0.

22 **216-A-29 Ditch** – This waste site does not exceed human health direct-contact protection  
23 criteria; however, it exceeds both groundwater and ecological PRGs in the 0 to 4.6 m (0 to 15 ft)  
24 zone. As such, this alternative is not protective of groundwater or the environment.

25 **216-B-63 Trench** – The 216-B-63 Trench meets the criteria for overall protection of human  
26 health and the environment because contaminants are within the 95%UCL for direct human  
27 contact, groundwater protection, or ecological receptors.

28 **216-S-10 Ditch** – The 216-S-10 Ditch site does not exceed groundwater protection criteria or  
29 human health direct-contact PRGs. However, it does exceed the ecological PRGs in the 0 to  
30 4.6 m (0 to 15 ft) zone. As such, this alternative is not protective of the environment.

31 **216-S-10 Pond and its Analogous Site** – The 216-S-10 Pond and its analogous site  
32 (216-S-11 Pond) meet the criteria for overall protection of human health and the environment  
33 because they currently meet PRGs.

### 1 **6.2.2.2 Compliance with Applicable or Relevant and Appropriate Requirements**

2 Under Alternative 2, groundwater ARARs would not be met at the 216-A-29 Ditch. ARARs  
3 would not be met at two sites (216-A-29 Ditch and 216-S-10 Ditch) for ecological protection.  
4 Risk analysis (Chapter 2.0 and Table 2-39) shows that ecological protection standards will be  
5 exceeded at the 216-A-29 Ditch and 216-S-10 Ditch. Conversely, the 216-B-63 Trench and the  
6 216-S-10 Pond representative site meets ARARs.

### 7 **6.2.2.3 Long-Term Effectiveness and Permanence**

#### 8 **Human Health**

9 Alternative 2 would rely on natural attenuation (e.g., radioactive decay) to decrease contaminants  
10 until concentrations reached levels that would be protective of human health and the  
11 environment. As mentioned under Alternative 1, natural attenuation is a proven and acceptable  
12 technology. This alternative would incorporate the use of institutional controls to prevent  
13 inadvertent human and biological intrusion into the waste until contaminant concentrations  
14 reached acceptable levels. Institutional controls (e.g., deed restrictions, fencing, signage,  
15 monitoring of groundwater) would be required components of this alternative. Institutional  
16 controls generally are considered to be proven and acceptable technologies meant to prevent  
17 access to hazards. To be effective, institutional control and monitoring would be required for the  
18 entire time that contaminants exceed PRGs. Institutional controls are assumed to lapse after  
19 500 years.

20 Table 2-39 summarizes risk assessments for the four sites. The 216-A-29 Ditch groundwater  
21 protection standards are exceeded. At the 216-A-29 Ditch and 216-S-10 Ditch, the ecological  
22 contaminants are persistent in the environment. The chemical contaminants that pose ecological  
23 risk will not decay, and after the institutional control period, it may be expected that deep-rooted  
24 flora may be exposed to these contaminant.

25 **216-A-29 Ditch** – Under Alternative 2, COCs would remain in the vadose zone at concentrations  
26 below the PRGs. Therefore, this alternative is protective of human health in the long term.

27 **216-B-63 Trench** – Under Alternative 2, the 216-B-63 Trench meet the criteria for long-term  
28 effectiveness because contaminants are within the 95%UCL for direct human contact,  
29 groundwater protection, or ecological receptors.

30 **216-S-10 Ditch** – Under Alternative 2, COCs would remain in the vadose zone at concentrations  
31 below the PRGs. Therefore, this alternative is protective of human health in the long term.

32 **216-S-10 Pond and its Analogous Site** – Under Alternative 2, the 216-S-10 Pond and its  
33 analogous site meet the criteria for long-term effectiveness because they currently meet PRGs.

#### 34 **Protection of Groundwater**

35 **216-A-29 Ditch** – Nitrate is predicted to reach the groundwater at this site. Therefore,  
36 Alternative 2 does not provide long-term effectiveness for groundwater protection for this site.

1 **216-B-63 Trench** – No contaminants are predicted to reach the groundwater above maximum  
2 contaminant levels at this site. Therefore, Alternative 2 provides long-term effectiveness for  
3 groundwater protection for this site.

4 **216-S-10 Ditch** – No contaminants are predicted to reach the groundwater at this site.  
5 Therefore, Alternative 2 provides long-term effectiveness for groundwater protection for this  
6 site.

7 **216-S-10 Pond and its Analogous Site** – No contaminants are predicted to reach the  
8 groundwater at this site. Therefore, Alternative 2 provides long-term effectiveness for  
9 groundwater protection for this representative site and its analogous site.

## 10 **The Environment**

11 Two of the sites (216-A-29 Ditch and 216-S-10 Ditch) have contaminants located in the shallow  
12 soils (0 to 4.6 m [0 to 15 ft] bgs) that present potential risks to burrowing animals. At the  
13 216-A-29 and 216-S-10 Ditches, the COCs are persistent in the environment. As such, this  
14 alternative fails to provide long-term protection to the environment. The 216-B-63 Trench and  
15 the 216-S-10 Pond sites currently meet ARARs. Therefore, this alternative provides long-term  
16 protection to the environment.

### 17 **6.2.2.4 Reduction of Toxicity, Mobility, or Volume through Treatment**

18 Alternative 2 does not provide any engineered treatment to reduce toxicity, mobility, or volume.  
19 However, natural attenuation will occur through radioactive decay. In EPA/540/R-99/009, the  
20 EPA acknowledges that natural attenuation can be an appropriate treatment for contaminated  
21 soil. Because of uncertainties in the science of natural attenuation process, the EPA considers  
22 source control and performance monitoring to be fundamental components of the alternative.

23 This alternative provides a reduction in the mass of radionuclides and chemical contaminants at  
24 the four sites. However, two sites, the 216-A-29 Ditch and 216-S-10 Ditch, contain  
25 polychlorinated biphenyls and heavy metals, which are persistent in the environment.

### 26 **6.2.2.5 Short-Term Effectiveness**

#### 27 **6.2.2.5.1 Remediation Worker Risk**

28 For Alternative 2, only minimal short-term worker risks are expected, and these risks are  
29 associated with monitoring and maintenance activities. Experienced workers using appropriate  
30 safety precautions would conduct these activities. Risks would decrease over time as the  
31 chemicals decompose. As such, the risk to workers is qualitatively identified as low.  
32 Additionally, active DOE control of the Central Plateau is assumed for the next 50 years given  
33 DOE's commitment to vitrify the waste in the tank farms. Therefore, failure of this alternative in  
34 the short term is considered unlikely.

#### 1 **6.2.2.5.2 Impact to Environment During Remediation**

2 This alternative reduces the risk to human and ecological receptors using existing soil covers and  
3 the implementation of institutional controls. Currently, the 216-A-29 Ditch and 216-S-10 Ditch  
4 have contamination within the shallow soils (0 to 4.6 m [0 to 15 ft]). As such, short-term  
5 impacts to vegetation and wildlife may occur at these sites during the implementation of this  
6 alternative. The waste sites have been highly disturbed, and the existing soil cover provides  
7 protection for all but the deep-rooted flora or deep-burrowing animals. The short-term impacts  
8 to the environment are expected to be low.

#### 9 **6.2.2.5.3 Time to Meet the Remedial Action Objectives**

10 In this alternative, RAOs only can be fully met through natural decomposition of contaminants,  
11 which can take hundreds of years to achieve. As such, the 216-B-63 Trench, 216-S-10 Pond, and  
12 the analogous site meet this RAO. However, the remaining sites do not meet RAOs in a  
13 reasonable time frame.

#### 14 **6.2.2.6 Implementability**

15 Alternative 2 could be readily implemented and would not present technical problems. This  
16 alternative currently is being implemented through Hanford Site access controls, surface and  
17 subsurface radiation area work and access controls, and the waste site/radiation area surveillance  
18 and maintenance program.

#### 19 **6.2.2.7 Cost**

20 Cost estimates for Alternative 2 were developed based on existing costs for similar activities  
21 currently conducted on the Hanford Site. Details of the cost estimates are presented in  
22 Appendix D. Summarized costs for the sites are presented in Table 6-1. The input parameters  
23 used in these estimates are the best available at this time, but in many cases the data on COCs,  
24 site locations, and site dimensions are limited. The uncertainties identified above are similar for  
25 all the sites evaluated in this FS. Despite these uncertainties, the cost estimates are of sufficient  
26 quality to fulfill the primary objective, which is to aid in selecting preferred remedial  
27 alternatives.

28 This alternative involves costs for activities similar to current activities. These activities involve  
29 periodic surveillance of the waste sites for evidence of contamination and biologic intrusion;  
30 emplacement of vegetation, herbicide application, or other activities to control deep-rooted  
31 plants; control of deep-burrowing animals; maintenance of signs and/or fencing; maintenance of  
32 the existing soil cover (including an assumed periodic addition of soil); administrative controls;  
33 and site reviews. The present-worth costs assume a 3.2 percent discount rate (based on  
34 2003 Office of Management and Budget information) and assumes an operation and maintenance  
35 period equal to the time required for PRGs to be met.

1 **6.2.3 Detailed Analysis of Alternative 3 – Removal,**  
 2 **Treatment, and Disposal**

3 Under Alternative 3, contaminated soil and debris (such as concrete or pipe associated with the  
 4 sites) would be removed, treated as necessary to meet disposal facility waste acceptance criteria,  
 5 and transported for disposal at an approved waste disposal facility. Soils would be removed to  
 6 meet PRGs. Alternative 3 has two potential disposal paths: one for disposal of soils  
 7 contaminated with only chemicals and one for disposal of soils that are not contaminated with  
 8 both chemicals and radionuclides. These latter soils would be disposed on-site at the  
 9 Environmental Restoration Disposal Facility (ERDF). Soils are not anticipated to require  
 10 treatment before disposal at the ERDF, based on the data collected for the waste sites.  
 11 Alternative 3 would remove contaminated waste and soil from waste sites to a depth to meet the  
 12 RAOs.

13 This alternative generally provides a high degree of overall protection of human health and the  
 14 environment, because contaminants are removed to meet PRGs. Removal of the contaminants  
 15 provides for the most flexibility for future land use.

16 This alternative would provide future protection to humans and the environment because the  
 17 contaminants are removed from the waste site. The groundwater would be protected because  
 18 COCs are removed to meet the PRGs. The contaminated soil would be removed from a waste  
 19 site and placed in an approved disposal facility; therefore, failure of this alternative is not likely.  
 20 Residual risks would be at acceptable levels for protection of human health, the environment,  
 21 and groundwater. Verification sampling would be conducted to determine that PRGs are met by  
 22 the removal activities. Risks associated with the failure of the disposal facility are not evaluated  
 23 here, but are evaluated as part of the permitting process for the facility.

24 **6.2.3.1 Overall Protection of Human Health and the Environment**

25 Because this alternative removes contaminants that are above PRGs, it provides overall  
 26 protection (human health and the environment) in all cases.

- 27 • **216-A-29 Ditch** – Risk analysis of the 216-A-29 Ditch showed that contamination above  
 28 PRGs occurs only in the shallow zone (0 to 4.6 m [0 to 15 ft]). A groundwater and  
 29 ecological risk is present due to presence of nitrates, Aroclor 1254, and heavy metals.  
 30 Chemical and radiological contaminants in excess of the PRGs extend to a depth of  
 31 approximately 4 m (13 ft). Existing data indicate that the southern 306.4 m (1,005 ft) and  
 32 the 779.9 m (2,558 ft) of the ditch exceed PRGs.
- 33 • **216-B-63 Trench** – Analysis of the 216-B-63 Trench shows contaminants are within the  
 34 95%UCL for direct human contact, groundwater protection, or ecological receptors.  
 35 Therefore, this alternative does not apply
- 36 • **216-S-10 Ditch** – Risk analysis of the 216-S-10 Ditch showed that contamination above  
 37 PRGs occurs only in the shallow zone (0 to 4.6 m [0 to 15 ft]). The only risk to human  
 38 health and the environment is an ecological risk from Aroclor 1254 and heavy metals.  
 39 Chemical contaminants in excess of the PRGs extend to a depth of approximately 4.6 m

1 (15 ft). Existing data indicate that only the northern 296.3 m (972 ft) of the ditch exceed  
2 PRGs. Therefore, only the northern portion of the ditch requires remedial action.

- 3 • **216-S-10 Pond and its Analogous Site** – Analysis of the 216-S-10 Pond shows no  
4 contaminants above PRGs. Therefore, this alternative does not apply.

### 5 **6.2.3.2 Compliance with Applicable or Relevant and Appropriate Requirements**

6 Alternative 3 would comply with chemical-specific ARARs by removing soil that exceeds the  
7 PRGs and by removing or abandoning structures. Removal of all contaminants would achieve  
8 the chemical-specific ARARs discussed in Section 6.2.1.2 for protection of human health,  
9 ecological receptors, and groundwater protection. Other action-specific ARARs that could be  
10 pertinent to Alternative 3 are Washington State solid and dangerous waste regulations (for  
11 management of characterization and remediation wastes and performance standards for waste  
12 left in place), *Atomic Energy Act of 1954* regulations (for performance standards for radioactive  
13 waste sites), and Federal and state regulations related to air emissions. It is anticipated that these  
14 ARARs could be met. No location-specific ARARs have been identified for the waste sites  
15 addressed in this FS.

### 16 **6.2.3.3 Long-Term Effectiveness and Permanence**

#### 17 **Human Health**

18 With regard to human health, this alternative would be effective and permanent in the long term  
19 for all sites because excavation activities under Alternative 3 would remove contaminants to  
20 meet human health and ecological RAOs. EPA and Ecology cleanup authorities prescribe  
21 remedies that use permanent solutions to the maximum extent practicable and where cost  
22 effective. Removal of contaminants would be a permanent solution at the waste sites; however,  
23 much of the waste would remain on site at the ERDF.

24 The removal of buried materials from the Central Plateau, for disposal on the Hanford Site at the  
25 ERDF, transfers the long-term impact of buried waste from individual waste sites to one  
26 consolidated disposal facility. The ERDF is designed for long-term management of buried  
27 waste.

#### 28 **Protection of Groundwater**

29 The groundwater would be protected because modeling shows no impact to the groundwater in  
30 1,000 years. Therefore, Alternative 3 meets this criterion.

#### 31 **The Environment**

32 All contaminated soil in the 0 to 4.6 m (0 to 15 ft) bgs zone is removed in this alternative.  
33 Therefore, this alternative would be effective and permanent for all sites with respect to the  
34 environment. Excavation and transportation of waste and structures would disturb areas beyond  
35 the waste site boundaries during the implementation period. These areas would need to be  
36 revegetated after disturbance and would require activities to control intrusion by non-native,  
37 noxious plants. This should not adversely affect the alternative in the long term or permanently.

#### 1 6.2.3.4 Reduction of Toxicity, Mobility, or Volume through Treatment

2 Reduction of toxicity, mobility, or volume would occur in the form of natural attenuation.  
3 Natural attenuation is a process that results in a reduction of toxicity, mobility, or volume  
4 through the natural radioactive decay process. Radioactive decay is the only process currently  
5 available to eliminate nuclear particle emissions. Some of the contaminants identified during  
6 characterization would be influenced by the radioactive decay process; however, concentrations  
7 are high enough to require long time periods for radionuclides to decay to PRG levels (hundreds  
8 and, in a few cases, thousands of years).

9 In EPA/540/R-99/009, the EPA acknowledges that natural attenuation can be an appropriate  
10 treatment for contaminated soil. Because of uncertainties in the science of natural attenuation  
11 process, the EPA considers source control and performance monitoring to be fundamental  
12 components of the alternative.

13 In general, the removal, treatment, and disposal alternative would include treatment to reduce  
14 toxicity, mobility, or volume. However, with the availability of the ERDF, treatment is not  
15 anticipated. Radiological decay ultimately results in reduction of toxicity and volume.  
16 Movement of the waste to the ERDF would result in reduction of mobility. Both facilities would  
17 provide additional protection against remobilization of contaminants over their current location.

#### 18 6.2.3.5 Short-Term Effectiveness

##### 19 6.2.3.5.1 Remediation Worker Risk

20 The levels of contamination in the 216-A-29 Ditch and 216-S-10 Ditch do not pose a significant  
21 dose threat to workers. As such, shielded excavation equipment for these wastes should not be  
22 required. Worker protection may include dust suppression. These activities limit the worker  
23 risk, but also have a direct impact on schedule and cost. Nonetheless, excavation with dust  
24 suppression and health and safety controls has been proven effective in excavating soil sites.

##### 25 6.2.3.5.2 Impact to Environment During Remediation

26 Physical disruption of the waste sites during excavation, increased human activity, and noise, in  
27 addition to the generation of fugitive dust, affect local biological resources. However, the waste  
28 sites are located within historically disturbed industrial areas. Potential animal intrusion and  
29 biological uptake also are issues that will require control of open excavations and exposed  
30 contaminated soils at the end of each day. This control could be accomplished through  
31 placement of covers or fixatives. Areas of disturbed surface are documented in Appendix D and  
32 reported below. The additional disturbed area was estimated to average 20 percent of the  
33 site area.

- 34 • **216-A-29 Ditch** – The surface area disturbed during excavation of this site will be 1.3 ha  
35 (3.2 a). A conservative assumption is that an additional 0.2 ha (0.5 a) will be disturbed  
36 by activities such as staging construction activities and stockpiling clean soil, for a total  
37 disturbed area of 1.5 ha (3.7 a).

- 1 • **216-B-63 Trench** – No surface area will be disturbed at this representative site because  
2 this alternative is not applicable to this site.
- 3 • **216-S-10 Ditch** – The surface area disturbed during excavation of this site will be 0.49 ha  
4 (1.2 a). It is assumed that an additional 0.2 ha (0.5 a) will be disturbed by activities such  
5 as staging construction activities and stockpiling clean soil, for a total disturbed area of  
6 0.69 ha (1.7 a).
- 7 • **216-S-10 Pond and its Analogous Site** – No surface area will be disturbed at this  
8 representative site because this alternative is not applicable to this site.

9 Transportation activities on the Central Plateau would increase as a result of bringing  
10 construction equipment to the site, transporting contaminated soils to the ERDF, and bringing  
11 clean fill to the excavated sites. Because the ERDF is located onsite, minimal uncertainties are  
12 associated with the transport of waste. Air monitoring around the waste sites would be used to  
13 monitor potential air releases (e.g., waste or fill-material particulates) that could affect the public  
14 and the environment.

#### 15 **6.2.3.5.3 Time to Achieve the Remedial Action Objectives**

16 This alternative prevents the risk to human or ecological receptors by moving the source to an  
17 engineered disposal facility. Construction and waste excavation activities would be expected to  
18 require approximately a month to complete. Once completed, all long-term RAOs will be met  
19 (reducing risk to human health and ecological receptors, protection of groundwater, and  
20 reduction of exposure to industrial workers). The following estimates of time to complete  
21 remediation activities under Alternative 3 are from Appendix D. The time frame for the waste  
22 sites is based on assumptions used in Appendix D and an assumed 12-month design schedule.

- 23 • **216-A-29 Ditch** – Design and remediation of this site would take approximately  
24 18 months.
- 25 • **216-B-63 Trench** – The 216-B-63 Trench site currently meet risk requirements.
- 26 • **216-S-10 Ditch** – Remediation of this waste site would take approximately 14 months.
- 27 • **216-S-10 Pond and its Analogous Site** – The 216-S-10 Pond and its analogous site  
28 currently meet risk requirements.

#### 29 **6.2.3.6 Implementability**

30 Excavation is a proven and implementable technology used to remove wastes. Deeper  
31 excavations will require the use of more sophisticated digging equipment and techniques, the use  
32 of approach ramps and shoring, extensive removal of clean material to obtain adequately safe  
33 side slopes, etc. The aboveground structures (e.g., vent pipes and concrete structures) would be  
34 removed along with the waste site soil covers and contaminated soils. Every 0.3 m (1 ft) of  
35 excavation would require 0.46 m (1.5 ft) of side slope for a 1:1.5 vertical to horizontal ratio.

1 **216-A-29 Ditch** – To remove soils above the PRGs, standard excavation equipment is needed.  
2 Standard construction practices will be used. The excavation would be advanced to a depth of  
3 about 4 m (13 ft) bgs for approximately 295.7 m (970 ft). Every 0.3 m (1 ft) of excavation  
4 would require 0.46 m (1.5 ft) of side slope for a 1:1.5 vertical to horizontal ratio. This safety  
5 measure increases the amount of material excavated. To remove the COCs at this group,  
6 1,835.6 m<sup>3</sup> (2,399 yd<sup>3</sup>) of contaminated soil would have to be removed and sent to the ERDF.

7 **216-B-63 Trench** – Analysis of the 216-B-63 Trench site shows contaminants are within the  
8 95%UCL for direct human contact, groundwater protection, or ecological receptors. Therefore,  
9 this alternative does not apply.

10 **216-S-10 Ditch** – To remove soils above the PRGs, the excavation would be advanced to a depth  
11 of 4.6 m (15 ft) bgs for approximately 296.3 m (972 ft). Every 0.3 m (1 ft) of excavation would  
12 require 0.46 m (1.5 ft) of side slope for a 1:1.5 vertical to horizontal ratio. This safety measure  
13 increases the amount of material excavated. To remove the COCs at this site, 2,498.2 m<sup>3</sup>  
14 (3,265 yd<sup>3</sup>) of soil would have to be removed and sent to the ERDF.

15 **216-S-10 Pond and its Analogous Site** – Analysis of the 216-S-10 Pond and its analogous site  
16 shows no contaminants above PRGs. Therefore, this alternative does not apply.

17 Coordination with other agencies and local governments would be necessary after approval of  
18 the alternative. Excavation and disposal would require coordination with state agencies to assess  
19 matters relative to storm water control and the potential for radioactive air emissions.

#### 20 6.2.3.7 Cost

21 Costs include mobilizing personnel and equipment; monitoring, sampling, and analysis;  
22 excavating; disposing of the waste at the ERDF; backfilling with onsite resources and additional  
23 backfilling from a local stockpile; revegetating; and performing prime contractor oversight.

24 Costs are based on the use of standard excavation equipment (e.g., hydraulic excavators,  
25 front-end loaders, tractor-trailers). The costs are based on the assumption that a subcontractor  
26 would do the work, with oversight performed by prime contractor personnel. Details of the cost  
27 estimates are presented in Appendix D. Summarized costs for the sites are presented in  
28 Table 6-2.

#### 29 6.2.4 Detailed Analysis of Alternative 4 – Engineered 30 Barrier

31 The following sections present a detailed analysis of Alternative 4 against the evaluation criteria.  
32 Table 6-3 summarizes this analysis. This alternative analyzed two types of caps: an  
33 evapotranspiration and a modified *Resource Conservation and Recovery Act of 1976* (RCRA) C.  
34 The evapotranspiration barrier was analyzed at the 216-A-29 Ditch, the 216-B-63 Trench, and  
35 the 216-S-10 Ditch.

#### 1 **6.2.4.1 Overall Protection of Human Health and the Environment**

2 This alternative would be protective of human health and the environment because the capping  
3 system would break potential exposure pathways to receptors through placement of a surface  
4 barrier to limit infiltration and intrusion. The cap would be sufficiently robust to account for the  
5 types and levels of contamination in the waste sites. A capping system would provide additional  
6 distance between potential human and ecological receptors beyond the existing soil cover over  
7 the waste sites. Additionally, the capping system would include institutional controls such as  
8 monitoring, and provide a warning to potential intruders and notification of land-use restrictions.

9 Institutional controls, including maintenance of the cap, use restrictions, and monitoring, would  
10 be instituted at capped sites until the PRGs are achieved through natural attenuation.  
11 Institutional controls would provide additional protection against human intrusion. No  
12 groundwater monitoring is proposed because modeling shows no impact within 1,000 years. The  
13 cap would be designed to address potential lapse of the institutional controls after the 500-year  
14 period. Alternative 4 would be protective, because the barrier would be constructed to meet the  
15 ecological point of compliance.

#### 16 **6.2.4.2 Compliance with Applicable or Relevant and Appropriate Requirements**

17 Alternative 4 would comply with all ARARs for the waste sites by breaking the pathways for  
18 exposure and emplacing caps that meet the intent of the regulations. In addition to the cap,  
19 institutional controls such as additional land-use restrictions and groundwater monitoring are  
20 elements of this alternative.

#### 21 **6.2.4.3 Long-Term Effectiveness and Permanence**

##### 22 **Human Health**

23 The capping alternative would be protective of human health and the environment by breaking  
24 exposure pathways. Chemicals and radionuclides left in place at the waste sites would be  
25 physically separated from receptors by the thickness of the cap and by the additional thickness of  
26 the existing soil covers. Intrusion layers in the caps, along with institutional controls such as  
27 markers and use restrictions, would help protect against inadvertent intruders. Because  
28 contaminants at the waste sites have the potential to impact ecological receptors, caps would be  
29 designed to meet the point of compliance.

30 A significant amount of risk attenuates within the active institutional controls period for sites  
31 with significant risk contribution from short-lived radioisotopes. Therefore, failure of the caps in  
32 later years would be associated with lower risks than at present. Additionally, the 5-year reviews  
33 required for sites with contaminants above PRGs would serve to monitor the effectiveness and  
34 reliability of the caps; adjustments and maintenance activities could be instituted to help prevent  
35 failure, based on the 5-year review results.

36 The long-term effectiveness depends on the proper construction and maintenance of the barrier  
37 and associated institutional controls throughout the natural attenuation time frame to prevent  
38 exposure to potential receptors. Maintenance activities would include erosion repairs and  
39 possible vegetation maintenance. Subsidence is not considered a major factor in maintenance

1 activities for these waste sites. Failure of the cap is unlikely if maintenance and institutional  
2 control activities continue. The assumption used is that institutional controls past 500 years or so  
3 would not necessarily be maintained and could lapse. Caps would be designed and constructed  
4 to account for the necessary time frame to reach acceptable risk levels and to minimize  
5 maintenance requirements and impacts from a lapse in the institutional controls.

6 In addition, management controls (e.g., deed restrictions, fencing, signage) would be required  
7 components of this alternative. Once remediated, the barrier and surrounding disturbed area  
8 would be revegetated to further enhance evapotranspiration, limit erosion, and blend the site area  
9 into the surrounding landscape.

10 **216-A-29 Ditch** – The COCs for this site are Aroclor 1254, nitrate, and heavy metals. These  
11 COCs represent an unacceptable groundwater and ecological risk. With the exception of nitrate,  
12 the remaining COCs are relatively immobile. Based on previous modeling results, this cap  
13 inhibits the migration of nitrate and is protective of groundwater.

14 **216-B-63 Trench** – Analysis of the 216-B-63 Trench shows contaminants are within the  
15 95%UCL for direct human contact, groundwater protection, or ecological receptors. Therefore,  
16 this alternative does not apply

17 **216-S-10 Ditch** – The COCs for this site are Aroclor 1254, silver, and total chromium. These  
18 COCs represent an unacceptable ecological risk.

19 **216-S-10 Pond and its Analogous Site** – Analysis of the 216-S-10 Pond and its analogous site  
20 shows no contaminants above PRGs. Therefore, this alternative does not apply.

#### 21 **Protection of Groundwater**

22 The groundwater would be protected because modeling shows no impact to the groundwater in  
23 1,000 years. Therefore, Alternative 4 meets this criterion.

#### 24 **The Environment**

25 This alternative would provide protection to the environment by placing a barrier between the  
26 waste and the surface flora and fauna. As previously mentioned, two sites (216-A-29 Ditch and  
27 216-S-10 Ditch) fail the protection of the environment. At these sites, the caps would be  
28 designed to prevent the intrusion of deep-rooted flora and burrowing animals.

#### 29 **6.2.4.4 Reduction of Toxicity, Mobility, or Volume through Treatment**

30 Reduction of toxicity, mobility, or volume would occur in the form of natural attenuation. The  
31 capping alternative would rely on natural attenuation processes (most importantly radioactive  
32 decay) to reduce radioactivity to levels that would not present a risk to human health or the  
33 environment. Natural attenuation is a process that results in a reduction of toxicity, mobility, or  
34 volume through the natural radioactive decay process. Radioactive decay is the only process  
35 currently available to eliminate nuclear particle emissions. The contaminants identified during  
36 characterization would be influenced by the radioactive decay process.

1 In EPA/540/R-99/009, the EPA acknowledges that natural attenuation can be an appropriate  
 2 treatment for contaminated soil. Because of uncertainties in the science of natural attenuation  
 3 process, the EPA considers source control and performance monitoring to be fundamental  
 4 components of the alternative.

#### 5 **6.2.4.5 Short-Term Effectiveness**

##### 6 **6.2.4.5.1 Remediation Worker Risk**

7 Experienced workers using appropriate safety precautions would conduct these activities. Risks  
 8 to workers for this alternative were compared to the baseline no-action alternative. For  
 9 Alternative 4, only moderate short-term risks are expected. The capping alternative would not  
 10 require excavation of contaminated soils, so the risks to workers primarily would be associated  
 11 with general construction activities at the borrow sites and placement of the cap. If structures  
 12 were removed, workers could be exposed to potentially contaminated debris. Worker risk would  
 13 be controlled through adherence to site health and safety procedures. Air monitoring would  
 14 address potential air releases (e.g., barrier-material particulates) that could affect the public  
 15 during construction of the surface barriers.

##### 16 **6.2.4.5.2 Impact to Environment During Remediation**

17 Physical disruption of the waste sites during cap construction, increased human activity and  
 18 noise, and the generation of fugitive dust affect local biological resources. However, the waste  
 19 sites are located within historically disturbed industrial areas. As such, short-term impacts to  
 20 vegetation and animals at these sites would be low because these sites currently are poor wildlife  
 21 habitats.

##### 22 **6.2.4.5.3 Time to Meet the Remedial Action Objectives**

23 The following estimates of time to complete remediation activities under Alternative 4 are from  
 24 Appendix D and an assumed 12-month design schedule. Appendix D calculated time to  
 25 complete remediation for the sites only; time to complete remediation for the analogous sites was  
 26 calculated by using the cap surface areas ratio. This technique may overestimate time to  
 27 complete remediation for the entire waste group, because operations may proceed concurrently  
 28 rather than consecutively.

- 29 • **216-A-29 Ditch** – Design and construction of the cap for this waste site would take  
 30 approximately 18 months.
- 31 • **216-B-63 Trench** – The 216-B-63 Trench site currently meets risk requirements.
- 32 • **216-S-10 Ditch** – Design and construction of the cap for this waste site would take  
 33 approximately 19 months.
- 34 • **216-S-10 Pond and its Analogous Site** – The 216-S-10 Pond and its analogous site  
 35 currently meet risk requirements.

#### 1 6.2.4.6 Implementability

2 The capping alternative is considered implementable at all waste sites. Other types of barriers  
3 have not been used at the Hanford Site, but have been implemented at other sites and are  
4 straightforward to construct and maintain. The existing soil covers over the waste sites would be  
5 considered a part of the overall design to minimize the cost of materials and to minimize the  
6 impact to visual aesthetics.

7 Construction of the caps would follow standard procedures that have been thoroughly  
8 field-tested. The caps likely would require minor repair and possibly replacement during the  
9 restoration time frame. Monitoring the continued integrity of the caps would be accomplished  
10 through visual inspection and would be supplemented with groundwater sampling.  
11 Implementation of the capping alternative would require additional design data  
12 (e.g., ground-penetrating radar) and possibly confirmatory sampling, because existing data may  
13 not be adequate for determining the lateral extent of the caps.

14 Gravel, sand, and silt/loam soil used for the caps would be transported from borrow areas located  
15 on or near the Hanford Site. Anticipated volumes of these materials are identified in  
16 Appendix D. Area C currently is designated as a silt borrow location; the area has a large  
17 volume of fine-grained material. Other locations have not yet been determined. Soil most likely  
18 would come from near the waste sites or from Pit 30, which is located between the 200 East and  
19 200 West Areas. Borrow material may occur in environmentally sensitive areas; obtaining  
20 sufficient capping material, especially for a multilayered cap, would affect areas of ecological  
21 significance and is a consideration in evaluating the relative risk reduction gained by installing  
22 the cap. Materials such as rip-rap that may be used in the cap construction could be obtained on  
23 the Hanford Site or could be purchased from local dealers.

24 Capping materials hauled to the Central Plateau from borrow areas and gravel pits within the  
25 Hanford Site would increase heavy equipment use and transportation activities at the sites.  
26 However, radioactive or hazardous waste would not have to be hauled from the Site.

27 **216-A-29 Ditch** – An evapotranspiration cap would be installed at the 216-A-29 Ditch. The  
28 main design feature would be to store water during the wet periods and release it back to  
29 indigenous vegetation during prolonged periods of dry weather. The cap would be built to cover  
30 0.93 ha (2.3 a) on the southern portion of the ditch and 2.35 ha (5.8 a) on the northern section of  
31 the ditch.

32 **216-B-63 Trench** – Analysis of the 216-B-63 Trench shows contaminants are within the  
33 95%UCL for direct human contact, groundwater protection, or ecological receptors. Therefore,  
34 this alternative does not apply.

35 **216-S-10 Ditch** – An evapotranspiration cap would be installed at the 216-S-10 Ditch site. The  
36 main design feature would be to store water during the wet periods and release it back to  
37 indigenous vegetation during prolonged periods of dry weather. The cap would be built to cover  
38 0.93 ha (2.3 a) on the northern section of the ditch.

39 **216-S-10 Pond and its Analogous Site** – Analysis of the 216-S-10 Pond and its analogous site  
40 shows no contaminants above PRGs. Therefore, this alternative does not apply.

#### 1 6.2.4.7 Cost

2 Costs, shown in Table 6-3, include stabilization of the existing site; excavation or import,  
3 transportation, and placement of capping material; compaction of the cap; prime contractor  
4 oversight; and confirmatory sampling. Costs are based on the use of standard equipment  
5 (e.g., hydraulic excavators, front-end loaders, dozers) and assume that a subcontractor would do  
6 the work, with oversight performed by the prime contractor. The subcontractor personnel are  
7 assumed to be wearing Level D personal protective equipment (e.g., blues and no respirators)  
8 during construction. The present-worth costs assume a 3.2 percent discount rate (based on  
9 2003 Office of Management and Budget information) and assume operations and maintenance  
10 (active institutional controls period) for 150 years. The operations and maintenance costs  
11 include site inspection/surveillance, periodic radiation site surveys of surface soil, biotic control,  
12 maintenance of signs and markers, cover maintenance, and site reviews. Details of the cost  
13 estimates are presented in Appendix D. Summarized costs for the sites are presented in  
14 Table 6-3.

### 15 6.3 NEPA VALUES EVALUATION

16 The NEPA process is intended to help Federal agencies make decisions that are based on  
17 understanding environmental consequences, then to take actions that protect, restore, and  
18 enhance the environment. Secretarial policies (DOE 1994) and DOE O 451.1A require that  
19 CERCLA documents incorporate NEPA values, such as analysis of cumulative, offsite,  
20 ecological, and socioeconomic impacts to the extent practicable, in lieu of preparing separate  
21 NEPA documentation for CERCLA activities.

#### 22 6.3.1 Description of NEPA Values

23 Several of the CERCLA evaluation criteria involve consideration of environmental resources,  
24 but the emphasis frequently is directed at the potential effects of chemical contaminants on living  
25 organisms. The NEPA regulations (40 CFR 1502.16, "Environmental Impact Statement,"  
26 "Environmental Consequences") specify evaluation of the environmental consequences of  
27 proposed alternatives. These consequences include potential effects on transportation resources,  
28 air quality, and cultural and historical resources; noise; visual, and aesthetic effects;  
29 environmental justice; and the socioeconomic aspects of implementation. The NEPA process  
30 also involves consideration of several issues such as cumulative impacts (direct and indirect),  
31 mitigation of adversely impacted resources, and the irreversible and irretrievable commitment of  
32 resources.

33 The NEPA-related resources and values that the DOE has considered in this evaluation include  
34 the following:

- 35 • Transportation impacts. This value considers impacts of the proposed remedial action on  
36 local traffic (e.g., traffic at the Hanford Site) and traffic in the surrounding region.  
37 Transportation impacts are considered in part under the CERCLA criteria of short-term  
38 effectiveness or implementability.

- 1     • Air quality. This value considers potential air quality concerns associated with emissions  
2     generated during the proposed remedial actions.
- 3     • Natural, cultural, and historical resources. This value considers impacts of the proposed  
4     remedial actions on wildlife, wildlife habitat, archeological sites and artifacts, and  
5     historically significant properties on the Central Plateau.
- 6     • Noise, visual, and aesthetic effects. This value considers increases in noise levels or  
7     impaired visual or aesthetic values during or after the proposed remedial actions.
- 8     • Socioeconomic impacts. This value considers impacts pertaining to employment,  
9     income, other services (e.g., water and power utilities), and the effect of implementation  
10    of the proposed remedial actions on the availability of services and materials.
- 11    • Environmental justice. Environmental justice, as mandated by Executive Order 12898,  
12    *Federal Actions to Address Environmental Justice in Minority Populations and*  
13    *Low-Income Populations*, refers to fair treatment of humans of all races, cultures, and  
14    income levels with respect to laws, policies, and government actions. This value  
15    considers whether the proposed remedial actions would have inappropriately or  
16    disproportionately high and adverse human health or environmental effects on minority  
17    or low-income populations.
- 18    • Cumulative impacts (direct and indirect). This value considers whether the proposed  
19    remedial actions could have cumulative impacts on human health or the environment  
20    when considered together with other activities on the Central Plateau, at the Hanford Site,  
21    or in the region.
- 22    • Mitigation. If adverse impacts cannot be avoided, remedial action planning should  
23    minimize them to the extent practicable. This value identifies required mitigation  
24    activities.
- 25    • Irreversible and irretrievable commitment of resources. This value evaluates the use of  
26    nonrenewable resources for the proposed remedial actions and the effects that resource  
27    consumption would have on future generations. When a resource (e.g., energy, minerals,  
28    water, wetland) is used or destroyed and cannot be replaced within a reasonable amount  
29    of time, its use is considered irreversible.

## 30    6.3.2 Detailed Evaluation of NEPA

### 31    6.3.2.1 Transportation Impacts

32    Implementation of remedial action at the waste sites likely would have some short-term impacts  
33    on local traffic and traffic in the surrounding region. For Alternative 4, impacts would result  
34    from hauling cover material to the waste site areas. For Alternatives 3, impacts would result  
35    from hauling waste to the ERDF and hauling clean fill to the waste sites. For Alternatives 3  
36    and 4, impacts could be expected from increased traffic bringing supplies, equipment, and  
37    workers to the sites. To mitigate these potential impacts, a transportation safety analysis would

1 be performed before any transport activities began. The analysis would identify the need for  
2 specific precautions (e.g., road closures, preferred hauling times, staggered work shifts) to be  
3 taken as necessary. Increases in the workforce traffic related to waste treatment would be  
4 expected to be minor.

#### 5 **6.3.2.2 Air Quality**

6 No current air quality impacts are associated with Alternatives 1 and 2; however, potential  
7 impacts to air quality could be associated with plant or animal uptake of contaminants and wind  
8 dispersion. Potential near-term impacts to air quality associated with Alternatives 3 and 4 are  
9 expected to be minor and could be mitigated through appropriate engineering controls.

10 Potential air quality impacts primarily would be associated with fugitive dust during site  
11 preparation, structure demolition, excavation, placement of backfill or barriers, and revegetation  
12 activities. Dust suppression (using water and water treated with soil fixatives) would be used to  
13 control visible fugitive dust, so neither local nor regional air quality is expected to be affected.  
14 Routine emissions from vehicles would occur.

#### 15 **6.3.2.3 Natural, Cultural, and Historical Resources**

16 In all cases, remediation will be performed on sites that have been disturbed by industrial  
17 activities. Therefore, although cultural resources could be encountered with Alternatives 3 and 4  
18 during the excavation and construction of staging areas, the probability is low. To ensure that  
19 impacts to cultural resources are avoided and/or mitigated, a cultural resource mitigation plan  
20 would be established before remediation was begun. If cultural resources were encountered  
21 during excavation, *work would be stopped in the area and unanticipated and inadvertent*  
22 *discovery procedures would be followed pursuant to DOE/RL-98-10, Hanford Cultural*  
23 *Resource Management Plan.*

24 Some short-term adverse impacts to natural resources (e.g., local wildlife) could occur during the  
25 construction and implementation phases of remedial action. Ecological surveys would be  
26 performed to identify the species present and the special precautions that should be taken to  
27 minimize adverse impacts.

#### 28 **6.3.2.4 Noise, Visual, and Aesthetic Effects**

29 Alternatives 1 and 2 would have little to no impact on current noise, visual, or aesthetic site  
30 characteristics. Alternative 3 would increase noise levels and impair visual values, but the  
31 impacts would be short-term during remedial actions and ultimately would improve the  
32 aesthetics by removing any remaining site structures. Likewise, Alternative 4 would increase  
33 noise levels and impair visual values in the short term during construction of the cap. These  
34 alternatives also could have some long-term visual and aesthetic impacts, both positive and  
35 negative. Positive impacts would result from the removal of aboveground site structures.  
36 Negative impacts would be associated with the visibility and aesthetics of the caps over large  
37 distances if they are not contoured to blend in with the surrounding area. Aesthetically, given the  
38 past disturbance in the 200 Areas and on the Central Plateau, no impacts would be expected from  
39 the alternatives.

### 6.3.2.5 Socioeconomic Impacts

Alternative 1 would have no socioeconomic impacts. The other alternatives would have some positive socioeconomic impacts related to the employment opportunities that would occur during the life of the remedial action project. The labor force required to implement remedial action would be drawn from current Hanford Site contractors and the local labor force, so the socioeconomic impacts would be expected to be minimal.

### 6.3.2.6 Environmental Justice

Under Alternative 3, environmental justice issues would not be a concern because future surface uses on the Central Plateau would not be restricted beyond the Central Plateau-wide restrictions. Under Alternatives 1, 2, and 4, environmental justice impacts would be minimal because future-use restrictions would pertain to only a small percentage of the Central Plateau, and the Central Plateau still would be under active waste management industrial-land use.

### 6.3.2.7 Irreversible and Irretrievable Commitment of Resources

Alternatives 3 and 4 would require some irreversible or irretrievable commitment of natural resources. All of the alternatives with the exception of Alternative 1 would result in some land-use loss. Alternatives 3 and 4 would require additional soils, including materials that could come from ecologically sensitive areas, and some energy resources. They would require a commitment of resources in the form of land-use loss in the waste site areas until RAOs and goals were met through the natural attenuation process. The amount of land-use loss would vary among alternatives. Alternative 2 generally would require land-use loss of the entire site surface and subsurface for the necessary attenuation period to meet RAOs. Alternative 3 generally would allow land use from the ground surface to a depth of 4.6 m (15 ft) bgs or greater following the completion and regulatory acceptance of remedial activities. Alternative 4 would allow surface use of the sites, but would not allow any subsurface site use until the end of the necessary attenuation period to meet RAOs. This use would be limited based on potential impacts to surface-barrier integrity.

For Alternative 3, the ERDF would not need to be expanded to accommodate the additional waste. The waste volumes from the aboveground structure demolition in Alternatives 3 and 4 are relatively small and are not anticipated to specifically require additional ERDF capacity.

Alternatives 3 and 4 would require an irretrievable and irreversible commitment of resources in the form of geologic materials and petroleum products (e.g., diesel fuel, gasoline). With Alternative 3, excavated material would be replaced with a stockpile of clean soil cover removed from the site, as well as clean sand and gravel fill from onsite borrow pits (e.g., Area C borrow area). The sand and gravel for the surface-barrier alternative would come from nearby borrow pits, but the silt would need to come either from the Fitzner-Eberhardt Arid Lands Ecology Reserve or from off site. Rip-rap or other armoring materials needed to provide intrusion protection likely would come from off site.

### 6.3.2.8 Cumulative Impacts

The proposed RAOs could have impacts when considered together with impacts from past and foreseeable future actions at and near the Hanford Site. Authorized current and future activities include soil and groundwater remediation; waste management and treatment (e.g., tank farms, the Waste Treatment Plant); and surveillance, maintenance, decontamination, and decommissioning of facilities. Other Hanford Site activities that might be ongoing during remedial action at the Central Plateau waste sites include deactivation and decontamination of reprocessing facilities and operation of the Energy Northwest reactor. Activities near the Hanford Site include a privately owned radioactive and mixed waste treatment facility, a commercial fuel manufacturer, a commercial low-level radioactive waste disposal site, and a titanium reprocessing plant.

The proposed remediation alternatives would have minimal impacts on transportation; air quality; and natural, cultural, and historical resources. Noise, visual, and aesthetic effects and socioeconomic impacts also would be minimal. Therefore, cumulative impacts with respect to these values are expected to be insignificant. The most notable area for cumulative impacts is with respect to the irretrievable and irreversible commitment of resources. All of the proposed alternatives except Alternative 1 would require long-term land-use restrictions.

To varying levels, Alternatives 2, 3, and 4 would result in the loss of some land uses on the Central Plateau, but the cumulative impacts with respect to loss of land use are not expected to be significant. Alternative 3 also would require a commitment of land use as a result of the ERDF expansion on the Central Plateau. This would be in addition to numerous other Hanford Site projects that would commit land use on the Central Plateau.

Under Alternatives 3 and 4, cumulative impacts also would occur with respect to the irretrievable and irreversible commitment of geologic resources. The Central Plateau waste sites constitute only a portion of the total actions requiring material for barriers and backfill at the Hanford Site. The total quantity of geologic materials required for other Hanford Site actions currently is being identified (BHI-01551, *Alternative Fine-Grained Soil Borrow Source Study Final Report*) and may be subject to a separate NEPA evaluation. Currently, a borrow area (Area C) is being developed west of Route 240 to support capping activities planned at the U Plant area.

**DISCUSS NEPA DOCUMENT FOR THIS.**

### 6.3.2.9 Mitigation

Alternative 1 would not include mitigation. Mitigation measures under Alternative 2 would include surveillance, physical controls, and potential interim remedies. Mitigation measures taken under Alternatives 3 and 4 would include dust suppression, stockpiling clean topsoil for reuse, minimizing the size of construction areas, and planning activities to avoid nesting and breeding cycles of birds and mammals.

### 6.3.2.10 Summary of NEPA Evaluation

Remedial actions at the Central Plateau waste sites would result in some impacts to public health and the environment. However, the overall environmental impacts under normal operating conditions would not be very large, nor would they vary greatly among the remedial alternatives.

1 6.4 REFERENCES

2 40 CFR 141, "National Primary Drinking Water Regulations," Title 40, *Code of Federal*  
3 *Regulations*, Part 141, as amended.

4 40 CFR 141, "National Primary Drinking Water Regulations," Section 141.66, "Maximum  
5 Contaminant Levels for Radionuclides," Title 40, *Code of Federal Regulations*, Part 141,  
6 as amended.

7 40 CFR 1502.16, "Environmental Impact Statement," "Environmental Consequences," Title 40,  
8 *Code of Federal Regulations*, Part 1502.16, as amended.

9 *Atomic Energy Act of 1954*, 42 USC 2011, et seq.

10 BHI-01551, 2002, *Alternative Fine-Grained Soil Borrow Source Study Final Report*, Rev. 0,  
11 Bechtel Hanford, Inc., Richland, Washington.

12 *Comprehensive Environmental Response, Compensation, and Liability Act of 1980*,  
13 42 USC 9601, et seq.

14 DOE O 451.1A, *National Environmental Policy Act Compliance Program*, U.S. Department of  
15 Energy, Washington, D.C.

16 DOE, 1994, *Secretarial Policy on the National Environmental Policy Act* (memorandum from  
17 H. R. O'Leary, Secretary of Energy, for Secretarial Officers and Heads of Field  
18 Elements), U.S. Department of Energy, Washington, D.C., June 13.

19 DOE/RL-98-10, 2003, *Hanford Cultural Resource Management Plan*, U.S. Department of  
20 Energy, Richland Operations Office, Richland, Washington.

21 DOE/RL-2004-17, 2004, *Remedial Investigation Report for the 200-CS-1 Chemical Sewer*  
22 *Group Operable Units*, Rev. 0, U.S. Department of Energy, Richland Operations Office,  
23 Richland, Washington.

24 DOE-STD-1153-2002, 2002, *A Graded Approach for Evaluating Radiation Doses to Aquatic*  
25 *and Terrestrial Biota*, DOE Technical Standard, U.S. Department of Energy,  
26 Washington, D.C., available on the Internet at  
27 <http://www.eh.doe.gov/techstds/standard/std1153/1153.htm> .


28 EPA/540/2-88/002, 1988, *Technological Approaches to Cleanup of Radiologically*  
29 *Contaminated Superfund Sites*, U.S. Environmental Protection Agency,  
30 Washington, D.C.

31 EPA/540/G-89/004, 1988, *Guidance for Conducting Remedial Investigations and Feasibility*  
32 *Studies under CERCLA, (Interim Final)*, OSWER 9355.3-01, Office of Solid Waste and  
33 Emergency Response, U.S. Environmental Protection Agency, Washington, D.C.

- 1 EPA/540/R-99/009, 1999, *Use of Monitored Natural Attenuation at Superfund RCRA Corrective*
- 2 *Action and Underground Storage Tank Sites November 1997*, OSWER 9200.4-17P,
- 3 Office of Emergency and Remedial Response, U.S. Environmental Protection Agency,
- 4 Washington, D.C.
  
- 5 Executive Order 12898, 1994, *Federal Actions to Address Environmental Justice in Minority*
- 6 *Populations and Low-Income Populations*, William J. Clinton, February 11.
  
- 7 *National Environmental Policy Act of 1969*, 42 USC 4321, et seq.
  
- 8 *Resource Conservation and Recovery Act of 1976*, 42 USC 6901, et seq.
  
- 9 WAC-173-340-900, "Tables," *Washington Administrative Code*, as amended, Washington State
- 10 Department of Ecology, Olympia, Washington.

1  
2

Figure 6-1. Logic Diagram for Selecting Applicable Alternatives.



**LEGEND**

- ECO = Ecological.
- GW = Groundwater.
- HH = Human Health.
- MRL = Millirem.
- PRG = Preliminary Remediation Goal.
- < = Less Than.

**NOTES:**

- If human health PRGs are not met, then the ecological PRGs have little influence on the alternatives.
- If human health PRGs are met, then the ecological PRGs have a significant influence on the alternatives.

3

1

Table 6-1. Detailed Analysis Summary for Alternative 2 – Maintain Existing Soil Cover, Monitored Natural Attenuation, and Institutional Controls. (2 Pages)

Waste Site	Threshold Criteria		Balancing Criteria				
	Overall Protection of Human Health and the Environment	Compliance with ARARs	Long-Term Effectiveness and Permanence	Reduction of Toxicity, Mobility, or Volume Through Treatment	Short-Term Effectiveness	Implementability	Cost in Thousands
<b>Representative Sites</b>							
216-A-29 Ditch	Not protective, because contaminants remain above PRGs after 500 years.	Does not comply.	Groundwater is not protected. Potential risks to burrowing animals and deep-rooted plants exist.	Reduction through natural attenuation of radionuclides and Aroclor 1254.	Human receptors would be exposed to minimal short-term risks. The short-term impacts to the environment are expected to be low.	Readily implementable.	\$868,340
216-B-63 Trench	Protective. Existing contamination levels are within the 95%UCL for direct human contact, groundwater protection, or ecological receptors.	Complies.	Existing contamination levels are within the 95%UCL for direct human contact, groundwater protection, or ecological receptors.	There are no risk-based issues at this site.	Existing contamination levels are within the 95%UCL for direct human contact, groundwater protection, or ecological receptors.	Readily implementable.	N/A
216-S-10 Ditch	Not protective, because contaminants remain above PRGs.	Does not comply.	Groundwater is protected. Potential risks to burrowing animals and deep-rooted plants exist.	Reduction through natural attenuation of radionuclides and Aroclor 1254.	Human receptors would be exposed to minimal short-term risks. The short-term impacts to the environment are expected to be low.	Readily implementable.	\$876,538
216-S-10 Pond	Protective, because contaminants are below PRGs.	Complies.	Existing contamination levels are below PRGs.	Existing contamination levels are below PRGs.	Existing contamination levels are below PRGs.	Readily implementable.	N/A

Table 6-1. Detailed Analysis Summary for Alternative 2 – Maintain Existing Soil Cover, Monitored Natural Attenuation, and Institutional Controls. (2 Pages)

Waste Site	Threshold Criteria		Balancing Criteria				
	Overall Protection of Human Health and the Environment	Compliance with ARARs	Long-Term Effectiveness and Permanence	Reduction of Toxicity, Mobility, or Volume Through Treatment	Short-Term Effectiveness	Implementability	Cost in Thousands
<b>Waste Site Analogous to 216-S-10 Pond</b>							
216-S-11 Pond	Protective, because contaminants are below PRGs.	Complies.	Existing contamination levels are below PRGs.	Existing contamination levels are below PRGs.	Existing contamination levels are below PRGs.	Readily implementable.	N/A

ARAR = applicable or relevant and appropriate requirement.

N/A = not applicable.

PRG = preliminary remediation goal.

1

Table 6-2. Detailed Analysis Summary for Alternative 3 – Removal, Treatment, and Disposal. (2 Pages)

Waste Site	Threshold Criteria		Balancing Criteria				
	Overall Protection of Human Health and the Environment	Compliance with ARARs	Long-Term Effectiveness and Permanence	Reduction of Toxicity, Mobility, or Volume Through Treatment	Short-Term Effectiveness	Implementability	Cost in Thousands
<b>Representative Sites</b>							
216-A-29 Ditch	Protective. Excavation would remove 2.7 m (9) ft of contaminants. Would eliminate direct contact with human and ecological receptors.	Complies.	Effective and permanent in the long term because excavation removes contaminants to meet human health RAOs, and the environment.	Contaminants are moved to a less mobile environment. Reduction through natural attenuation of radionuclides and decomposition of chemical.	Medium short-term risks to workers; ecological risks not expected because contaminants are removed.	Readily implementable.	\$2,759,317
216-B-63 Trench	Analysis of the 216-B-63 Trench shows contaminants are within the 95%UCL for direct human contact, groundwater protection, or ecological receptors.	Complies.	Analysis of the 216-B-63 Trench shows contaminants are within the 95%UCL for direct human contact, groundwater protection, or ecological receptors.	Existing contamination levels are within the 95%UCL for direct human contact, groundwater protection, or ecological receptors	Existing contamination levels are within the 95%UCL for direct human contact, groundwater protection, or ecological receptors.	Readily implementable.	N/A
216-S-10 Ditch	Protective. Excavation would remove 0.5 to 1.2 m (1.5 to 4 ft) of contaminants. Would eliminate direct contact with human and ecological receptors.	Complies.	Effective and permanent in the long term because excavation removes contaminants to meet human health RAOs, and the environment.	Contaminants are moved to a less mobile environment. Reduction through natural attenuation of chemical.	Medium short-term risks to workers; ecological risks not expected because contaminants are removed.	Readily implementable.	\$1,679,178
216-S-10 Pond	Protective, because contaminants are below PRGs.	Complies.	Effective, existing contamination levels are below PRGs.	Existing contamination levels are below PRGs.	Effective; existing contamination levels are below PRGs.	Readily implementable.	N/A

Table 6-2. Detailed Analysis Summary for Alternative 3 – Removal, Treatment, and Disposal. (2 Pages)

Waste Site	Threshold Criteria		Balancing Criteria				
	Overall Protection of Human Health and the Environment	Compliance with ARARs	Long-Term Effectiveness and Permanence	Reduction of Toxicity, Mobility, or Volume Through Treatment	Short-Term Effectiveness	Implementability	Cost in Thousands
<b>Waste Site Analogous to 216-S-10 Pond</b>							
216-S-11 Pond	Protective, because contaminants are below PRGs.	Complies.	Effective; existing contamination levels are below PRGs.	Existing contamination levels are below PRGs.	Effective; existing contamination levels are below PRGs.	Readily implementable.	N/A

ARAR = applicable or relevant and appropriate requirement.

N/A = not applicable.

PRG = preliminary remediation goal.

RAO = remedial action objective.

Table 6-3. Detailed Analysis Summary for Alternative 4 – Capping. (2 Pages)

Waste Site	Threshold Criteria		Balancing Criteria				
	Overall Protection of Human Health and the Environment	Compliance with ARARs	Long-Term Effectiveness and Permanence	Reduction of Toxicity, Mobility, or Volume Through Treatment	Short-Term Effectiveness	Implementability	Cost In Thousands
<b>Representative Sites</b>							
216-A-29 Ditch	Protective. This alternative would break potential exposure pathways to receptors through placement of a surface barrier to limit infiltration and intrusion.	Complies with ARARs because the barrier is in place.	Would be effective. Cap is protective of groundwater.	Reduction through natural attenuation of radionuclides and decomposition of chemical.	Limited short-term risks to workers. No ecological risks expected; site will be capped and clean soil placed as the final layer.	Readily implementable.	\$9,488,213
216-B-63 Trench	Protective. Analysis of the 216-B-63 Trench shows contaminants are within the 95%UCL for direct human contact, groundwater protection, or ecological receptors.	Complies with ARARs.	Analysis of the 216-B-63 Trench shows contaminants are within the 95%UCL for direct human contact, groundwater protection, or ecological receptors.	Existing contamination levels are within the 95%UCL for direct human contact, groundwater protection, or ecological receptors.	Existing contamination levels are within the 95%UCL for direct human contact, groundwater protection, or ecological receptors.	Readily implementable.	N/A
216-S-10 Ditch	This alternative would break potential exposure pathways to receptors through placement of a surface barrier to limit infiltration and intrusion.	Complies with ARARs because the barrier is in place.	Would be effective barrier to reach ecological PRGs.	Reduction through natural attenuation of chemical.	Limited short-term risks to workers. No ecological risks expected; site will be capped and clean soil placed as the final layer.	Readily implementable.	\$3,573,574
216-S-10 Pond	Protective because contaminants are below PRGs.	Complies.	Effective; existing contamination levels are below PRGs.	Existing contamination levels are below PRGs.	Effective; existing contamination levels are below PRGs.	Readily implementable.	N/A

Table 6-3. Detailed Analysis Summary for Alternative 4 – Capping. (2 Pages)

Waste Site	Threshold Criteria		Balancing Criteria				
	Overall Protection of Human Health and the Environment	Compliance with ARARs	Long-Term Effectiveness and Permanence	Reduction of Toxicity, Mobility, or Volume Through Treatment	Short-Term Effectiveness	Implementability	Cost In Thousands
<b>Waste Site Analogous to 216-S-10 Pond</b>							
216-S-11 Pond	Protective, because contaminants are below PRGs.	Complies.	Effective; existing contamination levels are below PRGs.	Existing contamination levels are below PRGs.	Effective; existing contamination levels are below PRGs.	Readily implementable.	N/A

ARAR = applicable or relevant and appropriate requirement.

N/A = not applicable.

PRG = preliminary remediation goal.

**This page intentionally left blank.**

1

**CHAPTER 7.0 TERMS**

2	95%UCL	95th upper confidence level
3	ARAR	applicable or relevant and appropriate requirement
4	CERCLA	<i>Comprehensive Environmental Response, Compensation, and Liability Act of 1980</i>
5		
6	ERDF	Environmental Restoration Disposal Facility
7	PRG	preliminary remediation goal

1

**This page intentionally left blank.**

2

## 7.0 COMPARATIVE ANALYSIS OF ALTERNATIVES

This chapter presents the comparative analysis of the four remedial alternatives for the 200-CS-1 Operable Unit waste sites to identify their relative advantages and disadvantages. This comparison is based on the seven *Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (CERCLA)* evaluation criteria discussed in Chapter 6.0. The results of this analysis provide a basis for selecting a remedial alternative for each representative waste site and associated analogous waste site. These remedial alternatives are as follows:

- Alternative 1 – No Action
- Alternative 2 – Maintain Existing Soil Cover, Monitored Natural Attenuation, and Institutional Controls
- Alternative 3 – Removal, Treatment, and Disposal
- Alternative 4 – Capping.

### 7.1 OVERALL PROTECTION OF HUMAN HEALTH AND THE ENVIRONMENT

Alternative 1 would provide overall protection of human health and the environment at the 216-B-63 Trench because contaminants are within the 95th upper confidence level (95%UCL) for direct human contact, groundwater protection, or ecological receptors. Alternative 1 is also applicable at the 216-S-10 Pond and its analogous site because contaminants are below the preliminary remediation goals (PRG). Alternative 1 would fail to provide overall protection of human health and the environment at the 216-A-29 Ditch and 216-S-10 Ditch because contaminants at concentrations above the PRGs would remain on site with no actions to restrict intrusion.

Alternative 2 would provide overall protection of human health and the environment for the 216-B-63 Trench because contaminants are within the 95%UCL for direct human contact, groundwater protection, or ecological receptors and at the 216-S-10 Pond and its analogous site. These sites have no contaminants of concern (COC) above PRGs. As such, this alternative is not applicable to these sites. Alternative 2 would not provide overall protection of human health at the 216-A-29 Ditch and the 216-S-10 Ditch if no credit is taken for existing soil covers. With the existing soil cover, this alternative is protective of human health. The 216-A-29 Ditch and 216-S-10 Ditch exceed ecological exposure. As such, these sites fail to protect the environment under this alternative.

Alternative 3 is considered protective of long-term human health and the environment, because contaminants are removed below PRGs. This alternative is applicable at the 216-A-29 Ditch and 216-S-10 Ditch. COCs are located within the shallow zone (0 to 4.6 m [0 to 15 ft]) and can be removed with conventional construction equipment. The COCs represent a minor worker risk. Furthermore, the COCs meet ERDF waste acceptance criteria and there is available disposal

1 space. There are no risks at the 216-B-63-Trench, 216-S-10 Pond, and its analogous site.  
2 Therefore, this alternative is not applicable for these sites.

3 Alternative 4 is considered protective of human health and the environment, because it would  
4 break potential exposure pathways to receptors through placement of a surface barrier and  
5 implementation of institutional controls. The barrier also would provide ecological protection by  
6 providing at least 4.6 m (15 ft) of clean overburden above the waste. Barriers would be designed  
7 commensurate with site contaminant conditions, and institutional controls would be used at  
8 capped sites to augment protectiveness. The sites would incorporate monitoring and inspections  
9 of barrier performance.

10 **7.2 COMPLIANCE WITH APPLICABLE OR**  
11 **RELEVANT AND APPROPRIATE**  
12 **REQUIREMENTS**

13 Alternative 1 complies with applicable or relevant and appropriate requirements (ARAR) for the  
14 216-B-63 Trench because contaminants are within the 95%UCL for direct human contact,  
15 groundwater protection, or ecological receptors. The 216-S-10 Pond and its analogous site meet  
16 the criteria for the no-action alternative, because contaminant levels are below PRGs. For the  
17 216-A-29 Ditch and 216-S-10 Ditch, Alternative 1 does not comply with ARARs.

18 Alternative 2 generally does not comply with ARARs at the 216-A-29 Ditch and 216-S-10 Ditch  
19 because it is not protective of the environment. However, for reasons stated above, the  
20 216-B-63 Trench does comply with ARARs. This alternative does comply with all ARARs for  
21 the 216-S-10 Pond and its analogous site because the contamination levels are below PRGs.

22 Alternative 3 complies with ARARs because it removes contamination to the PRGs. Worker  
23 protection ARARs will not be exceeded.

24 Alternative 4 complies with ARARs by breaking exposure pathways.

25 **7.3 LONG-TERM EFFECTIVENESS AND**  
26 **PERMANENCE**

27 Alternative 1 is effective in the long term for the 216-B-63 Trench site because contaminants are  
28 within the 95%UCL for direct human contact, groundwater protection, or ecological receptors.  
29 In addition, Alternative 1 is effective in the long term for the 216-S-10 Pond and its analogous  
30 site because they have no contamination above PRGs. Alternative 1 is not effective in the long  
31 term for the 216-A-29 Ditch and 216-S-10 Ditch waste sites because contamination would be left  
32 in place above PRGs.

33 Alternative 2 would be an effective and permanent remedial action in the long term for the  
34 216-B-63 Trench, 216-S-10 Pond, and the analogous site. However, this alternative is not  
35 effective for the 216-A-29 Ditch and the 216-S-10 Ditch. Mobile contaminants at the  
36 216-A-29 Ditch would adversely affect the groundwater. Also, heavy metal contaminants and

1 polychlorinated biphenyls at the 216-A-29 and 216-S-10 Ditches would adversely affect the  
2 environment.

3 Alternative 3 would provide a high degree of effectiveness in the long term. With Alternative 3,  
4 contaminant concentrations above the PRGs would be removed. The removed contaminated  
5 material would be disposed of at the Environmental Restoration Disposal Facility (ERDF) or at a  
6 commercially permitted facility.

7 Alternative 4 also provides a high degree of overall effectiveness in the long term for a majority  
8 of the sites, because it addresses the potential pathways, groundwater, and biota. Several studies  
9 at the Hanford Site have shown that contaminant transport through the vadose zone is linked to  
10 the rate that water moves through the vadose zone or the recharge rate. PNNL-14744, *Recharge*  
11 *Data Package for the 2005 Integrated Disposal Facility Performance Assessment*, indicates  
12 recharge rates can vary from nearly zero in silt loam soil covered in sagebrush to more than  
13 100 mm/yr (3.94 in/yr) in gravel-covered soil without vegetation. As shown in Appendix A,  
14 some of the sites currently are gravel covered to sparsely covered with vegetation. As such, the  
15 current recharge rate at these sites is expected to be closer to 100 mm/yr (3.94 in/yr).

16 Alternative 4 would be protective by breaking the exposure pathways and reducing the  
17 infiltration through the vadose zone. Long-term effectiveness depends on the design and  
18 maintenance of the cap and associated monitoring (e.g., cap performance, natural attenuation).  
19 For those waste sites where deeper contamination is identified as exceeding groundwater  
20 protection criteria, Alternative 4 would require additional monitoring (e.g., groundwater  
21 protection); therefore, long-term restrictions would apply.

#### 22 7.4 REDUCTION IN TOXICITY, MOBILITY, OR 23 VOLUME THROUGH TREATMENT

24 The alternatives do not include treatment and, therefore, do not reduce toxicity, mobility, or  
25 volume of the contaminants through treatment. All the alternatives incorporate natural  
26 attenuation in the form of radiological decay and or chemical decomposition, which ultimately  
27 results in reduced toxicity and volume.

#### 28 7.5 SHORT-TERM EFFECTIVENESS

29 Alternative 1 would be effective in the short term at the 216-B-63 Trench and 216-S-10 Pond  
30 and its analogous site because it does not involve any remedial actions. However, at the  
31 216-A-29 Ditch and 216-S-10 Ditch sites, contaminants are in the biological active zone (active  
32 rooting zone and burrowing animal zone), and biota could be exposed to unacceptable  
33 concentrations.

34 Alternatives 2 and 4 would be more effective in the short term than Alternative 3 predominantly  
35 because potential exposure to contaminated soil and fugitive dust would be greater in the short  
36 term. Alternative 3 would generate contaminated soil and debris, which would create a potential  
37 for short-term worker impacts during excavation and transportation of the excavated materials.

1 Worker risks for Alternative 3 are considered minimal due to the low concentrations of COCs at  
2 the 216-A-29 and 216-S-10 Ditch sites. There are no risk-related issues at the other sites.

### 3 7.6 IMPLEMENTABILITY

4 Alternative 1 would be easily implemented because no action is performed.

5 Alternative 2 is currently in use for all of the waste sites. The waste sites are in a surveillance  
6 and monitoring program and are posted with signs and/or the area is fenced. Access to the waste  
7 sites also is controlled through Hanford Site access requirements, an excavation permit program,  
8 and a radiation work permit program. The addition of monitoring wells or boreholes is easily  
9 implementable.

10 Alternative 3 is implementable for sites with COCs above the PRGs. However, this alternative is  
11 judged slightly more difficult than Alternative 4 because of the safety requirements associated  
12 with the excavation, transportation, and disposal of contaminated soil and debris. Alternative 3  
13 would involve excavation and segregation of solid waste, if found. Disposal of all the  
14 contaminated soils at the ERDF would require approximately  $4,333.8 \text{ m}^3$  ( $5,664 \text{ yd}^3$ ) of space,  
15 which is available at the ERDF.

16 Alternative 4 is implementable. A barrier has been implemented at the Hanford Site; other types  
17 of barriers have been approved and implemented at other western arid sites and are  
18 straightforward to construct and maintain. Facilities and infrastructure near waste sites could  
19 influence the implementability of a surface barrier option at a particular site.

### 20 7.7 COST

21 The cost to implement the alternatives is presented in Chapter 6.0, Chapter 8.0, and Appendix D.  
22 The following comparisons are generic in nature only to compare the relative costs of the  
23 alternatives. Specific cost comparisons are in Chapter 6.0; Chapter 8.0, Tables 8-1 through 8-4;  
24 and Appendix D.

25 Alternative 1 has no cost associated with it and has no additional benefit to human health and the  
26 environment over current risks. Alternative 2 generally does not protect human health and the  
27 environment; however, Alternative 2 would have the lowest present-worth cost because it is  
28 minimally invasive and does not include labor-intensive activities. Alternative 3 is cost effective  
29 for this operable unit because the depth of excavation is relatively shallow (less than 3 m [10 ft]  
30 below ground surface). Alternative 4 is more expensive than Alternative 3 because of the small  
31 size of the barriers and additional fill material needed to contour the sites in comparison to the  
32 shallow nature of the contamination.

DOE/RL-2005-63 DECISIONAL DRAFT

1 7.8 REFERENCES

2 *Comprehensive Environmental Response, Compensation, and Liability Act of 1980,*  
3 42 USC 9601, et seq.

4 PNNL-14744, 2004, *Recharge Data Package for the 2005 Integrated Disposal Facility*  
5 *Performance Assessment*, Pacific Northwest National Laboratory, Richland, Washington.

1

This page intentionally left blank.

2

CHAPTER 8.0 TERMS

1

2	ARAR	applicable or relevant and appropriate requirement
3	FS	feasibility study
4	IC	institutional control
5	MESC	maintain existing soil cover
6	MNA	monitored natural attenuation
7	OU	operable unit
8	PRG	preliminary remediation goal
9	RAO	remedial action objective
10	ROD	record of decision
11	RTD	removal, treatment, and disposal
12	TMV	toxicity, mobility, or volume through treatment
13	TSD	treatment, storage, and/or disposal (unit)
14	WAC	<i>Washington Administrative Code</i>

1

**This page intentionally left blank.**

2

## 8.0 CONCLUSIONS AND PATH FORWARD

This chapter summarizes the results of the feasibility study (FS) and presents the path forward for the 200-CS-1 Operable Unit (OU) waste sites. This chapter also identifies the preferred alternatives for remediation of the waste sites.

### 8.1 FEASIBILITY STUDY SUMMARY

Four remedial alternatives were evaluated for the 200-CS-1 OU waste sites. These alternatives are as follows:

- Alternative 1 – No Action
- Alternative 2 – Maintain Existing Soil Cover, Monitored Natural Attenuation, and Institutional Controls
- Alternative 3 – Removal, Treatment, and Disposal
- Alternative 4 – Capping.

The alternatives were evaluated against the *Comprehensive Environmental Response, Compensation, and Liability Act of 1980* (CERCLA) criteria, and then they were evaluated against each other using the CERCLA criteria. Tables 8-1 through 8-5 show the preferred remediation alternative for each representative site and associated analogous waste sites in the 200-CS-1 OU. These tables also provide summary justification for the preferred alternative selection based on the detailed and comparative analyses presented in Chapters 6.0 and 7.0 of this FS.

#### 8.1.1 216-A-29 Ditch Site

The 216-A-29 Ditch exceeds ecological preliminary remediation goals (PRG) in the upper part of the ditch. The preferred alternative for this site is Alternative 3 – Removal, Treatment, and Disposal, because this alternative is protective of human health, the environment, and workers; is easily implementable; and is cost-effective. Table 8-1 provides a summary of the analysis of alternatives supporting the selection of the preferred alternative for this waste site.

#### 8.1.2 216-B-63 Trench Site

Based on existing data at the 216-B-63 Trench, contaminants are within the 95th upper confidence level for direct human contact, groundwater protection, or ecological receptors. As such, the preferred alternative is the no-action alternative. Table 8-2 provides a summary of the analysis of alternatives supporting the selection of the preferred alternative for this waste site.

### 1 8.1.3 216-S-10 Ditch Site

2 The 216-S-10 Ditch exceeds the ecological PRGs in a portion of the ditch. Groundwater  
3 protection is not required. The preferred alternative for this site is Alternative 3 – Removal,  
4 Treatment, and Disposal, because this alternative is protective of the environment and workers, is  
5 easily implementable, and is cost-effective. Table 8-3 provides a summary of the analysis of  
6 alternatives supporting the selection of the preferred alternative for this waste site.

### 7 8.1.4 216-S-10 Pond and its Analogous Waste Site

8 Based on existing data at the 216-S-10 Pond, no PRGs are exceeded at this waste site or its  
9 analogous site (216-S-11 Pond). As such, the preferred alternative is the no-action alternative  
10 with confirmatory sampling. Confirmatory sampling would be performed at the 216-S-11 Pond.  
11 A data quality objectives document would guide sample selection and location. Tables 8-4 and  
12 8-5 provide a summary of the analysis of alternatives supporting the selection of the preferred  
13 alternatives for this group of waste sites.

## 14 8.2 PATH FORWARD

15 A proposed plan is being prepared to document the preferred alternatives for the 200-CS-1 OU  
16 (DOE/RL-2005-64, *Proposed Plan for the 200-CS-1 Chemical Sewer Group Operable Units*).  
17 The proposed plan details the closure options, and it documents which waste sites will be  
18 remediated in accordance with the record of decision (ROD), developed following issuance of  
19 the proposed plan.

20 Four waste sites in the 200-CS-1 OU were evaluated in this FS, based on data reported in  
21 DOE/RL-2004-17, *Remedial Investigation Report for the 200-CS-1 Operable Unit*.  
22 DOE/RL-98-28, *200 Areas Remedial Investigation/Feasibility Study Implementation Plan –*  
23 *Environmental Restoration Program*, Section 2.5, defines this strategy as a means to streamline  
24 remedial investigations and focus the CERCLA process to obtain a decision. As identified in  
25 DOE/RL-98-28 Section , additional sampling phases conducted post-ROD are meant to augment  
26 the remedial investigation data, confirm the alternative selection, support the design, and provide  
27 information for final site closeout, as well as clean closure of the treatment, storage, and/or  
28 disposal (TSD) unit soils as described in Appendix E. Confirmatory sampling is conducted to  
29 confirm that the representative site model used to evaluate the analogous site is appropriate to the  
30 site conditions and to confirm that the appropriate remedial alternative was selected. Design  
31 sampling is conducted to obtain data necessary to design the remedial alternative and refine the  
32 cost estimated for the FS. Verification sampling is conducted to verify that the remedial goals  
33 have been met by the implementation of the remedial alternative.

34 Table 8-6 presents the confirmatory, design, and verification sampling phases for each site. This  
35 table illustrates the assumed data needs for each sampling phase for the representative sites and  
36 for analogous sites that are similar (or equal) to the representative sites (see Chapter 2.0 for  
37 additional details). This table builds off the decision logic presented in Figure 2-12 and  
38 Table 2-2 and provides a basis for initiating the data quality objectives process for the  
39 confirmatory sampling and design sampling phases.

1 Post-ROD sampling will be determined through data quality objectives identification and a  
2 sampling and analysis plan that will be developed to direct the sampling needed at the analogous  
3 sites. This sampling will be used to confirm that the correct alternative has been selected and to  
4 provide design data through a "plug-in" approach, as defined in the following sections.

5 Sites slated for no action will need verification sampling, depending on the amount, type, and  
6 quality of data available to support the no-action decision. CERCLA operations and  
7 maintenance sampling could include the monitoring of natural attenuation and performance  
8 monitoring of the cap.

### 9 8.2.1 Plug-in Approach of the 200-CS-1 Operable Unit 10 Waste Sites

11 The plug-in approach is a process that helps make remedial action decisions for additional waste  
12 sites using existing CERCLA evaluations. In the future, the plug-in approach is proposed for  
13 any similar waste sites already defined within the 200-CS-1 OU and for newly discovered waste  
14 sites that have a similar conceptual site model to waste sites already addressed in this FS. The  
15 plug-in approach will be used on the analogous sites considered in this FS after additional data  
16 are collected in the confirmatory and design sampling phases.

17 The plug-in approach benefits the goal of remediating waste sites within the OUs in conjunction  
18 with the analogous site approach. The traditional CERCLA approach for remedy selection  
19 would require the development of multiple proposed plans and RODs that, for similar sites,  
20 would be nearly identical to the FSs, proposed plans, and RODs already developed and proven to  
21 be successful. The plug-in approach allows remedial actions to begin much more quickly at a  
22 waste site, without the need for redundant remedy selection processes.

23 The plug-in approach requires three main elements to establish its use as a cost-effective tool for  
24 remediation.

- 25 • First, multiple sites must be identified that share common physical and contaminant  
26 characteristics. These characteristics are referred to as the conceptual site model.
- 27 • Second, a remedial alternative, or standard remedy, must be established that has been  
28 shown to be protective and cost-effective for sites that share the common conceptual site  
29 model.
- 30 • Finally, sites sharing a common conceptual site model must be shown to require remedial  
31 action due to contaminant concentrations that pose risk to human health and the  
32 environment.

33 To use the plug-in approach for a waste site not evaluated in the FS, the site must fit the defined  
34 conceptual model and must be shown to require remedial action. The site then can be "plugged  
35 in" to the standard remedy. The following information describes how the plug-in approach is  
36 proposed for remedy selection.

1 **8.2.1.1 Establishing the Conceptual Site Model**

2 Four conceptual site models have been defined based on the site characteristics contained in the  
3 FS. These characteristics include the following:

- 4 • Type of contaminant inventory
- 5 • Concentrations of contaminants in environmental media
- 6 • Function of the waste site
- 7 • Types of contaminated environmental media (soil) or material (e.g., concrete, metal,  
8 wood)
- 9 • Extent of contamination within the environment (i.e., the depth of discharge, the expected  
10 contaminant distributions, and the potential for hydrologic and contaminant impacts to  
11 groundwater).

12 Based on the representative sites evaluated in the FS, the following three conceptual site models  
13 were developed:

- 14 • Waste sites where no hazardous material was disposed at the waste site or where  
15 contaminants disposed of currently meet the remedial action objectives (RAO).
- 16 • Waste sites where limited contamination exists at the waste sites, an existing soil cover is  
17 in place and of sufficient thickness to provide protection, contaminants are expected to  
18 meet the RAOs during the institutional control period (such as within 150 years), and  
19 groundwater PRGs are not exceeded. Contaminated environmental media include soil,  
20 solid waste, debris, and materials associated with the waste sites, such as timbers and  
21 pipes.
- 22 • Waste sites where contaminants exceed the RAOs and contamination is shallow,  
23 low-volume, and can be cost effectively remedied through removal, treatment, and  
24 disposal. Typically, these contaminants exceed the human health and ecological PRGs;  
25 however, groundwater PRGs are not exceeded at depths that make excavation  
26 impracticable. Contaminated environmental media include soil, solid waste, debris, and  
27 materials associated with the waste sites, such as timbers and vent pipes.

### 8.2.1.2 Establishment of the Standard Remedy

The standard remedies, based on the 200-CS-1 OU waste sites, have been defined on the basis of the conceptual models presented by the representative waste sites, as well as the alternative evaluations conducted for all waste sites. As such, three standard remedies are identified for potential plug-in sites. These remedies are highlighted below along with their required characteristics.

- **Alternative 1: No Action** has been defined as a standard remedy for waste sites whose conceptual site model indicates that no hazardous materials were disposed of at the waste site or that contaminants disposed of currently meet the RAOs.
- **Alternative 2: Maintain Existing Soil Cover, Monitored Natural Attenuation, and Institutional Controls** has been defined as the standard remedy for waste sites whose conceptual site model indicates that limited contamination exists at the waste sites, an existing soil cover is in place and of sufficient thickness to provide protection, contaminants are expected to meet the RAOs during the institutional control period (such as within 500 years), and groundwater PRGs are not exceeded. Contaminated environmental media are similar to the media at the waste sites included in this FS. These media include soil, solid waste, debris, and materials associated with the waste sites, such as timbers and pipes.
- **Alternative 3: Removal, Treatment, and Disposal** has been defined as the standard remedy for waste sites whose conceptual site model indicates that contaminants exceed the RAOs and that contamination is shallow, low-volume, and can be cost effectively remedied through the removal, treatment, and disposal of contaminated media. Typically, these contaminants exceed the human health and ecological PRGs. Contaminated environmental media are similar to the media at the waste sites included in this FS. These media include soil, solid waste, debris, and materials associated with the waste sites, such as timbers and pipes.

### 8.2.1.3 Establishing the Need for Remedial Action

Waste sites that share a common conceptual site model will “plug-in” to the standard remedy if they are determined to require remedial action due to a risk to human health and the environment (based on the defined RAOs and associated PRGs, as defined previously). Some of the waste sites in the 200-CS-1 OU likely will require confirmatory sampling to validate the conceptual site model and the identified preferred remedy. The preferred remedy will be implemented following confirmation of the conceptual site model. Should the confirmatory sampling indicate variations in the defined conceptual site model, this plug-in approach will be used to define the appropriate remedy.

## 8.3 CLOSURE OF RCRA TREATMENT, STORAGE, AND/OR DISPOSAL UNITS

The RCRA TSD units within the 200-CS-1 OU include the 216-A-29 Ditch, the 216-B-63 Trench, and the 216-S-10 Pond and Ditch (two waste sites are combined into one TSD

1 unit). These TSD units will undergo closure following the requirements of the *Hanford Federal*  
 2 *Facility Agreement and Consent Order* (Ecology et al. 1989) (Tri-Party Agreement);  
 3 WA7890008967, *Hanford Facility Resource Conservation and Recovery Act Permit*, ; and  
 4 *Washington Administrative Code* (WAC) 173-303-610, "Dangerous Waste Regulations,"  
 5 "Closure and Post-Closure." Characterization sampling of these TSD units occurred, during the  
 6 remedial investigation, in conjunction with the CERCLA remedial action for the 200-CS-1 OU.

7 Tri-Party Agreement Milestone M-20-39 requires submittal of the 216-S-10 Pond and Ditch  
 8 closure plan by March 31, 2006. Closure plans for the 216-B-63 Trench and the 216-A-29 Ditch  
 9 were originally submitted in 1995 in accordance with Tri-Party Agreement Milestone M-20-36.  
 10 The two 1995 closure plans are being superseded with the March 2006 submittal. The closure  
 11 plans for 216-B-63 Trench and 216-S-10 Pond and Ditch TSD units will be submitted separately  
 12 because soils and structures can be clean closed as is without any need to coordinate remedial  
 13 activities with the 200-CS-1 OU. The closure plan for the 216-A-29 Ditch is contained in  
 14 Appendix E of this FS because closure is dependent on 200-CS-1 OU remedial activities. Public  
 15 review and approval of the 216-A-29 Ditch closure plan is anticipated to occur concurrently with  
 16 the review of the Feasibility Study. Public review and approval for the 216-B-63 Trench and  
 17 216-S-10 Pond and Ditch closure plans can occur separately from the Feasibility Study or can  
 18 also occur concurrently, if appropriate. The Hanford Facility RCRA Permit modification process  
 19 will be determined based on the timing of the public review and approval process with when the  
 20 TSD units will be incorporated into the Hanford Facility RCRA Permit. RCRA/CERCLA  
 21 integration of closure plan activities with the 200-CS-1 OU remedial actions is only needed for  
 22 the 216-A-29 Ditch closure plan.

23 The proposed closure strategy for each of these TSD units is as follows:

24 • **216-A-29 Ditch.** Based on analytical data obtained during the remedial investigation and  
 25 review of Hanford Environmental Information System (HEIS) data, all elements of this unit (soil  
 26 and groundwater) are expected to qualify for clean closure in accordance with WAC  
 27 173-303-610(2) after remediation of the soils. A plan for clean closure of this unit is provided in  
 28 Appendix E. A RCRA final status groundwater monitoring plan will not be required for this  
 29 unit.

30 • **216-B-63 Trench.** Based on analytical data obtained during the remedial investigation  
 31 and review of HEIS data, all elements of this unit (soils, structures, and groundwater) qualify for  
 32 clean closure in accordance with WAC 173-303-610(2) without further physical closure  
 33 activities. A plan for clean closure of this unit is provided in DOE/RL-2006-11, *Hanford*  
 34 *Facility Dangerous Waste Closure Plan for 216-B-63 Trench*. A RCRA final status groundwater  
 35 monitoring plan will not be required for this unit.

36 • **216-S-10 Pond and Ditch.** Based on analytical data obtained during the remedial  
 37 investigation, this soils for this unit qualify for clean closure in accordance with  
 38 WAC 173-303-610(2) without further physical closure activities. Based on review of HEIS data,  
 39 the groundwater associated with this TSD unit does not meet the clean closure levels and will  
 40 require post closure monitoring. A plan for clean closure of the soils associated with this unit is  
 41 provided in DOE/RL-2006-12, *Hanford Facility Dangerous Waste Closure/Postclosure Plan for*

1 provided in DOE/RL-2006-12, *Hanford Facility Dangerous Waste Closure/Postclosure Plan for*  
2 *the 216-S-10 Pond and Ditch*. A RCRA final status groundwater-monitoring plan has been  
3 prepared separately from the closure plan.

#### 4 8.4 PUBLIC INVOLVEMENT IN THE PLUG-IN 5 APPROACH

6 To ensure that the public is involved in the application of the plug-in approach, the  
7 U.S. Department of Energy, U.S. Environmental Protection Agency, and Washington State  
8 Department of Ecology will publish explanations of significant differences at the following  
9 points in the plug-in process:

- 10     • When newly discovered waste sites are proven through analysis to be above remediation  
11 goals and can plug in to the standard remedy
- 12     • When confirmatory sampling identified for the waste sites discussed herein indicates  
13 variations in the defined conceptual site model such that the preferred remedy is no  
14 longer protective.

#### 15 8.5 REFERENCES

16 *Comprehensive Environmental Response, Compensation, and Liability Act of 1980,*  
17 42 USC 9601, et seq.

18 DOE/RL-98-28, 1999, *200 Areas Remedial Investigation/Feasibility Study Implementation*  
19 *Plan – Environmental Restoration Program*, Rev. 0, U.S. Department of Energy,  
20 Richland Operations Office, Richland, Washington.

21 DOE/RL-2004-17, 2004, *Remedial Investigation Report for the 200-CS-1 Chemical Sewer*  
22 *Group Operable Unit*, Rev. 0, U.S. Department of Energy, Richland Operations Office,  
23 Richland, Washington.

24 DOE/RL-2006-11, 2006, *Hanford Facility Dangerous Waste Closure Plan for 216-B-63 Trench,*  
25 *Decisional Draft*, U.S. Department of Energy, Richland Operations Office, Richland,  
26 Washington.

27 DOE/RL-2006-12, 2006, *Hanford Facility Dangerous Waste Closure/Postclosure Plan for the*  
28 *216-S-10 Pond and Ditch*, *Decisional Draft*, U.S. Department of Energy, Richland  
29 Operations Office, Richland, Washington.

1 WA7890008967, 2004, *Hanford Facility Resource Conservation and Recovery Act Permit,*  
2 *Dangerous Waste Portion, Revision 8, for the Treatment, Storage, and Disposal of*  
3 *Dangerous Waste,* Washington State Department of Ecology, Richland, Washington, as  
4 amended.

5 WAC 173-303-610, "Dangerous Waste Regulations," "Closure and Post-Closure," *Washington*  
6 *Administrative Code,* as amended, Washington State Department of Ecology, Olympia,  
7 Washington.

Table 8-1. Preferred Alternative for the Representative Site 216-A-29 Ditch.

Comparison of Alternatives - Representative Site 216-A-29 Ditch				
Criteria for Representative and Analogous Waste Sites	Alternatives			
	① No Action	② MESC, MNA, IC	③ RTD	④ Capping
Representative Site 216-A-29 Ditch			<input checked="" type="checkbox"/>	
<b>Threshold Criteria</b>				
Overall protection	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
Compliance with ARARs	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>
<b>Balancing Criteria</b>				
Long-term effectiveness	◇	◇	◆	◇
Reduction in TMV	◇	◇	◇	◇
Short-term effectiveness	◇	◇	◇	◆
Implementability	◇	◇	◆	◇
Cost (in thousands)				
Capital costs	\$0	\$35,400	\$2,759,317	\$3,587,527
Non-discounted costs	\$0	\$4,031,232		\$25,954,293
Total present worth	\$0	\$868,340	\$2,759,317	\$9,488,213

NOTE: The choice of the preferred alternative is based on information at the writing of this feasibility study. The preferred alternative may be revised based on future characterization efforts at the analogous sites.

- = Indicates the preferred alternative (see Note).
- = Yes, meets criterion.
- = No, does not meet criterion.
- ◆ = High: best satisfies evaluation guidelines.
- ◇ = Moderate: satisfies evaluation guidelines.
- ◇ = Low: least satisfies evaluation guidelines.

ARAR = applicable or relevant and appropriate requirement.  
 IC = institutional controls.  
 MESC = maintain existing soil cover.  
 MNA = monitored natural attenuation.  
 RTD = removal, treatment, and disposal.

1

Table 8-2. Preferred Alternative for the Representative Site 216-B-63 Trench.

Comparison of Alternatives - Representative Site 216-B 63 Trench				
Criteria for Representative and Analogous Waste Sites	Alternatives			
	① No Action	② MESC, MNA, IC	③ RTD	④ Capping
Representative Site 216-B-63 Trench	☑			
<b>Threshold Criteria</b>				
Overall protection	☑	N/A	N/A	N/A
Compliance with ARARs	☑	N/A	N/A	N/A
<b>Balancing Criteria</b>				
Long-term effectiveness	◆	N/A	N/A	N/A
Reduction in TMV	◆	N/A	N/A	N/A
Short-term effectiveness	◆	N/A	N/A	N/A
Implementability	◆	N/A	N/A	N/A
Cost (in thousands)				
Capital costs	N/A	N/A	N/A	N/A
Non-discounted costs	N/A	N/A	N/A	N/A
Total present worth	N/A	N/A	N/A	N/A

NOTE: The choice of the preferred alternative is based on information at the writing of this feasibility study. The preferred alternative may be revised based on future characterization efforts at the analogous sites.

- ☑ = Indicates the preferred alternative (see Note).
- ☑ = Yes, meets criterion.
- ☐ = No, does not meet criterion.
- ◆ = High: best satisfies evaluation guidelines.
- ◇ = Moderate: satisfies evaluation guidelines.
- ◇ = Low: least satisfies evaluation guidelines.

ARAR = applicable or relevant and appropriate requirement.  
 IC = institutional controls.  
 MESC = maintain existing soil cover.  
 MNA = monitored natural attenuation.  
 N/A = not applicable.  
 RTD = removal, treatment, and disposal.

2

Table 8-3. Preferred Alternative for the Representative Site 216-S-10 Ditch.

Comparison of Alternatives - Representative Site 216-S-10 Ditch				
Criteria for Representative and Analogous Waste Sites	Alternatives			
	① No Action	② MESC, MNA, IC	③ RTD	④ Capping
<b>Representative Site 216-S-10 Ditch</b>			☑	
<b>Threshold Criteria</b>				
Overall protection	☐	☐	☑	☑
Compliance with ARARs	☐	☐	☑	☑
<b>Balancing Criteria</b>				
Long-term effectiveness	◇	◇	◆	◇
Reduction in TMV	◇	◇	◇	◇
Short-term effectiveness	◇	◇	◆	◇
Implementability	◇	◇	◇	◇
Cost (in thousands)				
Capital costs	\$0	\$35,400	\$1,679,178	\$1,647,518
Non-discounted costs	\$0	\$4,077,514		\$8,456,185
Total present worth	\$0	\$876,538	\$1,679,178	\$3,573,574

NOTE: The choice of the preferred alternative is based on information at the writing of this feasibility study. The preferred alternative may be revised based on future characterization efforts at the analogous sites.

- ☑ = Indicates the preferred alternative (see Note).
- ☑ = Yes, meets criterion.
- ☐ = No, does not meet criterion.
- ◆ = High: best satisfies evaluation guidelines.
- ◇ = Moderate: satisfies evaluation guidelines.
- ◇ = Low: least satisfies evaluation guidelines.

ARAR = applicable or relevant and appropriate requirement.  
 IC = institutional controls.  
 MESC = maintain existing soil cover.  
 MNA = monitored natural attenuation.  
 RTD = removal, treatment, and disposal.

1

Table 8-4. Preferred Alternative for the Representative Site 216-10-Pond and Analogous Waste Sites.

Comparison of Alternatives - Representative Site 216-S-10 Pond				
Criteria for Representative and Analogous Waste Sites	Alternatives			
	① No Action	② MESC, MNA, IC	③ RTD	④ Capping
Representative Site 216-S-10-Pond	☑			
<b>Threshold Criteria</b>				
Overall protection	☑	N/A	N/A	N/A
Compliance with ARARs	☑	N/A	N/A	N/A
<b>Balancing Criteria</b>				
Long-term effectiveness	◆	N/A	N/A	N/A
Reduction in TMV	◆	N/A	N/A	N/A
Short-term effectiveness	◆	N/A	N/A	N/A
Implementability	◆	N/A	N/A	N/A
Cost (in thousands)				
Capital costs	N/A	N/A	N/A	N/A
Non-discounted costs	N/A	N/A	N/A	N/A
Total present worth	N/A	N/A	N/A	N/A

NOTE: The choice of the preferred alternative is based on information at the writing of this feasibility study. The preferred alternative may be revised based on future characterization efforts at the analogous sites.

- ☑ = Indicates the preferred alternative (see Note).
- ☑ = Yes, meets criterion.
- ☐ = No, does not meet criterion.
- ◆ = High: best satisfies evaluation guidelines.
- ◇ = Moderate: satisfies evaluation guidelines.
- ◇ = Low: least satisfies evaluation guidelines.

- ARAR = applicable or relevant and appropriate requirement.
- IC = institutional controls.
- MESC = maintain existing soil cover.
- MNA = monitored natural attenuation.
- N/A = not applicable.
- RTD = removal, treatment, and disposal.

2

1

Table 8-5. Preferred Alternative for the Representative Site 216-11 Pond.

Comparison of Alternatives - Representative Site 216-S-11 Pond				
Criteria for Representative and Analogous Waste Sites	Alternatives			
	① No Action	② MESC, MNA, IC	③ RTD	④ Capping
<b>Representative Site 216-S-11 Pond</b>	<input checked="" type="checkbox"/>			
<b>Threshold Criteria</b>				
Overall protection	<input checked="" type="checkbox"/>	N/A	N/A	N/A
Compliance with ARARs	<input checked="" type="checkbox"/>	N/A	N/A	N/A
<b>Balancing Criteria</b>				
Long-term effectiveness	◆	N/A	N/A	N/A
Reduction in TMV	◆	N/A	N/A	N/A
Short-term effectiveness	◆	N/A	N/A	N/A
Implementability	◆	N/A	N/A	N/A
Cost (in thousands)				
Capital costs	N/A	N/A	N/A	N/A
Non-discounted costs	N/A	N/A	N/A	N/A
Total present worth	N/A	N/A	N/A	N/A

NOTE: The choice of the preferred alternative is based on information at the writing of this feasibility study. The preferred alternative may be revised based on future characterization efforts at the analogous sites.

- = Indicates the preferred alternative (see Note).
- = Yes, meets criterion.
- = No, does not meet criterion.
- ◆ = High: best satisfies evaluation guidelines.
- ◇ = Moderate: satisfies evaluation guidelines.
- ◇ = Low: least satisfies evaluation guidelines.

ARAR = applicable or relevant and appropriate requirement.  
 IC = institutional controls.  
 MESC = maintain existing soil cover.  
 MNA = monitored natural attenuation.  
 N/A = not applicable.  
 RTD = removal, treatment, and disposal.

2

1

Table 8-6. Post-Record of Decision Sampling.

Alternative	Confirmatory Sampling						Design Sampling	Verification Sampling		
	Confirm Appropriate Remedial Action	Nature of Contamination	Extent of Contamination	Groundwater Protection	Ecological Sampling	Observational Approach	Extent of Contamination	Verify No-Action Alternative	Ecological Sampling	Verify PRG Attainment
<b>Alternative 1 – No Action</b>										
216-B-63 Trench										
216-S-10 Pond										
216-S-11 Pond								●		
<b>Alternative 3 – Removal, Treatment, and Disposal</b>										
216-A-29 Ditch						●	●			●
216-S-10 Ditch						●	●			●

PRG = preliminary remediation goal.  
 ● = proposed post-record of decision sampling.

2

## 9.0 REFERENCES

- 1
- 2 36 CFR 60, "National Register of Historic Places," Title 36, *Code of Federal Regulations*,  
3 Part 60, as amended.
- 4 36 CFR 60, "National Register of Historic Places," Section 60.4, "Criteria for Evaluation,"  
5 Title 36, *Code of Federal Regulations*, Part 60, as amended.
- 6 40 CFR 141, "National Primary Drinking Water Regulations," Title 40, *Code of Federal*  
7 *Regulations*, Part 141, as amended.
- 8 40 CFR 141, "National Primary Drinking Water Regulations," Section 141.66, "Maximum  
9 Contaminant Levels for Radionuclides," Title 40, *Code of Federal Regulations*, Part 141,  
10 as amended.
- 11 40 CFR 300, "National Oil and Hazardous Substances Pollution Contingency Plan," Title 40,  
12 *Code of Federal Regulations*, Part 300, as amended.
- 13 40 CFR 300, "National Oil and Hazardous Substances Pollution Contingency Plan,"  
14 Appendix B, "National Priorities List," Title 40, *Code of Federal Regulations*, Part 300,  
15 as amended.
- 16 40 CFR 1502.16, "Environmental Impact Statement," "Environmental Consequences," Title 40,  
17 *Code of Federal Regulations*, Part 1502.16, as amended.
- 18 64 FR 61615, "Record of Decision: Hanford Comprehensive Land-Use Plan Environmental  
19 Impact Statement (HCP EIS)," *Federal Register*, Vol. 64, No. 218, pp. 61615-61625,  
20 November 12, 1999.
- 21 Albright, W. H., C. H. Benson, G. W. Gee, T. Abichou, A. C. Roesler, and S. A. Rock, 2003,  
22 "Examining the Alternatives," *Civil Engineering*, Vol. 73, No. 5, May.
- 23 Amdur, M. O., M. D. Doull, and C. D. Klassen, 1991, *Casarett and Doull's Toxicology: The*  
24 *Basic Science of Poisons*, Pergamon Press, New York.
- 25 ANL, 2002, *RESRAD for Windows*, Version 6.21, Environmental Assessment Division, Argonne  
26 National Laboratory, Argonne, Illinois.
- 27 ARH-2015, 1971, *Radioactive Liquid Wastes Discharged to Ground in the 200 Areas During*  
28 *1970; Part 3*, Atlantic Richfield Hanford, Richland, Washington.
- 29 ASTM E1943-98, 2004, *Standard Guide for Remediation of Groundwater by Natural*  
30 *Attenuation at Petroleum Release Sites*, American Society for Testing and Materials,  
31 Conshohocken, Pennsylvania.
- 32 *Atomic Energy Act of 1954*, 42 USC 2011, et seq.

- 1 Benjamin, M.A., 2002, *Water Chemistry*, McGraw-Hill, New York
- 2 BHI-00139, 2002, *Environmental Restoration Disposal Facility Waste Acceptance Criteria*,  
3 Rev. 4, Bechtel Hanford, Inc, Richland, Washington.
- 4 BHI-00176, 1995, *S Plant Aggregate Area Management Study Technical Baseline Report*,  
5 Rev. 0, Bechtel Hanford, Inc., Richland, Washington.
- 6 BHI-01177, 1998, *Borehole Summary Report for the 216-B-2-2 Ditch*, Rev. 0, Bechtel  
7 Hanford, Inc., Richland, Washington.
- 8 BHI-01276, 1999, *200-CS-1 Operable Unit DQO Summary Report*, Rev. 0, Bechtel Hanford,  
9 Inc., Richland, Washington.
- 10 BHI-01551, 2002, *Alternative Fine-Grained Soil Borrow Source Study Final Report*, Rev. 0,  
11 Bechtel Hanford, Inc., Richland, Washington.
- 12 BHI-01651, 2002, *200-CS-1 Operable Unit Test Pit Summary Report for Fiscal Year 2002*,  
13 Rev. 0, Bechtel Hanford, Inc., Richland, Washington.
- 14 BHI-062455, 1998, *Transmittal of Final Letter Report on Sampling and Analytical Activities at*  
15 *the 216-A-29 Ditch*, letter report, Bechtel Hanford, Inc., Richland, Washington.
- 16 BNWL-1794, 1973, *Distribution of Radioactive Jackrabbit Pellets in the Vicinity of the*  
17 *B-C Cribs, 200 East Area, USAEC Hanford Reservation*, Battelle Northwest  
18 Laboratories, Richland, Washington.
- 19 Census, 2001, *Poverty Thresholds in 2000, by Size of Family and Number of Related Children*  
20 *Under 18 Years*, last revised January 29, 2001, U.S. Bureau of the Census,  
21 U.S. Department of Commerce, Washington, D.C. Available at <http://www.census.gov>.
- 22 *Comprehensive Environmental Response, Compensation, and Liability Act of 1980*,  
23 42 USC 9601, et seq.
- 24 Dean, J. E. 1992, *Lange's Handbook of Chemistry*, CRC Press, Boca Raton, Florida.
- 25 DOE O 451.1A, *National Environmental Policy Act Compliance Program*, U.S. Department of  
26 Energy, Washington, D.C.
- 27 DOE, 1994, *Secretarial Policy on the National Environmental Policy Act* (memorandum from  
28 H. R. O'Leary, Secretary of Energy, for Secretarial Officers and Heads of Field  
29 Elements), U.S. Department of Energy, Washington, D.C., June 13.
- 30 DOE/EIS-0222-F, 1999, *Final Hanford Comprehensive Land-Use Plan Environmental Impact*  
31 *Statement*, U.S. Department of Energy, Washington, D.C.
- 32 DOE/RL-91-45, 1995, *Hanford Site Baseline Risk Assessment Methodology*, Rev. 3,  
33 U.S. Department of Energy, Richland Operations Office, Richland, Washington.

DOE/RL-2005-63 DRAFT A

- 1 DOE/RL-92-19, 1993, *200 East Groundwater Aggregate Area Management Study Report*,  
2 Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- 3 DOE/RL-92-24, 2001, *Hanford Site Background: Part 1, Soil Background for Nonradioactive*  
4 *Analytes*, Rev. 4, 2 vols., U.S. Department of Energy, Richland Operations Office,  
5 Richland, Washington.
- 6 DOE/RL-93-33, 1996, *Focused Feasibility Study of Engineered Barriers for Waste Management*  
7 *Units in the 200 Areas*, Rev. 1, U.S. Department of Energy, Richland Operations Office,  
8 Richland, Washington.
- 9 DOE/RL-96-12, 1996, *Hanford Site Background: Part 2, Soil Background for Radionuclides*,  
10 Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- 11 DOE/RL-96-32, 1996, *Hanford Site Biological Resources Management Plan*, Rev. 0,  
12 U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- 13 DOE/RL-96-81, 1997, *Waste Site Grouping for 200 Areas Soil Investigations*, Rev. 0,  
14 U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- 15 DOE/RL-97-56, 1998, *Hanford Site Manhattan Project and Cold War Era Historic District*  
16 *Treatment Plan*, Rev. 1, U.S. Department of Energy, Richland Operations Office,  
17 Richland, Washington.
- 18 DOE/RL-98-10, 2003, *Hanford Cultural Resource Management Plan*, U.S. Department of  
19 Energy, Richland Operations Office, Richland, Washington.
- 20 DOE/RL-98-28, 1999, *200 Areas Remedial Investigation/Feasibility Study Implementation*  
21 *Plan – Environmental Restoration Program*, Rev. 0, U.S. Department of Energy,  
22 Richland Operations Office, Richland, Washington.
- 23 DOE/RL-99-11, 1999, *200-BP-1 Prototype Barrier Treatability Test Report*, Rev. 0,  
24 U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- 25 DOE/RL-99-44, 2000, *200-CS-1 Operable Unit RI/FS Work Plan and RCRA TSD Unit Sampling*  
26 *Plan*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland,  
27 Washington.
- 28 DOE/RL-2000-35, 2001, *200-CW-1 Operable Unit Remedial Investigation Report*,  
29 U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- 30 DOE/RL-2001-06, 2001, *Comments on Hanford 2012: Accelerating Cleanup and Shrinking the*  
31 *Site*, U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- 32 DOE/RL-2001-54, 2003, *Central Plateau Ecological Evaluation*, Draft B, U.S. Department of  
33 Energy, Richland Operations Office, Richland, Washington.

- 1 DOE/RL-2002-39, 2002, *Standardized Stratigraphic Nomenclature for Post-Ringold Formation*  
2 *Sediments Within the Central Pasco Basin*, U.S. Department of Energy, Richland,  
3 Washington.
- 4 DOE/RL-2002-42, 2003, *Remedial Investigation Report for the 200-TW-1 and*  
5 *200-TW-2 Operable Units (Includes the 200-PW-5 Operable Unit)*, Rev. 0,  
6 U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- 7 DOE/RL-2004-17, 2004, *Remedial Investigation Report for the 200-CS-1 Chemical Sewer*  
8 *Group Operable Unit*, Rev. 0, U.S. Department of Energy, Richland Operations Office,  
9 Richland, Washington.
- 10 DOE/RL-2006-11, 2006, *Hanford Facility Dangerous Waste Closure Plan for 216-B-63 Trench*,  
11 *Decisional Draft*, U.S. Department of Energy, Richland Operations Office, Richland,  
12 Washington.
- 13 DOE/RL-2006-12, 2006, *Hanford Facility Dangerous Waste Closure/Postclosure Plan for the*  
14 *216-S-10 Pond and Ditch*, *Decisional Draft*, U.S. Department of Energy, Richland  
15 Operations Office, Richland, Washington.
- 16 DOE-STD-1153-2002, 2002, *A Graded Approach for Evaluating Radiation Doses to Aquatic*  
17 *and Terrestrial Biota*, DOE Technical Standard, U.S. Department of Energy,  
18 Washington, D.C., available on the Internet at  
19 <http://www.eh.doe.gov/techstds/standard/std1153/1153.htm> .
- 20 Dragun, J., 1998, *The Soil Chemistry of Hazardous Materials*, Amherst Scientific Publishers,  
21 Amherst, Massachusetts.
- 22 Dragun, J., and K. Chekiri, 2005, *Elements in North American Soils*, 2<sup>nd</sup> ed., Amherst Scientific  
23 Publishers, Amherst, Massachusetts.
- 24 Drummond, M. E., 1992, *The Future for Hanford: Uses and Cleanup, The Final Report of the*  
25 *Hanford Future Site Uses Working Group*, Richland, Washington.
- 26 Ecology 94-145, 2001, *Cleanup Levels and Risk Calculations under the Model Toxics Control*  
27 *Act Cleanup Regulation; CLARC, Version 3.1*, Washington State Department of Ecology,  
28 Olympia, Washington.
- 29 Ecology, 2003, *Cleanup Levels and Risk Calculations (CLARC) Database*,  
30 <https://fortress.wa.gov/ecy/clarc/CLARCHome.aspx> .
- 31 Ecology, EPA, and DOE, 1989, *Hanford Federal Facility Agreement and Consent Order*,  
32 2 vols., Washington State Department of Ecology, U.S. Environmental Protection  
33 Agency, and U.S. Department of Energy, Olympia, Washington, as amended.
- 34 *Endangered Species Act of 1973*, 16 USC 1531, et seq.

- 1 EPA, 2002, *Calculating Upper Confidence Limits for Exposure Point Concentrations at*  
2 *Hazardous Waste Sites*, OSWER 9285.6-10, Office of Emergency and Remedial  
3 Response, U.S. Environmental Protection Agency, Washington, D.C.
- 4 EPA, 2003, *Guidance for Developing Ecological Soil Screening Levels*, OSWER Directive  
5 9285.7-55, Office of Solid Waste and Emergency Response, U.S. Environmental  
6 Protection Agency, Washington, D.C. Available at:  
7 [http://www.epa.gov/ecotox/ecossl/pdf/ecossl\\_guidance\\_chapters.pdf](http://www.epa.gov/ecotox/ecossl/pdf/ecossl_guidance_chapters.pdf)
- 8 EPA, 2005, *IRIS Profile for Arsenic*, Integrated Risk Information System,  
9 <http://www.epa.gov/iris/>, U.S. Environmental Protection Agency, Washington, D.C.
- 10 EPA/540/1-89/002, 1989, *Risk Assessment Guidance for Superfund (RAGS), Volume I -- Human*  
11 *Health Evaluation Manual, (Part A) Interim Final*, OSWER 9285.7-01A,  
12 U.S. Environmental Protection Agency, Washington, D.C.
- 13 EPA/540/2-88/002, 1988, *Technological Approaches to Cleanup of Radiologically*  
14 *Contaminated Superfund Sites*, U.S. Environmental Protection Agency,  
15 Washington, D.C.
- 16 EPA/540/D-00/001a, 1999, *Screening Level Ecological Risk Assessment Protocol for Hazardous*  
17 *Waste Combustion Facilities*, U.S. Environmental Protection Agency, Washington, D.C.
- 18 EPA/540/G-89/004, 1988, *Guidance for Conducting Remedial Investigations and Feasibility*  
19 *Studies under CERCLA, (Interim Final)*, OSWER 9355.3-01, Office of Solid Waste and  
20 Emergency Response, U.S. Environmental Protection Agency, Washington, D.C.
- 21 EPA/540/R-97/006, 1997, *Ecological Risk Assessment Guidance for Superfund: Process for*  
22 *Designing and Conducting Ecological Risk Assessments (Interim Final)*, Office of Solid  
23 Waste and Emergency Response, U.S. Environmental Protection Agency,  
24 Washington, D.C.
- 25 EPA/540/R-99/005, 2004, *Risk Assessment Guidance for Superfund, Volume I: Human Health*  
26 *Evaluation Manual (Part E, Supplemental Guidance for Dermal Risk Assessment) Final*,  
27 U.S. Environmental Protection Agency, Washington, D.C.
- 28 EPA/540/R-99/009, 1999, *Use of Monitored Natural Attenuation at Superfund RCRA Corrective*  
29 *Action and Underground Storage Tank Sites November 1997*, OSWER 9200.4-17P,  
30 Office of Emergency and Remedial Response, U.S. Environmental Protection Agency,  
31 Washington, D.C.
- 32 EPA/600/P-95/002B, 1996, *Exposure Factor Handbook, Volume I, General Factors*,  
33 U.S. Environmental Protection Agency, Washington, D.C.
- 34 EPA/630/R-95/002F, 1998, *Guidelines for Ecological Risk Assessment*, U.S. Environmental  
35 Protection Agency, Risk Assessment Forum, Washington, D.C. Available at:  
36 <http://cfpub.epa.gov/ncea/cfm/recordisplay.cfm?deid=12460>

- 1 EPA/800/6-85/002b, 1985, *Water Quality Assessment: A Screening Procedure for Toxic and*  
2 *Conventional Pollutants in Surface and Groundwater – Part II*, Environmental Research  
3 Laboratory, Athens, Georgia.
- 4 ES/ER/TN-86/R3, 1996, *Toxicological Benchmarks for Wildlife: 1996 Revision*, Risk  
5 Assessment and Health Sciences Research Division, Oak Ridge National Laboratory,  
6 Oak Ridge, Tennessee.
- 7 Executive Order 12898, 1994, *Federal Actions to Address Environmental Justice in Minority*  
8 *Populations and Low-Income Populations*, William J. Clinton, February 11.
- 9 Gee, G. W., M. J. Fayer, M. L. Rockhold, and M. D. Campbell, 1992, "Variations in Recharge at  
10 the Hanford Site," *Northwest Science*, Vol. 66, pp. 237-250.
- 11 GSC, 1998, *SESOIL*, General Sciences Corporation, Beltsville, Maryland.
- 12 Hakonson, T. E., J. L. Martinez, and G. C. White, 1982, "Disturbance of a Low-Level Waste  
13 Burial Site Cover by Pocket Gophers," *Health Physics*, 42:868-871.
- 14 HW-43121, 1956, *Tabulation of Radioactive Liquid Waste Disposal Facilities*, General Electric  
15 Company, Richland, Washington.
- 16 HW-60807, 1959, *Unconfined Underground Radioactive Waste and Contamination in the*  
17 *200 Areas - 1959*, General Electric Company, Richland, Washington.
- 18 INEEL-01-00281, 2001, *Engineering Design File, Operable Unit 7-13/14 Evaluation of Soil and*  
19 *Buried Waste Retrieval Technologies*, Revision A, Idaho National Engineering and  
20 Environmental Laboratory, Idaho Falls, Idaho.
- 21 Klein, K. A., D. R. Einan, and M. A. Wilson, 2002, "Consensus Advice #132: Exposure  
22 Scenarios Task Force on the 200 Area," (letter to Mr. Todd Martin, Hanford Advisory  
23 Board, from Keith A. Klein, U.S. Department of Energy; David R. Einan,  
24 U.S. Environmental Protection Agency; and Michael A. Wilson, State of Washington,  
25 Department of Ecology), Richland, Washington, July 11.
- 26 Lindsay, W. L., 1979, *Chemical Equilibria in Soils*, John Wiley and Sons, New York.
- 27 Mackay, D., W. Y. Shiu, and K. C. Ma, 2000, *Physical-Chemical Properties and Environmental*  
28 *Fate Handbook*, Chapman & Hall Publishers, CRC Press, Boca Raton, Florida.
- 29 *Migratory Bird Treaty Act of 1918*, 16 USC 703, et seq.
- 30 NAP, 1983, *Risk Assessment in the Federal Government: Managing the Process*, National  
31 Academy Press, National Academy of Sciences, Washington, D.C.
- 32 *National Environmental Policy Act of 1969*, 42 USC 4321, et seq.
- 33 *National Historic Preservation Act of 1966*, 16 USC 470, et seq.

- 1 Pendas, H., and A. Kabata-Pendas, 1992, "Trace Elements in Soils and Plants," 2<sup>nd</sup> Ed.,  
2 CRC Press, Boca Raton, Florida.
- 3 PNL-6415, 1996, *Hanford Site National Environmental Policy Act (NEPA) Characterization*,  
4 Rev. 8, Pacific Northwest Laboratory, Richland, Washington.
- 5 PNNL-6415, 2005, *Hanford Site National Environmental Policy Act (NEPA) Characterization*,  
6 Rev. 17, Pacific Northwest National Laboratory, Richland, Washington.
- 7 PNL-7264, 1990, *Archaeological Survey of the 200 East and 200 West Areas, Hanford Site*,  
8 *Washington*, Pacific Northwest Laboratory, Richland, Washington.
- 9 PNNL-11472, 1997, *Hanford Site Environmental Report for Calendar Year 1996*, Pacific  
10 Northwest National Laboratory, Richland, Washington.
- 11 PNNL-11800, 1998, *Composite Analysis for Low-Level Waste Disposal in the 200 Area Plateau*  
12 *of the Hanford Site*, Pacific Northwest National Laboratory, Richland, Washington.
- 13 PNNL-12261, 2000, *Revised Hydrogeology for the Suprabasalt Aquifer System 200-East Area*  
14 *and Vicinity, Hanford Site, Washington*, Pacific Northwest National Laboratory,  
15 Richland, Washington.
- 16 PNNL-13033, 1999, *Recharge Data Package for the Immobilized Low-Activity Waste 2001*  
17 *Performance Assessment*, Pacific Northwest National Laboratory, Richland, Washington.
- 18 PNNL-13198, 2000, *Borehole Data Package for the 216-S-10 Pond and Ditch*  
19 *Well 299-W26-13*, Rev. 0, Pacific Northwest National Laboratory, Richland, Washington.
- 20 PNNL-13788, 2002, *Hanford Site Groundwater Monitoring for Fiscal Year 2001*, Pacific  
21 Northwest National Laboratory, Richland, Washington.
- 22 PNNL-13858, 2002, *Revised Hydrogeology for the Suprabasalt Aquifer System, 200-West Area*  
23 *and Vicinity, Hanford Site, Washington*, Pacific Northwest National Laboratory,  
24 Richland, Washington.
- 25 PNNL-13895, 2003, *Hanford Contaminant Distribution Coefficient Database and Users Guide*,  
26 Rev. 1, Pacific Northwest National Laboratory, Richland, Washington.
- 27 PNNL-13910, 2002, *Hanford Site Environmental Report for Calendar Year 2001*, Pacific  
28 Northwest National Laboratory, Richland, Washington.
- 29 PNNL-14187, 2003, *Hanford Site Groundwater Monitoring for Fiscal Year 2002*, Pacific  
30 Northwest National Laboratory, Richland, Washington.
- 31 PNNL-14070, 2002, *Groundwater Monitoring Plan for the 216-S-10 Pond and Ditch*, Pacific  
32 Northwest National Laboratory, Richland, Washington, October 2002.
- 33 PNNL-14744, 2004, *Recharge Data Package for the 2005 Integrated Disposal Facility*  
34 *Performance Assessment*, Pacific Northwest National Laboratory, Richland, Washington.

- 1 Price, J. B., 2002, "Re: Waste Transfer Line Crossing Over the 216-A-29 Ditch Treatment,  
2 Storage, and Disposal Unit, 02-RCA-0301," (letter to J. E. Rasmussen, U.S. Department  
3 of Energy, Office of River Protection, and J. B. Hebdon, U.S. Department of Energy,  
4 Richland Operations Office), Washington State Department of Ecology, Kennewick,  
5 Washington, June 24.
- 6 RAIS, 2005, *Toxicity Profile for Sulfate*, U.S. Department of Energy's Risk Assessment  
7 Information System, [http://risk.lsd.ornl.gov/tox/rap\\_toxp.shtml](http://risk.lsd.ornl.gov/tox/rap_toxp.shtml).
- 8 RCW 36.70A, "Counties," "Growth Management – Planning by Selected Counties and Cities,"  
9 Title 36, Chapter 70A, *Revised Code of Washington*, as amended, Washington State,  
10 Olympia, Washington.
- 11 *Resource Conservation and Recovery Act of 1976*, 42 USC 6901, et seq.
- 12 RHO-CD-798, 1979, *Current Status of the 200 Area Ponds*, Rockwell Hanford Operations,  
13 Richland, Washington.
- 14 RHO-CD-1010, 1980, *B Plant Chemical Sewer System Upgrade*, Rockwell Hanford Operations,  
15 Richland, Washington.
- 16 *Risk Assessment Information System* (RAIS) database, prepared by Bechtel Jacobs Company  
17 LLC, for the U.S. Department of Energy, Oak Ridge Operations Office, Oak Ridge,  
18 Tennessee. Available at <http://risk.lsd.ornl.gov/>
- 19 Schacklette, H. T., and J. C. Boerngen, 1984, *Element Concentrations in Soils and Other*  
20 *Surficial Materials of the Conterminous United States*, U.S. Geological Survey  
21 Professional Paper 1270, U.S. Government Printing Office, Washington, D.C.
- 22 SD-496-CDR-001, 1984, *Conceptual Design Report Chemical Sewer Upgrade,*  
23 *221-B Project B-496*, Rockwell Hanford Operations, Richland, Washington.
- 24 TNC, 1999, *Biodiversity Inventory and Analysis of the Hanford Site, Final Report 1994-1999,*  
25 *The Nature Conservancy of Washington*, Seattle, Washington.
- 26 Vitro-R-642, 1980, *Title I Report, Chemical Sewer Sampling, Monitoring, Flow Totalizing and*  
27 *Diverting System (PUREX), Project B-190*, Vitro Engineering Corporation, Richland,  
28 Washington.
- 29 WA7890008967, 2004, *Hanford Facility Resource Conservation and Recovery Act Permit,*  
30 *Dangerous Waste Portion, Revision 8, for the Treatment, Storage, and Disposal of*  
31 *Dangerous Waste*, Washington State Department of Ecology, Richland, Washington, as  
32 amended.
- 33 WAC 173-160, "Minimum Standards for Construction and Maintenance of Wells," *Washington*  
34 *Administrative Code*, as amended, Washington State Department of Ecology, Olympia,  
35 Washington.

- 1 WAC 173-303-610, "Dangerous Waste Regulations," "Closure and Post-Closure," *Washington*  
2 *Administrative Code*, as amended, Washington State Department of Ecology, Olympia,  
3 Washington.
- 4 WAC 173-340, "Model Toxics Control Act -- Cleanup," *Washington Administrative Code*, as  
5 amended, Washington State Department of Ecology, Olympia, Washington.
- 6 WAC 173-340-720, "Ground Water Cleanup Standards," *Washington Administrative Code*, as  
7 amended, Washington State Department of Ecology, Olympia, Washington.
- 8 WAC 173-340-740, "Unrestricted Land Use Soil Cleanup Standards," *Washington*  
9 *Administrative Code*, as amended, Washington State Department of Ecology, Olympia,  
10 Washington.
- 11 WAC 173-340-745, "Soil Cleanup Standards for Industrial Properties," *Washington*  
12 *Administrative Code*, as amended, Washington State Department of Ecology, Olympia,  
13 Washington.
- 14 WAC 173-340-745(5), "Soil Cleanup Standards for Industrial Properties," "Method C Industrial  
15 Soil Cleanup Levels," *Washington Administrative Code*, as amended, Washington State  
16 Department of Ecology, Olympia, Washington.
- 17 WAC 173-340-745(5)(b)(iii)(A), "Soil Cleanup Standards for Industrial Properties," "Method C  
18 Industrial Soil Cleanup Levels," "Standard Method C Industrial Soil Cleanup Levels,"  
19 "Human Health Protection," "Ground Water Protection," *Washington Administrative*  
20 *Code*, as amended, Washington State Department of Ecology, Olympia, Washington.
- 21 WAC 173-340-745(7), "Soil Cleanup Standards for Industrial Properties," "Point of  
22 Compliance," *Washington Administrative Code*, as amended, Washington State  
23 Department of Ecology, Olympia, Washington.
- 24 WAC 173-340-747, "Deriving Soil Concentrations for Ground Water Protection," *Washington*  
25 *Administrative Code*, as amended, Washington State Department of Ecology, Olympia,  
26 Washington.
- 27 WAC 173-340-747(3)(e), "Deriving Soil Concentrations for Ground Water Protection,"  
28 "Overview of Methods," "Alternative Fate and Transport Models," *Washington*  
29 *Administrative Code*, as amended, Washington State Department of Ecology, Olympia,  
30 Washington.
- 31 WAC 173-340-747(8), "Deriving Soil Concentrations for Ground Water Protection,"  
32 "Alternative Fate and Transport Models," *Washington Administrative Code*, as amended,  
33 Washington State Department of Ecology, Olympia, Washington.
- 34 WAC 173-340-900, "Tables," *Washington Administrative Code*, as amended, Washington State  
35 Department of Ecology, Olympia, Washington.

- 1 WAC 173-340-7490, "Terrestrial Ecological Evaluation Procedures," *Washington*  
2 *Administrative Code*, as amended, Washington State Department of Ecology, Olympia,  
3 Washington.
- 4 WAC 173-340-7492, "Simplified Terrestrial Ecological Evaluation Procedures," *Washington*  
5 *Administrative Code*, as amended, Washington State Department of Ecology, Olympia,  
6 Washington.
- 7 WAC 173-340-7493, "Site-Specific Terrestrial Ecological Evaluation Procedures," *Washington*  
8 *Administrative Code*, as amended, Washington State Department of Ecology, Olympia,  
9 Washington.
- 10 WAC 246-290, "Department of Health," "Public Water Supplies," *Washington Administrative*  
11 *Code*, as amended, Washington State Department of Health, Olympia, Washington.
- 12 WHC-EP-0342, 1990, Addendum 2, *PUREX Plant Chemical Sewer Stream-Specific Report*,  
13 Westinghouse Hanford Company, Richland, Washington.
- 14 WHC-EP-0342, 1990, Addendum 6, *B Plant Chemical Sewer Stream-Specific Report*,  
15 Westinghouse Hanford Company, Richland, Washington.
- 16 WHC-EP-0342, 1990, Addendum 9, *S Plant Wastewater Stream-Specific Report*, Westinghouse  
17 Hanford Company, Richland, Washington.
- 18 WHC-SD-EN-AP-031, 1990, *Interim-Status Groundwater Quality Assessment Program Plan for*  
19 *the 216-A-29 Ditch*, Rev. 0-A, Westinghouse Hanford Company, Richland, Washington.
- 20 WMP-17755, 2003, *200-CS-1 Operable Unit Field Summary Report for Fiscal Year 2003*,  
21 Rev. 0, Fluor Hanford, Inc., Richland, Washington.
- 22 WNHP, 1998, *Washington Rare Plant Species by County*, Washington Natural Heritage  
23 Program, available at <http://www.wa.gov/dnr/htdocs/fr/nhp/plantco.html#benton>.

1

**APPENDIX A**

2

3

**WASTE SITE PHOTOS**

4

This page intentionally left blank

1

**FIGURES**

2 Figure A-1. 216-A-29 Ditch. .... A-1  
3 Figure A-2. 216-B-63 Trench. .... A-2  
4 Figure A-3. 216-S-10 Ditch and 216-S-10 Pond. .... A-3  
5 Figure A-4. 216-S-11 Pond. .... A-4


1

This page intentionally left blank.

2

1  
2


Figure A-1. 216-A-29 Ditch.



3

1


Figure A-2. 216-B-63 Trench.



2  
3

1

Figure A-3. 216-S-10 Ditch and 216-S-10 Pond.




2  
3

Figure A-4. 216-S-11 Pond.

1

2



3

**APPENDIX B**

**POTENTIAL APPLICABLE OR RELEVANT AND APPROPRIATE REQUIREMENTS**

This page intentionally left blank.

CONTENTS

B1.0 POTENTIAL APPLICABLE OR RELEVANT AND APPROPRIATE REQUIREMENTS.....B-1

B1.1 WAIVERS FROM APPLICABLE OR RELEVANT AND APPROPRIATE REQUIREMENTS.....B-2

B1.2 POTENTIAL ARARS APPLICABLE TO REMEDIAL ACTIONS FOR WASTE SITES IN THE 200-CS-1 OPERABLE UNITS .....B-3

B2.0 REFERENCES .....B-3

TABLES

Table B-1. Identification of Potential Federal Applicable or Relevant and Appropriate Requirements and to be Considered for the Remedial Action Sites. .... B-6

Table B-2. Identification of Potential State Applicable and Relevant or Appropriate Requirements and to be Considered for the Remedial Action Sites. .... B-8

**TERMS**

ARAR	applicable or relevant and appropriate requirement
CERCLA	<i>Comprehensive Environmental Response, Compensation, and Liability Act of 1980</i>
CFR	<i>Code of Federal Regulations</i>
DOE	U.S. Department of Energy
EPA	U.S. Environmental Protection Agency
MCL	maximum contaminant level
OU	operable unit
PCB	polychlorinated biphenyl
p/m	parts per million
RCRA	<i>Resource Conservation and Recovery Act of 1976</i>
TBC	to be considered
TSD	treatment, storage, and/or disposal (unit)
WAC	<i>Washington Administrative Code</i>

APPENDIX B

POTENTIAL APPLICABLE OR RELEVANT AND APPROPRIATE REQUIREMENTS

B1.0 POTENTIAL APPLICABLE OR RELEVANT  
AND APPROPRIATE REQUIREMENTS

This appendix identifies and evaluates potential applicable or relevant and appropriate requirements (ARAR) for waste site remediation in the 200-CS-1 Operable Unit (OU). The potential ARARs identified in this document have been used to form the basis for the levels to which contaminants must be remediated to protect human health and the environment. The *Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (CERCLA)* provides for the identification of to-be-considered (TBC) nonpromulgated advisories, criteria, guidance, or proposed standards that may be consulted to interpret ARAR to-be-determined remediation goals when ARARs do not exist or are insufficient. Independent of the TBC and ARARs identification process at the Hanford Site, the requirements of U.S. Department of Energy (DOE) orders must be met.

Because the waste sites in the 200-CS-1 OU will be remediated under a CERCLA decision document, remedial and corrective actions at the sites will be required to meet ARARs. This appendix identifies and evaluates potential ARARs for these sites. Final ARARs for remediation will be established in the record of decision. In many cases, the ARARs form the basis for the preliminary remediation goals to which contaminants must be remediated to protect human health and the environment. In other cases, the ARARs define or restrict how specific remedial measures can be implemented.

The ARARs identification process is based on CERCLA guidance (EPA/540/G-89/006, *CERCLA Compliance with Other Laws Manual: Interim Final* and EPA/540/G-89/004, *Guidance for Conducting Remedial Investigations and Feasibility Studies under CERCLA, (Interim Final)*, OSWER 9355.3-01). Section 121 of CERCLA, as amended, requires, in part, that any applicable or relevant and appropriate standard, requirement, criterion, or limitation promulgated under any Federal environmental law, or any more stringent state requirement promulgated pursuant to a state environmental statute, be met (or a waiver justified) for any hazardous substance, pollutant, or contaminant that will remain on site after completion of remedial action.

Under this process, potential ARARs are classified into one of three categories: chemical-specific, location-specific, or action-specific. These categories are defined as follows.

- Chemical-specific requirements are usually health- or risk-based numerical values or methodologies that, when applied to site-specific conditions, result in the establishment of public and worker safety levels and site cleanup levels.

- Location-specific requirements are restrictions placed on the concentration of dangerous substances or the conduct of activities solely because they occur in special geographic areas.
- Action-specific requirements are usually technology- or activity-based requirements or limitations triggered by the remedial actions performed at the site.

When requirements in each of these categories are identified, a determination must be made as to whether those requirements are ARARs. A requirement is applicable if the specific terms or jurisdictional prerequisites of the law or regulations directly address the circumstances at a site. If not applicable, a requirement may nevertheless be relevant and appropriate if (1) circumstances at the site are, based on best professional judgment, sufficiently similar to the problems or situations regulated by the requirement and (2) the requirement's use is well suited to the site. Only the substantive requirements (e.g., use of control/containment equipment, compliance with numerical standards) associated with ARARs apply to CERCLA onsite activities. ARARs associated with administrative requirements, such as permitting, are not applicable to CERCLA onsite activities (CERCLA, Section 121[e][1]). In general, this CERCLA permitting exemption will be extended to all remedial and corrective action activities conducted at the 200-CS-1 OU, with the exception of the *Resource Conservation and Recovery Act of 1976* (RCRA) units, which will be incorporated into WA7890008967, *Hanford Facility RCRA Permit*.

TBC information is nonpromulgated advisories or guidance issued by Federal or state governments that is not legally binding and does not have the status of potential ARARs. In some circumstances, TBCs will be considered along with ARARs in determining the remedial action necessary for protection of human health and the environment. The TBCs complement the ARARs in determining protectiveness at a site or implementation of certain actions. For example, because soil cleanup standards do not exist for all contaminants, health advisories, which would be TBCs, may be helpful in defining appropriate remedial action goals.

### **B1.1 WAIVERS FROM APPLICABLE OR RELEVANT AND APPROPRIATE REQUIREMENTS**

The U.S. Environmental Protection Agency (EPA) may waive ARARs and select a remedial action that does not attain the same level of site cleanup as that identified by the ARARs. Section 121 of the *Superfund Amendments and Reauthorization Act of 1986* identifies six circumstances in which the EPA may waive ARARs for onsite remedial actions. The six circumstances are as follows:

- The remedial action selected is only a part of a total remedial action (such as an interim action), and the final remedy will attain the ARAR upon its completion
- Compliance with the ARAR will result in a greater risk to human health and the environment than alternative options
- Compliance with the ARAR is technically impracticable from an engineering perspective

- An alternative remedial action will attain an equivalent standard of performance through the use of another method or approach
- The ARAR is a state requirement that the state has not consistently applied (or demonstrated the intent to apply consistently) in similar circumstances
- In the case of Section 104 (Superfund-financed remedial actions), compliance with the ARAR will not provide a balance between protecting human health and the environment and the availability of Superfund money for response at other facilities.

## **B1.2 POTENTIAL ARARS APPLICABLE TO REMEDIAL ACTIONS FOR WASTE SITES IN THE 200-CS-1 OPERABLE UNITS**

Potential Federal and state ARARs are presented in Tables B-1 and B-2, respectively. The chemical-specific ARARs likely to be most relevant to remediation of the 200-CS-1 OU are elements of the Washington State regulations that implement *Washington Administrative Code* (WAC) 173-340, "Model Toxics Control Act -- Cleanup," specifically associated with developing risk-based concentrations for cleanup (WAC 173-340-745, "Soil Cleanup Standards for Industrial Properties"). The requirements of WAC 173-340-745 risk-based concentrations help establish soil cleanup standards for nonradioactive and radioactive contaminants at waste sites. The several Federal and state air emission standards are likely to be important in identifying air emission limits and control requirements for any remedial actions that produce air emissions. RCRA land-disposal restrictions will be important standards during the management of wastes generated during remedial actions.

No location-specific ARARs have been identified for the waste sites considered in this feasibility study.

Action-specific ARARs that could be pertinent to remediation are state solid and dangerous waste regulations (for management of characterization and remediation wastes and performance standards for waste left in place), *Atomic Energy Act of 1954* regulations (for performance standards for radioactive waste sites), and Federal and state regulations related to air emissions.

## **B2.0 REFERENCES**

40 CFR 61, "National Emission Standards for Hazardous Air Pollutants," Title 40, *Code of Federal Regulations*, Part 61, as amended.

40 CFR 61, Subpart H, "National Emission Standards for Emissions of Radionuclides Other than Radon from Department of Energy Facilities," Title 40, *Code of Federal Regulations*, Part 61, as amended.

40 CFR 141, "National Primary Drinking Water Regulations," Title 40, *Code of Federal Regulations*, Part 141, as amended.

40 CFR 268, "Land Disposal Restrictions," Title 40, *Code of Federal Regulations*, Part 268, as amended.

40 CFR 761, "Polychlorinated Biphenyls (PCBs) Manufacturing, Processing, Distribution in Commerce, and Use Prohibitions," Title 40, *Code of Federal Regulations*, Part 761, as amended.

*Atomic Energy Act of 1954*, 42 USC 2011, et seq.

*Comprehensive Environmental Response, Compensation, and Liability Act of 1980*, 42 USC 9601, et seq.

EPA/540/G-89/004, 1988, *Guidance for Conducting Remedial Investigations and Feasibility Studies under CERCLA, (Interim Final)*, OSWER 9355.3-01, Office of Solid Waste and Emergency Response, U.S. Environmental Protection Agency, Washington, D.C.

EPA/540/G-89/006, 1988, *CERCLA Compliance with Other Laws Manual: Interim Final*, U.S. Environmental Protection Agency, Washington, D.C.

*Resource Conservation and Recovery Act of 1976*, 42 USC 6901, et seq.

*Superfund Amendments and Reauthorization Act of 1986*, 42 USC 103, et seq.

WA7890008967, 1994, *Hanford Facility RCRA Permit*, Washington State Department of Ecology, Olympia, Washington.

WAC 173-160, "Minimum Standards for Construction and Maintenance of Wells," *Washington Administrative Code*, as amended, Washington State Department of Ecology, Olympia, Washington.

WAC 173-303, "Dangerous Waste Regulations," *Washington Administrative Code*, as amended, Washington State Department of Ecology, Olympia, Washington.

WAC 173-304, "Minimum Functional Standards for Solid Waste Handling," *Washington Administrative Code*, as amended, Washington State Department of Ecology, Olympia, Washington.

WAC 173-340, "Model Toxics Control Act -- Cleanup," *Washington Administrative Code*, as amended, Washington State Department of Ecology, Olympia, Washington.

WAC 173-350, "Solid Waste Handling Standards," *Washington Administrative Code*, as amended, Washington State Department of Ecology, Olympia, Washington.

WAC 173-400, "General Regulations for Air Pollution Sources," *Washington Administrative Code*, as amended, Washington State Department of Ecology, Olympia, Washington.

WAC 173-480, "Ambient Air Quality Standards and Emission Limits for Radionuclides," *Washington Administrative Code*, as amended, Washington State Department of Ecology, Olympia, Washington.

Table B-1. Identification of Potential Federal Applicable or Relevant and Appropriate Requirements and to be Considered for the Remedial Action Sites. (2 Pages)

ARAR Citation	ARAR or TBC	Requirement	Rationale for Use
<b>"National Primary Drinking Water Regulations," 40 CFR 141</b>			
"Maximum Contaminant Levels for Organic Contaminants," 40 CFR 141.61	ARAR	Establishes MCLs that are drinking water criteria designed to protect human health from the potential adverse effects of organic contaminants in drinking water.	The groundwater in the 200-CS-1 OU is not currently used for drinking water. However, 200 Area groundwater is hydraulically connected to the Columbia River (which is used for drinking water). Remedial alternatives must ensure that migration of contaminants from the waste sites do not cause degradation at the point of compliance; therefore, the substantive requirements in 40 CFR 141.61 for organic constituents are relevant and appropriate.
"Maximum Contaminant Levels for Inorganic Contaminants," 40 CFR 141.62	ARAR	Establishes MCLs that are drinking water criteria designed to protect human health from the potential adverse effects of inorganic contaminants in drinking water.	The groundwater in the 200-CS-1 OU is not currently used for drinking water. However, 200 Area groundwater is hydraulically connected to the Columbia River (which is used for drinking water). Remedial alternatives must ensure that migration of contaminants from the waste sites do not cause degradation at the point of compliance; therefore, the substantive requirements in 40 CFR 141.62 for inorganic constituents are relevant and appropriate.
"Maximum Contaminant Levels for Radionuclides," 40 CFR 141.66	ARAR	Establishes MCLs that are drinking water criteria designed to protect human health from the potential adverse effects of radionuclides in drinking water.	The groundwater in the 200-CS-1 OU is not currently used for drinking water. However, 200 Area groundwater is hydraulically connected to the Columbia River (which is used for drinking water). Remedial alternatives must ensure that migration of contaminants from the waste sites do not cause degradation at the point of compliance; therefore, the substantive requirements in 40 CFR 141.66 for radionuclides are relevant and appropriate.
<b>"Polychlorinated Biphenyls (PCBs) Manufacturing, Processing, Distribution in Commerce, and Use Prohibitions," 40 CFR 761</b>			
"Applicability," Specific Subsections: 40 CFR 761.50(b)(1) 40 CFR 761.50(b)(2) 40 CFR 761.50(b)(3) 40 CFR 761.50(b)(4) 40 CFR 761.50(b)(7) 40 CFR 761.50(c)	ARAR	These regulations establish standards for the storage and disposal of PCB wastes.	The substantive requirements of these regulations are potentially applicable or relevant and appropriate to the storage and disposal of PCB liquids, items, remediation waste, and bulk product waste at $\geq 50$ p/m. The specific subsections identified from 40 CFR 761.50(b) reference the specific sections for the management of PCB waste type. The disposal requirements for radioactive PCB waste are addressed in 40 CFR 761.50(b)(7).

Table B-1. Identification of Potential Federal Applicable or Relevant and Appropriate Requirements and to be Considered for the Remedial Action Sites. (2 Pages)

ARAR Citation	ARAR or TBC	Requirement	Rationale for Use
<b>"National Emission Standards for Hazardous Air Pollutants," 40 CFR 61</b>			
"Standard," 40 CFR 61.92	ARAR	Requires that emissions of radionuclides to the ambient air from U.S. Department of Energy facilities shall not exceed amounts that would cause any member of the public to receive in any year an effective dose equivalent of 10 mrem/yr.	The substantive requirements of this standard are potentially applicable to remedial action activities in the 200-CS-1 OU, such as excavation of contaminated soils and the operation of air quality management equipment in support of remediation activities, which may result in the release of radioactive particulates to unrestricted areas. As a result, requirements limiting emissions potentially apply. This is a risk-based standard for protecting human health and the environment.
"Emission Monitoring and Test Procedures," 40 CFR 61.93	ARAR	Establishes the methods for monitoring emissions rates from existing point sources.	The substantive requirements of this standard are potentially applicable because emissions of radionuclides to the ambient air may result from remediation activities performed in the 200-CS-1 OU, or from related use of temporary sources such as air quality management equipment in support of remediation activities.
"Archaeological and Historic Preservation Act of 1976" 16 USC 469aa-mm	ARAR	Requires that remedial actions at 200-CS-1 OU waste sites do not cause the loss of any archaeological or historic data. This act mandates preservation of the data and does not require protection of the actual waste site or facility.	Archeological and historic sites have been identified within the 200 Areas, therefore the substantive requirements of this act are applicable to actions that might disturb these sites.
"National Historic Preservation Act of 1966," 16 USC 470, Section 106	ARAR	Requires federal agencies to consider the impacts of their undertaking on cultural properties through identification, evaluation and mitigation processes, and consultation with interested parties.	Cultural and historic sites have been identified within the 200 Areas, and therefore the substantive requirements of this act are applicable to actions that might disturb these types of sites.
"Native American Graves Protection and Repatriation Act," 25 USC 3001, et seq.	ARAR	Establishes federal agency responsibility for discovery of human remains, associated and unassociated funerary objects, sacred objects and items of cultural patrimony.	Substantive requirements of this act are applicable if remains and sacred objects are found during remediation and will require Native American Tribal consultation in the event of discovery.
"Endangered Species Act of 1973" 16 USC 1531 et seq, subsection 16 USC 1536(c)	ARAR	Prohibits actions by federal agencies that are likely to jeopardize the continued existence of listed species or result in the destruction or adverse modification or critical habitat. If remediation is within critical habitat or buffer zones surrounding threatened or endangered species, mitigation measures must be taken to protect the resource.	Substantive requirements of this act are applicable if threatened or endangered species are identified in areas where remedial actions will occur.

Table B-1. Identification of Potential Federal Applicable or Relevant and Appropriate Requirements and to be Considered for the Remedial Action Sites. (2 Pages)

ARAR Citation	ARAR or TBC	Requirement	Rationale for Use
Regulations pursuant to the <i>Resource Conservation and Recovery Act of 1976</i> and implemented through WAC 173-303, "Dangerous Waste Regulations" (see Table B-2).			

40 CFR 61, "National Emission Standards for Hazardous Air Pollutants."

40 CFR 141, "National Primary Drinking Water Regulations."

40 CFR 761, "Polychlorinated Biphenyls (PCBs) Manufacturing, Processing, Distribution in Commerce, and Use Prohibitions."

*Resource Conservation and Recovery Act of 1976*, 42 USC 6901, et seq.

ARAR = applicable or relevant and appropriate requirement.

CFR = *Code of Federal Regulations*.

MCL = maximum contaminant level.

OU = operable unit.

p/m = parts per million.

PCB = polychlorinated biphenyl.

TBC = to be considered.

WAC = *Washington Administrative Code*.

Table B-2. Identification of Potential State Applicable and Relevant or Appropriate Requirements and to be Considered for the Remedial Action Sites. (6 Pages)

ARAR Citation	ARAR or TBC	Requirement	Rationale for Use
<b>"Dangerous Waste Regulations," WAC 173-303</b>			
"Identifying Solid Waste," WAC 173-303-016	ARAR	Identifies those materials that are and are not solid wastes.	Substantive requirements of these regulations are potentially applicable because these define how to determine which materials are subject to the designation regulations. Specifically, materials that are generated for removal from the CERCLA site during the remedial action would be subject to the procedures for identification of solid waste to ensure proper management.
"Recycling Processes Involving Solid Waste," WAC 173-303-017	ARAR	Identifies materials that are and are not solid wastes when recycled.	Substantive requirements of these regulations are potentially applicable because these define how to determine which materials are subject to the designation regulations. Specifically, materials that are generated for removal from the CERCLA site during the remedial action would be subject to the procedures for identification of solid waste to ensure proper management.
"Designation of Dangerous Waste," WAC 173-303-070	ARAR	Establishes the method for determining whether a solid waste is, or is not, a dangerous waste or an extremely hazardous waste.	Substantive requirements of these regulations are potentially applicable to materials encountered during the remedial action. Specifically, solid waste that is generated for removal from the CERCLA site during this remedial action would be subject to the dangerous waste designation procedures to ensure proper management.
"Excluded Categories of Waste," WAC 173-303-071	ARAR	Describes those categories of wastes that are excluded from the requirements of WAC 173-303 (excluding WAC 173-303-050).	The conditions of this requirement are applicable to remedial actions in the 200-CS-1 OU should wastes identified in WAC 173-303-071 be encountered.
"Conditional Exclusion of Special Wastes," WAC 173-303-073	ARAR	Establishes the conditional exclusion and the management requirements of special wastes, as defined in WAC 173-303-040.	Substantive requirements of these regulations are potentially applicable to materials encountered during the remedial action. Specifically, the substantive standards for management of special waste are applicable to the interim management of certain waste that will be generated during the remedial action.

Table B-2. Identification of Potential State Applicable and Relevant or Appropriate Requirements and to be Considered for the Remedial Action Sites. (6 Pages)

ARAR Citation	ARAR or TBC	Requirement	Rationale for Use
"Requirements for Universal Waste," WAC 173-303-077	ARAR	Identifies those wastes exempted from regulation under WAC 173-303-140 and WAC 173-303-170 through 173-303-9907 (excluding WAC 173-303-960). These wastes are subject to regulation under WAC 173-303-573.	Substantive requirements of these regulations are potentially applicable to materials encountered during the remedial action. Specifically, the substantive standards for management of universal waste are applicable to the interim management of certain waste that will be generated during the remedial action.
"Recycled, Reclaimed, and Recovered Wastes," WAC 173-303-120 Specific Subsections: WAC 173-303-120(3) WAC 173-303-120(5)	ARAR	These regulations define the requirements for the recycling of materials that are solid and dangerous waste. Specifically, WAC 173-303-120(3) provides for the management of certain recyclable materials, including spent refrigerants, antifreeze, and lead-acid batteries.  WAC 173-303-120(5) provides for the recycling of used oil.	Substantive requirements of these regulations are potentially applicable to certain materials that might be encountered during the remedial action. Recyclable materials that are exempt from regulation as dangerous waste and that are not otherwise subject to CERCLA as hazardous substances can be recycled and/or conditionally excluded from certain dangerous waste requirements.
"Land Disposal Restrictions," WAC 173-303-140(4)	ARAR	This regulation establishes state standards for land disposal of dangerous waste and incorporates by reference, Federal land disposal restrictions of 40 CFR 268 that are applicable to solid waste that designates as dangerous or mixed waste in accordance with WAC 173-303-070(3).	The substantive requirements of this regulation are potentially applicable to materials encountered during the remedial action. Specifically, dangerous/mixed waste that is generated and removed from the CERCLA site during the remedial action for offsite (as defined by CERCLA) land disposal would be subject to the identification of applicable land disposal restrictions at the point of generation of the waste. The actual offsite treatment of such waste would not be ARAR to this remedial action, but would instead be subject to all applicable laws and regulations.
"Requirements for Generators of Dangerous Waste," WAC 173-303-170	ARAR	Establishes the requirements for dangerous waste generators.	Substantive requirements of these regulations are potentially applicable to materials encountered during the remedial action. Specifically, the substantive standards for management of dangerous/mixed waste are applicable to the interim management of certain waste that will be generated during the remedial action. For purposes of this remedial action, WAC 173-303-170(3) includes the substantive provisions of WAC 173-303-200 by reference. WAC 173-303-200 further includes certain substantive standards from WAC 173-303-630 and -640 by reference.

Table B-2. Identification of Potential State Applicable and Relevant or Appropriate Requirements and to be Considered for the Remedial Action Sites. (6 Pages)

ARAR Citation	ARAR or TBC	Requirement	Rationale for Use
"Closure and post-closure," WAC 173-303-610	ARAR	Establishes the closure performance standards for RCRA TSD units.	These requirements are applicable to the closure of RCRA TSD units in the OU, 216-A-29 Ditch, 216-B-63 Trench, 216-S-10 Ditch, and 216-S-10 Pond.
<b>"Model Toxics Control Act -- Cleanup," WAC 173-340</b>			
"Soil Cleanup Standards for Industrial Properties," WAC 173-340-745(S)(b)	ARAR	Identifies the methods used to identify risk-based concentrations and their use in the selection of a cleanup action. Cleanup and remediation levels are based on protection of human health and the environment, the location of the site, and other regulations that apply to the site. The standard specifies cleanup goals that implement the strictest Federal or state cleanup criteria.	The state-established risk-based concentrations for soils and protection of groundwater are potentially relevant and appropriate to the 200-CS-1 OU waste site remedial actions, because no Federal standard exists.
<b>"Minimum Functional Standards for Solid Waste Handling," WAC 173-304</b>			
"On-Site Containerized Storage, Collection and Transportation Standards for Solid Waste," WAC 173-304-200(2)	ARAR	Establishes the requirements for the onsite storage of solid wastes that are not radioactive or dangerous wastes.	Substantive requirements of these regulations are potentially applicable to materials encountered during the remedial action. Specifically, nondangerous, nonradioactive solid wastes (i.e., hazardous substances that are only regulated as solid waste) that will be containerized for removal from the CERCLA site would be managed on site according to the substantive requirements of this standard.
<b>"Solid Waste Handling Standards," WAC 173-350</b>			
"On-Site Storage, Collection and Transportation Standards," WAC 173-350-300	ARAR	Establishes the requirements for the temporary storage of solid waste in a container on site and the collecting and transporting of the solid waste.	The substantive requirements of this newly promulgated rule are potentially relevant and appropriate to the onsite collection and temporary storage of solid wastes at the 200-CS-1 OU remediation waste sites. Compliance with this regulation is being implemented in phases for existing facilities.

Table B-2. Identification of Potential State Applicable and Relevant or Appropriate Requirements and to be Considered for the Remedial Action Sites. (6 Pages)

ARAR Citation	ARAR or TBC	Requirement	Rationale for Use
<b>"Minimum Standards for Construction and Maintenance of Wells," WAC 173-160</b>			
WAC 173-160-161	ARAR	Identifies well planning and construction requirements.	The substantive requirements of this regulation are potentially applicable to actions that include construction of wells used for groundwater extraction, monitoring, or injection of treated groundwater or wastes. The requirements of WAC 173-160-161 through 173-160-381 (excluding 173-160-211, 173-160-251, 173-160-261, 173-160-361, 173-160-400, 173-160-420, 173-160-430, 173-160-440, 173-160-450, and 173-160-460) are applicable to groundwater well construction, monitoring, or injection of treated groundwater or wastes in the 200-CW-5, 200-CW-2, 200-CW-4, and 200-SC-1 OUs.
WAC 173-160-171	ARAR	Identifies the requirements for locating a well.	
WAC 173-160-181	ARAR	Identifies the requirements for preserving natural barriers to groundwater movement between aquifers.	
WAC 173-160-191	ARAR	Identifies the design and construction requirements for completing wells.	
WAC 173-160-201	ARAR	Identifies the casing and liner requirements for water supply wells.	
WAC 173-160-221	ARAR	Identifies the requirements for sealing materials.	
WAC 173-160-231	ARAR	Identifies the requirements for surface seals on water wells.	
WAC 173-160-241	ARAR	Identifies the requirements for formation sealing.	
WAC 173-160-271	ARAR	Identifies the special sealing standards for driven wells, jetted wells, and dewatering wells.	
WAC 173-160-281	ARAR	Identifies the construction standards for artificial gravel-packed wells.	
WAC 173-160-291	ARAR	Identifies the standards for the upper terminal of water wells.	
WAC 173-160-301	ARAR	Identifies the requirements for temporary capping.	
WAC 173-160-311	ARAR	Identifies the requirements for well tagging.	
WAC 173-160-321	ARAR	Identifies the standards for testing a well.	
WAC 173-160-331	ARAR	Identifies the method for keeping equipment and the water well free of contaminants.	
WAC 173-160-341	ARAR	Identifies the method for ensuring the quality of the well water.	
WAC 173-160-351	ARAR	Identifies the standards for the installation of a pump.	
WAC 173-160-371	ARAR	Identifies the standard for chemical conditioning.	

Table B-2. Identification of Potential State Applicable and Relevant or Appropriate Requirements and to be Considered for the Remedial Action Sites. (6 Pages)

ARAR Citation	ARAR or TBC	Requirement	Rationale for Use
WAC 173-160-381	ARAR	Identifies the standard for decommissioning a well.	
WAC 173-160-400	ARAR	Identifies the minimum standards for resource protection wells and geotechnical soil borings.	
WAC 173-160-420	ARAR	Identifies the general construction requirements for resource protection wells.	
WAC 173-160-430	ARAR	Identifies the minimum casing standards.	
WAC 173-160-440	ARAR	Identifies the equipment cleaning standards.	
WAC 173-160-450	ARAR	Identifies the well sealing requirements.	
WAC 173-160-460	ARAR	Identifies the decommissioning process for resource protection wells.	
"General Regulations for Air Pollution Sources," WAC 173-400			
"General Standards for Maximum Emissions," WAC 173-400-040	ARAR	Establishes the general emission standards for emission units. Emission standards identified in other chapters for specific emission units will take precedence over the general emission standards of this section.	The substantive requirements of this standard are potentially relevant and appropriate to remedial actions performed at the site that could result in the emission of criteria pollutants (i.e., fugitive dust). Substantive standards established for the control and prevention of air pollution under this regulation are considered to be relevant and appropriate to remedial actions that may be proposed at a site.
"Ambient Air Quality Standards and Emission Limits for Radionuclides," WAC 173-480			
"Emission Monitoring and Compliance Procedures," WAC 173-480-070	TBC	Requires that radionuclide emissions shall be determined by calculating the dose to members of the public at the point of maximum annual air concentration in an unrestricted area where any member of the public may be.	The substantive requirements of this standard are applicable to remedial actions conducted in the 200-CS-1 OU, because excavation of contaminated soil may emit radionuclides to unrestricted areas.

40 CFR 268, "Land Disposal Restrictions."

*Comprehensive Environmental Response, Compensation, and Liability Act of 1980*, 42 USC 9601, et seq.

*Resource Conservation and Recovery Act of 1976*, 42 USC 6901, et seq.

WAC 173-160, "Minimum Standards for Construction and Maintenance of Wells."

WAC 173-303, "Dangerous Waste Regulations."

WAC 173-304, "Minimum Functional Standards for Solid Waste Handling."

WAC 173-340, "Model Toxics Control Act -- Cleanup."

WAC 173-350, "Solid Waste Handling Standards."

WAC 173-400, "General Regulations for Air Pollution Sources."

WAC 173-480, "Ambient Air Quality Standards and Emission Limits for Radionuclides."

Table B-2. Identification of Potential State Applicable and Relevant or Appropriate Requirements and to be Considered for the Remedial Action Sites. (6 Pages)

ARAR Citation	ARAR or TBC	Requirement	Rationale for Use
ARAR = applicable or relevant and appropriate requirement.	OU = operable unit.	RCRA = <i>Resource Conservation and Recovery Act of 1976.</i>	TBC = to be considered.
CERCLA = <i>Comprehensive Environmental Response, Compensation, and Liability Act of 1980.</i>	WAC = <i>Washington Administrative Code.</i>		
CFR = <i>Code of Federal Regulations.</i>			

This page intentionally left blank.

1

**APPENDIX C**

2

3

**NATIVE AMERICAN EXPOSURE SCENARIO RISK ASSESSMENT**

This page intentionally left blank.

1

**CONTENTS**

2	C1.0 INTRODUCTION .....	C-1
3	C2.0 CONCEPTUAL SITE MODEL .....	C-3
4	C3.0 EXPOSURE ASSUMPTIONS, TOXICITY FACTORS, AND METHODS .....	C-4
5	C4.0 SUMMARY OF DOSE AND RISK ESTIMATES FOR NONRADIOLOGICAL	
6	AND RADIOLOGICAL CONSTITUENTS .....	C-6
7	C4.1 216-A-29 DITCH .....	C-7
8	C4.2 216-B-63 TRENCH .....	C-8
9	C4.3 216-S-10 DITCH .....	C-8
10	C4.4 216-S-10 POND .....	C-9
11	C5.0 UNCERTAINTY ANALYSIS .....	C-9
12	C6.0 REFERENCES .....	C-11

13

14

**FIGURES**

15	Figure C-1. Game-Based Native American Traditional Subsistence Lifeways Conceptual	
16	Site Model and Garden .....	C-13
17	Figure C-2. Model for Estimating Chemical Concentrations in Breast Milk .....	C-14

18

19

**TABLES**

20	Table C-1. Native American Exposure Scenario, Traditional Subsistence Lifeways	
21	(Harris 2004; Harris and Harper 1997). .....	C-15
22	Table C-2. Native American, Traditional Subsistence Lifeways Scenario	
23	Chemical-Specific Input Parameters. ....	C-16
24	Table C-3. Radionuclide Screening Result and 95%UCL Concentrations.....	C-17
25	Table C-4. Native American, Traditional Subsistence Lifeways Scenario	
26	Chemical-Specific Toxicity Factors. ....	C-19
27	Table C-5. 216-A-29 Ditch Native American Subsistence Lifeways Radiological Dose	
28	and Risk. ....	C-20

DOE/RL-2005-63 DRAFT A

1 Table C-6. 216-A-29 Ditch Native American Subsistence Lifeways Nonradiological  
2 Risk and Hazard Index. .... C-21

3 Table C-7. 216-B-63 Trench Native American Subsistence Lifeways Radiological Dose  
4 and Risk. .... C-22

5 Table C-8. 216-S-10 Ditch Native American Subsistence Lifeways Radiological Dose  
6 and Risk. .... C-22

7 Table C-9. 216-S-10 Ditch, Native American Subsistence Lifeways Nonradiological Risk  
8 and Hazard Index. .... C-23

9 Table C-10. 216-S-10 Pond Native American Subsistence Lifeways Radiological Dose  
10 and Risk. .... C-24

## APPENDIX C

## NATIVE AMERICAN EXPOSURE SCENARIO RISK ASSESSMENT

## C1.0 INTRODUCTION

This appendix provides the results of the hypothetical Native American Scenario Risk Assessment (NARA) for four representative sites in the 200-CS-1 Area: the 216-A-29 Ditch, 216-B-63 Trench, 216-S-10 Ditch, and 216-S-10 Pond. The human health risk assessment described in this appendix addresses pathways associated chemical and radionuclide contamination found within the shallow zone soil (0 to 4.6 m [0 to 15 ft] below ground surface [bgs]).

This risk assessment was performed to evaluate the potential for risk to human health under conditions described in Harris 2004, "Exposure Scenario for CTUIR Traditional Subsistence Lifeways." The results are used, in part, to help assess whether remedial action may need further evaluation and to focus the feasibility study (FS). The assessment draws from information presented previously in the FS, particularly Chapter 2.0, where a summary of the remedial investigation baseline risk assessment and a description of the extended risk assessment are found.

**Introduction to the Hypothetical Native American Traditional Subsistence Lifeways Scenario**

The U.S. Department of Energy (DOE) remains committed to considering Tribal exposure scenarios for conducting the risk assessments necessary to evaluate whether Hanford Site cleanup alternatives are protective of human health and the environment (Roberson 2002, "Hazard Categorization of EM Inactive Waste Sites as Less Than Hazard Category 3"). The DOE, U.S. Environmental Protection Agency (EPA), and Washington State Department of Ecology (Tri-Parties) have interacted with the stakeholder Tribes over the past several years to obtain their input on developing a Native American exposure scenario or scenarios, including key parameters for the Central Plateau risk assessment models.

The Tribes were involved in the risk assessment framework workshops during the summer of 2002, and in October 2002, they were asked to provide written suggestions on specific risk assessment parameters (exposure assumptions) for Tribal-use scenarios (DOE-RCA-2002-0584, 2002a, Letter [no title; topic: Tribal Input on the *Comprehensive Environmental Response, Compensation, and Liability Act of 1980* (CERCLA) Risk Assessment], to Richard Gay, Confederated Tribes of the Umatilla Indian Reservation, from the Tri-Party Agreement signatories; DOE-RCA-2002-0584, 2002b, Letter [no title; topic: Tribal Input on CERCLA Risk Assessment], to Russell Jim, Confederated Tribes and Bands of the Yakama Nation, from the Tri-Party Agreement signatories; DOE-RCA-2002-0584, 2002c, Letter [no title; topic: Tribal Input on CERCLA Risk Assessment], to Patrick Sobotta, Nez Perce Tribe, from the Tri-Party Agreement signatories). This request culminated in a workshop in December 2002 that included the Tri-Parties and representatives from the Confederated Tribes of the Umatilla Indian

1 Reservation, the Confederated Tribes and Bands of the Yakama Nation, and the Nez Perce Tribe.  
2 The Yakamas and the Nez Perce participated in the workshop but believed they needed  
3 additional time to provide input. The Umatillas asked that the information from DOE/RL-91-45,  
4 *Hanford Site Baseline Risk Assessment Methodology*, and Harris and Harper 1997, "A Native  
5 American Exposure Scenario," be used to calculate risk estimates for a Native American  
6 subsistence scenario. The information from this study was used to estimate potential risks to a  
7 Native American from radiological constituents.

8 The Native American subsistence scenario proposed in Harris and Harper (1997) represents a  
9 "typical" Native American culture that incorporates the use of the entire Columbia Basin for  
10 food, water, and shelter.

11 The Harris and Harper 1997 scenario has been revised, based on additional work by  
12 Harris (2004), and it is now referred to as the Native American Traditional Subsistence Lifeways  
13 scenario. Harris' revision has resulted in a more concisely structured age stratification including  
14 description of infant (ages 0 to 2 years), child (ages 2 to 6 years), youth (ages 7 to 16), adult  
15 worker (ages 17 to 55 years), and elder (ages 56 to 70 years) activities. Harris (2004) also  
16 provides updated consumption exposure factors that emerge from distinguishing between a  
17 fish-focused diet (applicable for Hanford Reach areas near the Columbia River) and a  
18 game-focused diet (applicable to locations that do not rely on consumption from the river). In  
19 this risk assessment, the game-focused diet is used because the Central Plateau, where the  
20 200-CS-1 Operable Unit (OU) sites are located, is in the dry upland land portion of the Hanford  
21 Site; nearly 5 miles from the Columbia River. Additionally, as discussed later, the conceptual  
22 site model (CSM) indicates that constituents in the soils at the 200-CS-1 OU sites will not affect  
23 the river.

24 This hypothetical scenario was evaluated to provide a basis of comparison (assuming  
25 unrestricted land use) to the site-specific scenario (e.g., industrial) and the hypothetical intruder  
26 scenario previously described in Chapter 2.0 of the FS. Considerable uncertainty is associated  
27 with applying the Native American Traditional Subsistence Lifeways exposure assumptions to  
28 each waste site, because applying these assumptions likely overestimates the dose, risk, and  
29 hazard index associated with each waste site.

### 30 **Risk Assessment Organization**

31 This Native American Traditional Subsistence Lifeways risk assessment consists of the  
32 following components:

- 33     • An **Introduction** (this section) that discusses the NARA framework and orients the  
34     reader to the report.
- 35     • Development of the **CSM**, which identifies the pathways by which human exposures  
36     could occur is discussed in Chapter C2.0.
- 37     • **Exposure factors, toxicity data and other method issues** including the contact rate,  
38     frequency, and duration factors used to quantify exposure are presented in Chapter C3.0.

- 1 • Risk assessments for each Representative Site are presented in Chapters C4.0  
2 through C4.4.
- 3 • Risk assessment uncertainties are discussed in Chapter C5.0.
- 4 • A listing of references used in Appendix C is provided in Chapter C6.0.

## 5 C2.0 CONCEPTUAL SITE MODEL

6 The CSM, illustrated in Figure C-1, identifies the means by which receptors on the 200-CS-1 OU  
7 waste sites could be exposed to chemicals in environmental media. The CSM addresses  
8 exposures that could result under from potential future Traditional Subsistence Lifeways uses for  
9 the sites and the surrounding areas. The CSM provides a current understanding of the sources of  
10 contamination, physical setting, and current and future land use, and identifies potentially  
11 complete human exposure pathways for the study areas. Information generated during the RI/FS  
12 process has been incorporated into this CSM to help identify potential exposure scenarios. Key  
13 features of the CSM include the following:

- 14 • Soil contamination existing within the 0 to 4.6 m (0 to 15 ft), resulting from surface  
15 deposition is the principal source of contamination for all pathways.
- 16 • The deep-zone groundwater is not accessible to Tribal members. This is due to its  
17 significant depth, typically about 270 ft, beneath the surface. This fact eliminates  
18 domestic use of groundwater and the application of contaminated groundwater for sweat  
19 lodge use of as potential exposure pathways.
- 20 • The CSM illustrates that, conceptually, the deep groundwater could discharge to the  
21 Columbia River. However, the river is on-the-order-of 5 miles from the Central Plateau  
22 where the four sites are located. This gives rise to two important risk assessment  
23 findings.
  - 24 1. The pathway from soils at the sites to fish in the Columbia River is, for practical  
25 purposes incomplete. Migration of soil contaminants from the vadose zone to the  
26 deep groundwater has been largely been discounted as a viable transport pathway  
27 in the RI/FS. Moreover, even if migration of soil contaminants from the vadose  
28 zone to the deep groundwater were a viable pathway, contaminant concentrations  
29 in the surface water would be so low that they would not accumulate in the edible  
30 tissues of fish in the River. This is because of significant reduction in  
31 concentration that would come about from initially mixing in the deep  
32 groundwater, followed by additional concentration reduction from saturated zone  
33 advective migration over 5 miles, and further mixing upon discharge into the  
34 Columbia River.

1           2. Future Tribal members residing on the Central Plateau are not likely to obtain a  
2           principal portion of their protein intake from consumption of fish obtained from  
3           the Columbia River.

- 4           • Future Tribal members participate in a subsistence lifestyle described by Harris and  
5           Harper (1997) and Harris (2004) as “hunting, fishing, and gathering activities.” Tribal  
6           member consume (1) plants that grow in the shallow soils and (2) local game that also  
7           consume plants growing in the soil as which also consume contaminated soils while  
8           grazing. The Traditional Subsistence Lifeways scenario is not an agricultural  
9           arrangement like the Intruder scenario discussed in Chapter 2.0 of the FS. The two  
10          scenarios are similar in that they both employ food chain pathways as the important  
11          exposure features. However, the Traditional Subsistence Lifeways scenario is similar to  
12          a “living of the land” situation whereby significant portions of the Tribal member’s diet  
13          are fulfilled by consumption of native plants and game.

14       Readers will note that Figure C-1 is a modification and expansion of Figure 2-23, Intruder  
15       Scenario Conceptual Site Model and Garden, in the FS. The significant differences between two  
16       CSMs are as follows. First, there is no garden employing drill cuttings mixed with clean soils  
17       for plant anchorage in the Traditional Subsistence Lifeways scenario. Rather, native plants grow  
18       in the unadulterated, though contaminated soils. Second, the Traditional Subsistence Lifeways  
19       scenario includes a simplified game-based food chain model incorporating consumption of  
20       native animals that graze and forage in the affected soils. The Traditional Subsistence Lifeways  
21       scenario also includes an infant consumption of breast milk as described by Harris and  
22       Harper (1997) and Harris (2004).

23       Complete pathways, those with an X in the Potential Receptor box, will be evaluated.

## 24           **C3.0 EXPOSURE ASSUMPTIONS, TOXICITY FACTORS, AND METHODS**

### 25           **Scenario Overview**

26       Exposure assumptions for the Traditional Subsistence Lifeways scenario were obtained from  
27       Harris and Harper (1997) and modified to conform to Harris (2004). Harris and Harper (1997)  
28       suggested that a traditional Tribal member would lead a moderately active lifestyle, spending  
29       180 days/yr conducting various subsistence activities (e.g., hunting, fishing, and gathering), and  
30       spending the full year consuming materials obtained through these activities. For the purposes of  
31       this assessment, it is assumed that a Tribal member spends 365 days/yr near the representative  
32       sites (Harris 2004). This conservative simplification will tend to overstate the risk. However,  
33       the assumption parallels the intent of EPA guidance to identify reasonable maximum exposure  
34       conditions to provide an upper bound hazard assessment (EPA 1990).

1 The scenario assumes that a Tribal member is residing within the boundaries of the specific  
2 200-CS-1 OU site and he/she obtains all of his/her daily caloric need from consuming plant  
3 intake and game consumption from local plants and animals. Key features of this scenario  
4 include the following:

- 5 • Direct contact outdoors with dust that originated as contaminated soils, including  
6 incidental ingestion, inhalation, and dermal contact from day-to-day living, including  
7 hunting and foraging
- 8 • Secondary contact indoors with dust that originated as soils, including additional  
9 incidental ingestion, inhalation, and dermal contact
- 10 • Consumption of vegetables and fruits that grow in the contaminated soils
- 11 • Consumption of game that grazes and feeds on vegetation that grows in the contaminated  
12 soils
- 13 • Irradiation from radionuclides in the soil
- 14 • Exposure occurs 365 days/yr for 70 years.

15 **Additional Exposure Conditions**

16 For purposes of evaluating the impacts of the intruder scenario, it is assumed that after 150 years,  
17 Tribal members could obtain access to the area. The scenario assumes no significant attenuation  
18 of nonradionuclides; however, natural decay of radionuclides is assumed to occur over the  
19 150-year period. No attenuation of decay is assumed for the nonradionuclide contaminants of  
20 potential concern (COPC).

21 The scenario is intentionally conservative and may not actually be plausible. For example, it  
22 may not be possible for the lands in the Central Plateau to produce and sustain sufficient native  
23 fruits and vegetables, and game to support 2500 per day calorie adult specified by Harris (2004).

24 Exposure factors used to characterize the scenario are presented in Table C-1. As indicated, with  
25 one exception (infant exposure to milk), Tribal member exposure is modeled as a hybrid of a  
26 small child-adult receptor, occasionally referred to as the child-to-adult receptor. As indicated in  
27 Table C-1, exposure factors were taken directly from Harris (2004) and Harris and  
28 Harper (2004). Age durations for the different segments of life stages were taken from  
29 Harris (2004). These were augmented with typical bodyweight values from  
30 EPA/600/P-95/002B, *Exposure Factor Handbook, Volume I, General Factors*, to arrive at the  
31 Age/Body Weight Weighted Average exposure factors.

32 In addition to the human exposure factors, several chemical-specific variables are necessary to  
33 compute exposures; they are shown in Table C-2.

## 1 Contaminants of Potential Concern and Exposure Point Concentrations

2 Nonradionuclide COPCs were identified as those constituents that were assessed in the intruder  
3 risk assessment(s) found in Chapter 2.0 of the FS. Readers will recall that COPCs for the  
4 intruder risk assessment used background considerations and conservative residential exposure  
5 values for screening.

6 To focus the radiological assessment on the important radionuclides, a screening step, designed  
7 to identify the radionuclides posing the greatest dose potential, was used. The screening step  
8 used maximum concentrations from the top 0 to 15 ft soils interval from each site as inputs into  
9 the RESidual RADioactivity dose model (RESRAD). The dose output was viewed for the  
10 150-year interval. Radionuclides that contributed less than 1 percent to the total dose were  
11 excluded from further analysis. The screening results are presented in Table C-3. For those  
12 radionuclides that were retained, 95th upper confidence level (95%UCL) exposure point  
13 concentrations (EPC) were computed using EPA's PROUCL statistical program in accordance  
14 with EPA guidance (EPA 2002, *Calculating Upper Confidence Limits for Exposure Point*  
15 *Concentrations at Hazardous Waste Sites*, OSWER 9285.6-10). Additional discussion of the  
16 method for computing 95%UCL concentrations can be found in Chapter 2.0 of the FS.

17 Toxicity information (cancer slope factors and reference doses) tabulated in Table C-4 were  
18 obtained from the Cleanup Levels and Risk Calculations (CLARC) Web site (Ecology 2005,  
19 *Cleanup Levels and Risk Calculations (CLARC) Database*,  
20 <https://fortress.wa.gov/ecy/clarc/CLARCHome.aspx> ). As indicated in Table C-4, the  
21 provisional chronic reference dose (RfD) for sulfate was developed in Chapter 2.0 of the FS.

22 All radiological COPCs were evaluated under the hypothetical Traditional Subsistence Lifeways  
23 exposure scenario using RESRAD version 6.3 (ANL 2004, *RESRAD for Windows*).  
24 Nonradiological COPCs were evaluated using a simplified exposure paradigm patterned after  
25 EPA/540/1-89/002, *Risk Assessment Guidance for Superfund (RAGS), Volume I -- Human*  
26 *Health Evaluation Manual, (Part A) Interim Final*, OSWER 9285.7-01A and  
27 EPA/530-D-98-001A, *Human Health Risk Assessment Protocol for Hazardous Waste*  
28 *Combustion Facilities*. All scenarios were evaluated assuming the absence of clean cover and a  
29 contaminated zone ranging from 0 m to 4.6 m (0 to 15 ft).

## 30 C4.0 SUMMARY OF DOSE AND RISK ESTIMATES FOR 31 NONRADIOLOGICAL AND RADIOLOGICAL CONSTITUENTS

32 Tables C-5 through C-10 summarize the dose and risk estimates for the Native American  
33 Traditional Lifeways Subsistence scenario for the four 200-CS-1 OU representative waste sites.

1 For comparison, risk and dose estimates are discussed relative to the following exposure times,  
 2 which are based on the results of risk framework workshops as documented in the Tri-Parties'  
 3 response to the Hanford Advisory Board (Klein et al. 2002, "Consensus Advice #132: Exposure  
 4 Scenarios Task Force on the 200 Area"), as amended.

- 5 • 50 years is the estimated time that the DOE will have an onsite presence.
- 6 • 150 years is the estimated time that institution controls are assumed effective.
- 7 • Dose estimates are provided for the exposure time when the target dose limit of  
 8 15 mrem/yr is achieved.<sup>1</sup>
- 9 • Excess lifetime cancer risk (ELCR) is compared to the 1E-6 to 1E-4 risk management  
 10 range identified in the NCP (EPA 1990).
- 11 • Hazard Indexes (HI) are compared to the unity benchmark, 1.0, also identified in the  
 12 NCP (1990).

13 The nonradiological risk assessment assumes that site conditions are at steady state and that there  
 14 is no attenuation or decay of COPC concentrations. In essence, the nonradiological is equivalent  
 15 to a time interval "0" years assessment.

#### 16 C4.1 216-A-29 DITCH

17 As shown in Table C-5, the maximum estimated total Tribal member radiological dose at the  
 18 216-A-29 Ditch is 225 mrem/yr and the maximum ELCR is 3E-3 at year 0 (i.e., 2005). This  
 19 dose exceeds the 15 mrem/y target and the ELCR under this exposure scenario is above the  
 20 target 1E-6 to 1E-4 risk management range at all simulation times. The primary contributors to  
 21 total dose and risk are Cs-137 and Pu-239; the chief pathways are plant consumption, the ground,  
 22 and the soil.

23 Inspection of Table C-6 indicates that the maximum nonradiological ELCR for the child to adult  
 24 Tribal member is 1E-1; the maximum hazard quotient (HQ) is 1E4. The ELCR exceeds 1E-6 to  
 25 1E-4 risk management range. Additionally, the HQ is also well above the benchmark HQ of 1.0.  
 26 The polycyclic aromatic hydrocarbons (PAH) benzo(a)anthracene and chrysene are the major  
 27 ELCR contributors; the HQ is dominated by Aroclor 1254. Consumption of game is the  
 28 dominant pathway for exposure to nonradionuclide constituents.

29 Table C-6 also indicates that the maximum nonradiological ELCR for the infant breast milk  
 30 consumption 8E-2 and the maximum HQ is 3E8. The ELCR exceeds 1E-6 to 1E-4 risk range  
 31 management range and the HQ is well above the benchmark HQ of 1.0. Once again,

---

<sup>1</sup> For the purposes of this risk assessment, the radiation dose limit is 15 mrem/yr (EPA/540/R-99/006, *Radiation Risk Assessment At CERCLA Sites: Q & A*, Directive 9200.4-31P). This dose limit was developed for members of the public who are unknowingly exposed to radiation.

1 benzo(a)anthracene and chrysene are the major ELCR contributors; the HQ is dominated by  
2 Aroclor 1254. Maternal consumption of game is the dominant pathway.

3 As indicated in the note section of Table C-6, these risk and HQs are driven by isolated  
4 detections of conspicuously elevated maximum concentrations that are not representative of site  
5 conditions (discussed in the FS, Chapter 2.0). Additionally, the food chain and infant milk  
6 consumption models are conservative. Consequently, estimated ELCRs and HQs are likely to be  
7 overestimated.

#### 8 C4.2 216-B-63 TRENCH

9 Table C-7 reveals the estimated maximum total Tribal member radiological dose at the  
10 216-B-63 Trench site is 88 mrem/yr and the maximum ELCR is  $2E-3$  at year 0 (i.e., 2005). This  
11 maximum dose exceeds the 15 mrem/y target and the ELCR under this exposure scenario at this  
12 time interval is above the target  $1E-6$  to  $1E-4$  risk range. However, as the Sr-90 decays, the dose  
13 drops significantly and is below the 15 mrem/yr target at all times after year 150. Similarly, after  
14 year 150, the ELCR is  $1E-4$ , which is within the  $1E-6$  to  $1E-4$  risk management range. The  
15 primary contributors to total dose and risk are Sr-80 and Th-230. Consumption of plants is the  
16 principal exposure pathways.

17 There are no nonradiological COPCs associated with the 216-B-63 Trench site.

#### 18 C4.3 216-S-10 DITCH

19 As shown in Table C-8, the maximum estimated total Tribal member radiological dose at the  
20 216-S-10 Ditch is 14 mrem/yr and the maximum ELCR is  $3E-4$  at year 0 (i.e., 2005). This  
21 maximum dose does not exceed the 15 mrem/y target; however, the ELCR under this exposure  
22 scenario is just above the target  $1E-6$  to  $1E-4$  risk range management range. Notably, as the  
23 Cs-137 decays, by simulation year 50, the ELCR comes down to  $1E-4$  and it continues to  
24 diminish to  $3E-6$  by the year 1000. Thus, after year 50, the ELCR is within the  $1E-6$  to  $1E-4$  risk  
25 management range. The primary contributors to total dose and risk are Cs-137 and Pu-239; the  
26 chief exposure pathways are the ground and plant consumption.

27 Examination of Table C-9 points out that the maximum nonradiological ELCR for the child to  
28 adult Tribal member is  $1E-1$ ; the maximum HQ is  $5E3$ . The ELCR exceeds  $1E-6$  to  $1E-4$  risk  
29 range management range and the HQ is well above the benchmark HQ of 1.0. Once again, the  
30 PAHs benzo(a)anthracene, benzo(a)pyrene, and chrysene are the major ELCR contributors and  
31 the HQ is dominated by Aroclor 1254. Consumption of game is the dominant pathway for  
32 exposure to nonradionuclide constituents.

33 Table C-9 also indicates that the maximum nonradiological ELCR for the infant breast milk  
34 consumption  $5E-1$  and the maximum HQ is  $1E8$ . The ELCR exceeds  $1E-6$  to  $1E-4$  risk range  
35 management range and the HQ is well above the benchmark HQ of 1.0. As noted above,  
36 benzo(a)anthracene, benzo(a)pyrene, and chrysene are the major ELCR contributors; the HQ is  
37 dominated by Aroclor 1254. Maternal consumption of game is the dominant pathway.

1 Once again, the estimated ELCR and HQ are likely to be overestimated. The note section of  
2 Table C-9, indicates that these risk and HQs are driven by isolated maximum detections and that  
3 the food chain and infant milk consumption models are conservative.

#### 4 **C4.4 216-S-10 POND**

5 Review of Table C-10 reveals the estimated maximum total Tribal member radiological dose at  
6 the 216-S-10-Pond site is 11 mrem/yr and the maximum ELCR is  $2E-4$  at year 0 (i.e., 2005).  
7 This maximum dose exceeds the 15 mrem/y target and the ELCR under this exposure scenario is  
8 just above the target  $1E-6$  to  $1E-4$  risk range. As the short-lived radionuclides decay, the dose  
9 and risk both drop precipitously, such that at all times after year 1, all risk are within the  $1E-6$   
10 to  $1E-4$  risk management range. The primary contributors to total dose and risk are Sr-90, C-14,  
11 Cs-137, Pu-239, and Th-230 in the later simulation years. Consumption of plants is the principal  
12 exposure pathway.

13 There are no nonradiological COPCs associated with the 216-S-10 Pond site.

#### 14 **C5.0 UNCERTAINTY ANALYSIS**

15 Several sources of uncertainty affect the overall estimates of ELCR and no carcinogenic hazards  
16 as presented in this human health risk assessment.

##### 17 **Uncertainty Associated with Sampling and Analysis**

18 Uncertainties associated with sampling and analysis include the inherent variability (standard  
19 error) in the analysis, representativeness of the samples, sampling errors, and heterogeneity of  
20 the sample matrix. While the quality assurance/quality control program used in conducting the  
21 sampling and analysis reduces errors, it cannot eliminate all errors associated with sampling and  
22 analysis.

##### 23 **Uncertainty Associated with Exposure Assessment**

24 Future soil EPCs were assumed to be equal to existing soil concentrations. This assumption does  
25 not account for fate and transport processes likely to occur in the future. For example, ignoring  
26 the fact that contaminant soil concentrations will decrease as contaminant mass migrates into the  
27 vadose zone will tend to overestimate future soil exposure risks.

28 In addition, existing soil concentrations are based on biased sampling results. These results were  
29 collected at a limited number of points on each release site, and the sampling may or may not  
30 have produced results that are truly representative of the average contaminant concentrations at  
31 each site. In the case of nonradiological COPCs, maximum concentration of PAHs and  
32 Aroclor 1254 were used, even though the bulk of the data suggests that the overall EPC would be  
33 much lower. Risk calculations may be overestimated as a result of the limited amount of  
34 sampling that was available.

1 The estimation of exposure requires many assumptions to describe potential exposure situations.  
2 Uncertainties exist regarding the likelihood of exposure, frequency of contact with contaminated  
3 media, the concentration of contaminants at exposure points, and the time period of exposure.  
4 These tend to simplify and approximate actual waste site conditions. In general, these  
5 assumptions are intended to be conservative and yield an overestimate of the true risk or hazard.

6 The RESRAD model was used to evaluate the potential for unacceptable radiation dose impacts  
7 at a given waste site. The input parameter values that were used in this model are uncertain,  
8 because the future is uncertain and modeling is based on many exposure assumptions. This  
9 parameter uncertainty may cause risk to be over- or underestimated at a given waste site. All of  
10 the uncertainties discussed in this section might cause errors in dose estimates in the same way  
11 they may cause errors in risk estimates.

12 Similarly, the model used to evaluate nonradiological COPCs is a simplified spreadsheet  
13 calculation using common algorithms from EPA/540/1-89/002 and EPA/530-D-98-001A. These  
14 screening-level equations cannot capture and express the dynamic conditions of a complicated  
15 exposure situation such as that of the Traditional Lifeways Subsistence scenario.

#### 16 **Uncertainty Associated with Toxicity Assessment**

17 The toxicological database also was a source of uncertainty. The EPA has outlined some of the  
18 sources of uncertainty in EPA/540/1-89/002. These sources may include or result from the  
19 extrapolation from high to low doses and from animals to humans; the species, gender, age, and  
20 strain differences in a toxin's uptake, metabolism, organ distribution, and target site  
21 susceptibility; and the human population's variability with respect to diet, environment, activity  
22 patterns, and cultural factors.

#### 23 **Uncertainty Associated with Risk Characterization**

24 In the risk characterization, the assumption was made that the total risk of developing cancer  
25 from exposure to site contaminants is the sum of the risk attributed to each individual  
26 contaminant. Likewise, the potential for the development of noncancerous adverse effects is the  
27 sum of the HQs estimated for exposure to each individual contaminant. This approach, in  
28 accordance with EPA guidance, did not account for the possibility that constituents act  
29 synergistically or antagonistically.

1

## C6.0 REFERENCES

- 2 ANL, 2004, *RESRAD for Windows*, Version 6.3, Environmental Assessment Division, Argonne  
3 National Laboratory, Argonne, Illinois.
- 4 DOE-RCA-2002-0584, 2002a, Letter (no title; topic: Tribal Input on CERCLA Risk  
5 Assessment), to Richard Gay, Confederated Tribes of the Umatilla Indian Reservation,  
6 from the Tri-Party Agreement signatories: J. Hebdon, U.S. Department of Energy,  
7 Richland Operations Office; N. Ceto, U.S. Environmental Protection Agency; and  
8 J. Price, Washington State Department of Ecology), Washington State Department of  
9 Ecology, Olympia, Washington, October 8.
- 10 DOE-RCA-2002-0584, 2002b, Letter (no title; topic: Tribal Input on CERCLA Risk  
11 Assessment), to Russell Jim, Confederated Tribes and Bands of the Yakama Nation, from  
12 the Tri-Party Agreement signatories: J. Hebdon, U.S. Department of Energy, Richland  
13 Operations Office; N. Ceto, U.S. Environmental Protection Agency; and J. Price,  
14 Washington State Department of Ecology), Washington State Department of Ecology,  
15 Olympia, Washington, October 8.
- 16 DOE-RCA-2002-0584, 2002c, Letter (no title; topic: Tribal Input on CERCLA Risk  
17 Assessment), to Patrick Sobotta, Nez Perce Tribe, from the Tri-Party Agreement  
18 signatories: J. Hebdon, U.S. Department of Energy, Richland Operations Office; N. Ceto,  
19 U.S. Environmental Protection Agency; and J. Price, Washington State Department of  
20 Ecology), Washington State Department of Ecology, Olympia, Washington, October 8.
- 21 DOE/RL-91-45, 1995, *Hanford Site Baseline Risk Assessment Methodology*, Rev. 3,  
22 U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- 23 Ecology 94-145, 2001, *Cleanup Levels and Risk Calculations Under the Model Toxics Control  
24 Act Cleanup Regulation; CLARC, Version 3.1*, Washington State Department of Ecology,  
25 Olympia, Washington.
- 26 Ecology, 2005, *Cleanup Levels and Risk Calculations (CLARC) Database*,  
27 <https://fortress.wa.gov/ecy/clarc/CLARCHome.aspx>.
- 28 EPA, 1993, "Guidance on Indirect Exposure Assessments for Hazardous Waste Combustion  
29 Facilities," from Jeffery D. Denit, Acting Administrator, Office of Solid Waste and  
30 Emergency Response, Washington, D.C.
- 31 EPA, 2002, *Calculating Upper Confidence Limits for Exposure Point Concentrations at  
32 Hazardous Waste Sites*, OSWER 9285.6-10, Office of Emergency and Remedial  
33 Response, U.S. Environmental Protection Agency, Washington, D.C.
- 34 EPA/530-D-98-001A, 1998, *Human Health Risk Assessment Protocol for Hazardous Waste  
35 Combustion Facilities*, U.S. Environmental Protection Agency, Washington, D.C.

DOE/RL-2005-63 DRAFT A

- 1 EPA/540/1-89/002, 1989, *Risk Assessment Guidance for Superfund (RAGS), Volume I -- Human*  
2 *Health Evaluation Manual, (Part A) Interim Final*, OSWER 9285.7-01A,  
3 U.S. Environmental Protection Agency, Washington, D.C.
- 4 EPA/540/R-99/005, 1999, *Risk Assessment Guidance for Superfund, Volume I: Human Health*  
5 *Evaluation Manual (Part E, Supplemental Guidance for Dermal Risk Assessment)*  
6 *Interim*, U.S. Environmental Protection Agency, Washington, D.C.
- 7 EPA/540/R-99/006, 1999, *Radiation Risk Assessment At CERCLA Sites: Q & A,*  
8 *Directive 9200.4-31P*, Office of Emergency and Remedial Response, Office of Radiation  
9 and Indoor Air, U.S. Environmental Protection Agency, Washington, D.C.
- 10 EPA/600/P-95/002B, 1996, *Exposure Factor Handbook, Volume I, General Factors,*  
11 U.S. Environmental Protection Agency, Washington, D.C.
- 12 Harris, S., 2004, "Exposure Scenario for CTUIR Traditional Subsistence Lifeways,"  
13 Confederated Tribes of the Umatilla Indian Reservation, Department of Science &  
14 Engineering, Pendleton, Oregon.
- 15 Harris, S. G., and B. L. Harper, 1997, "A Native American Exposure Scenario," *Risk Analysis,*  
16 Vol. 17, No. 6, Plenum Publishing Corporation, New York, New York.
- 17 Klein, K. A., D. R. Einan, and M. A. Wilson, 2002, "Consensus Advice #132: Exposure  
18 Scenarios Task Force on the 200 Area," (letter to Mr. Todd Martin, Hanford Advisory  
19 Board, from Keith A. Klein, U.S. Department of Energy; David R. Einan,  
20 U.S. Environmental Protection Agency; and Michael A. Wilson, State of Washington,  
21 Department of Ecology), Richland, Washington, July 11.
- 22 Roberson, J. H., 2002, "Hazard Categorization of EM Inactive Waste Sites as Less Than Hazard  
23 Category 3," (Memorandum for Distribution), U.S. Department of Energy,  
24 Washington, D.C., September 17.

Figure C-1. Game-Based Native American Traditional Subsistence Lifeways Conceptual Site Model and Garden.




Figure C-2. Model for Estimating Chemical Concentrations in Breast Milk.\*

$$C_{\text{Chemical in breast milk, per mg/L of milk fat, mg/L}} = \frac{m * h * f_1}{0.693 * f_2}$$

where

C is the chemical concentration in the portion of breast milk, mg/L,

m = average maternal intake (i.e., exposure dose), mg/kg-day

h = the maternal biological half-life of the chemical, days

f<sub>1</sub> = fraction of ingested chemical stored in maternal fat

0.693 = half – life constant

f<sub>2</sub> = fraction of mother's weight that is fat.

Variable	Value Used	Remark
m	Chemical-specific sum exposure dose all pathways	A function of concentration and all pathways and exposure factors.
h	Assume to be 5 years (1,825 days)	Based on dioxin, a long-lived organic (EPA 1993). Probably conservative.
f <sub>1</sub>	90%	Based on dioxin, a long-lived organic (EPA 1993). Probably conservative.
f <sub>2</sub>	10%	Based on dioxin, a long-lived organic (EPA 1993). Probably conservative.

Fat content in mothers milk assume to be 5%. Whole dairy milk typically is 4%.

\*EPA 1993, "Guidance on Indirect Exposure Assessments for Hazardous Waste Combustion Facilities."

Table C-1. Native American Exposure Scenario, Traditional Subsistence Lifeways (Harris 2004; Harris and Harper 1997).<sup>a</sup>

Exposure Route	Adult <sup>b</sup>	Age/Body Weight Weighted Average <sup>c</sup>	Reference
Soil, ingestion, mg/day	400	347	Harris 2004
Soil, dermal, mg/cm <sup>2</sup> -day	5,000	4,340	Harris and Harper 1997
Soil, inhalation (dust), m <sup>3</sup> /day	20	17	Harris and Harper 1997
Soil, external, h/day	24	24	Harris and Harper 1997
Air, inhalation, m <sup>3</sup> /day	30	26	Harris 2004
Water, ingestion, L/day	4	3.5	Harris and Harper 1997
Water, inhalation, m <sup>3</sup> /day	1	0.87	Harris and Harper 1997
Water, dermal, h/day	0.17	0.15	Harris and Harper 1997
Water, external, h/day, swimming	2.6	2.6	Harris and Harper 1997
Biota, fish, g/day	0	0	See below
Biota, meat (game, fowl, other organs), g/day	958	833	Harris 2004 (The caloric requirement specified from fish consumption is compensated for by additional consumption of meat)
Biota, breast milk, mL/day	742 for 1 to 2 yr	742 for 1 to 2 yr	Harris and Harper 1997
Biota, fruit and vegetation (roots, berries, fruits, greens, other) g/day	1350	1172	Harris 2004
Sweat lodge, inhalation, and dermal h/day	2	2	Harris 2004

<sup>a</sup>Harris, S. G., "Exposure Scenario for CTUIR Traditional Subsistence Lifeways" (2004). Harris, S. G., and B. L. Harper, 1997, "A Native American Exposure Scenario," *Risk Analysis*, Vol. 17, No. 6, Plenum Publishing Corporation, New York, New York.

<sup>b</sup>Harris provides an exposure factor breakdown by life stage including: infant (0 to 2 years), child (2-6 years), youth (7-16 years), adult (17-55 years), and elder (56 to 70 years). This column contains the exposure factors for the adult segment. It is comparable to previous exposure factors provided by Harris and Harper (1997).

<sup>c</sup> Age/body weight adjusted exposure factors derived from the following equation:

$$\text{Age - Body Weight Adjusted Factor} = \sum_{\text{all age intervals}} \prod_{\text{ith age interval}} \frac{\text{Years}_{\text{ith age interval}}}{\text{Years Exposure (70years)}} * \frac{\text{Average Body Weight}_{\text{ith age interval}}}{\text{Adult Body Weight (70kg)}} * \text{Adult}$$

The age-body weight adjustment results in an approximate 13% adjustment.

1

Table C-2. Native American, Traditional Subsistence Lifeways Scenario Chemical-Specific Input Parameters.

COPC	Soil to Plant Transfer <sup>a</sup>	Soil and Plant to Animal Tissue Transfer <sup>a</sup>	Dermal Absorption <sup>b</sup>
Arsenic	0.036	0.002	0.001
Sulfate	00.036	0.002	0.001
Aroclor 1254	0.01	3.097	0.14
Benzo(a)anthracene	0.0202	3.99	0.13
Benzo(a)pyrene	0.0111	3.99	0.13
Benzo(b)fluoranthene	0.01007	3.76	0.13
Benzo(k)fluoranthene	0.0101	3.61	0.13
Chrysene	0.01866	3.99	0.13

NOTE: Transfer factors are not readily available for sulfate. Based on sulfate's inorganic and ionic nature; transfer factors for arsenic were assumed to be conservatively representative for sulfate.

<sup>a</sup> Source: EPA/530-D-98-001A, *Human Health Risk Assessment Protocol for Hazardous Waste Combustion Facilities*.

<sup>b</sup> Source: EPA/540/R-99/005, *Risk Assessment Guidance for Superfund, Volume I: Human Health Evaluation Manual (Part E, Supplemental Guidance for Dermal Risk Assessment) Interim*.

Table C-3. Radionuclide Screening Result and 95%UCL Concentrations.

216-A-29 Ditch											
Radionuclide	Am <sup>241</sup>	Sb <sup>125</sup>	Cs <sup>137</sup>	Np <sup>237</sup>	Pu <sup>238</sup>	Pu <sup>230/240</sup>	Ra <sup>226</sup>	Th <sup>230</sup>	Sr <sup>90</sup>	H <sup>3</sup>	U <sup>233/234</sup>
Percent Contribution to Dose	14%	<1%	2%	<1%	<1%	79%	4%	<1%	<1%	ND	<1%
95%UCL pCi/g	30.1	--	22	--	--	200.2	0.65	--	--	--	--
216-B-63 Trench											
Radionuclide	Am <sup>241</sup>	Cs <sup>137</sup>	Np <sup>237</sup>	Ni <sup>63</sup>	Tc <sup>99</sup>	Sr <sup>90</sup>	Th <sup>230</sup>	H <sup>3</sup>	--	--	--
Percent Contribution to Dose	<1%	4%	8%	ND	ND	57%	30%	ND	--	--	--
95%UCL pCi/g	--	2.4	0.06	--	--	15.0	0.7	--	--	--	--
216-S-10 Ditch											
Radionuclide	Am <sup>241</sup>	Cs <sup>137</sup>	Ni <sup>63</sup>	Pu <sup>239</sup>	Ra <sup>226</sup>	Th <sup>228</sup>	Th <sup>230</sup>	Th <sup>232</sup>	Sr <sup>90</sup>	H <sup>3</sup>	--
Percent Contribution to Dose	7%	26%	a	67%	a	a	a	a	2	b	--
95%UCL pCi/g	0.2	4.1	--	1.5	--	--	--	--	0.2	--	--

Table C-3. Radionuclide Screening Result and 95%UCL Concentrations.

216-S-10 Pond											
Radionuclide	Am <sup>241</sup>	C <sup>14</sup>	Cs <sup>137</sup>	Np <sup>237</sup>	Ni <sup>63</sup>	Pu <sup>239/240</sup>	Th <sup>228</sup>	Th <sup>230</sup>	Sr <sup>90</sup>	H <sup>3</sup>	--
Percent Contribution to Dose	4	<1	4	a	b	34	<1	53	4	b	--
95%UCL pCi/g	0.23	12.2 <sup>c</sup>	0.8	--	--	0.9	--	0.7	0.7	--	--

<sup>a</sup>Not above background in the 0 to 15-ft interval.

<sup>b</sup>No laboratory analysis in the 0 to 15-ft interval.

<sup>c</sup>Maximum concentration use because 95%UCL exceeded the maximum.

95%UCL = 95th upper confidence level.

ND = Not detected in the 0 to 15-ft depth interval.

Table C-4. Native American, Traditional Subsistence Lifeways Scenario Chemical-Specific Toxicity Factors.

Constituent	$Sf_{oral}$	$Sf_{inhalation}$	$Sf_{dermal}$	$RfD_{oral}$	$RfD_{inhalation}$	$RfD_{dermal}$
	(Risk/mg/kg d)	(Risk/mg/kg d)	(Risk/mg/kg d)	(mg/kg d)	(mg/kg d)	(mg/kg d)
Arsenic	1.5E+00	1.5E+01	--	3.0E-04	1.5E+01	--
Sulfate*	--	--	--	7.8 E1	7.8 E1	7.8 E1
Aroclor 1254	--	--	--	2.0E-05	--	2.0E-05
Benzo(a)anthracene	7.30E+00	--	7.30E+00	--	--	--
Benzo(a)pyrene	7.30E+00	--	7.30E+00	--	--	--
Benzo(b)fluoranthene	7.30E+00	--	7.30E+00	--	--	--
Benzo(k)fluoranthene	7.30E+00	--	7.30E+00	--	--	--
Chrysene	7.30E+00	--	7.30E+00	--	--	--

\*Derived oral RfD based on U.S. Environmental Protection Agency data. See Equation 4 in Section 2.12.7.2 of the feasibility study.

-- No toxicity data.

Source: Ecology 94-145, *Cleanup Levels and Risk Calculations Under the Model Toxics Control Act Cleanup Regulation; CLARC, Version 3.1.*

RfD = chronic reference dose.

$RfD_{dermal}$  =

$RfD_{inhalation}$  = inhalation chronic reference dose.

$RfD_{oral}$  = oral chronic reference dose.

$Sf_{dermal}$  =

$Sf_{inhalation}$  =

$Sf_{oral}$  =

1

Table C-5. 216-A-29 Ditch Native American Subsistence Lifeways Radiological Dose and Risk.

Time (years)	Total Dose (mrem/y)	Total ELCR	Primary Radionuclide	Percent of Total Dose	Primary Pathway
0	225	3E-3	Pu-239	58	Plant
			Cs-137	28	Ground
1	224	3E-3	Pu-239	58	Plant
			Cs-137	28	Ground
50	183	2E-3	Pu-239	71	Plant
			Cs-137	11	Ground
150	162	1E-3	Pu-239	80	Plant
			Am-241	11	Soil
500	148	1E-3	Pu-239	86	Plant
1,000	139	8E-4	Pu-239	91	Plant

ELCR = excess lifetime cancer risk.

2

Table C-6. 216-A-29 Ditch Native American Subsistence Lifeways Nonradiological Risk and Hazard Index.

All Life Stages Child to Adult Model (Excluding Infant Milk Consumption)							
Carcinogenic Constituents				Non-Carcinogenic Constituents			
Sum ELCR	Primary Constituent	Percent of Total Risk	Primary Pathway	Hazard Index	Primary Constituent	Percent of Total Hazard Index	Primary Pathway
1E-1	Benzo(a)anthracene	46	Game consumption	1E4	Aroclor 1254	99	Game consumption
	Chrysene	53					
Infant Milk Consumption							
Sum ELCR	Primary Constituent	Percent of Total Risk	Primary Pathway	Hazard Index	Primary Constituent	Percent of Total Hazard Index	Primary Pathway
8E-2	Benzo(a)anthracene	46	Maternal game consumption	3E8	Aroclor 1254	~100	Maternal game consumption
	Chrysene	53					

NOTE:

All constituent concentrations arise from isolated detections and do not reflect integrated exposure  
 The food chain and infant milk consumption models are conservative and subject to significant uncertainty.

ELCR = excess lifetime cancer risk.

Table C-7. 216-B-63 Trench Native American Subsistence Lifeways Radiological Dose and Risk.

Time (years)	Total Dose (mrem/y)	Total ELCR	Primary Radionuclide	Percent of Total Dose	Primary Pathway
0	88	2E-3	Sr-90	91	Plant
1	86	2E-3	Sr-90	91	Plant
50	27	6E-4	Sr-90	88	Plant
150	4	1E-4	Sr-90 Th-230	54 26	Plant
500	4	1E-4	Th-230	85	Plant
1,000	4	1E-4	Th-230	91	Plant

ELCR = excess lifetime cancer risk.

1

2

Table C-8. 216-S-10 Ditch Native American Subsistence Lifeways Radiological Dose and Risk.

Time (years)	Total Dose (mrem/y)	Total ELCR	Primary Radionuclide	Percent of Total Dose	Primary Pathway
0	14	3E-4	Cs-137	85	Ground
1	14	3E-4	Cs-137	84	Ground
50	5	1E-4	Cs-137	72	Ground
150	1	1E-5	Pu-239	66	Plant
500	1	4E-6	Pu-239	96	Plant
1,000	1	3E-6	Pu-239	98	Plant

ELCR = excess lifetime cancer risk.

Table C-9. 216-S-10 Ditch, Native American Subsistence Lifeways Nonradiological Risk and Hazard Index.

All Life Stages Child to Adult Model (Excluding Infant Milk Consumption)							
Carcinogenic Constituents				Non-Carcinogenic Constituents			
Sum ELCR	Primary Constituent	Percent of Total Risk	Primary Pathway	Hazard Index	Primary Constituent	Percent of Total Hazard Index	Primary Pathway
1E-1	Benzo(a)anthracene	22%	Game consumption	5E3	Aroclor 1254	100%	Game consumption
	Benzo(a)pyrene	20%					
	Chrysene	27%					
Infant Milk Consumption							
Sum ELCR	Primary Constituent	Percent of Total Risk	Primary Pathway	Hazard Index	Primary Constituent	Percent of Total Hazard Index	Primary Pathway
5E-1	Benzo(a)anthracene	22%	Maternal game consumption	1E8	Aroclor 1254	100%	Maternal game consumption
	Benzo(a)pyrene	20%					
	Chrysene	27%					

Note:

All constituent concentrations arise from isolated detections and do not reflect integrated exposure  
 The food chain and infant milk consumption models are conservative and subject to significant uncertainty.

ELCR = excess lifetime cancer risk.

Table C-10. 216-S-10 Pond Native American Subsistence Lifeways Radiological Dose and Risk.

Time (years)	Total Dose (mrem/y)	Total ELCR	Primary Radionuclide	Percent of Total Dose	Primary Pathway
0	11	2E-4	C-14 Sr-90	39% 33%	Plant
1	8	1E-4	Cs-137 Sr-90	30% 45%	Plant
2.9	3	7E-5	Cs-137 Sr-90	25% 37%	Plant
150	2	5E-5	Th-230 Pu-239	54% 30%	Plant
500	4	1E-4	Th-230	83%	Plant
1,000	4	12E-4	Th-230	90%	Plant

Note there are no nonradiological COPCs for the 216-B-63 Trench site.

ELCR = excess lifetime cancer risk.

1

This page intentionally left blank.

2

1

**APPENDIX D**

2

3

**COST ESTIMATE BACKUP**

4

1

This page intentionally left blank.

2

## CONTENTS

1			
2	D1.0	INTRODUCTION .....	D-1
3	D2.0	ALTERNATIVE COST ESTIMATES.....	D-2
4	D2.1	ALTERNATIVE 1 – NO ACTION.....	D-2
5	D2.2	ALTERNATIVE 2 – MAINTAIN EXISTING SOIL COVER, MONITORED NATURAL ATTENUATION, AND INSTITUTIONAL	
6		CONTROLS .....	D-2
7			
8	D2.3	ALTERNATIVE 3 – REMOVAL, TREATMENT, AND DISPOSAL.....	D-3
9	D2.4	ALTERNATIVE 4 – ENGINEERED BARRIER .....	D-4
10	D3.0	ASSUMPTIONS.....	D-4
11	D3.1	GLOBAL ASSUMPTIONS.....	D-4
12		D3.1.1 Labor.....	D-4
13		D3.1.2 Markups .....	D-5
14		D3.1.3 General Assumptions .....	D-5
15		D3.1.4 Long-Term Groundwater Monitoring Costs.....	D-6
16	D3.2	ALTERNATIVE 2 – MAINTAIN EXISTING SOIL COVER, MONITORED NATURAL ATTENUATION, AND INSTITUTIONAL	
17		CONTROLS .....	D-8
18			
19		D3.2.1 General Assumptions .....	D-8
20		D3.2.2 Representative Site 216-A-29 Ditch .....	D-9
21		D3.2.3 Representative Site 216-S-10 Ditch.....	D-11
22	D3.3	ALTERNATIVE 3 – REMOVAL, TREATMENT, AND DISPOSAL.....	D-14
23		D3.3.1 Representative Site 216-A-29 Trench.....	D-17
24		D3.3.2 Representative Site 216-S-10 Ditch.....	D-21
25	D3.4	ALTERNATIVE 4 – ENGINEERED BARRIER.....	D-25
26		D3.4.1 General Assumptions .....	D-25
27		D3.4.2 Representative Site 216-A-29 Ditch .....	D-28
28		D3.4.3 Representative Site 216-S-10 Ditch.....	D-32
29	D4.0	REFERENCES .....	D-36
30			

**TABLES**

1  
2  
3  
4  
5  
6  
7  
8  
9  
10

Table D-1. 216-A-29 Ditch Alternative 2..... D-38  
Table D-2. 216-S-10 Ditch Alternative 2. .... D-39  
Table D-3. 216-A-29 North Ditch – Alternative 3 – Removal, Treatment, and Disposal..... D-40  
Table D-4. 216-S-10 Ditch – Alternative 3 – Removal, Treatment, and Disposal..... D-44  
Table D-5. 216-A-29 North Ditch – Alternative 4 – Engineered Barrier..... D-46  
Table D-6. 216-S-10 Ditch – Alternative 4 – Engineered Barrier..... D-50  
Table D-7. 200-CS-1 Operable Unit Representative and Analogous Site Information..... D-52  
Table D-8. 200-CS-1 Operable Unit Net Present Value and Non-Discounted Costs..... D-53

1 APPENDIX D  
2 COST ESTIMATE BACKUP

3 D1.0 INTRODUCTION

4 The feasibility study (FS) provides a logical progression for evaluating sites that require remedial  
5 action. During the detailed analysis portion of the FS, nine factors (two threshold, five  
6 balancing, and two modifying) are evaluated. This FS evaluated the two threshold criteria and  
7 five balancing criteria. The remaining two factors are assessed during the review and comment  
8 period. One of the balancing criteria is the cost to implement the various alternative remedial  
9 actions.

10 Cost estimates for the feasibility study (FS) have an accuracy of +50 percent, -30 percent, which  
11 is the accuracy specified in EPA/540/R-00/002, *A Guide to Developing and Documenting Cost*  
12 *Estimates During the Feasibility Study*, OSWER 9355.0-75. The cost estimates provide a  
13 discriminator for deciding between similar protective and implemental alternatives for a specific  
14 waste site. Therefore, the costs are relational, not absolute, costs for the evaluation of the  
15 alternatives. Cost estimates by waste site were developed using the MAESTRO cost models  
16 developed by the Fluor Hanford, Inc. (FH) Project Controls Estimating department.

17 The various cost elements are taken from EPA/540/R-00/002; the FH contract with the  
18 U.S. Department of Energy (DE-AC06-96RL13200, *Contract Between the U.S. Department of*  
19 *Energy, Richland Operations Office, and Fluor Daniel Hanford, Inc.*); R. S. Means; and  
20 technical and historical site information. Contingency is applied to the cost estimate to cover  
21 potential cost overruns. Contingency covers two types, scope and bid. Scope covers the  
22 unknown elements of the alternative as remedial design proceeds, while bid contingency covers  
23 the unknown elements of remedial action and operations and maintenance as they proceed. A  
24 contingency of 25 percent is applied based on the level of engineering information available at  
25 this time. This FS does not evaluate the economies associated with implementing multiple sites  
26 or groups with a common alternative or aggregated remediation. They will be considered in the  
27 future as part of long-range planning and through the post-record-of-decision activities, such as  
28 remedial design. Potential areas of cost sharing to reduce overall remediation costs include the  
29 following:

- 30 • Remediating all waste sites with a common preferred alternative at the same time  
31 • Sharing mobilization/demobilization costs  
32 • Sharing surveillance and maintenance costs  
33 • Sharing barrier performance monitoring costs.  
34 • Sharing training costs.

35 Present-net-worth costs were estimated using the real discount rate published in Appendix C of  
36 the Office of Management and Budget Circular No. A-94, *Guidelines and Discount Rates for*  
37 *Benefit-Cost Analysis of Federal Programs*, which is effective through the end of January 2004.  
38 Programs with durations longer than 30 years use the 30-year interest rate of 3.1 percent.  
39 Present-net-worth costs are discussed for each alternative in the following subsections.

40 Non-discounted costs were calculated because of recommendations presented in  
41 EPA/540/R-00/002. Non-discounted constant dollar costs demonstrate the impact of a discount

1 rate on the total present-value cost. The non-discounted costs are presented for comparison  
2 purposes only.

3 Major assumptions are covered in Chapter D3.0. These assumptions are necessary to provide the  
4 level of detail necessary for independent review.

## 5 **D2.0 ALTERNATIVE COST ESTIMATES**

6 This chapter describes the cost estimates based on the remedial alternatives developed in  
7 Chapter 6.0 of the FS. This chapter also summarizes the alternatives considered and the total  
8 present-worth costs, and provides summary and backup information for costs by waste site or  
9 group.

### 10 **D2.1 ALTERNATIVE 1 – NO ACTION**

11 The no-action alternative represents a situation where no legal restrictions, access controls, or  
12 active remedial measures are applied to the waste site. Taking no action implies “walking away  
13 from the waste site” and allowing the waste to remain in its current configuration, affected only  
14 by natural processes. No maintenance or other activities would be instituted or continued.  
15 Chapter 6.0 of the FS describes the no-action alternative.

16 Because the no-action alternative assumes no further actions will be taken at a waste site, costs  
17 are assumed to be zero.

### 18 **D2.2 ALTERNATIVE 2 – MAINTAIN EXISTING** 19 **SOIL COVER, MONITORED NATURAL** 20 **ATTENUATION, AND INSTITUTIONAL** 21 **CONTROLS**

22 Chapter 6.0 of the FS provides a description of the Maintain Existing Soil Cover, Monitored  
23 Natural Attenuation, and Institutional Controls alternative. Cost models for each representative  
24 site are discussed in detail in Section D3.2. The primary annual/periodic costs associated with  
25 this alternative are surveillance and cover maintenance and monitored natural attenuation costs.  
26 This alternative also includes the cost of long term groundwater monitoring. The costs for these  
27 annual/periodic activities were estimated based on the area of the individual waste sites or  
28 groups. Tables D-1 and D-2 provide details of the capital and annual/periodic cost estimates.

29 The unit cost for surveillance and maintenance was assumed to be the same as the current unit  
30 cost for surveillance and maintenance activities conducted annually on the waste sites. The unit  
31 cost accounts for such activities as site radiation surveys, and repair of the existing soil cover on  
32 the sites where it is present. Because the existing soil cover is maintained annually, costs for  
33 replacing all or large portions of the existing cover at specified intervals (i.e., every 20 years) are  
34 considered unnecessary.

35 The costs associated with natural attenuation monitoring are divided into three components:  
36 radiological surveys of surface soils, spectral gamma logging of vadose zone boreholes, and  
37 groundwater monitoring. The costs to perform radiological surveys of surface soils at waste sites

1 are assumed to be similar to those for current survey practices at the sites and are included in the  
2 surveillance and maintenance costs.

3 Vadose zone monitoring costs assume spectral gamma logging of one borehole per waste site to  
4 a 15 m (50 ft) depth once every 5 years until the site meets all preliminary remediation goals.  
5 This monitoring is considered for sites with high concentrations of contaminants in the shallow  
6 zone or near the bottom of crib and trench structures. It also assumes that the service life of  
7 vadose zone boreholes is 30 years. Costs are included for logging and periodic replacement of  
8 these boreholes until all preliminary remediation goals are met for the site (assume 150 years).

9 Groundwater monitoring costs likely will be incurred for sites that have high concentrations of  
10 mobile contaminants deep within the vadose zone and/or where groundwater contamination is  
11 known to have occurred. However, for the purpose of this FS the groundwater sampling activity  
12 will be considered as a periodic cost.

13 Institutional controls, which can have one-time or recurring costs (capital, annual operation and  
14 maintenance, or periodic), are non-engineering or legal/administrative measures to reduce or  
15 minimize the potential for exposure to site contamination or hazards by limiting or restricting site  
16 access.

17 Examples include institutional controls plan, restrictive covenants, property easements,  
18 zoning, deed notices, advisories, groundwater use restrictions, and site information database.  
19 An institutional controls plan would describe the controls for a site and how to implement  
20 them. A site information database would provide a system for managing data necessary to  
21 characterize the current nature and extent of contamination. Institutional controls are project-  
22 specific costs that can be an important component of a remedial alternative and, as such, should  
23 generally be estimated separately from other costs, usually on a sub-element basis. Institutional  
24 controls may need to be updated or maintained, either annually or periodically.

25 The institutional control cost model used for this alternative was developed by the FH Project  
26 Controls and Estimating Department. The duration for institutional controls only considers the  
27 initial, "Year-one" period. The annual/periodic activities were based on the length of time  
28 required to reach the preliminary remediation goals of 150 years. The combined  
29 present-net-worth costs for surveillance and maintenance, natural attenuation monitoring and  
30 institutional control activities represent the present-worth cost for this alternative. The real  
31 discount rate of 3.1 percent is used for discounting real (constant-dollar) flows for the duration  
32 until all preliminary remediation goals are reached at each site (assume 150 years). The  
33 non-discounted cost for the 150 year project duration is presented for comparison purposes.

### 34 **D2.3 ALTERNATIVE 3 – REMOVAL, TREATMENT, AND DISPOSAL**

35 Chapter 6.0 of this FS describes the removal, treatment, and disposal (RTD) alternative. Cost  
36 models for each representative site are discussed in detail in Section D3.3. Cost estimates for the  
37 RTD alternative are provided in Tables D-3 and D-4. Table D-7 lists the excavation depths for  
38 this alternative.

39 Annual/periodic and institutional control costs were not added to the removal, treatment, and  
40 disposal alternative because the contaminants are assumed to be removed to concentrations at or  
41 below the preliminary remediation goals. This alternative removes the human health and  
42 ecological risks associated with the contaminated soils at each site evaluated in this FS.

1 The RTD construction activities represent the present-worth cost for this alternative. The real  
 2 discount rate of 3.1 percent is used for discounting real (constant-dollar) flows for the duration  
 3 until all preliminary remediation goals are reached at each site (assume 150 years). The  
 4 non-discounted cost for the 150 year project duration is presented for comparison purposes. For  
 5 this alternative, the present worth cost and non discounted cost are zeroed-out once the RTD  
 6 activities are complete.

## 7 **D2.4 ALTERNATIVE 4 – ENGINEERED BARRIER**

8 Chapter 6.0 of this FS provides a description of the barrier alternative. Cost models for each  
 9 representative site are discussed in detail in Section D3.4. Cost estimates for the capping  
 10 alternative are included in Tables D-5 and D-6. Figures D-1 to D-2 shows details of the assumed  
 11 barrier design for the Evapotranspiration Capillary Barrier (ET).

12 Operation and maintenance costs for the barrier alternative include barrier performance  
 13 monitoring and repair costs. For purposes of this FS, all sites will assume annual repairs to the  
 14 barrier (replacement of 15.2 cm [2 ft] of topsoil layer and revegetation over 10 percent of the  
 15 barrier area). This is considered a conservative estimate because the barrier has been designed to  
 16 require minimal maintenance, particularly after vegetation has been established.

17 Institutional controls are an integral component of the barrier alternative and would be required  
 18 to prevent both intrusion to the barrier area and activities that might alter the integrity and  
 19 effectiveness of the barrier. Groundwater monitoring likely would be a part of the barrier  
 20 alternative. However, the cost estimate considers groundwater sampling periodic costs.  
 21 Therefore, they are not considered in the capital cost estimates.

22 The institutional control cost model used for this alternative was developed by the FH Project  
 23 Controls and Estimating Department. The duration for institutional controls only considers the  
 24 initial, "Year-one" period. The Annual/Periodic activities were based on the length of time  
 25 required to reach the preliminary remediation goals (assume 150 years).

26 The combined present-net-worth costs for remove and dispose construction activities,  
 27 surveillance and maintenance; natural attenuation monitoring and institutional control activities  
 28 represent the present-worth cost for this alternative. The real discount rate of 3.1 percent is used  
 29 for discounting real (constant-dollar) flows for the duration until all preliminary remediation  
 30 goals are reached at each site (assume 150 years). The non-discounted cost for the 150-year  
 31 project duration is presented for comparison purposes.

## 32 **D3.0 ASSUMPTIONS**

33 Assumptions used for Alternatives 3 and 4 are discussed in the following sections.

### 34 **D3.1 GLOBAL ASSUMPTIONS**

#### 35 **D3.1.1 Labor**

- 36 • Fixed price construction craft labor rates are those listed in Appendix A to the Hanford  
 37 Site Stabilization Agreement (HSSA). The HSSA rates include base wage, fringe

1 benefits, and other compensation as negotiated between FH and the National Building  
 2 and Construction Trades Department AFL-CIO. Other factors to cover additional costs  
 3 for Workman's Compensation, FICA, state and federal unemployment insurance to  
 4 develop a fully burdened rate by craft have been incorporated. The labor rates used are  
 5 for 2006.

- 6 • FH labor rates for management, engineering, safety oversight, and technical support are  
 7 based on the FH approved planning rates for FY2006.

### 8 **D3.1.2 Markups**

#### 9 **Direct Cost Factors**

- 10 • Sales tax has been applied to all materials and equipment purchases at 8.3%.
- 11 • Construction consumables are estimated at 3.5% of FP direct craft labor costs to allow for  
 12 small tools, tape, plastics, gloves, etc.
- 13 • General foreman factor of 3% has been applied to FP craft labor hours.

#### 14 **Indirect Cost Factors**

- 15 • Fixed Price contractor overhead, profit, bond and insurance costs have been applied at  
 16 26.5% on FP labor, materials, and equipment.
- 17 • FH G&A of 16.5% has been applied to all FH labor, material and equipment. The G&A  
 18 is also applied to the FP Contractor costs.

### 19 **D3.1.3 General Assumptions**

- 20 • FH Cost Estimating Templates for site remediation were used as the basis for each waste  
 21 site. Standard templates used include trench/ ditch/ crib and ET Capillary Barrier.
- 22 • Construction labor, material and equipment units have been estimated based upon  
 23 standard commercial estimating resources and databases: R. S. Means, Richardson's  
 24 Process Plant Construction Estimating Standards, and the US Army Corps MCACES  
 25 Database. The units may have been factored or adjusted by the estimator as appropriate  
 26 to reflect influences by contract, work site, or other identified project or special  
 27 conditions.
- 28 • Quotes from local commercial sources have been used for materials that need to be  
 29 acquired for the construction of barriers or temporary improvements.
- 30 • Equipment Rates are based on 21 working days per month.
- 31 • Equipment operation is based on one shift of 8 hours per day.
- 32 • Work week equals 5 days per week.
- 33 • Work stoppages or shut downs due to inclement weather are not factored into the  
 34 estimates or planning schedules for this study.
- 35 • Work delays or stoppages due caused by waiting for lab results or approval for  
 36 backfilling waste site excavations are not factored into the estimates or planning  
 37 schedules for this study.

- 1 • The cost estimates does include costs for design, work plan preparation, or any other
- 2 preparation costs normally associated with activities occurring before field mobilization.
- 3 • Remedial Design Capital Costs are based on EPA/540/R-00/002 Exhibit 5-8. The
- 4 following guide is used in this study:
  - 5 ○ For projects with construction costs less than \$100K – Remedial design is planned
  - 6 at 20% of construction costs.
  - 7 ○ For projects with construction costs from \$100K to \$500K – Remedial design is
  - 8 planned at 15% of construction costs.
  - 9 ○ For projects with construction costs from \$500K to \$2M – Remedial design is
  - 10 planned at 12% of construction costs.
  - 11 ○ For projects with construction costs from \$2M to \$10M – Remedial design is
  - 12 planned at 8% of construction costs.
  - 13 ○ For projects with construction costs greater than \$10M – Remedial design is
  - 14 planned at 6% of construction costs.
- 15 • Escalation has not been included in the calculations. All costs are present day (FY2006).
- 16 • Contingency Rates are based on Section 5.4 of EPA/540/R-00/002.

17 **D3.1.4 Long-Term Groundwater Monitoring Costs**

18 Under each alternative that includes annual inspections and maintenance costs (Alternatives 2  
 19 and 4) there will be a cost for periodic groundwater monitoring. The cost associated with  
 20 periodic groundwater monitoring is distributed equally over applicable closure zones. The  
 21 following is a description of the periodic groundwater costs.

22 Periodic groundwater sampling will be performed in each closure zone. Each closure zone will  
 23 contain three monitoring wells that will be sampled during the periodic sampling event. The  
 24 present worth cost for the periodic groundwater monitoring program will be the same for each  
 25 closure zone. That cost then will be divided equally among all the waste sites within that closure  
 26 zone. A summary of the facility closure zones associated with this FS is presented below.

27 <u>Closure Zone</u>	<u>Number of Sites in Each Closure Zone</u>
28 200-E Ponds	55
29 200-W Ponds	28

30 Based on historical information from similar Hanford Site planning, the cost to install a  
 31 compliant monitoring well is approximately \$180,000<sup>1</sup> per well. It is assumed that this cost  
 32 includes all required labor and material. In addition, each of the wells will need to be replaced  
 33 every 30 years.

34 Cost to install wells (3 wells) = \$180,000/well x 3 wells

---

<sup>1</sup> Installation/replacement, as well as maintenance and sampling, costs have been rounded-off to facilitate explanation of long-term groundwater program costs.

1 = \$540,000

2 Replacement costs (3 wells) = \$180,000/well x 3 wells

3 = \$540,000 every 30 years

4 Maintenance will need to be performed on each of the wells every 5 years during the 150-year

5 active monitoring period.

6 Maintenance costs (3 wells) = \$5,000/well x 3 wells

7 = \$15,000 every 5 years

8 During each sampling event, three groundwater samples will be collected for analysis.

9 Total analytical cost per sampling event = \$1,599

10 The labor cost of doing all the paper work, labeling, monitoring, and delivery to the laboratory is

11 approximately \$300 per well sampled.

12 Total labor cost = \$300/well x 3 wells

13 = \$900/sampling event

14 Total cost to collect and analyze samples per sampling event = \$2,499

15 Sampling events will occur at the following frequencies:

16 Year 1	Quarterly (4 sampling events)
17 Year 2	Semi-annually (2 sampling events)
18 Years 3 through 5	Annually (3 sampling events)
19 Years 6 through 10	Every 2 years (3 sampling events)
20 Years 11 through 50	Every 5 years (8 sampling events)
21 Years 51 through 150	Every 10 years (10 sampling events).

22 The present worth cost to conduct a periodic groundwater-monitoring program for each closure

23 zone for 150 years was calculated.

24 Present-worth cost for long-term groundwater program = \$557,583/closure zone.

25 As a comparison, the non-discounted present worth cost for long-term groundwater program was

26 calculated to compare the effect of a discount rate on the total project cost.

27 Present worth non-discounted costs for long-term groundwater program = \$3,089,808/closure

28 zone.

29 The present worth cost, on a per site basis, will be added to the calculated costs. Because there

30 are a different number of sites in each closure zone, the following list presents the long-term

31 groundwater monitoring cost per site for each closure zone and the sites included in this FS. The

32 non-discounted long-term groundwater monitoring cost per site is presented in parentheses.

<u>Closure Zone</u>	<u>Number of Sites in Each Closure Zone</u>	<u>Cost Per Site</u>
200-E Ponds	55	\$10,138 (\$56178)
200-W Ponds	28	\$19,914 (\$110,350)

Lastly, the following table lists the sites included in this cost estimate, their associated closure zone, and the cost that will be added into the costs for Alternatives 2 and 4. Non-discounted costs are presented in parentheses.

Closure Zone: 200-E Ponds	Cost per Site: \$10,138 (\$56,178)
216-A-29 Ditch	
Closure Zone: 200-W Ponds	Cost per Site: \$19,914 (\$110,350)
216-S-10 Ditch	

## **D3.2 ALTERNATIVE 2 – MAINTAIN EXISTING SOIL COVER, MONITORED NATURAL ATTENUATION, AND INSTITUTIONAL CONTROLS**

### **D3.2.1 General Assumptions**

The general assumptions for Alternative 2 are as follows:

- D3.2.1.1 Similar to the cost estimates for Alternatives 3 and 4, Alternative 2 costs were calculated for each of the sites. Using the processes presented in the site cost backup text presented in this appendix, equations were used to calculate the cost for each Site using the specific area of each Site.
- D3.2.1.2 Typical site areas range from under 100 ft<sup>2</sup> to 1,000,000 ft<sup>2</sup>. Because of this difference, larger construction crews will be used for sites larger than 100,000 ft<sup>2</sup>. For example, existing cover maintenance will use five trucks to haul material to the site for areas greater than 100,000 ft<sup>2</sup> and one truck for sites less than 100,000 ft<sup>2</sup>.
- D3.2.1.3 Fencing and monuments/signs for institutional controls and fencing maintenance are considered institutional costs and are considered in this cost estimate.
- D3.2.1.4 Periodic groundwater monitoring costs will be added to long term monitoring costs as indicated in Section D3.1.4.
- D3.2.1.5 Alternative 2 consists of seven general activities: institutional controls, site inspection and surveillance, existing cover maintenance, natural attenuation monitoring, reporting, site reviews and monitoring. These activities are described for the representative sites in the following sections.

1 D3.2.1.6 The prices that make up the cost estimate were obtained from one of the following  
2 sources:

- 3 • *ECHOS Environmental Remediation Cost Data – Unit Price, 7<sup>th</sup> Annual Edition*  
4 (Means 2001a)
- 5 • *Facility Construction Cost Data, 19<sup>th</sup> Annual Edition (Means 2004b)*
- 6 • Experience on similar projects.

### 7 D3.2.2 Representative Site 216-A-29 Ditch

8 **Institutional Controls Implementation:** Preparing and implementing institutional controls is a  
9 capital cost and includes office or administrative costs to implement deed restrictions, land-use  
10 restrictions, and groundwater-use restrictions. Costs presented in the cost estimates are based on  
11 the following:

- 12 • Time to produce institutional controls = 200 hours (assumption)
- 13 • Labor rate = \$56/h (assumption).

14 **Site Inspection and Surveillance:** The cost associated with site inspection and surveillance is  
15 an operation and maintenance cost. This cost will be incurred annually as long as the alternative  
16 is being used. The activities performed under site inspection and surveillance include radiation  
17 surveys of surface soil and physical site inspection. Activities may include control of deeply  
18 burrowing animals and deep-rooted plants by using herbicide or by physical removal (cost for  
19 these items are not included).

20 **Site radiation surveys:** For costing purposes, sites 1 acre or smaller are assumed to cost \$8,712  
21 for every surveying event. An additional \$1,000 will be required for site radiation surveys for  
22 every additional 5,000 ft<sup>2</sup> of site area above 1 acre.

- 23 • Area of site = 16,117 ft<sup>2</sup> (see Table D-7)  
24 = minimum 1 acre
- 25 • Radiation surveys of surface soil = \$8,712/event (\$1,000/5,000 ft<sup>2</sup>).

26 **Physical site inspection:** For costing purposes, sites 1 acre (43,560 ft<sup>2</sup>) or smaller are assumed to  
27 require a team of two inspectors to perform the activities associated with site inspection and  
28 surveillance. An additional crew time will be needed for site inspection and surveillance for site  
29 areas larger than 1 acre.

30 The cost for site inspection and surveillance is based on the following.

- 31 • Area of site = 16,117 ft<sup>2</sup> (see Table D-7)  
32 = minimum 1 acre
- 33 • Cost to complete inspection = \$781/acre.

34  
35 **Existing Cover Maintenance:** The cost associated with existing cover maintenance is an  
36 operation and maintenance cost. This cost will be incurred annually as long as the alternative is  
37 being used. Because cover maintenance is performed annually, including costs for replacing all  
38 or large portions of the existing cover at specified intervals is unnecessary. Rather, cover  
39 maintenance is assumed to include replacing cover soils over 10 percent of the area to a depth of



1 30 years. Therefore, every 30 years a replacement borehole will be drilled. Costs are based on  
2 the following:

- 3 • Unit cost for vadose zone monitoring = \$75/ft of borehole
- 4 • Length of borehole drilling = 50 ft
- 5 • Cost of vadose zone monitoring = \$75/ft x 50 ft = \$3,750
- 6 • Installation cost of borehole = \$50/ft of borehole
- 7 • Length of borehole installation = 50 ft
- 8 • Cost of borehole installation = \$50/ft x 50 ft = \$2,500
- 9 • Oversight (assumption) = 1 day = 8 hours (\$56/h).

10 Other costs associated with installing replacement boreholes are included on the cost estimate  
11 sheets. These items include, but are not limited to, mobilization of a drill rig, decontamination of  
12 a drill rig, and handling of investigation derived waste (IDW).

13 **Reporting:** Annual and periodic activities will be recorded in an annual report. The report will  
14 contain descriptions of activities that occurred during the year. Reports will contain all  
15 appropriate/required backup and material purchase information. The cost for the annual reports  
16 is based on the following assumption:

- 17 • Annual reports = \$10,000/report.

18 **Site Reviews:** The cost associated with site reviews is an operation-and-maintenance cost. This  
19 cost will be incurred every 5 years as long as the alternative is being used. Site reviews will be  
20 conducted to assess site conditions and to evaluate the selected alternative and determine  
21 whether additional steps toward remediation are required. The cost for the five year site reviews  
22 is based on the following assumption:

- 23 • 5-year site review = \$20,000/review.

24 **Monitoring:** Monitoring includes collecting groundwater samples from down-gradient wells to  
25 evaluate the performance of the barrier system. Refer to Section D3.1.4.

### 26 D3.2.3 Representative Site 216-S-10 Ditch

27 **Institutional Controls Implementation:** Preparing and implementing institutional controls is a  
28 capital cost and includes office or administrative costs to implement deed restrictions, land-use  
29 restrictions, and groundwater-use restrictions. Costs presented in the cost estimates are based on  
30 the following:

- 31 • Time to produce institutional controls = 200 hours (assumption)
- 32 • Labor rate = \$56/h (assumption).

33 **Site Inspection and Surveillance:** The cost associated with site inspection and surveillance is  
34 an operation and maintenance cost. This cost will be incurred annually as long as the alternative  
35 is being used. The activities performed under site inspection and surveillance include radiation  
36 surveys of surface soil and physical site inspection. Activities may include control of deeply  
37 burrowing animals and deep-rooted plants by using herbicide or by physical removal (cost for  
38 these items are not included).

1 Site radiation surveys: For costing purposes, sites 1 acre or smaller are assumed to cost \$8,712  
 2 for every surveying event. An additional \$1,000 will be required for site radiation surveys for  
 3 every additional 5,000 ft<sup>2</sup> of site area above 1 acre.

- 4 • Area of representative site = 5,663 ft<sup>2</sup> (see Table D-7)
- 5 = minimum 1 acre
- 6 • Radiation surveys of surface soil = \$8,712/event (\$1,000/5,000 ft<sup>2</sup>).

7 Physical site inspection: For costing purposes, sites 1 acre (43,560 ft<sup>2</sup>) or smaller are assumed to  
 8 require a team of two inspectors to perform the activities associated with site inspection and  
 9 surveillance. An additional crew time will be needed for site inspection and surveillance for site  
 10 areas larger than 1 acre.

11 The cost for site inspection and surveillance is based on the following.

- 12 • Area of representative site = 5,663 ft<sup>2</sup> (see Table D-7)
- 13 = minimum 1 acre
- 14 • Cost to complete inspection = \$781/acre.

16 **Existing Cover Maintenance:** The cost associated with existing cover maintenance is an  
 17 operation and maintenance cost. This cost will be incurred annually as long as the alternative is  
 18 being used. Because cover maintenance is performed annually, including costs for replacing all  
 19 or large portions of the existing cover at specified intervals is unnecessary. Rather, cover  
 20 maintenance is assumed to include replacing cover soils over 10 percent of the area to a depth of  
 21 2 ft. The soil used to repair the existing cover is a silt loam and pea gravel mixture. The pea  
 22 gravel is used to make the soil resistant to wind erosion.

23 For costing purposes, it is assumed that the silt loam can be acquired for no material cost from an  
 24 on site borrow source (Area C) and that pea gravel must be purchased at an offsite location.  
 25 Both materials (silt loam and pea gravel) must be mixed before being transported and placed at  
 26 the site. It is assumed that periodically a large volume of silt and pea gravel will be mixed and  
 27 stockpiled by a subcontractor at Area C. This mixture will be for the repair of barrier surfaces.  
 28 The material and transportation cost of pea gravel, excavation and hauling of the silt, and the  
 29 blending and stockpiling are estimated to cost \$8.95/CY for the mixture in stockpile at Area C.

30 For representative sites whose area are greater than 100,000 ft<sup>2</sup>, it is assumed for transporting the  
 31 silt loam/pea gravel mixture to the waste site, that one front end loader, with operator will load  
 32 dump trucks for transportation to the site. To transport the silt loam to the site, it is assumed that  
 33 five dump trucks and five drivers will be used and each dump truck will be able to make 2 trips  
 34 an hour to the site carrying 12 yd<sup>3</sup> per trip. For representative sites less than 100,000 ft<sup>2</sup> in size,  
 35 one front end loader with one operator will directly load 2 dump trucks making 2 trips an hour to  
 36 the site.

37 Once the material is at the waste site it is assumed that the silt loam/pea gravel mixture will be  
 38 unloaded at the repair area and spread with a LGP dozer over the area. A 3,000-gal water truck  
 39 will be used for dust control during the spreading process. For sites with areas less than  
 40 100,000 ft<sup>2</sup> one LGP dozer will be used. For sites with areas greater than 100,000 ft<sup>2</sup>, two LGP  
 41 dozers will be used. Once the silt loam and pea gravel is in place these areas will need to be  
 42 revegetated. It is assumed that a revegetation crew can reseed a one acre in an hour.

1 In addition to the transportation, spreading, and revegetation costs, it is assumed that FH will  
2 have a site engineer on site during cover maintenance activities to provide oversight.

3 For planning purposes the repair of a 1-acre waste site will require 323 yd<sup>3</sup> of silt loam/pea  
4 gravel mixture, 3 hours to load and transport, 4 hours to spread, and one hour to reseed. With  
5 supervisory over site the cost per acre is \$5,728. Waste sites less than 1 acre in size are assumed  
6 to cost the same as one acre.

7 The cover maintenance costs are calculated as follows:

- 8     • Cover maintenance (footprint of cover)
- 9         - Area of cover system                                 = 0.13 Acres
- 10   = minimum 1 acre
- 11         - Area requiring repair (10% of total area)     = 484 yd<sup>2</sup>
- 12         - Volume of cover repair (2 ft)                     = 323 yd<sup>3</sup>
- 13         - Oversight   = 3 hours.

14 **Monitoring for Natural Attenuation:** The cost associated with natural attenuation monitoring  
15 is an operation and maintenance cost. This cost will be incurred annually as long as the  
16 alternative is being used. The cost for natural attenuation monitoring includes spectral gamma  
17 logging of vadose zone boreholes.

18 Vadose zone monitoring costs assume spectral gamma logging of one borehole per waste site to  
19 a depth of 50 ft once every 5 years. The service life of a vadose zone borehole is assumed to be  
20 30 years. Therefore, every 30 years a replacement borehole will be drilled. Costs are based on  
21 the following:

- 22     • Unit cost for vadose zone monitoring = \$75/ft of borehole
- 23     • Length of borehole drilling                             = 50 ft
- 24     • Cost of vadose zone monitoring                         = \$75/ft x 50 ft = \$3,750
- 25     • Installation cost of borehole                           = \$50/ft of borehole
- 26     • Length of borehole installation                       = 50 ft
- 27     • Cost of borehole installation                         = \$50/ft x 50 ft = \$2,500
- 28     • Oversight (assumption)                                 = 1 day = 8 hours (\$56/h).

29 Other costs associated with installing replacement boreholes are included on the cost estimate  
30 sheets. These items include, but are not limited to, mobilization of a drill rig, decontamination of  
31 a drill rig, and handling of investigation derived waste (IDW).

32 **Reporting:** Annual and periodic activities will be recorded in an annual report. The report will  
33 contain descriptions of activities that occurred during the year. Reports will contain all  
34 appropriate/required backup and material purchase information. The cost for the annual reports  
35 is based on the following assumption:

- 36     • Annual reports   = \$10,000/report.

1 **Site Reviews:** The cost associated with site reviews is an operation-and-maintenance cost. This  
 2 cost will be incurred every 5 years as long as the alternative is being used. Site reviews will be  
 3 conducted to assess site conditions and to evaluate the selected alternative and determine  
 4 whether additional steps toward remediation are required. The cost for the five year site reviews  
 5 is based on the following assumption:

- 6 • 5-year site review = \$20,000/review.

7 **Monitoring:** Monitoring includes collecting groundwater samples from down-gradient wells to  
 8 evaluate the performance of the cap system. Refer to Section D3.1.4.

### 9 **D3.3 ALTERNATIVE 3 – REMOVAL, TREATMENT, AND DISPOSAL**

10 Trenches and cribs are excavated to the required depth and contaminated material is removed to  
 11 the Environmental Restoration Disposal Facility (ERDF) for disposal. The sites are then  
 12 remediated.

#### 13 **General Assumptions**

14 The general assumptions for Alternative 3 are as follows:

15 D3.3.1.1 The field work such as mobilization/demobilization, excavation, backfill,  
 16 revegetation, and some of the post construction work will be contracted to a Fixed  
 17 Price Contractor (FP). The Project Management, Radiological Control Technician  
 18 (RCT) support, sampling, and Safety oversight will be performed by FH. The waste  
 19 disposal work involved with hauling from the site to ERDF and ERDF dumping  
 20 cost/fees will be performed by the Environmental Restoration Contractor responsible  
 21 for ERDF.

22 D3.3.1.2 Mobilization and Start Up include site training, mobilization of equipment and  
 23 personnel, installing temporary construction fences, construction of staging/container  
 24 storage areas and access roads, setting up office, change, and storage trailers with  
 25 utilities, truck scales, temporary survey buildings, and decontamination areas.

26 D3.3.1.3 For excavation sites that will have contaminated waste removed to a maximum depth  
 27 of 62 feet. The sides of the excavation will be sloped at 1.5:1 to the bottom of the  
 28 excavation; except for those sites that were originally constructed using 2:1 slopes.  
 29 For sites where the total depth of excavation is less than 5 ft the sloping of the sides of  
 30 the excavation is not required. During the removal process heavy equipment will be  
 31 kept out of the excavation site.

32 D3.3.1.4 For excavation sites overburden will be removed with a 2-3 yd<sup>3</sup> excavator, and two  
 33 haul trucks. The soil will be stockpiled near by the waste site. A highway truck with  
 34 water tank trailer is used to control dust during this activity. The production rate for  
 35 one crew is 127 yd<sup>3</sup>/h.

36 D3.3.1.5 Contaminated waste will be excavated using a 2-3 yd<sup>3</sup> hydraulic crawler excavator.  
 37 The contaminated soil will be directly placed into lined ERDF Containers and hauled  
 38 from the excavation site. A highway truck with water tank trailer is used to control  
 39 dust during this activity. Depending on the volume of waste to move, one to four  
 40 crews can be working at a site. Crew labor is made up of one operator, one laborer,

1 and one truck driver. The production rate for one crew is 55 yd<sup>3</sup>/h. An FH RCT  
2 supports the work at 1 ½ hours per excavation crew hour.

3 D3.3.1.6 Air sampling will be performed during the excavation of contaminated soil. A  
4 minimum of two samples will be taken per day. Planning cost per sample is  
5 \$520 each. The sampling crew is made up of one sampler and RCT.

6 D3.3.1.7 Soil samples will be taken of the overburden, from ERDF containers, and for  
7 verification that the completion of the excavation. The soil sampling cost developed  
8 as follows:

9 • Non Contaminated Soil sampling

- 10 ○ Maximum of 6 samples or 1 sample per yd<sup>3</sup> which ever is less.
- 11 ○ Quality Assurance (QA) sample required is 1
- 12 ○ The planning cost per sample is \$754/sample
- 13 ○ The soil being sampled is the overburden that is uncontaminated and will not be  
14 removed from the site.

15 • Sampling required for waste going to ERDF:

- 16 ○ One sample is required for every 70 containers
- 17 ○ There will be a minimum of 6 samples per site
- 18 ○ QA samples required is a minimum of 1 or 5% of total of ERDF samples which  
19 ever is greater.
- 20 ○ The planning cost per sample is \$452/sample

21 • Pre - Verification Process sampling

- 22 ○ One sample will be required per 2500 sq m (50m x 50m)(26899 sf)
- 23 ○ There will be a minimum of 6 samples per site
- 24 ○ QA samples required are a minimum of 2 or 5% of total the samples which ever is  
25 greater
- 26 ○ The planning cost per sample is \$1,146/sample
- 27 ○ These samples are the preliminary samples needed to see if all of the required  
28 waste has been removed from a site being excavated.
- 29 ○ This process is expected to happen twice during the excavation process.
- 30 ○ If the samples show that the site has met the requirement then the Verification  
31 Process will start.

32 • Verification Process Sampling

- 33 ○ One sample will be required per 625 sq m (25m x 25m)(6724 sf)
- 34 ○ There will be a minimum of 6 samples per site
- 35 ○ QA samples required are a minimum of 2 or 5% of total the samples which ever is  
36 greater

- 1           ○ The planning cost per sample is \$1,404/sample
- 2           ○ These samples are the final samples needed to see if all of the required waste has
- 3           been removed from a site being excavated
- 4           ○ This process happens once during the excavation process.
- 5       • Sampling Crews
- 6           ○ Verification Sampling – 1 hour for each sample taken by a crew made up of one
- 7           FH RCT and sampler technician.
- 8           ○ Other sampling (Air, ERDF, Non Contaminated) – 1 hour for each sample taken
- 9           by a crew made up of one FH RCT and sampler technician.
- 10 D3.3.1.8 The ERDF Container handling and loading process starts with a site haul truck
- 11 picking up an empty container at the staging area. The container is moved to a
- 12 preparation area where laborers install a bed liner and it is inspected by a ½ time
- 13 RCT. The haul truck and container proceed to the loading area. After loading the
- 14 liner is sealed and the container is secured by laborers. The container is moved to the
- 15 survey building where a team of three RCTs inspect and survey the container and
- 16 truck for contamination. From there the haul truck and container are weighed on a
- 17 platform scale and then driven to the storage area. The container is unloaded from the
- 18 truck at the storage area. Three trucks are required to support each contaminated
- 19 excavation crew.
- 20 D3.3.1.9 ERDF disposal fee, transportation, and handling costs are estimated at \$980 per
- 21 container. An Environmental Restoration Contractor driver and truck/trailer will
- 22 move a loaded container to ERDF and place an empty container in the staging area.
- 23 The estimated costs include the rental of the containers used. For planning purposes
- 24 the capacity of an ERDF container is 11 bank yd<sup>3</sup> or 12.7 loose yd<sup>3</sup> of contaminated
- 25 waste.
- 26 D3.3.1.10 Backfilling is performed by three different operations:
- 27       • The moving of the stockpiled overburden back to the excavation site will require one
- 28 crew. The equipment used by a crew is one 4-5 yd<sup>3</sup> loader, and two haul trucks. Labor is
- 29 one operator, and two truck drivers. The production rate for one crew is 185 yd<sup>3</sup>/h.
- 30       • The moving of borrow material to the excavation site is typically performed by one crew
- 31 hauling from an on site pit source. The equipment used by a crew is one 4-5 yd<sup>3</sup> loader,
- 32 six 20 yd<sup>3</sup> highway truck/trailers and one water truck. Labor is one operators, and seven
- 33 truck drivers. The production rate for one crew is 185 yd<sup>3</sup>/h.
- 34       • Spreading and compaction of the backfill at the site is performed by one crew. The
- 35 equipment used per crew is one 300-hp dozers, and one 6,000-gal water truck/trailer.
- 36 Labor is made up of one operator, one truck driver, and one laborer. The production rate
- 37 for one crew is 185 yd<sup>3</sup>/h.
- 38 D3.3.1.11 Revegetation of the waste site includes planting native dry land grass using tractors
- 39 with seed drills and hand broadcasting, hand planting sage brush seedlings, and
- 40 irrigation four times in the spring or early summer. All disturbed areas such as the
- 41 waste site, stockpile, staging areas and access roads are to be replanted.

- 1 D3.3.1.12 The FH Project Management team is made up of a part time project manager, with a  
 2 full time field supervisor, and part time engineering support. QA, Rad Con, and  
 3 Safety also provide oversight along with other support for contract management, and  
 4 project controls. Total hours for this staff are planned at 22.5 hours per day. The  
 5 duration of this work is based on total project duration.
- 6 D3.3.1.13 The Fix Price Contractor field supervisory team is made up of a full construction  
 7 manager and field supervisor, along with part time QA, construction safety, and  
 8 clerical support. Two pickup trucks are included in the cost. Total hours for this staff  
 9 are planned at 21 hours per day. The duration of this work is based on total project  
 10 duration.
- 11 D3.3.1.14 Demobilization include demobilization of equipment and personnel, removing  
 12 temporary construction fences, construction of staging/container storage areas, access  
 13 roads, office/change/storage trailers, truck scales, temporary survey buildings, and  
 14 decon areas.
- 15 D3.3.1.15 Excavation and backfill quantities listed below are based on loose or truck cubic  
 16 yards. The swell factor used is 15%.

### 17 D3.3.1 Representative Site 216-A-29 Ditch

18 The site work is estimated to 117 working days based on the following breakdown. Time  
 19 required for remedial engineering, proposal/bidding/selection process, and startup  
 20 submittals/permits is in addition to the times shown.

- 21 • Mobilization: 10 days to mobilize personnel, equipment, and materials, construction  
 22 staging areas with roads, installing temporary trailers with utilities, setting up survey  
 23 buildings and decontamination sites.
- 24 • Excavate contaminated and uncontaminated soil: 57 days
- 25 • Restore site: 40 days to backfill and revegetation of site
- 26 • Demobilize: 10 days

27 Total construction duration = 117 days = 23.4 weeks = 5.6 months

28 **Site Description:** The basis for the following information can be found on Table D-7):

- 29 • Area of contamination: 2698 ft X 6 ft = 16,188 sq ft
- 30 • Depth of clean overburden: 0 to 6 ft below ground surface
- 31 • Total excavated depth: 7 to 17 ft below ground surface
- 32 • Volume of contaminated soil to be removed: 4,361 yd<sup>3</sup>
- 33 • Total excavated volume (1.5:1 side slopes): 45,117 yd<sup>3</sup>
- 34 • Volume of clean overburden: 40,756 yd<sup>3</sup>
- 35 • Volume of borrow from onsite source: 4,361 yd<sup>3</sup>

36 **Mobilization and Demobilization:** The activities involved in mobilizing and demobilizing  
 37 personnel, equipment, and other startup work have been broken down in to several categories.

1 Typical heavy equipment mobilized to and demobilized from the site is:

- 2 • one large dozer
- 3 • one 2-3 yd<sup>3</sup> excavator
- 4 • one 4-5 yd<sup>3</sup> wheel loader
- 5 • six off highway dump trucks
- 6 • backhoe loader
- 7 • two farm tractors
- 8 • motor grader
- 9 • six semi tractors and 20 yd<sup>3</sup> bottom dump trailers
- 10 • two 4,000 to 6,000-gal water trucks
- 11 • one flatbed truck
- 12 • three trucks with tilt container beds
- 13 • revegetation equipment-seed drill, mulcher, and tiller.

14 The cost of moving equipment 35 miles from a commercial storage yard to the waste site is  
15 planned at \$5,950 to mobilize. The cost to demobilize is planned at \$16,947, which also includes  
16 the decontamination of the equipment included, along with moving the equipment to the storage  
17 yard. This includes the FP labor to clean the equipment. The FH RCT labor hours support to  
18 decontamination of the construction equipment 40 hours, which is planned at \$2,565.

19 Contractor personnel are given training before the start of work at the site. The cost of training is  
20 planned at \$28,420. The training will meet site requirements to work at a waste site. The four  
21 typical crews were used to calculate the cost of training.

22 The contractor will setup or construct a temporary staging area, two office trailers, change trailer,  
23 storage container, truck scales, and survey building at a cost of \$58,768. The rental cost of the  
24 trailers, scales and utilities are also included and are based on the duration of the work. Site  
25 access roads will also be constructed at a cost of \$8,393. Decon areas will be setup as part of the  
26 site mobilization at a cost of \$47,194. The staging area and roads will be scarified as part of  
27 demobilization and the planning costs is \$882. The decon areas will also be removed at planning  
28 cost of \$21,454. The office trailers, truck scales, storage containers will be remove by contractor  
29 or off site vender and are considered part to the rental cost.

30 A temporary fence is constructed around the waste site work area. It will be a steel post with  
31 orange mesh fabric. The planning cost for this site is \$21,418 to construct and \$4,273 to remove.

32 Before remediation work starts at the waste site, a boundary/topog/location survey is performed  
33 by the contractor. The planning cost for this work is \$9,775 and is based on the area of the waste  
34 site.

35 **Monitoring and Sampling:** FH will perform all sampling required.

36 Soil sampling (non contaminated soil, ERDF certification, Pre Verification, Verification  
37 samples). See D3.3.1 General Assumption for sampling rate and process.

- 1     • Non contaminated samples (includes QA samples): 7 samples
- 2     • ERDF Certification samples(includes QA samples): 7 samples
- 3     • Pre Verification samples(includes QA samples): 16 samples
- 4     • Verification samples (includes QA samples): 16 samples
- 5     • Soil Sampling Cost: \$56,534

6 Air Sampling (Industrial and Environmental) See assumption for sampling rate.

- 7     • Industrial Air Samples: 184 samples
- 8     • Quarterly Environmental Permit Samples: 6 samples
- 9     • Air Sampling Cost: \$113,432

10 Field Sampling FH Crew Support

- 11     • Sampling crew: 220 hours
- 12     • Sampling crew cost: \$25,284.

13 **Site Work:** This activity covers the backfilling of the site with the overburden soil and soil  
14 hauled from an on site borrow source. There are three items of work for this activity: Loading  
15 and hauling the overburden, Loading and hauling the borrow soil, and spreading backfill at the  
16 site. Dust control is included in this work. See D3.3.1 General Assumptions for crews and  
17 production rates. For this site one crew working one shift per day has been used to for the  
18 planned work. Miscellaneous site cleanup covers the labor and equipment to cover a work area  
19 cleanup on a weekly basis. Overburden, borrow and backfill quantities are based on loose or  
20 truck cubic yards.

- 21     • Load/ Haul Overburden Volume: 46,870 yd<sup>3</sup>
- 22     • Planning cost to Load/ Haul Overburden: \$101,412
- 23     • Load/ Haul Borrow Soil Volume: 5016 yd<sup>3</sup>
- 24     • Planning cost to Load/ Haul Borrow Soil: \$29,918
- 25     • Spread Backfill/Compaction Volume: 51,886 yd<sup>3</sup>
- 26     • Planning cost to Spread Backfill/Compaction: \$115,418
- 27     • Miscellaneous Clean up Duration: 28 weeks
- 28     • Planning cost for Miscellaneous Clean up: \$11,184

29 Site Revegetation is part of Site Restoration. This work covers the seeding of native dry land  
30 grasses; planting sage brush and irrigation for four times during the spring and early summer  
31 months. The areas to be re-vegetated include the waste site, overburden stockpile, staging areas  
32 and access roads.

- 33     • Total area to be re-vegetated: 11 acres
- 34     • Planning cost for reseeded: \$12,894

- 1 • Planning cost for planting sagebrush: \$14,408

- 2 • Planning cost for Irrigation: \$67,370

### 3 **Soil Excavation:**

- 4 • Excavation: The work activities covered by Excavation include stripping and stockpiling  
5 overburden soil, and excavation of contaminated soil. The contaminated soil is placed  
6 directly into the ERDF containers. The moving from of the containers from excavation  
7 site and processing of the containers is covered in the section Container Loading and  
8 Handling Process. Dust suppression is included in each activity. A description of how the  
9 work is performed is discussed in D3.3.1 General Assumptions. For this site one crew  
10 working one shift per day has been used to for the planned work. Overburden, and  
11 contaminated soil quantities are based on loose or truck cubic yards.

- 12 ○ Overburden soil removed and stockpiled: 46,870 yd<sup>3</sup>

- 13 ○ Planning cost to remove overburden: \$205,247

- 14 ○ Excavation of contaminated soil: 5,016 yd<sup>3</sup>

- 15 ○ Planning cost to excavate contaminated soil: \$26,341

- 16 ○ RCT support for soil excavation: 387 hours

- 17 ○ RCT Excavation support cost: \$37,232

- 18 ○ FH Industrial Safety support: 448 hours

- 19 ○ FH Industrial Safety cost: \$30,957

- 20 • Container Loading and Handling Process: This activity involves installing liners in  
21 containers, hauling the containers to a survey area, weighing, unloading at a temporary  
22 storage area. See D3.3.1 General Assumption for detail of how the work is performed.  
23 For this site one crew working one shift per day has been used to for the planned work.

- 24 ○ Number of ERDF Containers hauled, weigh, processed: 390 containers

- 25 ○ The planning cost for hauling and securing the containers is \$36,418

- 26 ○ The planning cost for preparing containers for loading is \$18,485

- 27 ○ The planning cost for weighing and storing containers: \$35,384

- 28 ○ RCT support for Queue operations survey: 65 hours

- 29 ○ RCT support for Queue operations planning cost: \$2,085

- 30 ○ RCT support for container radiation surveying: 65 hours

- 31 ○ RCT support for container radiation surveying planning cost: \$12,506

- 32 • ERDF Transportation and Disposal: The planning cost for disposal and transportation is  
33 \$882 per container without overhead charges. This cost includes the disposal fee, the  
34 transportation cost from the wastes site staging area to ERDF, and the replacement of the  
35 loaded container with an empty container at the staging area.

- 36 ○ Total number of containers required: 390 containers

- 1           o Cost of containers: \$402,774
- 2   **Construction Staff:** The contractor will have a field staff to manage the work at the site. See  
3 D3.3.1 General Assumption for a description of the crew and trucks. The duration of this work is  
4 based on total project duration. Prepare Final D&D Report covers the cost of the contractor to  
5 turn over submittals required to close out the work. This activity is considered a lump sum cost  
6 to the project.
- 7           • Duration of project: 117 days
- 8           • Planning cost for Field management: \$336,552
- 9           • Planning cost for Final D&D Report: \$9,780
- 10 **Fluor Hanford Project Management:** FH will provide oversight for the duration of the  
11 construction activities (mobilization through demobilization). See D3.3.1 for a description of the  
12 crew. Prepare Final D&D Report covers the cost of the as built documentation process for FH.  
13 This activity is considered lump sum cost to the project. The final site survey by FH survey team  
14 is part of the as built process and is based on the area of the waste site.
- 15           • Duration of project management: 117 days
- 16           • Project management cost: \$216,863
- 17           • Planning cost for Final D&D Report: \$2,342
- 18           • Area of Final Site Survey: 11 acres
- 19           • Planning cost for Final Site Survey: \$4,312
- 20 **Annual Cost:** No annual costs are associated with Alternative 3. No site monitoring is required  
21 because all of the contaminated waste will be removed.
- 22 **D3.3.2 Representative Site 216-S-10 Ditch**
- 23 The site work is estimated to 25 working days based on the following breakdown. Time required  
24 for remedial engineering, proposal/bidding/selection process, and startup submittals/permits is in  
25 addition to the times shown.
- 26           • Mobilization: 10 days to mobilize personnel, equipment, and materials, construction  
27 staging areas with roads, installing temporary trailers with utilities, setting up survey  
28 buildings and decontamination sites.
- 29           • Excavate contaminated and uncontaminated soil: 2 days
- 30           • Restore site: 3 days to backfill and revegetation of site
- 31           • Demobilize: 10 days
- 32 Total construction duration = 25 days = 5 weeks = 1.2 months
- 33 **Site Description:** The basis for the following information can be found on Table D-7)
- 34           • Area of contamination: 958 ft X 6 ft = 5,748 sq ft
- 35           • Depth of clean overburden: 0 ft below ground surface
- 36           • Total excavated depth: 1.5 to 4 ft below ground surface

- 1 • Volume of contaminated soil to be removed: 523 yd<sup>3</sup>
- 2 • Total excavated volume ( no side slopes): 523 yd<sup>3</sup>
- 3 • Volume of clean overburden: 0 yd<sup>3</sup>
- 4 • Volume of borrow from onsite source: 523 yd<sup>3</sup>

5 **Mobilization and Demobilization:** The activities involved in mobilizing and demobilizing  
6 personnel, equipment, and other startup work have been broken down in to several categories.

7 Typical heavy equipment mobilized to and demobilized from the site is:

- 8 • one large dozer
- 9 • one 2-3 yd<sup>3</sup> excavator
- 10 • one 4-5 yd<sup>3</sup> wheel loader
- 11 • six off highway dump trucks
- 12 • backhoe loader
- 13 • two farm tractors
- 14 • motor grader
- 15 • six semi tractors and 20 yd<sup>3</sup> bottom dump trailers
- 16 • two 4,000 to 6,000-gal water trucks
- 17 • one flatbed truck
- 18 • three trucks with tilt container beds
- 19 • revegetation equipment -seed drill, mulcher & tiller

20 The cost of moving equipment 35 miles from a commercial storage yard to the waste site is  
21 planned at \$5,950 to mobilize. The cost to demobilize is planned at \$16,947, which also includes  
22 the decontamination of the equipment included, along with moving the equipment to the storage  
23 yard. This includes the FP labor to clean the equipment. The FH RCT labor hours support to  
24 decontamination of the construction equipment 40 hours, which is planned at \$2,565.

25 Contractor personnel are given training before the start of work at the site. The cost of training is  
26 planned at \$28,420. The training will meet site requirements to work at a waste site. The four  
27 typical crews were used to calculate the cost of training.

28 The contractor will setup or construct a temporary staging area, two office trailers, change trailer,  
29 storage container, truck scales, and survey building at a cost of \$38,712. The rental cost of the  
30 trailers, scales and utilities are also included and are based on the duration of the work. Site  
31 access roads will also be constructed at a cost of \$8,226. Decon areas will be setup as part of the  
32 site mobilization at a cost of \$47,194. The staging area and roads will be scarified as part of  
33 demobilization and the planning costs is \$882. The decon areas will also be removed at planning  
34 cost of \$21,454. The office trailers, truck scales, storage containers will be remove by contractor  
35 or off site vender and are considered part to the rental cost.

36 A temporary fence is constructed around the waste site work area. It will be a steel post with  
37 orange mesh fabric. The planning cost for this site is \$8,217 to construct and \$1,639 to remove.

1 Before remediation work starts at the waste site, a boundary /topog /location survey is performed  
2 by the contractor. The planning cost for this work is \$2,665 and is based on the area of the waste  
3 site.

4 **Monitoring and Sampling:** FH will perform all sampling required.

5 Soil sampling (non contaminated soil, ERDF certification, Pre Verification, Verification  
6 samples). See D3.3.1 General Assumption for sampling rate and process.

7 • Non contaminated samples (includes QA samples): 1 samples

8 • ERDF Certification samples(includes QA samples): 2 samples

9 • Pre Verification samples(includes QA samples): 16 samples

10 • Verification samples (includes QA samples): 8 samples

11 • Soil Sampling Cost: \$35,850

12 **Air Sampling (Industrial and Environmental)** See assumption for sampling rate.

13 • Industrial Air Samples: 4 samples

14 • Quarterly Environmental Permit Samples: 4 samples

15 • Air Sampling Cost: \$4,776

16 **Field Sampling FH Crew Support**

17 • Sampling crew: 8 hours

18 • Sampling crew cost: \$2,027

19 **Site Work:** This activity covers the backfilling of the site with the overburden soil and soil  
20 hauled from an on site borrow source. There are three items of work for this activity: Loading  
21 and hauling the overburden, Loading and hauling the borrow soil, and spreading backfill at the  
22 site. Dust control is included in this work. See D3.3.1 General Assumptions for crews and  
23 production rates. For this site one crew working one shift per day has been used to for the  
24 planned work. Miscellaneous site cleanup covers the labor and equipment to cover a work area  
25 cleanup on a weekly basis. Overburden, borrow and backfill quantities are based on loose or  
26 truck cubic yards.

27 • Load/ Haul Overburden Volume: 0 yd<sup>3</sup>

28 • Planning cost to Load/ Haul Overburden: \$0

29 • Load/ Haul Borrow Soil Volume: 602 yd<sup>3</sup>

30 • Planning cost to Load/ Haul Borrow Soil: \$3,590

31 • Spread Backfill/Compaction Volume: 602 yd<sup>3</sup>

32 • Planning cost to Spread Backfill/Compaction: \$1,339

33 • Miscellaneous Clean up Duration: 6 weeks

34 • Planning cost for Miscellaneous Clean up: \$2,396

1 Site Revegetation is part of Site Restoration. This work covers the seeding of native dry land  
 2 grasses; planting sage brush and irrigation for four times during the spring and early summer  
 3 months. The areas to be re-vegetated include the waste site, overburden stockpile, staging areas  
 4 and access roads.

- 5 • Total area to be re-vegetated: 5 acres
- 6 • Planning cost for reseeded: \$5,861
- 7 • Planning cost for planting sagebrush: \$6,549
- 8 • Planning cost for Irrigation: \$30,622

#### 9 **Soil Excavation:**

- 10 • Excavation: The work activities covered by Excavation include stripping and stockpiling  
 11 overburden soil, and excavation of contaminated soil. The contaminated soil is placed  
 12 directly into the ERDF containers. The moving from of the containers from excavation  
 13 site and processing of the containers is covered in the section Container Loading and  
 14 Handling Process. Dust suppression is included in each activity. A description of how the  
 15 work is performed is discussed in D3.3.1 General Assumptions. For this site one crew  
 16 working one shift per day has been used to for the planned work. Overburden, and  
 17 contaminated soil quantities are based on loose or truck cubic yards.
  - 18 ○ Overburden soil removed and stockpiled: 0 yd<sup>3</sup>
  - 19 ○ Planning cost to remove overburden: \$0
  - 20 ○ Excavation of contaminated soil: 602 yd<sup>3</sup>
  - 21 ○ Planning cost to excavate contaminated soil: \$3,161
  - 22 ○ RCT support for soil excavation: 8 hours
  - 23 ○ RCT Excavation support cost: \$769
  - 24 ○ FH Industrial Safety support: 16 hours
  - 25 ○ FH Industrial Safety cost: \$1,105
- 26 ■ Container Loading and Handling Process: This activity involves installing liners in  
 27 containers, hauling the containers to a survey area, weighing, unloading at a temporary  
 28 storage area. See D3.3.1 General Assumption for detail of how the work is performed.  
 29 For this site one crew working one shift per day has been used to for the planned work.
  - 30 ○ Number of ERDF Containers hauled, weigh, processed: 47 containers
  - 31 ○ The planning cost for hauling and securing the containers is \$4,376
  - 32 ○ The planning cost for preparing containers for loading is \$725
  - 33 ○ The planning cost for weighing and storing containers: \$1,507
  - 34 ○ RCT support for Queue operations survey: 8 hours
  - 35 ○ RCT support for Queue operations planning cost: \$1,507
  - 36 ○ RCT support for container radiation surveying: 8 hours

- 1       o RCT support for container radiation surveying planning cost: \$1,539
- 2       • ERDF Transportation and Disposal: The planning cost for disposal and transportation is
- 3       \$882 per container without overhead charges. This cost includes the disposal fee, the
- 4       transportation cost from the wastes site staging area to ERDF, and the replacement of the
- 5       loaded container with an empty container at the staging area.
- 6       o Total number of containers required: 47 containers
- 7       o Cost of containers: \$55,444

8 **Construction Staff:** The contractor will have a field staff to manage the work at the site. See  
 9 D3.3.1 General Assumption for a description of the crew and trucks. The duration of this work is  
 10 based on total project duration. Prepare Final D&D Report covers the cost of the contractor to  
 11 turn over submittals required to close out the work. This activity is considered a lump sum cost  
 12 to the project.

- 13       • Duration of project: 25 days
- 14       • Planning cost for Field management: \$71,912
- 15       • Planning cost for Final D&D Report: \$9,780

16 **Fluor Hanford Project Management:** FH will provide oversight for the duration of the  
 17 construction activities (mobilization through demobilization). See D3.3.1 General Assumption  
 18 for a description of the crew. Prepare Final D&D Report covers the cost of the as built  
 19 documentation process for FH. This activity is considered lump sum cost to the project. The final  
 20 site survey by FH survey team is part of the as built process and is based on the area of the waste  
 21 site.

- 22       • Duration of project management: 25 days
- 23       • Project management cost: \$46,338
- 24       • Planning cost for Final D&D Report: \$2,342

25 **Annual Cost:** No annual costs are associated with Alternative 3. No site monitoring is required  
 26 because all of the contaminated waste will be removed.

#### 27 **D3.4 ALTERNATIVE 4 – ENGINEERED BARRIER**

28 ET Capillary Barriers will be constructed over the 216-A-29 and 216-S-10 Ditches. For  
 29 planning purposes the side overlap for all types of barriers will be 20 feet for all exterior sides.

##### 30 **D3.4.1 General Assumptions**

31 The general assumptions for Alternative 4 are as follows:

32 D3.4.1.1 The field work such as mobilization/demobilization, borrow site excavation, barrier  
 33 fill, revegetation, and some for the post construction work will be contracted to a FP  
 34 Contractor. The Project Management, RCT support, sampling, and Safety oversight  
 35 will be performed by FH.

36 D3.4.1.2 Mobilization and Start Up include site training, mobilization of equipment and  
 37 personnel, installing temporary construction fences, construction of access roads,  
 38 setting up office, and storage trailers with utilities. Air sampling will be performed

- 1 during the construction of the first layer of the barrier. A minimum of two samples  
2 will be taken per day. Planning cost per sample is \$520 each. The sampling crew is  
3 made up of one sampler and RCT.
- 4 D3.4.1.3 Revegetation of the waste site barrier includes planting native dry land grass using  
5 tractors with seed drills and hand broadcasting, hand planting sage brush seedlings,  
6 and irrigation four times in the spring or early summer. All disturbed areas such as the  
7 around the barrier, stockpile, staging areas and access roads are to be replanted.
- 8 D3.4.1.4 The FH Project Management team is made up of a part time project manager, with a  
9 full time field supervisor, and part time engineering support. QA, Rad Con, and  
10 Safety also provide oversight along with other support for contract management, and  
11 project controls. Total hours for this staff are planned at 22.5 hours per day. The  
12 duration of this work is based on total project duration.
- 13 D3.4.1.5 The FP Contractor field supervisory team is made up of a full construction manager  
14 and field supervisor, along with part time QA, construction safety, and clerical  
15 support. Two pickup trucks are included in the cost. Total hours for this staff are  
16 planned at 21 hours per day. The duration of this work is based on total project  
17 duration.
- 18 D3.4.1.6 Demobilization shall include demobilization of equipment and personnel, removing  
19 temporary construction fences, access roads, and office/storage trailers.
- 20 D3.4.1.7 There are two on site sources for the fill materials to construct the three soil/fill  
21 layers. The source for engineered fill is located at Pit 30 approximately halfway  
22 between 200E and 200W. This pit is assumed to have the sufficient quantity for this  
23 project. The source for the silt required for Layers 1 and 2 is located at area C about  
24 two miles south of 200W.
- 25 D3.4.1.8 The sand, drainage gravel, gravel filter, crushed base course, fractured basalt, and the  
26 asphalt pavement will be supplied by off site vendors or from commercial gravel pits.  
27 These materials are delivered to the waste site by the vendor.
- 28 D3.4.1.9 All barrier sites are considered to have settled and are compacted enough to support  
29 construction of a barrier with out further settling. Dynamic Compaction is not used  
30 for group of barriers.
- 31 D3.4.1.10 Sites that will get an ET Barrier are considered level before the constructing the  
32 barrier. All sites will require pre-leveling before the start of construction of the  
33 barrier. The construction process is the same as the bottom layer of a barrier.
- 34 D.3.4.1.11 The ET/Capillary Barrier will be made up of four different layers.
- 35 • The bottom layer will be constructed of 20 inches of engineered fill. The construction of  
36 the engineered fill requires the excavation of suitable borrow from an on site pit source.  
37 The estimated time to complete the fill is based on the production rate of a of a 4-5 yd<sup>3</sup>  
38 loader excavating at the pit. All material is screened with a grizzly mounted on a surge  
39 bin to remove 4 inch or larger rocks. The six semi tractor trucks with 20 yd<sup>3</sup> bottom dump  
40 trailer trailers are needed to keep up with the loader. A 6000 gal water tanker provides  
41 dust control at the pit. The Production rate for this work is 185 yd<sup>3</sup>/h. The spreading and  
42 compaction equipment used at the barrier is a 250-300-hp Dozer with a U-blade to spread

- 1 fill and two 12 ton vib tandem rollers. Dust control is by a truck with a 6,000-gal water  
2 trailer.
- 3 • To produce a smooth surface to prevent low areas, the surface of engineered fill is fine  
4 graded. Work involves a motor grader, 4-5 yd<sup>3</sup> loader, two 12-ton vib single drum roller,  
5 and water tanker. The production rate is 5,000 yd<sup>2</sup>/day for the engineered fill surface  
6 area. One labourer supports the grader operator as a grade checker. Two engineer  
7 technicians set up the grade and elevation control.
  - 8 • The third layer will be constructed of 6 inches of sand covered with geotextile. Work  
9 covers the spreading, compacting and fine grading of the filter sand used for the third  
10 layer. The sand will come from an off site source. The sand will be delivered by haul  
11 truck spread on the engineered fill layer. The equipment used to construct this layer is a  
12 motor grader, two 12-ton vib tandem rollers and a truck with a 6,000-gal water trailer.  
13 Production Rate for this work is 208 yd<sup>3</sup>/hr. Three equipment operators and one truck  
14 driver operates the equipment. One labourer supports the grader operator as a grade  
15 checker and to help unload trucks truck.
  - 16 • Layer 3 will be fine graded to produce a smooth surface before placement of the  
17 geotextile. Work involves a motor grader, 4-5 yd<sup>3</sup> loader, one 12-ton vib single drum  
18 roller, and water tanker. The production rate is 2500 yd<sup>2</sup>/h for the engineered fill surface  
19 area. One labourer supports the dozer operator and water truck. Two engineer  
20 technicians set up the grade and elevation control.
  - 21 • A geotextile is placed on top of Layer 3. This item of work covers the placement of  
22 needle punched 120 mil polypropylene geotextile over the sand filter layer. The  
23 production rate is 150 yd<sup>2</sup>/h. Three laborers place and splice the fabric.
  - 24 • The second layer will be constructed of 20 inches of silt fill. The construction of this  
25 layer involves excavating and hauling the silt from the on site pit to the barrier. The  
26 production rate is based on a 4-5 yd<sup>3</sup> loader excavating and loading at the pit. There are  
27 six trucks that are 20 yd<sup>3</sup> bottom dump trailer and semi tractor combinations. The  
28 Production rate for this work is 185 yd<sup>3</sup>/h based on the production of the loader. At the  
29 barrier the silt is spread with a 200-250 hp low ground pressure dozer. The silt is  
30 scarified to prevent over compaction. Dust control at the pit and the barrier uses trucks  
31 with a 6,000-gal water trailers.
  - 32 • The top layer will be constructed of 20 inches of silt/pea gravel fill. The fill material is  
33 made up of silt with 15% pea gravel added by weight. The silt is excavated with a 4-5 yd<sup>3</sup>  
34 Loader and hauled from the site silt source by two dump trucks to a process area near the  
35 pit. Pea gravel from an off site source. It is hauled and stockpiled at the silt process area.  
36 A 4-5 yd<sup>3</sup> loader and a pug mill with belt loader are used to mix the silt and gravel. The  
37 hauling from the process area and the spreading of the material is the same as described  
38 for the second layer.
  - 39 • The side slopes of the barrier will be covered with fractured basalt 1 foot deep and  
40 engineered fill 1 foot deep.
    - 41 ○ The side slopes of the barrier are graded before placing any ballast, gravel filter or  
42 fractured basalt. The work involves a 100-150-hp dozer with laser controls,  
43 4-5 yd<sup>3</sup> loader, one 12-ton vib single drum roller, and water tanker. The

1 production rate is 2500 yd<sup>2</sup>/h for the engineered fill surface area. One labourer  
 2 supports the dozer operator and water truck. Two engineer technicians set up the  
 3 grade and elevation control.

- 4 ○ The construction of the ballast and the gravel filter for the side slope follows the  
 5 grading of the side slope. A truck with a water trailer provides dust control. The  
 6 Production rate for this work is 125 yd<sup>3</sup>/h. The spreading and compaction  
 7 equipment used at the barrier to spread fill is a 4-5 yd<sup>3</sup> loader, 100-150-hp dozer  
 8 with laser controls, and one 12-ton vib single drum roller. One laborer supports  
 9 the dozer operator and water truck. Both gravel layers are 6 inches deep. The  
 10 ballast and the gravel filter will come from a commercial source and will be  
 11 delivered and stockpiled at the construction site. The delivered cost for ballast is  
 12 \$19.98/ yd<sup>3</sup> and for gravel filter is \$16.70/ yd<sup>3</sup> based on vendor quotes.
- 13 ○ The fractured basalt with silt layer is the last layer of the side slopes to be  
 14 constructed. The fractured basalt will come from a commercial source and will be  
 15 delivered and stockpiled at the construction site. The delivered cost of the rock is  
 16 based on vendor quotes of \$21.61/yd<sup>3</sup>. The silt will come from the same source as  
 17 Layer 2. The silt will be delivered and stockpiled at the barrier site when the silt  
 18 for Layer 2 is being hauled. One loader and 300-hp dozer are used to place the  
 19 basalt on the fill slope. One laborers support the work. The production rate is  
 20 70 yd<sup>3</sup>/h. A quarter time water truck and driver are used for dust control.

21 D3.4.1.13 Instrumentation is not included for this series of barriers.

22 D3.4.1.14 After completion of the barrier construction work a 4-ft steel post with chain fence is  
 23 to be built around the site. The fence location is at the toe of the barrier slope.

24 D.3.4.1.15 During the construction of the barrier compaction testing will be performed on the  
 25 three layers of fill. The lower level will require that a minimum level of compaction  
 26 has been reached. While the top two layers will be tested to ensure that the fill does  
 27 not become over compacted.

28 D3.3.1.16 The yd<sup>3</sup> quantities listed below are based on loose or truck cubic yards. The swell  
 29 factor used is 15%.

### 30 **D3.4.2 Representative Site 216-A-29 Ditch**

31 The site work is estimated to 112 working days based on the following breakdown. Time  
 32 required for remedial engineering, proposal/bidding/selection process, and startup  
 33 submittals/permits is in addition to the times shown. The construction process will use one crew  
 34 to perform the work.

- 35 • Mobilization: 15 days to mobilize personnel, equipment, and materials, construction  
 36 staging areas with roads, installing temporary trailers with utilities, setting up survey  
 37 buildings and decontamination sites.
- 38 • Capping: 83 days
- 39 • Revegetation: 4 days
- 40 • Demobilize: 10 days

41 Total construction duration = 112 days = 22.4 weeks = 5.6 months

1 **Site Description:** The basis for the following information can be found on Table D-7):

- 2 • Area of waste site contamination:  $2794 \text{ ft} \times 6 \text{ ft} = 16,764 \text{ ft}^2$
- 3 • Area of waste site with 20-ft overlap:  $(2794+(20 \times 2)) \times (6+(20 \times 2)) = 125,948 \text{ ft}^2$
- 4 • Type of Cap: ET Capillary
- 5 • Side Slope of Cap: 3:1
- 6 • Depth of pre leveling required:  $\theta$  3 ft
- 7 • Depth Cap:  $\theta$  5.5 ft
- 8 • Horizontal Side Slope Distance: 22.8 ft
- 9 • Cap foot print length:  $(2794+((20+22.8) \times 2)) = 2880 \text{ ft}$
- 10 • Cap foot print width:  $(6+((20+22.8) \times 2)) = 92 \text{ ft}$
- 11 • Area of Cap foot print:  $2880 \times 92 = 263960 \text{ sq ft}$

12 **Mobilization and Demobilization:** The activities involved in mobilizing and demobilizing  
 13 personnel, equipment, and other startup work have been broken down in to several categories.

14 Typical heavy equipment mobilized to and demobilized from the site is:

- 15 • Large dozer
- 16 • two LPG dozers
- 17 • 2-3CY excavator
- 18 • two 4-5CY wheel loaders
- 19 • Soil Vib Rollers
- 20 • two off highway dump trucks
- 21 • Pug Mill with hoppers and belt loaders
- 22 • two farm tractors
- 23 • motor grader
- 24 • six semi tractors and 20CY bottom dump trailers
- 25 • two 4,000 to 6,000-gal water trucks
- 26 • flatbed truck
- 27 • revegetation equipment -seed drill, mulcher,& tiller

28 The cost of moving equipment 35 miles from a commercial storage yard to the waste site is  
 29 planned at \$25,649 to mobilize and to demobilize.

30 Contractor personnel are given training before the start of work at the site. The cost of training is  
 31 planned at \$9,581. The training will meet site requirements to work at a waste site.

32 The contractor will setup or construct a temporary staging area, office trailers, change trailer, and  
 33 storage container, at a cost of \$ 24,912. The rental cost of the trailers, and utilities are also

1 included and are based on the duration of the work. Site access roads will also be constructed at a  
 2 cost of \$ 8,784. The staging area and roads will be scarified as part of demobilization and the  
 3 planning costs is \$699. The office trailers, storage containers will be removed by contractor or  
 4 off site vender and are considered part to the rental cost.

5 A temporary fence is constructed around the waste site work area. It will be a steel post with  
 6 orange mesh fabric. The planning cost for this site is \$31,851 to construct and \$4,967 to remove.

7 Before remediation work starts at the waste site, a boundary /topog /location survey is performed  
 8 by the contractor. The planning cost for this work is \$20,992 and is based on the area of the  
 9 waste site.

10 **Fluor Hanford Sampling and Crew Support:** FH will perform all sampling required.

11 Air Sampling (Industrial and Environmental) See assumption for sampling rate.

- 12 • Industrial Air Samples: 33 samples
- 13 • Quarterly Environmental Permit Samples: 6 samples
- 14 • FH Sampling crew: 35 hours
- 15 • Air Sampling Cost: \$ 28,874

16 **Site Work:**

- 17 • **Installation of Cap:** Site 216-A-29 Ditch requires an ET Capillary Barrier. The design,  
 18 construction, and production rates for the barrier are discussed above in the General  
 19 Assumptions. The yd<sup>3</sup> quantities are based on loose or truck cubic yard.

20 These areas and volumes will be used for the cost estimates:

- 21 ○ Area (footprint) of Barrier: 264,960 ft<sup>2</sup>
- 22 ○ Pre level Volume: 32,280 yd<sup>3</sup>
- 23 ○ Layer 4 - Volume of engineered fill: 15,035 yd<sup>3</sup>
- 24 ○ Layer 3 – Volume of Sand: 4,105 yd<sup>3</sup>
- 25 ○ Layer 3 – area of geotextile: 21,416 yd<sup>2</sup>
- 26 ○ Layer 2 – Volume of silt: 11,801 yd<sup>3</sup>
- 27 ○ Layer 1 – Volume of silt & pea gravel mixture: 9832 yd<sup>3</sup>
- 28 ○ Side Slope - Volume gravel filter: 2,184 yd<sup>3</sup>
- 29 ○ Side Slope - Volume Ballast: 2,184 yd<sup>3</sup>
- 30 ○ Side Slope – Volume fractured basalt and silt: 6,084 yd<sup>3</sup>
- 31 • The planning costs for the layers are:
  - 32 ○ Pre Level: \$340,692
  - 33 ○ Layer 4 Engineered Fill: \$166,877
  - 34 ○ Layer 3 Sand: \$208,055
  - 35 ○ Layer 2 Silt: \$107,497

- 1       ○ Layer 1 Silt & Pea gravel: \$89,561
- 2       ○ Side Slope: \$712,141
- 3       ○ Silt Pit Process Operations: \$112,131
- 4       ● Other items of work that are involved in the construction of the barrier are construction
- 5       survey/ elevation control, soils compaction testing, site cleanup, construction of a site
- 6       fence, and FHRCT support. Miscellaneous site cleanup covers the labor and equipment
- 7       to cover a work area cleanup on a weekly basis.
- 8       ○ Planning cost for Surveying: \$ 69,072
- 9       ○ Planning cost for Soils Compaction Testing: \$39,369
- 10      ○ Planning cost for Miscellaneous Clean up: \$1,693
- 11      ○ Planning cost for Site Fence: \$29,843
- 12      ○ RCT support for Construction cost: \$35,135
- 13      ● Site Revegetation is part of Site Work. This work covers the seeding of native dry land
- 14      grasses; planting sagebrush and irrigation for four times during the spring and early
- 15      summer months. The areas to be re-vegetated include the waste site cap, construction
- 16      staging areas and temporary access roads.
- 17      ○ Total area to be re-vegetated: 15 acres
- 18      ○ Planning cost for reseeding: \$10,600
- 19      ○ Planning cost for planting sagebrush: \$14,781
- 20      ○ Planning cost for Irrigation: \$75,438
- 21      **Fix Price Contractor Field Management:** The contractor will have a field staff to manage the
- 22      work at the site. See D3.3.1 General Assumption for a description of the crew and trucks. The
- 23      duration of this work is based on total project duration. Prepare Final D&D Report covers the
- 24      cost of the contractor to turn over submittals required to close out the work. The activity is
- 25      considered lump sum cost to the project.
- 26      ● Duration of project: 112 days
- 27      ● Planning cost for Field management: \$405,721
- 28      ● Planning cost for Final D&D Report: \$10,986
- 29      **Fluor Hanford Project Management:** FH will provide oversight for the duration of the
- 30      construction activities (mobilization through demobilization). See D3.4.1 General Assumption
- 31      for a description of the crew. Prepare Final D&D Report covers the cost of the as built
- 32      documentation process for FH. The activity is considered lump sum cost to the project.
- 33      ● Duration of project management: 112 days
- 34      ● Project management cost: \$216,620
- 35      ● Planning cost for Final D&D Report: \$2,342
- 36      **Surveillance and Cap Maintenance:** The costs associated with surveillance and cap
- 37      maintenance are operation and maintenance costs and are incurred annually. The activities

1 performed during surveillance and cap maintenance are expected to be the same as those  
 2 described for site inspection/surveillance and existing cover maintenance cost items under  
 3 Alternative 2. Refer to the Alternative 2 assumptions for these cost items. The surveillance and  
 4 cap maintenance costs are calculated as follows:

5 • Surveillance/inspections (footprint of cap system)

- 6 - Area of cap system = 264,960 ft<sup>2</sup> = 6.1 Acre  
 7 - Team hours to complete inspections = 5.3 days (1 day for every 50,000 ft<sup>2</sup>)  
 8 - Daily inspection rate (2 Techs) = \$896/day (\$56/h/person)  
 9 - Barrier Cover Inspection of surface soil = \$896 X 5.3 days  
 10 = \$4,749/event  
 11 - Radiation surveys of surface soil = \$1,000 for every 5,000 ft<sup>2</sup>  
 12 = \$52,992/event

13 • Cap maintenance (footprint of cap system)

- 14 - Area of cap system = 6.1 Acre  
 15 - Area requiring repair (10% of total area) = 2,952 yd<sup>2</sup>  
 16 - Volume of cap repair (2 ft) = 1969 yd<sup>3</sup>  
 17 - Oversight (soil placement 130 yd<sup>3</sup>/h) = 1.9 days- Oversight (vegetation  
 18 5,000 yd<sup>2</sup>/h) = 0.4 day

19 Oversight performed by one FH Engineer at \$60/h.

20 **Monitoring:** Monitoring includes collecting groundwater samples from down-gradient wells to  
 21 evaluate the performance of the cap system. Refer to Section D3.1.4.

22 **D3.4.3 Representative Site 216-S-10 Ditch**

23 The site work is estimated to 78 working days based on the following breakdown. Time required  
 24 for remedial engineering, proposal/bidding/selection process, and startup submittals/permits is in  
 25 addition to the times shown. The construction process will use one crew to perform the work.

- 26 • Mobilization: 15 days to mobilize personnel, equipment, and materials, construction  
 27 staging areas with roads, installing temporary trailers with utilities, setting up survey  
 28 buildings and decontamination sites.  
 29 • Barrier Construction: 51 days  
 30 • Revegetation: 2 days  
 31 • Demobilize: 10 days

32 Total construction duration = 78 days = 15.6 weeks = 3.7 months

33 **Site Description:** The basis for the following information can be found on Table D-7):

- 34 • Area of waste site contamination: 958 ft X 6 ft = 4,590 ft<sup>2</sup>  
 35 • Area of waste site with 20-ft overlap: (958+(20X2)) X (6+(20X2)) = 45,908 ft<sup>2</sup>

- 1     • Type of Cap: ET Capillary
- 2     • Side Slope of Cap: 3:1
- 3     • Depth of pre leveling required: 9 ft
- 4     • Depth Cap: 5.5 ft
- 5     • Horizontal Side Slope Distance: 22.8 ft
- 6     • Cap foot print length:  $(958 + ((20 + 22.8) \times 2)) = 1044$  ft
- 7     • Cap foot print width:  $(6 + ((20 + 22.8) \times 2)) = 92$  ft
- 8     • Area of Cap foot print:  $1044 \times 92 = 96,048$  ft<sup>2</sup>

9     **Mobilization and Demobilization:** The activities involved in mobilizing and demobilizing  
 10  personnel, equipment, and other startup work have been broken down in to several categories.

11  Typical heavy equipment mobilized to and demobilized from the site is:

- 12     • Large dozer
- 13     • two LPG dozers
- 14     • 2-3CY excavator
- 15     • two 4-5CY wheel loaders
- 16     • Soil Vib Rollers
- 17     • two off highway dump trucks
- 18     • Pug Mill with hoppers and belt loaders
- 19     • two farm tractors
- 20     • motor grader
- 21     • six semi tractors and 20CY bottom dump trailers
- 22     • two 4,000 to 6,000-gal water trucks
- 23     • flatbed truck
- 24     • revegetation equipment - seed drill, mulcher, and tiller.

25  The cost of moving equipment 35 miles from a commercial storage yard to the waste site is  
 26  planned at \$25,649 to mobilize and to demobilize.

27  Contractor personnel are given training before the start of work at the site. The cost of training is  
 28  planned at \$9,581. The training will meet site requirements to work at a waste site.

29  The contractor will setup or construct a temporary staging area, office trailers, change trailer, and  
 30  storage container, at a cost of \$17,247. The rental cost of the trailers, and utilities are also  
 31  included and are based on the duration of the work. Site access roads will also be constructed at a  
 32  cost of \$8,784. The staging area and roads will be scarified as part of demobilization and the  
 33  planning costs is \$699. The office trailers, storage containers will be removed by contractor or  
 34  off site vender and are considered part to the rental cost.

1 A temporary fence is constructed around the waste site work area. It will be a steel post with  
 2 orange mesh fabric. The planning cost for this site is \$13,412 to construct and \$2,091 to remove.  
 3 Before remediation work starts at the waste site, a boundary /topog /location survey is performed  
 4 by the contractor. The planning cost for this work is \$9,142 and is based on the area of the waste  
 5 site.

6 **Fluor Hanford Sampling and Crew Support:** FH will perform all sampling required.

7 **Air Sampling (Industrial and Environmental)** See assumption for sampling rate.

- 8 • Industrial Air Samples: 33 samples
- 9 • Quarterly Environmental Permit Samples: 6 samples
- 10 • FH Sampling crew: 39 hours
- 11 • Air Sampling Cost: \$28,874

12 **Site Work:**

- 13 • **Installation of Cap:** Site 216-S-10 Ditch requires an ET Capillary Barrier. The design,  
 14 construction and production rates for the barrier are discussed above in the General  
 15 Assumptions.

16 These areas and volumes will be used for the cost estimates:

- 17 ○ Area (footprint) of Cap: 96,048 ft<sup>2</sup>
- 18 ○ Pre level Volume: 42,240 yd<sup>3</sup>
- 19 ○ Layer 4 - Volume of engineered fill: 5,390 yd<sup>3</sup>
- 20 ○ Layer 3 – Volume of Sand: 1,466 yd<sup>3</sup>
- 21 ○ Layer 3 – area of geotextile: 7,647 yd<sup>2</sup>
- 22 ○ Layer 2 – Volume of silt: 4,196 yd<sup>3</sup>
- 23 ○ Layer 1 – Volume of silt & pea gravel mixture: 3,474 yd<sup>3</sup>
- 24 ○ Side Slope - Volume gravel filter: 823 yd<sup>3</sup>
- 25 ○ Side Slope - Volume Ballast: 823 yd<sup>3</sup>
- 26 ○ Side Slope – Volume fractured basalt and silt: 2298 yd<sup>3</sup>
- 27 • The planning costs for the layers are:
  - 28 ○ Pre Level: \$445,813
  - 29 ○ Layer 4 Engineered Fill: \$59,825
  - 30 ○ Layer 3 Sand : \$74,292
  - 31 ○ Layer 2 Silt: \$38,222
  - 32 ○ Layer 1 Silt & Pea gravel: \$31,645
  - 33 ○ Side Slope: \$176,807
  - 34 ○ Silt Pit Process Operations: \$39,623

- 1 • Other items of work that are involved in the construction of the barrier are construction
- 2 survey/ elevation control, soils compaction testing, site cleanup, construction of a site
- 3 fence, and FH RCT support. Miscellaneous site cleanup covers the labor and equipment
- 4 to cover a work area cleanup on a weekly basis.
- 5 ○ Planning cost for Surveying: \$27,764
- 6 ○ Planning cost for Soils Compaction Testing: \$30,274
- 7 ○ Planning cost for Miscellaneous Clean up: \$1,69
- 8 ○ Planning cost for Site Fence: \$11,403
- 9 ○ RCT support for Construction cost: \$35,408
- 10 • Site Revegetation is part of Site Work. This work covers the seeding of native dry land
- 11 grasses; planting sagebrush and irrigation for four times during the spring and early
- 12 summer months. The areas to be re-vegetated include the waste site cap, construction
- 13 staging areas and temporary access roads.
- 14 ○ Total area to be re-vegetated: 7 acres
- 15 ○ Planning cost for reseeding: \$4,947
- 16 ○ Planning cost for planting sagebrush: \$6,898
- 17 ○ Planning cost for Irrigation: \$35,204

18 **Fix Price Contractor Field Management:** The contractor will have a field staff to manage the

19 work at the site. See D3.3.1 General Assumption for a description of the crew and trucks. The

20 duration of this work is based on total project duration. Prepare Final D&D Report covers the

21 cost of the contractor to turn over submittals required to close out the work. The activity is

22 considered lump sum cost to the project.

- 23 • Duration of project: 78 days
- 24 • Planning cost for Field management: \$282,555
- 25 • Planning cost for Final D&D Report: \$10,986

26 **Fluor Hanford Project Management:** FH will provide oversight for the duration of the

27 construction activities (mobilization through demobilization). See D3.4.1 General Assumption

28 for a description of the crew. Prepare Final D&D Report covers the cost of the as built

29 documentation process for FH. The activity is considered lump sum cost to the project.

- 30 • Duration of project management: 78 days
- 31 • Project management cost: \$150,861
- 32 • Planning cost for Final D&D Report: \$2,342

33 **Surveillance and Cap Maintenance:** The costs associated with surveillance and cap

34 maintenance are operation and maintenance costs and are incurred annually. The activities

35 performed during surveillance and cap maintenance are expected to be the same as those

36 described for site inspection/surveillance and existing cover maintenance cost items under

37 Alternative 2. Refer to the Alternative 2 assumptions for these cost items. The surveillance and

38 cap maintenance costs are calculated as follows:

- 1 • Surveillance/inspections (footprint of cap system)
- 2 - Area of cap system = 96,048 ft<sup>2</sup> = 2.2 Acre
- 3 - Team hours to complete inspections = 1.9 days (1 day for every 50,000 ft<sup>2</sup>)
- 4 - Daily inspection rate (2 Techs) = \$896/day (\$56/h/person)
- 5 - Barrier Cover Inspection of surface soil = \$896 X 1.9 days
- 6 = \$1702/event
- 7 - Radiation surveys of surface soil = \$1,000 for every 5,000 ft<sup>2</sup>
- 8 = \$19,210/event
- 9 • Cap maintenance (footprint of cap system)
- 10 - Area of cap system = 2.28 Acre
- 11 - Area requiring repair (10% of total area) = 1,067 yd<sup>2</sup>
- 12 - Volume of cap repair (2 ft) = 715 yd<sup>3</sup>
- 13 - Oversight (soil placement 130 yd<sup>3</sup>/h) = 0.7 day
- 14 - Oversight (vegetation 5,000 yd<sup>2</sup>/h) = 0.2 day

15 Oversight performed by one FH Engineer at \$60/h.

16 **Monitoring:** Monitoring includes collecting groundwater samples from down-gradient wells to  
 17 evaluate the performance of the cap system. Refer to Section D3.1.4.

#### 18 D4.0 REFERENCES

- 19 DE-AC06-96RL13200, 1996, *Contract Between the U.S. Department of Energy, Richland*  
 20 *Operations Office, and Fluor Daniel Hanford, Inc.*, U.S. Department of Energy, Richland  
 21 *Operations Office, Richland, Washington, as amended.*
- 22 EPA/540/R-00/002, 2000, *A Guide to Developing and Documenting Cost Estimates During the*  
 23 *Feasibility Study*, OSWER 9355.0-75, U.S. Environmental Protection Agency,  
 24 *Washington, D.C.*
- 25 OMB Circular No. A-94, 2002, *Guidelines and Discount Rates for Benefit-Cost Analysis of*  
 26 *Federal Programs*, Office of Management and Budget, Washington, D.C., as revised.

- 1 Means, R. S., 2001a, *ECHOS Environmental Remediation Cost Data – Unit Price*, 7<sup>th</sup> Annual  
2 Edition, Robert S. Means Company, Kingston, Massachusetts.
- 3 Means, R. S., 2004b, *Facility Construction Cost Data*, 19<sup>th</sup> Annual Edition, Robert S. Means  
4 Company, Kingston, Massachusetts.
- 5 *Site Stabilization Agreement for All Construction Work for the U.S. Department of Energy at the*  
6 *Hanford Site*, 1984, as amended, commonly known as the Hanford Site Stabilization  
7 Agreement (original title, *Site Stabilization Agreement, Hanford Site, between J. A. Jones*  
8 *Construction Services Company and Morrison-Knudsen Company, Inc., and the Building*  
9 *and Construction Trades Department of the AFL-CIO and its affiliated international*  
10 *unions, and the International Brotherhood of Teamsters, Chauffeurs, Warehousemen,*  
11 *and Helpers of America).*

1

Table D-1. 216-A-29 Ditch Alternative 2.

Item	Item Cost				Notes
	Annually	Per 3 Years	Per 5 Years	Per 30 Years	
Existing Cover Inspection	\$781				Cost is based on a two-person crew (8 h/day. It is assumed to require 1 day to inspect sites up to 50,000 ft <sup>2</sup> in size. An additional day is required for each additional 50,000 ft <sup>2</sup> . The site area
Radiation Survey of Site Surface	\$8,712				Cost is based on \$1,000 for every 5,000 ft <sup>2</sup> . The site area
Existing Cover Maintenance	\$5,723				Cost includes the purchase of soil to repair ruts and holes over 10% of the site area
Vadose Zone Monitoring Replacement			\$3,473	\$7,130	Replacement of vadose zone monitoring occurs once every 5 years. Bore hole replacement occurs once every 30 years
Prepare and Issue Sampling Reporting			\$10,000		Obtain lab, prepare sampling plan, document sampling event and results
Site Reviews			\$20,000		Prepare Site Condition Report every 5 years
Ground water monitoring well replacement			\$9,818		Includes the installation, maintenance, and replacement of three monitoring wells
Groundwater sampling and analysis	\$4,180				Represents the non-discounted cost of sampling and analysis in years 1-150

2

1

2

Table D-2. 216-S-10 Ditch Alternative 2.

Item	Item Cost				Notes
	<b>Annually</b>	<b>Per 3 Years</b>	<b>Per 5 Years</b>	<b>Per 30 Years</b>	
Existing Cover Inspection	\$781				Cost is based on a two-person crew (8 h/day). It is assumed to require 1 day to inspect sites up to 50,000 ft <sup>2</sup> in size. An additional day is required for each additional 50,000 ft <sup>2</sup> . The site area -
Radiation Survey of Site Surface	\$8,712				Cost is based on \$1,000 for every 5,000 ft <sup>2</sup> . The site area -
Existing Cover Maintenance	\$5,723				Cost includes the purchase of soil to repair ruts and holes over 10% of the site area.
Vadose Zone Monitoring Replacement			\$3,473	\$7,130	Replacement of vadose zone monitoring occurs once every 5 years. Bore hole replacement occurs once every 30 years.
Prepare and Issue Sampling Reporting			\$10,000		Obtain lab, prepare sampling plan, document sampling event and results.
Site Reviews			\$20,000		Prepare Site Condition Report every 5 years.
Ground water monitoring well replacement			\$9,818		Includes the installation, maintenance, and replacement of three monitoring wells.
Groundwater sampling and analysis	\$4,180				Represents the non-discounted cost of sampling and analysis in years 1-150.

3

Table D-3. 216-A-29 North Ditch – Alternative 3 – Removal, Treatment, and Disposal. (4 Pages)

**FLUOR HANFORD**

DD / FH  
TRENCH TEMPLATE  
EST NO. CS29NT3C

**200-CS-1 FEASIBILITY STUDY**  
**216-A-29 North Ditch - Alt 3 RTD**  
**FT\_R02N - WORK BREAKDOWN STRUCTURE SUMMARY**

PAGE 1  
PRINTED 02/15/2006 9:14 AM  
UPDATED 02/15/2006 9:13 AM  
PREPARED BY BA Gilkeson

EST WBS	ESTIMATE WBS DESCRIPTION	ESTIMATE SUBTOTAL	TOTAL INDIRECTS	SUB TOTAL	ESCALATN TOTAL	ESCAL %	SUB TOTAL	CONT %	CONTGNCY TOTAL	TOTAL AMOUNT
<b>1.03.02 MOBILIZATION / DEMOBILIZATION</b>										
302010301	PERSONNEL TRAINING-BASIC	24,388	4,031	28,420	0	0.00	28,420	0	0	28,420
302020102	WASTE SITE SURVEY	6,863	1,134	7,997	0	0.00	7,997	0	0	7,997
302020203	MOB SITE WORK EQUIPMENT	5,106	844	5,950	0	0.00	5,950	0	0	5,950
302020301	INSTALL TEMP CONST BARRIER	17,117	2,829	19,946	0	0.00	19,946	0	0	19,946
302020302	TEMP OFFICE & FACILITIES	41,826	6,913	48,740	0	0.00	48,740	0	0	48,740
302020304	CONSTRUCT DECON AREA	40,499	6,694	47,194	0	0.00	47,194	0	0	47,194
302020305	TEMP SITE ROAD	7,203	1,190	8,393	0	0.00	8,393	0	0	8,393
302090101	REMOVE TEMP CONST BARRIER	3,414	564	3,979	0	0.00	3,979	0	0	3,979
302090102	REMOVE DECON AREA	18,411	3,043	21,454	0	0.00	21,454	0	0	21,454
302090103	REMOVE ROADS & PARKING	757	125	882	0	0.00	882	0	0	882
302090301	DEMOBILIZE CONSTRUCTION EQUIPMENT	14,543	2,404	16,947	0	0.00	16,947	0	0	16,947
302090304	FH DECON CONSTRUCTION EQUIPMENT SUPPORT	2,201	363	2,565	0	0.00	2,565	0	0	2,565
<b>SUBTOTAL MOBILIZATION / DEMOBILIZATION</b>		<b>182,332</b>	<b>30,138</b>	<b>212,472</b>	<b>0</b>	<b>0.00</b>	<b>212,472</b>	<b>0</b>	<b>0</b>	<b>212,472</b>
<b>1.03.03 MONITORING /SAMPLING</b>										
302030102	SITE AIR MONITORING	46,800	6,931	53,731	0	0.00	53,731	0	0	53,731
302030302	RAD SAMPLING,ANALYSIS-VEG/SEDMSOIL	51,646	7,648	59,294	0	0.00	59,294	0	0	59,294
302030403	FH SAMPLE CREW	11,156	1,844	13,000	0	0.00	13,000	0	0	13,000
<b>SUBTOTAL MONITORING /SAMPLING</b>		<b>109,602</b>	<b>16,423</b>	<b>126,026</b>	<b>0</b>	<b>0.00</b>	<b>126,026</b>	<b>0</b>	<b>0</b>	<b>126,026</b>
<b>1.03.04 SITE WORK</b>										
302080101	LOAD/HAUL OVERBURDEN FROM STOCKPILE	42,011	6,944	48,956	0	0.00	48,956	0	0	48,956
302080102	LOAD/HAUL FROM BORROW SITE	7,114	1,176	8,290	0	0.00	8,290	0	0	8,290
302080201	BACKFILL & COMPACTION	45,844	7,578	53,422	0	0.00	53,422	0	0	53,422
302080301	MECH SEEDING GRASS	10,059	1,662	11,722	0	0.00	11,722	0	0	11,722
302080302	SHRUBS/TREES/GROUND COVER	11,240	1,856	13,096	0	0.00	13,096	0	0	13,096
302080303	IRRIGATION	52,558	8,687	61,245	0	0.00	61,245	0	0	61,245
302090104	MISC CLEANUP	5,484	906	6,390	0	0.00	6,390	0	0	6,390
<b>SUBTOTAL SITE WORK</b>		<b>174,313</b>	<b>28,914</b>	<b>203,127</b>	<b>0</b>	<b>0.00</b>	<b>203,127</b>	<b>0</b>	<b>0</b>	<b>203,127</b>
<b>1.03.05 SOIL EXCAVATION</b>										

Maestro

Master the Art of Estimating

DOE/RL-2005-63 DRAFT A

D-40

Table D-3. 216-A-29 North Ditch – Alternative 3 – Removal, Treatment, and Disposal. (4 Pages)

**FLUOR HANFORD**

DD / FH  
TRENCH TEMPLATE  
EST NO. CS29NT3C

**200-CS-1 FEASIBILITY STUDY**

216-A-29 North Ditch - Alt 3 RTD  
FT\_R02N - WORK BREAKDOWN STRUCTURE SUMMARY

PAGE 2  
PRINTED 02/15/2006 9:14 AM  
UPDATED 02/15/2006 9:13 AM  
PREPARED BY BA Gilkeson

EST WBS	ESTIMATE WBS DESCRIPTION	ESTIMATE SUBTOTAL	TOTAL INDIRECTS	SUB TOTAL	ESCALATN TOTAL	ESCAL %	SUB TOTAL	CONT %	CONTGNCY TOTAL	TOTAL AMOUNT
302040101	UNCONTAMINATED/OVERBURDEN SOIL	85,026	14,054	99,080	0	0.00	99,080	0	0	99,080
302040102	EXCAVATE CONTAMINATED SOIL W/DUST CONTR	6,264	1,035	7,299	0	0.00	7,299	0	0	7,299
302040106	RCT SUPPORT	14,365	2,374	16,740	0	0.00	16,740	0	0	16,740
302040107	INDUSTRIAL SAFETY TECH SUPPORT	12,112	1,708	13,820	0	0.00	13,820	0	0	13,820
302060403	LOAD/HAUL RAD CONT SOIL	8,683	1,435	10,119	0	0.00	10,119	0	0	10,119
302060501	QUEUE AREA OPERATIONS	14,793	2,445	17,238	0	0.00	17,238	0	0	17,238
302060502	FH QUEUE AREA OPERATIONS	522	86	609	0	0.00	609	0	0	609
302060601	LOW ACTIVITY CONTAINERS	4,433	732	5,166	0	0.00	5,166	0	0	5,166
302060603	FH DECONTAMINATE CONTAINERS	3,137	518	3,655	0	0.00	3,655	0	0	3,655
302060801	ERDF DISPOSAL COST	102,976	15,250	118,227	0	0.00	118,227	0	0	118,227
<b>SUBTOTAL SOIL EXCAVATION</b>		<b>252,314</b>	<b>39,842</b>	<b>291,957</b>	<b>0</b>	<b>0.00</b>	<b>291,957</b>	<b>0</b>	<b>0</b>	<b>291,957</b>
<b>1.03.07 CONSTRUCTION STAFF</b>										
302090201	PREPARE FINAL D&D REPORT	8,393	1,387	9,780	0	0.00	9,780	0	0	9,780
303020101	CONSTRUCTION FIELD STAFF-FP	160,451	26,522	186,973	0	0.00	186,973	0	0	186,973
<b>SUBTOTAL CONSTRUCTION STAFF</b>		<b>168,844</b>	<b>27,909</b>	<b>196,754</b>	<b>0</b>	<b>0.00</b>	<b>196,754</b>	<b>0</b>	<b>0</b>	<b>196,754</b>
<b>1.03.08 PROJECT MANAGEMENT</b>										
302090201	PREPARE FINAL D&D REPORT	2,010	332	2,342	0	0.00	2,342	0	0	2,342
302090203	FINAL SITE SURVEY -FH	3,043	491	3,535	0	0.00	3,535	0	0	3,535
303010101	PROJECT MANAGEMENT-FH-CPT	103,389	17,090	120,479	0	0.00	120,479	0	0	120,479
<b>SUBTOTAL PROJECT MANAGEMENT</b>		<b>108,443</b>	<b>17,814</b>	<b>126,357</b>	<b>0</b>	<b>0.00</b>	<b>126,357</b>	<b>0</b>	<b>0</b>	<b>126,357</b>
<b>TOTALS</b>		<b>995,851</b>	<b>160,844</b>	<b>1,156,695</b>	<b>0</b>	<b>0.00</b>	<b>1,156,695</b>	<b>0</b>	<b>0</b>	<b>1,156,695</b>

DOE/RL-2005-63 DRAFT A

Table D-3. 216-A-29 South Ditch – Alternative 3 – Removal, Treatment, and Disposal. (4 Pages)

**FLUOR HANFORD**

DD / FH  
TRENCH TEMPLATE  
EST NO. CS29ST3C

**200-CS-1 FEASIBILITY STUDY**  
216-A-29 South Ditch - Alt 3 RTD  
FT\_R02N - WORK BREAKDOWN STRUCTURE SUMMARY

PAGE 1  
PRINTED 02/15/2006 9:21 AM  
UPDATED 02/15/2006 9:20 AM  
PREPARED BY BA Gilkeson

EST WBS	ESTIMATE WBS DESCRIPTION	ESTIMATE SUBTOTAL	TOTAL INDIRECTS	SUB TOTAL	ESCALATN TOTAL	ESCAL %	SUB TOTAL	CONT %	CONTGNCY TOTAL	TOTAL AMOUNT
<b>1.03.02 MOBILIZATION / DEMOBILIZATION</b>										
302010301	PERSONNEL TRAINING-BASIC	24,388	4,031	28,420	0	0.00	28,420	0	0	28,420
302020102	WASTE SITE SURVEY	3,050	504	3,554	0	0.00	3,554	0	0	3,554
302020203	MOB SITE WORK EQUIPMENT	5,108	844	5,950	0	0.00	5,950	0	0	5,950
302020301	INSTALL TEMP CONST BARRIER	7,548	1,247	8,796	0	0.00	8,796	0	0	8,796
302020302	TEMP OFFICE & FACILITIES	37,523	6,202	43,726	0	0.00	43,726	0	0	43,726
302020304	CONSTRUCT DECON AREA	40,499	6,694	47,194	0	0.00	47,194	0	0	47,194
302020305	TEMP SITE ROAD	7,203	1,190	8,393	0	0.00	8,393	0	0	8,393
302090101	REMOVE TEMP CONST BARRIER	1,505	248	1,754	0	0.00	1,754	0	0	1,754
302090102	REMOVE DECON AREA	18,411	3,043	21,454	0	0.00	21,454	0	0	21,454
302090103	REMOVE ROADS & PARKING	757	125	882	0	0.00	882	0	0	882
302090301	DEMOBILIZE CONSTRUCTION EQUIPMENT	14,543	2,404	16,947	0	0.00	16,947	0	0	16,947
302090304	FH DECON CONSTRUCTION EQUIPMENT SUPPORT	2,201	363	2,565	0	0.00	2,565	0	0	2,565
<b>SUBTOTAL MOBILIZATION / DEMOBILIZATION</b>		<b>162,738</b>	<b>26,900</b>	<b>189,640</b>	<b>0</b>	<b>0.00</b>	<b>189,640</b>	<b>0</b>	<b>0</b>	<b>189,640</b>
<b>1.03.03 MONITORING / SAMPLING</b>										
302030102	SITE AIR MONITORING	23,920	3,542	27,462	0	0.00	27,462	0	0	27,462
302030302	RAD SAMPLING, ANALYSIS-VEG/SEDW/SOIL	39,010	5,777	44,787	0	0.00	44,787	0	0	44,787
302030403	FH SAMPLE CREW	6,396	1,057	7,454	0	0.00	7,454	0	0	7,454
<b>SUBTOTAL MONITORING / SAMPLING</b>		<b>69,326</b>	<b>10,377</b>	<b>79,704</b>	<b>0</b>	<b>0.00</b>	<b>79,704</b>	<b>0</b>	<b>0</b>	<b>79,704</b>
<b>1.03.04 SITE WORK</b>										
302080101	LOAD/HAUL OVERBURDEN FROM STOCKPILE	18,858	3,084	21,743	0	0.00	21,743	0	0	21,743
302080102	LOAD/HAUL FROM BORROW SITE	7,012	1,159	8,171	0	0.00	8,171	0	0	8,171
302080201	BACKFILL & COMPACTION	21,797	3,803	25,401	0	0.00	25,401	0	0	25,401
302080301	MECH SEEDING GRASS	8,035	997	7,033	0	0.00	7,033	0	0	7,033
302080302	SHRUBS/TREES/GROUND COVER	6,744	1,114	7,859	0	0.00	7,859	0	0	7,859
302080303	IRRIGATION	31,534	5,212	36,747	0	0.00	36,747	0	0	36,747
302090104	MISC CLEANUP	3,770	623	4,393	0	0.00	4,393	0	0	4,393
<b>SUBTOTAL SITE WORK</b>		<b>95,554</b>	<b>15,795</b>	<b>111,349</b>	<b>0</b>	<b>0.00</b>	<b>111,349</b>	<b>0</b>	<b>0</b>	<b>111,349</b>
<b>1.03.05 SOIL EXCAVATION</b>										

D-42

DOE/RL-2005-63 DRAFT A

Maestro

Master the Art of Estimating

Table D-3. 216-A-29 South Ditch – Alternative 3 – Removal, Treatment, and Disposal. (4 Pages)

**FLUOR HANFORD**

DD / FH  
TRENCH TEMPLATE  
EST NO. C529ST3C

**200-CS-1 FEASIBILITY STUDY**  
216-A-29 South Ditch - Alt 3 RTD  
FT\_R02N - WORK BREAKDOWN STRUCTURE SUMMARY

PAGE 2  
PRINTED 02/15/2006 9:21 AM  
UPDATED 02/15/2006 9:20 AM  
PREPARED BY BA Gilkeson

EST WBS	ESTIMATE WBS DESCRIPTION	ESTIMATE SUBTOTAL	TOTAL INDIRECTS	SUB TOTAL	ESCALATN TOTAL	ESCAL %	SUB TOTAL	CONT %	CONTNGCY TOTAL	TOTAL AMOUNT
302040101	UNCONTAMINATED/OVERBURDEN SOIL	37,783	6,242	44,005	0	0.00	44,005	0	0	44,005
302040102	EXCAVATE CONTAMINATED SOIL W/DUST CONTR	6,174	1,020	7,194	0	0.00	7,194	0	0	7,194
302040106	RCT SUPPORT	7,182	1,187	8,370	0	0.00	8,370	0	0	8,370
302040107	INDUSTRIAL SAFETY TECH SUPPORT	6,298	888	7,186	0	0.00	7,186	0	0	7,186
302060403	LOAD/HAUL RAD CONT SOIL	6,547	1,412	9,960	0	0.00	9,960	0	0	9,960
302060501	QUEUE AREA OPERATIONS	6,330	1,377	9,707	0	0.00	9,707	0	0	9,707
302060502	FH QUEUE AREA OPERATIONS	495	81	577	0	0.00	577	0	0	577
302060601	LOW ACTIVITY CONTAINERS	4,352	719	5,071	0	0.00	5,071	0	0	5,071
302060603	FH DECONTAMINATE CONTAINERS	2,972	491	3,463	0	0.00	3,463	0	0	3,463
302060801	ERDF DISPOSAL COST	101,212	14,989	116,201	0	0.00	116,201	0	0	116,201
<b>SUBTOTAL SOIL EXCAVATION</b>		<b>183,329</b>	<b>28,410</b>	<b>211,739</b>	<b>0</b>	<b>0.00</b>	<b>211,739</b>	<b>0</b>	<b>0</b>	<b>211,739</b>
<b>1.03.07 CONSTRUCTION STAFF</b>										
302090201	PREPARE FINAL D&D REPORT	8,393	1,387	9,780	0	0.00	9,780	0	0	9,780
303020101	CONSTRUCTION FIELD STAFF-FP	108,613	17,953	126,566	0	0.00	126,566	0	0	126,566
<b>SUBTOTAL CONSTRUCTION STAFF</b>		<b>117,006</b>	<b>19,341</b>	<b>136,347</b>	<b>0</b>	<b>0.00</b>	<b>136,347</b>	<b>0</b>	<b>0</b>	<b>136,347</b>
<b>1.03.08 PROJECT MANAGEMENT</b>										
302090201	PREPARE FINAL D&D REPORT	2,010	332	2,342	0	0.00	2,342	0	0	2,342
302090203	FINAL SITE SURVEY -FH	1,352	218	1,571	0	0.00	1,571	0	0	1,571
303010101	PROJECT MANAGEMENT-FH-CPT	69,986	11,568	81,555	0	0.00	81,555	0	0	81,555
<b>SUBTOTAL PROJECT MANAGEMENT</b>		<b>73,348</b>	<b>12,119</b>	<b>85,468</b>	<b>0</b>	<b>0.00</b>	<b>85,468</b>	<b>0</b>	<b>0</b>	<b>85,468</b>
<b>TOTALS</b>		<b>701,306</b>	<b>112,944</b>	<b>814,250</b>	<b>0</b>	<b>0.00</b>	<b>814,250</b>	<b>0</b>	<b>0</b>	<b>814,250</b>

D-43

DOE/RL-2005-63 DRAFT A

Maestro

Master the Art of Estimating

Table D-4. 216-S-10 Ditch – Alternative 3 – Removal, Treatment, and Disposal. (2 Pages)

**FLUOR HANFORD**

DD / FH  
TRENCH TEMPLATE  
EST NO. CSS10T3C

**200-CS-1 FEASIBILITY STUDY**  
**216-S-10 Ditch - Alt 3 RTD**  
**FT\_R02N - WORK BREAKDOWN STRUCTURE SUMMARY**

PAGE 1  
PRINTED 02/15/2006 9:24 AM  
UPDATED 02/15/2006 9:24 AM  
PREPARED BY BA Gilkeson

EST WBS	ESTIMATE WBS DESCRIPTION	ESTIMATE SUBTOTAL	TOTAL INDIRECTS	SUB TOTAL	ESCALATN TOTAL	ESCAL %	SUB TOTAL	CONT %	CONTGNCY TOTAL	TOTAL AMOUNT
<b>1.03.02 MOBILIZATION / DEMOBILIZATION</b>										
302010301	PERSONNEL TRAINING-BASIC	24,388	4,031	28,420	0	0.00	28,420	0	0	28,420
302020102	WASTE SITE SURVEY	3,050	504	3,554	0	0.00	3,554	0	0	3,554
302020203	MOB SITE WORK EQUIPMENT	5,106	844	5,950	0	0.00	5,950	0	0	5,950
302020301	INSTALL TEMP CONST BARRIER	7,681	1,269	8,951	0	0.00	8,951	0	0	8,951
302020302	TEMP OFFICE & FACILITIES	37,523	6,202	43,726	0	0.00	43,726	0	0	43,726
302020304	CONSTRUCT DECON AREA	40,499	6,694	47,194	0	0.00	47,194	0	0	47,194
302020305	TEMP SITE ROAD	7,203	1,190	8,393	0	0.00	8,393	0	0	8,393
302090101	REMOVE TEMP CONST BARRIER	1,532	253	1,785	0	0.00	1,785	0	0	1,785
302090102	REMOVE DECON AREA	18,411	3,043	21,454	0	0.00	21,454	0	0	21,454
302090103	REMOVE ROADS & PARKING	757	125	882	0	0.00	882	0	0	882
302090301	DEMOBILIZE CONSTRUCTION EQUIPMENT	14,543	2,404	16,947	0	0.00	16,947	0	0	16,947
302090304	FH DECON CONSTRUCTION EQUIPMENT SUPPORT	2,201	363	2,565	0	0.00	2,565	0	0	2,565
<b>SUBTOTAL MOBILIZATION / DEMOBILIZATION</b>		<b>162,898</b>	<b>26,927</b>	<b>189,826</b>	<b>0</b>	<b>0.00</b>	<b>189,826</b>	<b>0</b>	<b>0</b>	<b>189,826</b>
<b>1.03.03 MONITORING /SAMPLING</b>										
302030102	SITE AIR MONITORING	38,480	5,698	44,178	0	0.00	44,178	0	0	44,178
302030302	RAD SAMPLING,ANALYSIS-VEG/SED/MSOIL	43,174	6,394	49,568	0	0.00	49,568	0	0	49,568
302030403	FH SAMPLE CREW	9,620	1,590	11,211	0	0.00	11,211	0	0	11,211
<b>SUBTOTAL MONITORING /SAMPLING</b>		<b>91,274</b>	<b>13,683</b>	<b>104,958</b>	<b>0</b>	<b>0.00</b>	<b>104,958</b>	<b>0</b>	<b>0</b>	<b>104,958</b>
<b>1.03.04 SITE WORK</b>										
302080101	LOAD/HAUL OVERBURDEN FROM STOCKPILE	26,904	4,447	31,352	0	0.00	31,352	0	0	31,352
302080102	LOAD/HAUL FROM BORROW SITE	19,219	3,177	22,396	0	0.00	22,396	0	0	22,396
302080201	BACKFILL & COMPACTION	34,828	5,757	40,585	0	0.00	40,585	0	0	40,585
302080301	MECH SEEDING GRASS	6,035	997	7,033	0	0.00	7,033	0	0	7,033
302080302	SHRUBS/TREES/GROUND COVER	6,744	1,114	7,859	0	0.00	7,859	0	0	7,859
302080303	IRRIGATION	31,534	5,212	36,747	0	0.00	36,747	0	0	36,747
302090104	MISC CLEANUP	4,786	783	5,569	0	0.00	5,569	0	0	5,569
<b>SUBTOTAL SITE WORK</b>		<b>130,066</b>	<b>21,500</b>	<b>151,566</b>	<b>0</b>	<b>0.00</b>	<b>151,566</b>	<b>0</b>	<b>0</b>	<b>151,566</b>
<b>1.03.05 SOIL EXCAVATION</b>										

D-44

DOE/RL-2005-63 DRAFT A

Maestro

Master the Art of Estimating

Table D-4. 216-S-10 Ditch – Alternative 3 – Removal, Treatment, and Disposal. (2 Pages)

**FLUOR HANFORD**

DD / FH  
TRENCH TEMPLATE  
EST NO. CSS10T3C

**200-CS-1 FEASIBILITY STUDY**  
216-S-10 Ditch - Alt 3 RTD  
FT\_R02N - WORK BREAKDOWN STRUCTURE SUMMARY

PAGE 2  
PRINTED 02/15/2006 9:24 AM  
UPDATED 02/15/2006 9:24 AM  
PREPARED BY BA Gilkeson

EST WBS	ESTIMATE WBS DESCRIPTION	ESTIMATE SUBTOTAL	TOTAL INDIRECTS	SUB TOTAL	ESCALATN TOTAL	ESCAL %	SUB TOTAL	CONT %	CONTGNCY TOTAL	TOTAL AMOUNT
302040101	UNCONTAMINATED/OVERBURDEN SOIL	54,451	9,000	63,452	0	0.00	63,452	0	0	63,452
302040102	EXCAVATE CONTAMINATED SOIL W/DUST CONTR	18,922	2,797	19,719	0	0.00	19,719	0	0	19,719
302040106	RCT SUPPORT	12,301	2,033	14,334	0	0.00	14,334	0	0	14,334
302040107	INDUSTRIAL SAFETY TECH SUPPORT	10,658	1,503	12,161	0	0.00	12,161	0	0	12,161
302060403	LOAD/HAUL RAD CONT SOIL	23,396	3,867	27,263	0	0.00	27,263	0	0	27,263
302060501	QUEUE AREA OPERATIONS	3,815	630	4,445	0	0.00	4,445	0	0	4,445
302060502	FH QUEUE AREA OPERATIONS	1,348	222	1,571	0	0.00	1,571	0	0	1,571
302060601	LOW ACTIVITY CONTAINERS	11,876	1,963	13,840	0	0.00	13,840	0	0	13,840
302060603	FH DECONTAMINATE CONTAINERS	8,090	1,337	9,428	0	0.00	9,428	0	0	9,428
302060801	ERDF DISPOSAL COST	264,382	39,155	303,537	0	0.00	303,537	0	0	303,537
<b>SUBTOTAL SOIL EXCAVATION</b>		<b>487,244</b>	<b>62,511</b>	<b>469,756</b>	<b>0</b>	<b>0.00</b>	<b>469,756</b>	<b>0</b>	<b>0</b>	<b>469,756</b>
<b>1.03.07 CONSTRUCTION STAFF</b>										
302090201	PREPARE FINAL D&D REPORT	8,393	1,387	9,780	0	0.00	9,780	0	0	9,780
303020101	CONSTRUCTION FIELD STAFF-FP	140,703	23,258	163,961	0	0.00	163,961	0	0	163,961
<b>SUBTOTAL CONSTRUCTION STAFF</b>		<b>149,096</b>	<b>24,645</b>	<b>173,742</b>	<b>0</b>	<b>0.00</b>	<b>173,742</b>	<b>0</b>	<b>0</b>	<b>173,742</b>
<b>1.03.08 PROJECT MANAGEMENT</b>										
302090201	PREPARE FINAL D&D REPORT	2,010	332	2,342	0	0.00	2,342	0	0	2,342
302090203	FINAL SITE SURVEY -FH	1,352	218	1,571	0	0.00	1,571	0	0	1,571
303010101	PROJECT MANAGEMENT-FH-CPT	90,664	14,986	105,651	0	0.00	105,651	0	0	105,651
<b>SUBTOTAL PROJECT MANAGEMENT</b>		<b>94,027</b>	<b>15,537</b>	<b>109,565</b>	<b>0</b>	<b>0.00</b>	<b>109,565</b>	<b>0</b>	<b>0</b>	<b>109,565</b>
<b>TOTALS</b>		<b>1,034,608</b>	<b>164,805</b>	<b>1,199,415</b>	<b>0</b>	<b>0.00</b>	<b>1,199,415</b>	<b>0</b>	<b>0</b>	<b>1,199,415</b>

D-45

DOE/RL-2005-63 DRAFT A

Table D-5. 216-A-29 North Ditch – Alternative 4 – Engineered Barrier. (4 Pages)

**FLUOR HANFORD**

DD / FH  
ET CAPILLARY/MONOFILL TEMPLATE  
EST NO. CS29NB4B

**200-CS-1 FEASIBILITY STUDY**  
216-A-29 North Ditch - Alt 4 ET Barrier  
FT\_R02N - WORK BREAKDOWN STRUCTURE SUMMARY

PAGE 1  
PRINTED 02/15/2006 9:08 AM  
UPDATED 02/15/2006 9:07 AM  
PREPARED BY BA Gilkeson

EST WBS	ESTIMATE WBS DESCRIPTION	ESTIMATE SUBTOTAL	TOTAL INDIRECTS	SUB TOTAL	ESCALATN TOTAL	ESCAL %	SUB TOTAL	CONT %	CONTGNCY TOTAL	TOTAL AMOUNT
<b>1.04.02 MOBILIZATION/DEMobilIZATION</b>										
302010301	PERSONNEL TRAINING-BASIC	8,222	1,359	9,581	0	0.00	9,581	0	0	9,581
302020102	WASTE SITE SURVEY	15,399	2,545	17,945	0	0.00	17,945	0	0	17,945
302020203	MOB SITE WORK EQUIPMENT	22,011	3,638	25,649	0	0.00	25,649	0	0	25,649
302020301	INSTALL TEMP CONST BARRIER	25,372	4,194	29,567	0	0.00	29,567	0	0	29,567
302020302	TEMP OFFICE & FACILITIES	21,378	3,533	24,912	0	0.00	24,912	0	0	24,912
302020305	TEMP SITE ROAD	7,538	1,246	8,784	0	0.00	8,784	0	0	8,784
302090101	REMOVE TEMP CONST BARRIER	3,957	654	4,611	0	0.00	4,611	0	0	4,611
302090103	REMOVE ROADS & PARKING	600	99	699	0	0.00	699	0	0	699
<b>SUBTOTAL MOBILIZATION/DEMobilIZATION</b>		<b>104,486</b>	<b>17,270</b>	<b>121,751</b>	<b>0</b>	<b>0.00</b>	<b>121,751</b>	<b>0</b>	<b>0</b>	<b>121,751</b>
<b>1.04.03 MONITORING/SAMPLING</b>										
302030102	SITE AIR MONITORING - INDUSTRIAL	18,903	3,307	22,210	0	0.00	22,210	0	0	22,210
302030103	SITE AIR MONITORING - ENVIRONMENTAL	3,780	661	4,442	0	0.00	4,442	0	0	4,442
<b>SUBTOTAL MONITORING/SAMPLING</b>		<b>22,684</b>	<b>3,968</b>	<b>26,652</b>	<b>0</b>	<b>0.00</b>	<b>26,652</b>	<b>0</b>	<b>0</b>	<b>26,652</b>
<b>1.04.04 SITE WORK</b>										
302080301	MECH SEEDING GRASS	8,490	1,403	9,894	0	0.00	9,894	0	0	9,894
302080302	SHRUBS/TREES/GROUND COVER	11,839	1,956	13,796	0	0.00	13,796	0	0	13,796
302080303	IRRIGATION	60,421	9,987	70,408	0	0.00	70,408	0	0	70,408
<b>SUBTOTAL SITE WORK</b>		<b>80,750</b>	<b>13,346</b>	<b>94,096</b>	<b>0</b>	<b>0.00</b>	<b>94,096</b>	<b>0</b>	<b>0</b>	<b>94,096</b>
<b>1.04.06 CAP-ET-CAPILLARY</b>										
302080401	SITE LEVELING & COMPACTION	264,450	43,713	308,164	0	0.00	308,164	0	0	308,164
302080402	LAYER 8 CONTOUR FILL	138,709	22,928	161,638	0	0.00	161,638	0	0	161,638
302080407	LAYER 3 SAND FILTER	173,758	28,722	202,480	0	0.00	202,480	0	0	202,480
302080408	LAYER 2 TOP SOIL	122,422	20,236	142,658	0	0.00	142,658	0	0	142,658
302080409	LAYER 1 TOP SOIL W/ PEA GRAVEL	70,470	11,848	82,319	0	0.00	82,319	0	0	82,319
302080410	SIDE SLOPE - BERM	369,805	61,128	430,934	0	0.00	430,934	0	0	430,934
302080412	PIT C & PROCESS OPERATIONS	88,227	14,583	102,811	0	0.00	102,811	0	0	102,811
302080413	SURVEYING	53,463	8,837	62,301	0	0.00	62,301	0	0	62,301

D-46

DOE/RL-2005-63 DRAFT A

Maestro

Master the Art of Estimating

2  
3

Table D-5. 216-A-29 North Ditch – Alternative 4 – Engineered Barrier. (4 Pages)

**FLUOR HANFORD**

DD / FH  
 ET CAPILLARY/MONOFILL TEMPLATE  
 EST NO. CS29NB4B

**200-CS-1 FEASIBILITY STUDY**  
 216-A-29 North Ditch - Alt 4 ET Barrier  
 FT\_R02N - WORK BREAKDOWN STRUCTURE SUMMARY

PAGE 2  
 PRINTED 02/15/2006 9:08 AM  
 UPDATED 02/15/2006 9:07 AM  
 PREPARED BY BA Gilkeson

EST WBS	ESTIMATE WBS DESCRIPTION	ESTIMATE SUBTOTAL	TOTAL INDIRECTS	SUB TOTAL	ESCALATN TOTAL	ESCAL %	SUB TOTAL	CONT %	CONTGNCY TOTAL	TOTAL AMOUNT
302080414	TESTING	33,250	5,496	38,746	0	0.00	38,746	0	0	38,746
302080415	FH-RCT SUPPORT	28,088	4,312	32,401	0	0.00	32,401	0	0	32,401
302080416	MINOR WORK	23,575	3,897	27,473	0	0.00	27,473	0	0	27,473
302090104	MISC CLEANUP	1,453	240	1,693	0	0.00	1,693	0	0	1,693
<b>SUBTOTAL CAP-ET-CAPILLARY</b>		<b>1,367,676</b>	<b>225,746</b>	<b>1,593,422</b>	<b>0</b>	<b>0.00</b>	<b>1,593,422</b>	<b>0</b>	<b>0</b>	<b>1,593,422</b>
<b>1.04.08 CONSTRUCTION STAFF</b>										
302090201	PREPARE FINAL D&D REPORT	9,428	1,558	10,986	0	0.00	10,986	0	0	10,986
303020101	CONSTRUCTION FIELD STAFF-FP	338,843	56,010	394,853	0	0.00	394,853	0	0	394,853
<b>SUBTOTAL CONSTRUCTION STAFF</b>		<b>348,271</b>	<b>57,568</b>	<b>405,840</b>	<b>0</b>	<b>0.00</b>	<b>405,840</b>	<b>0</b>	<b>0</b>	<b>405,840</b>
<b>1.04.09 PROJECT MANAGEMENT</b>										
302090201	PREPARE FINAL D&D REPORT	2,010	332	2,342	0	0.00	2,342	0	0	2,342
303010101	PROJECT MANAGEMENT-FH-CPT	180,913	29,905	210,818	0	0.00	210,818	0	0	210,818
<b>SUBTOTAL PROJECT MANAGEMENT</b>		<b>182,923</b>	<b>30,237</b>	<b>213,160</b>	<b>0</b>	<b>0.00</b>	<b>213,160</b>	<b>0</b>	<b>0</b>	<b>213,160</b>
<b>TOTALS</b>		<b>2,106,786</b>	<b>348,140</b>	<b>2,454,926</b>	<b>0</b>	<b>0.00</b>	<b>2,454,926</b>	<b>0</b>	<b>0</b>	<b>2,454,926</b>

D-47

DOE/RL-2005-63 DRAFT A

Table D-5. 216-A-29 South Ditch – Alternative 4 – Engineered Barrier. (4 Pages)

**FLUOR HANFORD**

DD / FH  
ET CAPILLARY/MONOFILL TEMPLATE  
EST NO. CS29SB4B

**200-CS-1 FEASIBILITY STUDY**  
**216-A-29 South Ditch - Alt 4 ET Barrier**  
**FT\_R02N - WORK BREAKDOWN STRUCTURE SUMMARY**

PAGE 1  
PRINTED 02/15/2006 9:17 AM  
UPDATED 02/15/2006 9:17 AM  
PREPARED BY BA Gilkeson

EST WBS	ESTIMATE WBS DESCRIPTION	ESTIMATE SUBTOTAL	TOTAL INDIRECTS	SUB TOTAL	ESCALATN TOTAL	ESCAL %	SUB TOTAL	CONT %	CONTGNCY TOTAL	TOTAL AMOUNT
<b>1.04.02 MOBILIZATION/DEMobilIZATION</b>										
302010301	PERSONNEL TRAINING-BASIC	8,222	1,359	9,581	0	0.00	9,581	0	0	9,581
302020102	WASTE SITE SURVEY	7,845	1,296	9,142	0	0.00	9,142	0	0	9,142
302020203	MOB SITE WORK EQUIPMENT	22,011	3,638	25,649	0	0.00	25,649	0	0	25,649
302020301	INSTALL TEMP CONST BARRIER	10,393	1,718	12,112	0	0.00	12,112	0	0	12,112
302020302	TEMP OFFICE & FACILITIES	11,511	1,902	13,414	0	0.00	13,414	0	0	13,414
302020305	TEMP SITE ROAD	7,538	1,246	8,784	0	0.00	8,784	0	0	8,784
302090101	REMOVE TEMP CONST BARRIER	1,822	301	2,124	0	0.00	2,124	0	0	2,124
302090103	REMOVE ROADS & PARKING	600	99	699	0	0.00	699	0	0	699
<b>SUBTOTAL MOBILIZATION/DEMobilIZATION</b>		<b>88,945</b>	<b>11,581</b>	<b>100,526</b>	<b>0</b>	<b>0.00</b>	<b>100,526</b>	<b>0</b>	<b>0</b>	<b>100,526</b>
<b>1.04.03 MONITORING/SAMPLING</b>										
302030102	SITE AIR MONITORING - INDUSTRIAL	7,561	1,322	8,884	0	0.00	8,884	0	0	8,884
302030103	SITE AIR MONITORING - ENVIRONMENTAL	2,520	440	2,961	0	0.00	2,961	0	0	2,961
<b>SUBTOTAL MONITORING/SAMPLING</b>		<b>10,081</b>	<b>1,763</b>	<b>11,845</b>	<b>0</b>	<b>0.00</b>	<b>11,845</b>	<b>0</b>	<b>0</b>	<b>11,845</b>
<b>1.04.04 SITE WORK</b>										
302080301	MECH SEEDING GRASS	4,245	701	4,947	0	0.00	4,947	0	0	4,947
302080302	SHRUBS/TREES/GROUND COVER	5,919	978	6,898	0	0.00	6,898	0	0	6,898
302080303	IRRIGATION	30,210	4,993	35,204	0	0.00	35,204	0	0	35,204
<b>SUBTOTAL SITE WORK</b>		<b>40,375</b>	<b>6,673</b>	<b>47,048</b>	<b>0</b>	<b>0.00</b>	<b>47,048</b>	<b>0</b>	<b>0</b>	<b>47,048</b>
<b>1.04.06 CAP-ET-CAPILLARY</b>										
302080401	SITE LEVELING & COMPACTION	106,330	17,576	123,907	0	0.00	123,907	0	0	123,907
302080402	LAYER 8 CONTOUR FILL	54,958	9,084	64,042	0	0.00	64,042	0	0	64,042
302080407	LAYER 3 SAND FILTER	68,587	11,337	79,925	0	0.00	79,925	0	0	79,925
302080408	LAYER 2 TOP SOIL	48,082	7,948	56,030	0	0.00	56,030	0	0	56,030
302080409	LAYER 1 TOP SOIL W/ PEA GRAVEL	27,478	4,541	32,018	0	0.00	32,018	0	0	32,018
302080410	SIDE SLOPE - BERM	153,373	25,352	178,726	0	0.00	178,726	0	0	178,726
302080412	PIT C & PROCESS OPERATIONS	34,402	5,686	40,089	0	0.00	40,089	0	0	40,089
302080413	SURVEYING	24,407	4,034	28,441	0	0.00	28,441	0	0	28,441

D-48

DOE/RL-2005-63 DRAFT A

Maestro

Master the Art of Estimating

2  
3

Table D-5. 216-A-29 South Ditch – Alternative 4 – Engineered Barrier. (4 Pages)

**FLUOR HANFORD**

DD / FH  
 ET CAPILLARY/MONOFILL TEMPLATE  
 EST NO. CS29SB4B

**200-CS-1 FEASIBILITY STUDY**  
 216-A-29 South Ditch - Alt 4 ET Barrier  
 FT\_R02N - WORK BREAKDOWN STRUCTURE SUMMARY

PAGE 2  
 PRINTED 02/15/2006 9:17 AM  
 UPDATED 02/15/2006 9:17 AM  
 PREPARED BY BA Gilkeson

EST WBS	ESTIMATE WBS DESCRIPTION	ESTIMATE SUBTOTAL	TOTAL INDIRECTS	SUB TOTAL	ESCALATN TOTAL	ESCAL %	SUB TOTAL	CONT %	CONTGNCY TOTAL	TOTAL AMOUNT
302080414	TESTING	13,685	2,262	15,947	0	0.00	15,947	0	0	15,947
302080415	FH-RCT SUPPORT	11,377	1,746	13,124	0	0.00	13,124	0	0	13,124
302080416	MINOR WORK	9,889	1,634	11,524	0	0.00	11,524	0	0	11,524
302090104	MISC CLEANUP	1,453	240	1,693	0	0.00	1,693	0	0	1,693
<b>SUBTOTAL CAP-ET-CAPILLARY</b>		<b>554,026</b>	<b>91,446</b>	<b>645,472</b>	<b>0</b>	<b>0.00</b>	<b>645,472</b>	<b>0</b>	<b>0</b>	<b>645,472</b>
<b>1.04.08 CONSTRUCTION STAFF</b>										
302090201	PREPARE FINAL D&D REPORT	9,428	1,558	10,986	0	0.00	10,986	0	0	10,986
303020101	CONSTRUCTION FIELD STAFF-FP	186,519	30,831	217,350	0	0.00	217,350	0	0	217,350
<b>SUBTOTAL CONSTRUCTION STAFF</b>		<b>195,947</b>	<b>32,390</b>	<b>228,337</b>	<b>0</b>	<b>0.00</b>	<b>228,337</b>	<b>0</b>	<b>0</b>	<b>228,337</b>
<b>1.04.09 PROJECT MANAGEMENT</b>										
302090201	PREPARE FINAL D&D REPORT	2,010	332	2,342	0	0.00	2,342	0	0	2,342
303010101	PROJECT MANAGEMENT-FH-CPT	99,585	16,461	116,046	0	0.00	116,046	0	0	116,046
<b>SUBTOTAL PROJECT MANAGEMENT</b>		<b>101,595</b>	<b>16,793</b>	<b>118,389</b>	<b>0</b>	<b>0.00</b>	<b>118,389</b>	<b>0</b>	<b>0</b>	<b>118,389</b>
<b>TOTALS</b>		<b>971,971</b>	<b>160,630</b>	<b>1,132,601</b>	<b>0</b>	<b>0.00</b>	<b>1,132,601</b>	<b>0</b>	<b>0</b>	<b>1,132,601</b>

D-49

DOE/RL-2005-63 DRAFT A

Maestro

Master the Art of Estimating

Table D-6. 216-S-10 Ditch – Alternative 4 – Engineered Barrier. (2 Pages)

**FLUOR HANFORD**

DD / FH  
ET CAPILLARY/MONOFILL TEMPLATE  
EST NO. CSS10B4D

**200-CS-1 FEASIBILITY STUDY**  
**216-S-10 Ditch -AK4 ET Barrier**  
**FT\_R02N - WORK BREAKDOWN STRUCTURE SUMMARY**

PAGE 1  
PRINTED 02/15/2006 9:27 AM  
UPDATED 02/15/2006 9:26 AM  
PREPARED BY BA Gilkeson

EST WBS	ESTIMATE WBS DESCRIPTION	ESTIMATE SUBTOTAL	TOTAL INDIRECTS	SUB TOTAL	ESCALATN TOTAL	ESCAL %	SUB TOTAL	CONT %	CONTGNCY TOTAL	TOTAL AMOUNT
<b>1.04.02 MOBILIZATION/DEMOBILIZATION</b>										
302010301	PERSONNEL TRAINING-BASIC	8,222	1,359	9,581	0	0.00	9,581	0	0	9,581
302020102	WASTE SITE SURVEY	7,845	1,298	9,142	0	0.00	9,142	0	0	9,142
302020203	MOB SITE WORK EQUIPMENT	22,011	3,638	25,649	0	0.00	25,649	0	0	25,649
302020301	INSTALL TEMP CONST BARRIER	11,703	1,934	13,638	0	0.00	13,638	0	0	13,638
302020302	TEMP OFFICE & FACILITIES	14,800	2,446	17,247	0	0.00	17,247	0	0	17,247
302020305	TEMP SITE ROAD	7,538	1,246	8,784	0	0.00	8,784	0	0	8,784
302090101	REMOVE TEMP CONST BARRIER	1,825	301	2,127	0	0.00	2,127	0	0	2,127
302090103	REMOVE ROADS & PARKING	600	99	699	0	0.00	699	0	0	699
<b>SUBTOTAL MOBILIZATION/DEMOBILIZATION</b>		<b>74,548</b>	<b>12,322</b>	<b>86,869</b>	<b>0</b>	<b>0.00</b>	<b>86,869</b>	<b>0</b>	<b>0</b>	<b>86,869</b>
<b>1.04.03 MONITORING/SAMPLING</b>										
302030102	SITE AIR MONITORING - INDUSTRIAL	21,424	3,748	25,172	0	0.00	25,172	0	0	25,172
302030103	SITE AIR MONITORING - ENVIRONMENTAL	3,780	661	4,442	0	0.00	4,442	0	0	4,442
<b>SUBTOTAL MONITORING/SAMPLING</b>		<b>25,204</b>	<b>4,409</b>	<b>29,614</b>	<b>0</b>	<b>0.00</b>	<b>29,614</b>	<b>0</b>	<b>0</b>	<b>29,614</b>
<b>1.04.04 SITE WORK</b>										
302080301	MECH SEEDING GRASS	4,245	701	4,947	0	0.00	4,947	0	0	4,947
302080302	SHRUBS/TREES/GROUNDCOVER	5,919	978	6,898	0	0.00	6,898	0	0	6,898
302080303	IRRIGATION	30,210	4,993	35,204	0	0.00	35,204	0	0	35,204
<b>SUBTOTAL SITE WORK</b>		<b>48,375</b>	<b>6,674</b>	<b>55,049</b>	<b>0</b>	<b>0.00</b>	<b>55,049</b>	<b>0</b>	<b>0</b>	<b>55,049</b>
<b>1.04.06 CAP-ET-CAPILLARY</b>										
302080401	SITE LEVELING & COMPACTION	393,388	85,027	458,415	0	0.00	458,415	0	0	458,415
302080402	LAYER 8 CONTOUR FILL	55,062	9,101	64,164	0	0.00	64,164	0	0	64,164
302080407	LAYER 3 SAND FILTER	68,719	11,359	80,078	0	0.00	80,078	0	0	80,078
302080408	LAYER 2 TOP SOIL	48,176	7,963	56,139	0	0.00	56,139	0	0	56,139
302080409	LAYER 1 TOP SOIL W/ PEA GRAVEL	27,531	4,550	32,082	0	0.00	32,082	0	0	32,082
302080410	SIDE SLOPE - BERM	153,664	25,400	179,064	0	0.00	179,064	0	0	179,064
302080412	PIT C & PROCESS OPERATIONS	34,474	5,698	40,172	0	0.00	40,172	0	0	40,172
302080413	SURVEYING	24,407	4,034	28,441	0	0.00	28,441	0	0	28,441

D-50

DOE/RL-2005-63 DRAFT A

Maestro

Master the Art of Estimating

Table D-6. 216-S-10 Ditch – Alternative 4 – Engineered Barrier. (2 Pages)

**FLUOR HANFORD**

DD / FH  
 ET CAPILLARY/MONOFILL TEMPLATE  
 EST NO. CSS10B4D

**200-CS-1 FEASIBILITY STUDY**

216-S-10 Ditch -Alt4 ET Barrier  
 FT\_R02N - WORK BREAKDOWN STRUCTURE SUMMARY

PAGE 2  
 PRINTED 02/15/2006 9:27 AM  
 UPDATED 02/15/2006 9:26 AM  
 PREPARED BY BA Gilkeson

EST WBS	ESTIMATE WBS DESCRIPTION	ESTIMATE SUBTOTAL	TOTAL INDIRECTS	SUB TOTAL	ESCALATN TOTAL	ESCAL %	SUB TOTAL	CONT %	CONTGNCY TOTAL	TOTAL AMOUNT
302080414	TESTING	27,690	4,577	32,268	0	0.00	32,268	0	0	32,268
302080415	FH-RCT SUPPORT	31,644	4,858	36,502	0	0.00	36,502	0	0	36,502
302080416	MINOR WORK	9,906	1,637	11,544	0	0.00	11,544	0	0	11,544
302090104	MISC CLEANUP	1,453	240	1,693	0	0.00	1,693	0	0	1,693
<b>SUBTOTAL CAP-ET-CAPILLARY</b>		<b>676,119</b>	<b>144,450</b>	<b>1,020,569</b>	<b>0</b>	<b>0.00</b>	<b>1,020,569</b>	<b>0</b>	<b>0</b>	<b>1,020,569</b>
<b>1.04.08 CONSTRUCTION STAFF</b>										
302090201	PREPARE FINAL D&D REPORT	9,428	1,558	10,986	0	0.00	10,986	0	0	10,986
303020101	CONSTRUCTION FIELD STAFF-FP	251,800	41,622	293,423	0	0.00	293,423	0	0	293,423
<b>SUBTOTAL CONSTRUCTION STAFF</b>		<b>261,228</b>	<b>43,181</b>	<b>304,410</b>	<b>0</b>	<b>0.00</b>	<b>304,410</b>	<b>0</b>	<b>0</b>	<b>304,410</b>
<b>1.04.09 PROJECT MANAGEMENT</b>										
302090201	PREPARE FINAL D&D REPORT	2,010	332	2,342	0	0.00	2,342	0	0	2,342
303010101	PROJECT MANAGEMENT-FH-CPT	134,440	22,222	156,663	0	0.00	156,663	0	0	156,663
<b>SUBTOTAL PROJECT MANAGEMENT</b>		<b>136,450</b>	<b>22,555</b>	<b>159,005</b>	<b>0</b>	<b>0.00</b>	<b>159,005</b>	<b>0</b>	<b>0</b>	<b>159,005</b>
<b>TOTALS</b>		<b>1,413,925</b>	<b>233,592</b>	<b>1,647,518</b>	<b>0</b>	<b>0.00</b>	<b>1,647,518</b>	<b>0</b>	<b>0</b>	<b>1,647,518</b>

D-51

DOE/RL-2005-63 DRAFT A

Maestro

Master the Art of Estimating

Table D-7. 200-CS-1 Operable Unit Representative and Analogous Site Information.

Waste Site	Site Dimensions (ft)			Overburden Depth (ft)	Excavation Dimensions (ft)			Contaminated Volume (yd <sup>3</sup> )	Excavated Volume (yd <sup>3</sup> )	Clean Soil Volume (yd <sup>3</sup> )	Area of Barrier in Acres
	Length	Width	Depth		Length	Width	Depth				
216-A-29 Ditch	4,000	6	2-15	6	3,594	37 to 45	10 to 13	2,399	30,811	28,412	8.1
216-S-10 Ditch	2,250	6	6	0	1025	51	15	3,625	15,865	0	2.3
					Total volume of soil to ERDF			6,024 yd <sup>3</sup>			

Table D-8. 200-CS-1 Operable Unit Net Present Value and Non-Discounted Costs.

WASTE SITES	ALTERNATIVE 1: No Action	ALTERNATIVE 2: Maintain Existing Soil Cover, Monitored Natural Attenuation, and Institutional Controls	ALTERNATIVE 3: Removal, Treatment, and Disposal	ALTERNATIVE 4: Engineered Barrier
216-A-29 Ditch (Non-discounted cost)	N/A	\$868,340 \$4,031,232	\$2,759,317 \$0	\$3,587,527 \$25,954,293
216-B-64 Trench (Non-discounted cost)	\$0	N/A N/A	N/A N/A	N/A N/A
216-S-10 Ditch (Non-discounted cost)	N/A	\$867,538 \$4,077,514	\$1,679,178 \$0	\$3,573,574 \$8,456,185
216-S-10 Pond (Non-discounted cost)	\$0	N/A N/A	N/A N/A	N/A N/A
216-S-11 Pond (Non-discounted cost)	\$0	N/A N/A	N/A N/A	N/A N/A

D-53

This page intentionally left blank.

1

**APPENDIX E**

2

3

**CLOSURE PLAN FOR THE 216-A-29 DITCH**

This page intentionally left blank.

## CONTENTS

1			
2	E1.0	INTRODUCTION .....	E1-1
3	E2.0	UNIT DESCRIPTION .....	E2-1
4	E2.1	PHYSICAL DESCRIPTION AND OPERATIONS .....	E2-1
5	E2.2	SECURITY .....	E2-1
6	E3.0	PROCESS INFORMATION .....	E3-1
7	E4.0	WASTE CHARACTERISTICS .....	E4-1
8	E4.1	ESTIMATE OF MAXIMUM INVENTORY OF WASTE .....	E4-1
9	E4.2	WASTE CHARACTERISTICS .....	E4-1
10	E5.0	GROUNDWATER MONITORING .....	E5-1
11	E5.1	HISTORY OF RCRA GROUNDWATER MONITORING .....	E5-4
12	E5.2	AQUIFER IDENTIFICATION .....	E5-4
13	E5.3	WELL LOCATION AND DESIGN .....	E5-4
14	E5.4	RESULTS OF RCRA INTERIM-STATUS GROUNDWATER	
15		MONITORING DATA .....	E5-5
16	E6.0	CLOSURE STRATEGY AND PERFORMANCE STANDARDS .....	E6-1
17	E6.1	CLOSURE STRATEGY .....	E6-1
18	E6.2	CLOSURE PERFORMANCE STANDARDS .....	E6-1
19		E6.2.1 Treatment, Storage, and Disposal Unit Closure Performance	
20		Standards .....	E6-1
21		E6.2.2 Soil Closure Standards .....	E6-2
22	E7.0	CLOSURE ACTIVITIES .....	E7-1
23	E7.1	TREATMENT, STORAGE, AND DISPOSAL UNIT PHYSICAL	
24		ISOLATION .....	E7-1
25	E7.2	TREATMENT, STORAGE, AND DISPOSAL UNIT SAMPLING AND	
26		ANALYSIS .....	E7-1
27		E7.2.1 Soil Sampling and Analysis .....	E7-1
28		E7.2.2 Soil Sample Results .....	E7-2
29	E7.3	OTHER ACTIVITIES REQUIRED FOR CLOSURE .....	E7-3
30	E7.4	INSPECTIONS .....	E7-3
31	E7.5	TRAINING .....	E7-3
32	E7.6	SCHEDULE FOR CLOSURE .....	E7-4
33	E7.7	AMENDMENT OF CLOSURE PLAN .....	E7-4
34	E7.8	CERTIFICATION OF CLOSURE .....	E7-4
35	E8.0	POSTCLOSURE PLAN .....	E8-1
36	E9.0	REFERENCES .....	E9-1
37			

1

**FIGURES**

2 Figure E-1. 216-A-29 Ditch Location and Site Plan.....E2-2  
3 Figure E-2. Borehole and Test Pit Location Map for the 216-A-29 Ditch.....E3-3

4

5

**TABLES**

6 Table E-1. Comparison of 216-A-29 Ditch Remedial Investigation Data to  
7 Clean-Closure Levels. ....E4-2  
8 Table E-2. Comparison of 216-A-29 Ditch Groundwater Data to Clean-Closure Levels.....E5-2

9

TERMS

1		
2	CERCLA	<i>Comprehensive Environmental Response, Compensation, and Liability Act of 1980</i>
3		
4	DQO	data quality objectives
5	Ecology	Washington State Department of Ecology
6	GW	groundwater
7	HEIS	<i>Hanford Environmental Information System</i> database
8	MCL	maximum contaminant level
9	N/A	not applicable
10	ND	not detected
11	OU	operable unit
12	PUREX	Plutonium-Uranium Extraction Plant
13	RCRA	<i>Resource Conservation and Recovery Act of 1976</i>
14	RI	remedial investigation
15	SMCL	secondary maximum contaminant level
16	Tri-Party Agreement	<i>Hanford Federal Facility Agreement and Consent Order</i>
17		(Ecology et al. 1989a)
18	Tri-Party Agreement Action Plan	<i>Hanford Federal Facility Agreement and Consent Order</i>
19		<i>Action Plan</i> (Ecology et al. 1989b)
20	TSD	treatment, storage, and disposal (unit)
21	U	undetected

## METRIC CONVERSION CHART

Into Metric Units			Out of Metric Units		
<i>If You Know</i>	<i>Multiply By</i>	<i>To Get</i>	<i>If You Know</i>	<i>Multiply By</i>	<i>To Get</i>
<b>Length</b>			<b>Length</b>		
inches	25.4	Millimeters	millimeters	0.039	inches
inches	2.54	Centimeters	centimeters	0.394	inches
feet	0.305	Meters	meters	3.281	feet
yards	0.914	Meters	meters	1.094	yards
miles	1.609	Kilometers	kilometers	0.621	miles
<b>Area</b>			<b>Area</b>		
sq. inches	6.452	sq. centimeters	sq. centimeters	0.155	sq. inches
sq. feet	0.093	sq. meters	sq. meters	10.76	sq. feet
sq. yards	0.0836	sq. meters	sq. meters	1.196	sq. yards
sq. miles	2.6	sq. kilometers	sq. kilometers	0.4	sq. miles
acres	0.405	Hectares	hectares	2.47	acres
<b>Mass (weight)</b>			<b>Mass (weight)</b>		
ounces	28.35	Grams	grams	0.035	ounces
pounds	0.454	Kilograms	kilograms	2.205	pounds
ton	0.907	metric ton	metric ton	1.102	ton
<b>Volume</b>			<b>Volume</b>		
teaspoons	5	Milliliters	milliliters	0.033	fluid ounces
tablespoons	15	Milliliters	liters	2.1	pints
fluid ounces	30	Milliliters	liters	1.057	quarts
cups	0.24	Liters	liters	0.264	gallons
pints	0.47	Liters	cubic meters	35.315	cubic feet
quarts	0.95	Liters	cubic meters	1.308	cubic yards
gallons	3.8	Liters			
cubic feet	0.028	cubic meters			
cubic yards	0.765	cubic meters			
<b>Temperature</b>			<b>Temperature</b>		
Fahrenheit	subtract 32, then multiply by 5/9	Celsius	Celsius	multiply by 9/5, then add 32	Fahrenheit
<b>Radioactivity</b>			<b>Radioactivity</b>		
picocuries	37	Millibecquerel	millibecquerel	0.027	picocuries

## APPENDIX E

## CLOSURE PLAN FOR THE 216-A-29 DITCH

## E1.0 INTRODUCTION

The original closure plan for the 216-A-29 Ditch (DOE/RL-93-74, 200-BP-11 Operable Unit RFI/CMS and 216-B-3 Main Pond, 216-B-63 Trench, and 216-A-29 Ditch Work/Closure Plan) was submitted to the Washington State Department of Ecology (Ecology) pursuant to *Hanford Federal Facility Agreement and Consent Order* (Tri-Party Agreement) (Ecology et al. 1989a) milestone M-20-36 in June 1995. This closure plan has been rewritten to supersede the June 1995 closure plan. Documents and information sources mentioned in this closure plan are not intended for incorporation in WA7890008967, *Hanford Facility Resource Conservation and Recovery Act Permit, Dangerous Waste Portion, Revision 8, for the Treatment, Storage, and Disposal of Dangerous Waste*.

The 216-A-29 Ditch Treatment, Storage, and/or Disposal (TSD) unit will be incorporated into the *Hanford Facility RCRA Permit*. When the permit modification to incorporate the TSD unit becomes effective, the provisions of *Hanford Facility RCRA Permit* Conditions II.Y.2.c will apply. Permit Condition II.Y.2.c establishes the corrective action status of the waste site following certification of closure. This closure plan is written to address only the dangerous waste constituents of concern relating to *Resource Conservation and Recovery Act of 1976* (RCRA) TSD unit operations (TSD unit constituents). Therefore, any other constituents of concern described in DOE/RL-2004-17, *Remedial Investigation Report for the 200-CS-1 Chemical Sewer Group Operable Unit*, related to past-practice activities at this waste site will be addressed under past-practice authority, in accordance with Permit Condition II.Y.2.c.ii. Any physical activities necessary to complete remediation of non-TSD unit constituents is outside the scope of this closure plan and will be performed in conjunction with Tri-Party Agreement past-practice activities for the 200-CS-1 source operable unit (OU) and the 200-PO-1 Groundwater OU.

The development of this closure plan has been coordinated with the 200-CS-1 source OU in accordance with Tri-Party Agreement milestone M-15-39C. This coordinated approach was established in June 2002 following the completion of negotiations between the U.S. Department of Energy, U.S. Environmental Protection Agency, and Washington State Department of Ecology (Ecology) on the modifications to 200 Areas waste site cleanup milestones through Tri-Party Agreement change requests M-13-02-01, M-15-02-01, M-16-02-01, and M-20-02-01. As a result, much of the text contained in this closure plan has been obtained from existing 200-CS-1 OU *Comprehensive Environmental Response, Compensation, and Liability Act of 1980* (CERCLA) documentation.

1 The proposed closure strategy for the 216-A-29 Ditch soils is clean closure following  
2 remediation of the soils and clean closure of the TSD unit pertaining to groundwater following  
3 approval of this closure plan. The soil strategy is based on analytical data summarized in  
4 DOE/RL-2004-17 and verification sampling activities in the soil to be completed following soil  
5 remediation as part of the 200-CS-1 OU activities. Groundwater data contained in the *Hanford*  
6 *Environmental Information System* (HEIS) database was used to show that the TSD unit has not  
7 impacted groundwater.

8

## E2.0 UNIT DESCRIPTION

This chapter provides a physical description of the 216-A-29 Ditch and describes security related to the 216-A-29 Ditch.

### E2.1 PHYSICAL DESCRIPTION AND OPERATIONS

The 216-A-29 Ditch is located to the east of the 200 East Area of the Hanford Facility (Figure E-1). The 216-A-29 Ditch received discharge from the Plutonium-Uranium Extraction (PUREX) Plant chemical sewer. The ditch was uncovered and unlined and followed the natural topography. The ditch originated from the southeast side of the A Tank Farm (east of the AP Tank Farm) outside the 200 East Area perimeter fence. The ditch was estimated to be 1,220 m (4,000 ft) long and 1.8 m (6 ft) wide and varied from 0.6 to 4.6 m (2 to 15 ft). The head end of the ditch was modified in 1983 to allow the construction of the AP Tank Farm. The end of the ditch connects to the 216-B-3-3 Ditch and finally to the 216-B-3 Pond.

The PUREX Plant chemical sewer operated between November 1955 and July 1991. At the beginning of its operation, the 216-A-29 Ditch received discharge from the PUREX Plant cooling water and discharge from the chemical sewer. In early 1980, because of effluent monitoring requirements, the chemical sewer lines feeding the 216-A-29 Ditch required upgrades to allow for monitoring and diversion capabilities. A diversion box was upgraded and connected to the 216-A-42 Retention Basin. The basin received contaminated diversions from the PUREX Plant chemical sewer line, cooling water line, and steam condensate discharge. During 1990, plans were developed and approved to discontinue discharges to and close the 216-A-29 Ditch, and in 1991, all discharges were discontinued. Stabilization of the 216-A-29 Ditch was performed in three phases from July to October 1991.


### E2.2 SECURITY

Security information for the Hanford Facility is discussed in DOE/RL-91-28, *Hanford Facility Dangerous Waste Permit Application*, Section 6.1, General Information Portion. Because the 216-A-29 Ditch is located near the 200 East Area, the security information pertaining to the 200 Areas applies to this TSD unit.

Changes to security are expected to occur during the course of 200 East Area deactivation and decommissioning activities. Security measures will remain in place that limit entry to authorized personnel and that preclude unknowing access by unauthorized individuals. Following clean-closure certification of this TSD unit as described in Section 7.8, security provisions no longer will apply.

1  
2  
3  
4

Figure E-1. 216-A-29 Ditch Location and Site Plan.



1 **E3.0 PROCESS INFORMATION**

2 The following waste streams, which are summarized from the stream-specific, report  
3 (WHC-EP-0342, Addendum 2, *PUREX Plant Chemical Sewer Stream-Specific Report*),  
4 contributed to the 216-A-29 Ditch:

- 5 • Various floor drains: 202-A Canyon Building pipe and operations gallery; air  
6 compressor, process blower, and service blower rooms in 202-A; 211-A pump house; and  
7 202-A Canyon Building instrument and maintenance shops
- 8 • 618-1 and 618-2 flash tanks containing heating coils, spray water, and steam condensate
- 9 • 206-A Vacuum Acid Fractionator Building condensers and reboiler cooling water and  
10 steam condensate
- 11 • Sink drain from the battery room, instrument shop, and maintenance shop in 202-A
- 12 • 202-A laboratory ventilation room; heating, ventilation, and air conditioning-related  
13 drainage
- 14 • 202-A laboratory nonradioactive clothing change room drains
- 15 • 202-A blower room condensate
- 16 • Overflow from various demineralized water storage tanks
- 17 • Overflow from the emergency water supply tank
- 18 • Raw water used to flush continuously the PUREX Plant chemical sewer line.

19 See Section 7.1 for additional information on physical isolation of the TSD unit.

This page intentionally left blank.

## E4.0 WASTE CHARACTERISTICS

This chapter identifies the estimate of maximum inventory and the characteristics of the waste disposed at the 216-A-29 Ditch.

### E4.1 ESTIMATE OF MAXIMUM INVENTORY OF WASTE

During operations, approximately 22,700,000 L/day (6,000,000 gal/day) of liquid wastewater reached the 216-A-29 Ditch. Accurate records are not available concerning the total volume of waste disposed. The ditch was equipped with a meter for measuring flow rate. Flow rates varied from approximately 378 to 5,290 L/min (100 to 1,400 gal/min), depending on the operating conditions of the PUREX Plant. The average flow was about 3,760 L/min (970 gal/min).

### E4.2 WASTE CHARACTERISTICS

The dangerous waste received at the 216-A-29 Ditch includes nitric acid, sulfuric acid, sodium hydroxide, potassium hydroxide, hydrazine, hydroxylamine nitrate, cadmium nitrate, ammonium fluoride, and ammonium nitrate. Some of these chemicals are regulated under WAC 173-303, "Dangerous Waste Regulations," as a dangerous waste because they have a characteristic of corrosivity (D002). Cadmium nitrate is regulated because of the cadmium (D006). Hydrazine is regulated because it is in the listed waste code (U133). In addition, other constituents are regulated because it is mentioned in the state-only WT02 waste code. These TSD unit constituents are identified in WHC-EP-0342, Addendum 2; DOE/RL-89-28, *216-B-3 Expansion Pond Closure Plan*, Rev. 2 (Attachment 23 to Revision 6 of the *Hanford Facility RCRA Permit*); and DOE/RL-2004-17, Appendix B, Table B-2.

Based on the dangerous waste received at the 216-A-29 Ditch, the TSD unit constituents of concern for RCRA closure are sodium (from sodium hydroxide), potassium (from potassium hydroxide), sulfate (from sulfuric acid), nitrate (from nitric acid, hydroxylamine nitrate, cadmium nitrate, and ammonium nitrate), ammonia (from ammonium fluoride, and ammonium nitrate), fluoride (from ammonium fluoride), cadmium (from cadmium nitrate) and hydrazine. These constituents constitute the scope of the TSD unit RCRA closure activities (Table E-1). The pH ranges of the pond and ditch soils are reported as 6.5 to 9.5 and are well within the noncorrosive range from WAC 173-303-090(6), "Dangerous Waste Characteristics," "Characteristic of Corrosivity."

Table E-1. Comparison of 216-A-29 Ditch Remedial Investigation Data to Clean-Closure Levels. (2 Pages)

TSD Unit Constituent Related to Part A Waste Codes D002, D006, U133, and WT02	Maximum Concentration Shallow-Zone Soil (mg/kg)	Maximum Concentration Deep Zone Soil (mg/kg)	Hanford Site Soil Background (mg/kg) <sup>1</sup> 90% Log Normal Distribution	Environmental Protection Ecological Receptors for Shallow Zone Soils <sup>2</sup> (mg/kg)	Human Health Protection Soil Direct Contact <sup>3</sup> (mg/kg)		Soil Concentration Protective of Groundwater <sup>4</sup> (mg/kg)	Clean Closure Driver <sup>5</sup>	Meet Clean Closure Standard?
					Carcinogen	Non-carcinogen			
Sodium	873	Not in RI report table	690	N/A	N/A	N/A	N/A	Not regulated	Yes
Potassium	2,260	ND	2,440	N/A	N/A	N/A	N/A	Not regulated	Yes
Sulfate	2,970	46.2	237	N/A	N/A	N/A	1,030	Soil concentration protective of GW	No
Nitrate (as N)	210	76.4	11.7	N/A	N/A	5,600,000	83 <sup>6</sup>	Soil concentration protective of GW	No
Ammonia	34.3	ND	9.23	N/A	N/A	N/A	N/A	Not regulated	Yes
Fluoride (using fluoride)	5.26	ND	100	N/A	N/A	210,000	24.1	Background	Yes
Cadmium	28	0.32	-	N/A	N/A	3,500 <sup>7</sup>	N/A	Human health protection	Yes
Hydrazine	Not in RI, Table 4-1	Not in RI, Table 4-3	-	N/A	0.3333	N/A	Practical quantitation limit <sup>8</sup>	Practical quantitation limit	Yes <sup>9</sup>

<sup>1</sup> DOE/RL-92-24, Volume 1, Hanford Site Background: Part 1, Soil Background for Nonradioactive Analytes, Rev. 3.

<sup>2</sup> WAC 173-340-745(5)(b)(ii), "Soil Cleanup Standards for Industrial Properties," "Method C Industrial Soil Cleanup Levels," "Standard Method C Industrial Soil Cleanup Levels," "Environmental Protection," Environmental protection ecological receptors are not clean up levels, based on WAC 173-340-7493(2)(a)(i), "Site-Specific Terrestrial Ecological Evaluation Procedures," "Problem Formulation Step," "The Chemicals of Ecological Concern" WAC 173-340-745(3)(b)(ii), "Soil Cleanup Standards for Industrial Properties," "Method A Industrial Soil Cleanup Levels," "General Requirements," values are identical to WAC 173-340-740(3)(b)(ii), "Unrestricted Land Use Soil Cleanup Standards," "Method B Soil Cleanup Levels for Unrestricted Land Use," "Standard Method B Soil Cleanup Levels," "Environmental Protection," because they use the same approach.

<sup>3</sup> WAC 173-340-745(5)(b)(iii)(B)(I) and (II), "Soil Cleanup Standards for Industrial Properties," "Method C Industrial Soil Cleanup Levels," "Standard Method C Industrial Soil Cleanup Levels," "Human Health Protection," "Soil Direct Contact," "Noncarcinogens," and "Carcinogens." Equations are found in (I) (noncarcinogens) and (II) (carcinogens) for human health direct contact. Point of compliance is surface to 15 ft (WAC 173-340-740(6), "Unrestricted Land Use Soil Cleanup Standards," "Point of Compliance").

<sup>4</sup> WAC 173-340-745(5)(b)(iii)(A), "Soil Cleanup Standards for Industrial Properties," "Method C Industrial Soil Cleanup Levels," "Standard Method C Industrial Soil Cleanup Levels," "Human Health Protection," "Ground Water Protection." Point of compliance is soils throughout the site (WAC 173-340-740(6)). WAC 173-340-745(5)(b)(iii)(A) values are identical to WAC 173-340-740(3)(b)(iii)(A), "Unrestricted Land Use Soil Cleanup Standards," "Method B Soil Cleanup Levels for Unrestricted Land Use," "Standard Method B Soil Cleanup Levels," "Human Health Protection," "Ground Water Protection," because they use the same approach.

<sup>5</sup> Represents the most restrictive level after ensuring the most restrictive level is not less than natural background and for analytical considerations as indicated in WAC 173-340-700(6)(d), "Overview of Cleanup Standards," "Requirements for Setting Cleanup Levels," "Natural Background and Analytical Considerations."

<sup>6</sup> Alternate fate and transport model established pursuant to WAC 173-340-747(8), "Deriving Soil Concentrations for Ground Water Protection," "Alternative Fate and Transport Models." See DOE/RL-2005-63, Feasibility Study for the 200-CS-1 Chemical Sewer Group Operable Unit, Table 3-1.

<sup>7</sup> Soils also meet WAC 173-340-740(3)(b)(iii)(B)(I), "Unrestricted Land Use Soil Cleanup Standards," "Method B Soil Cleanup Levels for Unrestricted Land Use," "Standard Method B Soil Cleanup Levels," "Human Health Protection," "Soil Direct Contact," "Noncarcinogens," noncarcinogen value of 80 mg/kg.

<sup>8</sup> The practical quantitation limit for hydrazine exceeds the soil concentration protective of groundwater standard of 0.0000625. Therefore, the practical quantitation limit is used for clean-closure determinations.

Table E-1. Comparison of 216-A-29 Ditch Remedial Investigation Data to Clean-Closure Levels. (2 Pages)

TSD Unit Constituent Related to Part A Waste Codes D002, D006, U133, and WT02	Maximum Concentration Shallow-Zone Soil (mg/kg)	Maximum Concentration Deep Zone Soil (mg/kg)	Hanford Site Soil Background (mg/kg) <sup>1</sup> 90% Log Normal Distribution	Environmental Protection Ecological Receptors for Shallow Zone Soils <sup>2</sup> (mg/kg)	Human Health Protection Soil Direct Contact <sup>3</sup> (mg/kg)		Soil Concentration Protective of Groundwater <sup>4</sup> (mg/kg)	Clean Closure Driver <sup>5</sup>	Meet Clean Closure Standard?
					Carcinogen	Non-carcinogen			

<sup>1</sup> Hydrazine was not identified as a constituent of concern during the 200-CS-1 Operable Unit data quality objectives process. Contained-in determinations for listed waste code U133 for hydrazine in soils have been approved by the Washington state Department of Ecology. Clean closure is based on the data quality objectives process and the contained-in determination.

- GW = groundwater.
- N/A = not applicable.
- ND = not detected.
- Part A = DOE 2002, 216-S-10 Pond and Trench Part A, Form 3 Dangerous Waste Permit Application, Rev. 6.
- RI = remedial investigation (DOE/RL-2004-17, Remedial Investigation Report for the 200-CS-1 Chemical Sewer Group Operable Unit).
- TSD = treatment, storage, and disposal (unit).

This page intentionally left blank.

## E5.0 GROUNDWATER MONITORING

1

2 The 216-A-29 Ditch groundwater closure approach is clean closure. The closure approach is  
3 based on the data gathered to date from the monitoring network (PNNL-13047, *Groundwater*  
4 *Monitoring Plan for the 216-A-29 Ditch*), the groundwater data contained in the HEIS, and text  
5 provided in PNNL-15070, *Hanford Site Groundwater Monitoring for Fiscal Year 2004*, Section  
6 2.11.3.4, for the 216-A-29 Ditch. Groundwater monitoring also will continue, as appropriate, in  
7 the 200-PO-1 Groundwater OU for past-practice discharges. Table E-2 shows a comparison of  
8 the TSD unit constituent levels in groundwater to clean-closure levels. The clean-closure levels  
9 for groundwater are the calculated overall groundwater cleanup levels. Following approval of  
10 this closure plan, the TSD unit groundwater monitoring program for the 216-A-29 Ditch will be  
11 discontinued.

12 The current interim-status groundwater monitoring plan (as required by WAC  
13 173-303-400, "Dangerous Waste Regulations," "Interim Status Facility Standards," and  
14 40 CFR 265, "Interim Status Standards for Owners and Operators of Hazardous Waste  
15 Treatment, Storage, and Disposal Facilities," Subpart F, "Ground-Water Monitoring") is  
16 contained in a separate document, PNNL-13047. This document contains further details  
17 regarding the geology, hydrology, and current groundwater monitoring programs for the RCRA  
18 TSD unit. Excerpts from PNNL-15070 are presented below that provide for more recent  
19 monitoring network and groundwater conditions.

20 The 216-A-29 Ditch unit continued to be monitored under an interim-status detection program  
21 (40 CFR 265.93(b), "Interim Status for Owners and Operators of Hazardous Waste Treatment,  
22 Storage, and Disposal Facilities," "Preparation, Evaluation, and Response,") in fiscal year 2004.  
23 The groundwater beneath the 216-A-29 Ditch is monitored for evidence of dangerous waste  
24 migration, as required by interim-status RCRA regulations (40 CFR 265.93(b) as referenced by  
25 WAC 173-303-400). The groundwater monitoring network at this TSD unit is sampled twice  
26 annually for constituents that include contamination indicator parameters, annual groundwater  
27 quality parameters, and site-specific constituents. The well network is adequate for the current  
28 groundwater flow directions.

29 Except for specific conductance, indicator parameters in downgradient wells did not exceed  
30 critical mean values in fiscal year 2004. Specific conductance exceeded its critical mean value in  
31 three downgradient wells during fiscal year 2003 (wells 299-E26-13, 299-E25-48, and  
32 299-E25-35) (Figure E-2). During fiscal year 2004, specific conductance did not exceed the  
33 critical mean in well 299-E26-13, although the other two wells still showed the exceedance. The  
34 reason for the exceedance at wells 299-E25-48 and 299-E25-35, which lie at the head end of the  
35 216-A-29 Ditch, is the high sulfate concentrations in groundwater associated with discharges of  
36 sulfuric acid. The reason for the elevation of specific conductance in wells in other portions of  
37 the ditch is unknown.

38

Table E-2. Comparison of 216-A-29 Ditch Groundwater Data to Clean-Closure Levels.

Dangerous Constituent Related to Part A Waste Codes D002, D006, U133, and WT02	Maximum Concentration in Groundwater from HEIS ( $\mu\text{g/L}$ )	Hanford Site Groundwater Background ( $\mu\text{g/L}$ ) <sup>1</sup> (90 % Log Normal Distribution)	Overall Groundwater Cleanup Level ( $\mu\text{g/L}$ )	Clean Closure Driver <sup>2</sup>	Meet Clean Closure standard?
Sodium	48,500	26,998	N/A	Not regulated	Yes
Potassium	8,130	9,122	N/A	Not regulated	Yes
Sulfate	236,000 <sup>3</sup>	47,014	250,000	SMCL	Yes
Nitrate (as N)	4,697 <sup>3</sup>	6,067	10,000	MCL	Yes
Ammonia	Not analyzed	113	N/A	Not regulated	Yes
Fluoride (fluorine)	1,000	1,047	4,000	MCL	Yes
Cadmium	<5 <sup>5</sup>	0.916	5	MCL	Yes
Hydrazine	1.6 U <sup>6</sup>	-	Practical quantitation limit <sup>7</sup>	Practical quantitation limit	Yes

<sup>1</sup> DOE/RL-96-61, *Hanford Site Background: Part 3, Groundwater Background.*

<sup>2</sup> Listed values represent the most restrictive level of the groundwater pathways after evaluation of this value to ensure that it is not less than natural background and for analytical considerations as indicated in WAC 173-340-700(6)(d), "Overview of Cleanup Standards," "Requirements for Setting Cleanup Levels," "Natural Background and Analytical Considerations."

<sup>3</sup> Trends for these constituents are currently increasing, but the contamination is from sources other than the 216-A-29 Ditch.

<sup>4</sup> All values reported as undetected with variable detection limits ranging from 1,000  $\mu\text{g/L}$  to 36  $\mu\text{g/L}$ .

<sup>5</sup> All values reported as undetected with variable detection limits ranging from 10  $\mu\text{g/L}$  to 0.058  $\mu\text{g/L}$ .

<sup>6</sup> All values reported as undetected with variable detection limits ranging from 3,000  $\mu\text{g/L}$  to 1.6  $\mu\text{g/L}$ .

<sup>7</sup> The clean up level of 0.0146  $\mu\text{g/l}$  is below the practical quantitation limit. Clean closure is based on the practical quantitation limit.

HEIS = *Hanford Environmental Information System.*

MCL = maximum contaminant level.

N/A = not applicable.


Part A = DOE 2002, *216-S-10 Pond and Trench Part A, Form 3 Dangerous Waste Permit Application, Rev. 6.*

SMCL = secondary maximum contaminant level.

U = undetected.

1  
2

Figure E-2. Borehole and Test Pit Location Map for the 216-A-29 Ditch.



G:\Maps\042999M.DWG

1 Two of the three wells that exceeded the critical mean for specific conductance in fiscal year  
2 2003 continued to exhibit an increasing trend. The trend for the third well has reached a plateau.  
3 Elevated sulfate levels have been shown to increase specific conductance at the 216-A-29 Ditch  
4 in the past. Sulfate levels continued to rise in network wells – most of them with a concomitant  
5 rise in specific conductance. This association also has been reported near the Liquid Effluent  
6 Retention Facility, Low-Level Waste Management Area 2, and Waste Management Areas A-AX  
7 and C. All of these waste management areas are located at the west edge of the decommissioned  
8 B Pond. The direction of groundwater flow near the 216-A-29 Ditch generally is to the  
9 south-southwest, and the gradient is largely flat. The B Pond continues to create a small  
10 hydraulic barrier that contributes to now localized reversals of groundwater flow. The lower  
11 mud unit of the Ringold Formation inhibits flow to the east near the 216-A-29 Ditch and  
12 groundwater, therefore, is forced to the south. The resulting groundwater flow rate is low, not  
13 exceeding ~0.1 m/day.

#### 14 **E5.1 HISTORY OF RCRA GROUNDWATER** 15 **MONITORING**

16 The RCRA groundwater monitoring of the 216-A-29 Ditch began in November 1988 with an  
17 interim-status indicator parameter evaluation (detection-level) program (DOE/RL-92-03, *Annual*  
18 *Report for RCRA Groundwater Monitoring Projects at Hanford Site Facilities for 1991*). The  
19 wells were sampled quarterly for one year to establish background levels. Background sampling  
20 was completed in August 1989. The program was elevated to an assessment-level program in  
21 1990 because of elevated specific conductance beyond the critical mean in one downgradient  
22 well. The results of the groundwater quality assessment, which concluded in 1995, are reported  
23 in WHC-SD-EN-EV-032, *Results of the Groundwater Quality Assessment Program at the*  
24 *216-A-29 Ditch*. The program then reverted to indicator evaluation monitoring in October 1996.

#### 25 **E5.2 AQUIFER IDENTIFICATION**

26 The uppermost or unconfined aquifer beneath the 216-A-29 Ditch is approximately 2 to 24 m  
27 (7 to 79 ft) thick and is contained within sediments of the Hanford formation and the Ringold  
28 Formation. The aquifer extends from the water table to the top of the basalt or, in some areas,  
29 the lower mud unit of the Ringold Formation. Groundwater flow is to the southwest because of  
30 the groundwater recharge from the 216-B-3 Pond system. The average groundwater flow  
31 velocities range from approximately 0.03 to 0.09 m/day (PNNL-13047). The water table beneath  
32 the ditch has declined significantly since the discharges to the 216-B-3 Pond system ceased.

#### 33 **E5.3 WELL LOCATION AND DESIGN**

34 At the end of the assessment monitoring program, the monitoring well network reverted to a  
35 smaller group of 10 wells. There were two upgradient wells (699-43-43 and 699-43-45) and  
36 eight downgradient wells. Well 699-43-43 no longer produces representative groundwater  
37 samples and was removed from the sampling schedule in 2001. The downgradient wells

1 (prefixed by 299-) are E25-26, E25-28, E25-32P, E25-34, E25-35, E25-48, E26-12, and E26-13  
2 (Figure E-2). All of the wells are sampled semiannually with dedicated sampling pumps.

3 Construction of wells followed the RCRA standard well-construction specifications. The  
4 standards in WAC 173-160, "Minimum Standards for Construction and Maintenance of Wells,"  
5 were used to set the basic design requirements. The interim-status groundwater monitoring  
6 network for the 216-A-29 Ditch includes 10 wells constructed from 1985 through 1992. Nine of  
7 the wells are constructed with screens at the water table, and the remaining well is screened  
8 above the top of the basalt. Construction summaries and details of drilling and design  
9 specifications for all wells in the interim-status groundwater monitoring system are contained in  
10 several reports and are available upon request. Two upgradient wells (699-43-43 and 699-43-45)  
11 were selected to determine the background groundwater chemistry.

#### 12 **E5.4 RESULTS OF RCRA INTERIM-STATUS** 13 **GROUNDWATER MONITORING DATA**

14 The RCRA indicator parameters are specific conductance, pH, total organic carbon, and total  
15 organic halides. Site-specific parameters include inductively coupled plasma metals, anions,  
16 alkalinity, and turbidity. These constituents, other than turbidity, are analyzed annually although  
17 the wells are sampled semiannually. Groundwater quality parameters are chloride, iron  
18 (filtered), manganese (filtered), phenols, sodium (filtered), and sulfate. The 216-A-29 Ditch was  
19 placed into an assessment-level groundwater monitoring program in 1990 because of elevated  
20 specific conductance beyond the critical mean in one downgradient well. From that time until  
21 1995, comprehensive sampling and analysis were performed to determine the cause of this  
22 exceedance. The assessment report (WHC-SD-EN-EV-032) concluded that elevated specific  
23 conductance was caused by high concentrations of sulfate, sodium, and calcium in the  
24 groundwater beneath the 216-A-29 Ditch. The TSD unit reverted to an indicator parameter  
25 evaluation program. In fiscal year 2004, specific conductance increased slightly in nearly all of  
26 the network wells.

27 The groundwater near the 216-A-29 Ditch displays pH at levels above interim drinking water  
28 standards, but these are not considered attributable to the TSD unit. Unfiltered chromium and  
29 iron historically have exceeded drinking water standards in several wells, but filtered results have  
30 not exceeded the drinking water standard. These concentrations have been attributed to well  
31 construction and oxidizing conditions in the aquifer.

1

**This page intentionally left blank.**

1                   **E6.0 CLOSURE STRATEGY AND PERFORMANCE STANDARDS**

2   This chapter identifies the 216-A-29 Ditch closure strategy and closure performance standards  
3   for soils. Groundwater is discussed in Section 5.0.

4   **E6.1           CLOSURE STRATEGY**

5   The standards for closure of Hanford Facility interim-status TSD units are contained in  
6   WAC 173-303-610, "Dangerous Waste Regulations," "Closure and Post-Closure," based on the  
7   *Hanford Federal Facility Agreement and Consent Order Action Plan (Tri-Party Agreement*  
8   *Action Plan)* (Ecology et al. 1989b), Section 5.3. The possibility for clean closure for all TSD  
9   units at the Hanford Facility is described in the Tri-Party Agreement Action Plan, Section 6.3.1.

10   **E6.2           CLOSURE PERFORMANCE STANDARDS**

11   This section identifies general clean-closure performance standards and the specific closure  
12   standards for the soils.

13   **E6.2.1        Treatment, Storage, and Disposal Unit**  
14   **Closure Performance Standards**

15   The closure performance standards of WAC 173-303-610(2)(a)(i - iii), "Dangerous Waste  
16   Regulations," "Closure and Post-Closure," "Closure Performance Standard," require the owner  
17   or operator of a TSD facility to close the facility in a manner that: (1) "minimizes the need for  
18   further maintenance," (2) "controls, minimizes, or eliminates, to the extent necessary to protect  
19   human health and the environment, postclosure escape of dangerous waste, dangerous waste  
20   constituents, leachate, contaminated runoff, or dangerous waste decomposition products to the  
21   ground, surface water, groundwater, or the atmosphere" and, (3) "returns the land to the  
22   appearance and use of surrounding land areas to the degree possible given the nature of the  
23   previous dangerous waste activity." These standards can be met by the clean-closure removal or  
24   decontamination standard of WAC 173-303-610(2)(b) or by implementing the alternative closure  
25   requirements of WAC 173-303-610(1)(e), "Dangerous Waste Regulations," "Closure and  
26   Post-Closure," "Applicability."

27   Potential contaminant exposures and health impacts to humans are largely dependent on land  
28   use. The land use for the 200 Areas selected by The U.S. Department of Energy through  
29   64 FR 61615, "Record of Decision: Hanford Comprehensive Land-Use Plan Environmental  
30   Impact Statement (HCP EIS)," is industrial (exclusive). Industrial cleanup standards are  
31   identified in WAC 173-340-745(5), "Soil Cleanup Standards for Industrial Properties,"  
32   "Method C Industrial Soil Cleanup Levels." Before the application of the WAC 173-340-745(5)  
33   standards, however, clean closure is evaluated based on the traditional application of  
34   WAC 173-340-740(3), "Unrestricted Land Use Soil Cleanup Standards," "Method B Soil  
35   Cleanup Levels for Unrestricted Land Use," as required by WAC 173-303-610(2)(b)(i).

1 The standards in WAC 173-340-745(5) can be imposed through the alternative closure  
2 requirements of WAC 173-303-610(1)(e).

3 The first approach to examine for TSD unit closure is clean closure. Clean closure will eliminate  
4 the need for future inspections and maintenance necessitated by TSD unit constituent  
5 contamination. Clean closure also will eliminate the need for future postclosure monitoring and  
6 maintenance of the soils. Clean closure using the WAC 173-340-740(3) values were examined  
7 first because if the DOE/RL-2004-17 data showed that the soils met WAC 173-340-740(3)  
8 values as is without further remediation, the TSD unit clean closure can occur independent of the  
9 OU remediation activities.

10 If the TSD unit constituents cannot meet the WAC 173-340-740(3) values, then the  
11 WAC 173-340-745(5) values are used to determine if the closure standard has been met. If the  
12 DOE/RL-2004-17 data showed that the soils met WAC 173-340-745(5) values as is without  
13 remediation, the alternative closure requirements of WAC 173-303-610(1)(e) would be used to  
14 implement closure.

15 To achieve clean closure following remediation of the soils, verification sampling and analysis  
16 must be used to demonstrate that TSD unit constituent concentrations meet the closure standard.

#### 17 **E6.2.2 Soil Closure Standards**

18 The clean-closure requirements are established in WAC 173-303-610(2)(b) and the surface  
19 impoundment standards in WAC 173-303-650(6)(a), "Dangerous Waste Regulations," "Surface  
20 Impoundments," "Closure and Post-Closure Care," to remove or decontaminate unit soils  
21 contaminated above clean-closure standards. These soil clean-closure cleanup levels are the  
22 numeric levels identified in WAC 173-340-740(3) that are either: (1) levels calculated using the  
23 most restrictive WAC 173-340-740(3) formulas for unrestricted use, or (2) background levels  
24 (DOE/RL-92-24, *Hanford Site Background: Part 1, Soil Background for Nonradioactive*  
25 *Analytes*) when the most restrictive WAC 173-340-740(3) formulas are more stringent than  
26 Hanford Site background concentrations.

27 WAC 173-340-740(3) contains the following potential clean-closure standards: Environmental  
28 protection related to ecological receptors, soil concentrations protective of groundwater, soil  
29 direct-contact carcinogens, soil direct-contact noncarcinogens, soil direct-contact petroleum  
30 vapors, and soil vapors. The 'environmental protection related to ecological receptors' values  
31 are not a clean-closure standard for TSD unit closure, based on WAC 173-340-7493(2)(a)(i),  
32 "Site-Specific Terrestrial Ecological Evaluation Procedures," "Problem Formulation Step," "The  
33 Chemicals of Ecological Concern.") The 'soil concentration protective of groundwater,' 'soil  
34 direct-contact carcinogens,' and 'soil direct-contact noncarcinogens' are applicable and are  
35 identified in Table E-1. The 'soil concentrations protective of groundwater' value for nitrate was  
36 established using the alternative fate and transport provisions in WAC 173-340-747(8),  
37 "Deriving Soil Concentrations for Ground Water Protection," "Alternative Fate and Transport  
38 Models," as described in DOE/RL-2005-63, *Feasibility Study for the 200-CS-1 Chemical Sewer*  
39 *Group Operable Unit*, Section 2.13 and Table 3-1. The 'soil direct-contact petroleum vapors'  
40 and 'soil vapors' standards do not apply, because there are no petroleum compounds and no  
41 volatile organic compounds related to TSD unit closure, respectively.

1 WAC 173-340-745(5) contains the identical potential clean-closure standards as  
2 WAC 173-340-740(3)<sup>1</sup>. The applicability statements for the individual pathways stated above  
3 under WAC 173-340-740(3) also apply to the WAC 173-340-745(3), "Soil Cleanup Standards  
4 for Industrial Properties," "Method A Industrial Soil Cleanup Levels," standards. In addition,  
5 the following individual pathways and their methods to arrive at a standard are identical:  
6 environmental protection related to ecological receptors, soil concentrations protective of  
7 groundwater, and soil vapors. There is no difference in these standards when comparing  
8 WAC 173-340-740(3) to WAC 173-340-745(5). The only differences between  
9 WAC 173-340-740(3) and WAC 173-340-745(5) for applicable standards are: 'soil direct-  
10 contact carcinogens,' and 'soil direct-contact noncarcinogens.' See Table E-1 for additional  
11 information on the clean-closure standards.

12 Historical listed waste (U133) hydrazine discharges will not prevent clean closure of the  
13 216-A-29 Ditch. Hydrazine was ruled out as a potential contaminant of concern during the data  
14 quality objectives (DQO) process for the 200-CS-1 OU. The DQO report (BHI-01276,  
15 *200-CS-1 Operable Unit DQO Summary Report*) states: "Hydrazine is a listed waste that was  
16 potentially discharged with the cooling waters. However, because hydrazine is extremely  
17 reactive and volatile, it no longer is present in any media associated with the 200-CS-1 OU."  
18 The practical quantitation limit for hydrazine exceeds the soil concentration protective of  
19 groundwater standard of 0.0000625. Therefore, the practical quantitation limit is used for  
20 clean-closure determinations. Furthermore, 216-A-29 Ditch hydrazine was subject to  
21 a contained-in determination by Ecology (letter 072750, "200 Area Hydrazine Contained-In  
22 Determination Strategy"; letter 02-RCA-0261, "216-A-29 Ditch Hydrazine Contained-in  
23 Determination (CID) Request"; Ecology 2002, "Letter, J. Hebdon, U.S. Department of Energy,  
24 to J. B. Price, Washington State Department of Ecology, 216-A-29 Ditch Hydrazine  
25 Contained-in Determination (CID) Request, DOE/RL 02-RCA-0261, dated April 4, 2004").  
26 This contained-in determination addressed the 216-A-29 Ditch soils. Therefore, clean closure  
27 can be pursued for hydrazine at the 216-A-29 Ditch, and the U133 waste code no longer applies  
28 to 216-A-29 Ditch soils. Clean closure for hydrazine is based on the DQO process and the  
29 contained-in determinations.

---

<sup>1</sup> Clean closure using health based standards other than those prescribed by WAC 173-303-610(2)(b)(i) is described in two memos: (1) EPA, 1996, "Coordination Between RCRA Corrective Action and Closure and CERCLA Site Activities," and (2) EPA, 1998, "Risk Based Clean Closure."

**This page intentionally left blank.**

**E7.0 CLOSURE ACTIVITIES**

This chapter summarizes clean-closure activities for the 216-A-29 Ditch performed as part of the 200-CS-1 OU remediation process. Physical closure activities included TSD unit physical isolation, borehole and test pit drilling, sampling and analysis, removal of 216-A-29 Ditch soils, and verification sampling following soil removal. Administrative closure activities also are discussed (e.g., certification).

The unit soils are planned to be clean closed based on the results of DOE/RL-2004-17 and remediation of the 216-A-29 Ditch soils. Soil will be removed and generated as waste. The soil generated as a waste will require subsequent designation according to WAC 173-303-070(3), "Designation of Dangerous Waste," "Designation Procedures," and (5), "Additional Designation Required," and management as part of closure. Because soils are not expected to be designated as dangerous waste, treatment of the soils is not expected before they are disposed of at the Environmental Restoration Disposal Facility.

**E7.1 TREATMENT, STORAGE, AND DISPOSAL UNIT PHYSICAL ISOLATION**

To preclude any further discharges to the unit and in support of TSD unit closure, the 216-A-29 Ditch was physically isolated from receipt of the PUREX Plant chemical sewer effluent. Stabilization of the 216-A-29 Ditch was performed in three phases from July to October 1991. The trench no longer can accept dangerous waste.

**E7.2 TREATMENT, STORAGE, AND DISPOSAL UNIT SAMPLING AND ANALYSIS**

The following sections describe sampling and analyses activities that have been completed for the 216 A-29 Ditch.

**E7.2.1 Soil Sampling and Analysis**

As part of the 200-CS-1 OU remedial investigation, data were collected to characterize the nature and vertical extent of contamination and the physical conditions in the vadose zone underlying the 216-A-29 Ditch. Drilling, test pit excavation, surface and borehole geophysical surveys, and soil sampling and analysis were conducted during the field activities. Borehole and test pit locations are shown in Figure E-2.

Borehole B8826 was drilled and sampled in the 216-A-29 Ditch east of the AP Tank Farm in the 200 East Area. Test Pits AD-1 through AD-3 were excavated and sampled at the 216-A-29 Ditch in fiscal year 2002, and details are summarized in DOE/RL-2004-17. Data collected from Test Pit AD-3 was additional to the data required by DOE/RL-99-44, *200-CS-1 Operable Unit RI/FS Work Plan and RCRA TSD Unit Sampling Plan*, and was used to support

1 the decision-making process for locating a proposed waste transfer line to the Waste Vitrification  
2 Plant.

3 Borehole B8826 was drilled and sampled during fiscal year 2003. The borehole was drilled  
4 through the 216 A-29 Ditch, from the ground surface to a depth of 83.2 m (273 ft). The borehole  
5 was logged using a high-resolution spectral gamma-ray logging system and a neutron-moisture  
6 logging system. The borehole was drilled to better define stratigraphy and to assess the nature  
7 and vertical extent of contamination, as well as to determine the physical properties of the soil  
8 beneath the TSD unit.

9 The test pit locations were prepared by removing 0.3 to 0.6 m (1 to 2 ft) of topsoil from the site.  
10 The test pits were excavated to a maximum depth of 7 m (25 ft) below ground surface using a  
11 track-hoe. Samples were obtained directly from the track-hoe bucket at intervals of  
12 approximately 0.7 m (2.5 ft). Before being placed in a sample jar, soil samples were screened in  
13 the field to assist in selecting sample points, to support worker health and safety, and to provide  
14 shipping information. Samples were analyzed for chemical and physical properties. The test pits  
15 were backfilled in the reverse order from which they were excavated, using the track hoe.

16 Soils from the boreholes and test pits were screened in the field both for indications of  
17 contamination and for assisting in determining the discrete sample locations or depths before the  
18 samples were collected. Soil samples were collected for analysis and determination of physical  
19 properties. The sampling approach generally required a greater sample frequency near the  
20 bottom of the TSD unit, which is the area of highest suspected contamination. Sample collection  
21 always was attempted at depths of 4.6 and 7.6 m (15 and 25 ft) below ground surface to define  
22 contamination profiles. Sample frequency generally was reduced to 6.1 to 15.2 m (20- to 50-ft)  
23 intervals below a depth of 7.6 m (25 ft) in the boreholes.

24 Soil samples were analyzed for the constituents of concerns from DOE/RL-2004-17. Samples  
25 were analyzed selectively for field bulk density and moisture content. In addition, ditch bottom  
26 samples from each of the test pits were analyzed for an expanded list of compounds, to satisfy  
27 waste-designation requirements. Soil descriptions were recorded to better define stratigraphic  
28 relationships in the OU. The results obtained from previous characterization activities also were  
29 evaluated as part of this remedial investigation.

### 30 **E7.2.2 Soil Sample Results**

31 Analytical results obtained from the remedial investigation were intended for RCRA closure  
32 decisions and are defensible for use in this closure plan. Table E-1 identifies the maximum  
33 concentration of TSD unit constituents in shallow soils and deep-zone soils from  
34 DOE/RL-2004-017, Tables 4-1 and 4-3. The maximum values are compared to the clean-closure  
35 levels described in Section 6.2.2.

36 After comparing the TSD unit constituent concentrations found in DOE/RL-2004-17, Tables 4-1  
37 and 4-3, to the WAC 173-340-740(3) values, the TSD unit was not eligible for clean closure  
38 without remediation. The TSD unit constituent concentrations were then compared to the  
39 WAC 173-340-745(5) values with the same result. Not all constituents met the  
40 WAC 173-340-745(5) standard without remediation. Remediation of the 216-A-29 Ditch soils

1 will prevent the need for barrier construction as part of the 200-CS-1 OU decision making. The  
2 WAC 173-340-745(5) standards still can be used to meet clean-closure standards.

3 Table E-1 shows that six of eight TSD unit constituents (sodium, potassium, ammonia, fluoride,  
4 cadmium, and hydrazine) meet the clean-closure standard, the constituent is not regulated, or, in  
5 the case of hydrazine, other provisions are used to demonstrate clean closure. Nitrate and sulfate  
6 are the TSD unit constituents that do not meet the clean-closure standard. To meet  
7 WAC 173-340-745(5) cleanup levels, 216-A-29 Ditch soils will require removal. Furthermore,  
8 because the 200-CS-1 OU is removing the 216-A-29 Ditch soils, the closure approach for the  
9 soils will be to remove the 216-A-29 Ditch soils and conduct verification sampling.

### 10 **E7.3 OTHER ACTIVITIES REQUIRED FOR** 11 **CLOSURE**

12 The 200-CS-1 OU activities planned to support clean closure of the TSD unit include the  
13 removal of the 216-A-29 Ditch soils. This activity is expected to achieve clean closure for the  
14 TSD unit soils. In addition, a DQO action with follow-on verification sampling will be  
15 performed to determine if the clean-closure levels have been met, as part of the 200-CS-1 OU  
16 activities. After closure, appearance of the land will be consistent with future land-use  
17 determinations for adjacent portions of the 200 Areas as an industrial-exclusive portion of the  
18 Hanford Facility.

### 19 **E7.4 INSPECTIONS**

20 The TSD unit has been inspected to ensure that it meets interim-status requirements. Annual  
21 inspections are performed based on Ecology approval in 2003. Following closure certification as  
22 described in Section 7.8, inspections for the 216-A-29 Ditch will be discontinued.

### 23 **E7.5 TRAINING**

24 A dangerous waste training plan has been maintained for the TSD unit to meet interim-status  
25 requirements. The duties associated with dangerous waste management activities include  
26 performing inspections, notifying Ecology of any potential threats to human health and the  
27 environment, and performing groundwater monitoring. Following closure certification as  
28 described in Section 7.8, the dangerous waste training plan addressing the 216-A-29 Ditch waste  
29 management duties will be discontinued. Following approval of this closure plan, the dangerous  
30 waste training plan will be revised to remove the groundwater monitoring duties.

31 During the time that the remaining closure activities are performed, as described in Section 7.6,  
32 personnel training will be conducted in accordance with the CERCLA training requirements  
33 contained in 40 CFR 300.150, "National Oil and Hazardous Substances Pollution Contingency  
34 Plan," "Worker Health and Safety."

1 **E7.6 SCHEDULE FOR CLOSURE**

2 The remaining closure activities for this TSD unit include (1) removal of the 216-A-29 Ditch  
3 soils, (2) completion of a DQO process for verification sampling, and (3) verification sampling  
4 of the soils. These activities will be conducted as part of the 200-CS-1 OU activities. Following  
5 submittal of this closure plan to Ecology, Ecology's 90-day review period begins in accordance  
6 with the Tri-Party Agreement Action Plan, Figure 9-2.

7 **E7.7 AMENDMENT OF CLOSURE PLAN**

8 As required by WAC 173-303-610(3)(b), "Dangerous Waste Regulations," "Closure and  
9 Post-Closure," "Closure Plan; Amendment of Plan," the closure plan will be amended if changes  
10 to closure activities require a modification of the approved closure plan. Modifications to this  
11 plan could occur as a result of the activities identified in Section 7.6.

12 **E7.8 CERTIFICATION OF CLOSURE**

13 Upon removal of the 216-A-29 Ditch soils, verification sampling must be performed to  
14 determine if the closure activities meet the clean-closure standard. When verification sampling  
15 results have been evaluated, closure activities under this closure plan are planned to have been  
16 completed.

17 In accordance with WAC 173-303-610(6), "Dangerous Waste Regulations," "Closure and  
18 Post-Closure," "Certification of Closure," within 60 days of completion of TSD unit closure, the  
19 U.S. Department of Energy will submit to the lead regulatory agency (Ecology) a certification of  
20 closure. Both DOE and the Co-Operator identified on the current Part A Permit Application  
21 (DOE 2002, *216-A-29 Ditch Part A, Dangerous Waste Permit Application*, Rev. 6) will sign the  
22 certification of closure, and an independent Registered Professional Engineer will state that the  
23 unit has been closed in accordance with the approved closure plan. The certification will be  
24 submitted by registered mail or an equivalent delivery service. Documentation supporting the  
25 independent Registered Professional Engineer's certification will be placed in the Administrative  
26 Record.

27

1

**E8.0 POSTCLOSURE PLAN**

2 The closure strategy for the 216-A-29 Ditch is clean closure with regard to TSD unit constituents  
3 for soils and groundwater. Therefore, no postclosure plan is required. If the verification  
4 sampling following removal of the 216-A-29 Ditch soils does not demonstrate clean closure, a  
5 postclosure plan will be prepared for the 216-A-29 Ditch. The postclosure plan will be  
6 submitted to Ecology within 180 days following certification of closure or as otherwise agreed to  
7 by Ecology, based on 200-CS-1 OU schedules.

**This page intentionally left blank.**

## E9.0 REFERENCES

- 1
- 2 02-RCA-0261, 2002, "216-A-29 Ditch Hydrazine Contained-in Determination (CID) Request,"  
3 (Letter to John Price, Washington State Department of Ecology, from Joel Hebdon,  
4 U.S. Department of Energy, Richland Operations Office, Richland, Washington,  
5 April 4, 2002.
- 6 40 CFR 265, Subpart F, "Interim Status Standards for Owners and Operators of Hazardous  
7 Waste Treatment, Storage, and Disposal Facilities," Subpart F, "Ground-Water  
8 Monitoring," Title 40, *Code of Federal Regulations*, Part 265, as amended.
- 9 40 CFR 265.93(b), "Interim Status for Owners and Operators of Hazardous Waste Treatment,  
10 Storage, and Disposal Facilities," "Preparation, Evaluation, and Response," Title 40,  
11 *Code of Federal Regulations*, Part 265.93(b), as amended.
- 12 40 CFR 300.150, "National Oil and Hazardous Substances Pollution Contingency Plan,"  
13 "Worker Health and Safety," Title 40, *Code of Federal Regulations*, Part 300.150,  
14 as amended.
- 15 64 FR 61615, "Record of Decision: Hanford Comprehensive Land-Use Plan Environmental  
16 Impact Statement (HCP EIS)," *Federal Register*, Vol. 64, No. 218, pp. 61615-61625,  
17 November 12, 1999.
- 18 072750, 1999, "200 Area Hydrazine Contained-In Determination Strategy," (Letter to  
19 E. R. Skinnarland, Washington State Department of Ecology, from B. L. Foley),  
20 U.S. Department of Energy, Richland Operations Office, Richland, Washington,  
21 September 21, 1999.
- 22 BHI-01276, 1999, *200-CS-1 Operable Unit DQO Summary Report*, Rev. 0, Bechtel Hanford,  
23 Inc., Richland, Washington.
- 24 *Comprehensive Environmental Response, Compensation, and Liability Act of 1980*,  
25 42 USC 9601 et seq.
- 26 DOE 2002, *216-A-29 Ditch Part A, Dangerous Waste Permit Application*, Rev. 6,  
27 U.S. Department of Energy, Richland Operations Office, Richland, Washington,  
28 July 1, 2002.
- 29 DOE/RL-89-28, 1994, *216-B-3 Expansion Ponds Closure Plan*, Rev. 2, Attachment 23 to  
30 Revision 6 of Ecology's *Hanford Facility RCRA Permit* (WA7890008967),  
31 U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- 32 DOE/RL-91-28, 1993, *Hanford Facility Dangerous Waste Permit Application*, General  
33 Information Portion, Rev. 7, U.S. Department of Energy, Richland Operations Office,  
34 Richland, Washington.

- 1 DOE/RL-92-03, 1992, *Annual Report for RCRA Groundwater Monitoring Projects at Hanford*  
2 *Site Facilities for 1991*, U.S. Department of Energy, Richland Operations Office,  
3 Richland, Washington.
- 4 DOE/RL-92-24, 1997, *Hanford Site Background: Part 1, Soil Background for Nonradioactive*  
5 *Analytes*, Rev. 3, 2 vols., U.S. Department of Energy, Richland Operations Office,  
6 Richland, Washington.
- 7 DOE/RL-93-74, 1995, *200-BP-11 Operable Unit RFI/CMS and 216-B-3 Main Pond,*  
8 *216-B-63 Trench, and 216-A-29 Ditch Work/Closure Plan*, Rev. 0, Draft B,  
9 U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- 10 DOE/RL-96-61, 1997, *Hanford Site Background: Part 3, Groundwater Background*, Rev. 0,  
11 U.S. Department of Energy, Richland Operations Office, Richland, Washington.
- 12 DOE/RL-99-44, 2000, *200-CS-1 Operable Unit RI/FS Work Plan and RCRA TSD Unit Sampling*  
13 *Plan*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland,  
14 Washington.
- 15 DOE/RL-2004-17, *Remedial Investigation Report for the 200-CS-1 Chemical Sewer Group*  
16 *Operable Unit*, Rev. 0, U.S. Department of Energy, Richland Operations Office,  
17 Richland, Washington.
- 18 DOE/RL-2005-63, 2006, *Feasibility Study for the 200-CS-1 Chemical Sewer Group Operable*  
19 *Unit*, Decisional Draft, U.S. Department of Energy, Richland Operations Office,  
20 Richland, Washington.
- 21 Ecology 2002, "Letter, J. Hebdon, U.S. Department of Energy, to J. B. Price, Washington State  
22 Department of Ecology, 216-A-29 Ditch Hydrazine Contained-in Determination (CID)  
23 Request, DOE/RL 02-RCA-0261, dated April 4, 2004," (Letter to J. B. Hebdon,  
24 U.S. Department of Energy, Richland Operations Office, from J. Hedges), Washington  
25 State Department of Ecology, Olympia, Washington, May 23, 2002.
- 26 Ecology, EPA, and DOE, 1989a, *Hanford Federal Facility Agreement and Consent Order*,  
27 2 vols., Washington State Department of Ecology, U.S. Environmental Protection  
28 Agency, and U.S. Department of Energy, Olympia, Washington, as amended.
- 29 Ecology, EPA, and DOE, 1989b, *Hanford Federal Facility Agreement and Consent Order*  
30 *Action Plan*, Washington State Department of Ecology, U.S. Environmental Protection  
31 Agency, and U.S. Department of Energy, Olympia, Washington.
- 32 EPA, 1996, "Coordination Between RCRA Corrective Action and Closure and CERCLA Site  
33 Activities," (memo to Elliot Laws, from Steve Herman), U.S. Environmental Protection  
34 Agency, Washington, D.C., September 24, 1996.
- 35 EPA, 1998, "Risk Based Clean Closure," (memo to RCRA senior policy advisors, from  
36 Elizabeth Cotsworth, Acting Director), U.S. Environmental Protection Agency,  
37 Washington, D.C., March 16, 1998.

- 1 *Hanford Environmental Information System*, Hanford Site database.
- 2 PNNL-13047, 1999, *Groundwater Monitoring Plan for the 216-A-29 Ditch*, Pacific Northwest  
3 National Laboratory, Richland, Washington.
- 4 PNNL-15070, 2005, *Hanford Site Groundwater Monitoring for Fiscal Year 2004*, Pacific  
5 Northwest National Laboratory, Richland, Washington.
- 6 *Resource Conservation and Recovery Act of 1976*, 42 USC 6901, et seq.
- 7 WA7890008967, 2004, *Hanford Facility Resource Conservation and Recovery Act Permit,*  
8 *Dangerous Waste Portion, Revision 8, for the Treatment, Storage, and Disposal of*  
9 *Dangerous Waste*, Washington State Department of Ecology, Richland, Washington, as  
10 amended.
- 11 WAC 173-160, "Minimum Standards for Construction and Maintenance of Wells," *Washington*  
12 *Administrative Code*, as amended, Washington State Department of Ecology, Olympia,  
13 Washington.
- 14 WAC 173-303, "Dangerous Waste Regulations," *Washington Administrative Code*, as amended,  
15 Washington State Department of Ecology, Olympia, Washington.
- 16 WAC 173-303-070(3), "Designation of Dangerous Waste," "Designation Procedures,"  
17 *Washington Administrative Code*, as amended, Washington State Department of Ecology,  
18 Olympia, Washington.
- 19 WAC 173-303-070(5), "Designation of Dangerous Waste," "Additional Designation Required,"  
20 *Washington Administrative Code*, as amended, Washington State Department of Ecology,  
21 Olympia, Washington.
- 22 WAC 173-303-090(6), "Dangerous Waste Characteristics," "Characteristic of Corrosivity,"  
23 *Washington Administrative Code*, as amended, Washington State Department of Ecology,  
24 Olympia, Washington.
- 25 WAC 173-303-400, "Dangerous Waste Regulations," "Interim Status Facility Standards,"  
26 *Washington Administrative Code*, as amended, Washington State Department of Ecology,  
27 Olympia, Washington.
- 28 WAC 173-303-610, "Dangerous Waste Regulations," "Closure and Post-Closure," *Washington*  
29 *Administrative Code*, as amended, Washington State Department of Ecology, Olympia,  
30 Washington.
- 31 WAC 173-303-610(1), "Dangerous Waste Regulations," "Closure and Post-Closure,"  
32 "Applicability," *Washington Administrative Code*, as amended, Washington State  
33 Department of Ecology, Olympia, Washington.

- 1 WAC 173-303-610(2), "Dangerous Waste Regulations," "Closure and Post-Closure," "Closure  
2 Performance Standard," *Washington Administrative Code*, as amended, Washington State  
3 Department of Ecology, Olympia, Washington.
- 4 WAC 173-303-610(3)(b), "Dangerous Waste Regulations," "Closure and Post-Closure,"  
5 "Closure Plan; Amendment of Plan," *Washington Administrative Code*, as amended,  
6 Washington State Department of Ecology, Olympia, Washington.
- 7 WAC 173-303-610(6), "Dangerous Waste Regulations," "Closure and Post-Closure,"  
8 "Certification of Closure," *Washington Administrative Code*, as amended, Washington  
9 State Department of Ecology, Olympia, Washington.
- 10 WAC 173-303-650(6)(a), "Dangerous Waste Regulations," "Surface Impoundments," "Closure  
11 and Post-Closure Care," *Washington Administrative Code*, as amended, Washington State  
12 Department of Ecology, Olympia, Washington.
- 13 WAC 173-340-700(6)(d), "Overview of Cleanup Standards," "Requirements for Setting Cleanup  
14 Levels," "Natural Background and Analytical Considerations," *Washington*  
15 *Administrative Code*, as amended, Washington State Department of Ecology, Olympia,  
16 Washington.
- 17 WAC 173-340-740(3), "Unrestricted Land Use Soil Cleanup Standards," "Method B Soil  
18 Cleanup Levels for Unrestricted Land Use," *Washington Administrative Code*,  
19 as amended, Washington State Department of Ecology, Olympia, Washington.
- 20 WAC 173-340-740(3)(b)(ii), "Unrestricted Land Use Soil Cleanup Standards," "Method B Soil  
21 Cleanup Levels for Unrestricted Land Use," "Standard Method B Soil Cleanup Levels,"  
22 "Environmental Protection," *Washington Administrative Code*, as amended, Washington  
23 State Department of Ecology, Olympia, Washington.
- 24 WAC 173-340-740(3)(b)(iii)(A), "Unrestricted Land Use Soil Cleanup Standards," "Method B  
25 Soil Cleanup Levels for Unrestricted Land Use," "Standard Method B Soil Cleanup  
26 Levels," "Human Health Protection," "Ground Water Protection," *Washington*  
27 *Administrative Code*, as amended, Washington State Department of Ecology, Olympia,  
28 Washington.
- 29 WAC 173-340-740(3)(b)(iii)(B)(I), "Unrestricted Land Use Soil Cleanup Standards," "Method B  
30 Soil Cleanup Levels for Unrestricted Land Use," "Standard Method B Soil Cleanup  
31 Levels," "Human Health Protection," "Soil Direct Contact," "Noncarcinogens,"  
32 *Washington Administrative Code*, as amended, Washington State Department of Ecology,  
33 Olympia, Washington.
- 34 WAC 173-340-740(6), "Unrestricted Land Use Soil Cleanup Standards," "Point of Compliance,"  
35 *Washington Administrative Code*, as amended, Washington State Department of Ecology,  
36 Olympia, Washington.

- 1 WAC 173-340-745(3), "Soil Cleanup Standards for Industrial Properties," "Method A Industrial  
2 Soil Cleanup Levels," *Washington Administrative Code*, as amended, Washington State  
3 Department of Ecology, Olympia, Washington.
- 4 WAC 173-340-745(3)(b), "Soil Cleanup Standards for Industrial Properties," "Method A  
5 Industrial Soil Cleanup Levels," "General Requirements," *Washington Administrative  
6 Code*, as amended, Washington State Department of Ecology, Olympia, Washington.
- 7 WAC 173-340-745(4), "Soil Cleanup Standards for Industrial Properties," "Method B Industrial  
8 Soil Cleanup Levels," *Washington Administrative Code*, as amended, Washington State  
9 Department of Ecology, Olympia, Washington.
- 10 WAC 173-340-745(5), "Soil Cleanup Standards for Industrial Properties," "Method C Industrial  
11 Soil Cleanup Levels," *Washington Administrative Code*, as amended, Washington State  
12 Department of Ecology, Olympia, Washington.
- 13 WAC 173-340-745(5)(b)(ii), "Soil Cleanup Standards for Industrial Properties," "Method C  
14 Industrial Soil Cleanup Levels," "Standard Method C Industrial Soil Cleanup Levels,"  
15 "Environmental Protection," *Washington Administrative Code*, as amended, Washington  
16 State Department of Ecology, Olympia, Washington.
- 17 WAC 173-340-745(5)(b)(iii)(A), "Soil Cleanup Standards for Industrial Properties," "Method C  
18 Industrial Soil Cleanup Levels," "Standard Method C Industrial Soil Cleanup Levels,"  
19 "Human Health Protection," "Ground Water Protection," *Washington Administrative  
20 Code*, as amended, Washington State Department of Ecology, Olympia, Washington.
- 21 WAC 173-340-745(5)(b)(iii)(B)(I and II), "Soil Cleanup Standards for Industrial Properties,"  
22 "Method C Industrial Soil Cleanup Levels," "Standard Method C Industrial Soil Cleanup  
23 Levels," "Human Health Protection," "Soil Direct Contact," "Noncarcinogens," and  
24 "Carcinogens," *Washington Administrative Code*, as amended, Washington State  
25 Department of Ecology, Olympia, Washington.
- 26 WAC 173-340-747(8), "Deriving Soil Concentrations for Ground Water Protection,"  
27 "Alternative Fate and Transport Models," *Washington Administrative Code*, as amended,  
28 Washington State Department of Ecology, Olympia, Washington.
- 29 WAC 173-340-7493(2)(a)(i), "Site-Specific Terrestrial Ecological Evaluation Procedures,"  
30 "Problem Formulation Step," "The Chemicals of Ecological Concern," *Washington  
31 Administrative Code*, as amended, Washington State Department of Ecology, Olympia,  
32 Washington.
- 33 WHC-EP-0342, 1990, Addendum 2, *PUREX Plant Chemical Sewer Stream-Specific Report*,  
34 Westinghouse Hanford Company, Richland, Washington.
- 35 WHC-SD-EN-EV-032, 1995, *Results of the Groundwater Quality Assessment Program at the  
36 216-A-29 Ditch*, Rev. 0, Westinghouse Hanford Company, Richland Washington.

1

**This page intentionally left blank.**

1

**APPENDIX F**

2

3

**SEASONAL SOIL COMPARTMENT MODEL**

**This page intentionally left blank.**

1 CONTENTS

2 F1.0 BASIS FOR SEASONAL SOIL COMPARTMENT MODEL AS AN  
3 ALTERNATIVE TRANSPORT AND FATE MODEL..... F-1

4 F2.0 DETAILED DESCRIPTION OF THE SESOIL MODEL..... F-2

5 F2.1 SESOIL OVERVIEW..... F-2

6 F2.2 SESOIL THEORY..... F-3

7 F2.2.1 Model Description..... F-3

8 F2.2.2 Soil Compartment..... F-3

9 F2.2.3 Hydrologic Cycle..... F-4

10 F2.2.4 Pollutant Fate Cycle..... F-7

11 F3.0 REFERENCES..... F-16

12

13 FIGURES

14 Figure F-1. SESOIL General Conceptualization..... F-20

15 Figure F-2. Schematic of the Monthly Hydrologic Cycle..... F-21

16 Figure F-3. Illustration of SESOIL Layer and Sub-Layer General Configuration for the  
17 200-CS-1 Operable Unit Waste Sites..... F-22

18

19 TABLES

20 Table F-1. Comparison of WAC 173-340-747(8) Requirements and SESOIL as  
21 Configured for 200-CS-1 Operable Unit Waste Sites..... F-23

22

**TERMS**

1

2	AGTEHM	Agricultural Terrestrial Ecosystem Hydrology Model
3	AP	airport
4	COPC	contaminant of potential concern
5	EPA	U.S. Environmental Protection Agency
6	$K_d$	chemical-specific distribution coefficient
7	$K_{oc}$	soil organic carbon-water partition coefficient
8	NWS	National Weather Service
9	OTS	U.S. Environmental Protection Agency, Office of Water and Toxic
10		Substances
11	OU	operable unit
12	SESOIL	Seasonal Soil Compartment Model
13	WAC	<i>Washington Administrative Code</i>

## APPENDIX F

## SEASONAL SOIL COMPARTMENT MODEL

F1.0 BASIS FOR SEASONAL SOIL COMPARTMENT MODEL AS AN  
ALTERNATIVE TRANSPORT AND FATE MODEL

The extended risk analysis uses as a vadose zone to groundwater alternative transport and fate model in accordance with the requirements in *Washington Administrative Code* (WAC) 173-340-747(8), "Deriving Soil Concentrations for Ground Water Protection," "Alternative Fate and Transport Models," in order to help clarify uncertainties in the understanding of the threats posed by shallow (0 to 15 ft [0 to 4.6 m]) soil contamination. The uncertainties stem from initial use of Equation 747-1 from WAC 173-340-747(8) to evaluate vadose zone soil contamination impacts on groundwater. Equation 747-1 is a screening tool that does not account for the significant depth to groundwater, typically 270 ft (94 m), or the deficiency of net infiltration typical of the Hanford Site. WAC 173-340-747(8) specifies procedures and requirements for establishing soil concentrations that are protective of groundwater using fate and transport models other than Equation 747-1.

The alternative fate and transport model used to evaluate soil to groundwater impacts is the Seasonal Soil Compartment Model (SESOIL). SESOIL was developed originally by the U.S. Environmental Protection Agency's Office of Water and Toxic Substances. The Oak Ridge National Laboratory has upgraded the model several times, including a major effort in 1995. General Sciences Corporation (GSC 1998, *SESOIL*) currently licenses the model. SESOIL is widely used in the hazardous waste industry to assess soil-to-groundwater impacts at *Comprehensive Environmental Response, Compensation, and Liability Act of 1980* and *Resource Conservation and Recovery Act of 1976* sites such as those found at the 200-CS-1 Operable Unit (OU) waste sites. Various states, including Colorado and Kansas, use SESOIL to evaluate the impacts that contaminants in soils may have on groundwater. A detailed discussion of SESOIL can be found in Section F2.0.

SESOIL is a compartment model that computes the mass movement of constituents from overlying strata to the underlying strata using advective moisture movement from infiltration, water balance, and constituent-partitioning algorithms. SESOIL helps clarify the groundwater impacts assessment, over the use of Equation 747-1 from WAC 173-340-747(8), by:

- Using local climatological data to drive the moisture flux
- Incorporating the significant depth to groundwater that is intrinsic to the Hanford Site
- Integrating constituent-specific migration and attenuation characteristics over time.

The constituent partitioning and depth of penetration aspects of SESOIL are governed by (1) the distribution coefficient (e.g.,  $K_d$ ) in a method that is essentially similar to that used by Equation 747-1, and (2) the vertical moisture velocity computed by the model using site-specific meteorological (i.e., Pasco National Weather Service data).

1 A comparison of requirements for the use of alternative fate and transport models, as set forth in  
2 WAC 173-340-740, with SESOIL, as configured for the 200-CS-1 OU waste sites, is provided in  
3 Table F-1.

4 Examination of Table F-1 indicates that the use of SESOIL as an alternative fate and transport  
5 model to clarify uncertainties in the refined risk analysis has been accomplished in accordance  
6 with WAC 173-340-747(8). The uncertainties arise from the use of Equation 747-1, which does  
7 not account for the significant depth to groundwater, typically 270 ft (94 m), nor does the  
8 equation account for the scarcity of net infiltration typical of the arid Hanford Site. SESOIL  
9 modeling results, detailed in Sections 2-12 and 2-13 are credible and consistent with observed  
10 monitoring data.

## 11 F2.0 DETAILED DESCRIPTION OF THE SESOIL MODEL

### 12 F2.1 SESOIL OVERVIEW

13 SESOIL is a one-dimensional vertical transport software code for the unsaturated soil zone  
14 (Figure F-1).<sup>1</sup> SESOIL is a unique model, both in its structure and its mathematics. An  
15 integrated screening-level soil compartment model, SESOIL is designed to simultaneously  
16 model water transport, sediment transport, and pollutant fate. However, for applications at the  
17 200-CS-1 OU waste sites, sediment transport was not used.

18 SESOIL was developed for the U.S. Environmental Protection Agency (EPA) Office of Water  
19 and the Office of Toxic Substances in 1981 by Arthur D. Little, Inc., Cambridge, Massachusetts  
20 (Bonazountas and Wagner 1981, *SESOIL: A Seasonal Compartment Model*) as part of the EPA  
21 Risk Analysis Program. The model was updated in 1984 to include a fourth soil compartment  
22 (the original model included up to three layers) and soil erosion algorithms (Bonazountas and  
23 Wagner 1984, "Modeling Mobilization and Fate of Leachate Below Uncontrolled Hazardous  
24 Waste Sites"). Following a comprehensive evaluation of SESOIL (Watson and Brown 1985,  
25 *Testing and Evaluation of the SESOIL Model*), SESOIL was enhanced at the Oak Ridge National  
26 Laboratory (Hetrick et al. 1986, "Model Predictions of Watershed Hydrologic Components:  
27 Comparison and Verification"; Hetrick et al. 1988, "Model Predictions of Watershed Erosion  
28 Components"; ORNL/TM-10672, *Qualitative Validation of Pollutant Transport Components of  
29 an Unsaturated Soil Zone Model [SESOIL]*).

30 SESOIL was developed as a screening-level model, using less soil, chemical, and meteorological  
31 values as input than most other similar models. Output of the SESOIL model includes  
32 time-varying pollutant concentrations at various soil depths and pollutant loss from the  
33 unsaturated zone in terms of surface runoff, percolation to the groundwater, volatilization, and  
34 degradation.

---

<sup>1</sup> Much of this section was excerpted nearly verbatim from Chapter 7.0 in Bonazountas et al. 1997, *SESOIL in Environmental Fate and Risk Modeling*.

1 SESOIL accepts time-varying pollutant loading. It can simulate chemical releases to soil from a  
2 variety of sources, including landfill disposal, accidental leaks, agricultural applications, leaking  
3 underground storage tanks, or deposition from the atmosphere. Applications of SESOIL include  
4 long-term leaching studies from waste disposal sites, pesticide and sediment transport in  
5 watersheds, studies of hydrological cycles and water balances in soil compartments, and  
6 pre-calibration runs for other simulation models. The model can be used to estimate the effects  
7 of various site management or design strategies on pollutant distributions and concentrations in  
8 the environment.

9 The soil column in SESOIL is a user-defined compartment extending from the surface through  
10 the unsaturated zone to the groundwater table. Typically, SESOIL is used to estimate the  
11 migration rate of chemicals through soils and the concentration of the chemicals in soil layers  
12 following a chemical release to the soil environment. SESOIL simulation of chemical  
13 persistence considers mobility, volatility, and degradation. This is consistent with its  
14 applications at the 200-CS-1 OU waste sites. The SESOIL model requires several chemical and  
15 site-specific parameters to estimate the concentration of the chemical in the soil, its rate of  
16 leaching toward groundwater, and its impact on other environmental pathways. The user is  
17 required to provide chemical properties and release rate, and soil and climate data.

## 18 F2.2 SESOIL THEORY

### 19 F2.2.1 Model Description

20 SESOIL is a one-dimensional vertical transport model for the unsaturated soil zone. The model  
21 is based on mass balance and equilibrium partitioning of the chemical between different phases  
22 (i.e., dissolved, sorbed, vapor, and pure). SESOIL was designed to perform *long-term*  
23 simulations of chemical transport and transformations in the soil. The model employs  
24 theoretically derived equations to represent water transport, sediment transport on the land  
25 surface, pollutant transformation, and migration of the pollutant to the atmosphere and  
26 groundwater. Climatic data, compartment geometry, and soil and chemical property data are the  
27 major components used in the equations.

28 Processes modeled by SESOIL are categorized into three cycles: hydrology, sediment (not used  
29 for the 200-CS-1 OU waste sites), and pollutant transport. Each cycle is a separate submodel  
30 within the SESOIL code. Most mathematical environmental simulation models may be  
31 categorized as stochastic (i.e., statistical) or deterministic models; both models are theoretically  
32 derived. Stochastic models incorporate the concept of probability or some other measure of  
33 uncertainty, while deterministic models describe the system in terms of cause-effect  
34 relationships. SESOIL employs a stochastic approach for the hydrologic cycle and a  
35 deterministic approach for the pollutant transport cycle.

### 36 F2.2.2 Soil Compartment

37 In SESOIL, the soil compartment (or column) is a cell extending from the surface through the  
38 unsaturated zone to the upper level of the saturated soil zone (aquifer or groundwater table).  
39 While SESOIL estimates the pollutant mass added to the groundwater, the saturated zone is not

1 modeled. The output from SESOIL can be used for generating input values for groundwater  
 2 transport models. In the version used for the 200-CS-1 OU waste sites, a simple  
 3 groundwater-mixing model (Summers model) takes the SESOIL output and estimates  
 4 groundwater concentrations. The Summers model is an integrated feature of the modeling  
 5 system provided in RISKPRO Version 3.0 (GSC 1998).

6 SESOIL performs simulation for three separate cycles within the soil compartment. The cycles  
 7 and the processes included in each cycle are as follows:

- 8 • Hydrologic cycle, which includes rainfall, infiltration, groundwater runoff (i.e., recharge),  
 9 surface runoff, capillary rise, evapotranspiration, and soil moisture retention (storage)
- 10 • Sediment cycle, which includes sediment wash load (erosion due to storms), which was  
 11 not simulated for the 200-CS-1 OU waste sites
- 12 • Pollutant fate cycle, which includes the processes of advection, diffusion (e.g., air phase)  
 13 volatilization, sorption, cation exchange, hydrolysis, wash load, surface runoff,  
 14 groundwater runoff (i.e., recharge), metal complexation, and chemical degradation/decay.  
 15 For the 200-CS-1 OU waste sites, advection, sorption, and groundwater runoff were the  
 16 principal processes simulated. Chemical degradation/decay was simulated to address  
 17 benzene contamination at the 216-B-63 Trench.

### 18 F2.2.3 Hydrologic Cycle

19 The hydrologic cycle, illustrated in Figure F-2, is one-dimensional submodel that considers  
 20 vertical movement only and focuses on the role of soil moisture (or interstitial pore water) in the  
 21 soil compartment. The hydrologic cycle submodel calculates results for the hydrology of a site  
 22 and transfers these results to the sediment wash load cycle and the pollutant fate cycle. The  
 23 hydrologic cycle used in SESOIL is an adaptation of the water balance dynamics theory of  
 24 Eagleson 1978, "Climate, Soil, and Vegetation." The theory can be described as a dimensionless  
 25 analytical representation of an annual water balance. It is itself a model based on interacting  
 26 hydrological processes, which include parameters governing climate, soil, and vegetation of a  
 27 basin. These processes are coupled through statistical algorithms.

28 It is beyond the scope of this discussion to present the detailed physics and mathematical  
 29 expressions used. The hydrologic cycle is thoroughly described by Eagleson (1978) and  
 30 summarized by Bonazountas and Wagner (1984). It is based on the water balance equations (see  
 31 Equations 1 and 2). All of these parameters are expected or mean annual values, and in SESOIL  
 32 they are expressed in centimeters:

$$33 \quad P - E - MR = S + G = Y \quad \text{Eq 1}$$

$$34 \quad I = P - S \quad \text{Eq 2}$$

1 where

- 2 P = precipitation  
 3 E = evapotranspiration  
 4 MR = moisture retention  
 5 S = surface runoff  
 6 I = infiltration  
 7 Y = yield  
 8 G = groundwater runoff or recharge (includes term for capillary rise).

9 Precipitation is represented by Poisson arrivals of rectangular gamma-distributed intensity pulses  
 10 that have random depth and duration. Infiltration is described by the Philip equation, which  
 11 assumes the medium to be effectively semi-infinite, and the internal soil moisture content at the  
 12 beginning of each storm and interstorm period to be uniform at its long-term average.

13 Percolation to the groundwater is assumed to be steady throughout each time step of simulation,  
 14 at a rate determined by the long-term average soil moisture content. Capillary rise from the  
 15 water table is assumed to be steady throughout the time period and to take place to a dry surface.  
 16 Surface runoff is derived from the distribution of rainfall intensity and duration, and by use of  
 17 the Philip infiltration equation. The effects of moisture storage are included in the monthly  
 18 option in SESOIL, based on the work of Eagleson as modified by Bonazountas and  
 19 Wagner (1984).

20 Eagleson's theory assumes a one-dimensional vertical analysis in which all processes are  
 21 stationary at the long-term average. Eagleson's approach assumes that soils are homogeneous  
 22 and that the soil column is semi-infinite in relation to the surface processes. Thus, in the  
 23 hydrologic cycle of SESOIL, the entire unsaturated soil zone is conceptualized as a single layer  
 24 (or compartment), and the prediction for soil water content is an average value for the entire  
 25 unsaturated zone.

26 While the user can provide different permeability values as input for each of the four major soil  
 27 layers for SESOIL's pollutant cycle, the hydrologic cycle will compute and use the  
 28 depth-weighted average permeability according to the formula shown in Equation 3:

Eq 3

$$K_z = \frac{d}{\sum_{i=1}^n \frac{d_i}{K_i}}$$

32 where

- 33  $K_z$  = vertically averaged permeability ( $\text{cm}^2$ )  
 34  $K_i$  = permeability for layer  $i$  ( $\text{cm}^2$ )  
 35  $d$  = depth from surface to groundwater (cm)  
 36  $d_i$  = thickness of layer  $i$  (cm).

1 There is no explicit consideration of snow and ice, which are entered as precipitation. The model  
 2 assumes that the water table elevation is constant, with no change in groundwater storage from  
 3 year to year. Bonazountas et al. (1984) adopted this theory for annual and monthly simulations.

4 Each process in Equations 1 and 2 is written in terms of the soil moisture content. Solution of  
 5 the equations is accomplished by iterating on soil moisture until the calculated value for  
 6 precipitation is within 1 percent of the measured value input by the user. When this iteration is  
 7 completed, components such as infiltration and evapotranspiration in Equations 1 and 2 are  
 8 known. SESOIL uses this procedure in the annual and monthly routines. The monthly routine is  
 9 an extension of the annual routine. The monthly routine, used for the 200-CS-1 OU waste sites,  
 10 is discussed below.

### 11 *Monthly Hydrologic Cycle*

12 The monthly water balance routine is based on the same theory as the annual routine, with  
 13 modifications made to the details of moisture transfer from month to month (handling of  
 14 moisture storage) and to the radiation effects. The initial value for soil moisture content is  
 15 calculated in SESOIL by summing the appropriate monthly climatic input data (for the first year)  
 16 to obtain annual values and using the annual cycle algorithm. Then, for each month, the monthly  
 17 input values for precipitation, mean storm number, and mean length of the rain season are  
 18 multiplied by 12 to again obtain annual values. Equations 1 and 2 then are solved to compute the  
 19 soil moisture content, and the results for the components (e.g., infiltration, evapotranspiration)  
 20 are divided by 12 to attain average monthly values.

21 The monthly cycle in SESOIL accounts for the change in moisture storage from month to  
 22 month, incorporating the work of Metzger and Eagleson 1980, "The Effects of Annual Storage  
 23 and Random Potential Evapotranspiration on the One-Dimensional Annual Water Balance").  
 24 The SESOIL evapotranspiration algorithm has been modified from the original work of  
 25 Eagleson (1978) to include seasonal changes in average monthly radiation (radiation was a  
 26 constant function of latitude before). Hetrick 1984, "Simulation of the Hydrologic Cycle for  
 27 Watersheds," observed that hydrology predictions of the original SESOIL model were  
 28 insensitive to seasonal changes in meteorological data. To model the hydrology more  
 29 realistically, an algorithm from the Agricultural Terrestrial Ecosystem Hydrology Model  
 30 (AGTEHM) model (ORNL/TM-7856, *AGTEHM: Documentation of Modifications to the*  
 31 *Terrestrial Ecosystem Hydrology Model (TEHM) for Agricultural Applications*) is now used.  
 32 The AGTEHM algorithm computes daily potential radiation (incoming radiation for cloudless  
 33 skies) for a given latitude and Julian date (December 31= 365). The middle day of the month is  
 34 used in the algorithm and the effect of cloud cover is calculated with the expression (Hetrick et  
 35 al. 1986) shown in Equation 4:

$$36 \quad S_{avg} = S[(i-C) + k \cdot C] \quad \text{Eq 4}$$

37 where

- 38  $S_{avg}$  = the average monthly solar radiation  
 39  $S$  = the potential radiation  
 40  $C$  = the fraction of sky covered by clouds  
 41  $k$  = the transmission factor of cloud cover.

1 The value for k used in SESOIL is 0.32 as suggested by ORNL/TM-7856. Because latitude and  
 2 monthly cloud cover are required input for SESOIL (e.g., Pasco National Weather Service  
 3 Station for the 200-CS-1 waste sites), no new input data are needed to support this modification.

4 SESOIL model predictions (using the monthly option) of watershed hydrologic components have  
 5 been compared to those of (1) the more data-intensive terrestrial ecosystem hydrology model  
 6 AGTEHM (ORNL/TM-7856), and (2) empirical measurements at a deciduous forest watershed  
 7 and a grassland watershed (Hetrick et al. 1986). Although there were some differences in  
 8 monthly results between the two models, good agreement was obtained between model  
 9 predictions for annual values of infiltration, evapotranspiration, surface runoff, and groundwater  
 10 runoff (recharge). In addition, SESOIL model predictions compared well with the empirical  
 11 measurements at the forest stand and the grassland watersheds.

12 Figure F-3 illustrates how the SESOIL layer and sub-layer system typically were configured for  
 13 the 200-CS-1 OU waste sites.

#### 14 *Hydrologic Calibration*

15 Calibration of unsaturated soil zone models can be uncertain and difficult because climate, soil  
 16 moisture, soil infiltration, and percolation are strongly interrelated parameters that are difficult  
 17 and expensive to measure in the field. If possible, input parameters for any unsaturated soil zone  
 18 model should be calibrated so that hydrologic predictions agree with observations.

19 In SESOIL, all input parameters required for the hydrologic cycle can be estimated from field  
 20 studies with the exception of the pore disconnectedness index, "c." This parameter is defined as  
 21 the exponent relating the "wetting" or "drying" time-dependent permeability of a soil to its  
 22 saturated permeability (Eagleson 1978; Eagleson and Tellers 1982, "Ecological Optimality in  
 23 Water-Limited Natural Soil-Vegetation Systems, 2. Tests and Applications"). Brooks and  
 24 Corey 1966, "Properties of Porous Media Affecting Fluid Flow," presented the relationship  
 25 shown in Equation 5:

$$26 \quad K(S) = K(I) * S^c \quad \text{Eq 5}$$

27 where

28  $K(I)$  = saturated hydraulic conductivity (cm/s)

29  $K(S)$  = hydraulic conductivity at S (cm/s)

30 S = percent saturation

31 c = pore disconnectedness index.

32 This parameter is not commonly found in the literature. Default values for "c" proposed by  
 33 Eagleson (1978) and Bonazountas and Wagner (1981, 1984) are clay, 12; silty clay loam, 10;  
 34 clay loam, 7.5; sandy loam, 6; silt loam, 5.5; sandy clay loam, 4; and sand, 3.7.

#### 35 **F2.2.4 Pollutant Fate Cycle**

36 The pollutant fate cycle focuses on the various chemical transport and transformation processes  
 37 that may occur in the soil. These processes were summarized in Section 2.2.2, and are discussed

1 in more detail below. The pollutant fate cycle uses calculated results from the hydrologic cycle  
2 that are automatically provided to the pollutant fate cycle.

3 In SESOIL, the ultimate fate and distribution of the pollutant are controlled by the processes  
4 interrelated by the mass balance equation (Equation 6). The processes are selectively employed  
5 and combined by the pollutant fate cycle based on the chemical properties and the simulation  
6 scenario specified by the user. The actual quantity or mass of pollutant taking part in any one  
7 process depends on the competition among all the processes for available pollutant mass.  
8 Pollutant availability for participation in these processes and pollutant rate of migration to the  
9 groundwater depend on its partitioning in the soil between the gas (soil air), dissolved (soil  
10 moisture), and solid (adsorbed to soil) phases.

### 11 *Pollutant Cycle Foundation*

12 In SESOIL, any layer or sub-layer can receive pollutant, store it, and export it to other  
13 subcompartments. Downward movement of pollutant occurs only with the soil moisture, while  
14 upward movement can occur only by vapor phase diffusion. Like the hydrologic cycle, the  
15 pollutant fate cycle is based on a mass balance equation that tracks the pollutant as it moves in  
16 the soil moisture between subcompartments. Upon reaching and entering a layer or sub-layer,  
17 the model assumes instantaneous uniform distribution of the pollutant throughout that layer or  
18 sub-layer. The mass balance equation (Equation 6) is:

$$19 \quad O(t-1) + I(t) = T(t) + R(t) + M(t) \quad \text{Eq 6}$$

20 where

- 21  $O(t-1)$  = the amount of pollutant originally in the soil compartment at time t-1 (flg/cm<sup>2</sup>)  
22  $I(t)$  = the amount of pollutant entering the soil compartment during a time step (flg/cm<sup>2</sup>)  
23  $T(t)$  = the amount of pollutant transformed within the soil compartment during the time  
24 step (flg/cm<sup>2</sup>)  
25  $R(t)$  = the amount of pollutant remaining in the soil compartment at time t (flg/cm<sup>2</sup>)  
26  $M(t)$  = the amount of pollutant migrating out of the soil compartment during the time step  
27 (flg/cm<sup>2</sup>).

28 The fate of the pollutant in the soil column includes both transport and transformation processes,  
29 which depend on the chemical's partitioning among the three phases: soil air, soil moisture, and  
30 soil solids. The three phases are assumed to be in equilibrium with each other at all times, and  
31 the partitioning is a function of chemical-specific partition coefficients and rate constants  
32 supplied by the user.

33 Once the concentration in one phase is known, the concentrations in the other phases can be  
34 calculated. The pollutant cycle of SESOIL is based on the chemical concentration in the soil  
35 water. That is, all processes are written in terms of the pollutant concentration in soil water, and  
36 the model iterates on the soil moisture concentration until the system defined by Equation 6  
37 balances.

1 The concentration in the soil air is calculated via the modified Henry's law constant (see  
2 Equation 7):

$$3 \quad c_{sa} = \frac{c * H}{R * (T + 273)} \quad \text{Eq 7}$$

4 where

5  $c_{sa}$  = pollutant concentration in soil air ( $\mu\text{g/mL}$ )  
6  $c$  = pollutant concentration in soil water ( $\mu\text{g/mL}$ )  
7  $H$  = Henry's law constant ( $\text{m}^3\text{atm/mol}$ )  
8  $R$  = gas constant [ $8.2 * 10^{-5} \text{m}^3\text{atm}/(\text{mol } ^\circ\text{K})$ ]  
9  $T$  = soil temperature ( $^\circ\text{C}$ ).

10 The concentration adsorbed to the soil is calculated using the Freundlich isotherm (note that a  
11 cation exchange option, discussed later, is available in SESOIL) (see Equation 8):

$$12 \quad s = K_d c^n \quad \text{Eq 8}$$

13 where

14  $S$  = pollutant-adsorbed concentration ( $\mu\text{g/g soil}$ )  
15  $K_d$  = pollutant-partitioning coefficient ( $\mu\text{g/g soil}/(\mu\text{g/mL})$ )  
16  $c$  = pollutant concentration in soil water ( $\mu\text{g/mL}$ )  
17  $n$  = Freundlich constant.

18 The total concentration of the pollutant in the soil is computed as shown in Equation 9:

$$19 \quad c_o = f_a * c_{sa} * \theta + \rho_b n \quad \text{Eq 9}$$

20 where

21  $c_o$  = overall (total) pollutant concentration ( $\mu\text{g/cm}^3$ )  
22  $f_a$  =  $n - \theta$  = the air-filled porosity ( $\text{mL/mL}$ )  
23  $n$  = soil (total) porosity ( $\text{mL/mL}$ )  
24  $\theta$  = soil moisture (water) content ( $\text{mL/mL}$ )  
25  $\rho_b$  = soil bulk density ( $\text{g/cm}^3$ ).

26 In SESOIL, each soil layer or sub-layer has a set volume, and the total soil column is treated as a  
27 series of interconnected layers. Each layer or sub-layer has its own mass balance equation  
28 (Equation 6) and can receive and release pollutant to and from adjacent layers or sub-layers. The  
29 individual fate processes that compose the SESOIL mass balance equations (e.g., volatilization,  
30 degradation) are functions of the pollutant concentration in the soil water of each zone and a  
31 variety of first-order rate constants, partitioning coefficients, and other constants.

32 The pollutant cycle equations are formulated on a monthly basis and results are given for each  
33 month simulated. However, to account for the dynamic processes in the model more accurately,

1 an explicit time step of 1 day is used in the equations. The monthly output represents the  
2 summation of results from each day.

3 In the event that the dissolved concentration exceeds the aqueous solubility of the pollutant, the  
4 dissolved concentration is assumed to equal the aqueous solubility. That is, if during solution of  
5 the mass balance equation for any one layer, the dissolved concentration exceeds the solubility of  
6 the chemical, the iteration is stopped for that time step, and the solubility is used as the dissolved  
7 concentration. The adsorbed and soil air concentrations are calculated using the chemical  
8 partitioning equations as before (Equations 7 and 8).

9 To maintain the mass balance, the remaining pollutant is assumed to remain in a pure phase  
10 (undissolved). Transport of the pure phase is not considered, but the mass of the chemical in the  
11 pure phase is used as input to that same layer in the next time step. Simulation continues until  
12 the pure phase eventually disappears.

### 13 *Pollutant Depth Algorithm*

14 This section introduces the user to the major algorithms and processes simulated in the pollutant  
15 cycle of SESOIL, which is based on the pollutant concentration in soil moisture. In theory, a  
16 nonreactive dissolved pollutant originating in any unsaturated soil layer will travel to another soil  
17 layer or to the groundwater at the same speed as the moisture mass originating in the same soil  
18 layer. The movement of a reactive pollutant, however, will be retarded in relation to the  
19 movement of the bulk moisture mass because of vapor phase partitioning and the adsorption of  
20 the pollutant onto the soil particles. If it is assumed that no adsorption occurs, and that the vapor  
21 phase is negligible, the pollutant will move at the same rate as water through the soil.

22 Originally, only the advective velocity was used in SESOIL to determine the depth the pollutant  
23 reached during a time step. The depth (D) was calculated as shown in Equation 10:

$$24 \quad D = \frac{J_w t_c}{\theta} \quad \text{Eq 10}$$

25 where

26  $J_w$  = water velocity (cm/s)  
27  $t_c$  = advection time (s)  
28  $\theta$  = soil water content (cm<sup>3</sup>/cm<sup>3</sup>).

29 Using this approach, all chemicals reach the groundwater at the same time, irrespective of their  
30 chemical sorption characteristics. To account for retardation, SESOIL uses Equation 11 to  
31 calculate the depth reached by a chemical with a linear equilibrium partitioning between its  
32 vapor, liquid, and adsorbed phases (Jury et al, 1984, "Behavior Assessment Model for Trace  
33 Organics in Soil: II. Chemical Classification and Parameter Sensitivity"):

$$34 \quad D = \frac{J_w t_c}{\theta + \rho_b * K_d + \frac{f_a H}{R(T + 273)}} \quad \text{Eq 11}$$

1 All terms previously were defined.

2 SESOIL calculates the flux  $J_w$  (see below) for each layer using the infiltration rate and  
 3 groundwater runoff (recharge) rate computed by the hydrologic cycle, and the depths and  
 4 permeabilities input by the user. It must be noted that a different permeability can be input for  
 5 each of the four major soil layers. While the hydrologic cycle will use the weighted mean  
 6 average of layer permeabilities according to Equation 3, the pollutant cycle does take into  
 7 account the separate permeability for each layer in computing  $J_w$  at the layer boundaries  
 8 according to Equation 12:

$$9 \quad J_{w,z} = \left[ G + (I - G) \left( \frac{d_j}{d} \right) \right] \left( \frac{k_i}{K_z} \right) \quad \text{Eq 12}$$

10 where

- 11  $J_{w,z}$  = infiltration rate at depth z, which will be the boundary between two major layers  
 12 (cm/s)  
 13  $G$  = groundwater runoff (recharge) (cm/s)  
 14  $I$  = infiltration at surface (cm/s)  
 15  $d_j$  = depth of soil column below depth z (cm)  
 16  $d$  = depth of soil column from surface to groundwater table (cm)  
 17  $K_z$  = intrinsic permeability defined by Equation 3 (cm<sup>2</sup>)  
 18  $k_i$  = vertically averaged permeability for layer i (cm<sup>2</sup>); computed using Equation 3,  
 19 except d in the numerator of Equation 3 is the sum of the layer depths above  
 20 depth z and the summation in the denominator is from layer 1 to layer i.

21 The user is allowed three options for pollutant loading: (1) a spill loading, where all of the  
 22 pollutant is entered at the soil surface in the first time step of the month the loading occurs; or  
 23 (2) a steady application, where the pollutant load is distributed evenly for each time step during  
 24 the month the loading is specified; or (3) initial concentrations for any sub-layer can be input.  
 25 However, Option (3) allows the user to input initial concentrations into any sub-layer, allowing a  
 26 specific initial concentration distribution for the entire soil column. Option (3) was used for  
 27 assessing the 200-CS-1 OU waste sites.

28 Equation 11 is used to compute the depth of the pollutant front from that point. If initial  
 29 concentrations are input, the depth of the front begins at the middle of the lowest layer that has a  
 30 concentration. Subsequently, the pollutant is not allowed to enter a layer or sub-layer until the  
 31 depth of the pollutant front has reached the top of that layer or sub-layer. When the pollutant  
 32 depth reaches the groundwater table, the pollutant leaves the unsaturated zone by simply  
 33 multiplying the groundwater runoff (recharge) rate by the concentration in the soil moisture.

#### 34 *Volatilization/Diffusion*

35 In SESOIL, volatilization/diffusion includes movement of the pollutant from the soil surface to  
 36 the atmosphere and from lower soil layers to upper ones. The vapor phase diffusion in SESOIL  
 37 operates in the upward direction only. The rate of diffusion for a chemical is determined by the  
 38 properties of the chemical, the soil properties, and environmental conditions. The

1 volatilization/diffusion model in SESOIL is based on the model of Farmer et al. 1980,  
 2 "Hexachlorobenzene: Its Vapor Pressure and Vapor Phase Diffusion," and is a discretized  
 3 version of Fick's first law over space, assuming vapor phase diffusion as the rate-controlling  
 4 process. That is, the same equation is used for volatilization to the atmosphere as is used for  
 5 diffusion from lower layers to upper ones. The vapor phase diffusion flux through the soil  $J_s$ ,  
 6 ( $\mu\text{g}/\text{cm}^2\text{s}$ ) is described as shown in Equation 13:

$$7 \quad J_a = -D_a \left( \frac{f_a^{10}}{f^2} \right) \frac{dc_{sa}}{dz} \quad \text{Eq 13}$$

8 where

9  $D_a$  = the vapor diffusion coefficient of the compound in air ( $\text{cm}^2/\text{s}$ )  
 10  $c^{sa}$  = comes from Equation 7 and  $f_a$  and  $f$  are as defined previously.

11 The pollutant can volatilize directly to the atmosphere from the surface layer, but if the chemical  
 12 is in the second or lower layer, and the concentration in that layer is greater than the layer above  
 13 it, then the chemical will diffuse into the upper layer rather than volatilize directly into the  
 14 atmosphere.

#### 15 *Sorption: Adsorption/Desorption and Cation Exchange*

16 SESOIL includes two partitioning processes for movement of pollutant from soil moisture or soil  
 17 air to soil solids: (1) the sorption process, and (2) the cation-exchange mechanism. The  
 18 cation-exchange process was not used to evaluate the 200-CS-1 OU waste sites and information  
 19 relative to that process contained in the author's publication (Bonazountas et al. 1997, *SESOIL in*  
 20 *Environmental Fate and Risk Modeling*) is omitted from this presentation. Simulation of  
 21 adsorption for metal contaminants of potential concern (e.g., silver) used distribution  
 22 coefficients.

23 The sorption process may be defined as the adhesion of pollutant molecules or ions to the surface  
 24 of soil solids. Most sorption processes are reversible; adsorption describing the movement of  
 25 pollutant onto soil solids, and desorption being the partitioning of the chemical from solid into  
 26 the liquid or gas phase (Lyman et al. 1982, *Handbook of Chemical Property Estimation*  
 27 *Methods*). Adsorption and desorption are usually assumed to be occurring in equilibrium and are  
 28 therefore modeled as a single process. Adsorption is assumed to occur rapidly relative to the  
 29 migration of the pollutant in soil moisture; and it can drastically retard pollutant migration  
 30 through the soil column.

31 SESOIL employs the general Freundlich equation (Equation 8) to model soil sorption processes.  
 32 The equation correlates adsorbed concentration with the dissolved concentration of the pollutant  
 33 by means of an adsorption coefficient and the Freundlich parameter. This equation has been  
 34 found to most nearly approximate the adsorption of many pollutants, especially organic  
 35 chemicals, and a large amount of data has been generated and is available in the literature.

1 For most organic chemicals, adsorption occurs mainly on the organic carbon particles within the  
 2 soil (Lyman et al. 1982). The organic carbon partition coefficient (K) for organic chemicals can  
 3 be measured or estimated. The soil organic carbon-water partition coefficient ( $K_{oc}$ ) is converted  
 4 to the partition coefficient ( $K_d$ ) by multiplying by the fraction of organic carbon in the soil.

5 Values for the Freundlich exponent can be found in the literature. They generally range between  
 6 0.7 and 1.1, although values can be found as low as 0.3 and as high as 1.7. In the absence of  
 7 data, a value of 1.0 is recommended, because no estimation techniques for this parameter have  
 8 yet been developed. Note that using 1.0 for the Freundlich exponent assumes a linear model for  
 9 sorption (Equation 8).

#### 10 *Degradation: Biodegradation and Hydrolysis*

11 The pollutant cycle of SESOIL contains two transformation routines that can be used to estimate  
 12 pollutant degradation in the soil. Biodegradation is the biological breakdown of organic  
 13 chemicals, most often by microorganisms. Hydrolysis is the chemical reaction of the pollutant  
 14 with water. Both processes result in the loss of the original pollutant and the creation of new  
 15 chemicals. The SESOIL model accounts for the mass of original pollutant lost through  
 16 degradation, but does not keep track of any degradation products. The user is responsible for  
 17 knowing what the degradation products will be and their potential significance.

18 The biodegradation process usually is a significant loss mechanism in soil systems, because soil  
 19 environments have a diverse microbial population and a large variety of food sources and  
 20 habitats (Hamaker 1972, "Decomposition: Quantitative Aspects"). Many environmental factors  
 21 affect the rate of biodegradation in soil, including pH, moisture content of the soil, temperature,  
 22 redox potential, availability of nutrients, oxygen content of the soil air, concentration of the  
 23 chemical, presence of appropriate microorganisms, and presence of other compounds that may  
 24 be preferred substrates. However, SESOIL does not consider these factors.

25 Biodegradation in SESOIL is handled as primary degradation, defined as any structural  
 26 transformation in the parent compound that results in a change in the chemical's identity.  
 27 Biodegradation is estimated using the chemical's rate of decay in both the dissolved and  
 28 adsorbed phases according to the first-order rate equation (Equation 14):

$$29 \quad P_d = (C * \theta * K_{d1} + s * \rho_b * k_{ds}) * A * d_s * \Delta t \quad \text{Eq 14}$$

30 where

- 31  $P_d$  = decayed pollutant mass during time step  $\Delta t$   
 32  $k_{d1}$  = biodegradation rate of the compound in the liquid phase (per day)  
 33  $k_{ds}$  = biodegradation rate of the compound in the solid phase (per day)  
 34  $A$  = area of pollutant application ( $\text{cm}^2$ )  
 35  $d_s$  = depth of the soil sub-layer (cm)  
 36  $\Delta t$  = time step (day).

37  $C$ ,  $\theta$ ,  $s$ , and  $\rho_b$  are as defined for Equations 8 and 9.

38 The parameters  $C$ ,  $\theta$ ,  $s$  are functions of time in the SESOIL model.

1 The use of a first-order rate equation is typical for fate and transport models and generally is an  
2 adequate representation of biodegradation for many chemicals. However, because of the many  
3 factors affecting biodegradation, in some cases, a first-order rate may not be applicable to the site  
4 field conditions; a zero-order or a second- or higher-order rate might be more appropriate. The  
5 biodegradation algorithm in SESOIL described by Equation 14 cannot handle these cases.

6 The SESOIL hydrolysis algorithm allows the simulation of neutral, acid-, or base-catalyzed  
7 reactions and assumes that both dissolved and adsorbed pollutant are susceptible to hydrolysis  
8 (Lyman et al. 1982). Hydrolysis was not simulated in evaluation of the 200-CS-1 OU waste sites  
9 and it will not be discussed in this section.

#### 10 *Pollutant Cycle Evaluation*

11 Several approaches, such as verification, calibration, sensitivity analysis, uncertainty analysis,  
12 and validation, are used to evaluate the reliability and usefulness of an environmental model.

13 Verification establishes that results from each of the algorithms of the model are correct.  
14 Calibration is the process of adjusting selected model parameters within an accepted range until  
15 the differences between model predictions and field observations are within selected criteria of  
16 performance (Donnigan and Dean 1985, *Environmental Exposures from Chemicals*). Sensitivity  
17 analysis focuses on the relative impact that each parameter or term has on the model output, in  
18 order to determine the effect of data quality on output reliability. Uncertainty analysis seeks to  
19 quantify the uncertainty in the model output as a function of uncertainty in both model input and  
20 model operations. Validation also compares measured with predicted results, but includes  
21 analysis of the theoretical foundations of the model, focusing on the model's performance in  
22 simulating actual behavior of the chemical in the environment under study. Validation often has  
23 been broadly used to mean a variety of things, including all five of the techniques reported  
24 earlier.

25 A number of calibration, validation, and sensitivity studies have been performed on SESOIL.  
26 Extensive testing using extreme ranges of input data have verified the model. Studies of the  
27 hydrologic cycle were discussed above. The following discusses the kinds of evaluations that  
28 have been performed on the pollutant cycle of the SESOIL model. Note that model validation is  
29 a continuing process; no model is ever completely validated.

30 To assess SESOIL's predictive capabilities for pollutant movement, a pollutant transport and  
31 validation study was performed by Arthur D. Little, Inc., under contract to the EPA  
32 (Bonazountas et al. 1982, *Evaluation of Seasonal Soil Groundwater Pollutant Pathways*). The  
33 application/validation study was conducted on two field sites, one in Kansas and one in Montana.  
34 SESOIL results were compared to data for the metals chromium, copper, nickel, and sodium at  
35 the Kansas site, and to the organics naphthalene and anthracene at the Montana site. Results  
36 showed reasonable agreement between predictions and measurements, although the  
37 concentrations of the metals were consistently underestimated, and the rate of metal movement at  
38 the Kansas site was consistently overestimated; and at the Montana site, the concentrations of the  
39 organics were overestimated by SESOIL. Bonazountas et al. (1982) state that the  
40 overestimations for the organics probably occurred because biodegradation was not considered  
41 in the simulations. NOTE: This study was undertaken with the original SESOIL model, not the  
42 modified model described herein.

1 Hetrick et al. (1989) compared predictions of the improved version of SESOIL with empirical  
2 data from a laboratory study involving six organic chemicals (Melancon et al. 1986, "Evaluation  
3 of SESOIL, PRZM, and PESTAN in a Laboratory Column Leaching Experiment"); from three  
4 different field studies involving the application of aldicarb to two field plots (Hornsby et  
5 al. 1983, "Fate of Aldicarb in Florida Citrus Soils: Field and Laboratory Studies"; Jones 1983,  
6 "Fate of Aldicarb in Florida Citrus Soil: 2. Model Evaluation"; Jones 1985, "Field, Laboratory,  
7 and Modeling Studies on the Degradation and Transport of Aldicarb Residues in Soil and  
8 Groundwater"); and atrazine to a single-field watershed (EPA/600/3-78/056, *Transport of*  
9 *Agricultural Chemicals from Small Upland Piedmont Watersheds*). Results for several measures  
10 of pollutant transport were compared, including the location of chemical peak versus time, the  
11 time-dependent amount of pollutant leached to groundwater, the depth distribution of the  
12 pollutant at various times, the mass of the chemical degraded, and the amount of pollutant in  
13 surface runoff. This study showed that SESOIL predictions were in good agreement with  
14 observed data for both the laboratory study and the field studies.

15 SESOIL does a good job in predicting the leading edge of the chemical profile (Hetrick et  
16 al. 1989), due mainly to the improvement of the pollutant depth algorithm to include the  
17 chemical sorption characteristics (see the pollutant depth algorithm section). In addition, when a  
18 split-sample calibration/validation procedure was used on 3 years of data from the single-field  
19 watershed, SESOIL did a good job of predicting the amount of chemical in the runoff. The  
20 model was less effective in predicting actual concentration profiles; the simulated concentrations  
21 near the soil surface underestimated the measurements in most cases. One explanation is that  
22 SESOIL does not consider the potential upward movement of the chemical with the upward  
23 movement of water due to soil evaporation losses.

24 SESOIL is a very useful screening-level chemical migration and fate model. The model is  
25 relatively easy to use, the input data are straightforward to compile, and most of the model  
26 parameters can be readily estimated or obtained. Sensitivity analysis studies with SESOIL can  
27 be done efficiently.

28 SESOIL can be applied to generic environmental scenarios to evaluate the general behavior of  
29 chemicals. Care should be taken when applying SESOIL to sites with large vertical variations in  
30 soil properties, because the hydrologic cycle assumes a homogeneous soil profile. Only one  
31 value for the soil moisture content is computed for the entire soil column. If different  
32 permeabilities are input for each soil layer, the soil moisture content calculated in the hydrologic  
33 cycle using the vertically averaged permeability (Equation 3) may not be valid for the entire soil  
34 column. Thus, the user is warned that even though the model can accept different permeabilities  
35 for each layer, it does not fully account for the effects of variable permeability.

### 36 F3.0 SESOIL MODEL INPUT PARAMETERS

37 Section F2.0 provides a detailed explanation of the SESOIL model, and Sections F2.7.5 and  
38 F2.8.5 discuss the applications of the SESOIL model for evaluating the impacts from vadose  
39 zone soil contamination on underlying groundwater. This section presents the input parameters  
40 used in the SESOIL model and the long-term average results of the hydrologic cycle obtained by

1 the model from Equations 1 and 2. Site-specific soil column and chemical-specific parameters  
 2 are discussed in Sections F2.7.5 and F2.8.5. Model input parameters and hydrologic cycle  
 3 results are found in Tables F-2 through F-6.

#### 4 F4.0 REFERENCES

- 5 Bonazountas, M., and J. Wagner, 1981, *SESOIL: A Seasonal Compartment Model*,  
 6 Publication PB86-112406, Arthur D. Little, Inc., Cambridge, Massachusetts, prepared for  
 7 the U.S. Environmental Protection Agency, Office of Toxic Substances, National  
 8 Technical Information Service, Springfield, Virginia.
- 9 Bonazountas, M., and J. Wagner, 1984, "Modeling Mobilization and Fate of Leachate Below  
 10 Uncontrolled Hazardous Waste Sites," *Proceedings of the 5th National Conference on*  
 11 *Management of Uncontrolled Hazardous Waste Sites*, Hazardous Materials Control  
 12 Research Institute, Washington, D.C.
- 13 Bonazountas, M., D. M. Hetrick, P. T. Kostecki, and E. J. Calabrese, 1997, *SESOIL in*  
 14 *Environmental Fate and Risk Modeling*, Amherst Scientific Publishers, Amherst,  
 15 Massachusetts.
- 16 Bonazountas, M., J. Wagner, and B. Goodwin, 1982, *Evaluation of Seasonal Soil Groundwater*  
 17 *Pollutant Pathways*, EPA Contract No. 68-01-5949(9), Arthur D. Little, Inc., Cambridge,  
 18 Massachusetts.
- 19 Brooks, R. H., and A. T. Corey, 1966, "Properties of Porous Media Affecting Fluid Flow,"  
 20 *Proceedings, American Society of Civil Engineers, Journal of the Irrigation and*  
 21 *Drainage Division*, No. IR 2, Paper 4855.
- 22 *Comprehensive Environmental Response, Compensation, and Liability Act of 1980*,  
 23 42 USC 9601, et seq.
- 24 Donnigan, A. S., and J. D. Dean, 1985, *Environmental Exposures from Chemicals*, Vol. 1, edited  
 25 by W. B. Neely and G. E. Blau, p. 100, CRC Press, Boca Raton, Florida.
- 26 Eagleson, P. S., 1978, "Climate, Soil, and Vegetation," *Water Resources Research* 14(5):  
 27 705-776.
- 28 Eagleson, P. S., and T. E. Tellers, 1982, "Ecological Optimality in Water-Limited Natural  
 29 Soil-Vegetation Systems, 2. Tests and Applications," *Water Resources Research* 18(2):  
 30 341-354.
- 31 Ecology 2003, *Cleanup Levels and Risk Calculations (CLARC) Database*,  
 32 <https://fortress.wa.gov/ecy/clarc/CLARCHome.aspx>


- 1 EPA/600/3-78/056, 1978, *Transport of Agricultural Chemicals from Small Upland Piedmont*  
2 *Watersheds*, U.S. Environmental Protection Agency, Athens, Georgia, and  
3 U.S. Department of Agriculture, Watkinsville, Georgia.
- 4 EPA/800/6-85/002b, 1985, *Water Quality Assessment: A Screening Procedure for Toxic and*  
5 *Conventional Pollutants in Surface and Groundwater – Part II*, Environmental Research  
6 Laboratory, Athens, Georgia.
- 7 Farmer, W. J., M. S. Yang, J. Letey, and W. E. Spencer, 1980, "Hexachlorobenzene: Its Vapor  
8 Pressure and Vapor Phase Diffusion," *Soil. Soil Sci. Soc. Am.* 44, 676-680.
- 9 Freeze, R. A., and J. A. Cherry, 1979, *Groundwater*, Prentice Hall, Englewood Cliffs,  
10 New Jersey.
- 11 GSC, 1998, *SESOIL*, General Sciences Corporation, Beltsville, Maryland.
- 12 Hamaker, J. W., 1972, "Decomposition: Quantitative Aspects," *Organic Chemicals in the Soil*  
13 *Environment*, Vol. 1, C. A. I. Goring and J. W. Hamaker, eds, New York,  
14 Marcel Dekker, Inc.
- 15 Hetrick, D. M., 1984, "Simulation of the Hydrologic Cycle for Watersheds," *Ninth International*  
16 *Conference, Energy, Power, and Environmental Systems*, San Francisco, California.
- 17 Hetrick, D. M., and C. C. Travis, 1988, "Model Predictions of Watershed Erosion Components,"  
18 *Water Resources Bull.*, 24(2):413-419.
- 19 Hetrick, D. M., C. C. Travis, P. S. Shirley, and E. L. Etnier, 1986, "Model Predictions of  
20 Watershed Hydrologic Components: Comparison and Verification," *Water Resources*  
21 *Bull.*, 22(5):803-810.
- 22 Hornsby, A. G., P. S. C. Rao, W. B. Wheeler, P. Nkedi-Kizza, and R. L. Jones, 1983, "Fate of  
23 Aldicarb in Florida Citrus Soils: Field and Laboratory Studies," *Proceedings of the*  
24 *National Water Well Association, U.S. Environmental Protection Agency Conference on*  
25 *Characterization and Monitoring of the Vadose (Unsaturated) Zone*, 936-958,  
26 D. M. Nielsen and M. Curti, eds., Las Vegas, Nevada.
- 27 Jones, R. L., 1985, "Field, Laboratory, and Modeling Studies on the Degradation and Transport  
28 of Aldicarb Residues in Soil and Groundwater," *ACS Symposium on Evaluation of*  
29 *Pesticides in Groundwater*, Miami Beach, Florida.
- 30 Jones, R. L., P. S. C. Rao, and A. G. Hornsby, 1983, "Fate of Aldicarb in Florida Citrus  
31 Soil: 2. Model Evaluation," *Proceedings of the National Water Well Association,*  
32 *U.S. Environmental Protection Agency Conference on Characterization and Monitoring*  
33 *of the Vadose (Unsaturated) Zone*, 959-978, D. M. Nielsen and M. Curti, eds.,  
34 Las Vegas, Nevada.

- 1 Jury, W. A., W. Farmer, and W. F. Spencer, 1984, "Behavior Assessment Model for Trace  
2 Organics in Soil: II. Chemical Classification and Parameter Sensitivity," *J. Environ.*  
3 *Qual.* 13(4): 567-572.
- 4 Lyman, W. J., W. E Reehl, and D. H. Rosenblatt, 1982, *Handbook of Chemical Property*  
5 *Estimation Methods*, McGraw-Hill Book Company, New York.
- 6 Melancon, S. M., J. E. Pollard, and S. C. Hern, 1986, "Evaluation of SESOIL, PRZM, and  
7 PESTAN in a Laboratory Column Leaching Experiment," *Environ. Toxicol. Chem.*,  
8 5:865-878.
- 9 Metzger, B. H., and P. S. Eagleson, 1980, "The Effects of Annual Storage and Random Potential  
10 Evapotranspiration on the One-Dimensional Annual Water Balance," MIT Report  
11 No. 251, Massachusetts Institute of Technology, Cambridge, Massachusetts.
- 12 ORNL/TM-7856, 1982, *AGTEHM: Documentation of Modifications to the Terrestrial*  
13 *Ecosystem Hydrology Model (TEHM) for Agricultural Applications*, Oak Ridge National  
14 Laboratory, Oak Ridge, Tennessee.
- 15 ORNL/TM-10672, 1989, *Qualitative Validation of Pollutant Transport Components of an*  
16 *Unsaturated Soil Zone Model (SESOIL)*, Oak Ridge National Laboratory, Oak Ridge,  
17 Tennessee.
- 18 PNNL-13895, 2003, *Hanford Contaminant Distribution Coefficient Database and Users Guide*,  
19 Rev. 1, Pacific Northwest National Laboratory, Richland, Washington.
- 20 *Resource Conservation and Recovery Act of 1976*, 42 USC 6901, et seq.
- 21 WAC 173-340-702(14), "General Policies," "Burden of Proof," *Washington Administrative*  
22 *Code*, as amended, Washington State Department of Ecology, Olympia, Washington.
- 23 WAC 173-340-702(15), "General Policies," "New Scientific Information," *Washington*  
24 *Administrative Code*, as amended, Washington State Department of Ecology, Olympia,  
25 Washington.
- 26 WAC 173-340-702(16), "General Policies," "Criteria for Quality of Information," *Washington*  
27 *Administrative Code*, as amended, Washington State Department of Ecology, Olympia,  
28 Washington.
- 29 WAC 173-340-747(8), "Deriving Soil Concentrations for Ground Water Protection,"  
30 "Alternative Fate and Transport Models," *Washington Administrative Code*, as amended,  
31 Washington State Department of Ecology, Olympia, Washington.

- 1 Watson, D. B., and S. M. Brown, 1985, *Testing and Evaluation of the SESOIL Model*,
- 2 Anderson-Nichols and Co., Inc., Palo Alto, California.
  
- 3 WSU, 2005, *Soils of Washington*, Washington State Soils Website,
- 4 [http://remotesens.css.wsu.edu/washingtonsoil/Benton\\_soils/Benton\\_default.htm](http://remotesens.css.wsu.edu/washingtonsoil/Benton_soils/Benton_default.htm).

1  
2


Figure F-1. SESOIL General Conceptualization.



3

1  
2


Figure F-2. Schematic of the Monthly Hydrologic Cycle.



3

1  
2  
3

Figure F-3. Illustration of SESOIL Layer and Sub-Layer General Configuration for the 200-CS-1 Operable Unit Waste Sites.



SESOIL = Seasonal Soil Compartment Model  
COPC = Chemical of Potential Concern  
EPA = Environmental Protection Agency  
OTS = Office of Toxic Substances  
ORNL = Oak Ridge National Laboratory  
GSC = General Sciences Corporation

4  
5

Table F-1. Comparison of WAC 173-340-747(8) Requirements and SESOIL as Configured for 200-CS-1 Operable Unit Waste Sites. (2 Pages)

Section of WAC 173-340-747(8) Requirement	SESOIL as Configured for 200-CS-1 Operable Unit Waste Sites
(8)(a) Utilize site-specific data.	Uses local (Pasco National Weather Service Station) climatological data, local soil property data (Burbank soils are common on the Central Plateau), site-specific depths to groundwater (typically 270 ft [94 m] below ground surface), and site-specific soil constituent concentrations.
8(b) Chemical partitioning and advective flow and other processes may be used to predict fate and transport.	SESOIL simulates one-dimensional (vertical) advective flow and chemical partitioning. With one exception, advective flow and partitioning were the sole processes used by SESOIL to predict fate and transport. SESOIL can simulate other processes (e.g., volatilization and degradation), and benzene biodegradation at the 216-B-65 Trench was investigated to clarify uncertainties.
8(b)(i) Sorption values must be derived in accordance with §(4)(c) or §(5)(b). §(4)(c) specifies the use of default $K_d$ values; §(5)(b) addresses requirements for petroleum fractions and it is not applicable.	Sorption (partitioning) was simulated with default $K_d$ s obtained from the Washington State Department of Ecology (Ecology 2003). Default $K_d$ s were not available for nitrate, nitrite, and sulfate. For these constituents, a $K_d$ for nitrate, developed using site-specific data published by PNNL-13895 was used.  NOTE: SESOIL also uses aqueous solubility in its algorithms to ensure that partitioning does not result in concentrations exceeding solubility limits. Aqueous solubilities were obtained from reliable public domain sources and are documented in the report.
8(b)(ii) Sets forth requirements for assessing vapor phase partitioning; they are not applicable.	Vapor phase partitioning, as discussed in WAC 173-340-747(8)(b)(ii), was not simulated.
8(b)(iii) States that rates of natural degradation must be derived from site-specific measurements.	Natural degradation was not simulated, with the exception of benzene biodegradation, at the 216-B-65 Trench. In the case of benzene, a conservative degradation constant, obtained from a reliable public domain source, was used to help investigate the potential for benzene degradation. Documentation is provided in the report.
8(b)(iv) Requires that estimates of dispersion be derived from site-specific measurements or literature values.	SESOIL is a one-dimensional (vertical) compartment model that does not simulate dispersion as discussed in §8(b)(iv).
8(b)(v) Permits the use of algorithms that account for decay over time.	Decay, as discussed in §8(b)(v), was not simulated.
8(b)(vi) States that dilution should be estimated from site-specific measurements or estimated using site-specific characteristics.	Dilution is estimated using site-specific characteristics by virtue of the use of the Burbank soil and typical groundwater characteristics. Dilution is computed in the soil column through sequential mass balance algorithms. Constituent mass entering a compartment is mixed with the existing mass in the compartment. Dilution is computed in the groundwater by means of a simple mixing equation that uses typical site-specific gradient and hydraulic conductivity data.

Table F-1. Comparison of WAC 173-340-747(8) Requirements and SESOIL as Configured for 200-CS-1 Operable Unit Waste Sites. (2 Pages)

Section of WAC 173-340-747(8) Requirement	SESOIL as Configured for 200-CS-1 Operable Unit Waste Sites
<p>8(b)(vii) states that infiltration must be derived in accordance with §(5)(f)(ii)(A) or §(5)(f)(ii)(B). §(5)(f)(ii)(A) specifies a geographic locale consideration when using a default infiltration rate; this requirement is not applicable. §(5)(f)(ii)(B) requires that when a site-specific infiltration measurement or estimate is used, no cap or similar impeding structure can be assumed.</p>	<p>No cap or infiltration impeding structure was assumed.</p>
<p>8(c) Sets forth department evaluation criteria based on WAC 173-340-702(14), (15), and (16). WAC 173-340-702(14) places the burden of proof that <i>Washington Administrative Code</i> protectiveness requirements have been met on the respondent when deviations from default values are used. WAC 173-340-702(15) establishes a process for the department to consider new scientific information; this section is not applicable. WAC 173-340-702(16) establishes department "quality of information criteria," including considerations such as acceptance in the scientific community, relevance, rationale, and propensity to err on the side of safety.</p>	<p>The SESOIL model meets all requirements specified in WAC 173-340-747(8), which stresses the use of site-specific data. SESOIL was developed under U.S. Environmental Protection Agency direction and is widely accepted in the regulatory community. The use of SESOIL to clarify uncertainties in potential impacts to groundwater at the 200-CS-1 OU waste sites is consistent with the developer's intent. Significant errors on the side of safety, including conscious and considerable overestimation of the source mass in the vadose zone, ensure that the results will be conservative and protective.</p>

Ecology 2003, *Cleanup Levels and Risk Calculations (CLARC) Database*, <https://fortress.wa.gov/ecy/clarc/CLARCHome.aspx>.  
 PNNL-13895, *Hanford Contaminant Distribution Coefficient Database and Users Guide*.  
 WAC 173-340-702(14), "General Policies," "Burden of Proof."  
 WAC 173-340-702(15), "General Policies," "New Scientific Information."  
 WAC 173-340-702(16), "General Policies," "Criteria for Quality of Information."  
 WAC 173-340-747(8), "Deriving Soil Concentrations for Ground Water Protection," "Alternative Fate and Transport Models."

$K_d$  = chemical-specific distribution coefficient.  
 OU = operable unit.  
 SESOIL = Seasonal Soil Compartment Model.  
 WAC = *Washington Administrative Code*.

Table F-2. SESOIL Statistical Climate Parameters from Pasco, Washington, National Weather Service Station.

Month	Air Temp °C	Cloud Cover (Fraction)	Relative Humidity	Albedo	Precipitation (cm)	No. of Storms	Duration (days)
Oct.	10.94	0.6	0.65	0.16	1.48	1.77	0.234583
Nov.	4.22	0.8	0.8	0.23	2.22	2.91	0.3275
Dec.	0.39	0.8	0.8	0.36	2.93	3.39	0.355833
Jan.	-1.61	0.8	0.8	0.4	2.81	3.47	0.422917
Feb.	2.56	0.8	0.8	0.26	1.75	2.44	0.340833
Mar.	6.06	0.7	0.6	0.21	1.4	2.11	0.307083
Apr.	10.44	0.65	0.55	0.16	0.97	1.27	0.224583
May	15	0.6	0.5	0.15	1.48	1.69	0.332917
Jun.	18.72	0.6	0.5	0.15	1.29	1.74	0.239583
Jul.	22.61	0.3	0.4	0.15	0.41	0.49	0.111667
Aug.	21.61	0.4	0.4	0.16	0.82	0.92	0.185833
Sep.	17.5	0.4	0.5	0.23	0.86	1	0.175833

SESOIL = Seasonal Soil Compartment Model.

1

Table F-3. SESOIL Soil Parameters.

Variable	Parameter	Remark
Soil series	Burbank	The Burbank series consists of very deep, excessively drained, very slow to medium runoff; rapid permeability soils formed in basaltic glacial outwash or alluvium (WSU 2005). Burbank soils are commonly found in the 200-CS-1 Operable Unit sites.
Bulk density	1.569 g/cm <sup>3</sup>	Burbank series (GSC 1998).
Intrinsic permeability	1x10 <sup>-6</sup> cm <sup>2</sup>	High end of the range (1 x 10 <sup>-10</sup> to 1 x 10 <sup>-6</sup> cm <sup>2</sup> ) for silty sand soils (EPA 1986) and Freeze and Cherry (1979).
Pore disconnectedness index	3.9	Relates the wetting/drying time-dependant permeability of a soil to its saturated permeability (GSC 1998). See Equation 5 in this appendix. Values suggested in GSC (1998) include silt loam, 5.5; sandy loam, 6; sandy clay loam, 4; and sand, 3.7.
Effective porosity	0.28	Burbank series (GSC 1998).
Organic carbon content	0.1%	Default value (Ecology 2003).
Freundlich equation exponent	1.0	Default (GSC 1998). Freundlich equation not used in the assessment.

Ecology 2003, *Cleanup Levels and Risk Calculations (CLARC) Database*,  
<https://fortress.wa.gov/ecy/clarc/CLARCHome.aspx> .

EPA/800/6-85/002b, *Water Quality Assessment: A Screening Procedure for Toxic and Conventional Pollutants in Surface and Groundwater – Part II*.

Freeze, R. A., and J. A. Cherry, 1979, *Groundwater*.

WSU, 2005, *Soils of Washington*.

SESOIL = Seasonal Soil Compartment Model.

2

1

Table F-4. SESOIL Chemical Parameters for Nitrate and Nitrate/Nitrite.

Variable	Parameter	Remark
Solubility	990,000 mg/L	Assume essentially miscible (99% aqueous solubility).
Diffusion coefficient	0.0 cm <sup>2</sup> /s	No diffusion assumed.
Henry's constant	0.0 m <sup>3</sup> -atm/mole	No volatilization assumed.
Adsorption coefficient (K <sub>d</sub> )	1.17	Average of three Hanford Site measurements from gravely sands (82.5% gravel, 15.6% sand, 1.2% silt, 0.7% clay) (PNNL-13895).
Molecular weight	62 g/mole	Nitrate (NO <sub>3</sub> )
Hydrolysis, biodegradation, complexation	Various	These processes not simulated.

NOTE: See tables in individual sections of Chapter 2.0 of the main text for other chemicals.

PNNL-13895, *Hanford Contaminant Distribution Coefficient Database and Users Guide*.

SESOIL = Seasonal Soil Compartment Model.

2

1

Table F-5. SESOIL Summers Groundwater Mixing Model.

Variable	Parameter	Remark
Saturated hydraulic conductivity	0.86 cm/day	Typical of deep groundwater system.
Horizontal gradient	0.02 cm/cm	2% grade typical of deep groundwater system.
Thickness of groundwater mixing zone	500 cm	Nominal 5 m mixing zone is conservative.
Width of contaminated zone	800 cm	Nominal 8 m width perpendicular to groundwater flow generally corresponding to ditch/trench width.
Summers Mixing Model (GSC 1998):		
$C_{gw} = \frac{(Q_p * C_p) - (Q_a * C_a)}{Q_p + Q_a}$		
where		
$C_{gw}$ = groundwater concentration ( $\mu\text{g/mL}$ ).		
$Q_p$ = volumetric flow rate of soil water ( $\text{cm}^3/\text{day}$ ).		
$Q_a$ = volumetric flow rate of groundwater beneath contaminated area ( $\text{cm}^3/\text{day}$ ).		
$C_p$ = contaminant concentration in pore water entering groundwater ( $\mu\text{g/mL}$ ).		
$C_a$ = existing contaminant concentration in pore water in groundwater ( $\mu\text{g/mL}$ ).		

GSC, 1998, *SESOIL*.

SESOIL = Seasonal Soil Compartment Model.

2

1

Table F-6. SESOIL Long-term Average Hydrologic Cycle Components Obtained from Model Results.

Hydrologic Parameter	Result
Average soil moisture Zone 1 (waste layer)	1.337%
Average soil moisture below zone (unsaturated zone)	1.337%
Total precipitation	20.318 cm
Total infiltration	20.318 cm
Total evapotranspiration	3.508 cm
Total surface runoff	0.000 cm
Total groundwater runoff (recharge)	16.810 cm
Total moisture retention	0.000 cm
Total yield	16.810 cm
See Equations 1 and 2 in the text	

SESOIL = Seasonal Soil Compartment Model.

2

1

This page intentionally left blank.

2

3

DISTRIBUTION

1			
2			
3			
4	<u>Onsite</u>		
5	1	<u>U.S. Department of Energy</u>	
6		<u>Richland Operations Office</u>	
7		DOE Public Reading Room	H2-53
8	1	<u>Pacific Northwest National Laboratory</u>	
9		Hanford Technical Library	P8-55
10	1	<u>Lockheed Martin Information Technology</u>	
11		Document Clearance	H6-08

1

**This page intentionally left blank.**

2

**STATE ENVIRONMENTAL POLICY ACT  
ENVIRONMENTAL CHECKLIST**

**FOR THE**

**HANFORD FACILITY,  
216-A-29 DITCH CLOSURE**

**REVISION 0**

**March 2006**

**WASHINGTON ADMINISTRATIVE CODE  
ENVIRONMENTAL CHECKLIST  
[WAC 197-11-960]**

1

**A. BACKGROUND**

2 **1. Name of proposed project, if applicable:**

3 This *State Environmental Policy Act (SEPA) of 1971* Environmental Checklist is being submitted for  
4 closure of the Hanford Facility, 216-A-29 Ditch. This area will be closed with respect to dangerous  
5 waste contamination that resulted from treatment operations as a *Resource Conservation and Recovery*  
6 *Act (RCRA) of 1976* treatment, storage, and/or disposal (TSD) unit.

7

8 **2. Name of applicants:**

9 U.S. Department of Energy, Richland Operations Office (DOE-RL).

10

11 **3. Address and phone number of applicants and contact persons:**

12 U.S. Department of Energy  
13 Richland Operations Office  
14 P.O. Box 550  
15 Richland, Washington 99352

16

17 Contact:

18

19 Keith A. Klein, Manager  
20 Richland Operations Office  
21 (509) 376-7395

22

23 **4. Date checklist prepared:**

24 March 2006.

25

26 **5. Agency requesting the checklist:**

27 Washington State Department of Ecology  
28 P.O. Box 47600  
29 Olympia, Washington 98504-7600

30

31 **6. Proposed timing or schedule: (including phasing, if applicable):**

32 This SEPA Environmental Checklist is being submitted concurrently with a closure plan prepared in  
33 accordance with Washington Administrative Code (WAC) 173-303 Dangerous Waste Regulations. The  
34 closure plan will be submitted to the Washington State Department of Ecology by March 2006.

35

36 **7. Do you have any plans for future additions, expansion, or further activity related to or**  
37 **connected with this proposal? If yes, explain.**

38 No. The 216-A-29 Ditch closure plan is being submitted in conjunction with 216-S-10 Pond and Ditch  
39 closure plan and the 216-B-63 Trench closure plan. The 216-S-10 Pond and Ditch closure plan submittal  
40 is required by March 31, 2006 in accordance with Tri-Party Agreement (Ecology et al) Milestone

1 M-20-39. The 216-A-29 Ditch, 216-B-63 Trench, and the 216-S-10 Pond and Ditch TSD units are all  
2 within the 200-CS-1 source Operable Unit.

3  
4 **8. List any environmental information you know about that has been prepared, or will be**  
5 **prepared, directly related to this proposal.**

6 The original closure plan for the 216-A-29 Ditch was submitted to the State of Washington Department  
7 of Ecology (Ecology) pursuant to Tri-Party Agreement milestone M-20-36 in June 1995. An updated  
8 closure plan is being prepared.

9 This SEPA Environmental Checklist is being submitted to Ecology to address the 216-A-29 Ditch closure  
10 activities. Environmental information that has been prepared directly related to this proposal is contained  
11 in DOE/RL-2004-017, *Remedial Investigation Report for the 200-CS-1 Chemical Sewer Group Operable*  
12 *Unit* and groundwater data contained in the Hanford Environmental Information System (HEIS).  
13 Environmental information that will be prepared directly related to this proposal will be contained in the  
14 document(s) prepared to describe (1) the soil removal necessary to achieve clean closure, and (2) the data  
15 quality objectives and verification sampling implemented following soil removal. Any other information  
16 related to the 216-A-29 Ditch after closure of the TSD unit will be performed in conjunction with Tri-  
17 Party Agreement past practice activities for the 200-CS-1 source operable unit and 200-PO-1  
18 groundwater operable unit.

19 General information concerning the Hanford Facility environment can be found in the *Hanford Site*  
20 *National Environmental Policy Act (NEPA) Characterization*, PNL-6415, Revision 17, September 2005.  
21 This document is updated annually by Pacific Northwest National Laboratory (PNNL), and provides  
22 current information concerning climate and meteorology, ecology, history and archeology,  
23 socioeconomic, land use and noise levels, and geology and hydrology. These baseline data for the  
24 Hanford Site and past activities are useful for evaluating proposed activities and their potential  
25 environmental impacts.

26  
27 **9. Do you know whether applications are pending for government approvals of other proposals**  
28 **directly affecting the property covered by your proposal? If yes, explain.**

29 No other applications are pending. However, see response to A8 regarding physical activities necessary  
30 to complete remediation of non-TSD unit constituents.

31  
32 **10. List any government approvals or permits that will be needed for your proposal, if known.**

33 DOE-RL forwards the aforementioned 216-A-29 Ditch closure plan to Ecology for approval.

34  
35 **11. Give brief, complete description of your proposal, including the proposed uses and the size of**  
36 **the project and site. There are several questions later in this checklist that ask you to describe**  
37 **certain aspects of your proposal. You do not need to repeat those answers on this page.**

38 The proposed DOE-RL closure strategy for the 216-A-29 Ditch soils is clean closure following  
39 remediation of the soils and clean closure of the TSD unit pertaining to groundwater following approval  
40 of the closure plan.

41 The PUREX Plant chemical sewer operated between November 1955 and July 1991. At the beginning of  
42 its operation, the 216-A-29 Ditch received discharge from the PUREX Plant cooling water and discharge

1 from the chemical sewer. In early 1980, because of effluent monitoring requirements, the chemical  
2 sewer lines feeding the 216-A-29 Ditch required upgrades to allow for monitoring and diversion  
3 capabilities. A diversion box was upgraded and connected to the 216-A-42 Retention Basin. The basin  
4 received contaminated diversions from the PUREX Plant chemical sewer line, cooling water line, and  
5 steam condensate discharge. During 1990, plans were developed and approved to discontinue discharges  
6 to and close the 216-A-29 Ditch, and in 1991, all discharges were discontinued. Stabilization of the  
7 216-A-29 Ditch was performed in three phases from July to October 1991. The trench can no longer  
8 accept dangerous waste.

9 Current data show that six of eight TSD unit constituents (sodium, potassium, ammonia, fluoride,  
10 cadmium, and hydrazine) either meet the clean closure standard, the constituent is not regulated, or in the  
11 case of hydrazine, other provisions are used to demonstrate clean closure. Nitrate and sulfate are the  
12 TSD unit constituents not meeting the clean closure standard. To meet WAC 173-340-745(5) cleanup  
13 levels, 216-A-29 Ditch soils will require removal. Furthermore, since the 200-CS-1 Operable Unit is  
14 removing 216-A-29 Ditch soils, the closure approach for the soils will be to remove the 216-A-29 Ditch  
15 soils and conduct verification sampling.

16 No other physical activities are required for closure. After closure, appearance of the land will be  
17 consistent with land use determinations of the Hanford Facility.

18  
19 **12. Location of the proposal. Give sufficient information for a person to understand the precise**  
20 **location of your proposed project, including a street address, if any, and section, township,**  
21 **and range, if known. If a proposal would occur over a range of area, provide the range or**  
22 **boundaries of the site(s). Provide a legal description, site plan, vicinity map, and topographic**  
23 **map, if reasonably available. While you should submit any plans required by the agency, you**  
24 **are not required to duplicate maps or detailed plans submitted with any permit applications**  
25 **related to this checklist.**

26 The 216-A-29 Ditch is located to the east of the 200 East Area of the Hanford Facility. The  
27 216-A-29 Ditch received discharge from the PUREX Plant chemical sewer. The ditch was uncovered  
28 and unlined and followed the natural topography. The ditch originated from the southeastern side of the  
29 A Tank Farm (east of the AP Tank Farm) outside the 200 East Area perimeter fence. The ditch was  
30 estimated to be 1,220 m (4,000 ft) long and 1.8 m (6 ft) wide and varied from 0.6 m to 4.6 m (2 to 15 ft).  
31 The head end of the ditch was modified in 1983 to allow the construction of the AP Tank Farm. The end  
32 of the ditch connects to the 216-B-3-3 Ditch and finally to the 216-B-3 Pond.

TO BE COMPLETED BY APPLICANT

EVALUATIONS FOR  
AGENCY USE ONLY

1 **B. ENVIRONMENTAL ELEMENTS**

2 **1. Earth**

- 3 **a. General description of the site (circle one): Flat, rolling, hilly,**  
4 **steep slopes, mountainous, other\_\_\_\_\_.**

5 The southern portion of the 216-A-29 Ditch is flat, however a fair  
6 amount of the ditch is on a steep slope.

- 7  
8 **b. What is the steepest slope on the site (approximate percent**  
9 **slope)?**

10 The approximate slope of the southern portion of the 216-A-29  
11 Ditch is less than 2 percent. For the northern portion, the elevation  
12 change drops from approximately 205 meters down to approximately  
13 180 meters.

- 14  
15 **c. What general types of soils are found on the site? (for example,**  
16 **clay, sandy gravel, peat, muck)? If you know the classification**  
17 **of agricultural soils, specify them and note any prime farmland.**

18 Soil types consist mainly of eolian and fluvial sands and gravel.  
19 More detailed information concerning specific soil classifications  
20 can be found in the *Hanford Site National Environmental Policy Act*  
21 *(NEPA) Characterization*, PNL-6415, Revision 17, September 2005.  
22 Farming is not permitted on the Hanford Facility.

- 23  
24 **d. Are there surface indications or history of unstable soils in the**  
25 **immediate vicinity? If so, describe.**

26 No.

- 27  
28 **e. Describe the purpose, type, and approximate quantities of any**  
29 **filling or grading proposed. Indicate source of fill.**

30 Removed, contaminated soil would be replaced with clean fill from  
31 existing Hanford Site borrow areas. Additional information  
32 regarding Hanford Site borrow material may be found in DOE/EA-  
33 1403, *Use of Existing Borrow Areas, Hanford Site, Richland,*  
34 *Washington.*

- 35  
36 **f. Could erosion occur as a result of clearing, construction, or use?**  
37 **If so, generally describe.**

38 Erosion might only occur during soil removal activities, depending  
39 on the time of the year the activity is performed.

**TO BE COMPLETED BY APPLICANT**

**EVALUATIONS FOR  
AGENCY USE ONLY**

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36  
37  
38  
39

**g. About what percent of the site will be covered with impervious surfaces after project construction (for example, asphalt or buildings)?**

Not applicable. No construction is proposed as part of this project.

**h. Proposed measures to reduce or control erosion, or other impacts to the earth, if any:**

None.

**2. Air**

**a. What types of emissions to the air would result from the proposal (i.e., dust, automobile, odors, industrial wood smoke) during construction and when the project is completed? If any, generally describe and give approximate quantities, if known.**

Routine closure activities would generate dust.

An airborne radiological release could occur as a result of upset conditions. Such a release would not exceed immediately dangerous to life and health concentrations outside the immediate area of the spill/release because of the small quantity of material that is available for release.

**b. Are there any off-site sources of emissions or odors that may affect your proposal? If so, generally describe.**

No.

**c. Proposed measures to reduce or control emissions or other impacts to the air, if any?**

Good engineering practices [e.g., applying the principle of As Low As Reasonably Achievable (ALARA)] would be followed, and actions would comply with onsite procedures designed to protect the environment and personnel safety and health.

**3. Water**

**a. Surface**

**1) Is there any surface water body on or in the immediate vicinity of the site (including year-round and seasonal**

TO BE COMPLETED BY APPLICANT

EVALUATIONS FOR  
AGENCY USE ONLY

1 streams, saltwater, lakes, ponds, wetlands)? If yes, describe  
2 type and provide names. If appropriate, state what stream  
3 or river it flows into.

4 No. The 216-A-29 Ditch are over 7 kilometers from the  
5 Columbia River.

6  
7 **2) Will the project require any work over, in, or adjacent to**  
8 **(within 200 feet) the described waters? If yes, please describe**  
9 **and attach available plans.**

10 The work would not require any activity in or near the described  
11 waters and drainage.

12  
13 **3) Estimate the amount of fill and dredge material that would**  
14 **be placed in or removed from surface water or wetlands and**  
15 **indicate the area of the site that would be affected. Indicate**  
16 **the source of fill material.**

17 There would be no dredging or filling from or to surface water  
18 or wetlands.

19  
20 **4) Will the proposal require surface water withdrawals or**  
21 **diversions? Give general description, purpose, and**  
22 **approximate quantities if known.**

23 No surface water withdrawal or diversion would be required.

24  
25 **5) Does the proposal lie within a 100-year floodplain? If so,**  
26 **note location on the site plan.**

27 The 216-A-29 Ditch are not within the 100-year or 500-year  
28 floodplain [*Hanford Site National Environmental Policy Act*  
29 (*NEPA*) *Characterization*, PNL-6415, Revision 17,  
30 September 2005].

31  
32 **6) Does the proposal involve any discharges of waste materials**  
33 **to surface waters? If so, describe the type of waste and**  
34 **anticipated volume of discharge.**

35 No.

36

**TO BE COMPLETED BY APPLICANT**

**EVALUATIONS FOR  
AGENCY USE ONLY**

1       **b. Ground**

2           1) Will ground water be withdrawn, or will water be  
3           discharged to ground water? Give general description,  
4           purpose, and approximate quantities if known.

5           No.

6  
7           2) Describe waste material that will be discharged into the  
8           ground from septic tanks or other sources, if any (for  
9           example: Domestic sewage; industrial, containing the  
10          following chemicals...; agricultural; etc.). Describe the  
11          general size of the system, the number of such systems, the  
12          number of houses to be served (if applicable), or the number  
13          of animals or humans the system(s) are expected to serve.

14          None.

15  
16       **c. Water Run-off (including storm water)**

17           1) Describe the source of run-off (including storm water) and  
18           method of collection and disposal, if any (include quantities,  
19           if known). Where will this water flow? Will this water flow  
20           into other waters? If so, describe.

21           The Hanford Facility receives only 15.2 to 17.8 centimeters of  
22           annual precipitation. Precipitation runs off the existing  
23           buildings and seeps into the soil on and near the buildings. This  
24           precipitation does not reach the groundwater or surface waters.

25  
26           2) Could waste materials enter ground or surface waters? If  
27           so, generally describe.

28           Engineering controls during closure activities, such as using dry  
29           decontamination methods, visually checking the liners for  
30           breaches before using decontamination solutions (and  
31           minimizing the use of liquid solutions), etc., will prevent  
32           dangerous waste materials from entering ground or surface  
33           waters. All waste materials would be contained.

34  
35       **d. Proposed measures to reduce or control surface, ground, and**  
36       **run-off water impacts, if any:**

37           Measures would include visually checking for breaches or cracks,  
38           and sealing any found (or containing solutions in a catch pan),

**TO BE COMPLETED BY APPLICANT**

**EVALUATIONS FOR  
AGENCY USE ONLY**

1 before using decontamination solutions; and using dry  
2 decontamination methods and minimizing the use of liquids.

3  
4 **4. Plants**

5 **a. Check or circle the types of vegetation found on the site.**

- 6  deciduous tree: alder, maple, aspen, other  
7  evergreen tree: fir, cedar, pine, other  
8  shrubs  
9  grass  
10  pasture  
11  crop or grain  
12  wet soil plants: cattail, buttercup, bulrush, skunk cabbage,  
13 other  
14  water plants: water lily, eelgrass, milfoil, other  
15  other types of vegetation

16  
17 The most common vegetation community in the 200 East Area is  
18 sagebrush/cheatgrass or Sandberg's bluegrass. Native vegetation  
19 resides in the immediate vicinity of the 216-A-29 Ditch.

20  
21 **b. What kind and amount of vegetation will be removed or**  
22 **altered?**

23 Vegetation existing where the soil will be removed will also be  
24 removed during 216-A-29 Ditch closure activities.

25  
26 **c. List threatened or endangered species known to be on or near**  
27 **the site.**

28 No known threatened or endangered species are known to be on or  
29 near the 216-A-29 Ditch. Additional information on species can be  
30 found in *Hanford Site National Environmental Policy Act (NEPA)*  
31 *Characterization*, PNL-6415 (Revision 17, September 2005).

32  
33 **d. Proposed landscaping, use of native plants, or other measures**  
34 **to preserve or enhance vegetation on the site, if any:**

35 None.  
36

TO BE COMPLETED BY APPLICANT

EVALUATIONS FOR  
AGENCY USE ONLY

1 5. Animals

2 a. Indicate (by underlining) any birds and animals which have  
3 been observed on or near the site or are known to be on or  
4 near the site:

5 birds: Raptors (burrowing owls, ferruginous, redtail, and Swainson's  
6 hawks) eagles, songbirds,  
7 animals: deer, elk, coyotes, rabbits, rodents.

8  
9 Additional information on animals can be found in *Hanford Site*  
10 *National Environmental Policy Act (NEPA) Characterization,*  
11 *PNL-6415 (Revision 17, September 2005).*  
12  
13

14 b. List any threatened or endangered species known to be on or  
15 near the site.

16 One federal and state listed threatened or endangered species has  
17 been identified on the 1,517 square kilometer Hanford Site along the  
18 Columbia River (the bald eagle) and three in the Columbia River  
19 (steelhead, spring-run Chinook salmon, and bull trout). In addition,  
20 the state listed white pelican, sandhill crane, and ferruginous hawk  
21 also occur on or migrate through the Hanford Site.  
22

23 c. Is the site part of a migration route? If so, explain.

24 The Hanford Site is a part of the broad Pacific Flyway. However,  
25 the 216-A-29 Ditch location is not known as a haven for migratory  
26 birds.  
27

28 d. Proposed measures to preserve or enhance wildlife, if any:

29 This project contains no specific measures to preserve or enhance  
30 wildlife.  
31

32 6. Energy and Natural Resources

33 a. What kinds of energy (electric, natural gas, oil, wood stove,  
34 solar) will be used to meet the completed project's energy  
35 needs? Describe whether it will be used for heating,  
36 manufacturing, etc.

37 None.  
38

**TO BE COMPLETED BY APPLICANT**

**EVALUATIONS FOR  
AGENCY USE ONLY**

1           **b. Would your project affect the potential use of solar energy by**  
2           **adjacent properties? If so, generally describe.**

3           No.

4  
5           **c. What kinds of energy conservation features are included in the**  
6           **plans of this proposal? List other proposed measures to**  
7           **reduce or control energy impacts, if any:**

8           None.

9  
10       **7. Environmental Health**

11           **a. Are there any environmental health hazards, including**  
12           **exposure to toxic chemicals, risk of fire and explosion, spill, or**  
13           **hazardous waste that could occur as a result of this proposal?**  
14           **If so, describe.**

15           No.

16  
17           **1) Describe special emergency services that might be required.**

18           No special emergency services are known to be required.

19  
20           **2) Proposed measures to reduce or control environmental**  
21           **health hazards, if any:**

22           None.

23  
24           **b. Noise**

25           **1) What type of noise exists in the area which may affect your**  
26           **project (for example: traffic, equipment, operation, other)?**

27           None is anticipated.

28  
29           **2) What types and levels of noise would be created by or**  
30           **associated with the project on a short-term or a long-term**  
31           **basis (for example: traffic, construction, operation, other)?**  
32           **Indicate what hours noise would come from the site.**

33           None is anticipated.

34  
35           **3) Proposed measures to reduce or control noise impacts, if**  
36           **any:**

37           None.

**TO BE COMPLETED BY APPLICANT**

**EVALUATIONS FOR  
AGENCY USE ONLY**

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33  
34  
35  
36

**8. Land and Shoreline Use**

**a. What is the current use of the site and adjacent properties?**

The 216-A-29 Ditch site is not in use. Adjacent properties are industrial/research.

**b. Has the site been used for agriculture? If so, describe.**

No portion of the 200 East Area has been used for agricultural purposes since 1943.

**c. Describe any structures on the site.**

There are no structures at the 216-A-29 Ditch site.

**d. Will any structures be demolished? If so, what?**

Not applicable. There are no structures on the site (refer to Section B.8.c).

**e. What is the current zoning classification of the site?**

Does not apply. The site is located on Federal lands and as such is not subject to the Growth Management Act (State of Washington land use authority). However, for completeness, the Hanford Site is currently included in the Benton County Comprehensive Plan (June 22, 1998) as the undesignated "Hanford Sub-Area".

**f. What is the current comprehensive plan designation of the site?**

The Federal land management decision process has determined through NEPA [*Hanford Comprehensive Land-Use Plan Environmental Impact Statement Record of Decision* (64 FR 61615, November 12, 1999)] that the 200 East Area geographic area, which includes the 216-A-29 Ditch, is designated Industrial-Exclusive.

**g. If applicable, what is the current shoreline master program designation of the site?**

Does not apply.

**TO BE COMPLETED BY APPLICANT**

**EVALUATIONS FOR  
AGENCY USE ONLY**

1        **h. Has any part of the site been classified as an "environmentally**  
2        **sensitive" area? If so, specify.**

3        No.

4

5        **i. Approximately how many people would reside or work in the**  
6        **completed project?**

7        None after the closure activity is performed.

8

9        **j. Approximately how many people would the completed project**  
10       **displace?**

11       None.

12

13       **k. Proposed measures to avoid or reduce displacement impacts, if**  
14       **any:**

15       Does not apply.

16

17       **l. Proposed measures to ensure the proposal is compatible with**  
18       **existing and projected land uses and plans, if any:**

19       Does not apply (refer to Section B.8.f.).

20

21       **9. Housing**

22       **a. Approximately how many units would be provided, if any?**  
23       **Indicate whether high, middle, or low-income housing.**

24       None.

25

26       **b. Approximately how many units, if any, would be eliminated?**  
27       **Indicate whether high, middle, or low-income housing.**

28       None.

29

30       **c. Proposed measures to reduce or control housing impacts, if**  
31       **any:**

32       Does not apply.

33

**TO BE COMPLETED BY APPLICANT**

**EVALUATIONS FOR  
AGENCY USE ONLY**

1 **10. Aesthetics**

2 a. **What is the tallest height of any proposed structure(s), not**  
3 **including antennas; what is the principal exterior building**  
4 **material(s) proposed?**

5 No new structures are being proposed.  
6

7 b. **What views in the immediate vicinity would be altered or**  
8 **obstructed?**

9 None.  
10

11 c. **Proposed measures to reduce or control aesthetic impacts, if**  
12 **any:**

13 None.  
14

15 **11. Light and Glare**

16 a. **What type of light or glare will the proposal produce? What**  
17 **time of day would it mainly occur?**

18 None.  
19

20 b. **Could light or glare from the finished project be a safety**  
21 **hazard or interfere with views?**

22 No.  
23

24 c. **What existing off-site sources of light or glare may affect your**  
25 **proposal?**

26 None.  
27

28 d. **Proposed measures to reduce or control light and glare**  
29 **impacts, if any:**

30 None.  
31

32 **12. Recreation**

33 a. **What designated and informal recreational opportunities are**  
34 **in the immediate vicinity?**

35 None.  
36

**TO BE COMPLETED BY APPLICANT**

**EVALUATIONS FOR  
AGENCY USE ONLY**

1        **b. Would the proposed project displace any existing recreational**  
2            **uses? If so, describe.**

3            No.

4  
5        **c. Proposed measures to reduce or control impacts on recreation,**  
6            **including recreation opportunities to be provided by the**  
7            **project or applicant, if any?**

8            None.

9  
10    **13. Historic and Cultural Preservation**

11        **a. Are there any places or objects listed on, or proposed for,**  
12            **national, state, or local preservation registers known to be on**  
13            **or next to the site? If so, generally describe.**

14            No places or objects listed on, or proposed for, national, state, or  
15            local preservation registers are known to be on or next to the 216-A-  
16            29 Ditch.

17  
18        **b. Generally describe any landmarks or evidence of historic,**  
19            **archaeological, scientific, or cultural importance known to be**  
20            **on or next to the site.**

21            There are no known archaeological, historical, or Native American  
22            religious sites on or near the 216-A-29 Ditch.

23  
24        **c. Proposed measures to reduce or control impacts, if any:**

25            None.

26  
27    **14. Transportation**

28        **a. Identify public streets and highways serving the site, and**  
29            **describe proposed access to the existing street system. Show**  
30            **on site plans, if any.**

31            Does not apply.

32  
33        **b. Is site currently served by public transit? If not, what is the**  
34            **approximate distance to the nearest transit stop?**

35            No. The distance to the nearest public transit stop is approximately  
36            50 kilometers, located at Washington State University Tri-Cities.

37

**TO BE COMPLETED BY APPLICANT**

**EVALUATIONS FOR  
AGENCY USE ONLY**

1           **c. How many parking spaces would the completed project have?**  
2           **How many would the project eliminate?**

3           Not applicable.  
4

5           **d. Will the proposal require any new roads or streets, or**  
6           **improvements to existing roads or streets, not including**  
7           **driveways? If so, generally describe (indicate whether public**  
8           **or private).**

9           No.  
10

11          **e. Will the project use (or occur in the immediate vicinity of)**  
12          **water, rail, or air transportation? If so, generally describe.**

13          No.  
14

15          **f. How many vehicular trips per day would be generated by the**  
16          **completed project? If known, indicate when peak volumes**  
17          **would occur.**

18          Additional vehicular trips would be required to remove  
19          contaminated soils. Peak traffic volumes would occur during the  
20          daytime.  
21

22          **g. Proposed measures to reduce or control transportation**  
23          **impacts, if any:**

24          None.  
25

26          **15. Public Services**

27          **a. Would the project result in an increased need for public**  
28          **services (for example: fire protection, police protection, health**  
29          **care, schools, other)? If so, generally describe.**

30          No.  
31

32          **b. Proposed measures to reduce or control direct impacts on**  
33          **public services, if any:**

34          Does not apply.  
35

**TO BE COMPLETED BY APPLICANT**

**EVALUATIONS FOR  
AGENCY USE ONLY**

1 **16. Utilities**

2 a. **Circle utilities currently available at the site: electricity,**  
3 **natural gas, water, refuse service, telephone, sanitary sewer,**  
4 **septic system, other:**

5 No utilities currently are available at the 216-A-29 Ditch.  
6

7 b. **Describe the utilities that are proposed for the project, the**  
8 **utility providing the service, and the general construction**  
9 **activities on the site or in the immediate vicinity which might**  
10 **be needed.**

11 No utilities are planned for the proposed activity. If necessary, to  
12 support contaminated soil removal, portable electrical generators  
13 could be provided on a temporary basis.

1 **SIGNATURES**

2

3 The above answers are true and complete to the best of my knowledge. I understand that the lead agency  
4 is relying on them to make its decision.

5

6

7

8

9

10 \_\_\_\_\_  
11 Keith A. Klein, Manager  
12 U.S. Department of Energy  
13 Richland Operations Office

\_\_\_\_\_ Date

13

14

15