



0065541

Geotechnical Laboratory
PO Box 4339
1570 Bear Creek Road
Oak Ridge TN 37830
(865) 482-6497

CERTIFICATE OF ANALYSIS

Stephen Trent
Fluor Hanford, Inc.
825 Jadwin Avenue
Richland, Washington 99352

January 4, 2005

This is the Certificate of Analysis for the following samples:

Shaw Project ID:	Eberline - Hanford
Shaw Project Number:	100846.34000000
Client Sample Data Group:	H2817
Date Received by Lab:	November 17, 2004
Number of Samples:	One (1)
Sample Type:	Soil

RECEIVED
JUN 20 2005
EDMC

I. Introduction/Case Narrative


One soil sample was received by the Shaw Geotechnical Laboratory on November 17, 2004. The sample was submitted for determination of moisture content, bulk density, and sieve analysis, permeability, specific gravity and calcium carbonate content. The sample number received was B19NK4.

Please see Appendix A, Sample Number Cross Reference List; Appendix B, Analysis Results; and Appendix C, Chain-of-Custody/Sample Receipt Records.

"I certify that this data package is in compliance with the SOW, both technically and for completeness, for other than the conditions detailed above. Release of the data contained in this hardcopy data package has been authorized by the Laboratory Manager or a designee, as verified by the following signature."

Reviewed and Approved:

Ralph Cole
Laboratory Manager, Geotechnical Services



000000001

II. Analytical Results/Methodology

REFERENCES: United States Army Corps of Engineers (USACE), Engineer Manual 1110-2-1906, *Laboratory Soils Testing*, appendix II, 1970; United States Environmental Protection Agency, SW846, *Test Methods for Examining Solid Waste, Physical/Chemical Methods*, 3rd ed., Nov 1986 (EPA SW-846). Annual Book of ASTM Standards, Section 4, Construction, Volume 04.08, *Soil and Rock (I)*, and Volume 04.09, *Soil and Rock (II)*, 2004. Shaw Environmental and infrastructure, Standard Operating Procedures.

Moisture Content of Soil and Rock.....	ASTM D 2216
Bulk Density of Soils.....	EM 1110-2-1906
Particle-size Analysis of Soils	ASTM D 422
Specific Gravity of Soil.....	ASTM D 854
Calcium Carbonate Content.....	ASTM D 4373

III. Quality Control

Quality control checks such as duplicates and spikes (QC samples), are not normally applicable to geotechnical testing. This is due largely to the inability of obtaining samples with known characteristics, the heterogenous nature of the samples, and quality control procedures built-in to the analytical method.

QC measures to ensure accuracy and precision of test results include the following:

- 100% verification of all numerical results - raw data entries, transcriptions and calculations entered by lab technicians are checked, recalculated and verified. Most data calculations are performed by computer programs.
- Data validation through test reasonableness - summaries of all test results for individual reports are reviewed to determine the overall reasonableness of data and to determine the presence of any data that may be considered outliers.
- Quality control procedures are built into most standardized geotechnical procedures. For example, liquid limit and plastic limit analyses call for re-analyses and specify acceptance criteria.
- Routine instrument calibration - instruments, gauges and equipment used in testing are calibrated on a routine basis. All instrument calibration follows ASTM or manufacturer guidelines.
- Maintenance of all past calibration records - calibration records and certification documents of all instruments, gauges and equipment are updated routinely and maintained in the Quality Control Coordinators Quality/Operations files.

- Certified and trained personnel - all technicians are certified by the National Institute for Certification of Engineering Technicians (NICET) in geotechnical soil testing, and are trained in the application of standard laboratory procedures for geotechnical analyses as well as the quality assurance measures implemented by Shaw.
- Quantitative analyses frequently used in geotechnical/physical testing programs do not use QC tools common to wet chemistry or radiochemistry laboratories. Measures not employed in the analysis of samples reported in this report include: laboratory control samples (LCS), blanks, matrix spikes (MS), duplicate analyses, dilutions, digestions, correction factors, surrogate sample analyses, detection limit determinations, control charts, and/or tentatively identified compounds (TICs).

IV. Data Qualification

This soil sample contained a significant amount of oversize particles. Therefore, in addition to the normal specific gravity test (ASTM D 854) the specific gravity of the coarse fraction was determined by ASTM C 127. The value representing the overall sample specific gravity is given as "average bulk specific gravity". Other values are given that relate to materials used in civil engineering fields.

Appendix A
Sample Cross-Reference List

Page 4 of 14
January 4, 2005
Stephen Trent
Fluor Hanford, Inc.
Shaw Project Name: Eberline Hanford
Shaw Project No. 100846.34000000
SDG No. H2817

**Shaw Geotechnical
Laboratory
Oak Ridge TN
(865) 482-6497**

SAMPLE NUMBER CROSS-REFERENCE LIST

LAB SAMPLE NO.

CLIENT SAMPLE NO.

MATRIX

BC0472 B19NK4 Soil

00000005

Appendix B
Sample Test Results

MOISTURE CONTENT

PROJECT NUMBER

100846.34000000

[illegible]

Solids content is determined by subtracting the SW846 moisture (%) from 100.

00000007

00000008

PARTICLE-SIZE DISTRIBUTION ASTM D 422

Project Name Eberline Hanford

Field Sample No. B19NK4

Project No. 100846.34000000

Lab Sample No. BC0472


Moisture Content = 17.3%
 based on dry sample weight

SIEVE ANALYSIS

C O A R S E	Sieve No.	Diameter mm	Percent Finer
	3"	75.000	100.0%
	1.5"	37.500	100.0%
	0.75"	19.000	77.4%
	0.375"	9.500	64.2%
	#4	4.750	61.4%
	#10	2.000	59.7%

F I N E	Sieve No.	Diameter mm	Percent Finer
	#20	0.850	57.3%
	#40	0.425	33.0%
	#60	0.250	18.8%
	#100	0.149	13.3%
	#140	0.106	11.3%
	#200	0.075	9.7%

DISTRIBUTION CURVE



38.6% Gravel

51.6% Sand

9.7% Silt/Clay

00000009


**HYDRAULIC CONDUCTIVITY / PERMEABILITY
 ASTM D 5084**

PROJECT NAME: Eberline Hanford
 PROJECT NO. 100846.34000000

CLIENT SAMPLE NO. B19NK4
 LAB SAMPLE NO. BC0472

	INITIAL	FINAL		
Specimen diameter, cm	6.24		Hydraulic gradient	6.2
Specimen length, cm	5.69		Min. consolidation stress, psi	12.0
Wet weight of specimen, g.	377.65		Max. consolidation stress, psi	12.0
Specimen cross-sect. area, cm ²	30.56		Total backpressure, psi	0.0
Water content, %	17.3		Permeant Fluid	Deaired DI Water
Wet unit weight, pcf	135.6			
Dry unit weight, pcf	115.6			
Degree of saturation, %	107.2			
Specific gravity of solids	2.64			

Coefficient of Permeability, cm/s 1.6E-06



PROJECT NAME: Eberline Hanford **PROJECT NUMBER:** 100846.34

* Saturated Surface Dry

00000001 1

PROJECT NUMBER:
100846.34000000

[illegible]

Appendix C
Chain-of-Custody and Request-for-Analysis Records

Eberline Srvces

PAGE 1

CHAIN OF CUSTODY

ORD # R4-11-123

11/15/04 08:30:04

WORK ID: SAF# F03-018 SDG H2817

RCVD: 11/12/04 DUE: 12/27/04

KEEP: 12/27/05 DISP: S

DASH	SAMPLE IDENTIFICATION	STORED	TESTS				
01A-S	B19NK4	SHAW	DISPOS	E331S	E333S	E335S	E342S

<u>RELEASED BY</u>	<u>DATE</u>	<u>TRANSFERRED TO</u>	<u>DATE</u>	<u>RECEIVED BY</u>	<u>DATE</u>
Jud Dena	11/16/04	Shaw	11/16/04	Jud Dena	11-17-04

0000001 5