0056035

Attachment 2

Station 4 **S**

NOV 06 2001

ENGINEERING DATA TRANSMITTAL

Page 1 of 1

1. EDT 632901

2. To: (Receiving Organization) C-104 Retrieval Project	3. From: (Originating Organization) Project & Procurement Engineering	4. Related EDT No.: N/A
5. Proj./Prog./Dept./Div.: C-104/SST Retrieval Projects	6. Design Authority/Design Agent/Cog. Engr.: DB Parkman	7. Purchase Order No.: N/A
8. Originator Remarks:		9. Equip./Component No.: N/A
		10. System/Bldg./Facility: C-104 Waste Retvl Sys
		12. Major Assm. Dwg. No.: N/A
11. Receiver Remarks: 11A. Design Baseline Document? ☐ Yes ☒ No This EDT transmits to the Office of River Protection (ORP) the final C-104 F&R document. This document will be submitted to Washington Department of Ecology (WDOE) to initiate the primary agreement document review process. This document is not a design baseline document while pending approval as a primary agreement between ORP and WDOE.		13. Permit/Permit Application No.: N/A
		14. Required Response Date: N/A

15. DATA TRANSMITTED

(A) Item No.	(B) Document/Drawing No.	(C) Sheet No.	(D) Rev. No.	(E) Title or Description of Data Transmitted	(F) Approval Designator	(G) Reason for Transmittal	(H) Originator Disposition	(I) Receiver Disposition
1	RPP-7807, REV. 0		0	Single-Shell Tank C-104	E	1	1	
				Full Scale Sludge/Hard				
				Heel, Confined Sluicing				
				and Robotic Technologies,				
				Waste Retrieval				
				Demonstration Functions				
				and Requirements				

RECEIVED JAN 02 2002 EDMC

16. KEY

Approval Designator (F)	Reason for Transmittal (G)	Disposition (H) & (I)
E, S, Q, D OR N/A (See WHC-CM-3-5, Sec. 12.7)	1. Approval 2. Release 3. Information 4. Review 5. Post-Review 6. Dist. (Receipt Acknow. Required)	1. Approved 2. Approved w/comment 3. Disapproved w/comment 4. Reviewed no/comment 5. Reviewed w/comment 6. Receipt acknowledged

17. SIGNATURE/DISTRIBUTION (See Approval Designator for required signatures)

(G) Reason	(H) Disp.	(J) Name	(K) Signature	(L) Date	(M) MSIN	(G) Reason	(H) Disp.	(J) Name	(K) Signature	(L) Date	(M) MSIN
		Design Authority				1	1	RC Wilson		11/5/01	57-90
		Design Agent				1	1	WT Thompson	for	5 Nov 01	57-90
1	1	Cog. Eng. DB Parkman	DB Parkman	11-2-01	55-13	1	1	DW Crass		5 Nov 01	57-90
1	1	Cog. Mgr. KE Carpenter	KE Carpenter	11/2/01	57-90	1	1	RD Wojtasek		11/05/01	
		QA									
		Safety									
1	1	Env. PC Miller		11/5/01							

18.	19.	20.	21. DOE APPROVAL (if required)
KE Carpenter 11/2/01 Signature of EDT Originator / Date	KE Carpenter 11/2/01 Authorized Representative for Receiving Organization / Date	KE Carpenter 11/2/01 Design Authority/ Cognizant Manager / Date	Ctrl No. ____ ☐ Approved ☐ Approved w/comments ☐ Disapproved w/comments

Single-Shell Tank C-104 Full Scale Sludge/Hard Heel, Confined Sluicing and Robotics Technologies, Waste Retrieval Demonstration Functions and Requirements

Keith Carpenter
CHG
Richland, WA 99352
U.S. Department of Energy Contract DE-AC27-99RL14047

EDT/ECN: 632901 UC:
Cost Center: 7P300 Charge Code: 110424
B&R Code: EW01J2040 Total Pages: 255

Key Words: C-104, Functions and Requirements, TPA, Confined Sluicing, LDMM, Leak Detection, Monitoring, Mitigation

Abstract: This document establishes the functions and requirements (F&Rs), required by Milestone M-45-03-T04 of the Hanford Federal Facility Agreement and Consent Order, (DOE et al, 1989, as amended), for the retrieval of mixed waste stored in SST 241-C-104, a designated sound tank located in the 200 East Area of the Hanford Site. The systems proposed to retrieve the tank waste will demonstrate alternate technologies and approaches to retrieving the waste and to LDMM.

TRADEMARK DISCLAIMER. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.

Printed in the United States of America. To obtain copies of this document, contact: Document Control Services, P.O. Box 950, Mailstop H6-08, Richland WA 99352, Phone (509) 372-2420; Fax (509) 376-4989.

NOV 06 2001
DATE:
STA: 4
HANFORD RELEASE
ID: 21

11/5/01
Release Approval Date Release Stamp

Approved For Public Release

SINGLE-SHELL TANK C-104
FULL SCALE SLUDGE/HARD HEEL, CONFINED SLUICING AND ROBOTIC TECHNOLOGIES, WASTE RETRIEVAL DEMONSTRATION
FUNCTIONS AND REQUIREMENTS

EXECUTIVE SUMMARY

The Hanford Site has 149 single-shell tanks (SSTs) and 28 double-shell tanks (DSTs) containing high-level radioactive waste produced from nuclear fuel reprocessing. The U.S. Department of Energy Office of River Protection is responsible for operating the tank farms, retrieving the waste from the tanks, treating and immobilizing the waste for safe storage and ultimate disposal. The SSTs are not equipped with a secondary containment structure or capability, are beyond their design life, and many of the tanks have leaked or are suspected of leaking waste to the surrounding soil.

This document establishes for the life of the project the functions and requirements (F&Rs), required by Milestone M-45-03-T04 of the Hanford Federal Facility Agreement and Consent Order, (DOE et al, 1989, as amended), for the retrieval of mixed waste stored in SST 241-C-104, a designated sound tank located in the 200 East Area of the Hanford Site. The systems proposed to retrieve the tank waste will demonstrate alternate technologies and approaches to retrieving the waste and to leak detection, monitoring, and mitigation (LDMM). This functions and requirements document is a primary document as agreed among the U.S. Department of Energy, the Washington State Department of Ecology, and the U.S. Environmental Protection Agency. Upon approval, this document allows final design of the retrieval system to commence.

This document also presents lessons learned from other government and industry retrieval projects, which are tabulated in Appendix A. The scoping level Retrieval Performance Evaluation (RPE) for 241-C Farm, which focuses on 241-C-104, is in Appendix B. The LDMM and retrieval strategy for 241-C-104 is contained in Section 5.

The goals of this demonstration include the retrieval to safe storage of approximately 99% of the existing tank contents by volume and 89 kilograms of plutonium. This will leave a residual waste volume of approximately 360 cubic feet or less depending on the limits of the retrieval technology.

The SSTs, including 241-C-104, do not meet all State or Federal requirements for storage or operation of hazardous waste facilities, particularly those regulatory requirements for secondary containment and leak detection. In order to develop health-based limits for waste remaining in the tank after retrieval and for leakage that could occur during retrieval operations, a scoping level RPE was prepared. The RPE includes a human health and environmental risk assessment, and establishes the risks from waste remaining in the tank after retrieval and risks posed by leakage during retrieval for several exposure scenarios. The RPE methodology is an iterative process that can be applied before waste retrieval to help develop criteria for the extent of retrieval and leak loss, and then after retrieval to evaluate performance measures using actual retrieval and leak loss data. The results of the pre-retrieval RPE are incorporated into this functions and requirements document as requirements applicable to the design of the retrieval and LDMM systems.

The RPE indicates that waste remaining in the tank will exceed Class C limits (10 CFR 61.55) even after 99% of the waste has been removed. According to DOE M 435.1, the waste

remaining in the tanks following retrieval are to be managed as low-level waste provided the waste will be incorporated in a solid physical form at a concentration that does not exceed the applicable concentration limits for Class C low-level waste as set out in 10 CFR 61.55 or will meet alternative requirements as DOE may authorize. Based on the post retrieval inventory estimates in the RPE, DOE will have to pursue alternative waste classification for the residual waste in C-104. This will require the establishment of site-specific waste classification criteria, which is beyond the scope of this document.

The waste retrieval system design for the 241-C-104 retrieval demonstration will incorporate alternatives to past-practice sluicing. A confined sluicing system that minimizes the volume of free liquid in the tank during operations will be used to retrieve the tank waste. Minimizing the tank free liquid will minimize the potential for leaks to the environment, and demonstrate the viability of an alternate technology for retrieving SST wastes.

Mass and volumetric measurement techniques are the current EPA reference standard used for leak detection for petroleum and chemical process storage tanks. These methods will be incorporated into the 241-C-104 waste retrieval system design. Alternate technologies, if economically available and developed to a level that adds confidence and increased capability to the EPA reference methods, will be assessed using the Value Engineering process and incorporated into the 241-C-104 waste retrieval system design, as appropriate.

Table of Contents

1.0 INTRODUCTION 1-1
- 1.1 Background 1-1
- 1.2 Purpose 1-3
- 1.3 Scope 1-3
- 1.4 241-C-104 Conditions 1-5
- 1.5 Document Organization 1-7

2.0 REQUIREMENTS FRAMEWORK 2-1
- 2.1 Hanford Federal Facility Agreement and Consent Order Requirements 2-1
- 2.2 Regulatory Requirements 2-5

3.0 TECHNICAL APPROACH TO DEVELOPING RISK-BASED RETRIEVAL REQUIREMENTS 3-1
- 3.1 Integrated SST Waste Retrieval and LDMM Risk-Based Strategy 3-1
- 3.2 Development and Use of Performance Requirements Through the RPE 3-6
- 3.3 Use of Lessons Learned in Supporting Selection and Implementation of Retrieval and LDMM Technologies 3-9

4.0 FUNCTIONS & REQUIREMENTS 4-1
- 4.1 Control 241-C-104 Structure and Waste Temperature 4-1
- 4.2 Control 241-C-104 Waste Level 4-1
- 4.3 Control 241-C-104 Vapor Space Pressure 4-1
- 4.4 Control 241-C-104 Gaseous Discharges 4-2
- 4.5 Remove Waste from 241-C-104 4-2
- 4.6 Control and Monitor the 241-C-104 Waste Removal Process 4-2
  - 4.6.1 Detect Leaks During 241-C-104 Waste Removal 4-3
  - 4.6.2 Monitor Leaks From 241-C-104 During Waste Removal 4-3
  - 4.6.3 Control And Monitor 241-C-104 Waste Retrieval 4-3
- 4.7 Measure and Estimate Residual Waste in 241-C-104 4-4
- 4.8 Waste Minimization 4-4
- 4.9 Mitigate Leaks During 241-C-104 Waste Retrieval Process 4-4
- 4.10 Nuclear Safety 4-4
- 4.11 DST Design Limits 4-4
  - 4.11.1 DST Waste Temperature 4-5
  - 4.11.2 DST Pressure Limits 4-5
  - 4.11.3 DST Hydrostatic Load Limits 4-5
- 4.12 241-C-104 Waste Retrieval System Design 4-6
- 4.13 Occupational Safety and Health 4-6
- 4.14 SST and DST Dome Loading 4-6
- 4.15 Prohibited Materials 4-6
- 4.16 Waste Retrieval System Secondary Containment and Leak Detection 4-6
- 4.17 Waste Retrieval System Deactivation and Decontamination 4-7

5.0 LDMM AND RETRIEVAL STRATEGY 5-1
- 5.1 Integrated Strategy for LDMM and Retrieval 5-1
  - 5.1.1 Leak Detection 5-3

5.1.2 Leak Monitoring 5-8
5.1.3 Leak Mitigation 5-8
5.2 241-C-104 Retrieval and LDMM System Descriptions 5-9
5.2.1 241-C-104 Retrieval System Description 5-9
5.2.2 LDMM System Description 5-10
5.3 LDMM and Retrieval Operating Strategy 5-12
5.3.1 Pre-Retrieval 5-13
5.3.2 Retrieval 5-13
5.3.3 Post Retrieval 5-18
5.3.4 Alternative Technologies 5-19
6.0 HANFORD FEDERAL FACILITY AGREEMENT AND CONSENT ORDER F&R CHANGE CONTROL 6-1
7.0 REFERENCES 7-1

APPENDICES

APPENDIX A – Lessons Learned Basis For Selection And Implementation Of Retrieval And LDMM Technologies

APPENDIX B – Retrieval Performance Evaluation For Single-Shell Tank C-104 [Scoping Level RPE]

FIGURES

Figure 1-1. 241-C Farm Plan View and RCRA Monitoring Wells 1-4
Figure 1-2. 241-C Farm Plan View and Borehole (Drywell) Locations 1-6
Figure 3-1. Corrective Actions for Tank Farm Closure 3-3
Figure 3-2. 241-C-104 Retrieval Release Criterion vs. Residual Waste 3-5
Figure 5-1. Leak Minimization Triangle 5-2
Figure 5-2. Undetected Leak Volume vs. Retrieval Duration At Loss of 1.8 Gal/Hr 5-7
Figure 5-3. 241-C-104 Mobile Retrieval System 5-10
Figure 5-4. 241-C-104 Dynamic Leak Detection 5-11
Figure 5-5. 241-C-104 Static Leak Detection 5-12
Figure 5-6. Retrieval/LDMM Operational Response Process Diagram 5-15

TABLES

Table 2-1. Hanford Federal Facility Agreement and Consent Order Milestones Applicable to 241-C-104 2-2
Table 2-2. State and Federal Regulations 2-5
Table 4-1. Existing Double-Shell Tank Hydrostatic Load Limits 4-5
Table 5-1. Leak Volumes for Various Retrieval Durations with Constant Leak Rates 5-6
Table 5-2. Instrumentation Requirements for Dynamic Leak Detection 5-16
Table 5-3. Instrumentation Requirements for Static Leak Detection 5-18

Acronyms

ALARA	as low as reasonably achievable
ASTM	American Society for Testing and Materials
BATEA	best available technology economically achievable
BBI	Best Basis Inventory
CFR	Code of Federal Regulations
DOE	U.S. Department of Energy
DST	Double-Shell Tank
Ecology	State of Washington Department of Ecology
ENRAF™	Enraf-Nonius™
EPA	U.S. Environmental Protection Agency
FIC™	Food Instrument Corporation™
F&R	Functions & Requirements
FY	Fiscal Year
gal/hr	gallon(s) per hour
ILCR	Incremental Lifetime Cancer Risk
LDMM	Leak Detection, Monitoring & Mitigation
mgal	million gallons
MOU	Memorandum of Understanding
MUST	miscellaneous underground storage tanks
NEPA	National Environmental Policy Act of 1969
ORP	Office of River Protection
PNNL	Pacific Northwest National Laboratory
RCRA	Resource Conservation and Recovery Act of 1976
RPE	Retrieval Performance Evaluation
RPP	River Protection Project
SpG	specific gravity
SST	Single-Shell Tank
TWINS	Tank Waste Information System
WAC	Washington Administrative Code
w.g.	water-gauge - unit of measure for pressure or vacuum given as "inches of water-gauge"

1.0 INTRODUCTION

The River Protection Project (RPP) mission includes retrieval, immobilization, storage and disposal of high-level radioactive waste presently stored in 177 underground tanks located in the 200 East and 200 West Areas of the U.S. Department of Energy (DOE) Hanford Site. These tanks consist of 149 single-shell tanks (SSTs) - constructed between 1943 and 1964 and 28 newer double-shell tanks (DSTs). The SSTs and DSTs contain a variety of solid and liquid wastes resulting from several decades of nuclear fuel reprocessing and radionuclide recovery processes conducted at the Hanford Site. Immobilization of the retrieved tank wastes for subsequent interim storage and eventual disposal will be performed at a waste treatment facility that is to be constructed at the Hanford Site.

Due to concerns related to the liquid containment integrity of the older SSTs, current plans call for retrieving the SST waste and staging it in the more reliable DSTs to serve as feed material for the waste immobilization process. SST waste retrieval activities will be conducted, to the extent required, to meet requirements that allow ultimate closure of the tank and the tank farm. DOE, the State of Washington Department of Ecology (Ecology), and the U.S. Environmental Protection Agency (EPA) have adopted a risk-based approach to SST retrieval. Ecology is the lead agency in this work. This approach includes:

- Demonstrating alternative retrieval approaches and baseline planning, leak detection, monitoring and mitigation (LDMM) technologies in tanks containing sludge, saltcake, and mixed saltcake and sludge, and using the results of these demonstrations for future SST retrieval approaches.
- Retrieving tanks that pose the highest risk to minimize the impact of potential releases to the environment. Tank C-104 represents the highest amount of plutonium in any SST.
- Using human health and environmental risk analysis tied to ongoing vadose zone, characterization, and contaminant transport estimates to establish LDMM and retrieval system performance requirements and operating strategies.

1.1 Background

During the 1950s, 1960s, and 1970s, waste from SSTs was retrieved from 58 SSTs using past-practice sluicing. Past-practice sluicing used one or more high volume liquid jets to dislodge and mobilize the tank waste slurry. The slurry was then pumped from the tank. Most recently, waste from 241-C-106 was retrieved using past-practice sluicing to resolve a potential safety problem associated with high amounts of heat generated by the decay of radioactive isotopes in the waste. In this retrieval, the LDMM approach used a static liquid surface measurement along with ex-tank monthly dry well monitoring. The primary concern with continuing the use of past practice sluicing is the potential to leak large volumes of waste during retrieval, as the sluicing systems introduce large volumes of liquid into the tank during retrieval operations.

Numerous technologies have been identified for retrieving the various SST waste types to minimize the potential impacts to the environment. In addition to evaluating these technologies for their recovery capability and feasibility, the associated waste retrieval strategies and

equipment must also integrate the means to detect, monitor, and mitigate detectable leaks. LDMM is legally agreed to by DOE, Ecology, and EPA in the *Hanford Federal Facility Agreement and Consent Order* (DOE et al, 1989, as amended).

The development of a risk-based retrieval release protection strategy and the retrieval performance evaluation (RPE) process are the basis for establishing functions and requirements (F&Rs). The RPE process is an out-growth of procedures negotiated in 1994 to evaluate the 99% retrieval goal, following completion of retrieval demonstration activities. The procedures included determining if an alternative retrieval goal was appropriate if the interim 99% retrieval goal could not be met on a tank-by-tank basis. The RPE methodology was developed in response to a 1996 memorandum of understanding (MOU) between Ecology and DOE that acknowledged the uncertainty with the ability to attain the 99% interim retrieval goal and LDMM requirements (DOE/EPA 1996). Under the MOU, DOE was tasked to assess retrieval performance criteria for the 241-AX Farm as a means of improving the agency's understanding of the applicability of various performance requirements (e.g., the *Hanford Federal Facility Agreement and Consent Order*, State Dangerous Waste Regulations, and DOE Orders). The design, development, screening, and assessment of alternative technologies according to these F&Rs will result in a preferred LDMM and retrieval system design that is protective of human health and the environment.

The SST Retrieval Program Mission Analysis Report (LMHC 1998) documents a technically defensible approach that results in deployment of retrieval and LDMM technologies capable of retrieving waste from SSTs that contain varied waste forms and pose tank-specific physical constraints. The 241-C-104 retrieval demonstration has the following goals:

- Establish the feasibility and limits of a confined sluicing robotics system designed to meet *the Hanford Federal Facility Agreement and Consent* Order M-45-03F milestone retrieval goals; retrieve approximately 99% or more of the existing tank contents by volume from the SST, including approximately 89 kilograms of plutonium or the limit of waste retrieval technology capability.
- Establish performance characteristics and limits of an integrated retrieval and LDMM system designed to minimize leakage during retrieval, if it occurs, and detect leakage within a risk-based performance envelope.
- Upon completion of retrieval activities, provide a basis, along with other SST retrieval projects and demonstration lessons learned, for deploying retrieval and LDMM technologies in the remaining SSTs.
- Demonstrate sludge/hard heel tank retrieval using confined sluicing of robotic techniques (DOE/Ecology 2000, milestone M-45-03-T04).

Closure requirements for SSTs, including acceptable levels of residual waste in the tanks, ancillary equipment, and residual contamination in surrounding soils, as well as cumulative risks posed to human health and the environment from the 241-C Farm, other tank farms, and other waste management sites in the 200 Area, have not yet been agreed to by DOE, Ecology, and EPA. In absence of these requirements, the results of the RPE are used to determine the risk posed by residual waste (i.e., past leaks, leak losses, and residual tank waste) in the 241-C Farm to establish performance requirements that are protective of human health and the environment.

Risk results include the residential farmer post-closure land use scenario. The strategy used to incorporate the RPE results into the retrieval requirements is discussed in Section 3.0.

In addition to the RPE, nuclear safety requirements and existing SST and DST system operational limits are imposed on the waste retrieval system design and are contained in this F&R (see Section 4.0).

Additions of liquids for retrieval purposes and actions are discussed in the Resource Conservation and Recovery Act of 1976 (RCRA), Part A, Form 3, "Interim Status Permit Application."

1.2 Purpose

The purpose of this document is to (1) establish the F&Rs and (2) establish the LDMM and retrieval strategy for the 241-C-104 retrieval demonstration specified in *Hanford Federal Facility Agreement and Consent Order* Milestone M-45-03-T04. Approval of this document allows start of design. Definition of design start, for purposes of the *Hanford Federal Facility Agreement and Consent Order* milestone, is the initiation of final design (DOE Order 413.3) (i.e., beginning of activities to produce the products, engineering design drawings and written specifications that will be used for procurement and construction).

1.3 Scope

This document provides the F&Rs necessary to support the design of the demonstration waste retrieval system for 241-C-104. This document also provides the strategy used to define the functions and F&Rs for retrieval and leak detection based on the RPE (Appendix B). This document satisfies the requirements established in *Hanford Federal Facility Agreement and Consent Order* Milestone M-45-03-T04 by:

- Establishing the demonstration system requirements including the LDMM requirements (Section 4),
- Including a scoping level RPE (Appendix B) detailing the known and estimated radionuclide contamination and contaminant migration within the vadose zone as bases of calculation to provide environmental and human health risk evaluation data/information associated with estimated waste volumes to be retrieved, the maximum volume which could leak during retrieval, and risk from residual waste,
- Including lessons learned from previous DOE and industry retrieval projects (Appendix A),
- Including the LDMM and retrieval strategy for the 241-C-104 retrieval demonstration (Section 5), and
- Addressing mitigation strategies and decision thresholds for potential leaks during retrieval (Section 3).

The F&Rs identified in this document provide the foundation for the design criteria and design requirements documented in Level 2 design specifications. Design specifications are used to develop the project engineering concepts, scope, and boundaries. The content of the design specifications will include detailed requirements such as operating pressures, temperatures,

materials of construction and control system requirements, confinement boundaries and controls, interface requirements and similar detailed application requirements. The design specifications for the 241-C-104 retrieval system will be developed during pre-design and Title I design activities based on this approved F&Rs document.

Figure 1-1 provides a plan view of the 241-C Farm and nearby RCRA groundwater monitoring wells. Groundwater monitoring activities will be consistent with the *RCRA Groundwater Monitoring Plan for Single-Shell Tank Waste Management Area C at the Hanford Site"* (PNNL 2001) and any future changes that are implemented. Drywell monitoring will occur prior to, during, and following 241-C-104 waste retrieval activity.



Figure 1-1. 241-C Farm Plan View and RCRA Monitoring Wells

1.4 241-C-104 Conditions

The 241-C Farm was constructed between 1943 and 1944, as one of the first generation Tank Farms. (241-C-104 is one of twelve 100-series, 530,000-gal, 75-foot-diameter SSTs in the 241-C Farm.) Tank 241-C-104 operated in support of various fuel reprocessing and radionuclide recovery campaigns from 1946 through 1980, when the tank was removed from service. Tank C-104 was declared "interim stabilized" in September 1989, with the remaining waste categorized as sludge. Currently, 241-C-104 is categorized as sound (i.e., non-leaking), per *Waste Tank summary Report for July 2001* [CHG, 2001]).

Tank C-104 contains approximately 263,000 gallons of sludge produced from plutonium and uranium production (Tank Interpretive Report [TIR, 2000]). Primary contaminants of concern include plutonium, americium, cesium, and strontium. The tank currently contains approximately 23,500 curies of Plutonium, 6,400 curies of ^{241}Am, 114,000 curies of ^{137}Cs, and 579,000 curies of ^{90}Sr, with a total inventory of 1,470,000 curies from all isotopic constituents. Sample analysis data, along with estimates based on process modeling and flow sheets, have been used to develop the best basis inventory (BBI) for all Hanford underground tank waste from which the above data is taken (Tank Waste Information System [TWINS Website 2001]). The RPE provides additional information on tank waste constituents.

Figure 1-2 shows a plan view of tank farm 241-C with borehole (drywell) locations shown inside the tank farm. The drywells around 241-C-104 will be used in addition to other methods (see Section 5) for leak detection and monitoring of possible leaks. Ten dry wells (also called vadose zone monitoring boreholes) were installed around 241-C-104 between March of 1970 and October of 1974 to provide a means of detecting tank leaks. The casings are 6 inches in diameter. The wells end above the water table and vary in depth. Two are 50-feet deep, one is 60-feet deep, four are 100-feet deep, two are 135-feet deep and one is 145-feet deep (Vadose 2001). Leak detection was accomplished through periodic geophysical logging of the dry wells (e.g., to detect radiation and moisture increases).



Figure 14-11. Plan View of the C Tank Farm Showing Borehole Locations

Figure 1-2. 241-C Farm Plan View and Borehole (Drywell) Locations

1.5 Document Organization

This document is organized as follows:

- Section 1 provides an introduction, background, purpose, and scope to this document, as well as a summary of current 241-C-104 conditions.
- Section 2 identifies the regulatory framework and governing requirements documents under which the retrieval demonstration of 241-C-104 will be conducted.
- Section 3 presents a description of the technical approach that leads to the development of the risk-based requirements, including the LDMM requirements. The technical approach includes the use of experience from other similar retrieval projects that are captured as lessons learned.
- Section 4 lists the F&Rs, which will govern the design of the 241-C-104 retrieval demonstration.
- Section 5 defines the retrieval and LDMM strategy, including a description of the retrieval and LDMM systems, which will guide the design of the demonstration retrieval system for 241-C-104.
- Section 6 includes a discussion of the change control procedures that will govern changes of this document.
- Section 7 lists the references cited throughout the document.
- Appendix A is a summary of lessons learned and a bibliography of documented DOE and industry retrieval experience considered in developing the technical approach and F&Rs for retrieving 241-C-104.
- Appendix B is the draft scoping-level RPE for 241-C Farm, which supports the technical approach to the development of the retrieval and LDMM strategy for 241-C-104 based on the known and estimated radionuclide contamination and contaminant migration with the vadose zone.

2.0 REQUIREMENTS FRAMEWORK

This section defines the requirements framework under which the 241-C-104 retrieval demonstration system will be designed and operated. Sources of requirements include the *Hanford Federal Facility Agreement and Consent Order*, Code of Federal Regulations (CFRs) and applicable Washington Administrative Codes (WACs) governing DOE activities. Retrieval and LDMM technologies will be designed and operated in accordance with state and federal requirements as specified in *the Hanford Federal Facility Agreement and Consent Order* and DOE contracts.

The SST system was designed and built before existing standards were promulgated for radiological, environmental, and worker safety. The age and condition of the SSTs limit the extent of the upgrades and corrections that are physically possible. DOE, Ecology, and EPA have approved *Hanford Federal Facility Agreement and Consent Order* Milestone M-45-00, which states:

> "All parties recognize that the reclassification of previously identified RCRA past-practice units to ancillary equipment associated with the treatment, storage, and disposal unit is strictly for application of a consistent closure approach. Upgrades to previously classified RCRA past-practice units to achieve compliance with RCRA or dangerous waste interim status technical standards for tank systems (i.e., secondary containment, integrity assessments, etc.) will not be mandated as a result of this action. However, any equipment modified or replaced will meet interim status standards. In evaluating closure options for single-shell tanks, contaminated soil, and ancillary equipment, Ecology and EPA will consider cost, technical practicability, and potential exposure to radiation."

This agreement allows the project to apply appropriate design and construction standards that are relevant to the retrieval and LDMM of 241-C-104 and that emphasize protection of human health and the environment. The following subsections identify the requirements framework that will govern the design and operation of the 241-C-104 waste retrieval system.

2.1 Hanford Federal Facility Agreement and Consent Order Requirements

Table 2-1 lists the milestones for the 241-C-104 waste retrieval demonstration. This document meets the submittal requirements identified by Milestone M-45-03-T04 of the *Hanford Federal Facility Agreement and Consent Order*.

Table 2-1. Hanford Federal Facility Agreement and Consent Order Milestones Applicable to 241-C-104.

Milestone	Description	Required Completion
M-45-00 LEAD AGENCY: ECOLOGY	COMPLETE CLOSURE OF ALL SINGLE SHELL TANK FARMS. CLOSURE WILL FOLLOW RETRIEVAL OF AS MUCH TANK WASTE AS TECHNICALLY POSSIBLE, WITH TANK WASTE RESIDUES NOT TO EXCEED 360 CUBIC FEET (CU. FT.) IN EACH OF THE 100 SERIES TANKS, 30 CU. FT. IN EACH OF THE 200 SERIES TANKS, OR THE LIMIT OF WASTE RETRIEVAL TECHNOLOGY CAPABILITY, WHICHEVER IS LESS. IF THE DOE BELIEVES THAT WASTE RETRIEVAL TO THESE LEVELS IS NOT POSSIBLE FOR A TANK, THEN DOE WILL SUBMIT A DETAILED EXPLANATION TO EPA AND ECOLOGY EXPLAINING WHY THESE LEVELS CANNOT BE ACHIEVED, AND SPECIFYING THE QUANTITIES OF WASTE THAT THE DOE PROPOSES TO LEAVE IN THE TANK. THE REQUEST WILL BE APPROVED OR DISAPPROVED BY EPA AND ECOLOGY ON A TANK-BY-TANK BASIS. PROCEDURES FOR MODIFYING THE RETRIEVAL CRITERIA LISTED ABOVE, AND FOR PROCESSING WAIVER REQUESTS ARE OUTLINED IN THE APPENDIX TO THIS CHANGE REQUEST. FOLLOWING COMPLETION OF RETRIEVAL, SIX OPERABLE UNITS (TANK FARMS), AS DESCRIBED IN APPENDIX C (200-BP-7, 200-PO-3, 200-RO-4, 200-TP-5, 200-TP-6, 200-UP-3), WILL BE REMEDIATED IN ACCORDANCE WITH THE APPROVED CLOSURE PLANS. FINAL CLOSURE OF THE OPERABLE UNITS (TANK FARMS) SHALL BE DEFINED AS REGULATORY APPROVAL OF COMPLETION OF CLOSURE ACTIONS AND COMMENCEMENT OF POST-CLOSURE ACTIONS. FOR THE PURPOSES OF THIS AGREEMENT ALL UNITS LOCATED WITHIN THE BOUNDARY OF EACH TANK FARM WILL BE CLOSED IN ACCORDANCE WITH WAC 173-303-610. THIS INCLUDES CONTAMINATED SOIL AND ANCILLARY EQUIPMENT THAT WERE PREVIOUSLY DESIGNATED AS RCRA PAST PRACTICE UNITS. ADOPTING THIS APPROACH WILL ENSURE EFFICIENT USE OF FUNDING AND WILL REDUCE POTENTIAL DUPLICATION OF EFFORT VIA APPLICATION OF DIFFERENT REGULATORY REQUIREMENTS: WAC 173-303-610 FOR CLOSURE OF THE TSD UNITS AND RCRA SECTION 3004(U) FOR REMEDIATION OF RCRA PAST PRACTICE UNITS. ALL PARTIES RECOGNIZE THAT THE RECLASSIFICATION OF PREVIOUSLY IDENTIFIED RCRA PAST PRACTICE UNITS TO ANCILLARY EQUIPMENT ASSOCIATED WITH THE TSD UNIT IS STRICTLY FOR APPLICATION OF A CONSISTENT CLOSURE APPROACH. UPGRADES TO PREVIOUSLY CLASSIFIED RCRA PAST PRACTICE UNITS TO ACHIEVE COMPLIANCE WITH RCRA OR DANGEROUS WASTE INTERIM STATUS TECHNICAL STANDARDS FOR TANK SYSTEMS (I.E., SECONDARY CONTAINMENT, INTEGRITY ASSESSMENTS, ETC.) WILL NOT BE MANDATED AS A RESULT OF THIS ACTION. HOWEVER, ANY EQUIPMENT MODIFIED OR REPLACED WILL MEET INTERIM STATUS STANDARDS. IN EVALUATING CLOSURE OPTIONS FOR SINGLE-SHELL TANKS, CONTAMINATED SOIL, AND ANCILLARY EQUIPMENT, ECOLOGY AND EPA WILL CONSIDER COST, TECHNICAL PRACTICABILITY, AND POTENTIAL EXPOSURE TO RADIATION. CLOSURE OF ALL UNITS WITHIN THE BOUNDARY OF A GIVEN TANK FARM WILL BE ADDRESSED IN A CLOSURE PLAN FOR THE SINGLE-SHELL TANKS. COMPLIANCE WITH THE WORK SCHEDULES SET FORTH IN THIS M-45	9/30/2024

Table 2-1. Hanford Federal Facility Agreement and Consent Order Milestones Applicable to 241-C-104.

Milestone	Description	Required Completion
	SERIES IS DEFINED AS THE PERFORMANCE OF SUFFICIENT WORK TO ASSURE WITH REASONABLE CERTAINTY THAT DOE WILL ACCOMPLISH SERIES M-45 MAJOR AND INTERIM MILESTONE REQUIREMENTS. NOTE: DOE HAS APPEALED THE ISSUE NOTED WITHIN THE PRECEDING SENTENCE TO THE WASHINGTON POLLUTION CONTROL HEARINGS BOARD. THE OUTCOME OF THIS APPEAL MAY AFFECT THIS M-45-00 LANGUAGE. DOE INTERNAL WORK SCHEDULES (E.G., DOE APPROVED SCHEDULE BASELINES) AND ASSOCIATED WORK DIRECTIVES AND AUTHORIZATIONS SHALL BE CONSISTENT WITH THE REQUIREMENTS OF THIS AGREEMENT. MODIFICATION OF DOE CONTRACTOR BASELINE(S) AND ISSUANCE OF ASSOCIATED DOE WORK DIRECTIVES AND/OR AUTHORIZATIONS THAT ARE NOT CONSISTENT WITH AGREEMENT REQUIREMENTS SHALL NOT BE FINALIZED PRIOR TO APPROVAL OF AN AGREEMENT CHANGE REQUEST SUBMITTED PURSUANT TO AGREEMENT ACTION PLAN SECTION 12.0	
M-45-03-T04	SUBMIT C-104 SLUDGE/HARD HEEL, CONFINED SLUICING AND ROBOTIC TECHNOLOGIES, WASTE RETRIEVAL DEMONSTRATION FUNCTIONS AND REQUIREMENTS DOCUMENT. THIS DOCUMENT WILL ESTABLISH DEMONSTRATION SYSTEM SPECIFICATIONS (INCLUDING LDMM SYSTEM SPECIFICATIONS) AND WILL ALSO INCLUDE A SCOPING LEVEL RETRIEVAL PERFORMANCE EVALUATION (RPE). THE FUNCTIONS AND REQUIREMENTS DOCUMENT AND ITS ASSOCIATED RPE SHALL PROVIDE ENVIRONMENTAL AND HUMAN HEALTH RISK EVALUATION DATA/INFORMATION ASSOCIATED WITH ESTIMATED WASTE VOLUMES TO BE RETRIEVED, THE MAXIMUM VOLUME WHICH COULD LEAK DURING RETRIEVAL, AND RISK FROM RESIDUAL WASTE. THIS DOCUMENT WILL DETAIL KNOWN AND ESTIMATED RADIONUCLIDE CONTAMINATION AND CONTAMINANT MIGRATION WITHIN THE VADOSE ZONE AS BASES OF CALCULATION. LDMM AND RPE DOCUMENTATION PROVIDED WILL BE ADEQUATE TO ALLOW ECOLOGY TO ASSESS THE ADEQUACY OF THE DEMONSTRATION SYSTEMS. THIS DOCUMENT WILL INCORPORATE LESSONS LEARNED, INCLUDING LDMM, RETRIEVAL, INSTRUMENTATION, AND OPERATIONAL EXPERIENCE FROM PREVIOUS DOE AND INDUSTRY RELATED RETRIEVAL PROJECTS. DOE WILL SUBMIT ITS C-104 LDMM STRATEGY AS PART OF THE FUNCTIONS AND REQUIREMENTS DOCUMENT, PRIOR TO INITIATION OF DESIGN. THIS DOCUMENT WILL BE SUBMITTED FOR ECOLOGY APPROVAL AS AN AGREEMENT PRIMARY DOCUMENT. THIS FUNCTIONS AND REQUIREMENTS DOCUMENT WILL BE TIMELY SUBMITTED SO THAT PROJECT CRITICAL PATH IS NOT AFFECTED, AND SO AS TO ALLOW ADEQUATE TIME FOR DOE AND ECOLOGY REVIEW, REVISION AND APPROVAL.	12/31/2001

Table 2-1. Hanford Federal Facility Agreement and consent Order Milestones Applicable to 241-C-104

M-45-03G	COMPLETE C-104 SLUDGE/HARD HEEL, CONFINED SLUICING AND ROBOTIC TECHNOLOGIES, WASTE RETRIEVAL COLD DEMONSTRATION. THIS FULL SCALE DEMONSTRATION WILL BE SUFFICIENT TO SUPPORT FINAL DESIGN AND TESTING OF ALL EQUIPMENT, INCLUDING THE LDMM APPROACH USED IN THE ACTUAL SYSTEM. THE DEMONSTRATION MUST ESTABLISH THE PERFORMANCE OF THE EQUIPMENT SPECIFIED IN THE FUNCTIONS AND REQUIREMENTS DOCUMENT. A LETTER REPORT WILL BE SUBMITTED TO ECOLOGY TO DOCUMENT THE RESULTS OF THE COLD DEMONSTRATION.	6/30/2004
M-45-03H	COMPLETE C-104 SLUDGE/HARD HEEL, CONFINED SLUICING AND ROBOTIC TECHNOLOGIES, WASTE RETRIEVAL DEMONSTRATION DESIGN (TO INCLUDE ALL PHYSICAL SYSTEMS INCLUDING DESIGN AND OPERATING STRATEGIES NECESSARY FOR LEAK DETECTION MONITORING AND MITIGATION (LDMM)). DESIGN WILL BE CONSIDERED COMPLETE WHEN 90% OF THE DESIGN HAS BEEN APPROVED FOR FABRICATION AND/OR CONSTRUCTION.	9/30/2004
M-45-03I	COMPLETE C-104 SLUDGE/HARD HEEL, CONFINED SLUICING AND ROBOTIC TECHNOLOGIES, WASTE RETRIEVAL DEMONSTRATION CONSTRUCTION (TO INCLUDE ALL PHYSICAL SYSTEMS INCLUDING THOSE NECESSARY FOR LEAK DETECTION MONITORING AND MITIGATION). CONSTRUCTION WILL BE CONSIDERED COMPLETE WHEN ALL PROCESS EQUIPMENT IS INSTALLED AND ACCEPTANCE TESTS ARE COMPLETED.	9/30/2006
M-45-03F	COMPLETE FULL SCALE SLUDGE/HARD HEEL, CONFINED SLUICING AND ROBOTIC TECHNOLOGIES, WASTE RETRIEVAL DEMONSTRATION AT TANK C-104. WASTE SHALL BE RETRIEVED TO THE DST SYSTEM TO THE LIMITS OF THE TECHNOLOGY (OR TECHNOLOGIES) SELECTED. SELECTED SLUDGE/HARD HEEL TECHNOLOGY (OR TECHNOLOGIES) MUST SEEK TO IMPROVE UPON THE PAST-PRACTICE SLUICING BASELINE IN THE AREAS OF EXPECTED RETRIEVAL EFFICIENCY, LEAK LOSS POTENTIAL, AND SUITABILITY FOR USE IN POTENTIALLY LEAKING TANKS. CONFINED SLUICING IS DEFINED AS THE LOCALIZED ADDITION AND RETRIEVAL OF LIQUIDS AND WASTE. THIS DEMONSTRATION SHALL ALSO INCLUDE THE INSTALLATION AND IMPLEMENTATION OF FULL SCALE LEAK DETECTION, MONITORING, AND MITIGATION (LDMM) TECHNOLOGIES. THE PARTIES RECOGNIZE AND AGREE THAT THIS ACTION IS FOR DEMONSTRATION AND INITIAL WASTE RETRIEVAL PURPOSES. COMPLETION OF THIS DEMONSTRATION SHALL BE BY APPROVAL OF DOE AND ECOLOGY. GOALS OF THIS DEMONSTRATION SHALL INCLUDE THE RETRIEVAL TO SAFE STORAGE OF APPROXIMATELY 89 KG OF PLUTONIUM WHICH REPRESENTS APPROXIMATELY 17% OF THE TOTAL PLUTONIUM INVENTORY WITHIN THE SST SYSTEM), AND 99% OF TANK CONTENTS BY VOLUME (PER DOE'S BEST-BASIS INVENTORY DATA OF 8/01/2000).	TBE (This milestone shall be established during the parties' M-45-00C negotiations.)

2.2 Regulatory Requirements

Table 2-2 identifies the State and Federal regulations (i.e., WAC and CFR, respectively) that apply to the retrieval of 241-C-104. These regulatory requirements are imposed on the design of the 241-C-104 waste retrieval system via the requirement statements in Section 4 of this document.

Table 2-2. State and Federal Regulations.

Document Number	Title
40 CFR Subchapter R, 2000	"Toxic Substances Control Act," *Code of Federal Regulations*, as amended
10 CFR 830	"Nuclear Safety," *Code of Federal Regulations*
10 CFR 835	"Occupational Radiation Protection," *Code of Federal Regulations*
29 CFR 1910	"Occupational Safety and Health Standards," *Code of Federal Regulations*, as amended
40 CFR 61	"National Emission Standards for Hazardous Air Pollutants," *Code of Federal Regulations*, as amended
40 CFR 265	"Interim Status Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities," *Code of Federal Regulations*, as amended
40 CFR 280	"Technical Standards and Corrective Action Requirements for Owners and Operations of Underground Storage Tanks," *Code of Federal Regulations*, as amended
WAC 173-303-640	"Dangerous Waste Regulations - Tank Systems," *Washington Administrative Code*, as amended.
WAC 173-400	"General Regulations for Air Pollution Sources," *Washington Administrative Code*, as amended.
WAC 173-460	"Controls for New Sources of Toxic Pollutants," *Washington Administrative Code*, as amended.
WAC-246-247	"Radiation Protection-Air Emissions," *Washington Administrative Code*, as amended.

3.0 TECHNICAL APPROACH TO DEVELOPING RISK-BASED RETRIEVAL REQUIREMENTS

This section summarizes the current integrated SST waste retrieval and LDMM risk-based requirements development strategy embodied in the *Hanford Federal Facility Agreement and Consent Order* M-45 series milestones. It discusses how the current strategy evolved from the initial strategy embodied in the 1994 *Hanford Federal Facility Agreement and Consent Order* M45 milestones. In addition, this section describes the approach that the DOE Office of River Protection (ORP) and Ecology have agreed to use to support interim retrieval decisions. The interim retrieval decisions are needed to demonstrate waste retrieval and LDMM technologies for waste retrieval from the 149 SSTs at the Hanford Site. Finally, lessons learned from other projects are presented.

3.1 Integrated SST Waste Retrieval and LDMM Risk-Based Strategy

The *Hanford Federal Facility Agreement and Consent Order* recognizes that waste retrieval from aging SSTs poses technical challenges including the potential for loss of waste to the environment. These challenges would require DOE to demonstrate alternative retrieval technologies and develop and test methods to detect, monitor, and mitigate potential leaks during waste retrieval. The near-term M-45 series of milestones through 2006 were established to provide a framework for implementation of near-term waste retrieval in an environmentally sound manner within the context of:

- A schedule for retrieval driven by the availability of space in DSTs to support interim storage of SST waste.
- Utilizing available space in DSTs as waste from the DSTs is transferred to waste treatment facilities.
- A phased approach to capture lessons learned for vadose zone, retrieval performance, and establishing new milestones.

DOE and Ecology recognized that SST waste retrieval poses risks associated with retrieving waste from aging tanks. There are limited proven retrieval technologies, limited LDMM technologies, and constraints imposed by radiological, chemical, physical and environmental conditions. To address these uncertainties *the Hanford Federal Facility Agreement and Consent Order* included milestones associated with development and demonstration of retrieval and LDMM technologies. Since 1994, DOE, in partnership with Ecology, has:

- Reviewed and assessed lessons-learned from retrieval and LDMM technologies deployed at other DOE sites (e.g., Oak Ridge and Savannah River Sites, see Appendix A),
- Assessed emerging waste retrieval and LDMM technologies (CHG, 2000a),
- Completed retrieval of waste from 241-C-106 to resolve safety issues,

- Modified the *Hanford Federal Facility Agreement and Consent Order* to initiate Corrective Actions for 8 of the 12 SST Farms to improve understanding of the nature and extent of soil and groundwater contamination resulting from past tank leaks and spills and to identify, if appropriate, interim actions to mitigate threats to human health and the environment posed by past tank leaks (*Hanford Federal Facility Agreement and Consent Order* Change Control Number M-45-98-03, [Ecology 1999]),
- Refined the strategy for implementation of LDMM to ensure integration of LDMM with retrieval systems and to establish of LDMM requirements based on protection of human health and the environment (CHG 2000a), and
- Developed a methodology for evaluating retrieval options on a tank-specific basis that will support interim decisions on the extent of waste retrieval and retrieval leak loss. The methods/decisions will not restrict final decisions associated with tank farm closure and/or corrective action under WAC 173-303, DOE Order 435.1, or DOE/RL-98-72 (See Section 3.2 below).

In 1998, DOE initiated a re-baselining of the SST retrieval project. The basis for the re-baselining, and the strategy adopted to implement the SST retrieval project, were documented in the SST Retrieval Program Mission Analysis Report (LMHC 1998). The focus of the re-baselining was to:

- Provide a technically defensible program plan that will result in deployment of retrieval and LDMM technologies capable of retrieving waste from SSTs containing varied waste forms and meeting tank-specific physical constraints,
- Comply with applicable regulatory requirements (e.g., *Hanford Federal Facility Agreement and Consent Order* interim waste retrieval and LDMM requirements),
- Accelerate reduction of potential risks to human health and the environment, and
- Enhance integration with the planning and scheduling for waste processing, which will free DST space to support SST waste transfers to DSTs.

In 1999 and 2000, following completion of the SST Mission Analysis Report, DOE initiated revision of its SST LDMM and retrieval strategy. The outcome of this effort is documented in the Single-Shell Tank Retrieval Sequence: Fiscal Year (FY) 2000 Update (CHG 2000b), the FY 2000 Progress Report On The Development of Waste Tank Leak Monitoring /Detection and Mitigation Activities In Support of M-45-08 (CHG 2000a), and the change package for the M-45 series milestones (DOE/Ecology 2000). Key features of the revised strategy include:

- Integration of LDMM with retrieval technology and requirements on a tank specific basis,
- Development of risk-based requirements for extent of waste retrieval (i.e., volume of residual waste) and potential retrieval leak loss, based on a screening level assessment of threats to human health, that serve as minimum performance requirements for design and operation of retrieval and LDMM systems,
- Demonstration technology deployments early in the SST retrieval program to provide a basis for selection of cost-effective, tank-specific retrieval and LDMM technologies, and

- Integration of retrieval activities with tank farm Corrective Action and tank farm closure to mitigate potential risks to human health and the environment (see Figure 3-1). It is recognized that the 241-C Tank Farm is not currently in RCRA Corrective Action. However, the figure is provided to illustrate the relationship between corrective action, retrieval, and closure programs.



Figure 3-1. Corrective Actions for Tank Farm Closure

In 2000, the *Hanford Federal Facility Agreement and Consent Order* was modified to reflect the updated strategy. The modifications reflect an agreement among the agencies to retrieve waste from fewer SSTs that contain more hazardous long-lived radioactive waste, instead of retrieving waste from 10 relatively empty SSTs, and to establish a risk-based strategy and initial actions necessary for DOE to demonstrate alternative SST waste retrieval technologies. The technologies are targeted to be suitable to use in suspect, leaking, and/or deteriorating/aging SSTs to minimize the potential for leak losses that can impact the environment, and to develop performance and cost data necessary for application to future retrieval actions. These initial retrievals also include development and demonstration of LDMM methods. In addition to demonstrating waste retrieval technologies, the initial actions will focus on SSTs that pose the greatest risk (i.e., highest contaminants of concern loading) to the environment and on utilizing available DST space.

The retrieval strategy is founded on methods for evaluating retrieval performance that were developed in response to an August 1996, MOU between DOE and Ecology. The agencies

concurred that DOE should demonstrate the analysis necessary to make decisions on a tank-by-tank basis regarding the interim retrieval goal of at least 99% of the waste volume from SSTs and to establish tank-by-tank retrieval leakage loss limits (Doe/EPA 1996). The RPE of one tank farm (241-AX) was used to identify methods to establish tank-by-tank performance measures associated with short- and long-term human health impacts, closure requirements, technology limitations, and cost (*Retrieval Performance Evaluation Methodolgy for the Ax-Tank Farm* [DOE/RL-98-72]).

The 241-AX Farm RPE established screening level performance measures that are drivers for decisions on leak loss limits and residual waste volume. This methodology and these performance measures are used in the 241-C Farm RPE, and include:

- **Long-Term Risk.** Long-term human health risks posed by mixed waste (hazardous and radioactive) resulting from past tank leaks, retrieval losses, and residual waste (i.e., waste left in the tank following retrieval) migrating through the soil to groundwater and reaching a human receptor located outside of the tank farm following closure of the tank farms (*Hanford Federal Facility Agreement and Consent Order* and State Dangerous Waste Regulations). Under this scenario the receptor uses groundwater for domestic purposes and other uses depending on the specific exposure scenario. This performance measure is sensitive to changes in the total waste inventory (i.e., past leaks, retrieval losses and residual waste) and thus drives limits on leak losses and residual waste. Leak losses and residual waste are dependent variables (i.e., as one increases the other must decrease to stay within a total inventory limit). The contaminants that most influence this performance measure tend to be highly mobile in the environment (e.g., nitrates, ^{99}Tc). Because no single exposure scenario for evaluating long-term risk has been established, the AX-Tank Farm RPE presented risk results for Native American, Residential Farmer, Industrial Worker, and Recreational Shoreline exposure.
- **Intruder Risk.** Human health risks posed by residual waste in the tank or ancillary equipment that pose health risks following intrusion into the waste site. Two aspects of intruder risk evaluated include the DOE Intruder Scenario and comparison against concentration limits (10 CFR 61). This performance measure is sensitive to changes in the residual waste inventory. The contaminants that most influence this performance measure tend to be less mobile in the environment (e.g., Cesium, Strontium, Plutonium).
- **Worker Risk.** Human health risks posed by past tank leaks, retrieval losses, and residual waste to remediation workers required to implement various retrieval and closure strategies. Worker risks evaluated include industrial accidents, routine radiological exposure, and accident conditions. Tank closure strategies evaluated included clean closure which involved excavation of contaminated soils and removal of the ancillary equipment, tank, and its residual waste to meet closure requirements under State Dangerous Waste Regulations (i.e., clean close the tank farm to a residential standard or remediate areas of concern within a tank farm to support either a modified or landfill closure of the tank farm). This performance measure is sensitive to changes in the residual waste and retrieval loss inventories and tends to be most influenced by contaminants that are less mobile in the environment (e.g., Cesium, Strontium, Plutonium).

Figure 3-2 represents the concepts for application of the long-term and waste site intruder screening level performance measures. The curve in Figure 3.2 is applicable only for 241-C-104 and assumes a single retrieval campaign. Past tank leaks are accommodated in the risk allocation method as discussed in the RPE (Appendix B). The minimum performance requirements for waste retrieval leak loss and residual waste limits should fall somewhere under the 10^{-5} Incremental Lifetime Cancer Risk (ILCR) curve shown in Figure 3-2. The 10^{-5} curve is based on the risk allocation methodology discussed in Appendix B. The 10^{-5} curve intersects the vertical Y-axis at the maximum leak loss limit allowed ("Retrieval Release Criterion [Gallons]") and the horizontal X-axis at the maximum residual waste allowed ("Residual Waste [Gallons]"). These are the maximum upper limits which will bound the design criteria for the LDMM and retrieval systems minimum performance. As long as the combined risk remains at or below the curve, the retrieval activity can go forward to completion. Barring any other considerations, if the residual waste is less than the maximum (to the left of the intersection of the curve with the X-axis) and the retrieval leak loss or release is less than the maximum (below the intersection of the curve with the Y-axis), then the risk-based approach is satisfied. While the anticipated results will be well below either of these limits, there may be extreme cases (i.e., at other tanks) where either limit may be below what is achievable with available technology. If readily deployable and well-understood LDMM and retrieval technologies hold the combined risk below the curve, then risk and cost are held at reasonable levels, regardless of the calculated health-based design criteria. In any case, the goal of the 241-C-104 retrieval demonstration project is to retrieve at least 99% of the tank contents by volume or the maximum possible to the "the limit of waste retrieval technology capability" (Table 2-1, Milestones M-45-00 and M-45-03F).



Figure 3-2. 241-C-104 Retrieval Release Criterion vs. Residual Waste

3.2 Development and Use of Performance Requirements Through the RPE

Risk-based goals for SST waste retrieval have been incorporated into the *Hanford Federal Facility Agreement and Consent Order* through the change package for the M-45 series milestones (DOE/Ecology 2000). Milestone M-45-03-T04 for 241-C-104 (Table 2-1) requires a scoping level RPE as part of this F&R document.

The RPE process was developed to support waste retrieval and closure decisions using a systems approach that considers contributions from multiple sources (i.e., past leaks, potential retrieval leakage, and residual waste) across a number of performance measures. The RPE methodology is an iterative process that will be applied before waste retrieval to help develop criteria for the extent of retrieval leak losses and residual waste and then after retrieval to evaluate performance measures using actual retrieval leak loss and residual waste data. The RPE process for the 241-C SST Farm follows these steps:

1. A scoping-level RPE defines the tank farm risk on a tank-by-tank basis with the 241-C Farm RPE starting with 241-C-104. The scoping-level RPE focusing on 241-C-104 establishes the minimum retrieval and LDMM system performance requirements necessary to stay within risk-based limits. The risk allocation methodology is described in Appendix B and includes calculating a risk budget for 241-C-104 by starting at a 10^{-5} ILCR, subtracting the risk from past leaks, and allocating risk to 241-C-104 based on the volume of waste in 241-C-104 compared to the waste volume in the 241-C Farm tanks. Ancillary equipment contamination and existing waste in the soil due to past leaks is not included in this source term. These tank-specific performance requirements are given in terms of the maximum leak loss during retrieval and maximum residual waste after retrieval for 241-C-104.
2. After the 241-C-104 waste retrieval demonstration is complete, the tank farm RPE is updated to reflect the actual residual waste volume and estimated retrieval leak loss, if any. The risk associated with the remainder of the farm tanks is recalculated.
3. Steps one and two are repeated for each tank to be retrieved in the tank farm with the final RPE amended to include tank farm specific performance data a well as information regarding the cumulative impacts of the post-closure tank farm with other 200 Area waste sites as the tank farm closure RPE.

The current application of the RPE focuses on developing retrieval leak loss and residual waste criteria for 241-C-104 within the 241-C Farm. The impact analysis conducted for each of the retrieval cases includes assessing the screening performance measures from Section 3.1 (used to establish limits), as well as considering additional impacts, as listed below.

- Short-term human health risk – Risks to workers and the public from chemical and radiological exposures that are expected to occur during routine remedial actions (e.g., waste retrieval) or that could result form postulated accidents, and injuries and fatalities resulting from industrial type accidents.
- Long-term human health risk – Human health risks to future Site users (at the current tank farm boundary) that would occur after completing waste retrieval and implementing closure (post remediation). Long-term human health risk analysis involves evaluating health risks

resulting from exposure to contaminated groundwater. Contaminants of concern to long-term human health risks are those that are persistent and mobile in the environment. Long-term human health risks are evaluated over a 10,000-year period of interest based on the lifestyle of a residential farmer and an industrial worker. Since this analysis is being conducted to support interim tank farm decisions on the waste retrieval from one tank and not final tank farm closure decisions, the risk assessment is limited to evaluating risk from 241-C Farm only. The risk assessment does not address risks to down-river future populations or the cumulative risks from other SSTs and waste sites outside the tank farm.

- Groundwater quality – Impacts on groundwater quality resulting from contaminant release and migration to the groundwater are assessed and compared to regulatory standards. Groundwater quality impacts are evaluated at the tank farm boundary.
- Compliance assessment – The applicable and appropriate regulatory requirements have been identified including areas where open issues and specific quantitative performance measures exist.
- Technical constraints – For each of the cases an assessment of the technical constraints (e.g., effectiveness, implementability) is provided.

The best available data for each component of the tank farm system and the tanks of interest are used to provide a deterministic calculation for each performance measure. Where data were unavailable or highly uncertain, assumptions were developed to complete the analysis. These assumptions were based on engineering judgment following a review of available data or information from other Hanford Site, DOE complex, or non-DOE remediation programs. Application of the RPE methodology to the evaluation of 241-C-104, and the 241-C Farm included the following:

- Developing a conceptual model of the tank and tank farm system (e.g., the components of the tank farm, sources of contamination, engineered systems, and the natural environment) to analyze the potential implication of SST waste retrieval.
- Identifying retrieval cases that span a reasonable range of residual waste volume and retrieval leakage volumes that will be used to develop risk versus volume relationships for both residual waste and retrieval leakage.
- Performing a risk assessment to assess short- and long-term human health risks to human receptors.
- Comparing performance of the total system (i.e., the combination of all known tank farm contamination sources) to requirements established by Federal and State regulations, the *Hanford Federal Facility Agreement and Consent Order*, and stakeholder and Tribal Nation values.
- Evaluating the ability of static (measurements while pumping is shut down) and dynamic (measurements during pumping) in-tank leak detection methods to compare with risk-based leak limits.
- Evaluating the ability of dry well and groundwater monitoring as either leak detection methods or to augment the in-tank leak detection methods.

The RPE for the 241-C Farm is provided as Appendix B to this report. Figure 3-2 shows three curves, depicting the risks from residual waste and waste leakage to a future onsite worker (Industrial Worker), a farmer (Residential Farmer), and an inadvertent intruder plotted from RPE data.

Based on the RPE, the most conservative release criterion with 360 ft^3 of residual waste is taken from the curve presented in Figure 3-2 for the residential farmer risk scenario. The residential farmer scenario is a conservative exposure scenario because it contains multiple exposure pathways. It was chosen due to its conservatism and due to the uncertainties associated with the current information available regarding past tank leaks and spills, the in-tank inventories, postulated tank leaks, and cumulative inventories from other waste sites. The long-term risk results do not take into account cumulative impacts from other tank farms and closure sites. Non-tank farm source term contributions, which are additive to the 241-C Farm contribution, have not been quantified. Based on this, the residential farmer scenario is a reasonable approach for the scope of this document. Cumulative source term impacts from non-tank farm sources will be taken into account in the closure work plan.

The upper leak detection limit for the farmer scenario "*Farmer (ILCR* $\leq 10^{-5}$*)*" in Figure 3-2 is approximately 36,000 gallons. The target performance criterion for the leak detection system shall be 36,000 gallons or less. The best deployable leak detection technology currently available may not be able to reliably detect a leak of this size in a timely manner. However, different LDMM technologies are being tested by the Tank Focus Area Program, and eventually a new LDMM technology may be found that can deliver enhanced performance compared to currently deployable technologies. If a new technology is available and deployable within the context of the 241-C-104 retrieval demonstration design and construction schedule then it will be implemented. See Section 5 for further discussion of the limits of the current LDMM technologies. The 36,000-gallon leak volume is based on the Residential Farmer being located at the tank farm boundary. This is a conservative assumption. If the point of compliance location for the Residential Farmer were located away from this boundary, an updated RPE would increase the leak volume limit.

The uncertainties that contribute to the dynamic and static testing ranges include:

- Physical and chemical properties of the waste, including dissolution characteristics and solution densities, waste layering within 241-C-104, and hydraulic conductivity of the sludge (the density of the waste can change with temperature, dilution and mixing with other wastes),
- Time to reach equilibrium during static testing (retrieval is halted and any leaks continue unabated), and
- Ability to obtain a free liquid surface and maintain a constant liquid surface during static testing (confined sluicing/robotic retrieval technology minimizes the free liquid surface in the tank making it much more difficult to form a free liquid surface in a location convenient to instrumentation).

3.3 Use of Lessons Learned in Supporting Selection and Implementation of Retrieval and LDMM Technologies

DOE requires that lessons learned from previous activities will be documented and used in the design considerations for similar activities. This applies to tank waste retrieval and LDMM. Lessons learned from other similar projects provide valuable experience that is incorporated into the design and operation of the retrieval and LDMM system. Lessons learned do not form the functions and requirements for the retrieval and LDMM system design and execution. However, they do influence, based on past experience and application, how the functions and requirements are achieved. During the various project phases (i.e., initial engineering development, preliminary design, detailed design, construction and operations), lessons learned shall be identified and evaluated for application relevant to the 241-C-104 retrieval demonstration. This experience will guide the design team in the selection of the best retrieval and LDMM technologies. Lessons learned have shown that waste retrieval from any tank has not caused the tank to leak, including tanks in comparable or worse condition than 241-C-104.

The lessons learned evaluation for SST 241-C-104 focuses on gathering information and experience that is categorized as follows:

- Operational effectiveness of retrieval systems and approaches
- Retrieval system and demonstration technology effectiveness
- Leak detection systems used and developments in leak detection technologies
- Leak monitoring approaches and systems used and developments in leak monitoring technologies
- Leak mitigation approaches and systems used and developments in leak mitigation technologies

Appendix A contains a description of the process used to gather lessons learned, the relevant lessons learned that apply to this project, and the bibliography of sources used in gathering the lessons learned information. DOE will incorporate these lessons learned during the design and operation of the 241-C-104 waste retrieval system. The best available and deployable LDMM technology will be used for 241-C-104 retrieval.

Lessons learned has already provided some design and operational features that are being given consideration for implementation in the retrieval demonstration system for 241-C-104. These features are highlighted in Appendix A. Key considerations include, but are not limited to:

- Place more than one camera in the tank for maximum visibility during retrieval.
- Once retrieval has begun, do not stop for any but critical safety reasons.
- Initiate static leak detection testing only if retrieval has stopped for some other reason.

4.0 FUNCTIONS & REQUIREMENTS

The functions and requirements included in this document are derived from the need to satisfy the *Hanford Federal Facility Agreement and Consent Order* Milestone requirements to retrieve as much of the current 241-C-104 waste inventory as technically possible with a goal of retrieving to safe storage approximately 89 kilograms of Plutonium and 99% of the 241-C-104 contents by volume (per the DOE BBI data of 8/1/00) while maintaining a tank and waste retrieval system that safely isolates the waste from the workers, the environment, and the public. Some of these requirements are derived from regulatory documents such as the CFRs, and the resulting certification in the WAC while others are based on the design limitations of 241-C-104 and the DST receiver tank. The functions and requirements identified below are focused on appropriately driving the design of the 241-C-104 waste retrieval system so that the aforementioned needs are met.

4.1 Control 241-C-104 Structure and Waste Temperature

The 241-C-104 waste retrieval system shall control the 241-C-104 structure and waste temperature to within the following specified design limits to prevent structural damage to the tank:

Temperatures:

- Maximum 149 °C (300 °F) for waste
- Maximum 121 °C (250 °F) for dome
- Maximum change of 11 °C (20 °F) per day

[Basis: OSD-T-151-00013 (CHG 2000c)]

4.2 Control 241-C-104 Waste Level

The 241-C-104 waste retrieval system shall control the waste level in 241-C-104 to prevent waste overflow and limit the hydrostatic head-induced stresses in the tank and provide for leak detection monitoring. The 241-C-104 waste retrieval system shall prevent the waste level in 241-C-104 from exceeding 4.7 m (185 inch). The waste retrieval system shall limit the hydrostatic forces on 241-C-104 such that the hydrostatic forces do not exceed the force equivalent to 185 inch of waste with a specific gravity (SpG) of less than or equal to 2.0.

[Basis: HNF-4712, Rev. 0 (LMHC 1999)]

4.3 Control 241-C-104 Vapor Space Pressure

The 241-C-104 waste retrieval system shall control the vapor space pressure in 241-C-104 to within the following specified design limits to prevent structural damage to the tank:

- If waste level ≥ 38.1 cm (15 in.),

  Then -38.1 cm (15 in.) w.g. ≤ vapor space pressure ≤ 1.5 m (60 in.) w.g.

- If waste level < 38.1 cm (15 in.),

  Then negative (waste level) ≤ vapor space pressure ≤ 1.5 m (60 in.) w.g.

  (Note: Operational limits on in-tank vapor space pressure will be established as part of final design. If active ventilation is required for 241-C-104 during waste retrieval, then it is expected that a negative vapor space pressure with respect to atmosphere will be required at all times during retrieval system operation, as this is the preferred method for verifying that ventilation is operable and ensures confinement.)

  [Basis: HNF-4712 (LMHC 1999)]

4.4 Control 241-C-104 Gaseous Discharges

The 241-C-104 waste retrieval system shall control the vapor space pressure in 241-C-104 and filter the air exhaust to restrict emissions to the environment in accordance with WAC 173-400 and WAC 173-460 (non radioactive airborne emission limits); and 40 CFR 61 and WAC 246-247 (radioactive airborne emission limits).

[Basis: RPP-6665 (CHG 2000f)]

4.5 Remove Waste from 241-C-104

The 241-C-104 waste retrieval system shall be capable of removing (i.e., retrieving and transferring waste to the DST System) as much of the 241-C-104 waste inventory (see DOE BBI data of 8/01/2000 (TWINS Website 2000)) as technically feasible with a target goal of removing 99% of the tank contents by volume. The demonstration will be considered complete when the retrieval technology is no longer recovering waste or the residual waste in 241-C-104 is less than 2,700 gallons. Recovery limits will be documented. Retrieval system design shall be capable of retrieving the waste within a maximum of 108 days.

[Basis: DOE/ECOLOGY 2000 (Milestone M-45-03F)]

4.6 Control and Monitor the 241-C-104 Waste Removal Process

The 241-C-104 waste retrieval system shall monitor and control the process parameters for retrieving waste from 241-C-104. This includes the detection and monitoring of 241-C-104 leaks during waste removal as well as the controlling and monitoring of waste removal process parameters. Provisions shall be made to sample waste during retrieval operations.

[Basis: DOE/Ecology 2000 (Milestone M-45-03F)]

4.6.1 Detect Leaks During 241-C-104 Waste Removal

The 241-C-104 waste retrieval system shall be capable of detecting liquid waste releases from 241-C-104 during all waste removal operations.

- The system shall be designed to detect a cumulative leak loss during the retrieval campaign of 19,000 gallons.

  [Basis: As discussed in Section 3.2, the RPE establishes a value of 36,000 gallons for the risk-based maximum leak loss that would result in human health impacts. DOE will use best available technology economically achievable (BATEA) to develop a leak detection capability based on 19,000 gallons for this application.]

- Probability of Detection: The 241-C-104 waste retrieval system shall have a probability of leak detection of greater than 95%.

  [Basis: 40 CFR 280]

- Probability of False Alarm: The 241-C-104 waste retrieval system shall have a probability of false alarm less than or equal to 5%.

  [Basis: 40 CFR 280]

4.6.2 Monitor Leaks From 241-C-104 During Waste Removal

The 241-C-104 waste retrieval system shall quantify liquid waste release volumes from 241-C-104 if a release is detected during waste retrieval operations. The data shall be collected, in the event of a leak, to support a post-retrieval RPE, which will be used to address retrieval of the next C-Farm tank. Data collected will address estimates of the volume and composition of leaked material, as well as the residual waste in the tank.

[Basis: Section 3.2]

4.6.3 Control And Monitor 241-C-104 Waste Retrieval

The 241-C-104 waste retrieval system shall monitor and control the process and equipment parameters for retrieving waste from 241-C-104. Waste removal process parameters (e.g., waste transfer line pressures, flow rates, waste densities) and equipment parameters (e.g., transfer pump speed and motor amperage) shall be monitored for safe and effective operation of the 241-C-104 waste retrieval system.

[Basis: good engineering practice]

4.7 Measure and Estimate Residual Waste in 241-C-104

The 241-C-104 waste retrieval system shall measure and estimate the residual waste in 241-C-104 to verify that the target retrieval goals have been met (see Section 4.5). The 241-C-104 waste retrieval system shall be capable of measuring and estimating residual waste on the walls of the tank, on and under the stiffening rings of the tank, on exterior surfaces of in-tank debris, hardware and components, and on the bottom of the tank. Techniques may include video surveillance and topographic mapping.

[Basis: DOE/Ecology 2000 (Milestone M-45-03F)]

4.8 Waste Minimization

The 241-C-104 waste retrieval system shall minimize waste generation to the greatest extent possible, e.g., transfer DST System supernatant liquids to 241-C-104 for confined sluicing purposes during retrieval and use 241-C-106 for drain-back of flush water during and after sluicing.

4.9 Mitigate Leaks During 241-C-104 Waste Retrieval Process

The 241-C-104 waste retrieval system shall mitigate leaks as the primary means of minimizing environmental impact caused by releases during retrieval of SST waste. If a leak occurs, the release shall be evaluated according to the RPE and the appropriate actions implemented. As the primary mitigation means, the retrieval system will minimize the amount of liquid introduced into the tank. In addition, the retrieval pump shall be designed to allow continuous pumping for a sufficient amount of time (to be determined during design) to remove all pumpable liquids from 241-C-104.

[Basis: DOE/Ecology 2000 (Milestone M-45-03F)]

4.10 Nuclear Safety

The 241-C-104 waste retrieval system shall be designed to protect workers, the public, the environment, and equipment from exposure to tank radioactive waste during retrieval as set forth in 10 CFR 830 and 10 CFR 835.

[Basis: 10 CFR 830 and 10 CFR 835]

4.11 DST Design Limits

The 241-C-104 waste retrieval system shall not adversely affect the function of the DST System or exceed the DST Design and operational limits. The DST design and operational limits are as follows:

4.11.1 DST Waste Temperature.

The DST waste temperature shall not exceed:

- 195°F in all levels of the waste, or
- 195°F in the top 15 feet of waste and 215°F below 15 feet.

[Basis: HNF-SD-WM-TSR-006 (CHG 2000b)]

4.11.2 DST Pressure Limits

The 241-C-104 waste retrieval system shall not cause the following internal DST pressure limits to be exceeded:

Primary Tanks:

- -15.2 cm (6 in) w.g. ≤ vapor space pressure ≤ -0.76 cm (0.3 inch) w.g. during normal operating conditions and ≤ 0 during required maintenance or off-normal conditions (AN, AW, AY, AZ farms)

- -24.1 cm (9.5 in) w.g. ≤ vapor space pressure ≤ -0.76 cm (0.3 inch) w.g. during normal operating conditions and ≤ 0 during required maintenance or off-normal conditions (AP farm)

[Basis: HNF-3350 (CHG 2000d)]

4.11.3 DST Hydrostatic Load Limits

The 241-C-104 waste retrieval system shall not cause the internal DST hydrostatic loads limits specified in Table 4-1 to be exceeded.

Table 4-1. Existing Double-Shell Tank Hydrostatic Load Limits

Tank Farm	Hydrostatic Load
AN, AW	Maximum hydrostatic load as exerted by 4410 m^3 (1.16 Mgal) of fluid @ 1.7 SpG and a depth of 10.7 m (422 inch)
AP	Maximum hydrostatic load as exerted by 4410 m^3 (1.16 Mgal) of fluid @ 2.0 SpG and a depth of 10.7 m (422 inch)
AY, AZ	Maximum hydrostatic load as exerted by 3790 m^3 (0.998 Mgal) of fluid @ 1.22 SpG. and a depth of 9.25 m (364 inch)

[Basis: HNF-3350 (CHG2000d)]

4.12 241-C-104 Waste Retrieval System Design

The 241-C-104 waste retrieval system new components shall be designed to ensure proper structural strength, compatibility with the waste and protection against corrosion in accordance with requirements of 40 CFR 265.192 and WAC 173-303-640(3).

[Basis: RPP-6665 (CHG 2000f)]

The retrieval system design shall be constructed of modular and easily replaceable subsystem components.

[Basis DOE 430.1A]

The retrieval system shall be designed for reuse.

[Basis DOE 430.1A]

4.13 Occupational Safety and Health

The 241-C-104 waste retrieval system shall incorporate design features that comply with the requirements of 29 CFR 1910.

[Basis: 29 CFR 1910]

4.14 SST and DST Dome Loading

The 241-C-104 waste retrieval system shall not exceed the maximum dome loading on existing SSTs and DSTs specified in HNF-IP-1266, 5.16, Rev. 3a (LMHC 2000a).

[Basis: HNF-SD-WM-SAR-067 (CHG 2001a)]

4.15 Prohibited Materials

Materials that are restricted or prohibited from use in manufacturing and construction under regulations promulgated pursuant to 40 CFR Subchapter R, shall not be used in the design of the 241-C-104 waste retrieval system.

[Basis: 40 CFR Subchapter R]

4.16 Waste Retrieval System Secondary Containment and Leak Detection

The 241-C-104 waste retrieval system shall incorporate in new components secondary containment and leak-detection design features in accordance with 40 CFR 265.193 and WAC 173-303-640 (4).

[Basis: RPP-6665, (CHG 2000f)]

4.17 Waste Retrieval System Deactivation and Decontamination

The 241-C-104 waste retrieval system equipment deactivation shall be compatible with decontamination, reuse and/or disposal requirements.

[Basis: DOE G 430.1-3]

5.0 LDMM AND RETRIEVAL STRATEGY

This section of the document describes the LDMM and retrieval strategy for the 241-C-104 demonstration retrieval system, and presents a preliminary design description of the integrated retrieval and LDMM system. The functions and requirements established in Section 4.0 of this document will govern the design and development of the integrated system. However, the progression of design, development, and testing may demonstrate that adequate technologies do not exist to meet all requirements established by this document. Under these circumstances, BATEA will be employed, along with the change control process established in Section 6.0 of this document, to meet the demonstration goals of the *Hanford Federal Facility Agreement and Consent Order* Milestone M-45-03C.

The 241-C-104 demonstration retrieval release protection strategy is based on the "Proposed Strategy for Leak Detection, Monitoring, and Mitigation During Hanford Single-Shell Tank Waste Retrieval" and concepts first presented in 1996 and updated in 1999 and 2000 (WHC 1996). The integrated LDMM and retrieval strategy uses the risk-based strategy presented in Section 3.2 of this document to define a minimum leak detection requirement. By also adopting risk-based release response criteria, the LDMM/Retrieval strategy uses quantitative decision criteria for making appropriate operational responses if and when releases are detected.

5.1 Integrated Strategy for LDMM and Retrieval

A goal of this document is to develop and define an LDMM strategy for the SST 241-C-104 waste retrieval demonstration system that meets requirements specified in the M-45 series of milestones (DOE/Ecology 2000). The purpose of the LDMM strategy is to ensure that the demonstration waste retrieval system:

- Minimizes hazardous waste releases to the environment,
- Complies with applicable regulations and requirements,
- Is technically practicable and defensible, and
- Meets the programmatic needs of DOE ORP.

Leak detection, monitoring, and mitigation definitions were established in RPP-7012 (CHG 2000a):

- **Leak Detection:** technologies, methods, or systems used to detect a leak.

- **Leak Monitoring**: technologies, methods, or systems used to quantify liquid waste release volumes from a SST, if a release is detected during waste retrieval operations.

- **Leak Mitigation**: technologies, methods, or systems that can reduce a leak, or reduce the environmental impact of a leak.

Figure 5-1 illustrates the three elements necessary for a release of liquid waste from a tank to occur. If there are no leak paths in the tank (i.e., holes, pits or cracks), then by definition there is no possibility of a leak. If, however, there are one or more leak paths in the tank, the volume of liquid released can be reduced by controlling the volume of free liquid or the hydraulic head of the liquid. If any of the legs of the triangle are severed, then no leak can occur.



Figure 5-1. Leak Minimization Triangle

The environmental and programmatic risks posed by different retrieval technologies, tanks, and tank constituents vary significantly. To develop and implement a consistent and reasonable LDMM design concept, a risk-based approach is used to establish quantitative performance requirements. When integrated with a retrieval technology, the risk-based approach establishes leak detection limits as a function of potential retrieval leak loss volume and residual waste remaining in the tank following completion of retrieval activities.

The LDMM strategy for 241-C-104 is intended to be a combined approach, using leak detection, leak monitoring, and leak mitigation to reduce the risk to human health and the environment from retrieval leak loss. However, leak detection and leak monitoring using the currently best available technology require a free liquid surface within the tank to accurately measure liquid volumes. The retrieval technology selected for the 241-C-104 demonstration is designed to minimize the liquid volume and does not provide a free surface. The demonstration retrieval system for 241-C-104 relies on the principles presented in Figure 5-1 and:

- Minimizes the amount of liquid required for retrieval,
- Reduces the liquid volume in the tank, and
- Incorporates a retrieval strategy that reduces the free liquid surface and hydraulic head.

The retrieval and LDMM strategy relies on minimizing the retrieval duration to reduce the overall risk to human health and the environment. In addition to using the best proven and available technology for leak detection and leak monitoring, leak mitigation is strengthened by this reduction in the retrieval duration, which reduces the time available for leakage to occur.

The leak mitigation strategy (i.e., reduction of leak loss potential) will use the following techniques for protection of human health and the environment:

1. Minimize liquid in tank - Leak mitigation will be accomplished by minimizing the liquid inventory in the retrieval tank to limit the volume of waste that could leak in the event that a leak developed.
2. Use retrieval strategy -The system shall be operated in such a way that it can pump from the lowest achievable level in the tank if a leak should occur. This is a mitigation activity because it allows removal of the greatest amount of liquid from the tank in the event of a leak. The result is that less liquid would be lost.
3. Minimize retrieval campaign duration - The campaign duration shall be minimized to the extent possible to reduce the time available for an undetected leak to contaminate the soil column. (A shorter time frame further limits the volume of waste that can leak.) Operating the system as continuously as is reasonable and minimizing the frequency of static leak testing will accomplish this.
4. Risk evaluation - If a leak occurs, the risk (cancer risk to the exposed individual) shall be evaluated from the anticipated leak volume, the residual waste in the tank, and the impact of continuing or terminating retrieval operations. The options for continuing/ending operations will be weighed and the one presenting the lowest risk approach will be followed.

5.1.1 Leak Detection

The LDMM strategy focuses heavily on mitigation of the potential for and consequences of a leak and use of accepted and available methods of leak detection. These accepted and available methods include monitoring liquid and waste inventories while waste is actively being retrieved (i.e., dynamic test) and when operations are temporarily suspended (i.e., static test).

Work documented over much of the past decade shows that there are many possible methods to detect leaks in underground storage tanks. However, there are a limited number of methods that can be readily implemented for the SSTs. In 1998, a review of previous LDMM investigations and new information regarding LDMM technologies applicable to SST retrieval recommended the use of in-tank volumetric methods similar to the EPA approved methods used on underground petroleum tanks and external methods for leak detection. In 1999, an update of the SST retrieval LDMM strategy repeated these recommendations. These recommendations are based on tanks with a free liquid surface. A review of recent waste retrieval projects indicates that internal monitoring of liquid inventories is the most commonly used technology applicable to retrieval from 241-C-104 (See Appendix A). The approved EPA methods for leak detection where a free liquid surface exists are:

Volumetric Inventory Balance (Dynamic)

Akin to the mass balance technology, the volumetric inventory balance method uses level instruments in the retrieval and receiver tanks along with flow meters to continuously balance the flow in and flow out of the retrieval tank. This method is similar to Statistical Inventory Reconciliation employed by the petroleum industry in distribution systems like gas stations. It is important to note that this technique has not been evaluated for SSTs and the complexities of waste solubility and evaporation combined with the scale difference between a local gas station tank and a 75-feet-diameter SST are significant. The advantage of this technology is that it provides a continuous online measurement. This technique will be sensitive to a number of environmental and operational interferences, and require compensation for those interferences to achieve acceptable performance levels. Based upon the 241-C-106 retrieval, some of the influences, such as uncondensed evaporation, may be beyond a reasonable compensation effort. Evaluation of this technique for SST retrieval may show that it will not be useful.

Volumetric (Static)

This technology is used extensively in industry leak detection. Volumetric methods measure the liquid surface and convert the level data to volume data from the known tank parameters. Leak detection is accomplished by calculating the rate of volume change over time and comparing this rate to a pre-determined "leak detection threshold" to determine whether the tank has an inflow, an outflow, or that the tank is "tight." Differential pressure measurements are one type of sensor used by the DOE to measure liquid level and conduct leak detection tests. This method measures change in depth by measuring the change in the hydrostatic head above a pressure sensing port. Direct level-sensing instrumentation such as the ENRAF-Nonius™ (ENRAF™) and Food Instrument Corporation™ (FIC™) gauges are currently used in SSTs with a continuous liquid surface and are well suited for the volumetric method in tanks with a measurable air-liquid interface.

In-tank volumetric technologies, which can include adaptation of elements of the mass-based technology, were recommended for leak detection because of the advantages they have over other technologies. These advantages include:

- Deployment readiness,
- Technology maturity,
- Accuracy,
- Ability to evaluate system performance,
- Life cycle cost, and
- Successful application in industry and at other DOE sites.

The performance data for leak detection with volumetric systems are based on data obtained in tanks with a free liquid surface. The ability of these methods of leak detection to accurately determine the presence of a sufficiently small leak has not been determined without a liquid surface.

Understanding the performance of the leak detection method is important. It determines whether risk-based leak detection requirements are met, and how to successfully meet them (e.g., number of tests to be conducted or combined, number of in-tank parameters measured, and frequency of testing). The performance of each leak detection method or combination of methods will be determined in terms of the Probability of Detection and Probability of False Alarm expressed as a volume or volume rate using methods similar to American Society of Testing and Materials (ASTM) and EPA standard test procedures.

The 241-C-104 RPE establishes a maximum allowable retrieval leak volume of 36,000 gallons, based on the Farmer Scenario. The Farmer Scenario represents the most conservative leak loss scenario for ILCR. This leak detection objective is based on a retrieval goal of at least 99% of the waste in the tank by volume, or retrieval to a residual waste of approximately 2,700 gallons (360 ft^3). Based on industry experience for large volume tanks, at the most extreme estimate (lowest probability of succeeding), and with the presence of a free liquid surface, static testing has a projected capability to detect as small as a 1,540 gallon leak over the retrieval campaign. In contrast dynamic leak testing has the capability, at the most extreme estimate (lowest probability of succeeding) of detecting 15,400 gallons over the retrieval campaign. However, the 241-C-104 demonstration retrieval technology will not produce a free liquid surface. For the purpose of risk reduction, the liquid inventory will not be increased solely for improved detection capabilities. The increased liquid inventory required to produce a free liquid surface imposes a greater potential leak volume and hydraulic head and is contrary to the strategy of mitigating the risks associated with a release event.

In the absence of a uniform free liquid surface and including other uncertainties, the static leak detection performance is more likely to be approximately 19,000 gallons over the retrieval duration, or a full order of magnitude higher than for the free liquid surface case. Although dynamic leak detect methods are typically less precise than static methods, without the presence of a free liquid surface dynamic methods for leak detection are consistent with static methods. The 19,000 gallons limit for static detection and the 15,400 gallon limit for dynamic leak detection is less than the established 36,000 gallon leak loss limit. The circumstances and uncertainties that force the system toward a less accurate leak detection include:

- Lack of a uniform free liquid surface,
- Potential for increased false alarms,
- Uncertainties associated with the tank physics,
- Uncertainty of the waste characterization data,
- Uncertainty of waste pore volume and capillary height,
- Uncertainty of soluble to non-soluble waste retrieval rates, and
- Uncertainty of interstitial liquid movement.

The retrieval demonstration for 241-C-104 is expected to require from four weeks to three months to complete. Table 5-1 provides calculated total leak volumes for various leak rates and retrieval duration. For example, if an undetected leak of 5.0 gallon per hour (gal/hr) were to occur at the beginning of a 4-week-long retrieval campaign, the table shows that 3,360 gallons of liquid would be released during the 4-week period.

Leak Rate (gal/hr)	1 wk (gal)	2 wk (gal)	4 wk (gal)	6 wk (gal)	12 wk (gal)	24 wk (gal)
0.5	84	168	336	504	1,008	2,016
1.0	168	336	672	1,008	2,016	4,032
2.0	336	672	1,344	2,016	4,032	8,064
5.0	840	1,680	3,360	5,040	10,080	20,160
10.0	1,680	3,360	6,720	10,080	20,160	40,320
50.0	8,400	16,800	33,600	50,400	100,800	201,600

Table 5-1. Leak Volumes for Various Retrieval Durations with Constant Leak Rates

Based on Table 5-1, a leak rate during retrieval greater than 5 gal/hr (12-week retrieval campaign) will not exceed the risk based performance criteria of 36,000 gallons (Section 3.2, Figure 3-2). The non-catastrophic postulated leak loss (95% confidence) for Hanford SSTs is less than 1.8 gal/hr (RHO 1981). This analysis was reviewed again in 1998 and found consistent with SST leak data (LMHC 1999a). This leak loss leak rate is based on estimated averages of leaks in the 1960s-1970s from tanks with significant free liquids and are inclusive of catastrophic leaks for a few tanks (e.g. A-105, BX-102, and T-106). Therefore, this number should be a much larger leak rate than would be expected today. Based on the 1.8 gal/hr leak loss rate and an estimated retrieval duration of 4 to 12 weeks (30 to 90 days), a potential leak of this magnitude during retrieval operations would not be detectable using current best available technology.

If a truly catastrophic failure of the tank were to occur, and no mitigating measures were implemented, the entire tank volume could eventually be released to the environment. The maximum volume, which could be released under the hypothetical, worst-case scenario includes the tank inventory plus approximately three inches of fluid needed to support pump operations, is estimated at 271,000 gallons. Lessons learned indicate that catastrophic leaks are caused by improper design, construction or material composition. There have been no catastrophic failures in the Hanford 241-C Farm, and there is no evidence to indicate a catastrophic failure in 241-C-104 is likely.

Barring a catastrophic failure, and when considering waste porosity, capillary height of the waste, and the fluid properties of the waste that can leak, the maximum potential leak is estimated to be 33,000 gallons. Another consideration is that setting equipment to

monitor for small leak volumes increases the potential for false alarms. False alarms will result in suspension of retrieval operations to validate the alarm, increasing overall retrieval duration, which in turn would increase the risk of leak volume. This approach is not consistent with the leak mitigation strategy. Figure 5-2 illustrates accumulated leak volumes using a 1.8 gal/hr leak rate. At a rate of 1.8 gal/hr, the risk-based leak loss performance criteria of 36,000 gallons would only be exceeded after a 833-day retrieval campaign. Both Table 5-1 and Figure 5-2 demonstrate that increased retrieval duration leads to potential increased leak loss, which in turn leads to increased risk to human health and the environment.



Figure 5-2. Undetected Leak Volume vs. Retrieval Duration At Loss of 1.8 Gal/Hr

Lessons learned (Appendix A) show no evidence of retrieval operations causing a tank leak, and the 95% probability leak rate for a non-catastrophic leak in an SST (1.8 gal/hr) would be undetectable. Therefore, the overall strategy for leak detection is:

1. Minimize the amount of liquid in the tank,
2. Reduce the retrieval duration,
3. Test the tank frequently for the possibility of a catastrophic release while waste is actively being retrieved (dynamic testing),
4. Use existing drywell and ground water monitoring wells for detection[1] and monitoring,
5. Minimize activities that require suspending retrieval operations,
6. Statically test the tank at appropriate intervals during the retrieval campaign (e.g., when retrieval operation is suspended for a different reason) and
7. Use static leak detection if the dynamic or external tank leak detection system indicates a probable leak.

Regarding item four above, logging of drywells will be employed only as a secondary leak detection system because radiation detected in a drywell may be difficult to interpret for the following reasons:

- Lack of a reading may only mean that a release has not migrated to the well, and
- A positive reading may be the result of existing contamination or waste migration from another tank.

Due to this uncertainty, ex-tank methods using existing drywells will not be the primary method of leak detection. Even with these interpretation drawbacks, periodic scans will be obtained in existing wells before, during and after retrieval operations. When used in conjunction with other leak detection systems, they can be helpful in assessing the existence, extent, and mitigation of a leak.

5.1.2 Leak Monitoring

Leak monitoring is the quantification of a liquid waste release volume from a SST after detection of a leak during waste retrieval operations. A leak volume estimate must be predicted to quantify the environmental impact resulting from a leak. Dynamic, static, and ex-tank methods will be applied to quantify a potential leak volume during retrieval operations. The limitations associated with leak detection, as discussed above, apply to leak monitoring.

5.1.3 Leak Mitigation

Based on above discussions, the primary strategy for mitigation is a retrieval technology that limits the liquid volume and accelerates retrieval. The backup strategy for mitigation

[1] The present dry well and groundwater monitoring system is not designed for real time (i.e., instantaneous) leak detection and response, as time is required for waste to reach the area of influence of the dry well and for radiation data interpretation and analysis. Alternate ex-tank methods are being evaluated (see section 5.3.4) and will be considered for use based upon the results of proof-of-concept tests.

is to evaluate techniques to reduce contaminant migration. Items under consideration are reactive barriers, other barriers, or ex-tank treatment options.

5.2 241-C-104 Retrieval and LDMM System Descriptions

The retrieval and LDMM systems described in this section represent a conceptual view of the systems currently planned for deployment in 241-C-104. Detailed design will result in enhancing the definition of the system and may result in changes to the features described below. However, the final design will comply with the requirements established in this document and any subsequent changes established throughout the change control process described in Section 6.

5.2.1 241-C-104 Retrieval System Description

A confined sluicing, robotic type waste retrieval system, termed the mobile retrieval system, will be demonstrated to remove sludge from 241-C-104 (CHG, 2000a). The mobile retrieval system incorporates hydraulic nozzles to dislodge and mobilize the waste and a slurry removal mechanism to recover and transfer the resultant slurry. The retrieval system configuration is anticipated to include a waste transfer system that relies on a re-circulating waste stream between 241-C-104 and the receiving DST. Supernatant from the DST system is used as the mobilization fluid for the mobile retrieval system, and the resulting retrieved slurry from 241-C-104 is pumped back to the receiver DST. This arrangement allows for reuse of DST supernatant as sluicing media, thereby minimizing the volume of liquid waste generated during retrieval that requires storage in the DST system. This significantly reduces generation of secondary waste and the volume required to be sent to the DST receiver tank, thus allowing more SST waste to be retrieved. Figure 5-3 presents a conceptual sketch of the waste retrieval system. The primary system components are listed below:

- DST Transfer Pumping System - A submersible pump or several pumps in series will be installed in the receiver DST and will draw clear supernatant from the DST and deliver it to 241-C-104 for use by the mobile retrieval system. The flow rate selected will provide fluid velocity in excess of critical solids settling velocity, yet below the velocity that could cause excessive corrosion of the transfer piping.
- Mobile Retrieval System - The mobile retrieval system will perform the confined sluicing during the retrieval operations. It will deliver sluicing fluid using hydraulic nozzles. A slurry removal mechanism will also be located as close as is reasonable to the nozzles and waste to minimize liquid use and hydraulic head, and maximize slurry recovery.
- Sluice Nozzles - Sluice nozzles on the mobile retrieval system or on a mast in the tank are positioned to direct the sluice stream to the desired location. The nozzles are sized to produce a cohesive sluice stream. This will enable the mobile retrieval system to effectively wash waste from the tank walls and in-tank hardware.

- SST Slurry Booster Pump System - A booster pump mounted on or near C-104 will provide the motive force to transfer the retrieved slurry from 241-C-104 to the receiver DST.
- Slurry Distributor - A slurry distributor, installed in the receiver DST, introduces the retrieved waste from 241-C-104 into the DST.



Figure 5-3. 241-C-104 Mobile Retrieval System

5.2.2 LDMM System Description

As stated earlier, two methods of in-tank leak detection will be used during the retrieval effort: dynamic and static. Dynamic leak detection uses tank level and transfer flow measurements to calculate waste volume discrepancies between the SST being retrieved and the receiving DST (see Figure 5-4). Static leak detection uses discrepancies between level measurements taken at different points of time in the same tank and requires a halt in the retrieval effort to let the tank level achieve stasis (see Figure 5-5) and a free liquid surface to measure against. Drywells outside of 241-C-104 will be monitored to establish a pre-retrieval baseline for the SST and then periodically monitored to detect variation in radiation levels in the soil column.

Currently, tank level measurement is done with ENRAF-Nonius® level instruments. The ENRAF instrument is mounted on a tank riser dedicated to that purpose. The ENRAF is remotely controlled by a computer, which causes the instrument to raise, and lower a displacer suspended on a stainless-steel wire dispensed by a reel. The displacer is constantly weighed and the weight-sensing circuit can detect the difference between air, supernatant and sludge. The displacer wire dispensed length is measured via a rotary encoder on the reel. Changes in the waste level greater than the uncertainties associated with the measurement error are interpreted as a leak. This is currently defined as ½ inch, equating to a volumetric discrepancy of approximately 1,400 gallons (RHO 1981).

Transfer flow measurements are done with volumetric/mass-flow instruments, which provide real-time data on volumetric and mass flow. Volumetric flows between 241-C-104 and the receiver DST can be compared with tank volumes calculated from tank levels. Differences outside of the instrument error bands would indicate a leak. Any flush water additions or volume additions from other sources must also be accounted for in the volumetric balance calculations.



Figure 5-4. 241-C-104 Dynamic Leak Detection (Based on Mass/Volumetric Flow & Tank Liquid Level)



Figure 5-5. 241-C-104 Static Leak Detection (Based on Changes in Tank Liquid Level Only)

Leak detection is easily employed on the existing transfer lines, new transfer lines, and the receiving DST itself. Leak detection in the receiving DST will be performed primarily with the existing annulus leak detection. Unlike an SST, a DST has redundant protection against leakage (secondary encasement), which allows for using direct forms of leak detection, i.e., conductivity probes. The existing transfer lines and receiving DST are encased and the encasement on each leg of the transfer route will terminate inside of a pit. A conductivity probe will be placed beneath each low point pit drain to monitor for overflowing leaks in the primary line.

Transfer line leak detection may also be performed using volumetric/mass balancing. Flow meters placed at the inlet and outlet of the lines can be compared continuously for discrepancies greater than the anticipated measurement error.

5.3 LDMM and Retrieval Operating Strategy

The operating strategy for performing LDMM and retrieval applies to pre-retrieval and retrieval steps as described below.

5.3.1 Pre-Retrieval

A pre-retrieval LDMM assessment will be undertaken for 241-C-104 prior to the start of retrieval operations. This assessment will be consistent with the *Hanford Federal Facility Agreement and Consent Order,* Appendix H – "Single-Shell Tank Waste Retrieval Criteria Procedure" and includes:

- Establish an ex-tank baseline condition using gamma monitoring in existing drywells
- Calculate the volume (liquid, solid, and total) for both 241-C-104 and the DST receiver tank
- Measure/calculate 241-C-104 waste inventory via topographical or other mapping and survey techniques
- Perform an operational history review to look for evidence of releases
- Evaluate the operational functionality existing leak detection instrumentation
- Perform a data review of drywell/borehole and Tank Farm Vadose Zone Project instrumentation and data.
- Conduct an initial leak test and/or confirmation of "soundness" using active in-tank and ex-tank instrumentation following existing tank farm surveillance and monitoring programs and the tank leak assessment process.

This pre-retrieval LDMM assessment will provide a baseline assessment of 241-C-104 conditions prior to retrieval.

5.3.2 Retrieval

The overall retrieval strategy will consist of reducing the tank liquid inventory during retrieval operations, monitoring liquid inventories while waste is actively being retrieved (dynamic test), and monitoring liquid inventories when retrieval operations are intermittently suspended (static test). (See Figure 5-6) Dynamic testing will be performed throughout the retrieval operations. Static testing will be performed when the waste configuration and the location of the liquid surface is such that instrumentation can contact the liquid surface, i.e., a free liquid surface is accessible by the level instrumentation (beneath a riser). The opportunities for conducting static tests, as well as dynamic tests, will be established in a process control plan.

5.3.2.1 Retrieval Strategy

To reduce the tank liquid inventory during retrieval operations, nozzle(s) will be oriented to attempt to create a cone-shaped "well" in the waste around the slurry removal mechanism, which removes the mobilized sludge material and slurry. This strategy is key to leak mitigation since it minimizes the free liquid in the tank. As the sludge and slurry are removed from the tank, the mobile retrieval system is lowered further into the tank (or moved laterally, or both) to maintain a continual feed to the slurry removal

mechanism. In the event a "well" in the waste cannot be created or maintained, supernatant from another tank will be added in sufficient quantities to maintain feed to the slurry removal mechanism. Operations continue in this fashion until insufficient waste remains to provide a constant source of feed for the slurry removal mechanism, at which time bulk retrieval operations will end.

The 241-C-104 mobile retrieval system will utilize recycled supernatant from the receiving DST. The transfer lines to the receiving tank and the receiving tank itself are encased and provided with low-point conductivity type leak detection. As discussed previously, the current concept of the mobile retrieval system incorporates an on-board nozzle to dislodge and mobilize the waste and a slurry removal mechanism to recover and transfer the resultant slurry. During initial operation of the retrieval system, dynamic leak detection will be the primary means of leak detection. Once the retrieval operation has proceeded to a point that a "well" has formed in the sludge and free liquid has collected in the "well," a static leak test may be possible. Sampling can also be accomplished during the static leak test.



Figure 5-6. Retrieval/LDMM Operational Response Process Diagram

5.3.2.2 Dynamic Leak Detection

Dynamic leak detection will be implemented during waste retrieval operations. It will consist of liquid waste level measurements, including measurements required to compensate for short-term variations in the measurement signals, in both 241-C-104 and the DST receiver tank. In addition, flow measurements (also including other measurements required to compensate for short term variations) will be made in both the transfer piping going into and out of 241-C-104 and into and out of the DST. This will allow static leak tests to be performed as well as the dynamic estimates based on transferred volumes. Based on the required leak detection requirements and the capabilities of the instruments, a goal will be established that the analysis result of the dynamic leak detection data being collected during retrieval lags the ongoing operations by no more than 48 to 96 hours, with updates on an 48 to 96 hour basis.

Table 5-2 provides a typical listing of the instrumentation used for dynamic leak testing; the table describes the data and measurement functions for which it may be collected.

Table 5-2. Instrumentation Requirements for Dynamic Leak Detection

Instrument	Measurement Function	Purpose
Level gauge	Free liquid surface level inside SST	Direct measurement
Level gauge	Free liquid surface level inside DST	Direct measurement
Thermocouple	Air temperature inside SST	Instrument error
Thermocouple	Liquid temperature inside SST	Source material compensation
Thermocouple	Air temperature outside SST	Instrument error
Pressure gauge	Barometric pressure	Source material compensation
Pressure gauge	Static pressure inside SST (ventilation system)	Source material compensation
Pressure gauge	Static Pressure Inside DST (ventilation system)	Source material compensation
Pressure gauge	Transfer pipeline pressure	Source material compensation
Flow meter	Volumetric / mass flow out of SST	Direct measurement
Flow meter	Volumetric / mass flow into SST	Direct measurement
Psychrometrics	Evaporation / condensation in SST	External inflow/outflow
Batch sample	Liquid/sludge density inside SST	Source material compensation
Sensor and switch	Data acquisition and alarm	Record and process data inputs

For dynamic leak detection, the retrieval system will be treated like a closed loop system consisting of the recovery tank, 241-C-104, the receiving tank (a DST), and the connecting transfer lines (see Figure 5-4). Solids loading and specific gravity in the recovery line may be

measured and used to compensate/reconcile the recovery volume. The discrepancy between the inflow and outflow from 241-C-104 will be compared to the volume in the DST (converted from surface level measurements) and the transfer line. Any discrepancy greater than the uncertainties in the volume calculations and estimates of the 241-C-104 liquid inventory, including the error produced by all compensating measurements (thermal expansion, dissolution, solids loading, etc.), will be considered a leak in 241-C-104. This assumes that no leak is detected in the transfer line(s) or the DST. This assumption will be validated prior to commencing the actual retrieval operations via the pre-retrieval LDMM assessment process.

If a leak is indicated during retrieval operations process control procedures will be implemented (see Figure 5-6). The first response to an indication of a potential leak will be to validate the instrumentation. If the validation process concludes that no leak is indicated, retrieval operations would start-up and continue under normal operating procedures. However, if a leak is validated, the operating contractor will notify DOE-ORP, which will in turn notify Ecology. The process control procedures will consider the leak loss limit, leak loss rate, and estimated duration to completion of retrieval operations when determining the appropriate response action. Potential response actions include (1) continuing retrieval activities if the estimated leak volume would remain within the leak loss limit, (2) modifying leak monitoring (e.g., implementing more frequent in-tank or ex-tank monitoring/testing), (3) modifying operating conditions, (4) discontinuing adding or recycling liquids, (5) implementing emergency retrieval, or (6) stopping all operations (see Figure 5-6). The response actions would then be implemented and, if appropriate, retrieval operations would continue under modified procedures through the completion of the retrieval activities. The requirements for implementation of leak response actions during retrieval operations will be established in the Process Control Plan, which will be developed concurrent with the design of the retrieval and LDMM system.

5.3.2.3 Static Leak Testing

A static leak test will require that all sluicing operations be suspended for a period of time to allow the system to reach equilibrium and to conduct the leak detection test. Static leak detection is comprised of liquid waste level measurements in the SST being retrieved, as well as measurement of other liquid collection or dispersion points.

Once retrieval operations have been suspended, a waiting period will be observed to allow the liquids to gravity drain to retrieval system low points. Static testing will be performed once 241-C-104 has reached equilibrium. The frequency and duration of the static test will be determined during the design of the retrieval system. Data will be collected over a period of time (48 hours, for example), and measurements will include tank liquid waste levels and temperatures (to account for thermal expansion.) Table 5-3 provides a listing of the representative instrumentation required for static leak testing. The table also describes the data and the reason it is being collected. Once the data collection and analysis are complete and have shown that a leak has not occurred, tank waste retrieval operations are resumed.

Table 5-3. Instrumentation Requirements for Static Leak Detection

Instrument	Measurement Function	Purpose
Level gauge	Free liquid surface level inside SST	Direct measurement
Thermocouple	Air temperature inside SST	Instrument error
Thermocouple	Liquid temperature inside SST	Source material compensation
Thermocouple	Air temperature outside SST	Instrument error
Pressure gauge	Barometric pressure	Source material compensation
Pressure gauge	Static pressure inside SST (ventilation system)	Source material compensation
Psychrometrics	Evaporation / condensation in SST	External inflow/outflow
Batch sample	Liquid/sludge density in SST	Source material compensation
Sensor and switch	Data acquisition and alarm	Data Recording and Processing

The first response to an indication of a potential leak will be to validate the instrumentation. If the validation process concludes that no leak is indicated, retrieval operations would start-up and continue under normal operating procedures. However, if a leak is validated, the operating contractor will notify DOE-ORP, which will in turn notify Ecology and process control procedures will be implemented. The process control procedures will consider the leak loss limit, leak loss rate, and estimated duration to completion of retrieval operations when determining the appropriate response action. Potential response actions include 1) continuing retrieval activities if the estimated leak volume would remain within the leak loss limit, 2) modifying leak monitoring (e.g., implementing more frequent dynamic monitoring or static testing), 3) modifying operating conditions, 4) discontinuing adding or recycling liquids, 5) implementing emergency retrieval, and/or 6) stopping all operations (see Figure 5-6). The response actions would then be implemented and, if appropriate, retrieval operations would continue under modified procedures through completion of the retrieval activities. The requirements for implementation of leak response actions during retrieval operations will be established in the Process Control Plan, which will be developed concurrent with the design of the retrieval and LDMM system.

5.3.2.4 Drywell Monitoring

Drywells will be monitored periodically during retrieval operations to provide additional leak detection and monitoring capability. The frequency of drywell monitoring, the types of monitors to be used, and potential response actions will be established during the design phase of the project.

5.3.3 Post Retrieval

A post-retrieval LDMM assessment will be undertaken for 241-C-104 following completion of retrieval operations. This assessment will be consistent with the *Hanford Federal Facility Agreement and Consent Order*, Appendix H –"Single-Shell Tank Waste Retrieval Criteria Procedure" and includes:

- Reevaluate ex-tank conditions using gamma monitoring in existing drywells and compare with the baseline condition
- Measure/calculate 241-C-104 residual waste inventory via proposed topographical or other mapping and survey techniques.

When the 241-C-104 retrieval demonstration has been declared complete, an evaluation of the closure source term will be performed. If leak detection data does not indicate a leak occurred, no post-retrieval LDMM activities are planned. Existing vadose zone contamination is being addressed under a separate program. The SST closure work plan will specify any specific closure/post closure requirements. If a tank is shown to have leaked during retrieval, the present procedure (see Section 5.1.3) will address any follow-on actions.

5.3.4 Alternative Technologies

The 241-C-104 retrieval demonstration system will use the best available technology that is economically achievable for leak detection. During FY 2001, DOE-ORP is sponsoring testing and demonstrations to examine alternate LDMM technologies that provide indirect leak detection outside of the tank. These technologies may have potential to augment the existing drywell ex-tank leak detection system. These ex-tank LDMM technologies include:

- Electrical Resistance Tomography (PNNL 2001a)
- Cross-hole Seismic (PNNL 2001a)
- Cross-hole Radar (PNNL 2001a)
- Cross-hole Electromagnetic Induction (PNNL 2000)
- High-Resolution Resistivity (PNNL 2000)
- Partitioning Interwell Tracer Tests (CHG 2000a)

In addition, further in-tank leak detection technologies will be investigated during the 241-U-107 proof-of-concept test and during design and development of the 241-C-104 retrieval demonstration. These include:

- Liquid Observation Well used with gamma probe
- Topographical mapping techniques

If testing during FY 2001 demonstrates that any of these technologies significantly decreases uncertainty associated with static and dynamic leak testing, they will be evaluated for inclusion in the demonstration. The parameters that will be evaluated are:

- Maturity, accuracy, and precision of the technology
- Amount of additional development required to deploy the technology
- Degree by which LDMM is enhanced versus the cost to deploy the technology
- Impacts to the project schedule
- Cost impacts to the project baseline

6.0 HANFORD FEDERAL FACILITY AGREEMENT AND CONSENT ORDER F&R CHANGE CONTROL

This document is a *Hanford Federal Facility Agreement and Consent Order* Primary Document requiring Ecology review and approval. This document will establish the functions and requirements for the 241-C-104 retrieval demonstration for the life of the retrieval project. Document revisions will follow the criteria outlined in Section 9.3, "Document Revisions" of the *Hanford Federal Facility Agreement and Consent Order*. Modifications to this document will be assessed using existing criteria. Minor field changes (as discussed in Section 12.4 of the Agreement) can be made by the person in charge of the particular activity (i.e., the CHG Project Manager or equivalent). Minor field changes are those that have no adverse effect on the technical adequacy of the job or work schedule (i.e., does not impact completion of milestone commitments). Such field changes will be documented in daily logbooks (or equivalent) that are maintained by the project.

Revisions/Changes not considered minor field changes can be made through use of a change notice in accordance with Sections 9.3, "Document Revisions" and 12.0, "Changes to the Agreement." Major changes (those requiring a change notice) or revisions to the plan are further defined by the following criteria:

- Significant change affecting public health or the environment,
- Evaluation of remedial alternatives (i.e., major changes to retrieval technologies and/or programmatic decisions that impact the technical adequacy of the project or impact work schedules), and
- Protection of human health or the environment (i.e., exceeding maximum leak loss limits, or major design change to LDMM criteria).

7.0 REFERENCES

10 CFR 61.55, *Waste Classification*, Code of Federal Regulations.

10 CFR 830, *Nuclear Safety*, Code of Federal Regulations.

10 CFR 835, *Occupational Radiation Protection*, Code of Federal Regulations.

29 CFR 1910, *Occupational Safety and Health Standards*, Code of Federal Regulations.

40 CFR 61, *National Emissions Standards for Hazardous Air Pollutants*, Code of Federal Regulations.

40 CFR 265, *Interim Status Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities*, Code of Federal Regulations.

40 CFR 280, *Technical Standards and Corrective Action Requirements for Owners and Operators of Underground Storage Tanks*, Code of Federal Regulations.

40 CFR Subchapter R, *Toxic Substances Control Act*, Code of Federal Regulations.

CHG 2000, *Decision Document for Single-Shell Tank tank C-104 Preferred Waste Retrieval Technology*, RPP-7188, CH2M HILL Hanford Group, Inc., Richland, Washington.

CHG, 2000a, *Annual Progress Report on the Development of Waste Tank Leak Monitoring/Detection And Mitigation Activities in Support of M-45-08 (TPA Milestone M-45-09E Fiscal Year 2000 Progress Report)*, RPP-7012, CH2M HILL Hanford Group, Inc., Richland, Washington.

CHG, 2000b, *Single-Shell Tank Retrieval Sequence: Fiscal Year 2000 Update*, RPP-7087, CH2M HILL Hanford Group, Inc., Richland, Washington.

CGH 2000c, OSD-T-151-00013, *Operating Specification for Single-Shell Waste Storage Tanks*, CH2M Hill Hanford Group, Inc., Richland, Washington, November 2000.

CGH 2000d, HNF-3350, *Engineering Basis Document Review Supporting Double-Shell System Specification Development*, CH2M Hill Hanford Group, Inc., Richland, Washington.

CGH 2000e, HNF-IP-1266, *Tank Farms Operations Administrative Controls*, CH2M Hill Hanford Group, Inc., Richland, Washington.

CGH 2000f, RPP-6665, *Project W-523, Tank C-104 Waste Retrieval System Environmental Permits and Approvals Plan*, CH2M Hill Hanford Group, Inc., Richland, Washington.

CGH 2000g, RPP-7087, *Single-Shell Tank Retrieval Sequence, Fiscal Year 2000 update*, CH2M Hill Hanford Group Inc., Richland, Washington.

CHG, 2001, *Waste Tank Summary Report for July 2001*, HNF-EP-0182-160, Hanlon, B. M., CH2M HILL Hanford Group, Inc., Richland, Washington..

CGH 2001a, HNF-SD-WM-SAR-067, *Tank farms Final Safety Analysis Report*, CH2M Hill Hanford Group, Inc., Richland, Washington.

CGH 2001b, HNF-SD-WM-TSR-006, *Tank Farms Technical Safety Requirements*, CH2M Hill Hanford Group, Inc., Richland, Washington.

DOE, 1996, *Dangerous Waste Permit Application - Single-Shell Tank System*, U.S. Department of Energy, Washington, D.C.

DOE 1999, DOE/RL-98-72, *Retrieval Performance Evaluation Methodology for the AX Tank Farm*, US Department of Energy Richland, Washington, 1999.

DOE/Ecology 2000, *DRAFT Federal Facility Agreement and Consent Order Change, M-45-00-01A, 8/30/2000*, U.S. Department of Energy and Washington Department of Ecology Negotiation Team.

DOE/EPA 1996, Memorandum of Understanding, *"Required Percent of Waste Retrieval,"* U.S. Department of Energy and Washington State Department of Ecology. Richland, Washington, August 7, 1996.

DOE, EPA, and Washington Department of Ecology 1989, *Hanford Federal Facility Agreement and Consent Order*, DOE/RL 89-10, as amended, U. S Department of Energy, Richland Operations Office, Richland, Washington.

DOE G 430.1A, *Deactivation Implementation Guide*, U.S. Department of Energy, Washington, D.C., September 29, 1999

DOE Order 435.1 *Radioactive Waste Management*, U.S. Department of Energy, Washington, D.C., July 9, 1999.

Ecology, 1999, *Agreement Commitments Regarding Initial Single-Shell Tank Waste Management Area (WMA) Corrective Actions, Vadose Zone and Groundwater Characterization, Assessment, and the Integration of Vadose Zone and Groundwater Activities at Specified Associated Sites*, Change Request M-45-98-03, Washington Department of Ecology, January 8, 1999, Draft.

LMHC 1998, HNF-2944, 1998, *Single-Shell Tank Retrieval Program Mission Analysis Report*, Lockheed Martin Hanford Corporation. Richland, Washington.

LMHC 1999, HNF-4712, *Load Requirements for Maintaining Structural Integrity of Hanford Single Shell Tanks During Waste Feed Delivery and Retrieval Activities,* Lockheed Martin Hanford Corporation, Richland, Washington.

LMHC, 1999a, *Single Shell Tank Leak History Compilation, Volume 1 of 2,* HNF-4872, Lockheed Martin Hanford Company, 1999, Richland, Washington.

LMHC 2000, HNF-5095, *Single-Shell Tank Program Plan*, Lockheed Martin Hanford Corporation, Richland Washington.

PNNL, 2000, *Vadose Zone Transport Field Study: Detailed Test Plan for Simulated Leak Tests,* PNNL-13263, June 2000, Pacific Northwest National Laboratory, Ward, A.L. and Gee, G.W., Richland, Washington.

PNNL 2001, *RCRA Groundwater Monitoring Plan for Single-Shell Tank Waste Management Area C at the Hanford Site*, PNNL-13024, February 2001, Pacific Northwest National Laboratory, Richland, Washington.

PNNL 2001a, *Vadose Zone Transport Field Study: FY2001 Test Plan,* PNNL-13451, March 2001, Pacific Northwest National Laboratory, Ward, A.L. and Gee, G.W., Richland, Washington

RHO 1981, *A Scientific Basis for Establishing Dry Well Monitoring Frequencies,* RHO-ST-34, Isaacson, R. E. and Gasper, K. A., Rockwell Hanford Operations Energy Systems Group, Richland, Washington.

TIR 2000, *Tank Interpretive Report,* autocr.241-c-104.200103281017, from TWINS website, 3/28/01.

TWINS Website 2000, Tank Waste Information Network System, *http://twins.pnl.gov:8001/twins.htm* Best Basis Inventory Data as of 8/01/2000.

TWINS Website 2001, Tank Waste Information Network System, *http://twins.pnl.gov:8001/twins.htm* Downloaded tank C-104 BBI file on 3/28/2001.

Vadose 2001, *Hanford Tank Farms Vadose Zone Project Web Page*, C Tank Farm Report, Tank Summary Data Report, http://www.doegjpo.com/programs/hanf/htfvz.html, 4/17/01.

WAC 173-303-640, *Dangerous Waste Regulations – Tank Systems*, Washington Administrative Code, as amended.

WAC-173-400, *General Regulations for Air Pollution Sources*, Washington Administrative Code, as amended.

WAC-173-460, *Controls for New Sources of Toxic Pollutants*, Washington Administrative Code, as amended.

WAC-246-247, *Radiation Protection – Air Emissions*, Washington Administrative Code, as amended.

WHC 1996, *Proposed Strategy for Leak Detection, Monitoring, and Mitigation During Hanford Single-Shell Tank Waste Retrieval*, WHC-SD-WM-ES-378, Rev. 1.

APPENDIX A

LESSONS LEARNED BASIS FOR SELECTION AND IMPLEMENTATION OF RETRIEVAL AND LDMM TECHNOLOGIES

APPENDIX A - LESSONS LEARNED BASIS FOR SELECTION AND IMPLEMENTATION OF RETRIEVAL AND LDMM TECHNOLOGIES

A lessons-learned summary was prepared to support the development of the F&R for retrieval of Tank 241-C-104. A survey of technology application experience was conducted to identify lessons learned relevant to this planned application of confined sluicing and robotic retrieval technologies.

A.1 Methodology

Source information was taken from technical documents and communications with key personnel in the technical community from the DOE Complex, other federal agencies, and the private sector. The information was screened for consideration and applicability to this retrieval activity. Considerations relevant to the 241-C-104 retrieval activities were then formulated and presented in tabular format as illustrated below:



Although the selection process was primarily focused on confined sluicing and LDMM volumetric/mass balance systems supporting large-scale tank facilities, other applications also offered relevant information.

A.2 Information Sources.

Candidate items with experience in relevant technologies were identified. Key documents from these sources were reviewed and personnel contacted to acquire necessary information and to develop a basis to establish lessons learned for Tank 241-C-104 retrieval.

A.2.1 Hanford Tank 241-C-106 Retrieval

Project W-320 at Hanford retrieved 187 kgal of sludge from Tank 241-C-106 (Bailey 2000). The waste retrieval was accomplished using a past-practice sluicing technology in 24-hour batches with 12 hours between batches to perform heat load/transfer calculations. The heat load calculations also provided data for mass balance leak detection.

The mass balance technique employed during Project W-320 (Bailey 2000, and LMHC 1999) used both retrieval tank and receiver tank level measurements from sensors such as ENRAFs and FICs (Food Instrument Corporation liquid level monitors). This sensor data was used in combination with in-tank video and with characterization data to convert volume data to mass data. The mass data was run through an algorithm to compare how much sluiced material (by weight) went into the retrieval tank and how much waste material (by weight) came out of the retrieval tank.

This technique required liquid level interface measurements as well as shutdown of the retrieval operation to allow the level data to be acquired (this has been true for most technologies using in-tank measurements). Because some tanks have solid surface layers, it was necessary to "punch through" the layer for direct measurement of a liquid interface. Alternatively, measurements in the liquid observation wells, where available, could be taken using indirect measurement of the interface through neutron probe or gamma activity to estimate the volume moved between retrieval operations. As in any measurement of fluctuating quantities, "baselines" of level and level trends needed to be established and attributed to the causes for any observed change, before the data could be analyzed for "leaks," since normal and routine changes in inferred mass needed to be understood.

Flow rate-augmented mass balancing techniques have the potential to improve accuracy by measuring the rate at which liquids and slurries are transferred. Flow rate measurements were collected during the tank 241-C-106 retrieval operation, but the data has not been analyzed in terms of mass transfer. When this data is analyzed, the benefits and limitations of flow rate-augmented data will be more evident. In cases where no liquid interface is measurable, such as might be found in tanks containing stabilized sludges, this technique has limited value. Tank 241-C-106 retrieval operations did not use the mass balance method for leak detection; a heat load management method was used for that project.

A.2.2 Oak Ridge Gunite and Associated Tanks (GAAT)

The Oak Ridge Gunite and Associated Tanks (GAAT) project successfully completed waste retrieval on eight gunite tanks at the Oak Ridge National Laboratory between 1996 and 2000. The tanks include two 50-kgal gunite tanks in the North Tank Farm and six 140-kgal tanks in the South Tank Farm. Waste retrieval was completed for the last two tanks (W-8 and W-9) in fiscal year 2000.

The GAAT waste retrieval system consists of the Modified Light-Duty Utility Arm (MLUDA), Confined Sluicing End Effector (CSEE), and the Houdini. The Houdini is a multifunctional remotely operated crawler. Tank W-9 contained heavy sludge from previous waste consolidation efforts. A heavy-waste retrieval system consisting of an airlift system and heavy-duty pumps was used along with the three other technologies to successfully mobilize and transfer the wastes from the tank.

Leak detection and monitoring for the GAAT project was provided via an external tank monitoring system combined with internal tank volumetric techniques. The gunite tanks were monitored for a large sudden release by using the on-line level measurements that were monitored around the clock at the Waste Operations Control Center. Volumetric precision leak testing was accomplished by analyzing 48-hour data sets of tank level readings that were taken at one-minute intervals. This precision testing was conducted prior to waste retrieval operations to establish baseline conditions. Both the external leak monitoring system and the Waste Operations Control Center monitoring were used during waste retrieval operations.

The external leak monitoring system utilized the drywells adjacent to each tank to monitor the conductivity of the groundwater that naturally flows around the tanks. A significant increase in conductivity would indicate a potential release from a tank. The system worked because the groundwater conductivity was approximately two orders of magnitude (100 times) less than the conductivity of the fluids in the tanks. Field-testing showed that leaks on the order of 0.5 gallons per minute could be detected using the external drywell monitoring method. The method was deployed and used during all GAAT waste retrieval operations. The external drywell monitoring leak detection system has allowed the GAAT project to use several of the inactive tanks (W-8 and W-9) in the South Tank Farm for the temporary storage of sluiced material and supernatant liquids. This use has, in turn, resulted in significant cost avoidance and reduction in schedule by eliminating the need to construct new above-ground tanks and facilitating an efficient transfer of wastes out of the tanks (ORNL 1998,).

A.2.3 Savannah River Tank 19 Heel Removal Project

At the Savannah River Site (SRS), long-shaft mixer pumps are being used for initial waste retrieval from the underground double-shell tanks, in particular Tank 19. Waste mixing and removal using the slurry pumps has left approximately 40 kgal of residual sludge as waste heel in Tank 19. In a joint effort between Westinghouse Savannah River Company and the Tanks Focus Area, the use of Flygt® Mixer technology is being demonstrated as a means to remove the waste heel from Tank 19 and other SRS tanks.

Two years of scale up and verification testing of the Flygt Mixers were conducted at Pacific Northwest National Laboratory and the SRS TNX Test Facility. Following this effort, the third of three Flygt Mixers was installed in Tank 19 on August 2, 2000. The schedule calls for mixing to begin in September, with completion of waste retrieval in Tank 19 within approximately 1 month.

Leak detection in the SRS double-shell tanks is accomplished by monitoring the annular space between the inner and outer tanks with radiation monitors and electrical resistance leak detectors (SRS 1995). Nine tanks have leaked in the past, and tank liquids were detected in the annular space via radiation monitors and annulus photography (SRS 1995). The groundwater at the SRS typically ranges from ten to twenty feet below grade, and groundwater sampling is also used as part of the leak detection strategy.

A.2.4 Hanford Tank 241-SY-101 Surface Level Remediation Project

The 241-SY-101 tank contained nearly a million gallons of waste with a history of retained gases that were released during periodic rollover events. This had been remedied with the installation of a mixing pump in 1993. Subsequent to that time the level of the crust began to grow, retaining ammonia, nitrous oxide, and hydrogen at an increasing rate. This presented critical safety issues requiring transfer and dilution of the waste. This Project deployed a submersible canned rotor transfer pump that was based on technology developed for cooling naval reactors. A temporary at-grade transfer line comprised of a flexible hose within a hose was used for the transfer from 241-SY-101 to 241-SY-102. The transfer line was compliant with established technical and regulatory requirements. With the conclusion of transfers and back dilution the contents of 241-SY-101 were sufficiently changed to resolve this critical safety issue.

A.2.5 Other Federal Programs and Private Industry Demonstrations

Other commercial nuclear, robotics development, and Federal programs have carried out activities that have provided relevant information for this lessons learned review. Examples include Cybernex (France) development of industrial systems to operate in hazardous environments (Fidani 2001), DOE/NASA collaborations to develop robotic systems for Chernobyl (Osborn 2001), Toshiba (Japan) development of robotic systems to deploy systems to conduct maintenance on nuclear power plant large pressure vessel fuel core support structures (Shimamura et al 2001), US-EPA development of standards for leak detection on large petroleum tanks, and other remote or robotic systems with operating experience in hazardous environments (Maresca, et al, 1993).

There were no specific DOE-observed private industry LDMM demonstrations in fiscal year 2000. The Strategic Environmental Research and Development Program (SERDP) sponsored an applied research project through Pacific Northwest National Laboratory. The applied research project was to perform non-intrusive characterization of dense non-aqueous phase liquids (DNAPLs) in the subsurface (Gauglitz, et al 1995 and Gauglitz, et al 2000). The results of the research indicate that short-lived radiotracers in partitioning interwell tests can detect fluid saturation in the subsurface. An adaptation of this approach has been proposed to quantify annual baseline soil moisture changes in the vadose zone immediately surrounding an

underground storage tank as a leak detection technique. Previous studies have shown that under the ideal conditions of equilibrium partitioning, gaseous water-soluble tracers can quantify the water content in the vadose zone through an extension of earlier developments in partitioning tracers for delineating DNAPL contamination in aquifers and the vadose zone (Deeds, et al 1999, Jin, et al 1995, and Whitley, et al 1999).

A.3 Tables for Design and Operation Considerations

Lessons learned considerations for design and operation were recorded in one of five "topical" tables consisting of operational effectiveness, residual waste/ retrieval effectiveness, leak detection, leak monitoring, and leak mitigation/response; these are provided as Tables A-1 through A-5 respectively. Each entry is listed in the appropriate table along with the lessons learned, a statement regarding relevancy to Tank 241-C-104 retrieval, reference documentation, and the associated project. Although this information was drawn from a variety of sources, industries and applications, the "lessons" to facilitate successful deployment of the 241-C-104 retrieval systems typically fell into one of the categories listed below:

a) Careful and complete documentation of applicable *functions and requirements* should be completed before the design activities are initiated. They should be managed to ensure effective flow-down to subcontractors. The Project should prepare a compliance matrix to verify that the deployed system satisfies all (100%) requirements.

b) Establish, communicate, and support a clearly defined *deployment strategy* at all levels of design, safety analysis, construction, test, and operations activities. Assign operations personnel to the design team.

c) Effective *system integration* to control all elements of the Project must be achieved with particular emphasis on *configuration management* of all safety and safety related items.

d) *System availability* analysis should be provided to verify compliance with the functions and requirements using the traditional reliability/availability methodologies. Reliability analysis tools can be used to provide needed maintenance and operational flexibility necessary to avoid the operational problems and performance issues experienced in recent tracked-crawler retrieval operations. Examples of known availability issues to address include: loss of in-tank camera visibility due to fogging, misting, and condensation; insufficient physical access to maintain instrumentation; pump and pipeline plugging; ineffective back flushing or screen clearing features; functional failure of the tracked vehicles; and fouling/failure of tethered control cables.

e) Place the highest level of importance to the *system/operator interface* and associated operator training.

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.1	"Batch-wise sluicing" operations resulting from overly restrictive authorization basis control, unreliable LDMM methods, and/or insufficient process control are not cost effective. These require repeated startup and shut down operations with line flushing and system lay-up. This results in extended operating scenarios that are labor-intensive and inefficient.	May adversely impact schedule, operating costs and leak risk.	Design an integrated system to be capable of achieving performance criteria through continuous retrieval operations.	ORP W-320 Bailey 2000.
A.3.1.2	Overly restrictive controls imposed by authorization basis requirements can result in efficiency losses and extended outages when the need for maintenance or troubleshooting arises.	May adversely impact schedule, operating costs and leak risk.	Design an integrated system to provide sufficient operational flexibility to: a) Operate within safety controls, environmental permits, and operating plans for the retrieval operation, and b) Conduct normal maintenance, calibration, and trouble-shooting as required.	ORP W-320 Bailey 2000.
A.3.1.3	Waste tank cover gas grab samples were used as a basis to set unreasonably low limits for Volatile Organic Compound (VOC) emissions without consideration for organic compounds in the waste. During start-up operations limits for VOC and ammonia exceeded NOC prescribed limits.	May adversely impact schedule, operating costs and leak risk.	Base environmental permits on credible "disturbed waste" characterization information appropriate for operation so that an overly conservative air permit information does not result in operational delays due to NOC issues.	ORP W-320 Bailey 2000
A.3.1.4	Sluicer hydraulic drive systems over heated during the summer months due to inadequate cooling.	May adversely impact operational safety, schedule, operating costs and leak risk.	Provide adequate temperature control to ensure that components perform as required in the Hanford environment.	ORP W-320 Bailey 2000.
A.3.3.4	Hold-up of liquid in the hose loop prevented air trapped in the pump impeller casing from moving up into the transfer line; this prevented priming of the pump.	May adversely impact schedule, operating costs and leak risk.	Design flexible hoses and pipes to be self-draining after post-operation flushing and not prevent priming of the transfer pump.	ORP W-320 Bailey 2000.

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.5	Overly flexible hoses together with excessive rotation resistance hose linkage resulted in kinking of slurry and sluice pump discharge lines. This caused the system to be inoperable when the pumps were lowered as the liquid level decreased in the tank. As a remedy, the system was operated at overly high liquid levels, which reduced the effectiveness of the sluicing operation.	May adversely impact schedule, operating costs and leak risk.	Design flexible hoses to be the correct length and reinforced (or fitted with support devices) to ensure that rotary linkage performs effectively and no kinking will occur that would compromise the performance of the system	ORP W-320 Bailey 2000.
A.3.1.6	Poor pump seal performance resulted in excessive quantities of seal gas in the slurry line flow meter used to monitor aqueous fluid streams in the transfer lines. These gas bubbles were indicated as SpGs below 1.0 (i.e. no flow with no slurry solids loading) and inaccurate estimates of volume transferred from the tank.	May adversely impact schedule, operating costs and leak risk.	Design mass transfer instrumentation systems to mitigate the effects of retrieval system failures (e.g. entrained pump seal gas)	ORP W-320 Bailey 2000.
A.3.1.7	Poor pump seal (and associated seal gas control system) performance resulted in continuous manual adjustment by operations of seal line pressures to maintain manufacturer's guidance for seal gas.	May adversely impact schedule, operating costs and leak risk.	Make provisions for an appropriate pump seal fluid selection and seal pressure control system to minimize requirement for operator intrusion.	ORP W-320 Bailey 2000
A.3.1.8	Jumper leaks resulted from misalignment for the sluicer assembly and associated equipment.	May adversely impact operational safety, schedule, operating costs and leak risk.	Use flexible joints on ridgid jumper connections when correct alignment cannot be verified. Test all valves installed on jumpers before putting the jumper in service.	ORP W-320 Bailey 2000., Bailey 2000
A.3.1.9	Leaks were discovered in a purchased three-way valve; the blocking function of this valve should have been tested before deployment in C-104	May adversely impact operational safety, schedule, operating costs and leak risk.	Cold test all fluid connections and components prior to deployment in the operating system.	ORP W-320 Bailey 2000
A.3.1.10	Manual flushing after each sluicing batch required removal of cover blocks and the connection of flush water to a process jumper.	May adversely impact schedule, operating costs and leak risk.	Provide the capability to flush slurry/supernatant piping systems without excessive preparations or system modifications, and operator activity.	ORP W-320 Bailey 2000.

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.11	Houdini-II maintenance systems (e.g. TMADS) and supporting equipment did not provide adequate features for effective maintenance. Examples include: ▪ Full-length hinges for access panels that were replaced with doors with positive compressive seals. ▪ No means to illuminate the interior of the robot maintenance compartment in a powered-down (safe) state. ▪ Some items (e.g. power supplies) should not have been located inside containment. ▪ Inadequate sealing of the bag-out port during decontamination spraying operations. ▪ Inadequate glove and reach access for required maintenance activities.	May adversely impact operational safety, schedule, operating costs and leak risk.	Maintenance enclosures, tooling, and access features should: ▪ Design closure panels to provide required containment and confinement features for operating, maintenance, stand-by, and decontamination modes. ▪ Provide a separate power supply for maintenance activities when retrieval system power has been locked out. ▪ Whenever possible, locate support equipment outside containment to facilitate servicing and maintenance. ▪ Provide sufficient access to fully maintain and repair equipment.	ORNL GTRP Burks, et al 2001, & Falter 1997
A.3.1.12	Houdini-II system suffered from inadequate planning and preparations to effectively address needed maintenance and repair activities.	May adversely impact operational safety, schedule, operating costs and leak risk.	Develop a reliability/availability - based maintenance strategy utilizing qualitative failure mode effects and criticality analysis (FMECA) methodology. Verify that all required design requirements have been met and anticipated maintenance activities can be achieved in a safe manner consistent with good ALARA principles.	ORNL GTRP Burks, et al 2001, & Falter 1997

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.13	MLUDA/Houdini: A complete understanding of the needed maintenance and support tasks was not established prior to design of the tank riser interface compartment (TRIC). This resulted in the need to retrofit and modify TRIC after the fact.	May adversely impact operational safety, schedule, operating costs and leak risk.	Establish a life-cycle operating profile for the system to be deployed and identify required maintenance and support functions and requirements to be included in the technical basis for the retrieval project.	ORNL GTRP Providence Group 2001& Falter 1997
A.3.1.14	System integration issues with the deployment of the MLUDA/Houdini included: ▪ Failure of the tether cable system moisture protection seal; this limited the operation of the crawler to a maximum of 6-8 inches of sludge depth. ▪ Scarifying operations created aerosol-generated fog that rendered the cameras ineffective. ▪ Repeated hydraulic leaks due to incompatible hydraulic component fit-up. ▪ "Drifting" of the vertical positioning system due to use of hydraulic jacks. ▪ Inadequate strength capability of MLUDA during core sampling operations.	May adversely impact operational safety, schedule, operating costs and leak risk.	Systematically integrate project requirements to ensure performance objectives can be met with the deployed system of individual components and sub-systems. Examples would include: ▪ Adequate ventilation to ensure visual observation capability. ▪ Stable support systems with no excessive drifting during operations. ▪ Adequate hydraulic systems sealing capability. ▪ Reliable tether management process.	ORNL GTRP Providence Group 2001& Falter 1997
A.3.1.15	MLUDA maintenance systems (e.g. tank riser interface compartment or TRIC) and supporting equipment did not provide adequate features for effective maintenance. Examples include: ▪ Safety concerns that arose when the TRIC had to be open during testing of the gripper end effector (GEE) systems. This lead to a new design for GEE. ▪ Inadequate means to transfer tools and supplies to be transferred into TRIC.	May adversely impact operational safety, schedule, operating costs and leak risk.	Ensure that safety and ALARA requirements are addressed during design and deployment phases with particular emphasis on maintenance and support activities.	ORNL GTRP Providence Group 2001& Falter 1997

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.16	Logistics of crawler/deployment system (Houdini/MLUDA) operation in the tank identified important issues to address: ▪ An operational/logistics strategy needed to be established to coordinate crawler and sluicer operations below each riser. ▪ The sluicer typically cleared out an area for the crawler to initially operate from.	May adversely impact schedule, operating costs and leak risk.	Prior to initiation of design activities, establish: ▪ An operations and maintenance strategy for retrieval operations (contact or remote maintenance, etc.) ▪ Establish an operating strategy to coordinate crawler/slucier operations. ▪ Include applicable features as system design requirements.	ORNL GTRP Providence Group 2001& Falter 1997
A.3.1.17	Internal instrumentation should have been accessible without breaking containment.	May adversely impact schedule, operating costs and leak risk.	Where feasible, provide direct access to instrumentation systems without breaking containment.	ORNL GTRP Providence Group 2001& Falter 1997
A.3.1.18	Management and control of hydraulic fluids should have prevented oil from leaking into adjacent systems.	May adversely impact operational safety, schedule, operating costs and leak risk.	Provide engineered systems to safely manage hydraulic fluids under normal (operations and maintenance) and off-normal operations.	ORNL GTRP Providence Group 2001& Falter 1997
A.3.1.19	The multiple control system screens were too complex and busy for efficient/effective operations.	May adversely impact schedule, operating costs and leak risk.	Based on operational planning, integrate the control systems/user interface to provide effective means to conduct safe operations.	ORNL GTRP Providence Group 2001& Falter 1997

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.20	Air conveyance development testing without water injection resulted in: ▪ " ... *approximately ¼ in. of material coating the hose walls. It was necessary to convey water intermittently to keep material from building up on the hose walls*". In spite of these precautions, the system still plugged up. "*At this point a decision was made to install water injection to the nozzle*". The " *technology is a sound option for waste retrieval with some modification to the basic[commercial] design.*" ▪ "*It became obvious during testing that a water injection system is imperative to prevent hose plugging while conveying undiluted sludge....*" A system utilizing a water injection device at the feed nozzle and additional injection units placed along the hose runs will be necessary.	May adversely impact schedule, operating costs and leak risk.	If air conveyance is used, integrate water injection in the nozzle and the line. This is required to prevent sludge from building up on the walls and eventual plugging of the system.	Hanford Developmental Test Thompson 1990
A.3.1.21	Deployment of a confined sluicing end-effector in the ORNL Tank needed to be carefully managed ▪ to avoid premature submersion and possible plugging of end-effector nozzles. Low-pressure flushing of nozzles was not possible during deployment prior to full deployment of the support system masthead. ▪ to control higher pressure operation (>4,500 psi) which caused end-effector "bouncing" and position alarming and control system faulting. Tank wall scarifying, typically carried out at extremely high pressures, was limited by MLUDA's ability to counteract pneumatic forces above 20,000 psi.	May adversely impact schedule, operating costs and leak risk.	Possible plugging of end-effector nozzles should be addressed by: ▪ Carefully planning the deployment and operating sequence. ▪ Making provisions for in-tank recovery e.g. low-pressure flushing) in the event plugging does occur. High pressure operation should be addressed by ▪ Providing a means to counteract hydraulic loads and stabilize in-tank deployment structure to facilitate all phases of retrieval operations.	ORNL GTRP Lloyd, et. al. 2001

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.22	Successful retrieval operations with MLUDA/Houdini were made possible due to built-in system flexibility. For example, back-drivable joints allowed Houdini to drag the sluicing end-effector to the desired location. Most equipment could be operated in multiple modes (e.g. local versus remote, manual versus automatic). This permitted operations to adapt to varying conditions, maintenance needs, and testing requirements.	May positively impact schedule, operating costs and leak risk.	See item A.3.1.18 where it states: *"Provide engineered systems to safely manage hydraulic fluids under normal (operations and maintenance) and off-normal operations."*	ORNL GTRP Lloyd, et. al. 2001
A.3.1.23	The MLUDA/Houdini maintenance systems facilitated ready removal of key support system components to minimize hoisting and rigging, and space for lay-down while controlling contamination. Replacement of the retrieval system hose management assembly could be achieved without breaking tank vapor space containment. Decontamination of components during removal from the tank was achieved with "designed-in" elements integrated into the retrieval system. In addition end-of-shift flushing capability was also provided as part of the system.	May positively impact schedule, operating costs and leak risk.	See item A.3.1.16 where it states: *"Prior to initiation of design activities, establish:* ▪ *An operations and maintenance strategy for retrieval operations (contact or remote maintenance, etc.)* ▪ *Establish an operating strategy to coordinate crawler/slucier operations.* ▪ *Include applicable features as system design requirements."*	ORNL GTRP Lloyd, et. al. 2001

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.24	Various weaknesses were identified during the MLUDA/Houdini deployment consisting of operator ergonomics, maintenance issues, instrumentation deficiencies, and control system faults; these included: ▪ Glove box location and configuration limited tool handling, retraction, and maintenance operations. ▪ Lengthy and demanding process to deploy the main handling system (10 cable and 3 hose connections) ▪ Limited range/rotation of cable and hose management systems required periodic disassemble and reassembly of equipment. ▪ Replacement of a cable was necessary – made possible only because of a spare conduit was included in the design. ▪ "Coriolis" (FE-204) flow meter, was "completely ineffective" due to the highly dynamic 3-phase flow characteristics with significant "slugs" of air. ▪ Debris clogging the screen on the waste inlet. (However, this did prevent pump blockage.) ▪ Contamination traps in confinement box on tank riser. ▪ Inability to replace rupture disks. ▪ Poor seal design in the rotating end-effector. ▪ The control system was not capable of detecting a disconnected control cable; operations needed to de-energize and safely shut down system to conduct trouble shooting activities.	May adversely impact operational safety, schedule, operating costs and leak risk.	See item A.1.1.16 where it states: *"Provide engineered systems to safely manage hydraulic fluids under normal (operations and maintenance) and off-normal operations."* ▪ Provide visual assess for inspections ▪ Provide temporary power for maintenance ▪ Provide a variety of end-effectors to achieve performance objectives ▪ Mount flow instruments in vertical orientation to eliminate air pockets ▪ Provide for signal and control cable disconnection detection alarms.	ORNL GTRP Lloyd, et. al. 2001

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.25	During testing of the EMMA (Manufactured by GreyPilgrim, LLC). GreyPilgrim robotic manipulator, *"barrels used to receive conveyed waste imploded"*. This was the result of an instantaneous seal being made between the end-effector and surfaces of a waste tray *"because of high vacuum created"*. A scalloped hard rubber shroud used to prevent contact between the scarifier and the waste surface did not function well. *"One solution is to redesign the skirt"*. The possibilities include: ▪ Simple passive compliance via springs and contact shoe or caster to affect a compliant motion normal to the waste surface. ▪ A scalloped edge or other skirt design to allow proper airflow while maintaining contact with the waste surface. Other solutions might be: ▪ Active compliance proportional to ultra-sound surface distance feedback or vacuum sensor or tactile or capacitance sensor. ▪ Larger shroud (24"). ▪ Higher power blower. ▪ Hardened closed circuit digital cameras mounted at various points on arm to provide more information to operator." ▪ Use stronger drums. ▪ Use direct computer control of the e-stops to automate response instead of manual response.	May adversely impact schedule, operating costs and leak risk.	Establish (verify) methods to control vacuum suction and prevent loss of control suction cup (end-effector) distance to hard surface. These might include a variety of distance control systems, suction cup configuration, and vacuum rating of the components prone to damage.	Hanford HTI GreyPilgrim 1997
A.3.1.26	GreyPilgrim: Vacuum hoses "flattened along two locations and split in several others".	May adversely impact schedule, operating costs and leak risk.	Size the retrieval system hoses for the maximum vacuum and better strength to prevent collapse and splitting under vacuum.	Hanford HTI GreyPilgrim 1997.

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.27	GreyPilgrim: During testing, "... *it was observed that momentary setbacks or sudden stops in arm motion would lead to residual vibrations. These vibrations would generally take the form of free vibration response, a natural frequency of about 0.5 Hz, lightly damped (10 or 20%), and a peak to peak vibration of about 2 inches or so. This residual vibration is unacceptable for service unless it can be controlled. This could be mitigated by special operator action, which requires an extra skill. Another way to control this is through the control algorithm.*"	May adversely impact schedule, operating costs and leak risk.	Design and test the arm for the frequencies in the operation range and also design for proper vibration damping. To mitigate this effect, use experienced and well-trained operators and/or revise the control algorithm.	Hanford HTI GreyPilgrim 1997
A.3.1.28	GreyPilgrim: Limitations of the Deployment System - Issues regarding actual underground storage tank applications include: ▪ The ceiling above the tank (head space) should allow enough motion for the elevator movements. ▪ Allow adequate space for the actuator and its movements. ▪ Provide adequate space in the actuator room. ▪ Allow enough room so the pivot could be fully utilized.	May adversely impact schedule, operating costs and leak risk.	Design the system for adequate space for the elevator, pivot, and the actuator to be fully utilized.	Hanford HTI GreyPilgrim 1997.

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.29	Cybernex (France): ▪ A vital element for safe robotic operations is real-time response for "force-feedback" or tracking system applications. This requires highly responsive, good quality feedback, frequently with fragile components, operating in a very hazardous environment. ▪ *"An ill-designed cable management system can significantly impair the capabilities to perform tasks efficiently."* Some systems are being developed with reduced (eliminated) cabling systems. RF spread-spectrum or ultra sound technologies are being used to exchange data between the vehicle and controller.	May adversely impact operational safety, schedule, operating costs and leak risk.	▪ Consider response time as a performance parameter for feedback for tracking or force-feedback applications instrumentation. ▪ Identify and control critical operational requirements. ▪ Effective cable (umbilical, tether) management is critical for successful deployment of a robotic system. Consider alternate technologies to communicate with the robotic (remote system) device.	Non-DOE Cyber-netics Fidani 2001
A.3.1.30	Toshiba (Japan): Low-cost, high reliability robots with fewer degrees of freedom with relatively simple control systems are used to perform dedicated tasks. Collectively, these components accomplish complex tasks normally requiring a robot with many degrees of freedom (DOF) and a complex control system.	May positively impact schedule, operating costs and leak risk.	High reliability performance at relatively low cost robotic systems can be deployed using task-specific sub-systems requiring simpler control systems as an alternative to complex expensive multi-degree of freedom systems. Note – integrate with FMECA activities identified in section A.3.1.12: *"...Develop a reliability/availability - based maintenance strategy utilizing qualitative failure mode effects and criticality analysis (FMECA) ...".*	Non-DOE Toshiba FDH 1999

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.31	Development of the PIONEER crawler robot for Chornobyl applications identified several lessons learned and recommendations for future applications: ▪ Use of an on-board robot power distribution system would reduce the cross-section, weight, and stiffness of the tether. ▪ Place the highest priority on "operator ease" (e.g. remote viewing system).	May positively impact schedule, operating costs and leak risk.	Assess design trade-offs to enhance operability of remote system: ▪ Reduce tether weight and stiffness through careful selection of power distribution – even at the expense of robot weight and cost. ▪ Identify features early in the design phase to enhance operability of the system; manage these as high-priority objectives.	DOE/ NASA Chernobyl Osborn 2001
A.3.1.32	Pipeline Unplugging Technologies were tested with the conclusion that several viable alternatives are commercially available. One innovative approach from Atlantic Group's Hydrokinetics used sonic resonance together with high pressure water to clear plugged lines.	May positively impact schedule, operating costs and leak risk.	Integrate available pipe unplugging technology into the retrieval system as a contingency/recovery feature during operation.	DOE/ FL International University Sukegawa, et al 2001
A.3.1.33	PNNL developmental, non-intrusive, ultrasound sensor to measure density in air-entrained waste slurries. Designed to operate in flammable gas environments, this system has completed several laboratory tests and is scheduled to be installed on Tank 241-SY-101 at Hanford.	May positively impact schedule, operating costs and leak risk.	Assess performance applicability of ultrasound density sensor for 241-C-104 retrieval operations. Integrate into design as appropriate.	DOE PNNL Bamberger, et al 2001

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.34	Provides an alternative to run-to-failure mentality typical of a "corrective" maintenance philosophy which is in-appropriate where the consequence of failure is high [i.e. as in in-tank robotic applications such as 241-C-104]. Condition-based operations and maintenance (CBM) offers an approach less costly than preventive or predictive-based methods but more effective than corrective maintenance. Two key characteristics: ▪ Operations ownership in the need to recognize and correct the existence of an abnormal condition. ▪ Pro active identification, through root cause analysis, of the fundamental stressors (parameters outside the design envelope) responsible for off-design conditions.	May positively impact schedule, operating costs and leak risk.	Consider planning to implement condition-based operations and maintenance (CBM) methodologies concurrently with conceptual and definitive design to establish relationships between failure modes, stressors that could lead to system failure. Select and integrate appropriate sensors into the retrieval system design activity. Note – integrate with FMECA activities identified in section A.3.1.12: "*...Develop a reliability/availability - based maintenance strategy utilizing qualitative failure mode effects and criticality analysis (FMECA) ...*".	DOE NERI Jarrel 2001.

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.35	SRS lessons learned from deployment of a prototype "bagless" transfer system: ▪ Reliability - Schedule pressures resulted a "business decision" not to conduct reliability tests. A "demonstration" unit became the production unit and materials and parts wore out. This resulted in unplanned down time for repairs. ▪ Defense in Depth – insufficient process administrative and engineered controls led to undetected quality problems during operation. ▪ Training – Although a large investment was made during trouble shooting of problems, learning-curve challenges could have been more effective managed if more time had been spent with "…in-depth component specific training …. from….vendors..". In addition, operations and maintenance personnel should have been more involved with development, assembly, testing and troubleshooting. ▪ Resources – Too few engineers that were involved with deployment of the production unit stayed with the project through deployment and operation. This is a critical issue with first-of-a-kind development (or prototype) units.	May adversely impact schedule, operating costs and leak risk.	▪ Develop project and deployment planning with due consideration for reliability testing and process quality assurance. ▪ Address operator and maintenance personnel training and retention of key technical staff through the transition to operations with project "corporate history" to solve problems. Note – integrate with FMECA activities identified in section A.3.1.12: *"…Develop a reliability/availability - based maintenance strategy utilizing qualitative failure mode effects and criticality analysis (FMECA) …".*	SRS Bayer, et. al 2001

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.36	DNSFB TECH-30 identified several lessons learned which are applicable to any retrieval technology-based project: ▪ A comprehensive Preliminary Safety Analysis Report should be prepared to provide a basis for an integrated review of the facility design. This will avoid overly conservative assumptions, numerous activities to confirm the validity of early assumptions, and potential changes to the safety classification of components late in the project evolution. ▪ Thorough, timely, integrated design reviews during early phases of the project, including PSAR documentation, are necessary to avoid delays and excessive costs in later phases of the project. This should include development of matrices to assess compliance (design verification) with all applicable requirements. ▪ Effective implementation and management of quality assurance requirements for sub-contractors is necessary to avoid deficiencies with procured equipment (e.g. cleanliness requirements for valves, welding quality assurance) ▪ Preoperational test planning must ensure that appropriate rigor is provided to conduct and document tests. Emphasis should be placed on integrated tests rather than relying on tests of individual components and subsystems. Sufficient schedule should be provided to allow for recovery for failures or deficiency identification during testing.	May positively impact operational safety, schedule, operating costs and leak risk.	Develop project design/development construction and deployment planning with due consideration for design reviews (i.e. verification – including testing), quality and technical requirements management, and preliminary safety analysis early in the evolution of the project. Note – integrate with FMECA activities identified in section A.3.1.12: *"...Develop a reliability/availability - based maintenance strategy utilizing qualitative failure mode effects and criticality analysis (FMECA) ...".*	DOE DNSFB Hanford DNFSB 2001b.

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.37	The Year 2000 DNSFB report to Congress identified a number of lessons learned-type items for DOE implementation based on specific DOE-complex experiences that are applicable to 241-C-104 retrieval: ▪ Project design criteria were not prepared at the outset of the project. ▪ Failure to maintain storage tank chemistry within specified limits. ▪ Failure to assign ***system engineers*** (subject matter experts) to all safety processes and systems with: 1. Requisite knowledge of system safety design basis and operating limits from the safety analysis. 2. Lead responsibility for the configuration management of the design. ▪ Failure to impose appropriate safety requirement through procurement contracts. ▪ Failure to impose industry standards for reliability requirements for safety-related instrumentation and control systems.	May adversely impact operational safety, schedule, operating costs and leak risk.	Develop project and deployment planning with due consideration for: ▪ Project design criteria ▪ Maintain operating safety criteria within limits. ▪ Technical management of system safety requirements and associated configuration management of the design. ▪ Management of flow-down of quality and safety requirement to sub-contractors. ▪ Reliability standards for safety-related instrumentation and control systems. Note – integrate with FMECA activities identified in section A.3.1.11: *"...Develop a reliability/availability - based maintenance strategy utilizing qualitative failure mode effects and criticality analysis (FMECA) ...".*	DNSFB DOE-Complex DNSFB 2001a and DNFSB 2000
A.3.1.38	DNSFB recommendation for DOE criticality safety programs were for: ▪ More formalized and robust reviews to ensure requirements are met. ▪ Formalized surveillance, maintenance, and configuration control management process for those design features should be implemented.	May positively impact operational safety, schedule, operating costs and leak risk.	Develop project and deployment planning with due consideration for: ▪ Criticality safety reviews. ▪ Configuration management, surveillance, and maintenance of criticality safety design features.	DNSFB DOE-Complex DNSFB 2001

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.39	Rockwell Tank Farm experience from SST strontium retrieval operations in 1989-1990: ▪ Heavy duty, single-stage, centrifugal pumps built by Barrett Haentjens (Hazleton, PA) generally gave years of service under extreme operating conditions operating at 350 to 400 gallons per minute with SST heavy slurry. Bearings were water lubricated and completely isolated from the process liquids. ▪ Turbine-type pumps were used during final SST cleanout operations involving very low slurry concentrations, but were not suitable for the massive sludge transfers during normal sludge recovery operations. ▪ Pumps that provided long trouble free service in the AR-Vault transfer operation: single-stage, water-lubricated, centrifugal pumps, for sluicing and slurry transfer service; stainless steel, multi-stage, deep-well turbine pumps for clarified sludge. ▪ Standard Hanford deep-well turbine (TX-1) pumps were used to transfer thickened slurry. Service life was very short due to the abrasiveness of the slurry and the constant shaft and bearing stress produced by the powerful agitation in the tank and the resultant pump column flexing. Even heavy bracing of the pump columns could not alleviate the shaft breakage problem; the use of the standard pumps had to be discontinued.	May positively impact schedule, operating costs and leak risk.	▪ Applicable retrieval pump operational experience which led to successful operations with heavy sludge and low-concentration slurries. Consider need to fully characterize material to be retrieved to ensure successful pump operation.	Hanford Tank Farms Rasmussen 1980

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.40	During final SST sludge cleanout it became increasingly difficult to recover the sludge when the level in the tank decreased to a depth of 4 to 6 inches. More elaborate equipment and procedures were then required: ▪ Use of skirted, adjustable length slurry pumps to allow sluicing at the minimum liquid inventory essential for effective sludge recovery. ▪ Frequent in tank photography to chart sludge accumulation. ▪ Radiation monitors on sluice and slurry lines to measure sludge recovery. ▪ Carefully pre-planned sluicing strategies to move sludges toward the pump intake. ▪ Frequent sluicer direction changes to hit sludge concentrations from different angles. ▪ Fitting the intake of the slurry pumps with "funnels" to permit operation at low liquid levels; these funnels were massive enough to support the entire weight of the pump when necessary. High-pressure water nozzles were used to sluice the pumps into the sludge during initial installation. ▪ Aiming the sluicing nozzle precisely by means of a calibrated sluicer control unit calibrated head that provides for both horizontal and vertical adjustments and allows for accurate sluicing of the tank bottom area. The sluicer consisted of (1) high pressure water supply system, and (2) the nozzle aiming mechanism. ▪ The liquid level in the sluiced tank was kept as low as possible to maximize sluice stream penetration power.	May positively impact schedule, operating costs and leak risk.	Applicable retrieval pump operational experience: ▪ Sludge recovery technique for last 4-6 inched of tank bottoms. ▪ Instrumentation and surveillance methods to support retrieval. ▪ Sluicer positioning and operation.	Hanford Tank Farms Rasmussen 1980

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.41	SST sludge recovery was closely monitored with a radiation probe on the slurry line. After 1-2 days of sluicing, the tank would be pumped down and photographed to determine progress and the need for further sluicing. In some tanks the tank bottom was cleared to bare metal. In some cases the particles were so large sluicing was required to literally wear particles down. Because of the heat producing strontium present in the tank infrared scanner was used in a system developed by Barnes Engineering Corporation to make temperature profile plots of the tank	May adversely impact schedule, operating costs and leak risk.	Consider instrumentation and surveillance methods to support retrieval.	Hanford Tank Farms Rasmussen 1980
A.3.1.42	Feature Tests of a pneumatic Needle Scaler were conducted with various simulated waste configurations and on steel and masonry surfaces. These tests indicated that devices of this type can provide effective tools to facilitate retrieval. Deployment of a linear scarifying end-effector was not successful due to deployment difficulties resulting from inadequate integration into the overall retrieval "system".	Inadequate integration may adversely impact performance.	(see item A.3.1.14 regarding integration of required design elements into a system)	Hanford Tank Farms Squires 1990 and Fitzgerald 2001
A.3.1.43	Feature tests of Sine pumps indicated that the pump is capable of meeting the required pressure and flow at high viscosities. However, rapid wear with the soft (elastomer) components was experienced. Resolution of this will require additional development work. Feeding the pumps from the inlet hopper was another problem. Residue build-up on the interior hopper walls impeded flow of the product into the pump.	May adversely impact schedule, operating costs and leak risk.	The SINE pumps (positive displacement - used in the food industry) are capable of meeting retrieval flow and pressure requirements including ability to pump very viscous materials, but will require development of improved elastomer components.	Hanford Squires 1990a

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.44	The SRS structural integrity program conducted a comprehensive analysis of waste tanks and piping to assess past failures, failure mechanisms, and ageing effects. This resulted in some lessons learned applicable to SST retrieval activities. Many of these offer guidance for path-forward activities to avoid past system integrity issues that resulted on operational impacts and leaks to the environment.	May positively impact operational safety, schedule, operating costs and leak risk.	Develop project and deployment planning with due consideration for: ▪ Chemistry controls to avoid corrosive conditions. ▪ Chemistry monitoring to verify operation within control limits. ▪ Procurement and system operation. ▪ Use inspection processes to ensure structural integrity. ▪ Operational controls to prevent piping failures resulting from typical failure modes such as stagnant water, stress corrosion cracking, pitting, etc.	SRS SRS 1995

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.45	ORNL operation of the confined sluicing end effector (CSEE) in GAAT retrieved approximately 7,200 gal of supernatant above the sludge, 5,500 gal of sludge at the bottom of the tank, and 0.1 in of the scale from the tank wall. Less than 0.5% of the tank volume remained as a final residue waste. The retrieval of tank W-3 used 41,800 gal of water which was added to the waste stream, at a ratio of 3.3:1. This includes water used by the jet pump, flushing operations, and equipment decontamination. Approximately one third of the water was used for scarifying operations and two thirds was from jet pump operations.	Actual volume results in a radioactive waste environment.	Develop project and deployment planning with due consideration for: ▪ Reduced water usage through careful coordination of the activities. ▪ Riser access to accommodate equipment (for this demonstration 24" for Houdini &12" for MLDUA) [see A.3.1.11-15] ▪ Accommodation of in-tank to access all tank locations. ▪ Verification that any additional tank dome loads are within safety allowables. ▪ The addition of a "holster" to provide temporary parking of the CSEE. ▪ Provisions for a means to clear the conveyance inlet screen. (Back flushing with low pressure is not effective and uses a significant amount of water.)	ORNL GATT TFA 1999

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.46	The Hanford Tanks Initiative contracted to conduct feature tests designed to establish a better understanding of the technical challenge ahead for deployment of retrieval systems in tanks. ▪ The maneuverability of the tracked vehicle seemed to have an edge over the wheeled vehicle, whereas the wheeled vehicle seemed to have superior ability to get unstuck. The wheeled vehicle was superior to the tracked vehicle in dislodging and breaking up material. ▪ The complex control system in the wheeled vehicle needed to be redesigned to give the operator simpler controls. ▪ The tracked vehicle was jammed repeatedly with small rocks in its tracks; these were successfully un-jammed. A very hard object in a track created a failure mode from which recovery was difficult; the wheeled vehicle mobility and its ability to recover from a failed condition appear to be much better. ▪ A vehicle was weighed before and after decontamination where it was determined that 27 lbs of waste material was removed with 2 lbs remaining. Hold-up of material was worse for the tracked vehicle. ▪ It would be desirable to have multiple tank cameras, all equipped with zoom, pan ,and tilt, so the operator could view the work area no matter where the vehicle was in the tank.	May adversely impact schedule, operating costs and leak risk.	Applicable retrieval pump operational experience: ▪ Ensure that a tracked vehicle if used can be effectively maneuvered in the SSTwaste material, and decontaminated. ▪ Verify system availability (reliability/maintain-ability) will support deployment objectives; an effective means for recovery from faulted (stuck) conditions needs to be provided. ▪ Lighting and camera systems need to be able support operations throughout the tank and under all operating conditions (mist, fog, - see A.3.1.14 and 48) ▪ Operator training should be provided before deployment to ensure efficient in-tank operations and verify operator/ machine interface needs. (See A.3.1.35) Note – integrate with FMECA activities identified in section A.3.1.11: "*...Develop a reliability/availability - based maintenance strategy utilizing qualitative failure mode effects and criticality analysis (FMECA) ...*".	Hanford HTI Berglin, et. al 1997

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.47	Hanford Tanks Initiative Vehicle Based Waste Retrieval (non-radioactive) Demonstration Report provided information from feature tests regarding in-SST vehicle operation: ▪ A 100-ft long umbilical was intentionally dragged against the simulated risers to prove the ability a Trac-Pump to negotiate riser obstacles. Minimum bend radius of the umbilical under power of the Trac-Pump was 3 ft. The turn radius of the Trac-Pump assembly was 8 ft. Fifty feet of 5-inch tank-car hose was retrieved and deployed 3 times. ▪ Solids concentration in the waste determined the amount of make-up water required, partial re-circulation of the discharged slurry could be used to minimize the amount of make up water required. A grinder type re-circulation pump could be used to further process the solids. ▪ The back flush system was tested by intentionally blocking the discharge manifold with salt cake; it was unplugged within 1 minute with a 13-gpm 2000psi water jet. The second section was blocked with hardpan and took 3000 psi pressure to unblock it. ▪ Tests were conducted to identify additional features to facilitate assembly, maintenance, and decontamination. The need for a maintenance schedule was identified to verify that all necessary design features have been identified.	May adversely impact schedule, operating costs and leak risk.	Applicable retrieval pump operational experience: ▪ Umbilical system operating characteristics. ▪ Re-circulating water utilization. ▪ Pump inlet back flushing characteristics. ▪ Design for maximum system operational availability.	Hanford HTI ESG, L.L.C. 1997

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.48	A comprehensive report is available documenting sluicing Hanford operations for 43 tanks from 1952-1957, 10 tanks from 1962-1978 as well as rail cars and several other S-farm tanks. This provides a history of sluicing operations including sludge and heel removal and information regarding equipment (including pumps) failure histories and clean-out time cycles. Of particular interest are the methods used to control fogging and misting to improve the visibility inside the tanks during operations.	May adversely impact schedule, operating costs and leak risk.	Develop project and deployment planning using this operational and equipment performance history as a basis to make key conceptual and definitive design decisions. This would be useful information to support FMECA activities identified in section A.3.1.12: "*...Develop a reliability/availability-based maintenance strategy utilizing qualitative failure mode effects and criticality analysis (FMECA)...*".	Hanford Tank Farms Rodenhizer 1987
A.3.1.49	The Easily Manipulated Mechanical Arm (EMMA) used FMECA and RAM risk analysis methods as design tools. "*.....The level of analysis and documentation has to commensurate with their relative importance to safety, risk, complexity of the activity, equipment life cycle, and their importance to the key functional goals. The Failure Mode and Effect Analysis (FMEA) and Reliability, Maintainability, and Availability (RMA) have been done systematically. ....., the probability and consequence of failures are evaluated and the risk factors are calculated for the systems, structures and components. Then the risk factors are translated to performance grade. With five grade levels, (PG-1 requiring the highest level of control and management), it has been determined that the deployment tower qualifies for PG-4 and the other systems and structures are PG-5. The system should provide a 10-year operating life with MTBF of 1,000 hr.....*"	May adversely impact operational safety, schedule, operating costs and leak risk.	Use FMECA and RAM as design tools to meet functions and requirements. See also section A.3.1.12 "*.... Develop a reliability/availability-based maintenance strategy utilizing qualitative failure mode effects and criticality analysis (FMECA)...*".	Huang, et al

Table A-1 Operating Effectiveness

Section A.3.1	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.1.50	Resolution of the 241-SY-101 Surface Level Rise issue was achieved using traditional project management methods and tools. These consisted of planning the work, assigning a dedicated team, managing change control, tracking performance measures to closure, and documenting close-out of the work. Specific steps contributing to the success of this effort included: ▪ Assembling a dedicated project team with clear roles and responsibilities, schedule, and objectives. ▪ Measurable performance objectives. ▪ Characterization of interfaced and operational constraints. ▪ Rigorous and timely change control. ▪ Building consensus with client (including operations) , oversight organization, and project team participants. ▪ Effective and frequent communication with team members.	May adversely impact schedule, operating costs and leak risk.	Attributes for a successful project include: ▪ Defined scope managed through change control. ▪ Dedicated team, co-located, participating in frequent (daily) status meeting. ▪ Detailed WBS and resource-loaded schedule with no activity longer than 2 weeks. ▪ Cost estimated based on detail planning. ▪ Defined design process (including design verification). ▪ Pre-deployment testing of equipment and training of operators. ▪ Performance metrics defined and measured. ▪ Strict configuration management of the technical baseline (scope, schedule, technical basis). ▪ End state clearly defined and achieved.	CHG 2001a and CHG 2001b
A.3.1.51	The 241-AZ-101 Mixer Pump lessons learned identified items applicable to planned 241-C-104 retrieval: ▪ A realistic, resource-loaded schedule should be developed and staffed accordingly. ▪ Design issues that should have been addressed early impacted the reliability of the mixer test systems and equipment. ▪ Investing more resources (funding) up-front in the project would have resulted in fewer problems during testing.	May adversely impact schedule, operating costs and leak risk.	Efforts need to be made to: ▪ Provide a realistic schedule, resource-loaded to provide realistic support to Project activities. ▪ Develop a cost estimate based on detail planning; provide staff resources accordingly. ▪ Implement a rigorous design process to ensure reliable system performance.	Hanford AZ-101 CHG 2001b

Table A-2 Residual Waste/ Retrieval Effectiveness

Section A.3.2	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.2.1	Sluicer performance in large waste tanks has not met expectations due to inadequate verification of performance prior to deployment. This has been compromised further due to "de-tuning" of the sluicer system in an attempt to: ▪ reduce aerosols/evaporation resulting in gas in the mass flow meter ▪ reduce moisture on the in-tank surveillance cameras Failure to systematically integrate various sub-systems will result in less than adequate performance of the retrieval system.	Adverse impact on retrieval effectiveness and potential for leaving more residual waste than planned.	Verify (through modeling, reliability analysis, feature testing, or other suitable methods) that the design of the sluicer assembly will meet performance and maintenance criteria.	ORP W-320 Bailey 2000.
A.3.2.2	▪ Waste mobilization predictions based on core-sampling information have been determined to be invalid. ▪ Excessive dispersion (ineffective "straightening") of the sluice stream resulted in less than adequate performance.	Adverse impact retrieval effectiveness and potential for residual waste.	Methods to mobilize tank waste need to be verified prior to acceptance of the final design for procurement.	ORP W-320 Bailey 2000.
A.3.2.3	Although crawler system performance was severely limited due to reliability issues such as tether seal leaks, intermittent tether electrical problems and loss of one degree of freedom of MLUDA, the collective system was robust enough to achieve performance goals.	Positive result with confined sluicing/ robotic retrieval technology.	Provide redundant means to achieve performance goals through contingency planning and robust system design. [see associated FMECA recommendations in Table A-1]	ORNL GTRP Providence Group 2001

Table A-2 Residual Waste/ Retrieval Effectiveness

Section A.3.2	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.2.4	Partial submersion of the confined sluicing end-effector offered the best means to avoid 3-phase (solid, liquid, gas) pumping. For the last 1-3 inches of waste retrieval, the Houdini collected and plowed "waves" of waste to the end-effecter.	Adverse impact to retrieval effectiveness and potential for residual waste.	Retrieval pumping performance and confined sluicing operation should be integrated to establish the design-basis operation profile to achieve performance objectives. (See also A.3.1.40 and A.1.3.41) *Applicable retrieval pump operational experience:* ▪ *Sludge recovery technique for last 4-6 inched of tank bottoms.* ▪ *Instrumentation and surveillance methods to support retrieval.* ▪ *Sluicer positioning and operation.*	ORNL GTRP Lloyd, et. al. 2001

Table A-2 Residual Waste/ Retrieval Effectiveness

Section A.3.2	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.2.5	Various weaknesses were identified during the MLUDA/Houdini deployment consisting of ergonomics, maintenance issues, instrumentation deficiencies, and control system faults: ▪ Glove box location and configuration limited tool handling, retraction, and maintenance operations. ▪ Lengthy and demanding process to deploy the main handling system (10 cable and 3 hose connections) ▪ Limited range/rotation of cable and hose management systems required periodic disassemble and reassembly of equipment. ▪ Replacement of a cable was necessary – made possible only because of a spare conduit included in the design. ▪ Coriolos (FE-204) flow meter, was "completely ineffective" due to the highly dynamic 3-phase flow characteristics with significant "slugs" of air. ▪ Debris clogging the screen on the waste inlet. (However this did prevent pump blockage.) ▪ Contamination traps in confinement box on tank riser. ▪ Inability to replace rupture disks. ▪ Poor seal design in the rotating end-effector. ▪ Inability of the control system to detect a disconnected control cable; need to de-energize and safely shut down system.	Adverse impact to retrieval effectiveness and potential for too much residual waste.	See item A.3.1.18: *"Provide engineered systems to safely manage hydraulic fluids under normal (operations and maintenance) and off-normal operations."* Also, provide: ▪ Visual access for inspections ▪ Temporary maintenance power inside and outside glove boxes. ▪ Various end-effectors to achieve performance objectives. ▪ Contamination and corrosion control in high-humidity environments. ▪ "Tune" end-effectors to achieve maximum performance per unit time (e.g. diverging verses converging jets). ▪ Trade off higher jet pressures for control of airborne mist. ▪ Umbilical management optimization (including decontamination and tensioning monitoring systems). ▪ Consider using crawler to position the end-effector. ▪ Establish realistic need to upgrade existing tank farm support systems.	ORNL GTRP Lloyd, et. al. 2001

Table A-3 Leak Detection Section

Section A.3.3	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.3.1	A Gas Pressure Decay (GPD) method was used to test portions of the pressurized transfer piping of a Low Level Liquid Waste System at Oak Ridge National Laboratory (ORNL). This method analyzed the pressure decay rate of a gas introduced into the selected pipeline and expressed results in terms of an equivalent liquid leak rate. This system could measure a leak as small as .1 gal/hour with a probability of detection greater then 95% and a probability of false alarm less than 5%.	Candidate leak detection system for pipe lines between tank 104-C and receiver tank.	Could be a form of leak detection for the transfer lines provided the lines can be pressurized.	ORNL Starr, et al, 1993
A.3.3.2	Liquid integrity test of rusty carbon steel pipelines revealed sufficient integrity to allow GAAT to evaporator transfer. This allowed the project to use the pipeline avoiding the need for a new line resulting in savings in both cost and schedule.	Use existing equipment is qualified to be sound	Verify need for new, replacement lines prior to initiating design and fabrication of new equipment, test to determine if the exciting system is sound.	ORNL Ref. 98

Table A-3 Leak Detection Section

Section A.3.3	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A3.3.3	Items from Table A-1 *Operating Effectiveness* applicable to *Leak Detection*: A.3.1.12 A.3.1.16 A.3.1.17 A.3.1.31 A.3.1.34 A.3.1.35 A.3.1.37	May adversely impact Leak Detection Performance.	▪ *Establish an operation and maintenance strategy and integrate detection system operation.* ▪ *Where feasible, provide direct access to instrumentation systems without breaking containment.* ▪ *Identify features early in the design phase to enhance operability of the system...* ▪ *Implement planning to establish condition-based operations and maintenance (CBM) ...* ▪ *Develop project and deployment planning with due consideration for reliability testing and process quality assurance.* ▪ *Address operator and maintenance personnel training and retention of key technical staff...* ▪ *Management of flow-down of quality and safety requirements...* ▪ *"...Develop a reliability/ availability-based maintenance strategy utilizing FMECAs ...".*	

Table A-3 Leak Detection Section

Section A.3.3	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.3.4	The performance standard for tank tightness testing is established by the U.S. Environmental Protection agency. The standard was developed to address tanks nominally 8,000 to 10,000 gals in capacity or less. To meet regulatory standards for tank tightness testing of petroleum fuel tanks, volumetric leak detection systems must be able to accurately compensate for thermally induced volume changes in the stored fuel. A field study was done to investigate the magnitude of these volume changes with the following results: • Current procedures used to compensate for temperature when testing smaller tanks will not suffice for larger tanks. • The number of temperature sensors must be sufficient that the volume of product in the liquid layer around each sensor is not to great • Duration of testing must be long enough to measure the fluctuation of temperature after additions or subtractions of product and that the precision of the temperature and level instrumentation is sufficient to measure a leak. • An accurate experimental estimate of the constants is necessary for converting level and temperature changes to volume. • A waiting period of approximately 24 hour after addition of product is required to equalize the temperature	Performance criteria for level indication and temperature sensors to be used to monitor the waste level.	Baseline information is required on the physical characteristics of the tank contents. Temperature sensors should be installed 3 inches from top of liquid and bottom of tank and every 6-12 inches through the liquid. Wait at least 24 hours for horizontal gradient in rate of change of temperature to dissipate. Use the most precise temperature and level measurement systems available. Measure the coefficient of thermal expansion experimentally. Determine the height to volume conversion factor level measurements to volume measurements experimentally.	US-EPA Maresca, et al, 1993

Table A-4 Leak Monitoring Section

Section A.3.4	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.4.1	Tank leak monitoring of the GAAT provide the following information • Stratification of waste in tanks caused stratification of conductivity readings used to determine a base line for external monitoring • For external leak monitoring utilizing dry wells, the dry wells should be clear of debris • During baseline activities for external tank leak monitoring utilizing waste conductivity, evaluate and document rainwater impacts.	Dry well would be required and location would have to be evaluated to determine best location	Evaluate the overall conductivity of a tank for baseline and dry well conditions prior to insertion of conductivity instrumentation. Baseline information should be gathered over a period of time that would incorporate changes due to outside conditions (i.e. rain)	ORNL ORNL 1996, ORNL 1997, and ORNL 1997a
A.3.4.2	An un-answered low-level alarm resulted in fines to ORNL. Indications for the liquid level in tank WC-9 dropped from about 1000 gallons to zero gallons within a 24-hour period due to instrumentation error. A low-level alarm sounded and was not addressed for 36 hours because "false alarms are common place". These false alarms tended to be ignored.	Evaluate the instrumentatio n that will be used on tank 241-C-104 and determine its susceptibility to false alarms	Design the system to operator interface to facilitate immediate response to all alarms; develop instrumentation to minimize false alarms	ORNL Ref. 98
A.3.4.3	A common method for the detection of small leaks in pressurized underground storage tank pipelines containing petroleum is based on monitored pressure in the line. It has been documented that changes in pressure, taking into account temperature variations, can detect a leak of less than one gal/hr. With sufficient information about the physical configuration of the system, the pressure history in the pipeline can be predicted. Establish a baseline prior to initiating retrieval operations. Characterization of the physical properties of the material to be retrieved is crucial to design and operation of a monitoring system.	Leak monitoring system effectiveness.	Verify through analysis and testing that the level of waste characterization is appropriate for the leak monitoring system technology selected.	Indus-trial Appli-cation Maresca, et al 1990

Table A-4 Leak Monitoring Section

Section A.3.4	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A3.4.4	Items from Table A-1 *Operating Effectiveness* applicable to *Leak Monitoring*: A.3.1.12 A.3.1.16 A.3.1.17 A.3.1.31 A.3.1.34 A.3.1.35 A.3.1.37	May adversely impact Leak Monitoring Performance.	▪ *Establish operation and maintenance strategy and integrate detection system operation.* ▪ *Where feasible, provide direct access to instrumentation systems without breaking containment.* ▪ *Identify features early in the design phase to enhance operability of the system...* ▪ *Implement planning to implement condition-based operations and maintenance (CBM) ...* ▪ *Develop project and deployment planning with due consideration for reliability testing and process quality assurance.* ▪ *Address operator and maintenance personnel training and retention of key technical staff...* ▪ *Management of flow-down of quality and safety requirements...* ▪ *"...Develop a reliability/ availability -based maintenance strategy utilizing FMECAs ...".*	

Table A-5 Leak Mitigation/ Response Section

A.3.5	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A.3.5.1	Pipe line (WC-10) at Oak Ridge National Laboratory was shut down due to delays in reporting a potential leak. The Tennessee's TDEC (state environmental agency) ordered ORNL to shut down in order to remediate the leak	Need for an effective working relationship with regulators is essential to maintaining cost and schedule	Conduct regular liquid integrity tests and report results in a timely manner.	ORNL Ref. 98
A.3.5.2	An adversarial relationship between ORNL and TDEC was eased by open dialog regarding leak test program. Long standing mistrust between TDEC and MMES limited interactions. Leak Indication program for ORNL allowed open discussion of data and data collection facilities. This openness smoothed the MMES-TDEC relationship.	Need for effective working relationship with regulators is essential to maintaining cost and schedule	Provide a path for effective communication between regulators and technical staff.	ORNL Ref. 98

Table A-5 Leak Mitigation/ Response Section

A.3.5	Lesson Learned from Source/ Reference	Relevancy to 241-C-104 Retrieval	Considerations for Design and Operation	Source/ Reference
A3.3.3	Items from Table A-1 *Operating Effectiveness* applicable to *Leak Mitigation/Response*: A.3.1.12 A.3.1.16 A.3.1.17 A.3.1.31 A.3.1.34 A.3.1.35 A.3.1.37	May adversely impact Leak Mitigation/ Response Performance.	▪ *Establish operation and maintenance strategy and integrate detection system operation.* ▪ *Where feasible, provide direct access to instrumentation systems without breaking containment.* ▪ *Identify features early in the design phase to enhance operability of the system...* ▪ *Implement planning to implement condition-based operations and maintenance (CBM) ...* ▪ *Develop project and deployment planning with due consideration for reliability testing and process quality assurance.* ▪ *Address operator and maintenance personnel training and retention of key technical staff...* ▪ *Management of flow-down of quality and safety requirement...* ▪ *"...Develop a reliability/ availability-based maintenance strategy utilizing FMECAs ...".*	

Document Source Bibliography – For Lessons Learned

ALARA Review, *Post Job ALARA Review for Campaign I and II sluicing of C-106 and E-1116*

Alzheimer et. al 2001, *Crawler for U-Plant Drain Line Inspection,*

Arnold 1977, "Scumbuster" Pump Test Series Analysis, ARH-CD-935, Atlantic Richfield Hanford Company, Richland, Washington.

Arnold 1978, ***Fabrication and Testing of an Experimental Slurry Elevator for Use Within Single Shell Hanford Waste Tanks*, RHO-CD-273, Rockwell Hanford Operations, Richland, Washington.**

Asercion, et al 2000, *AZ-101 Mixer Pump Test Project Lessons Learned*, R. Asercion, W. Scott, and R. Kummer

Bailey 1999, *Waste Retrieval Sluicing System (WRSS) Jumper Assessment and Lessons Learned LL Document*, HND-4402, Rev. 0, Lockheed Martin Hanford Corp., Richland, Washington.

Bailey 2000, *Waste Retrieval Sluicing System (WRSS) and Project W-320 Tank 241-C-106 Sluicing Lessons Learned,* RPP-5687, Rev 0, CH2M Hill Hanford Group, Inc. , Richland, Washington

Bamberger, et al 2001, *Development of an Ultrasonic Sensor to Measure Density of Radioactive Waste Slurries During Pipeline Transport,* Pacific Northwest National Laboratories, Richland, Washington.

Bayer, et. al 2001, *Savannah River Sire Bagless Transfer – What have we learned?*, Westinghouse Savannah River Company, Aiken, South Carolina.

Berglin, et. al 1997, *Hanford Tanks Initiative, Fiscal Year 1997, Retrieval Technology Demonstrations*, HNF-SD-HTI-RPT-001, SGN Eurisys Services Corporation and Pacific Northwest National Laboratory, both of Richland, Washington.

Bogen 2000, *Site Visitation Notes* ,Holmes & Narver/DMJM, Richland, Washington

Burks, et al 2001, ***Lessons Learned and Final Report for Houodini Vehicle Remote Operations at ORNL***

CHG 2000, *Annual Progress Report on the Development of Waste Tank Leak Monitoring Activities in Support of M-45-08*, RPP-7012, U.S. Department of Energy, Office of River Protection, Richland, Washington.

CHG 2001, *F&R for 241-C-014 Waste Retrieval System, W-523*, RPP-6525 Rev 0,

CHG 2001a, *Lessons Learned Bulletin (CH2M Hill), The disciplined application of effective project management practices will result in project excellence*, #GP-01-02, CH2M Hill Hanford Group, Inc., Richland, Washington.

CHG 2001b, *Submittal for 2001 Project of the Year, SY-101 Surface Level Rise Remediation Project*, RPP-7657, CH2M Hill Hanford Group, Richland, Washington.,

Deeds, et al 1999, *Difluoromethane as a partitioning tracer to estimate vadose saturations.* L Env Engineer, in press.

Delphinus Engineering 1997, *Final Test Report – Deomonstration Testing in Support of the Track 3 System Waste Dilodgin, Retrieval and Conveyance Concepts*, HNF-MR-0543 Rev. O, Lockheed Martin Hanford Corp., Richland, Washington.

DNFSB 2000, *Defense Nuclear Facilities Safety Board Recommendation 2000-2 to the Secretary of Energy (pursuant to 42 U.S.C. 2286a(a)(5))*, Defense Nuclear Facilities Safety Board, Washington, D.C.

Document Source Bibliography – For Lessons Learned

DNFSB 2001b, ***Safety Review of the Hanford Spent Fuel Project During the Design and Construction Phase*, DNSFB/TECH-30, Defense Nuclear Facilities Safety Board, Washington, D.C.**

DNSFB 2001, *Criticality Safety at Department of Energy Defense Nuclear Facilities*, DNSFB/TECH-29, Defense Nuclear Facilities Safety Board, Washington, D.C.

DNSFB 2001a, *Eleventh Annual Report to Congress*, Defense Nuclear Safety Facilities Board, Washington, D.C.

ESG, L.L.C. 1997, ***HTI Vehicle-Based Waste Retrieval Demonstration Report Phase II, Track 2*, HNF-MR-0544 Rev 0, Lockheed Martin Hanford Corporation, Richland, Washington.**

Falter 1997, ***Houdini Remotely Operated Vehicle System Performance Assessment for Tank W-3 Waste Removal Operations.***

Farwick 2001, ***Memo- Lessons Learned LDMM*, Visa Engineering Technologies, L.L.C., Richland, Washington.**

FDH 1999, *1999 Leak Detection, Monitoring, and Mitigation Strategy Update*, HND-SD-WM-ES-378, Rev. 2, Fluor Daniel Hanford, Inc., Richland, Washington.

Fidani 2001, *The Challenges of Industrial Remotely Operated Systems for the 21st Century.*

Fitzgerald 2001, *Linear Scarifying End-Effector Developed for Wall Cleaning in Underground Storage Tanks*, Oak Ridge National Laboratory, Oak Ridge, Tennessee. .

Foster Wheeler 1995, *Technology Issues Related to Single-Shell Tank Waste Retrieval Leak Detection, Monitoring, and Mitigation: Final Report*, FWRD-WHC/4344-L95-085, Westinghouse Hanford Company, Richland, Washington.

Gauglitz, et al 1995, *DNAPL Characterization Using Tracer Test for Detection, Estimation and Remediation Performance Assessment of Subsurface Nonaqueous Phase Liquids*, Water Resources Res. Richland, Washington.

Gauglitz, et al 2000, *DNAPL Characterization Using Short-Lived Radiotracers in Partitioning Interwell Tracer Tests*, Remediation of Chlorinated and Recalcitrant Compounds, 2nd International Conference, Monterey, California.

Gibbons 1993, *Review of Prior Single-Schell Tank Waste Retrieval Process Studies*, WHC-SD-WM-ES-252, Westinghouse Hanford Company, Richland, Washington.

Gibbons 2001, ***Overview of the Tanks Focus Area HLW Tank Retrieval activities (Remote Operations)*, Numatec Hanford Corporation, Richland, Washington.**

GreyPilgrim 1997, *Hanford Tanks Initiative Alternative Retrieval System Demonstrations – Final Report of Testing Performed by GreyPilgrim LLC*, HNF-MR-0545 Rev 0, Lockheed Martin Hanford Corporation, Richland, Washington

Hatchell, et al 2001, *Russian Pulsating Mixed Pump Deployment in the GAAT at ORNL.*

Hayden 1997, *High Performance CLSM Field Mixing and Pumping Test Results*, WSRC-RP-97-272, Westinghouse Savannah River Company, Aiken, South Carolina..

Hertzel 1996, *Operational Tank Leak Detection and Minimization During Retrieval*, WHC-SD-WM-377, Westinghouse Hanford Company, Richland, Washington

Document Source Bibliography – For Lessons Learned

Hertzel 1996, ***Trade Study of Leakage Detection, Monitoring, and Mitigation Technologies to Support Hanford Single-Shell Waste Retrieval*, WHC-SD-WM-ES-379, Westinghouse Hanford Company, Richland, Washington.**

HND 2000, *Leak Detection, Monitoring, and Mitigation Design Concepts Evaluation Report for Sluicing-Based Retrieval Technologies*, RPP-6795 Rev 0 DRAFT, Holmes & Narver/DMJM, Richland, Washington.

Huang, et al , *Design of a 52.5 Foot Hyper-Redundant Serpentine Style Manipulator and Its Deployment Tower*, GreyPilgrim Inc., Rockville, MD

Jacobs 1998, *Hanford Site SST Retrieval Optimization Studies Support to Development of SST Retrieval Strategy, Draft Letter Report #4, Evaluate Relationship Between Retrieval Parametrics and Evaluation Metrics*, Lockheed Martin Hanford Corporation, Richland, Washington

Janicek 1981, *Equipment Development Study for Hydraulic Recovery of Single Shell Tank Sludges*, RHO-CD-1533, Rockwell Hanford Operations, Richland, Washington.

Jarrel 2001, *Remote Prognostics for Nuclear Plant ECCS Systems*, Pacific Northwest National Laboratories, Richland, Washington.

Jin, et al 1995, *PartitioningTracer Test for Detection, Estimation and Remediation Performance Assessment of Subsurface Nonaqueous Phase Liquids*, Water Resources Res 31(5):1201-1211

Krieg, et. al, 1990, *SST Waste Retrieval Study*, 1990, WHN-EP-0352-US-721, Westinghouse Hanford Company, Richland, Washington

Lloyd, et. al. 2001, *Performance Assessment if the Waste Dislodging and Conveyance System During GAAT Remediation Project.*

LMHC 1999, *Process Control Procedure for W-320*, HNF-SD-WM-PLP-013, Rev 2, Lockheed Martin, Hanford, Company, Richland, Washington.

Maresca, et al 1993, *Evaluation of Volumetric Leak Detection Systems for Large Underground Tanks*, 34(1993) 335-361, Journal of Hazardous Materials, Amsterdam.

Maresca, et al 1990, *Pressure and Temperature Fluctuation in Underground Storage Tanks Pipelines Containing Gasoline*, 29-56, Vista Engineering, California and U.S. Environmental Protection Agency, New Jersey

Morse, et al 1996, *Simulated Liquid Release Demonstration on Gunite Tanks W-3 and W-4 in the North Tank Farm*, Technical Report 1060-TR-96-001. .

ORNL 1996, ***Preliminary Evaluation of Liquid Integrity Monitoring Methods for Gunite and Associated Tanks at the Oak Ridge National Laboratory, Oak Ridge, Tennessee*, ORNL/ER-349, U.S. Department of Energy, Office of Environmental Management, Washington, D.C.**

ORNL 1997, ***Evaluation and Montoring Plan for Consolidation Tanks: Gunite and Associated Tanks Operable Unit, Waste Area Grouping 1, Oak Ridge National Laboratory, Oak Ridge, Tennessee*, ORNL/ER-396, U.S. Department of Energy, Office of Environmental Management, Washington, D.C.**

ORNL 1997a, *Baseline Monitoring and Simulated Liquid Release Test Report for Tank W-9, Oak Ridge National Laboratory, Oak Ridge, Tennessee*, ORNL/ER-410, U.S. Department of Energy, Office of Environmental Management, Washington, D.C.

ORNL 1998, *An Assessment of Liquid Integrity and Minimum Detectable Leak Rate for Gunite Tanks W-8, W-9, and W-10 (July 1997 through January 1998)*, Oak Ridge National Laboratory, Oak Ridge, Tennessee.

Document Source Bibliography – For Lessons Learned

Osborn 2001, *Opportunities and Challenges in the Development of Pioneer*, Carnegie Mellon University, et. al.

Pacquet, E. A. 1999, *Project W-320 Tank 241-C-106 Lessons Learned*, Numatec Hanford Company, Richland, Washington.

Providence Group 2001, *System Review of the MLDUA After the Completion of the ....Waste Removal.... At ORNL*

Rasmussen 1980, *Hanford Radioactive Tank Cleanout and Sludge Processing*, RHP-ST-30, Rockwell Hanford Operations, Richland, Washington.

Rodenhizer 1987, *Hanford Waste Tank Slucing History*, SD-WM-TI-302, Westinghouse Hanford Company, Richland, Washington.

Shimamura et al 2001, *Underwater Robotic System for Preventive Maintenance of Core Chroud by Laser Peening*

Squires 1990, *Feature Test of Sine Pump*, WHC-SD-ER-TRP-003, Westinghouse Hanford Company, Richland, Washington.

Squires 1990a, *Feature Test of the Pneumatic Needle Scaler*, WHC-SD-ER-TRP-002, Westinghouse Hanford Company, Richland, Washington.

SRS 1995, *SRS High Level Waste Tank and Piping Systems – Structural Integrity -Program and Topical Report (U)*, WSRC-TR-95-0076, Rev 0, Westinghouse Savannah River Company, Aiken, South Carolina.

Starr, et al, 1993, *Performance Evaluation of a Gas Pressure Decay Test for Detecting Leaks in LLLW Transfer Pipelines*, Technical Report 1040-TR-93-015, Vista Research, Inc., Mountain View, California.

Sukegawa, et al 2001, *Equipment Tests of Pipeline Unplugging Technologies on the Full-Size Test Beds*, Hemispheric Center for Environmental Technology, Florida and U.S. Department of Energy Tank Focus Area, Richland, Washington.

TFA 1999, *Confined Slucing End Effector*, DOE/EM-0372, U.S. Department of Energy, Office of Environmental Management, Washington, D.C.

Thompson 1990, *Feature Test of Air Conveyance Concept Review*, WHC-SD-ER-TRP-001, Westinghouse Hanford Company, Richland, Washington.

Treat, R., B. Peters, FWRD-WHC/4344-L-96-038, *Trade Study of LDMM Technologies Available for Support of Hanford SST Waste Retrieval by Sluicing*, Foster Wheeler Environmental Corporation, dated May 1996, (see also WHC-SD-WM-ES-379, Rev. 0).

Virto 1975, *Evaluation and Adaptation of Standard Mechanical Hydraulic and Pneumatic Devices for Saltcake and Sludge Retrieval at Hanford*, VITRO-R-375, Atlantic Richfield Hanford Company.

Vista 2000, Draft, *2000 Leak Detection, Monitoring, and Mitigation Strategy Update*, HNF-SD-WM-ES-378 Rev 2A, U.S. Department of Energy, Office of River Protection, Richland, Washington

WHC 1992, *Air/Water Jet Scarifier Feature Test – Final Test Report*, WHC-SD-ER-TRP- 006 Rev 0, Westinghouse Hanford Company, Richland, Washington.

WHC, 1995, *Technology Issues Related to Single-Shell Tank Waste Retrieval Leak Detection, Monitoring, and Mitigation (LDMM)*, dated July, 1995.

Whitley, et al 1999, *Contaminated Vadose Zone Characterization Using Partitioning Tracers*, J Env Engrg,

APPENDIX B

RETRIEVAL PERFORMANCE EVALUATION FOR SINGLE-SHELL TANK C-104

This page intentionally left blank.

CONTENTS

B.1.0 INTRODUCTION B-1

B.2.0 BACKGROUND B-5
B.2.1 SETTING B-5
B.2.2 FACILITIES DESCRIPTION B-8
B.2.2.1 C Tank Farm B-8
B.2.2.2 Tank C-104 ..... B-11
B.2.2.3 Ancillary Equipment B-11

B.3.0 TECHNICAL APPROACH B-12
B.3.1 OVERVIEW OF THE TECHNICAL APPROACH B-12
B.3.1.1 Conceptual Model of the C Tank Farm B-14
B.3.1.2 Use of Waste Retrieval Cases B-16
B.3.2 IDENTIFICATION OF WASTE RETRIEVAL CASES FOR ANALYSIS B-16
B.3.3 SOURCE TERM INVENTORY ESTIMATES B-19
B.3.3.1 Past Tank Leak Estimates B-21
B.3.3.2 Retrieval Leak Loss Estimates B-22
B.3.3.3 Residual Tank Waste Estimates B-23
B.3.3.4 Ancillary Equipment Inventory B-24
B.3.4 SHORT-TERM HUMAN HEALTH RISK B-24
B.3.4.1 Occupational Injuries, Illnesses, and Fatalities B-25
B.3.4.2 Radiological Risk From Accidents B-25
B.3.4.3 Chemical Exposure from Accidents B-27
B.3.4.4 Radiological Latent Cancer Fatality Risk from Routine Exposure B-27
B.3.4.5 Chemical Hazards from Routine Exposure B-28
B.3.5 GROUNDWATER IMPACTS B-28
B.3.6 LONG-TERM HUMAN HEALTH RISK B-30
B.3.6.1 Contaminants of Concern B-31
B.3.6.2 Scaling Factors B-31
B.3.6.3 Exposure B-32
B.3.6.4 Risk B-33
B.3.6.5 Risk Allocation B-35
B.3.7 INTRUDER RISK B-35
B.3.7.1 U.S. Department of Energy Intruder Scenario B-36
B.3.7.2 U.S. Nuclear Regulatory Commission Intruder Scenario B-37
B.3.8 REGULATORY COMPLIANCE B-39
B.3.8.1 Relevant Regulations and Requirements B-39
B.3.8.2 Regulatory Compliance of Waste Retrieval Approach B-46

B.4.0 DESCRIPTION OF WASTE RETRIEVAL CASES B-49
B.4.1 MAJOR ENABLING ASSUMPTIONS B-49
B.4.1.1 Waste Retrieval Technology Assumptions B-49
B.4.1.2 Leak Detection, Mitigation, and Monitoring System Assumptions B-50
B.4.1.3 Tank Stabilization Assumptions B-50
B.4.1.4 Ancillary Equipment Assumptions B-50
B.4.1.5 Surface Barrier Assumptions B-51
B.4.2 SUMMARY OF WASTE RETRIEVAL CASE DESCRIPTIONS B-51

B.5.0 ANALYSIS RESULTS B-54
B.5.1 SHORT-TERM HUMAN HEALTH RISK RESULTS B-54
B.5.1.1 Occupational Accident Results B-54
B.5.1.2 Routine Radiological Risk Results B-56
B.5.1.3 Routine Chemical Risk Results B-56
B.5.1.4 Radiological Accident Risk Results B-56
B.5.1.5 Chemical Accident Risk Results B-59
B.5.2 GROUNDWATER IMPACT RESULTS B-60
B.5.3 LONG-TERM HUMAN HEALTH RISK RESULTS B-62
B.5.3.1 Tank C-104 Long-Term Human Health Risk Assessment Results B-62
B.5.3.2 C Tank Farm Long-Term Human Health Risk Assessment Results B-68
B.5.3.3 Receptor Scenario Results Comparison B-69
B.5.4 INTRUDER RISK RESULTS B-69
B.5.4.1 U.S. Department of Energy Intruder Scenario B-69
B.5.4.2 U.S. Nuclear Regulatory Commission Requirements B-71
B.5.5 REGULATORY COMPLIANCE RESULTS B-73
B.5.5.1 Short-Term Human Health Risk Compliance B-73
B.5.5.2 Groundwater Protection Compliance B-74
B.5.5.3 Long-Term Human Health Risk Compliance B-74
B.5.5.4 Inadvertent Human Intruder Compliance B-75
B.5.5.5 HFFACO Milestone Compliance B-75

B.6.0 CONCLUSIONS B-77
B.6.1 SUMMARY CONCLUSIONS B-77
B.6.1.1 Tank C-104 Conclusions B-77
B.6.1.2 C Tank Farm Conclusions B-79
B.6.2 CONCLUSIONS BY AREA OF ANALYSIS B-79
B.6.2.1 Short-Term Human Health Risk Conclusions B-79
B.6.2.2 Groundwater Impact Conclusions B-81
B.6.2.3 Long-Term Human Health Risk Conclusions B-82
B.6.2.4 Intruder Risk Conclusions B-84
B.6.2.5 Regulatory Compliance Conclusions B-85
B.6.3 UNCERTAINTIES B-88

B.7.0 REFERENCES B-91

ATTACHMENTS

B1 RETRIEVAL AND RESIDUAL INVENTORY CALCULATIONS B1-i
B2 COPY OF RPP-6696 APPENDIX D: COMPARISON OF SUBSURFACE CONDITIONS BETWEEN THE AX AND C TANK FARMS THAT POTENTIALLY AFFECT SCALING IMPACT ASSESSMENT RESULTS B2-i

FIGURES

B.1.1. Single-Shell Tank Retrieval Logic B-3
B.2.1. Tank C-104 Waste Retrieval Demonstration Milestones B-6
B.2.2. Hanford Site Map and Vicinity B-7
B.2.3. Location Map of C Tank Farm and Surrounding Facilities in the 200 East Area B-9
B.2.4. C Farm Tanks B-10
B.3.1. C Tank Farm Conceptual Model for Long-Term Human Health Risk and Groundwater Impacts B-15
B.3.2. Evaluated Waste Sources, Release Mechanisms, Exposure Pathways, and Receptors B-17
B.3.3. Process for Assessing Percentage of Waste Retrieved from Waste Retrieval Operations B-48
B.4.1. Enhanced RCRA Subtitle C Barrier Cross-Section B-52
B.5.1. Tank C-104 Retrieval Leakage Risk Versus Retrieval Leakage Volume B-65
B.5.2. Tank C-104 Residual Waste Risk Versus Residual Waste Volume B-66
B.5.3. Tank C-104 Composite Risk Versus Retrieval Leakage Volume (Assuming 10,200 L [2,700 gal] of Residual Waste) B-67
B.5.4. Tank C-104 Composite Risk Versus Residual Waste Volume (Assuming 30,000 L [8,000 gal] of Retrieval Leakage) B-67
B.6.1. DOE Inadvertent Human Intruder Post-Driller Threshold Dose (100 mrem/yr) B-78
B.6.2. Industrial Worker and Residential Farmer ILCR Levels for Tank C-104 Retrieval Leakage Volume and Residual Waste Volume B-83

TABLES

B.1.1. Analysis, Approach, Results, and Conclusions Crosswalk B-2
B.3.1. Summary of Waste Retrieval Cases B-19
B.3.2. Groundwater Pathway Unit Risk Factors B-34
B.3.3. Intruder Scenario Unit Dose Factors at 100 Years from 1998 ..... B-36
B.3.4. Class C Low-Level Waste Upper Concentration Limits B-38
B.3.5. Relevant Federal Statutes and Regulations B-40
B.5.1. Occupational Accidents B-55
B.5.2. Routine Radiological Risk B-57
B.5.3. Routine Chemical Risk to Maximally Exposed Individuals B-59
B.5.4. Maximum Contaminant Concentrations in Groundwater for the Past Leak Source Term at 2,600 Years for the C Tank Farm B-60
B.5.5. Maximum Contaminant Concentrations in Groundwater for the Retrieval, Residual, and Composite Source Terms for the 10 Cases Considered for the C Tank Farm B-61
B.5.6. Industrial Worker Long-Term Human Health Risks by Source Term and Case B-63
B.5.7. Residential Farmer Long-Term Human Health Risks by Source Term and Case B-64
B.5.8. Comparison of Peak Hazard Index for Different Receptor Scenarios by Case B-70
B.5.9. Well Driller and Post-Driller Resident Dose in 2100 ..... B-71
B.5.10. Tank C-104 Residual Waste Concentrations Compared to the Class C Upper Limits B-72
B.5.11. Minimum Level of Grout Required to Reduce Concentrations to Class C Upper Limits B-73

LIST OF TERMS

CERCLA	*Comprehensive Environmental Response, Compensation, and Liability Act of 1980*
CoCs	contaminants of concern
DOE	U.S. Department of Energy
DST	double-shell tank
DWS	drinking water standard
Ecology	Washington State Department of Ecology
EDTA	ethylenediaminetetraacetic acid
EPA	U.S. Environmental Protection Agency
ERPG	emergency response planning guideline
F&R	functions and requirements
GTCC	Greater Than Class C
HFFACO	*Hanford Federal Facility Agreement and Consent Order*
HLW	high-level waste
HWMA	Hazardous Waste Management Act
ILCR	incremental lifetime cancer risk
LCF	latent cancer fatality
LDMM	leak detection, mitigation, and monitoring
LLW	low-level waste
LWC	lost workday case
MCL	maximum contaminant level
MEI	maximally exposed individual
MTCA	Model Toxics Control Act
NRC	U.S. Nuclear Regulatory Commission
RCRA	*Resource Conservation and Recovery Act of 1976*
RPE	retrieval performance evaluation
SST	single-shell tank
TRC	total recordable case
TRU	transuranic
TSD	treatment, storage, and/or disposal
URF	unit risk factor

This page intentionally left blank.

B.1.0 INTRODUCTION

This *Retrieval Performance Evaluation for Single-Shell Tank C-104* is written to document the results of a scoping-level retrieval performance evaluation (RPE) for waste retrieval from tank C-104 in the Hanford Site 241-C tank farm. The evaluation was performed to partially satisfy the requirements of Milestone M-45-03-T04 of the *Hanford Federal Facility Agreement and Consent Order* (HFFACO; Ecology et al. 1989). Milestone M-45-03-T04 calls for the development of a HFFACO functions and requirements (F&R) document for tank C-104 demonstration systems for waste retrieval and leak detection, mitigation, and monitoring (LDMM). This scoping-level RPE directly supports the tank C-104 F&R document. The HFFACO milestone further identifies that the scoping-level RPE will provide the following:

- Environmental and human health risk evaluation data/information associated with estimated waste volumes to be retrieved
- Environmental and human health risk evaluation data/information associated with the maximum volume which could leak during retrieval and the risk from residual waste
- Detail known and estimated radionuclide contamination and contaminant migration within the vadose zone as a basis of calculation.

The scoping-level RPE documented in this report considers human health risk and regulatory performance measures over a range of residual waste volumes and retrieval leakage volumes selected for tank C-104. Performance measures evaluated include short-term human health risk, impacts to groundwater, long-term human health risk, waste site intruder risk, and regulatory compliance. The results of the RPE analysis will be used to identify performance measures that influence the design and operation of the waste retrieval system. Examples of retrieval system requirements include retrieval leak volume limits considering residual waste remaining in the tank following retrieval and residual waste volume limits based on risk or regulatory performance measures. These performance measures provide one of the inputs to the decision-making process that results in the retrieval system requirements identified in the F&R document. A range of volumes for both residual waste and retrieval leakage are evaluated to investigate the sensitivity of the performance measures to changes in residual waste volumes or leakage volumes.

The fundamental goal of the tank C-104 waste retrieval technology demonstration is to test the limits of technology for a crawler-based retrieval system. The ideal result of any waste retrieval effort would be to retrieve all of the waste in the tank with no leak loss to the environment. However, achievement of that ideal goal is highly uncertain given the age of tank C-104, physical characteristics of the waste in the tank, and the limitations of the waste retrieval system. Given this uncertainty it is important to develop a design and operating approach that provides estimates for risk-based performance of the tank at various points along the retrieval path and considers risk and regulatory-based performance measures. Single-shell tank (SST) waste retrieval decisions and subsequent tank farm closure decisions are interrelated on a tank-by-tank and tank farm-by-tank farm basis. Because tank closure will be completed on a tank farm basis, all potential sources of contamination within the tank farms (past leaks, retrieval losses, and tank

residuals) must be considered when evaluating long-term impacts from the tank farm system. Near term retrieval actions for individual tanks (i.e., inventory remaining in the tank following retrieval and retrieval leakage) could affect future waste retrieval decisions. Tank farm retrieval decisions are also interrelated with remediation and closure decisions of other non-tank sources in the Hanford Site 200 East and 200 West Areas. Eventually the impacts from all waste sites will need to be considered together. The relationships between the *Resource Conservation and Recovery Act of 1976* (RCRA) field investigation, SST retrieval, and closure are shown in Figure B.1.1.

This analysis focuses on tank C-104 within the context of the C tank farm. The general approach used in this RPE involves definition of 10 waste retrieval cases that span a range of retrieval leak loss and residual waste volumes for tank C-104 and include retrieval and leak loss assumptions for the remaining C farm tanks. A range of leak loss and residual waste volumes are considered to establish risk versus volume relationships for both retrieval leakage and tank residuals. Table B.1.1 shows the areas of analysis considered in this RPE and provides a crosswalk of those areas to the corresponding section numbers that address technical approach, results of analysis, and conclusions.

Table B.1.1. Analysis, Approach, Results, and Conclusions Crosswalk

Area of Analysis	Technical Approach/Description	Analysis Results	Conclusions
Retrieval cases	Section B.3.2 and B.4.0	NA	Section B.6.0
Source terms	Section B.3.3 and Attachment B1		
Short-term human health risk	Section B.3.4	Section B.5.1	Section B.6.2.1
Groundwater impacts	Section B.3.5	Section B.5.2	Section B.6.2.2
Long-term human health risk	Section B.3.6	Section B.5.3	Section B.6.2.3
Intruder risk	Section B.3.7	Section B.5.4	Section B.6.2.4
Regulatory compliance	Section B.3.8	Section B.5.5	Section B.6.2.5

Note: Source term results, conclusions, and data needs are identified within each of the areas of analysis as appropriate.

NA = not applicable.

This RPE report is not intended to set the minimum performance standard for the waste retrieval demonstration. The intent of the retrieval demonstration is to collect performance data and establish a technical basis for the limit of the technology and the performance characteristics (e.g., loss in retrieval efficiency) as a function of waste volume remaining in the tank. Tank and tank farm closure criteria (as they are understood today) are considered in an effort to remove enough waste with minimal leakage providing reasonable assurance that the tank and the tank farm can be moved toward closure without having to plan for multiple retrieval campaigns.



Figure B.1.1. Single-Shell Tank Retrieval Logic

It is recognized that addressing tank farm closure at this stage of the program is preliminary and will be revisited throughout the life of the retrieval program; however, because waste retrieval for tank farm closure is the primary driver for remediating the SSTs it is important to evaluate the relationships between tank waste retrieval and tank farm closure before, during, and after tank waste retrieval.

The RPE methodology will be used to provide risk-based performance data for use in defining retrieval system requirements in the F&R document. The performance measures evaluated will be used to support identification of the requirements for the LDMM system in terms of required leak detection limits and response actions and the identification of requirements for the retrieval system in terms of the extent of waste retrieval necessary to meet risk and regulatory-based criteria. The HFFACO F&R document will discuss how the results of this RPE are applied to the waste retrieval system. Another aspect of the retrieval demonstration involves showing the limit of the retrieval technology (i.e., operational conditions for demonstrating when the technology has reached the practical limit), which will be defined in the HFFACO F&R document and not as part of this RPE report.

B.2.0 BACKGROUND

In 1999 the U.S. Department of Energy (DOE) completed the RPE methodology for the AX tank farm, documented in *Retrieval Performance Evaluation Methodology for the AX Tank Farm* (DOE/RL-98-72), as a demonstration of the methodologies, data, and analysis necessary to support making tank waste retrieval and tank farm closure decisions required under the HFFACO. DOE/RL-98-72 includes an evaluation of a range of residual waste and retrieval leakage volume cases and post-retrieval actions that could be taken to remediate contaminated soil and close the tank farm. The methodology in DOE/RL-98-72 uses a systems approach that considers the entire tank farm when evaluating the cases relative to potential performance criteria. These relationships can then be used to support decisions on the extent of waste retrieval and the limits of waste retrieval leak loss.

In August of 2000 the HFFACO was modified to reflect a revised strategy for SST waste retrieval activities via Milestone Change Package M-45-00-01A. The revised strategy focuses on maximizing risk reduction by prioritizing the retrieval of waste from tanks with a high inventory of contaminants of concern (CoCs) instead of focusing on maximizing the number of tanks entered for waste retrieval. The new strategy is also focused on demonstrating waste retrieval technologies in a variety of waste forms and tank farm locations to establish a basis for future work. To establish the overall F&R for the waste retrieval demonstration systems, the need for an overarching F&R document has been identified. That overarching document, referred to as the HFFACO F&R document, will provide the framework within which the waste retrieval systems will be designed and operated. The major elements of the HFFACO F&R document along with the HFFACO milestones leading up to completion of the waste retrieval demonstration in tank C-104 are shown in Figure B.2.1. HFFACO Milestone M-45-03-T04 specifies how the F&R document for tank C-104 should include a scoping-level RPE that provides a human health risk evaluation associated with waste volumes to be retrieved and the maximum volume of waste that could leak during waste retrieval operations. Milestone M-45-03F specifies the tank C-104 waste retrieval goal as retrieval of 99% of the August 2000 best-basis inventory volume (BBI 2000), with at least 89 kg of plutonium retrieved to safe storage.

B.2.1 SETTING

The Hanford Site 200 East Area (Figure B.2.2) is located on a plateau about 11 km (7 mi) south of the Columbia River. This area housed facilities called separations plants that received and dissolved irradiated fuel from the Site 100 Areas and then separated out the plutonium. Operations at the Hanford Site resulted in production of liquid, solid, and gaseous wastes. Most wastes resulting from Hanford Site operations have had at least the potential to contain hazardous and radioactive materials. From an operational standpoint, radioactive wastes were originally categorized as high-level waste (HLW) or low-level waste (LLW) depending on the level of radioactivity present. HLW was first stored in large underground SSTs. Portions of the contents of some of those SSTs have since leaked into the soil, either directly from the tanks or from associated transfer piping.

Figure B.2.1. Tank C-104 Waste Retrieval Demonstration Milestones



Figure B.2.2. Hanford Site Map and Vicinity



B.2.2 FACILITIES DESCRIPTION

This section contains descriptions of the C tank farm and tank C-104. Definition and description of ancillary equipment are also provided.

B.2.2.1 C Tank Farm

The C tank farm is located along the eastern edge of the 200 East Area (Figure B.2.3). The C tank farm contains 16 SSTs, 12 with 2,000,000-L (530,000-gal) capacity and 4 with 208,000-L (55,000-gal) capacity; waste transfer lines; leak detection systems; and tank ancillary equipment. The larger SSTs are 23 m (75 ft) in diameter while the smaller tanks are 6 m (20 ft) in diameter. Figure B.2.4 provides drawings of the two types of C farm tanks. The sediment cover from the apex of the dome to ground surface is approximately 2 m (7 ft).

The C tank farm was constructed between 1943 and 1944 as one of the first-generation tank farms at the Hanford Site. The tanks were designed to receive non-boiling waste. Each C farm tank was designed with a primary steel tank liner, concrete shell and dome, and dish-shaped bottom. The C farm tanks are treatment, storage, and/or disposal (TSD) units operating under interim status pending closure. Following waste retrieval, the C tank farm will be closed in accordance with "Closure and Postclosure" (WAC 173-303-610) under the Washington State "Hazardous Waste Management Act" (HWMA) and HFFACO Milestone M-45-00. Under the *Washington Administrative Code* and HFFACO requirements, individual tanks cannot be closed; an entire tank farm must be closed as a unit.

Information and data regarding the C tank farm facility description are taken from *Historical Tank Content Estimate for the Northeast Quadrant of the Hanford 200 East Area* (WHC-SD-WM-ER-349). Additional historical data on the C tank farm including historical operating data such as waste level, temperature profiles, and sample analyses, are provided in *Supporting Document for the Northeast Quadrant of the Hanford 200 East Area* (WHC-SD-WM-ER-313).

Tanks C-101 through C-106 received metal waste, and tanks C-107 through C-112 received first-cycle and B Plant decontamination wastes. Tanks C-201 through C-204 were used to settle waste while the supernate was sent to a crib. The C tank farm also received Plutonium-Uranium Extraction Plant fission product waste, which led to the high-heat load in tank C-106. The high-heat load in tank C-106 resulted in the SST Program prioritizing that tank for early waste retrieval. The bulk of the waste in tank C-106 was removed (using past-practice retrieval methods) in a retrieval campaign that was completed in fiscal year 2000, and the tank was removed from the Watch List.

Figure B.2.3. Location Map of C Tank Farm and Surrounding Facilities in the 200 East Area



Figure B.2.4. C Farm Tanks



B.2.2.2 Tank C-104

Tank C-104 was used to store metal waste beginning in October 1946. The tank was full in February 1947. The waste was sluiced from the tank in 1953 in an effort to recover the uranium. U Plant waste was introduced into the tank in 1955. The tank was subsequently emptied and then received various wastes until 1980 when the supernate was pumped out and the tank was declared inactive. Interim stabilization efforts were completed for tank C-104 in 1989. Tank C-104 is categorized as a sound tank and contains 995,000 L (263,000 gal) of waste (HNF-EP-0182, Rev. 150). The presence of gamma contamination in the vadose zone around tank C-104 was evaluated during baseline spectral gamma logging of the C tank farm (GJO-HAN-18). The spectral gamma logging effort concluded that the soil contamination around tank C-104 was not associated with a tank leak and is most likely from surface spills, and subsurface pipeline leaks.

B.2.2.3 Ancillary Equipment

Ancillary equipment is defined as structures, piping, and equipment outside the waste tanks but associated with tank farm operations. Most of the ancillary equipment in the C tank farm was abandoned in place when the C farm tanks were taken out of active service. Evaluating ancillary equipment is an important component of closure strategy evaluations because the equipment represents a potential source term for worker exposure (if the equipment is removed) or long-term human health risk (if the equipment is left in place). The ancillary equipment list for the C tank farm includes the following:

- Twelve surplus buildings and other surface facilities
- 70 drywells
- Tank riser penetrations
- Direct-buried piping, encased piping, and ventilation elements
- Pump pits, sluice pits, and valve pits associated with individual tanks
- Other valve pits, jumper pits, diversion boxes, and structures.

Potential sources of contamination include residual waste in the transfer lines, sluicing lines, valve pits, and pump pits. There is currently insufficient data available to assess the contaminant inventory in the ancillary equipment and, therefore, this contamination source was not included in the calculation of long-term risks. This approach is reasonable for this scoping level RPE to support retrieval decisions for tank C-104. Inventory estimates for the ancillary equipment will be needed for future performance evaluations of closure options.

B.3.0 TECHNICAL APPROACH

The value and response of risk and regulatory-based performance measures to variations in two main system parameters are the primary focus of this RPE. These two parameters are residual waste volume and retrieval leakage volume. Evaluation of the residual waste volumes supports the definition of the waste retrieval system requirements while evaluation of retrieval leakage volumes supports definition of the LDMM system requirements.

Section B.3.1 provides a summary-level overview of the technical approach. Section B.3.2 describes the approach used to identify specific waste retrieval cases for analysis. Section B.3.3 describes the approach used to develop contaminant inventory estimates for past leaks, potential retrieval leaks, and tank waste residuals for each of the waste retrieval cases. Sections B.3.4 through B.3.8 describe the approach used for the five areas of analysis included in this RPE. Using the technical approach described in this section, performance measures for each case are calculated for four areas of analysis including short-term human health risk, contaminant transport and groundwater impacts, long-term human health risk, and inadvertent human intruder risk. The results of these calculations are presented in Section B.5.0. The fifth area of analysis involves comparing the case-specific performance measures against the appropriate regulatory standards and identifying where regulatory uncertainty exists.

B.3.1 OVERVIEW OF THE TECHNICAL APPROACH

The RPE process was developed as a decision-making tool to support waste retrieval and closure decisions using a systems approach that considers contributions from multiple sources (i.e., past leaks, retrieval leakage, and residual waste) across a number of performance measures. The RPE methodology is an iterative process that can be applied before waste retrieval as one of the inputs in developing criteria for the extent of retrieval and leak loss criteria. After waste retrieval it can be used to evaluate performance measures using actual retrieval and leak loss data. The technical approach includes integration with related Site activities (e.g., Tank Farm Vadose Zone Project). The current application of this RPE focuses on developing waste retrieval and leak loss criteria for tank C-104 within the C tank farm.

The following performance measures are assessed.

- **Short-term human health risk** (Section B.3.4) – Human health risk to workers and the public from chemical and radiological exposures that is expected to occur during routine remedial actions (e.g., waste retrieval) or that could result from postulated accidents and injuries and fatalities resulting from industrial accidents.

- **Groundwater impacts** (Section B.3.5) – Impacts resulting from releases to the environment from past waste tank leaks and spills, potential releases during waste retrieval, and from residual waste that may remain in the tanks following closure. The assessment considers a 10,000-year period of interest beginning at present. The groundwater impact assessment relies on the results of the fate and transport analyses at the nearby AX tank farm. Those results are scaled, based on the inventory differences between the AX and C tank farm source terms, to estimate the groundwater concentration

of CoCs at the C tank farm boundary. This approach to estimating was selected for this screening level RPE because of similarities in vadose zone properties, conceptual site model, source term release mechanisms, and provides for impact assessment using a graded approach. The estimated groundwater concentrations of the CoCs for the C tank farm are provided as input to the assessment of long-term human health risk and are compared to regulatory standards.

- **Long-term human health risk** (Section B.3.6) – Human health risk to future Site users that would exist after completion of waste retrieval (post-remediation) and implementation of tank farm closure. Long-term human health risk analysis involves evaluating health risks resulting from exposure to contaminated groundwater. CoCs to long-term human health risk are those that are persistent and mobile in the environment.

  A 10,000-year period of interest was used for calculating long-term human health risk based on the lifestyle of a residential farmer and an industrial worker. This time period was selected for the following reasons:

  - Classification of the residual waste under DOE Order 435.1. If residuals do not meet the waste incidental to reprocessing criteria a determination from the U.S. Nuclear Regulatory Commission (NRC) will be required, based in part on demonstrating protection of human health and the environment over a 10,000-year period

  - Future *National Environmental Protection Act of 1969* requirements for assessing tank closure will consider the 10,000-year period

  - Based on previous analyses, the maximum long-term risk impacts from tank residuals are expected to occur 1,000 to 10,000 years following closure.

- **Inadvertent human intruder risk** (Section B.3.7) – Human health risk to future Site users who could inadvertently drill through the tank following closure and loss of institutional control at 100 years after closure. A comparison of the residual waste inventory to NRC waste classification criteria is also made to support a regulatory evaluation of the planned approach for reclassification of the residuals as incidental waste. CoCs to the inadvertent human intruder risk include cesium, strontium, tin, and transuranic (TRU) isotopes that are generally immobile in the environment.

- **Regulatory compliance** (Section B.3.8)– Applicable and appropriate regulatory requirements are identified including areas where waste retrieval issues and specific quantitative performance measures exist.

The best available data for each component of tank C-104 and the remaining tank farm system were used to provide calculations for each performance measure. Assumptions were developed to complete the analysis where data were unavailable or highly uncertain. Those assumptions were based on engineering judgment following a review of available data or information from other Hanford Site, DOE complex, or non-DOE remediation programs.

Application of the RPE methodology to the evaluation of tank C-104 and the C tank farm includes the following:

- Development of a conceptual model of the tank and tank farm system (e.g., tank farm components, sources of contamination, engineered systems, and the natural environment) to analyze the potential impacts of SST waste retrieval
- Identification of waste retrieval cases that span a range of residual waste volume and retrieval leakage volumes that will be used to develop risk versus volume relationships for both residual waste and retrieval leakage
- Development of factors to enable scaling groundwater impact results from evaluations of the nearby AX tank farm to the C tank farm
- Performance of a risk assessment to assess short- and long-term human health risks
- Comparison of the performance of the total system to requirements established by federal and state regulations and the HFFACO.

B.3.1.1 Conceptual Model of the C Tank Farm

The conceptual model of the C tank farm used for long-term human health risk and groundwater impact assessment is depicted in Figure B.3.1 and represents the following.

- The C tank farm including all tanks and soils within the tank farm boundary and from the surface to the groundwater.
- All waste sources within the C tank farm boundary including:
  - Contamination in the vadose zone from past tank spills and releases
  - Potential releases to the environment during waste retrieval activities
  - Releases to the environment from residual waste potentially remaining in the tank farm following completion of waste retrieval and assumed closure actions.
- Long-term degradation of the tanks and assumed tank closure system.
- Migration of mobile contaminants from the tank farm through the vadose zone and groundwater.
- Human exposure under residential farmer and industrial scenarios and resulting human health impacts from contaminants that have migrated beyond the tank farm boundary.

Figure B.3.1. C Tank Farm Conceptual Model for Long-Term Human Health Risk and Groundwater Impacts



The conceptual model shown in Figure B.3.1 identifies source terms, transport pathways, and exposure pathways that could be under investigation by other Site projects (e.g., Tank Farm Vadose Zone, Groundwater/Vadose Zone Integration Project). Efforts to integrate this RPE with other projects were made to provide consistency in approach and methodology. The C tank farm is not currently under the RCRA Corrective Action Program so there is not a direct integration point at the C farm. The past leak inventory for the C tank farm developed by the Groundwater/Vadose Zone Integration project was adopted for this RPE.

Figure B.3.2 depicts the waste sources, release mechanisms, exposure pathways, and receptors for all impacts analyzed in this RPE. Figures B.3.1 and B.3.2 also serve to illustrate much of the scope of this document which includes evaluations of impacts associated with all past leak releases, potential future releases from the tanks during retrieval and post-closure, and intrusion into the tanks during post-closure. The scope of this document does not include the impacts associated with immobilization and disposal of the waste once it has been retrieved from the tanks.

B.3.1.2 Use of Waste Retrieval Cases

The approach used to evaluate performance measures for tank C-104 and the C tank farm was to identify a number of specific waste retrieval cases that cover a range of retrieval leakage volumes and residual waste volumes for tank C-104 along with a baseline set of assumptions for the remaining C farm tanks. Performance measures for each of the cases have been calculated and these case-specific results used to develop risk versus volume relationships.

Because of the proximity of the C tank farm to the AX tank farm and similarities in the vadose zone properties and conceptual model for tank closure and release mechanisms, a scaling approach was developed for this scoping-level RPE that utilizes contaminant transport modeling results from the AX tank farm to predict results for the C tank farm. This approach provides for evaluation of potential impacts without the commitment of resources required to develop and execute a numerical model for the C tank farm. The technical rationale for the scaling approach is provided in Section B.3.5.

B.3.2 IDENTIFICATION OF WASTE RETRIEVAL CASES FOR ANALYSIS

Ten waste retrieval cases have been identified for this evaluation. Each case has specific values for retrieval leakage volume and residual waste volume for tank C-104 and the remaining C farm tanks. The cases were developed by varying one of the system components (i.e., retrieval leakage or residual waste volume) so that results could be compared and risk versus volume relationships developed. Because the long-term performance measures associated with closure are evaluated for the tank farm, each case involves identification of an assumed end state for tank C-104 and an assumed end state for the remaining C farm tanks. The purpose of defining and analyzing specific retrieval cases is not to select one of the cases for implementation but to evaluate how the performance measures change as the residual and leakage volumes change. The results may indicate that retrieval to residual levels lower than evaluated in any of the cases may be warranted or the leakage threshold may be between two of the leak volumes evaluated. It is also important to note that to provide results over a range of inputs, some of the cases identify residual waste volumes and retrieval leakage volumes that would not meet the objectives of the retrieval technology demonstration or the HFFACO.

Figure B.3.2. Evaluated Waste Sources, Release Mechanisms, Exposure Pathways, and Receptors



Receptor Exposure Pathways

Short-Term Human Health Risk				Long-Term Human Health Risk		Long-Term Human Health Risk Future Site User (Post-Remediation)	
Pathway	Involved Worker	Noninvolved Worker	Public	Waste Site Intruder		Residential Farmer	Industrial Worker
				NRC	DOE		
Inhalation	✓	✓	✓	NA	✓	✓	✓
Direct Exposure	✓			NA	✓	✓	✓
Groundwater Ingestion				NA		✓	✓
Food Ingestion			✓	NA	✓	✓	
Soil Ingestion				NA	✓	✓	
Dermal (Water)				NA		✓	✓

*The NRC intruder scenario is based on concentration limits of CoCs in the waste, which is addressed in Section B.3.7.2.

CoCs = contaminants of concern.
DOE = U.S. Department of Energy.
NA = not applicable.
NRC = U.S. Nuclear Regulatory Commission.

The major components considered when identifying cases for evaluation included the extent of waste retrieval and the potential retrieval leak loss that could occur during waste retrieval operations. Because the purpose of this analysis is to focus on near-term retrieval decisions, a number of the tank and tank farm closure elements that were considered in DOE/RL-98-72 were not evaluated in this analysis. A single baseline closure scenario is assumed for each of the waste retrieval cases.

The approach used to develop waste retrieval strategies resulting in volume retrieved and retrieval leak loss assumptions is based on the fiscal year 2000 *Preliminary Engineering Report for the 241-C-104 Retrieval System* (RPP-6843), and the experience gained in retrieving waste from tank C-106 in fiscal year 2000. A process was used to narrow the number of combinations to retrieval cases that accomplish the following:

- Represent a range of potential residual waste volumes and retrieval leakage volumes
- Be responsive to current waste retrieval goals
- Support analysis required to evaluate case-specific performance measures with applicable laws and regulations.

Ten waste retrieval cases have been defined, as shown in Table B.3.1. The principle variables are volume of waste retrieved (presented as residual waste volume) and retrieval leak loss. One case also includes construction of an interim barrier to evaluate how retrieval leakage impacts are affected by an interim barrier during waste retrieval operations.

The waste retrieval demonstration for tank C-104 is intended to demonstrate the capability of a retrieval technology to remove waste from the tank. It is anticipated that the effectiveness or efficiency of the retrieval system will drop off as the amount of waste remaining in the tanks decreases resulting in increasing cost and worker health risk per volume of waste retrieved. The process for determining when the retrieval system has reached the limit of the technology will be defined in the HFFACO F&R document. HFFACO Milestone M-45-03F establishes a waste retrieval goal of 89 kg of total plutonium and 99% by tank content volume. The estimated inventory of total plutonium retrieved under the retrieval cases will be evaluated and discussed.

The retrieval cases identified in Table B.3.1 are hypothetical cases intended to provide a range of residual volumes and leak loss volumes that are used to develop relationships between the source term volume and the performance measures. The probability that any of these cases would occur is not evaluated. For example there is a low probability that all of the C farm tanks would leak during retrieval. The likelihood that a large leak would occur in combination with the residual volumes in Table B.3.1 is not evaluated. One potential case for retrieval from an unsound tank is a large leak loss and a corresponding large residual volume resulting from shutting the retrieval system down. One could also postulate that for a tank with a small leak rate that leak loss volumes were proportional to the time operating the retrieval system and therefore smaller residual volumes could be correlated to higher leakage volumes.

Table B.3.1. Summary of Waste Retrieval Cases

Case Number	Residual Waste Volume Remaining Following Retrieval[a]			Retrieval Leak Loss			Interim Barrier
	Tank 241-C-104 (gal)	Remaining 100-Series Tanks (gal)	200-Series Tanks[b] (gal)	Tank 241-C-104[b] (gal)	Remaining 100-Series Tanks (gal)	200-Series Tanks (gal)	
1	2,700	2,700	220	8,000	8,000	800	N
2	6,000	6,000	600	8,000	8,000	800	N
3	1,300	2,700	220	4,000	8,000	800	N
4	2,700	2,700	220	0	0	0	N
5	2,700	2,700	220	0	8,000	800	N
6	2,700	2,700	220	40,000	8,000	800	N
7	2,700	2,700	220	80,000	8,000	800	N
8	27,000	2,700	220	8,000	8,000	800	N
9	50,000	2,700	220	8,000	8,000	800	N
10	2,700	2,700	220	8,000	8,000	800	Y

[a]2,700 gal represents the HFFACO interim retrieval goal of 360 ft^3 for the 100-series single-shell tanks.
[b]220 gal represents the HFFACO interim retrieval goal of 30 ft^3 for the 200-series single-shell tanks.

To obtain liters multiply gallons by 3.785.

HFFACO = *Hanford Federal Facility Agreement and Consent Order.*

A number of conservative assumptions were made in developing the 10 waste retrieval cases. This conservative approach results in providing a reasonable upper bound on the potential impacts of waste retrieval activities on the performance measures.

Conservative assumptions (i.e., assumptions that result in higher risks or impacts) were also made for the remaining tank farm elements so as not to underestimate the long-term human health risk contribution from the remaining C farm tanks. The assumptions made for the remaining C farm tanks are not intended to describe the planned approach but to develop a conservative basis for evaluating long-term human health risk for the tank farm. For all but one of the cases it is conservatively assumed that each of the tanks would leak during waste retrieval. No retrieval leakage would be expected from a sound tank.

B.3.3 SOURCE TERM INVENTORY ESTIMATES

Three discrete source terms are addressed in this evaluation: past leaks, retrieval leakage, and residual waste. The 10 waste retrieval cases evaluated are similar to those evaluated in DOE/RL-98-72 and include a single best-basis past leak release case and multiple retrieval leakage and residual waste release cases. A common closure end state is assumed for all cases (i.e., tank stabilization and enhanced RCRA Subtitle C cap). Multiple release cases are not of

interest for the past leak source term because a single best-estimate past leak inventory was developed for the C tank farm. In contrast, multiple release cases are of interest for the retrieval leakage and residual waste source terms because these variations provide the data needed to develop relationships between risk and volume. The risk-to-volume relationships are the basis for determining risk-based retrieval performance criteria (i.e., volume limits for retrieval leakage and residual waste).

Because the regulatory unit for closure decisions is a tank farm and not an individual tank, tank C-104 impacts on risk levels need to be understood within the context of the C tank farm. Source inventories are therefore developed for all tanks in the C tank farm. Source inventories are estimated individually for the past leak, retrieval leakage, and residual waste source terms and then combined to create the cases of interest for evaluation. Source inventories for leaks are developed by estimating contaminant-specific source concentrations and then multiplying by the source volumes of interest.

Evaluation of waste retrieval cases for the C tank farm requires the development of case-specific source terms. Source terms address different methods of release of contaminants from the engineered system (e.g., tanks) to the accessible environment. Developing source terms involves defining the contaminant inventory and evaluating potential release mechanisms. Identification and quantification of source terms are necessary to evaluate the short-term impacts to human health during routine remediation activities and accidents and the long-term impacts resulting from releases during and after remediation.

Potential inventory release mechanisms from underground storage tanks are identified in DOE/RL-98-72. The release mechanisms identified constitute the three source terms also used in this document. This section focuses on developing the C tank farm inventory data used to evaluate waste retrieval operations and their effects on short- and long-term human health risks. Inventory estimates were developed for each of the major long-term human health risk source term components. Source terms for short-term human health risk and accident analysis are strategy-specific and are based on the chemical and radiological inventory present in the tanks and equipment being analyzed. The waste retrieval technology evaluated in support of this RPE includes routine air emissions estimates that were used as short-term human health risk source terms.

Source terms of concern for assessing long-term human health risk include past leaks, residual waste remaining after retrieval, and potential waste retrieval leakage. Strategy-specific source term inventory estimates have been developed for these three components and are discussed in the following sections. These three source terms are evaluated in the analysis because they have the potential to impact the groundwater and reach potential receptors within the 10,000-year period of interest. Both residual waste and retrieval leak loss inventories are developed based on assumed events and future conditions during and after waste retrieval operations.

The source terms associated with each of the waste retrieval cases include the following.

- **Past leaks** – All cases consider vadose zone contamination from past leaks. The past leak source term includes contaminant inventory that is currently in the vadose zone from

tank leaks that have occurred in the past. It is assumed that this inventory is in the vadose zone and has not yet migrated to groundwater. Past leaks are included in the analysis to allow for the potential contribution of past leak impacts to be added to the impacts from retrieval leakage. A best-estimate inventory has been adapted for past leaks based on available data and information. See Section B.3.3.1 for further discussion.

- **Retrieval leakage** – Potential retrieval leakage volumes evaluated include 0; 15,000; 30,000; 150,000; and 300,000 L (0; 4,000; 8,000; 40,000; and 80,000 gal) for tank C-104 to cover a range of potential retrieval leakage. Because the long-term impacts from retrieval leakage will also be evaluated within the context of the tank farm, retrieval leakage volumes of 0 and 30,000 L (0 and 8,000 gal) were identified for the remaining 100-series tanks. Retrieval leakage volumes for the 200-series SSTs were scaled based on tank size to 3,000 L (800 gal).

- **Residual waste** – Residual waste is defined as the waste remaining in the tanks following waste retrieval. Post-retrieval residual waste volumes of 4,900; 10,000; 23,000; 100,000; and 190,000 L (1,300; 2,700; 6,000; 27,000; and 50,000 gal) were identified for tank C-104 to represent retrieval performance that bracket the HFFACO interim retrieval goal of 360 ft^3 (10,000 L [2,700 gal]). Because the long-term impacts from tank residuals are evaluated within the context of the tank farm, residual waste volumes of 10,000 L (2,700 gal) were assumed for the remaining 100-series tanks in all cases except one where a residual volume of 23,000 L (6,000 gal) was assumed to represent less-than-optimum retrieval across the tank farm.

B.3.3.1 Past Tank Leak Estimates

Seven of the C farm tanks (C-101, C-110, C-111, C-201, C-202, C-203, and C-204) are classified as assumed leakers (HNF-EP-0182, Rev. 150). Best estimate inventories were taken from recent work conducted to develop inventory estimates for past leaks in support of the Systems Assessment Capability (LA-UR-00-4050). The methodology was based on available process information regarding the type of waste that was stored in the tank or that was transferred at the time the leaks were believed to have occurred. The tank waste releases were estimated based on location, timing, and leak volume information. The leak compositions were defined using Hanford defined waste model waste streams (LA-UR-96-3860) and the supernate mixing model subroutine as a function of time (LA-UR-00-4050). The C tank farm past leak source term inventory estimates are provided in Attachment B1.

The approach used to develop past leak inventory data has the potential to underestimate the inventory associated with near-surface contamination associated with transfer line leaks. The recent spectral gamma logging data were reviewed to determine if there would be an impact on the past leak inventory estimates. The inventory data from *Vadose Zone Characterization Project at the Hanford Tank Farms Addendum to the C Tank Farm Report* (GJO-HAN-18) provides data for gamma emitting contaminants that is substantially less than the inventory estimate developed through the soil inventory model. For example, the spectral gamma logging effort resulted in a C tank farm inventory estimate for cesium-137 of 42 curies while the soil inventory model identified a cesium-137 inventory of 128,000 curies. Because of this

discrepancy the inventory estimates provided through the spectral gamma logging effort were not used in this RPE. The soil inventory model was used because this report gave a more conservative inventory estimate, which translates into a smaller retrieval leakage threshold volume.

Based on information from GJO-HAN-18, the cesium-137 and cobalt-60 located between tanks C-104 and C-105 is most likely the result of overfilling and subsequent leak from the cascade line (or cascade line connection) between tanks C-104 and C-105. Contamination from this leak appears to have migrated at least 7.6 m (25 ft) below the base of the tank. The horizontal extent cannot be determined because the cesium-137 appears to commingle with contamination from other sources. The cesium-137 contamination detected around the rest of tank C-104 is most likely the result of surface spills and subsurface pipeline leaks that have migrated through the backfill sediments and about 4.6 m (15 ft) into the Hanford formation.

The cobalt-60 contamination detected in the boreholes below and to the northwest of tank C-106 is probably from a nearby tank or subsurface pipeline leak, not tank C-106. Movement of the cobalt-60 has been observed through the recent spectral gamma logging effort; however, because of the anticipated travel time to the groundwater, the short half-life, and the inventory, cobalt-60 was not considered a CoC for the long-term human health risk in this RPE.

B.3.3.2 Retrieval Leak Loss Estimates

The current retrieval planning assumes the use of double-shell tank (DST) supernate to retrieve waste from sludge tanks. The driver for using DST supernate for retrieval is to conserve DST space. Because the C farm tanks are sludge tanks it is assumed that supernate from a number of DSTs will be used for waste retrieval (see Attachment B1). Because there are presently no specific plans for which DSTs will be used to provide supernate for waste retrieval from a given C farm tank, the available supernate was modeled as a composite of supernate from potential DSTs. The use of a composite supernate is not planned for actual retrieval, but is an enabling assumption used to account for retrieval of the sludge tanks with DST supernate. As retrieval plans are made in the future the leak losses from the remaining C farm tanks will have to be re-evaluated. This composite supernate is then assumed to have the same wash factor (tank specific estimate of solubility defined as the fraction of a contaminant inventory in the liquid to the total inventory) properties as water (for conservatism) and final chemical concentrations are calculated for retrieval liquid in each C farm tank. These final chemical concentrations are used to estimate chemical constituent releases due to retrieval leaks. Inventory estimates associated with a retrieval leakage volume of 30,000 L (8,000 gal) are developed for the 100-series tanks. For tank C-104, retrieval leak loss inventory estimates using volumes of 15,000 L (4,000 gal) and 300,000 L (80,000 gal) also are developed. To account for the significantly smaller tank volume of the 200-series tanks, the 30,000-L (8,000-gal) leak loss volume used for the 100-series tanks is scaled by the ratio of the 200-series tank volume to the 100-series tank volume, or one-tenth. Therefore, the 200-series tanks are analyzed using a leak loss volume of 3,000 L (800 gal).

The assumption that all of the C farm tanks will be retrieved using DST supernate is conservative from the long-term risk perspective in that it provides for a higher retrieval leakage source-term

even though it is unlikely that DST supernate would be used on any of the seven tanks that are assumed leakers. A sensitivity case is evaluated in *Enabling Assumptions and Calculations to Support the Tank C-104 Retrieval Performance Evaluation* (HNF-7989) to determine how retrieval source terms vary if the tanks designated as leakers are retrieved using water. The liquid used for waste retrieval will be evaluated on a tank-by-tank basis.

The estimated retrieval leakage volumes are based on meeting limiting conditions for waste transfer. The limiting conditions considered are a maximum supernate concentration of 5 Molar sodium and a maximum value of 10 wt% solids in the retrieved waste. These limits are established to minimize the possible crystallization of sodium-rich salts in the waste transfer lines and to minimize problems transferring slurries. Further discussion of how retrieval liquid concentrations are estimated and how the retrieval leakage source term inventory estimates are used is provided in Attachment B1.

B.3.3.3 Residual Tank Waste Estimates

The chemical and radiological inventories associated with various residual waste volumes have been evaluated for the C farm tanks. Residual tank waste solids volumes evaluated range from 4,900 L (1,300 gal) to 100,000 L (50,000 gal) for tank C-104. Residual waste volumes of 10,000 L (2,700 gal) and 23,000 L (6,000 gal) are evaluated for the remaining 100-series tanks, and 830 L (220 gal) to 2,300 L (600 gal) for the 200-series tanks. These tank residual waste volumes are selected to represent retrieval performances equal to or worse relative to the HFFACO interim retrieval goal of 360 ft^3 (10,000 L [2,700 gal]) for 100-series tanks and 30 ft^3 (830 L [220 gal]) for 200-series tanks and that bracket the HFFACO interim retrieval goal for tank C-104.

The starting point for calculating the residual waste inventory in the C farm tanks is the best-basis inventory estimates developed for each tank (BBI 2000). Some of these estimates are derived from tank waste samples while others depend on engineering evaluation, calculation, or tank composition models as described in *Hanford Tank Chemical and Radionuclide Inventories: HDW Model* (LA-UR-96-3860). Modeling data, through the use of standard templates, are used to describe the composition of waste types in tanks where samples have not been taken. The Hanford defined waste model (LA-UR-96-3860) is used to supply missing analytical values or to define the expected composition of missing analytes in these templates.

The best-basis inventory is normally defined in total kilograms for chemicals and total curies for radionuclides. To calculate the residual waste inventories in the C farm tanks it is assumed that the tank waste will be retrieved using DST supernate as the retrieval medium with, in the case of a 360-ft^3 (or less) retrieval heel, a final water rinse. The final water rinse would transport any soluble species in the waste to the DST receiver tank, leaving water-washed solids as residual waste in each tank. This method for determining residual waste inventories is chosen because it relies on the same data currently being used in the Hanford Tank Waste Operation Simulator (HTWOS) model to simulate all of the tank farm waste retrieval operations from waste retrieval to previtrification separations to glass production.

B.3.3.4 Ancillary Equipment Inventory

The contaminant inventory currently in the abandoned C tank farm ancillary equipment is of interest in calculating the total long-term impacts from the tank farm under a landfill closure type scenario. This inventory would add to the inventory remaining in the tank farm from tank residuals and contaminated soils and would contribute to the closure source term. There is currently insufficient data available to develop a reasonable estimate basis for the contaminant inventory in the ancillary equipment; therefore, an estimate of this inventory was not developed for this RPE. This is believed to be reasonable for this scoping-level RPE because of the following.

- The ancillary equipment inventory will likely be relatively small in comparison to the residual waste inventory remaining in the tanks following retrieval.
- This RPE is targeted at establishing retrieval requirements for initiating waste retrieval efforts in the C tank farm. Future updates to the RPE will allow additional information to be incorporated as it becomes available (e.g., ancillary equipment inventory, actual residual waste inventories, leak loss estimates).
- The risk allocation methodology provides for balancing the risk from an individual tank within the context of the tank farm and the ancillary equipment inventory can be accommodated as one of the other sources in the tank farm.

B.3.4 SHORT-TERM HUMAN HEALTH RISK

The intent of the short-term human health risk analysis is to estimate the potential health impacts from both accident and normal (nonaccident) conditions resulting from various tank retrieval cases for the C tank farms. The analysis identifies the spectrum of potential accidents associated with construction and operation activities. The hazards associated with these activities include potential occupational hazards resulting in physical trauma, radiological exposure resulting in latent cancer fatalities (LCFs), and toxicological exposure resulting in toxic or corrosive health effects. Initiating events that could result in hazardous health effects may include natural phenomena, human error, component failure, and spontaneous reactions. Health risks during normal conditions include anticipated exposure to radiation fields and radiological and chemical releases to the atmosphere during normal retrieval activities.

All waste retrieval cases assume a common closure configuration for the tank farm. Because the short-term human health risk associated with closure activities would be common to all the retrieval cases, it would not be a good differentiator and is therefore not included in this evaluation.

Retrieval losses are assumed to occur at or near the base of the tank. It is not anticipated that the subsurface leaks at the base of the tank would result in an atmospheric release (in the short-term) nor would the ionizing radiation have an appreciable health risk to workers. For this reason the short-term human health risk from various retrieval loss scenarios is not included in this evaluation.

B.3.4.1 Occupational Injuries, Illnesses, and Fatalities

The number of injuries, illnesses, and fatalities resulting from retrieval activities is calculated based on the most currently available incidence rates that would be applicable to the retrieval activities. The number of injuries, illnesses, and fatalities from construction or operations is calculated by multiplying the total person-years required to support the activity by the incidence rates.

B.3.4.2 Radiological Risk From Accidents

Radiological risk is expressed as the number of LCFs resulting from accidents in which people are exposed to radiation fields or radiological constituents released to the atmosphere. The probability of the accident occurring also is evaluated. The methodology used to identify and quantify the radiological risk from accidents involves the following steps.

Step 1. Accident identification. Potential hazards associated with retrieval activities are identified from existing preliminary hazards analyses and other safety documents. The hazards are reported in a tabular format showing, for each accident, the barriers within the facility that prevent or mitigate the consequences of the accident, a rough estimate of the magnitude of consequences of the accident assuming that the listed preventive barriers fail, and the estimated likelihood of the accident occurring.

Step 2. Accident strategy selection. The accident with the highest risk is screened for further analysis to determine, as accurately as possible, the consequences and probability of occurrence. The risk of a given accident is the product of the consequences of the accident and the estimated likelihood of the event occurring. Screening for the highest-risk accidents follows the same methodology as outlined in Section 3.3.2.3.5 of *Preparation Guide for U.S. Department of Energy Nonreactor Nuclear Facility Safety Analysis Reports* (DOE-STD-3009-94).

Step 3. Accident sequence quantification. The frequency of occurrence of the selected accidents is taken from referenced documents where available. Accident frequencies that are not available are estimated.

Step 4. Source-term development. The source term is the respirable fraction of inventory from which the receptor dose is calculated. The source term is developed based on the inventory that could be released into the environment from an accident. The major reduction factors that control the source term are considered in the evaluation. The reduction factors include damage ratios, airborne release fractions, airborne release rates, leak path factors, and respirable fractions. Use of the reduction factors is dependent on the nature of the accident (i.e., energy of accident at impact, waste form, and effectiveness of mitigating barriers). Exposure resulting from direct exposure to radiation under accident conditions also is evaluated. Direct exposure is the direct gamma radiation dose rate to a receptor.

Step 5. Atmospheric Dispersion Coefficients. Atmospheric dispersion coefficient (χ/Q) values are generated using the GXQ computer code following the methodology outlined in *Atmospheric Dispersion Models for Potential Accident Consequence Assessment at Nuclear*

Power Plants (NUREG 1.145). The meteorological data used by the GXQ code is in the form of joint frequency tables. The joint frequency data used are taken from data collected at the meteorology tower in the 200 West Area. The atmospheric dispersion coefficient values are used in equations to calculate the radiological dose experienced by the noninvolved worker and general public receptors as a result of inhaling radioactive materials. Ingestion of radioactive materials also is included for the general public receptor dose, as indicated in Figure B.3.2.

Step 6. Receptor determination. Potential health effects from radiological exposures are estimated for three subsets of populations and maximally exposed individuals (MEIs) in those populations. The dose to a receptor depends on the location of the receptor relative to the point of release of the radioactive material. The involved workers are those involved in the proposed action and are in the workplace performing work at the facility. Those workers are assumed to be in the center of a 10-m- (33-ft-) radius hemisphere where the airborne material has spread instantaneously and uniformly. The noninvolved workers are those that would be on the Hanford Site but not involved in the action. Those workers are assumed to extend from 100 m (330 ft) out to the Hanford Site boundary. The general public is assumed to be located at the site boundary to a distance of 80 km (50 mi) from the point of release. The Hanford Site boundary used in the analysis is the adjusted Site boundary that excludes areas that have been designated as part of the Hanford Reach National Monument (65 FR 7319). These areas include the North Slope, the Hanford Reach of the Columbia River, and the Fitzner-Eberhardt Arid Lands Ecology Reserve. The Site boundaries are as follows:

- North: Columbia River, 0.4 km (0.25 mi) south of the south river bank
- East: Columbia River, 0.4 km (0.25 mi) west of the west river bank
- South: A line running west from the Columbia River, just north of the Energy Northwest leased area, through the Wye Barricade to Highway 240
- West: Highway 240 and Highway 24.

Step 7. Radiological dose assessment. The inventory involved in each accident is evaluated to determine the activity concentrations. The activity concentrations are converted to unit liter dose, or gram, factors. The GENII computer code (PNL-6584) is used to generate a single unit liter dose factor for each composite source term for a 70-year dose commitment period. The receptor doses are given in terms of committed effective dose equivalents. The unit liter dose factors are used along with the appropriate atmospheric dispersion coefficient and the source term to determine the radiological dose to the noninvolved worker and general public receptors.

Step 8. LCF risk development. The likelihood that a dose of radiation would result in a fatal cancer at some future time is calculated by multiplying the receptor dose by a dose-to-risk conversion factor. Conversion factors are predictions of health effects from radiation exposure. The dose-to-risk conversion factors used for estimating LCFs from low doses of radiological exposure and from high doses are consistent with those in *1990 Recommendation of the*

International Commission on Radiological Protection (ICRP 1991). They are summarized as follows:

- **Involved worker and noninvolved worker**: 4.0×10^{-4} LCF/rem for low doses less than 20 rem and 8.0×10^{-4} LCF/rem for doses greater than or equal to 20 rem.

- **General public**: 5.0×10^{-4} LCF/rem for low doses less than 20 rem and 1.0×10^{-3} LCF/rem for doses greater than or equal to 20 rem. The dose-to-risk conversion factors for the general public accounts for the presence of children.

B.3.4.3 Chemical Exposure from Accidents

Potential acute hazards associated with exposure to concentrations of postulated accidental chemical releases are evaluated using a screening-level approach for the receptors. This involves directly comparing calculated exposure point concentrations of chemicals to a set of Hanford Site-specific air concentration screening criteria known as emergency response planning guidelines (ERPGs) (Dentler 1995). The ERPGs, as developed by the American Industrial Hygiene Association, are specific levels of chemical contaminants in air designed to be protective of acute adverse health impacts for the general population. The ERPGs are defined in the following text.

- **ERPG-1** – The maximum airborne concentration below which it is believed that nearly all individuals could be exposed for up to 1 hour without experiencing other than mild transient adverse effects or perceiving a clearly defined objectionable odor.

- **ERPG-2** – The maximum airborne concentration below which it is believed that nearly all individuals could be exposed for up to 1 hour without experiencing or developing irreversible or other serious health effects or symptoms that could impair their ability to take protective action.

- **ERPG-3** – The maximum airborne concentration below which it is believed that nearly all individuals could be exposed for up to 1 hour without experiencing or developing life-threatening health effects.

Determining the accidents to be used in the analysis, the source term, atmospheric dispersion coefficients, and the receptor location follow the same methodology as applied to radiological risk from accidents described earlier.

B.3.4.4 Radiological Latent Cancer Fatality Risk from Routine Exposure

Involved worker exposure is a combination of exposure from inhalation and direct radiation. Involved worker dose rates are estimated based on time, distance, and shielding considerations associated with various tasks. Noninvolved worker and general public exposures are estimated by determining the expected routine radiological releases during retrieval and closure. Noninvolved worker exposure is assumed to be from inhalation and external radiation from the plume continuously throughout a year and from deposition of radionuclides on the ground. The exposure pathways for the general public are assumed to be inhalation, external exposure

from submersion in a plume, and ingestion of contaminated farm products. The involved workers are assumed to be located in the radiation zone. The noninvolved worker population are assumed to be located 100m (330 ft) from the point of release out to the Hanford Site boundary. The general public population includes people located within 80 km (50 mi) of the Hanford Site boundary.

The GENII computer code (PNL-6584) is used to calculate the dose. The LCF risk is then calculated by multiplying the receptor dose by a dose-to-risk conversion factor (ICRP 1991).

B.3.4.5 Chemical Hazards from Routine Exposure

The nonradiological chemical intake (dose) is estimated for the involved worker, noninvolved worker, and general public according to the U.S. Environmental Protection Agency (EPA) methodology used in DOE/RL-98-72.

To estimate the potential noncarcinogenic effects from exposure to multiple chemicals, the hazard index approach is used consistent with the EPA methodology that was used in DOE/RL-98-72. The hazard index is defined as the summation of the hazard quotient (calculated dose divided by the reference dose) for each chemical and route of exposure. A total hazard index less than or equal to 1.0 is indicative of acceptable levels of exposure.

The potential carcinogenic or incremental lifetime cancer risk (ILCR) (i.e., the cancer risk from fatal and nonfatal cancers) from exposure to carcinogenic chemicals is calculated by multiplying the cancer slope factor for each chemical by the exposure intake of each chemical. Carcinogenic risk is assumed to be additive and is estimated by summing the upper-bound incremental cancer risk for all carcinogenic chemical emissions.

B.3.5 GROUNDWATER IMPACTS

Groundwater impacts estimated for the C tank farm are scaled from the DOE/RL-98-72 analyses in which a large number of waste retrieval and residual waste scenarios are considered. A subset of those scenarios is used for this evaluation. Note that the RPE for the S tank farm, which is located in the 200 West Area, is being prepared in parallel with this document using a different approach to assessing groundwater impacts. Factors that include the location of the S tank farm, which is distant from the AX tank farm and the differing vadose zone hydrostratigraphic conditions, make scaling an untenable approach for the S tank farm RPE. The groundwater impact approach for S tank farm follows closely that being developed under the Vadose Zone Project RCRA investigations.

Key to the C tank farm approach is the enabling assumption that vadose zone conditions at the AX tank farm are sufficiently similar to those at the C tank farm to allow for scaling of the AX tank farm groundwater impact assessment results to the C tank farm. A comparison of the vadose conditions at the AX and C tank farms is provided in Attachment B2.

It is recognized that this scaling approach introduces an added degree of uncertainty; however, this added uncertainty is acceptable for this scoping-level RPE because additional analysis will be performed in the future following tank waste retrieval and prior to tank farm closure.

The groundwater concentrations associated with the C tank farm were scaled from those calculated with a finite volume model of the AX tank farm and underlying aquifer. The scaled results for the C tank farm are believed to provide reasonable results and are comparable to the AX tank farm for the following reasons. The groundwater impact assessment approach used in the AX tank farm RPE (DOE/RL-98-72) was based in part on two calculations. First the contaminant flux downward through the vadose zone associated with releases from the tanks was calculated. Then, this contaminant flux was input into one finite volume element of a Sitewide groundwater flow and transport model to calculated the movement and concentration of the contaminants in the groundwater from the vicinity of the tanks to the Columbia River.
The Sitewide model was constructed with a finite volume grid spacing of 250 m by 250 m (820 ft by 820 ft). The AX tank farm consists of 4 tanks with a layout of approximately 90 m by 90 m (300 ft by 300 ft). The contaminant flux through the vadose zone was then input into the finite volume element that was directly beneath the AX tank farm. The larger C tank farm consists of 12 large tanks and 4 small tanks with a layout of approximately 120 m by 150 m (400 ft by 500 ft). Because the C tank farm impacts are scaled form the AX tank farm results, the flux from this tank farm is also effectively input onto a 250 m by 250 m (820 ft by 820 ft) volume element in the Sitewide groundwater model.

As described in Section 3.5 of DOE/RL-98-72, the approach to assessing the groundwater impacts for releases from the AX tank farm began with developing vadose zone and saturated zone conceptual models and associated assumptions based on best available data and analysis. The next step, using these conceptual models as a basis, was to determine uncertainty and most sensitive parameters for the complete pathway beginning with the source and ending with the calculated risk. This focused near-term data collection efforts and numeric model development. Based on the best available data, information learned from model application in the SX tank farm and screening-level analysis numeric models for the AX tank farm, vadose zone and groundwater models were developed. After this step, the migration of contaminants through the vadose zone and groundwater were calculated for the various strategies and options. This approach was intended to be iterative such that analysis would be updated when additional data become available, and these in turn would be used to focus the subsequent data collection efforts on the most important data.

Individual calculations (i.e., numerical model simulations) were performed for the following contaminant source terms:

- Contamination already released to the vadose zone from past tank leaks and spills
- Future waste retrieval leakage releases
- Tank and ancillary equipment waste residual releases.

The calculated contaminant flux through the vadose zone from each of these sources was used as input to a sitewide two-dimensional groundwater flow model that calculated the contaminant concentrations in the unconfined aquifer at selected time periods over a 10,000-year period. The fact that the groundwater impacts from each of the three AX tank farm source terms were calculated separately enables the evaluation of the AX tank farm results for the specific contaminant inventory scenarios associated with the C tank farm.

The PORFLOW numerical model (NUREG/CR-5991) was used to implement the calculation of flow and transport in the vadose zone and saturated zone (i.e., the unconfined aquifer or groundwater). PORFLOW numerically solves a variable set of equations for general transport, multi-phase pressure, and one or more chemical species. The governing equations are supplemented by constitutive equations, phase-change relations, equations of state, and initial and boundary conditions. Numerical implementation of the vadose zone flow and transport portion of the problem was based on the vadose zone conceptual model specifically developed for conditions known or assumed for the AX tank farm.

The saturated zone (groundwater) conceptual model is a working model describing the horizontal flow and transport of contaminants from the point where they reach the unconfined aquifer immediately below the AX tank farm to where they reach a receptor or are discharged to the Columbia River. The conceptual groundwater model used for the AX tank farm impact assessment was modified from *Composite Analysis for Low-Level Waste Disposal in the 200 Area Plateau of the Hanford Site* (PNNL-11800). PNNL-11800 uses a three-dimensional transient flow and transient transport model for groundwater flow and transport (PNL-10886; PNNL-11665; PNNL-11801). In general, the hydraulic and transport parameters adopted for the AX tank farm groundwater model can be traced back to the site groundwater model used in PNNL-11800, although implementation is significantly different. The large number of strategies that required analyses coupled with a long-term period of interest (10,000 years) necessitated an approach that was computationally efficient yet provided the appropriate level of detail. Numerical implementation and testing of both the AX tank farm vadose zone and groundwater model are provided in Appendix B of DOE/RL-98-72.

B.3.6 LONG-TERM HUMAN HEALTH RISK

The intent of the long-term human health risk analysis is to estimate the potential health effects to a hypothetical future site user from exposure to tank waste contaminants remaining onsite following the completion of waste retrieval and tank farm closure actions. The analysis identifies the peak risks at the tank farm boundary under residential farmer and industrial worker scenarios. Peak risks at the tank farm boundary from hazardous chemicals are also evaluated using the State of Washington "Model Toxics Control Act" (MTCA) Method B and C scenarios. The approach for this risk assessment is consistent with the overall RPE approach established in DOE/RL-98-72. The risks presented in this RPE are incremental risks. A cumulative risk analysis was not conducted to account for potential contamination from nearby waste sites.

Groundwater is considered the principal pathway (excluding inadvertent intrusion) for post-remediation human exposure to tank waste at compliance points outside of the tank farm boundary. The exposure pathways used in this assessment are therefore based on withdrawal and use of groundwater via wells.

The DOE/RL-98-72 analysis uses a contaminant transport analysis to predict the distribution of tank waste contaminants in time and space over the post-remediation period of interest. For this evaluation, groundwater contaminant concentrations are estimated by scaling from the results of the DOE/RL-98-72 analysis. It is recognized that long-term human health risk values calculated based on scaled groundwater concentrations contain an added level of uncertainty. Despite this

uncertainty, a scaling approach is considered appropriate for this evaluation given that there are no new vadose zone characterization data available to support detailed contaminant transport modeling and the waste retrieval performance of the remaining C farm tanks is uncertain. The approach presented in this section is intended only to support decisions related to waste retrieval from tank C-104. It is anticipated that final closure decisions for tank C-104 and the C tank farm as a whole will require more rigorous evaluation, including numerical modeling of contaminant fate and transport.

B.3.6.1 Contaminants of Concern

The CoCs considered in this evaluation are largely consistent with those used in DOE/RL-98-72. Those CoCs are as follows.

- **Radionuclides**: carbon-14, selenium-79, technetium-99, iodine-129, and uranium isotopes -233, -234, -235, -236, and -238.
- **Chemicals**: nitrite, nitrate, chromium, and total uranium.

This CoCs subset was selected for inclusion in DOE/RL-98-72 based on a screening analysis that indicated these constituents would be highly mobile in the vadose zone and groundwater and would contribute approximately 95% of the total groundwater pathway long-term human health risk. Inventory estimates could not be developed for cyanide and ethylenediaminetetraacetic acid (EDTA) because cyanide and EDTA are not routinely analyzed for and are not part of the best-basis inventory standard list of constituents (BBI 2000). EDTA is present in the estimated past leak inventory for several C farm tanks; however, no scaling factor could be developed for EDTA in the past leak source term because EDTA was not present in the past leak inventory for AX tank farm. Additionally, chromium has been identified as a CoC in the RCRA facility investigation/corrective measures study process and is included as a CoC in this analysis. The chemical CoCs for this evaluation therefore consist of nitrite, nitrate, and chromium.

B.3.6.2 Scaling Factors

Scaling factors for this RPE are calculated as the ratio of contaminant-specific groundwater concentration to initial source inventory.

$$K^{i}_{S(x,y,t)} = \frac{C^{i}_{S(x,y,t)}}{I^{i}_{S(AX)}} \qquad \text{Eq. B.1}$$

Where:

$K^{i}_{S(x,y,t)}$ = scaling factor for contaminant i released from source term S

$C^{i}_{S(x,y,t)}$ = groundwater concentration of contaminant i from source term S (DOE/RL-98-72 model output)

$I^{i}_{S(AX)}$ = initial source inventory of contaminant i released from source term S (DOE/RL-98-72 model input).

Receptor groundwater concentrations for this RPE are calculated as the product of the contaminant-specific scaling factors and the C tank farm source inventories. The DOE/RL-98-72 groundwater concentrations used to derive the scaling factors are taken at the AX tank farm boundary at the time of peak human health risk over the 10,000-year analysis period. Risks calculated with these scaling factors are therefore assumed to provide peak risks at the C tank farm boundary.

The DOE/RL-98-72 analysis evaluates one release scenario for past leaks and multiple release scenarios (i.e., variations in release volume) for retrieval leakage and residual waste. The latter scenarios comprise retrieval leakage volumes of 30,000 L (8,000 gal) and 150,000 L (40,000 gal) per tank; and residual waste volumes of 1,020; 10,200; and 102,000 L (270; 2,700; and 27,000 gal) per tank. Each DOE/RL-98-72 release scenario provides the basis for generating a set of contaminant-specific scaling factors (six sets in all) for use in this evaluation.

To support the development of tank C-104 risk-based retrieval performance criteria, this evaluation considers 10 retrieval leakage and residual waste release cases. Cases equivalent to those scenarios analyzed in DOE/RL-98-72 are evaluated, plus additional release cases as needed to bracket the risk-based regulatory action thresholds (e.g., the 1×10^{-4} federal and 1×10^{-5} state criteria for excess lifetime cancer risk). The corresponding scaling factor from DOE/RL-98-72 is used for C tank farm retrieval leakage volumes of 30,000 L (8,000 gal) and 150,000 L (40,000 gal) per tank; and for residual waste volumes of 830; 10,000; and 100,000 L (220; 2,700; and 27,000 gal) per tank. For C tank farm waste retrieval leakage and residual waste volumes lying between or outside of the volumes evaluated in DOE/RL-98-72, the scaling factor values are estimated by linear approximation (i.e., interpolation or extrapolation from the nearest data points). Discussion of the calculations used for scaling factors and tables showing scaling factors for past leak, retrieval leak loss, and residual waste source terms are provided in HNF-7989.

B.3.6.3 Exposure

The principal long-term human health risk receptor scenarios used for this evaluation are taken from the *Tank Waste Remediation System, Hanford Site, Richland, Washington, Final Environmental Impact Statement* (DOE/EIS-0189) analysis and include the residential farmer and industrial worker scenarios. Both scenarios were adapted for use in DOE/EIS-0189 from scenarios described in *Hanford Site Risk Assessment Methodology* (DOE/RL-91-45). Both scenarios involve multi-pathway groundwater exposures based on hypothetical future land uses and activities.

B.3.6.3.1 Residential Farmer Scenario. The residential farmer scenario represents exposures associated with the use of the land for residential and agricultural purposes. This scenario is a slight modification to the residential scenario described in DOE/RL-91-45; it includes all of the exposure pathways for the residential scenario plus most of the food ingestion pathways described in the DOE/RL-91-45 agriculture scenario. The residential farmer scenario includes using groundwater for drinking water (ingestion rate of 2 L/day [0.5 gal/day]) and other domestic uses as well as for irrigation to produce and consume animals, vegetables, and fruit products. The exposures are assumed to be continuous and include occasional shoreline-related recreational activities, which include contact with surface water sediments. A composite adult is

used as the receptor for some of the exposure pathways. The composite adult is evaluated using child parameters for 6 years and adult parameters for 24 years, with total exposure duration of 30 years. Body weights of 16 kg (35 lb) for a child and 70 kg (150 lb) for an adult and a lifetime of 70 years are assumed.

B.3.6.3.2 Industrial Worker Scenario. The industrial worker scenario represents exposures to workers in a commercial or industrial setting. The receptors are adult employees assumed to work at a location for 20 years. A body weight of 70 kg (150 lb) and a lifetime of 70 years are assumed. The scenario involves mainly indoor activities, although outdoor activities (e.g., soil contact) also are included. The groundwater exposure pathways for this scenario include drinking water ingestion (1 L/day [0.2 gal/day]), dermal absorption during showering, shower-water ingestion, and inhalation. These exposures would not be continuous because the worker would go home at the end of each work day (i.e., after 8 hours). The scenario is intended to represent nonremediation workers who do not wear job-specific personal protective equipment.

Analysis of MTCA Method B and Method C exposure scenarios (WAC 173-340-720) is also included to allow for comparison to risks being assessed for past tank leaks and releases at SST waste management areas under the RCRA corrective action process (DOE/RL-99-36).
The MTCA risk assessment criteria apply only to nonradioactive contaminants. Method B and Method C exposure scenarios essentially assume unrestricted and restricted use of groundwater, respectively, and are based on ingestion of drinking water (with an inhalation correction factor for volatile chemicals).

It is important to note that all of the scenarios require an assumption that groundwater wells are drilled at the downgradient C tank farm boundary and used as a water supply for the receptors.

B.3.6.4 Risk

Long-term human health risk is calculated for this evaluation using an unit risk factor (URF) approach consistent with the approach used for the DOE/EIS-0189 and DOE/RL-98-72 analyses. An URF is the risk associated with exposure to one concentration unit (e.g., risk per pCi/L for radionuclides in groundwater) of a given contaminant in a given exposure medium for a given human exposure scenario. Risk is calculated in the URF approach as the product of the URF and the contaminant concentration at the receptor for the exposure medium of interest. As previously discussed, the exposure medium of interest for this evaluation is groundwater and the contaminant concentration values used are scaled from the results of the DOE/RL-98-72 analysis. The URF values used for this analysis are contaminant- and scenario-specific groundwater URFs taken from Appendix D of DOE/EIS-0189. The URFs for the industrial worker and residential farmer scenarios are listed in Table B.3.2. The human health impact measures given by the URFs are ILCR for radionuclides and carcinogenic chemicals, and hazard index (sum of individual hazard quotients) for noncarcinogenic chemicals. ILCRs differ from LCFs in that ILCRs are total cancers (nonfatal and fatal) where LCFs are fatal cancers.

Table B.3.2. Groundwater Pathway Unit Risk Factors

Constituent	Units	Industrial Worker[a]	Residential Farmer[b]
C-14	ILCR per Ci/mL	5.23E+06	6.06E+08
I-129	ILCR per Ci/mL	9.33E+08	1.29E+10
Se-79	ILCR per Ci/mL	3.22E+07	2.87E+08
Tc-99	ILCR per Ci/mL	7.11E+06	2.61E+08
U-233	ILCR per Ci/mL	3.03E+08	1.38E+09
U-234	ILCR per Ci/mL	3.00E+08	1.34E+09
U-235	ILCR per Ci/mL	2.98E+08	1.37E+09
U-236	ILCR per Ci/mL	2.85E+08	1.27E+09
U-238	ILCR per Ci/mL	2.84E+08	1.28E+09
NO2	HQ per g/mL	9.92E+03	3.73E+04
NO3	HQ per g/mL	6.20E+03	7.59E+06
Cr	HQ per g/mL	3.31E+06	1.14E+07
U (Total)	HQ per g/mL	3.52E+06	1.41E+07

[a]Source = DOE/EIS-0189, Appendix D, Tables D.2.1.21 and D.2.1.23.
[b]Source = DOE/EIS-0189, Appendix D, Tables D.2.1.18 and D.2.1.20.

HQ = hazard quotient.
ILCR = incremental lifetime cancer risk.

The basic expression for risk using an URF approach is:

$$R_{S(x,y,t)} = \sum C^{i}_{S(x,y,t)} \cdot URF^{i}_{R} \qquad \text{Eq. B.2}$$

Where:

$R_{S(x,y,t)}$ = risk from source term S at point of compliance x,y,t

$C^{i}_{S(x,y,t)}$ = groundwater concentration at point of compliance x,y,t for contaminant i released from source term S

URF^{i}_{R} = groundwater URF for contaminant i and receptor scenario R

x,y = horizontal location coordinates

t = time.

The summation in Equation B.1 represents addition of the contributions from all CoCs in a given source term. The addition of contributions from the past leak, retrieval leakage, and residual waste source terms gives the composite risk for a given tank. The addition of composite risks for all tanks gives the composite risk for the tank farm.

Equation B.1 is used to calculate human health risk for all release cases included in the contaminant transport analysis. Additional cases for retrieval leakage and residual waste volumes intermediate to those included in the modeling runs are likely to be of interest for establishing risk-to-volume relationships. For these cases, risks are estimated by interpolation using a linear approximation.

Calculation detail for long-term human health risk is in HNF-7989. The long-term human health risk calculation results are used to develop risk-versus-volume relationships. Risk-based retrieval performance criteria (i.e., retrieval leakage limits and extent of retrieval requirements) are developed by plotting the human health risk values calculated for the retrieval cases against either retrieval leakage volume or residual waste volume. The risk values plotted can be either source-term specific or composite values. Plots using tank-specific risk and volume data for tank C-104 are of interest because they provide the primary basis for determining retrieval performance criteria for tank C-104. Plots using risk and volume data for the entire C tank farm are also of interest because they provide a sense of how quickly the C tank farm risk performance will change with departure from the baseline retrieval leakage and residual waste assumptions. The overall objective is to provide a range of combinations of residual waste volume and retrieval leak loss volume that would allow the tank C-104 composite risk to maintain compliance with certain risk-based regulatory standards.

B.3.6.5 Risk Allocation

In order to evaluate retrieval leakage within the context of tank farm risk, a risk allocation method is used. The methodology used involves selection of a risk threshold (i.e., 1.0×10^{-5}) and developing a risk budget for retrieval leakage. The methodology includes the following steps:

- Calculate the risks on a tank farm basis from past leaks and spills
- Calculate the risk budget for the tank farm by subtracting the risk from past leaks from the risk threshold
- Calculate a risk budget for tank C-104 by apportioning the tank farm risk budget by the fraction of the C farm waste volume contained in tank C-104.

Tank C-104 currently has 1,000,000 L (263,000 gal) and the C farm has 6,800,000 L (1,784,000 gal) of waste. Therefore C-104 contains 14.7% of the waste in the tank farm. Using this methodology, the risk budget for tank C-104 is equal to 14.7% of the tank farm risk budget. There are uncertainties associated with risk allocation on a tank farm basis when using the tank farm fenceline as the point of compliance.

B.3.7 INTRUDER RISK

The intent of the inadvertent human intrusion analysis is to estimate the potential health effects to a hypothetical future site user from exposure to tank waste contaminants remaining onsite following waste retrieval and tank farm closure actions. The inadvertent human intruder is assumed to excavate into or drill through the contamination within the tank farm.
The methodology used for assessing intruder impacts is consistent with the approach used in

DOE/RL-98-72. Because a well is only a few inches in diameter and can only penetrate one tank at a time, the intruder analysis addresses tank C-104 impacts only. The purpose of the intruder assessment is to support an analysis of compliance requirements and waste classification issues related to tank C-104 waste retrieval and closure. Intruder impacts are examined based on scenarios and requirements established in DOE regulations (DOE O 435.1; Frei 1996) and NRC regulations (10 CFR 61) related to LLW disposal.

B.3.7.1 U.S. Department of Energy Intruder Scenario

The DOE demonstrates protection of the inadvertent human intruder through site-specific performance assessments using a 100-mrem/yr chronic dose standard and a 500-mrem acute dose standard. The scenarios used in this RPE are consistent with those used in DOE/RL-98-72 and are based on the intrusion model in *Performance Assessment for the Disposal of Low-Level Waste in the 200 West Burial Grounds* (WHC-EP-0645). The scenarios used are the well driller scenario and the post-drilling resident scenario. These scenarios were selected based on their applicability to the deep contamination sources (i.e., tank residual waste and soil contaminated by retrieval leak loss) involved in this analysis.

Table B.3.3 presents the unit dose factors for each radionuclide-of-concern in the exhumed waste under the previously listed exposure conditions for the well driller and post-drilling resident scenarios. These dose factors are calculated using the GENII computer code (PNL-6584) and are the same as those used in DOE/EIS-0189. The unit dose factors are calculated for 100 years from tank closure, corresponding to the time of assumed loss of institutional control.

Table B.3.3. Intruder Scenario Unit Dose Factors at 100 Years from 1998

Radionuclide	Dose Factor (mrem per curies exhumed)	
	Well Driller	Post-Drilling Resident
Strontium-90	6.93E-01	8.42E+01
Tin-126	2.13E+03	6.93E+03
Cesium-137	6.13E-01	2.03E+02
Plutonium-238	8.29E+01	2.82E+02
Uranium-238	5.49E+01	2.15E+02
Plutonium-239	2.04E+02	6.96E+02
Plutonium-240	2.00E+02	6.91E+02
Americium-241	1.01E+03	3.27E+03
Plutonium-241	6.42E+00	2.21E+01

Contaminant transport is not considered for this analysis. Contaminants are assumed to be exhumed during well drilling and spread over the surface of certain land areas. The intruders receive radiation exposures because of their proximity to and use of these contaminated surface areas. The analysis considers radionuclide contaminants only. These radionuclides were

selected because their half-lives are greater than five years and they have been shown in past performance assessments to dominate intruder doses (DOE/EIS-0189).

The source is calculated as the total activity in curies of each constituent exhumed and made available at the surface. The well is assumed to be drilled through the residual waste in tank C-104 and into the underlying soil column down to the aquifer. The source is calculated based on the residual waste in tank C-104 and the contaminated soil from retrieval leakage. The source (Ci_{exh}) from tank C-104 is calculated using the following equation:

$$Ci_{exh} = Ci_{tnk} \cdot [r_{well} + r_{tnk}]^2 \qquad \text{Eq. B.3}$$

Where:

Ci_{tnk} = total activity of each radionuclide of concern in tank C-104
r_{well} = radius of the well or 0.15 m (0.5 ft)
r_{tnk} = radius of tank C-104 or 11.4 m (37.5 ft).

The source activity (Ci) is then multiplied by a unit dose factor (mrem/yr/Ci) for each receptor (well driller and post-drilling resident) to produce the receptor dose (mrem/yr). Unit dose factors are calculated for a unit activity (Ci) for each constituent based on the exposure conditions defined for each receptor. The well driller dose is from 40 hours of external exposure to the exhumed contaminants. The following is assumed of the post-drilling resident:

- Lives on a 2,500-m^2 (27,000-ft^2) parcel of land over which the exhumed waste has been spread
- Grows a variety of vegetables on the land
- Obtains 25% of total vegetables consumed from this garden.

The post-drilling resident ingests small amounts of contaminated soil each day (100 mg/day [0.004 oz/yr] and the total ingestion is 37 mg/yr (1.3 oz/yr). The annual inhalation and external exposures are based on the post-drilling resident spending 1,800 hours in his garden and 4,380 hours in his house. The remaining 2,580 hours is spent elsewhere away from the intruder site.

B.3.7.2 U.S. Nuclear Regulatory Commission Intruder Scenario

The NRC intruder scenario is considered in this analysis because of its implications to tank farm closure; closure options may be bounded by concentration of radionuclides in residual waste volumes remaining after retrieval. The NRC intruder scenario is described in "Licensing Requirements for Land Disposal of Radioactive Waste" (10 CFR 61). It is applied in this analysis not in terms of determining risk to the intruder but because it led to the derivation of a classification system for waste based on maximum concentration levels of radionuclides. Meeting Class C limits is a criterion in determination of incidental waste, which can be handled as LLW as described in Section B.3.8.1.1. Therefore, in this RPE the concentration of

radionuclides in the tank C-104 residual waste will be compared to the Class C limits derived through the NRC intruder scenario shown in Table B.3.4.

Table B.3.4. Class C Low-Level Waste Upper Concentration Limits

Long-Lived Radionuclides	Class C Upper Limits	Short-Lived Radionuclides	Class C Upper Limits
Carbon-14	8 Ci/m^3	Nickel-63	700 Ci/m^3
Carbon-14 in activated metal	80 Ci/m^3	Nickel-63 in activated metal	7,000 Ci/m^3
Nickel-59 in activated metal	220 Ci/m^3	Strontium-90	7,000 Ci/m^3
Niobium-94 in activated metal	0.2 Ci/m^3	Cesium-137	4,600 Ci/m^3
Technetium-99	3 Ci/m^3		
Iodine-129	0.08 Ci/m^3		
Alpha emitting transuranic with $t_{1/2} > 5$ yr	100 nCi/g		
Plutonium-241	3,500 nCi/g		
Curium-242	20,000 nCi/g		

Source: 10 CFR 61.

Class C waste concentration limits were derived based on calculated doses to inadvertent intruders, assuming intrusion occurred at 500 years after waste disposal. The intruder is assumed to contact the disposed waste while performing typical excavation work such as installing utilities, putting in basements, etc. Two scenarios were considered in developing the Class C limits: intruder-construction scenario and intruder-agriculture scenario. Class C limits are the waste concentrations that would deliver either a 500-mrem dose to the whole body or bone, or a 1,500-mrem dose to other organs under an intruder-construction or intruder-agriculture scenario (HNF-3428).

The Savannah River Site recently operationally closed two tanks that had been used to store mixed HLW. As part of the closure process, the unretrievable waste was stabilized in grout through a process described in *Summary of Communication with DOE Tank Sites on Tank Closure Issues* (Shyr and Bustard 1997) in accordance with *Branch Technical Position on Concentration Averaging and Encapsulation* (NRC 1995). In a December 1999 draft letter response from NRC to DOE Savannah River Site, the following statements were made with respect to conformance with criterion two of the incidental waste criteria (Paperiello 1999):

> Staff believes that concentration averaging in accordance with the Branch Technical Position on Concentration Averaging, is generally acceptable in this context to meet Class C concentration limits, and recognizes that the alternative provisions for waste classification proposed by DOE are generally similar to those in 10 CFR 61.58. The NRC proposes that the alternative provision for waste reclassification meet the following concentration limits. No radionuclide concentration shall exceed ten times the value specified in Table 1 of 10 CFR 61.55, at 500 years following the proposed Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) closure for each tank grouping, and no radionuclide concentration shall exceed the value

specified in Table 2 Column 3 in 10 CFR 61.55. The procedure established in 10 CFR 61.55(a)(7) shall be followed such that the sum of the fractions for all Table 1 radionuclides shall not exceed ten, and the sum of the fractions for all Table 2 radionuclides shall not exceed one.

The formulae for uniformly mixing grout with residual waste to yield concentrations that do not exceed Class C limits developed at the Savannah River Site may be applied to the residual waste in tank C-104, based on the results of other analyses in this evaluation. The feasibility of uniformly mixing the required amount of grout with the residual waste is uncertain. The criteria used to evaluate the stabilization and/or encapsulation of the residuals with grout are uncertain.

B.3.8 REGULATORY COMPLIANCE

Hanford Site tank waste and SST and DST facilities are regulated through the federal RCRA, the Washington State HWMA, and their implementing requirements. The Washington State Department of Ecology (Ecology) is authorized to implement HWMA requirements in lieu of federal program requirements pursuant to RCRA. EPA retains the federal authority for oversight of the state hazardous waste program and for elements of RCRA not yet authorized. Regulatory requirements applicable to Hanford Site tank wastes and tank waste systems include but are not limited to those specifying requirements for waste designation, permitting, storage, treatment, disposal, response to releases, and site closure (Fitzsimmons and Clarke 2000).

Regulations that may affect waste retrieval performance issues are addressed in this report. The methodology is to:

- Identify the potentially applicable regulations
- Develop a list of quantitative and qualitative performance measures
- Compare strategy and option performance against the measures
- Develop conclusions regarding ability of strategies to comply
- Refine performance measures based on regulations, analysis, and conclusions
- Identify data needs and uncertainties to support future analysis and decision making.

Statutory, regulatory, and permit requirements relevant to the retrieval and disposal of tank waste, contaminated soils, and tanks and ancillary equipment are described in Section B.3.8.1. Regulatory compliance of the tank C-104 waste retrieval approach is addressed in Section B.3.8.2.

B.3.8.1 Relevant Regulations and Requirements

Relevant federal and state statutes and regulations are addressed in the following sections.

B.3.8.1.1 Federal Statutes and Regulations. Table B.3.5 summarizes federal requirements that may apply to waste retrieval and endstate analysis associated with establishing waste retrieval performance measures. A more complete discussion of federal regulations is provided in Appendix D of DOE/RL-98-72.

Table B.3.5. Relevant Federal Statutes and Regulations

Federal Statutes and Regulations	Relevance
Resource Conservation and Recovery Act	Establishes requirements for the identification, generation, treatment, transportation, storage, and disposal of hazardous waste including mixed waste.
Federal Facility Compliance Act	Requires all federal facilities (e.g., the Hanford Site) to comply with RCRA and establishes requirements for DOE facilities pertaining to mixed waste.
Atomic Energy Act	Establishes the jurisdiction of federal and state agencies to regulate radioactive materials and provides requirements for such regulations.
Nuclear Waste Policy Act	Provides for development of repositories for disposal of HLW and spent nuclear fuel.
Clean Air Act	Regulates emissions of radioactive and nonradioactive pollutants from stationary sources.
Safe Drinking Water Act	Establishes standards for drinking water and groundwater protection.
Toxic Substances Control Act	Regulates toxic chemicals, specifically PCBs and asbestos.
Clean Water Act	Regulates discharges to and quality of surface water bodies (e.g., the Columbia River).
Occupational Safety and Health Act	Regulates safe and healthful working conditions.
Comprehensive Environmental Response, Compensation, and Liability Act	Provides emergency response, reporting, and cleanup requirements for uncontrolled release of contaminants.
National Environmental Policy Act	Requires analysis of potential impacts to human health and the environment of any major federal action.

DOE = U.S. Department of Energy.
HLW = high-level waste.
PCB = polychlorinated biphenyl.
RCRA = *Resource Conservation and Recovery Act of 1976.*

The following paragraphs summarize the federal statutes and regulations that affect tank waste retrieval and closure and are largely excerpted from *Regulatory Closure Options for the Residue in the Hanford Site Single-Shell Tanks* (HNF-3428). Three federal entities have the majority of regulatory authority for the disposal of radioactive waste: EPA, DOE, and NRC. Each of these entities has codified various laws, orders, directives, guidance documents, and branch technical positions that govern the various types of radioactive waste.

EPA has the authority to write standards, DOE has authority to write and enforce standards for radioactive wastes from atomic energy defense activities, and NRC has the authority to write and enforce regulations for disposal of commercially-generated LLW and for disposal of HLW. However, regulatory authority may depend on whether the radioactive waste has yet to be disposed of or the waste has already been released to the environment, (e.g., a spill or leak). EPA has the lead role for writing regulations, and DOE and NRC regulations and orders cannot

be inconsistent with EPA standards. There are many notable exceptions to these generalizations (HNF-3428).

Nuclear energy became subject to federal regulation with the passing of the *Atomic Energy Act of 1946*. With amendments the act later became the *Atomic Energy Act of 1954*. Through the *Atomic Energy Act of 1954*, Congress gave control of the production and use of fissile materials to the Atomic Energy Commission. The *Atomic Energy Act of 1954* has been amended a significant number of times.

When the EPA was created in 1970 by Reorganization Plan Number 3, President Nixon transferred the functions of the Atomic Energy Commission for establishing generally applicable environmental standards for the protection of the environment from radioactive materials "in the general environment outside the boundaries of locations under the control of persons possessing or using radioactive material." Thus, the EPA was granted the authority to set release standards but not the authority to implement the release standards. Later, Congress granted the EPA authority to address the cleanup of radioactive materials under the *Comprehensive Environmental Response, Compensation, and Liability Act of 1980* (CERCLA) to regulate air emissions of some radionuclides. Congress also asked the EPA to certify DOE compliance with "Environmental Radiation Protection Standards for Management and Disposal of Spent Nuclear Fuel, High-Level and Transuranic Radioactive Wastes" (40 CFR 191) and "Criteria for the Certification and Re-certification of the Waste Isolation Pilot Plant's Compliance with the 40 CFR 191 Disposal Regulations" (40 CFR 194) for the disposal of TRU wastes in the Waste Isolation Pilot Plant.

In 1974, the *Energy Reorganization Act of 1974* redirected federal energy efforts. The Atomic Energy Commission was abolished and replaced by the NRC and the Energy Research and Development Agency (which was later abolished and became DOE). Section 202 of the *Energy Reorganization Act of 1974* also gave the NRC licensing authority for facilities used primarily for the receipt and storage of HLW. Under this Section 202 authority NRC licenses the disposal of HLW.

The *Nuclear Waste Policy Act of 1982* establishes federal responsibility for the development of repositories for the disposal of HLW and spent nuclear fuel. DOE has responsibility for the disposal of commercially generated wastes with radionuclide concentrations exceeding the limits established in 10 CFR 61 for Class C LLW (i.e., Greater Than Class C [GTCC] LLW). This law requires the NRC to license the DOE facility for disposal of commercially-generated GTCC LLW.

The NRC has regulatory responsibilities under the *Atomic Energy Act of 1954* for establishing standards for the disposal of radioactive waste. NRC has established regulations for low-level radioactive waste that can be disposed of in near-surface disposal sites (10 CFR 61) and for high-level radioactive waste requiring disposal in a geologic repository (10 CFR 60). Under authority of the *Atomic Energy Act of 1954*, EPA has promulgated standards for managing and disposing of spent nuclear fuel, HLW, and TRU waste (40 CFR 191). EPA standards for managing and disposing of LLW are not yet finalized (10 CFR 193).

The *Atomic Energy Act of 1954* authorizes DOE to establish standards to protect health or minimize dangers to life or property for activities under DOE jurisdiction. Through a series of DOE orders, an extensive system of standards and requirements has been established to ensure safe operation of DOE facilities. The most relevant of these is *Radioactive Waste Management* (DOE O 435.1), which establishes requirements for managing DOE HLW, TRU waste, LLW, and the radioactive component of mixed waste.

According to definitions in *Radioactive Waste Management Manual* (DOE M 435.1), HLW is the highly radioactive waste material resulting from the reprocessing of spent nuclear fuel, and other highly radioactive material that is determined to require permanent isolation. TRU waste is radioactive waste containing more than 100 nanocuries of alpha-emitting TRU isotopes per gram of waste, with half lives greater than 20 years. Low-level radioactive waste is radioactive material that is not high-level, spent nuclear fuel, TRU waste, byproduct material (as defined in Section 11e[2] of the *Atomic Energy Act of 1954*), or naturally occurring radioactive material. Therefore HLW is defined by source (i.e., spent nuclear fuel); TRU waste is defined by isotope concentration and half-life; and LLW is defined by what it is not (i.e., it is not HLW, spent fuel, TRU waste, or byproduct material).

DOE M 435.1 is organized into four chapters. Chapter I contains requirements and responsibilities applicable to all radioactive waste types and delineates responsibilities for radioactive waste management decision making at the complex-wide and Field Element levels. Chapter II contains those requirements applicable to HLW, Chapter III discusses TRU waste, and Chapter IV discusses LLW.

Chapter II of DOE M 435.1 includes a discussion of general requirements for disposal of HLW. NRC determines whether HLW resulting from reprocessing spent nuclear fuel is considered *incidental to reprocessing*. If it is incidental it is not HLW and is managed under DOE regulatory authority in accordance with the requirements for TRU waste or LLW, as appropriate. The NRC uses either the citation or evaluation process to determine whether spent nuclear fuel reprocessing plant waste is managed as LLW, TRU waste, or HLW. Waste incidental to reprocessing by citation includes spent nuclear fuel reprocessing plant wastes that meet the description for proposed Appendix D of "Policy Relating to the Siting of Fuel Reprocessing Plant and Related Waste Management Facilities" (10 CFR 50). These radioactive wastes are the result of reprocessing plant operations such as, but not limited to, contaminated job wastes including laboratory items such as clothing, tools, and equipment.

Determinations that any waste is incidental to reprocessing by the evaluation process shall be documented to support the determinations. Such wastes may include spent nuclear fuel reprocessing plant wastes that will be managed as LLW and meet the following:

- Have been processed to remove key radionuclides to the maximum extent technically and economically practical
- Will be managed to meet safety requirements comparable to the performance objectives in 10 CFR 61

- Will be incorporated in a solid physical form at a concentration that does not exceed the applicable concentration limits for Class C LLW as set out in 10 CFR 61.55, or will meet alternative requirements for waste classification and characterization as DOE may authorize.

The waste may be managed as TRU waste and meet the following:

- Have been processed to remove key radionuclides to the maximum extent technically and economically practical
- Be incorporated in a solid physical form and meet alternative requirements for waste classification and characteristics as DOE may authorize
- Be managed pursuant to DOE authority under the *Atomic Energy Act of 1954* in accordance with Chapter III of DOE M 435.1.

A second set of laws and guidance documents is applicable to cleanup of radioactive wastes. Of these laws, the CERCLA and the regulations created to implement the statute are the broadest. CERCLA provides EPA with authority to address releases and threatened release of hazardous substances, including radioactive wastes. The EPA CERCLA Program has created a system to designate the highest priority sites for cleanup, and those sites are National Priorities List sites. The Hanford Site is on the National Priorities List.

RCRA establishes requirements for generators and transporters of hazardous waste and also establishes a specific permit program for TSD of hazardous waste. For purposes of this report, RCRA covers the statute and all amendments including the *Hazardous and Solid Waste Amendments of 1984*, the *Federal Facility Compliance Act of 1992*, and the *Land Disposal Program Flexibility Act of 1996*. RCRA creates cradle-to-grave regulations for the generation, identification, transportation, and TSD of hazardous waste; RCRA imposes requirements on all persons including DOE that perform regulated activities. EPA regulations implementing RCRA are found at 40 CFR 260 through 40 CFR 280.

Most, but not all, of the EPA hazardous waste program at the Hanford Site is delegated to Ecology (Rosenthal 1997). EPA delegated the RCRA-based program to Ecology in 1986.

B.3.8.1.2 Washington State Statutes and Regulations. Ecology and the Washington State Department of Health administer Washington State environmental requirements applicable to retrieval and closure actions. Those requirements are described in the following sections.

B.3.8.1.2.1 Hazardous Waste Management Act. The HWMA and its implementing regulations in "Dangerous Waste Regulations" (WAC 173-303), implement RCRA in Washington State. The HFFACO provides the framework for applying the state's requirements for dangerous waste TSD units at the Hanford Site. WAC 173-303 specifies requirements for design, permitting, operation, closure, and post-closure of dangerous and mixed waste management sites, including the tank farms. There are some differences between Washington State dangerous waste regulations and federal hazardous waste regulations. The state definition of dangerous waste includes more types of waste than does the federal definition of hazardous

waste. For example, the state regulations do not exclude source, special nuclear, and byproduct material from the definition of dangerous waste (Rosenthal 1997). Washington State also designates specific types of state-only dangerous waste, including extremely hazardous waste, that is subject to more stringent regulations (Rosenthal 1997). Other differences exist between the state and federal regulations on contained-in determinations, closure, and corrective actions.

The SSTs are classified as HWMA TSD units that contain hazardous waste as defined by either the characteristics of the waste (e.g., toxicity, corrosivity) or as designated hazardous through listing. In either case, because the SSTs contain dangerous waste, these units are managed as HWMA Subtitle C TSD units. Because the SSTs were in operation on the effective date of the RCRA regulations, they could continue operations without a final status permit. The SSTs were granted interim status (i.e., Part A permit) (WAC 173-303-400) to operate until Ecology determines that a final status permit must be issued (i.e., Part B permit). However, because the SSTs will not be used for continued dangerous waste management, the SSTs must undergo closure in lieu of final status permitting (Ecology et al. 1989).

B.3.8.1.2.2 Water Pollution Contol Act. The Washington State "Water Pollution Control Act" and its associated regulations (WAC 173-200) implement provisions of the federal Clean Water Act and establish requirements for protecting the quality of all waters of the state for public health and enjoyment.

B.3.8.1.2.3 HFFACO Requirements. The HFFACO establishes an action plan for cleanup that addresses priority actions, methods for resolving problems, and milestones. The HFFACO sets milestones to achieve coordinated cleanup of the Hanford Site and provides for the enforcement of these milestones to keep the program on schedule. In 2000 the HFFACO was amended to adjust near-term milestones, target dates, and associated language governing SST waste retrieval and closure activities prior to September 30, 2006 (i.e., modifications necessary to achieve compliance with federal and state hazardous waste requirements). DOE has committed to comply with requirements of the HFFACO related to managing tank waste and tank farm closure at the Hanford Site.

As described in the HFFACO, the agencies determined that the tanks will be closed under WAC 173-303-610 regardless of permit status. These regulations specify closure and post-closure requirements. DOE is required to submit a closure plan for the SST farms (not individual tanks) for approval by Ecology. If all of the dangerous waste cannot be removed or decontaminated, DOE will submit a post-closure work plan and a RCRA Part B permit application for Ecology approval. Upon completing the closure action for each SST TSD unit, the Hanford Facility RCRA Permit will be amended to indicate that the applicable unit has been closed (Ecology et al. 1989).

According to WAC-173-303-604, the SSTs are deemed unfit-for-use tanks based on secondary containment and/or inability for tank integrity assessment; the tanks must be removed from service immediately and the owner or operator must take mitigating actions.
This regulation further specifies that neither dangerous wastes nor treatment reagents may be placed in a tank system if they could cause the tank, its ancillary equipment, or the containment

system to rupture, leak, corrode, or otherwise fail. Therefore, additions of water and waste into SSTs are prohibited under the *Washington Administrative Code* and RCRA.

However, a rationale for the addition of liquids to the SSTs can be made under the RCRA Part A permit for SSTs (DOE 1996):

> Treatment of the mixed waste in the SST system occurs when solids and interstitial liquids are separated and/or cooling liquids are added. These treatment processes involve, but are not limited to, mechanical retrieval, sluicing, and saltwell pumping of the mixed waste.

Based on past-practice sluicing operations for tank waste retrieval, water or waste has been added to enable the waste to be pumped out of a tank. DOE, EPA, and Ecology recognize the need to remove the waste and that addition of liquids will be necessary to facilitate retrieval of SST waste and a modification of the Part A permit is being prepared.

DOE has met some of the requirements for unfit-for-use tanks. After 1980, all SSTs were removed from service. Through the interim stabilization program, pumpable liquids have been removed from almost all of the SSTs, and the remaining tanks will be pumped by fiscal year 2004 (DOE 1996). DOE will need either to obtain from Ecology (1) a waiver for the addition of water or DST supernate for waste retrieval on a tank-by-tank basis or (2) a universal waiver for the entire SST system.

DOE O 435.1 states that unless demonstrated to the contrary, all HLW shall be considered to be radioactive mixed waste and subject to the requirements of the *Atomic Energy Act of 1954* and RCRA. Hanford Site high-level radioactive tank waste contains hazardous, characteristic, and/or listed wastes under RCRA. To address potential differences between the requirements of RCRA and the *Atomic Energy Act of 1954*, DOE, EPA, and Ecology anticipated in the HFFACO that "the TSD units containing mixed waste will normally be closed with consideration of all hazardous substances, which includes radioactive constituents." However, the potential exists for conflict between the regulations for the hazardous and the radioactive components of the waste.

HFFACO Milestone M-45-00 links tank waste retrieval and tank farm closure. According to Milestone M-45-00:

> Closure will follow retrieval of as much tank waste as technically possible, with tank waste residues not to exceed 360 ft^3 in each of the 100 series tanks, 30 ft^3 in each of the 200 series tanks, or the limit of waste retrieval technology capability, whichever is less.

New requirements of the HFFACO through Change Package M-45-00-01A modify the agreement to achieve compliance with federal and state hazardous waste requirements.
The near-term strategy for SST waste retrieval activities shifts from focusing on maximizing the number of tanks entered for retrieval (regardless of waste volume or content) to a focus on scheduling the retrieval of wastes from those SSTs with a high volume of CoCs.
These contaminants are defined as mobile, long-lived radionuclides that have a potential of reaching the groundwater and Columbia River. The near-term strategy also focuses on the performance of key waste retrieval technology demonstrations in a variety of waste forms and

tank farm locations to establish a technical base for future work. The near-term work scope focuses on performing risk assessments, incorporating vadose zone characterization data on a tank-by-tank basis, updating tank farm closure/post-closure work plans, and maximizing waste storage space in DSTs from waste retrievals in SSTs.

Appendix H of the HFFACO provides the SST waste retrieval criteria procedure formally agreed upon by DOE, Ecology, and EPA. Modifications to this appendix occurred during negotiations for Change Package M-45-00-01A. The modifications included defining the reference baseline waste retrieval technology as past-practice sluicing that has been conducted on tanks AX-104 and C-106, and earlier past-practice sluicing efforts. The new technology design and deployments are to measure their performance against this reference baseline technology. The appendix provides for SST demonstration of achievability of waste retrieval goal during tank C-104 tank retrieval demonstrations. The second phase evaluates regulatory requirements of HLW disposal from applicable rules, regulations, and DOE orders. In addition, establishment of an interface with the NRC to reach formal agreement on the retrieval and closure actions for SSTs with respect to allowable waste residuals in the tanks and soil column is to be accomplished. Collected data from the demonstration of the waste retrieval technology will assist in the preparation of input in defining the retrieval goal evaluation to accommodate the agreements on allowable residuals.

B.3.8.2 Regulatory Compliance of Waste Retrieval Approach

HFFACO Milestone M-45-03F calls for 99% retrieval of tank C-104 contents and retrieval to safe storage of at least 89 kg of plutonium. For the tank C-104 waste retrieval demonstration, the goal will be assessed against two major areas. The first is the achievability of the goal during tank C-104 waste retrieval demonstrations. This will demonstrate retrieval of sludge/hard heel wastes in a tank in the 200 East Area. The effectiveness of the waste retrieval operation will be determined with a topographical measurement of remaining waste in the tank, and a calculation of waste inventory. The inventory calculation will be based on calculated volume of the tank and waste topography measurements with appropriate surveying techniques and will include adjustments for any detectable deformities in the tank structure (e.g., liner bulges). The second area of assessment will be against the evaluation of the regulatory requirements of HLW disposal from applicable rules, regulations, and DOE orders. An interface with the NRC will be established and formal agreement on the retrieval and closure actions for SSTs with respect to allowable waste residuals in the tank and soil column will be reached.

DOE and Ecology will assess the waste retrieval goal and modify the waste retrieval goal to match the most restrictive case (i.e., the highest retrieval percentage requirement).
The tank C-104 waste retrieval demonstration will be performed, and the residual waste inventory will be calculated. DOE and Ecology will then perform an assessment of the waste retrieval goal. Based on the demonstration results the goal may be modified to match the best available technology. The agencies will notify NRC as required for compliance with the *Nuclear Waste Policy Act of 1982*. Formal criteria for retrieval of waste from the remaining SSTs will be established, and closure plans for the C tank farm will be finalized with concurrence from regulatory agencies. Waste will be retrieved from the remaining C farm SSTs. Retrieval activities may occur on a tank-by-tank basis to allow flexibility to retrieve tanks from various

farms if desired to support safety issue resolution, pretreatment or disposal feed requirements, or other priorities. Completion of waste retrieval will be in accordance with approved closure plans.

As per HFFACO Appendix H, waste residuals will be calculated for each tank following retrieval. Notification to appropriate regulatory authorities will document compliance with criteria. If residuals comply with criteria, final closure operations will proceed. If residuals do not comply, a request for waiver will be prepared. If the waiver is accepted, closure operations for the tank farm will begin; if the waiver is not accepted, additional retrieval operations are required. A review of alternate technologies will be performed relative to additional waste removal. If additional technologies are available they will be used to retrieve additional waste. If additional technologies are not available, new technologies will be developed and deployed. The tank farm will be held in interim status pending completion of the additional retrieval operations.

When additional waste is retrieved, the residual waste volume will again be calculated and assessed against the criteria. An iterative process will occur. If the goal is met, final closure will proceed. If the goal is not met, a waiver will be petitioned or additional waste retrieval activities will occur until the appropriate regulatory authorities are satisfied. Figure B.3.3 provides a generic logic diagram of this process.

Figure B.3.3. Process for Assessing Percentage of Waste Retrieved from Waste Retrieval Operations



Source: HFFACO Appendix H.

B.4.0 DESCRIPTION OF WASTE RETRIEVAL CASES

This section summarizes the intent behind each of the 10 waste retrieval cases. Collectively, the cases describe varying levels of waste retrieval. The cases are designed to support investigation of how the three source terms (past leaks, retrieval leak loss, and residual waste) impact the performance measures investigated in this RPE (short-term human health risk, impacts to groundwater, long-term human health risk, and inadvertent human intrusion). Section B.4.1 outlines the major enabling assumptions associated with creating and evaluating the cases. Section B.4.2 contains a summary of the case descriptions.

The waste retrieval cases are defined to investigate tradeoffs between risk and volume (both residual waste and retrieval leak loss). The cases are not intended to provide a means to relax retrieval demonstration requirements, but to provide adequate risk-based analysis to support the HFFACO requirements for retrieval.

B.4.1 MAJOR ENABLING ASSUMPTIONS

This section summarizes the major enabling assumptions made to support development of the waste retrieval cases. Assumptions were made when available data were insufficient to support this RPE analysis. It is assumed that because a decision has been made to retrieve waste from tank C-104, this evaluation need not include a no-action case where the current waste inventory would be left in place. A baseline level of waste retrieval is assumed for all remaining tanks in the C tank farm. This assumption supports an evaluation of the long-term performance of tank C-104 cases combined with the long-term performance of the other C farm tanks.

B.4.1.1 Waste Retrieval Technology Assumptions

Preliminary engineering for the tank C-104 waste retrieval system was completed in fiscal year 2000 to develop the technical concepts and support the planning basis for Project W-523, as documented in RPP-6843. Three alternative retrieval system configurations were evaluated:

- Sluicing
- Mining with a remotely operated crawler
- Combined sluicing and crawler method.

RPP-6843 provides sufficient detail to move the tank C-104 waste retrieval project into the conceptual design phase. One of the three retrieval system alternatives is assumed to be selected for conceptual design.

RPP-6843 indicates that the projected performance of all three retrieval systems is similar with respect to the estimated residual waste volume remaining following retrieval. All three of the waste retrieval systems evaluated (when properly configured) have the potential to retrieve sufficient waste from tank C-104 to leave a heel of approximately 2,550 L (670 gal). Given this, any of the three systems evaluated could be deployed to meet the residual waste volumes of the waste retrieval cases identified.

B.4.1.2 Leak Detection, Mitigation, and Monitoring System Assumptions

The LDMM strategy for tank C-104 waste retrieval is described in *Single-Shell Tank C-104 Full Scale Sludge/Hard Heel Confined Sluicing and Robotic Technologies Waste Retrieval Demonstrations and Requirements* (RPP-7807). The current strategy includes in-tank volumetric methods, both static and dynamic, and external tank monitoring using the existing drywells around the tank.

B.4.1.3 Tank Stabilization Assumptions

Following waste retrieval, all tanks are assumed to be stabilized as a part of the closure process to prevent subsidence and provide a structurally sound base for the surface barrier. Closure designs for the SSTs have not been developed in detail; however, most concepts identified to date involve placement of gravel or grout in the tanks. It is likely that grout would be used as the initial step in stabilizing the tanks in an attempt to encapsulate the tank residuals, but no credit is taken for further encapsulation. There are uncertainties associated with grout stabilization or encapsulation of the residual waste; sand will need to be addressed as a part of the tank closure strategy development. These uncertainties do not require resolution for this scoping-level RPE. DOE/RL-98-72 includes a conceptual description of the activities necessary to stabilize an SST with grout.

Stabilization of tank residual waste with grout is an element of the tank closure process developed at the Savannah River Site (DOE/EIS-0303D). The grout is used in the tank closure to facilitate the NRC classification of the tank residuals as incidental waste by doing the following:

- Incorporating the residual waste into a stabilized waste form designed to reduce the release of contaminants to the environment
- Producing a waste form with radionuclide concentrations that, on average, meets NRC Class C LLW criteria.

B.4.1.4 Ancillary Equipment Assumptions

Stabilization of ancillary equipment is assumed to include (1) demolishing and removing all surface buildings and equipment that would interfere with constructing the surface barrier and (2) stabilizing the subsurface equipment with grout to prevent long-term subsidence. Concepts for stabilization of ancillary equipment were developed as a part of the AX tank farm RPE (DOE/RL-98-72). These same types of concepts could be used to stabilize the ancillary equipment in the C tank farm. One of the issues identified in developing and evaluating concepts for ancillary equipment stabilization was the worker health and safety issues associated with injecting grout into the abandoned waste transfer lines (HNF-3441). The concept developed for grouting the abandoned waste transfer lines required direct worker contact with equipment to establish grout injection points. If the length of a transfer line was greater than the distance that grout could be pumped, then it was assumed that supplemental pipe penetrations would have to be made along the length of the pipe. One of the conclusions drawn from the AX tank farm RPE

was that additional evaluation was required to determine the need for stabilizing the smaller diameter transfer lines.

B.4.1.5 Surface Barrier Assumptions

An enhanced RCRA Subtitle C barrier is assumed to be constructed over the C tank farm. The barrier would be larger than required to cover the tanks and is intended to provide a barrier over the ancillary equipment within the tank farm. The enhanced RCRA Subtitle C barrier design is described in greater detail in *Focused Feasibility Study of Engineered Barriers for Waste Management Units in 200 Areas* (DOE/RL-93-33). This surface barrier is an 8-layer barrier with a combined minimum thickness of 1.7 m (5.6 ft). This barrier is designed to provide long-term contaminant and hydrologic protection for a performance period of 500 years.

An enhanced RCRA Subtitle C barrier is similar in structure to a Hanford barrier, but layer thicknesses are reduced and there is no fractured basalt layer. The design incorporates provisions for biointrusion and human intrusion control. However, the provisions are modest relative to control features incorporated into the Hanford barrier design. The enhanced RCRA Subtitle C barrier is the baseline design for sites containing dangerous waste, Category 3 LLW or Category 3 low-level mixed waste, and Category 1 low-level mixed waste (DOE/RL-93-33). A cross-section of an enhanced RCRA Subtitle C barrier is provided in Figure B.4.1.

B.4.2 SUMMARY OF WASTE RETRIEVAL CASE DESCRIPTIONS

All 10 waste retrieval cases assume a common endpoint that includes the following parameters.

- Vadose zone contamination from past leaks is not remediated.
- Residual tank waste, ancillary equipment, and vadose zone characterization is conducted to support tank farm closure.
- Tanks and belowgrade ancillary equipment are stabilized with grout and/or a combination of grout and gravel.
- Above grade ancillary equipment is removed.
- An enhanced RCRA Subtitle C barrier (Figure B.4.1) is constructed over the tank farm.

The waste retrieval cases are designed to illustrate the effect of different waste retrieval performance levels in tank C-104 as well as for the entire C tank farm. The following summarize the intent of the different cases.

- Case 1 is designed as the baseline waste retrieval case and assumes retrieval from all C farm tanks to the HFFACO interim retrieval goal of 360 ft^3, with nominal leak loss from each tank.

Figure B.4.1. Enhanced RCRA Subtitle C Barrier Cross-Section



Cover Vegetation: Mixed perennial grasses

Layer 1: Silt loam topsoil with pea gravel admixture (50 cm [20 in.])

Layer 2: Compacted silt loam topsoil (50 cm [20 in.])

Layer 3: Sand filter layer (15 cm [6 in.])
Layer 4: Gravel filter layer (15 cm [6 in.])
Layer 5: Lateral drainage layer (drainage gravel) (15 cm [6 in.])
Layer 6: Low-permeability asphalt layer (15 cm [6 in.])
Layer 7: Asphalt base course (10 cm [4 in.])

Layer 8: Grading fill (variable thickness)

Adapted from DOE/RL-93-33

- Case 2 is designed to demonstrate the risks associated with retrieving waste from tank C-104 to the same extent as was achieved in the tank C-106 waste retrieval operations.

- Case 3 is designed to demonstrate the risks associated with retrieving waste down to a 5 m^3 (180 ft^3) heel with a 15,000 L (4,000 gal) retrieval leak loss.

- Cases 3, 4, 5, 6, and 7 are designed to evaluate the effects of varying amounts of retrieval leak loss from tank C-104.

- Cases 8 and 9 are designed to evaluate the effects of varying the volume of the residual waste heel left in tank C-104 after retrieval.

- Case 10 is designed to illustrate the effects of an interim surface barrier on retrieval leakage. The purpose of an interim surface barrier is to reduce the natural recharge to the vadose zone. The gravel surface on the tank farms enhance natural recharge. Placing an interim (temporary barrier installed prior to the closure barrier). Placing a temporary barrier significantly reduces the amount of infiltration into the ground, reducing the driver for contaminant migration.

Table B.3.1 provides a summary of the principle variables associated with each case. Specifics of the variables associated with each case are delineated in HNF-7989.

B.5.0 ANALYSIS RESULTS

This section describes the results of the impact assessment for the 10 waste retrieval cases. The human health risk assessment is presented in Sections B.5.1 to B.5.4. How well each case complies with applicable federal and state regulations is analyzed in Section B.5.5. Two significant number figures are used for presentation of results to show relative differences between the retrieval cases. This is not intended to imply a level of confidence in the results, which are generally order-of-magnitude projections.

B.5.1 SHORT-TERM HUMAN HEALTH RISK RESULTS

The short-term human health risk analysis supports a comparison of the short-term human health risks associated with variations in waste retrieval and the use of an interim barrier as defined by the 10 waste retrieval cases. Because of the limited amount of data and because only the differences between the waste retrieval cases are of interest, activities that are common among the cases are not included in the short-term human health risk calculations. For example, activities associated with retrieval of the waste from tank C-104 using the crawler system (e.g., installation of the crawler system and the support systems) would be the same for all the tank C-104 cases with the exception of retrieval operations and construction of an interim barrier. Therefore, only the short-term human health risk associated with retrieval operations and the construction of an interim barrier are calculated for comparison in this analysis. However, it should be noted that adding the risk from activities that are common to all cases would reduce the differences (by percent) between the waste retrieval cases. Therefore, the differences between the waste retrieval cases presented in this document are bounding. Retrieval leak losses are also excluded from this short-term human health risk analysis because they would not result in an appreciable short-term human health risk (the leaks are assumed to occur at the base of the tanks and are assumed to have no associated atmospheric release). Retrieval leak losses do, however, contribute to the long-term human health risk (i.e., post-remediation health impacts) and are evaluated in Sections B.5.2 and B.5.3.

Short-term human health risk is calculated for both normal (i.e., nonaccident or routine) and accident conditions. Routine conditions include anticipated exposure to radiation fields and radiological and chemical releases to the atmosphere during normal retrieval operation conditions and construction of an interim barrier. Accidents are unplanned events or a sequence of events that result in undesirable consequences. The accidents evaluated in this analysis include potential occupational accidents resulting in physical trauma, radiological exposure resulting in LCFs, and toxic or corrosive toxicological exposure resulting in adverse health effects. Initiating events that could result in adverse health effects include natural phenomena, human error, and component failure. The analysis methodology is discussed in Section B.3.4.

B.5.1.1 Occupational Accident Results

The occupational accidents in this analysis are evaluated in terms of the number of total recordable cases (TRCs) and lost workday cases (LWCs) resulting from accidental injuries. The analysis also includes the number of fatalities resulting from accidents. Injuries (i.e., TRCs

and LWCs) and fatalities are calculated by multiplying the labor requirements to support the activities of interest by Hanford Site specific incidence rates.

The parameters of the calculation and the number of incidents to the involved workers for each case are presented in Table B.5.1. Details of the enabling assumptions, data for analysis, and the analysis calculations are provided in HNF-7989.

Table B.5.1. Occupational Accidents

Incident	Labor Requirements (labor-hr)	Incident rate (incident/ labor-hr)	Number of Incidents
Cases 1, 4, 5, 6, and 7			
TRC	6.6E+03	1.9E-05	1.3E-01
LWC	6.6E+03	8.0E-06	5.3E-02
Fatality	6.6E+03	1.4E-08	9.0E-05
Cases 2			
TRC	6.5E+03	1.9E-05	1.3E-01
LWC	6.5E+03	8.0E-06	5.3E-02
Fatality	6.5E+03	1.4E-08	8.9E-05
Case 3			
TRC	7.1E+03	1.9E-05	1.4E-01
LWC	7.1E+03	8.0E-06	5.7E-02
Fatality	7.1E+03	1.4E-08	9.6E-05
Case 8			
TRC	6.0E+03	1.9E-05	1.2E-01
LWC	6.0E+03	8.0E-06	4.8E-02
Fatality	6.0E+03	1.4E-08	8.2E-05
Case 9			
TRC	5.4E+03	1.9E-05	1.1E-01
LWC	5.4E+03	8.0E-06	4.4E-02
Fatality	5.4E+03	1.4E-08	7.4E-05
Case 10			
TRC	1.3E+04	1.9E-05	2.5E-01
LWC	1.3E+04	8.0E-06	1.1E-01
Fatality	1.3E+04	1.4E-08	1.8E-04

LWC = lost workday case.
TRC = total recordable case.

B.5.1.2 Routine Radiological Risk Results

The unit of measure for routine radiological risk in this analysis is the number of LCFs resulting from radiological exposures from routine daily operations. Exposure to the involved worker would be from ionizing radiation fields in radiation zones. Exposure to the noninvolved worker and general public would be from abated air emissions during routine operations. Exposure rates are measured in a dose unit of rem and multiplied by a dose-to-risk conversion factor to calculate the LCF risk.

The parameters of the calculation and the routine radiological risk to the involved workers for each case are presented in Table B.5.2. Details of the enabling assumptions, data for analysis, and analysis calculations are provided in HNF-7989.

B.5.1.3 Routine Chemical Risk Results

The routine chemical risk from waste retrieval operations is toxic health effect measured in exceedance of a hazard index for each toxic chemical, and carcinogenic health effects measured in ILCR. The chemical health risk was evaluated for the involved worker MEI, noninvolved worker MEI, and the general public MEI.

The parameters of the calculation and the routine ILCR to the involved worker MEI, noninvolved worker MEI, and general public MEI for each case are presented in Table B.5.3. The enabling assumptions, data for analysis, and analysis calculations are provided in HNF-7989.
The chemical concentrations in the residual waste would be the same for all cases; therefore, the hazard index for all cases would be the same.

B.5.1.4 Radiological Accident Risk Results

Only operational accidents are evaluated in this RPE. Additional accidents will be evaluated as part of conceptual design. All 10 waste retrieval cases assume the same crawler technology for retrieval; therefore, each case is subject to the same type of accidents. Crawler-based retrieval accidents are evaluated in RPP-6843; that analysis was performed to determine if any accidents could be identified at the early preconceptual stage that would exceed the safety envelope of the tank farms authorization basis (HNF-SD-WM-SAR-067). The annual frequency and level of severity of the potential accidents evaluated in the assessment were shown to be bound by the authorization basis (HNF-SD-WM-SAR-067). The severity of a given accident and the frequency of the accident is common to all 10 cases evaluated; however, the probability of the accident occurring varies slightly because of the slight variation in duration of operations between the cases. The variation is so slight that there is no change in frequency categories.
A table of potential accidents, consequences, and likelihood is provided in HNF-7989.

Table B.5.2. Routine Radiological Risk (2 Sheets)

Receptor	Dose (rem)*	Dose-to-Risk Conversion Factor (LCF/rem)*	Risk (LCF)
Cases 1, 4, 5, 6, and 7			
Involved worker MEI	5.0E-01	4.0E-04	2.0E-04
Involved worker population	2.3E+00	4.0E-04	9.2E-04
Noninvolved worker MEI	1.8E-08	4.0E-04	7.2E-12
Noninvolved worker population	1.3E-05	4.0E-04	5.2E-09
General public MEI	8.6E-07	5.0E-04	4.3E-10
General public population	3.3E-02	5.0E-04	1.7E-05
Cases 2			
Involved worker MEI	5.0E-01	4.0E-04	2.0E-04
Involved worker population	2.3E+00	4.0E-04	9.1E-04
Noninvolved worker MEI	1.6E-08	4.0E-04	6.4E-12
Noninvolved worker population	1.3E-05	4.0E-04	5.2E-09
General public MEI	8.6E-07	5.0E-04	4.3E-10
General public population	3.3E-02	5.0E-04	1.7E-05
Case 3			
Involved worker MEI	5.0E-01	4.0E-04	2.0E-04
Involved worker population	2.4E+00	4.0E-04	9.7E-04
Noninvolved worker MEI	1.8E-08	4.0E-04	7.2E-12
Noninvolved worker population	1.4E-05	4.0E-04	5.6E-09
General public MEI	8.6E-07	5.0E-04	4.3E-10
General public population	3.3E-02	5.0E-04	1.7E-05
Case 8			
Involved worker MEI	5.0E-01	4.0E-04	2.0E-04
Involved worker population	2.1E+00	4.0E-04	8.3E-04
Noninvolved worker MEI	1.6E-08	4.0E-04	6.4E-12
Noninvolved worker population	1.2E-05	4.0E-04	4.8E-09
General public MEI	8.6E-07	5.0E-04	4.3E-10
General public population	3.3E-02	5.0E-04	1.7E-05

Table B.5.2. Routine Radiological Risk (2 Sheets)

Receptor	Dose (rem)*	Dose-to-Risk Conversion Factor (LCF/rem)*	Risk (LCF)
Case 9			
Involved worker MEI	5.0E-01	4.0E-04	2.0E-04
Involved worker population	1.9E+00	4.0E-04	7.5E-04
Noninvolved worker MEI	1.4E-08	4.0E-04	5.6E-12
Noninvolved worker population	1.1E-05	4.0E-04	4.4E-09
General public MEI	8.6E-07	5.0E-04	4.3E-10
General public population	3.3E-02	5.0E-04	1.7E-05
Case 10			
Involved worker MEI	5.0E-01	4.0E-04	2.0E-04
Involved worker population	3.8E+00	4.0E-04	1.5E-03
Noninvolved worker MEI	1.8E-08	4.0E-04	7.2E-12
Noninvolved worker population	1.3E-05	4.0E-04	5.2E-09
General public MEI	8.6E-07	5.0E-04	4.3E-10
General public population	3.3E-02	5.0E-04	1.7E-05

*Person-rem for population receptors

LCF = latent cancer fatality.
MEI = maximally exposed individual.

Table B.5.3. Routine Chemical Risk to Maximally Exposed Individuals

Receptor	ILCR	Hazard Index
Cases 1, 4, 5, 6, 7, and 10		
Involved worker MEI	5.2E-09	<2.3E-01
Noninvolved worker MEI	2.2E-09	<1.0E-07
General public MEI	6.7E-13	<5.3E-05
Case 2		
Involved worker MEI	5.0E-09	<2.3E-01
Noninvolved worker MEI	2.2E-09	<1.0E-07
General public MEI	6.5E-13	<5.3E-05
Case 3		
Involved worker MEI	5.5E-09	<2.3E-01
Noninvolved worker MEI	2.4E-09	<1.0E-07
General public MEI	7.1E-13	<5.3E-05
Case 8		
Involved worker MEI	4.7E-09	<2.3E-01
Noninvolved worker MEI	2.0E-09	<1.0E-07
General public MEI	6.0E-13	<5.3E-05
Case 9		
Involved worker MEI	4.2E-09	<2.3E-01
Noninvolved worker MEI	1.8E-09	<1.0E-07
General public MEI	5.4E-13	<5.3E-05

ILCR = incremental lifetime cancer risk.
MEI = maximally exposed individual.

Notes: Ammonia is the major chemical contributor for the hazard index. 1,3-Butadiene is the major chemical contributor for the ILCR.

B.5.1.5 Chemical Accident Risk Results

The same conclusions reached in Section B.5.1.4 for radiological accidents also apply to potential chemical accidents. Because all 10 waste retrieval cases assume the same crawler technology for waste retrieval, each case is subject to the same type of chemical accident. The severity of a given accident and the frequency of the accident are the same for all 10 cases; however, the probability of the accident occurring varies slightly because of the slight variation in duration of operations between the cases. The variation is so slight that there is no change in frequency category.

B.5.2 GROUNDWATER IMPACT RESULTS

The deterministic approach taken in DOE/RL-98-72, from which the scaled groundwater impacts have been obtained for this evaluation, is based on reasonably conservative best-estimate parameter values. The data on which the deterministic calculations are based are summarized in Appendix B of DOE/RL-98-72. The enabling assumptions used for this analysis are provided in HNF-7989. The means by which contaminants are transported in the vadose zone and groundwater are the same for all of the waste retrieval cases. The analysis methodology is discussed in Section B.3.5.

The estimated impacts to the groundwater system are provided in terms of contaminant concentrations of selected contaminants in each of three mobility groups. Those groups are based on assumed distribution coefficient values developed for DOE/RL-98-72. Group 0 contains the most mobile contaminants, those with an assumed distribution coefficient of zero. Group 1 contains contaminants that are mobile in the near-field (i.e., are assumed to have a distribution coefficient of zero from ground surface to a depth of approximately 36.5 m [120 ft] below ground surface) and slightly retarded below 36.5 m (120 ft) below ground surface where the distribution coefficient is assumed to be 0.6 mL/g. Group 2 contains contaminants that are slightly retarded (i.e., the distribution coefficient is assumed to be 0.6 mL/g in all parts of the vadose zone and groundwater system). The selected contaminants are technetium-99 and nitrate for Group 0, iodine-129 for Group 1, and uranium-238 for Group 2. The groundwater impacts from the past leak source term are constant for Cases 1 through 9 because those cases all assume the same recharge history. Case 10 assumes the application of a temporary barrier, resulting in a different recharge history and different maximum contaminant concentrations in groundwater. These impacts are summarized in Table B.5.4.

Table B.5.4. Maximum Contaminant Concentrations in Groundwater for the Past Leak Source Term at 2,600 Years for the C Tank Farm

Case	Technetium-99[a] (pCi/L)	Nitrate[b] (mg/L)	Iodine-129[c] (pCi/L)	Uranium-238[d] (pCi/L)
1-9	2	4.7E-04	2.4E-03	8.9E-04
10	22	4.9E-03	1.9E-03	6.4E-04

[a]The drinking water standard (40 CFR 141) for technetium-99 is 900 pCi/L.
[b]The drinking water standard (40 CFR 141) for nitrate is 45 mg/L.
[c]The drinking water standard (40 CFR 141) for iodine-129 is 1 pCi/L.
[d]The drinking water standard (40 CFR 141) for uranium-238 is approximately 6.7 pCi/L based on the drinking water standard of 0.02 mg/L for total uranium.

The groundwater impacts resulting from retrieval leakage, residual volume, and the composite of the three source terms (i.e., past leaks, retrieval leakage, and residual volume) for the C tank farm are summarized in Table B.5.5 for technetium-99, nitrate, iodine-129, and uranium-238.

Table B.5.5. Maximum Contaminant Concentrations in Groundwater for the Retrieval, Residual, and Composite Source Terms for the 10 Cases Considered for the C Tank Farm

Case	Maximum Contaminant Concentration in Groundwater Resulting from Retrieval Leakage at 2,600 years				Maximum Contaminant Concentration in Groundwater Resulting from Residual Waste Remaining in Tanks at 2,600 years				Maximum Contaminant Concentration in Groundwater as a Composite of Past Leaks, Retrieval Leakage, and Residual Volume at 2,600 years			
	Tc^{99} [a] (pCi/L)	Nitrate[b] (mg/L)	I^{129} [c] (pCi/L)	U^{238} [d] (pCi/L)	Tc^{99} [a] (pCi/L)	Nitrate[b] (mg/L)	I^{129} [c] (pCi/L)	U^{238} [d] (pCi/L)	Tc^{99} [a] (pCi/L)	Nitrate[b] (mg/L)	I^{129} [c] (pCi/L)	U^{238} [d] (pCi/L)
1	81	0.11	5.5E-02	1.1E-04	76	20	3.5E-02	8.9E-03	159	20	9.2E-02	9.9E-03
2	81	0.11	5.5E-02	1.1E-04	210	100	0.27	2.0E-02	293	100	0.33	2.1E-02
3	80	0.11	5.5E-02	1.1E-04	76	20	3.5E-02	8.4E-03	158	20	9.2E-02	9.4E-03
4	0	0	0	0	76	20	3.5E-02	8.9E-03	78	20	3.7E-02	9.8E-03
5	80	0.11	5.5E-02	1.1E-04	76	20	3.5E-02	8.9E-03	158	20	9.2E-02	9.9E-03
6	84	0.11	5.6E-02	1.2E-04	76	20	3.5E-02	8.9E-03	162	20	9.3E-02	9.9E-03
7	85	0.12	5.6E-02	1.4E-04	76	20	3.5E-02	8.9E-03	163	20	9.3E-02	1.0E-02
8	81	0.11	5.5E-02	1.1E-04	81	22	3.6E-02	1.9E-02	164	22	9.3E-02	2.0E-02
9	81	0.11	5.5E-02	1.1E-04	84	23	3.5E-02	1.1E-02	167	23	9.3E-02	1.2E-02
10	108	0.14	7.3E-02	7.1E-05	1.0	19	6.9E-04	8.9E-03	131	19	7.6E-02	9.6E-03

[a]The drinking water standard (40 CFR 141) for technetium-99 is 900 pCi/L.
[b]The drinking water standard (40 CFR 141) for nitrate is 45 mg/L.
[c]The drinking water standard (40 CFR 141) for iodine-129 is 1 pCi/L.
[d]The drinking water standard (40 CFR 141) for uranium-238 is approximately 6.7 pCi/L based on the drinking water standard of 0.02 mg/L for total uranium.

B.5.3 LONG-TERM HUMAN HEALTH RISK RESULTS

This section presents the results of the long-term human health risk assessment. The results are generated using the methodology described in Section B.3.6 and the source term inventories discussed in Section B.3.3. Tables B.5.6 and B.5.7 summarize the long-term human health risk analysis results. The tables show results for both tank C-104 and the C tank farm as a whole for each of the 10 waste retrieval cases by source term (i.e., past leaks, retrieval leak loss, residual waste, and composite). The results shown are the ILCR and the hazard index calculated for the industrial worker and residential farmer scenarios.

The Washington State Department of Health has issued guidance that the dose limit for release of a site is 15 mrem/year total effective dose equivalent (WDOH/320-015). The DOE dose limit defined in DOE O 435.1 for LLW facility closure is 25 mrem/year total effective dose equivalent from all exposure pathways. Dose can be converted to long-term human health risk by using a conversion factor of 6×10^{-4} cancer incidences per rem. The dose limit can be converted to an annual dose by taking the scenario specific exposure durations into account. Using the conversion an annual dose of 15 mrem/yr converts to a risk of 9×10^{-6} on an annual basis. When the exposure durations for the industrial worker (20 years) and residential farmer (30 years) are taken into account the 15 mrem/yr dose corresponds to an ILCR of 1.8×10^{-4} and 2.7×10^{-4} for the industrial worker and residential farmer scenarios, respectively. The risk values for both the industrial worker and residential farmer are higher than 10^{-5}.

Section B.5.3.1 provides the tank-specific results by source term for tank C-104. Section B.5.3.2 provides the results by source term for the C tank farm. Section B.5.3.3 compares the results for the receptor scenarios based on DOE/RL-91-45 formulas with those based on the MTCA formulas.

B.5.3.1 Tank C-104 Long-Term Human Health Risk Assessment Results

This section presents the tank-specific long-term human health risk results for tank C-104 by source term.

B.5.3.1.1 Tank C-104 Past Leaks. Tank C-104 is currently classified as sound and does not have a past leak source term. There would be no long-term human health risks from tank C-104 past leaks.

B.5.3.1.2 Tank C-104 Waste Retrieval Leak Loss. Ignoring the zero leak case (Case 4) for the industrial worker, the ILCR from tank C-104 waste retrieval leak loss varies between 4.0×10^{-9} and 7.4×10^{-8} and the hazard index varies between 1.1×10^{-5} and 3.1×10^{-4}. For the residential farmer, the ILCR varies between 9.0×10^{-8} and 1.7×10^{-6} and the hazard index varies between 1.8×10^{-3} and 7.2×10^{-2}. The low and high ILCR and hazard index values result from tank C-104 waste retrieval leak losses of 15,000 L (4,000 gal) and 300,000 L (80,000 gal), respectively. Figure B.5.1 shows the risk-to-volume relationship between ILCR and tank C-104 waste retrieval leak losses based on variations in the 10 waste retrieval cases analyzed excluding Case 10, which introduces the interim barrier. The peak risk of 7.4×10^{-8} ILCR to the industrial worker is equivalent to 1.2×10^{-4} rem (0.12 mrem).

Table B.5.6. Industrial Worker Long-Term Human Health Risks by Source Term and Case*

Case		Past Leaks	Waste Retrieval Leakage Loss		Residual Waste		Composite Source Term	
			Tank C-104	C Tank Farm Total	Tank C-104	C Tank Farm Total	Tank C-104	C Tank Farm Total
1	ILCR	2.0E-08	1.6E-08	6.7E-07	3.9E-09	9.2E-07	2.0E-08	1.6E-06
	HI	5.2E-05	4.2E-05	3.1E-03	3.9E-03	3.1E-01	4.0E-03	3.1E-01
2	ILCR	2.0E-08	1.6E-08	6.7E-07	1.6E-08	2.2E-06	3.2E-08	2.9E-06
	HI	5.2E-05	4.2E-05	3.1E-03	3.0E-02	2.4E+00	3.0E-02	2.4E+00
3	ILCR	2.0E-08	4.0E-09	6.6E-07	1.9E-09	9.2E-07	5.9E-09	1.6E-06
	HI	5.2E-05	1.1E-05	3.1E-03	1.9E-03	3.1E-01	1.9E-03	3.1E-01
4	ILCR	2.0E-08	0.0E+00	0.0E+00	3.9E-09	9.2E-07	3.9E-09	9.4E-07
	HI	5.2E-05	0.0E+00	0.0E+00	3.9E-03	3.1E-01	3.9E-03	3.1E-01
5	ILCR	2.0E-08	0.0E+00	6.6E-07	3.9E-09	9.2E-07	3.9E-09	1.6E-06
	HI	5.2E-05	0.0E+00	3.1E-03	3.9E-03	3.1E-01	3.9E-03	3.1E-01
6	ILCR	2.0E-08	6.1E-08	7.2E-07	3.9E-09	9.2E-07	6.4E-08	1.7E-06
	HI	5.2E-05	1.9E-04	3.3E-03	3.9E-03	3.1E-01	4.1E-03	3.1E-01
7	ILCR	2.0E-08	7.4E-08	7.3E-07	3.9E-09	9.2E-07	7.7E-08	1.7E-06
	HI	5.2E-05	3.1E-04	3.4E-03	3.9E-03	3.1E-01	4.3E-03	3.1E-01
8	ILCR	2.0E-08	1.6E-08	6.7E-07	7.4E-08	9.9E-07	8.9E-08	1.7E-06
	HI	5.2E-05	4.2E-05	3.1E-03	1.3E-01	4.4E-01	1.3E-01	4.4E-01
9	ILCR	2.0E-08	1.6E-08	6.7E-07	1.1E-07	1.0E-06	1.3E-07	1.7E-06
	HI	5.2E-05	4.2E-05	3.1E-03	1.8E-01	4.9E-01	1.8E-01	4.9E-01
10	ILCR	2.0E-08	2.1E-08	8.9E-07	1.8E-09	3.8E-07	2.3E-08	1.3E-06
	HI	5.2E-05	5.6E-05	4.2E-03	3.9E-03	3.0E-01	3.9E-03	3.1E-01

*Values shown are the source term specific risk contributions at the time of peak long-term human health risk over a 10,000-year post-remediation period.

HI = hazard index.
ILCR = incremental lifetime cancer risk.

Table B.5.7. Residential Farmer Long-Term Human Health Risks by Source Term and Case*

Case		Past Leaks	Waste Retrieval Leakage Loss		Residual Waste		Composite Source Term	
			Tank C-104	C Tank Farm Total	Tank C-104	C Tank Farm Total	Tank C-104	C Tank Farm Total
1	ILCR	6.8E-07	3.6E-07	2.2E-05	9.1E-08	2.3E-05	4.5E-07	4.6E-05
	HI	5.7E-03	7.3E-03	8.3E-01	6.7E-01	1.5E+02	6.8E-01	1.5E+02
2	ILCR	6.8E-07	3.6E-07	2.2E-05	3.8E-07	6.1E-05	7.4E-07	8.4E-05
	HI	5.7E-03	7.3E-03	8.3E-01	5.1E+00	7.9E+02	5.1E+00	7.9E+02
3	ILCR	6.8E-07	9.0E-08	2.2E-05	4.5E-08	2.3E-05	1.3E-07	4.6E-05
	HI	5.7E-03	1.8E-03	8.3E-01	3.2E-01	1.5E+02	3.2E-01	1.5E+02
4	ILCR	6.8E-07	0.0E+00	0.0E+00	9.1E-08	2.3E-05	9.1E-08	2.4E-05
	HI	5.7E-03	0.0E+00	0.0E+00	6.7E-01	1.5E+02	6.7E-01	1.5E+02
5	ILCR	6.8E-07	0.0E+00	2.2E-05	9.1E-08	2.3E-05	9.1E-08	4.6E-05
	HI	5.7E-03	0.0E+00	8.3E-01	6.7E-01	1.5E+02	6.7E-01	1.5E+02
6	ILCR	6.8E-07	1.4E-06	2.3E-05	9.1E-08	2.3E-05	1.5E-06	4.7E-05
	HI	5.7E-03	3.6E-02	8.6E-01	6.7E-01	1.5E+02	7.1E-01	1.5E+02
7	ILCR	6.8E-07	1.7E-06	2.3E-05	9.1E-08	2.3E-05	1.8E-06	4.7E-05
	HI	5.7E-03	7.2E-02	9.0E-01	6.7E-01	1.5E+02	7.4E-01	1.5E+02
8	ILCR	6.8E-07	3.6E-07	2.2E-05	1.7E-06	2.5E-05	2.1E-06	4.8E-05
	HI	5.7E-03	7.3E-03	8.3E-01	2.3E+01	1.7E+02	2.3E+01	1.7E+02
9	ILCR	6.8E-07	3.6E-07	2.2E-05	2.5E-06	2.6E-05	2.9E-06	4.8E-05
	HI	5.7E-03	7.3E-03	8.3E-01	3.1E+01	1.8E+02	3.1E+01	1.8E+02
10	ILCR	6.8E-07	4.8E-07	2.9E-05	1.3E-08	3.5E-06	4.9E-07	3.4E-05
	HI	5.7E-03	9.7E-03	1.1E+00	6.6E-01	1.5E+02	6.7E-01	1.5E+02

*Values shown are the source term specific risk contributions at the time of peak long-term human health risk over a 10,000-year post-remediation period.

HI = hazard index.
ILCR = incremental lifetime cancer risk.

Figure B.5.1. Tank C-104 Retrieval Leakage Risk Versus Retrieval Leakage Volume



B.5.3.1.3 Tank C-104 Residual Waste. For the industrial worker, the ILCR from tank C-104 residual waste varies between 1.8×10^{-9} and 1.1×10^{-7} and the hazard index varies between 1.9×10^{-3} and 1.8×10^{-1}. For the residential farmer, the ILCR varies between 1.3×10^{-8} and 2.5×10^{-6} and the hazard index varies between 3.2×10^{-1} and 3.1×10^{1}. The low and high ILCR and hazard index values result from tank C-104 residual waste volumes of 10,000 L (2,700 gal) (with interim barrier use) and 190,000 L (50,000 gal), respectively. Figure B.5.2 shows the risk-to-volume relationship between ILCR and tank C-104 residual waste based on variations in the 10 waste retrieval cases analyzed except for Case 10, which introduces the interim barrier. The peak risk of 1.1×10^{-7} ILCR to the industrial worker is equivalent to 1.8×10^{-4} rem, or an average annual dose of 0.018 mrem/yr.

Figure B.5.2. Tank C-104 Residual Waste Risk Versus Residual Waste Volume



B.5.3.1.4 Tank C-104 Composite Source Term. For the industrial worker, the ILCR from the tank C-104 composite source term varies between 3.9×10^{-9} and 1.3×10^{-7} and the hazard index varies between 1.9×10^{-3} and 1.8×10^{-1}. For the residential farmer, the ILCR varies between 7.7×10^{-7} and 3.5×10^{-6} and the hazard index varies between 3.3×10^{-1} and 3.1×10^{1}. The low ILCR and hazard index values would result from the composite of no waste retrieval leak losses and 10,000 L (2,700 gal) of residual waste. The high ILCR and hazard index values result from the composite of 30,000 L (8,000 gal) of waste retrieval leak losses and 190,000 L (50,000 gal) of residual waste.

Figures B.5.3 and B.5.4 show the risk-to-volume relationships between the composite ILCR and, respectively, tank C-104 waste retrieval leak losses (for cases with 10,000 L [2,700 gal] of residual waste) and tank C-104 residual waste (for cases with 30,000 L [8,000 gal] of waste retrieval leak losses) based on the 10 waste retrieval cases analyzed. Again, Case 10 was excluded from the graphic presentation because it introduces an additional variable, the interim barrier.

Figure B.5.3. Tank C-104 Composite Risk Versus Retrieval Leakage Volume (Assuming 10,200 L [2,700 gal] of Residual Waste)



Figure B.5.4. Tank C-104 Composite Risk Versus Residual Waste Volume (Assuming 30,000 L [8,000 gal] of Retrieval Leakage)



B.5.3.2 C Tank Farm Long-Term Human Health Risk Assessment Results

This section presents the long-term human health risk results for the C tank farm as a whole by source term.

B.5.3.2.1 C Tank Farm Past Leaks. A total of seven tanks in the C tank farm are documented as having leaked (tanks C-101, C-110, C-111, C-201, C-202, C-203, and C-204) (HNF-EP-0182, Rev. 150). The past leak source term for these tanks is the same for all 10 waste retrieval cases and, as a result, the long-term human health risk is identical for each case (Tables B.5.6 and B.5.7). For the industrial worker, the ILCR at the time of peak composite risk is 2.0×10^{-8} and the hazard index is 5.2×10^{-5}. For the residential farmer, the ILCR at the time of peak composite risk is 6.8×10^{-7} and the hazard index is 5.7×10^{-3} (Tables B.5.6 and B.5.7). Of the 7 C farm tanks classified as leakers, tank C-101 has by far the largest estimated past leak volume (76,000 L [20,000 gal]) and inventory and dominates the C tank farm long-term human health risk from past leaks.

B.5.3.2.2 C Tank Farm Waste Retrieval Leak Losses. Ignoring the zero leak loss case (Case 4) for the industrial worker, the ILCR from C tank farm waste retrieval leak losses varies between 6.6×10^{-7} and 8.9×10^{-7} and the hazard index varies between 3.1×10^{-3} and 4.2×10^{-3}. For the residential farmer, the ILCR varies between 2.2×10^{-5} and 2.9×10^{-5} and the hazard index varies between 8.3×10^{-1} and 1.1×10^{0}. The low ILCR and hazard index values result from a number of cases indicating relative insensitivity of total farm risk to tank C-104 contributions. The high ILCR and hazard index values result from interim barrier use with waste retrieval leak losses of 30,000 L (8,000 gal) from tank C-104 and the other 100-series tanks and 3,000 L (800 gal) from the 200-series tanks.

To reflect current near-term plans for waste retrieval from sound tanks, long-term human health risk calculations assume DST supernate will be used as the retrieval fluid. This also provides conservative leak loss inventory estimates. Recognizing that tanks classified as leakers will probably be retrieved using water, a sensitivity case assumes water is used to retrieve waste from leaking tanks. The risks are 15% to 20% lower on a tank basis. A more complete presentation is provided in HNF-7989.

B.5.3.2.3 C Tank Farm Residual Waste. For the industrial worker, the ILCR from C tank farm residual waste varies between 3.8×10^{-7} and 2.2×10^{-6} and the hazard index varies between 3.0×10^{-1} and 2.4. For the residential farmer, the ILCR varies between 3.5×10^{-6} and 6.1×10^{-5} and the hazard index varies between 1.5×10^{2} and 7.9×10^{2}. The low ILCR and hazard index values result from interim barrier use with residual waste volumes of 10,000 L (2,700 gal) in tank C-104 and the other 100-series tanks and 830 L (220 gal) in the 200-series tanks. The high ILCR and hazard index values result from residual waste volumes of 23,000 L (6,000 gal) in tank C-104 and the other 100-series tanks and 1,500 L (400 gal) in the 200-series tanks.

B.5.3.2.4 C Tank Farm Composite Source Term. For the industrial worker, the ILCR from the C tank farm composite source term varies between 9.4×10^{-7} and 2.9×10^{-6} and the hazard index varies between 3.1×10^{-1} and 2.4×10^{0}. For the residential farmer, the ILCR varies between 2.4×10^{-5} and 8.4×10^{-5} and the hazard index varies between 1.5×10^{2} and 7.9×10^{2}.

The low ILCR and hazard index values result from the composite of interim barrier use with past leaks; no waste retrieval leak losses for all tanks; and residual waste volumes of 10,000 L (2,700 gal) in the 100-series tanks and 830 L (220 gal) in the 200-series tanks. The high ILCR and hazard index values result from the composite of past leaks; waste retrieval leak losses of 30,000 L (8,000 gal) in tank C-104 and the other 100-series tanks and 3,000 L (800 gal) in the 200-series tanks; and residual waste volumes of 23,000 L (6,000 gal) in tank C-104 and the other 100-series tanks and 1,500 L (400 gal) in the 200-series tanks.

B.5.3.3 Receptor Scenario Results Comparison

Table B.5.8 compares the long-term human health risk results for the scenarios based on DOE/RL-91-45 (industrial worker and residential farmer) with the results for the scenarios based on MTCA (Method B and Method C). Because the risk criteria set forth in "The Model Toxics Control Act Cleanup Regulation" (WAC 173-340) are applicable only to nonradioactive contaminants, Table B.5.8 compares only hazard index values. Table B.5.8 indicates that the residential farmer scenario is consistently the most conservative (i.e., produces the highest hazard index values), followed by MTCA Method B and MTCA Method C. The industrial worker scenario is consistently the least conservative (i.e., produces the lowest hazard index values) of the four scenarios.

B.5.4 INTRUDER RISK RESULTS

This section presents the results of the risk analyses for the inadvertent human intruder based on the DOE and NRC methodologies described in Section B.3.7. The DOE inadvertent human intruder analysis involves a well driller scenario and post-driller resident scenario, whereas the NRC inadvertent human intruder analysis is based on a scenario of the tank waste meeting the concentration limits established for Class C for the inadvertent human intruder at 500 years.

B.5.4.1 U.S. Department of Energy Intruder Scenario

The doses to the well driller and post-driller resident for each of the 10 waste retrieval cases are presented in Table B.5.9. The source or the total activity in curies of each constituent exhumed and made available at the surface for all the cases includes a fraction of waste from the residual waste in tank C-104 and soil contaminated by tank C-104 waste retrieval leak losses.
The radiological activity in the residual waste and retrieval leak losses is obtained from calculations presented in Attachment B1.

Table B.5.8. Comparison of Peak Hazard Index for Different Receptor Scenarios by Case

Case	Tank C-104		C Tank Farm					
	Residential Farmer	Industrial Worker	MTCA Method B	MTCA Method C	Residential Farmer	Industrial Worker	MTCA Method B	MTCA Method C
1	6.8E-01	4.0E-03	1.6E-01	7.5E-02	1.5E+02	3.1E-01	1.5E+01	6.8E+00
2	5.1E+00	3.0E-02	1.2E+00	5.6E-01	7.9E+02	2.4E+00	8.8E+01	4.0E+01
3	3.2E-01	1.9E-03	7.8E-02	3.6E-02	1.5E+02	3.1E-01	1.5E+01	6.8E+00
4	6.7E-01	3.9E-03	1.6E-01	7.4E-02	1.5E+02	3.1E-01	1.5E+01	6.8E+00
5	6.7E-01	3.9E-03	1.6E-01	7.4E-02	1.5E+02	3.1E-01	1.5E+01	6.8E+00
6	7.1E-01	4.1E-03	1.7E-01	7.8E-02	1.5E+02	3.1E-01	1.5E+01	6.8E+00
7	7.4E-01	4.3E-03	1.8E-01	8.2E-02	1.5E+02	3.1E-01	1.5E+01	6.8E+00
8	2.3E+01	1.3E-01	5.5E+00	2.5E+00	1.7E+02	4.4E-01	2.0E+01	9.3E+00
9	3.1E+01	1.8E-01	7.5E+00	3.4E+00	1.8E+02	4.9E-01	2.2E+01	1.0E+01
10	6.7E-01	3.9E-03	1.6E-01	7.4E-02	1.5E+02	3.1E-01	1.5E+01	6.7E+00

Table B.5.9. Well Driller and Post-Driller Resident Dose in 2100

Case	Well Driller (mrem/incident)	Post-Driller Resident (mrem/yr)
1	2.1E+01	6.0E+01
2	4.5E+01	1.2E+02
3	1.1E+00	6.8E+00
4	1.9E+01	4.6E+01
5	1.9E+01	4.6E+01
6	3.0E+01	1.1E+02
7	4.0E+01	1.8E+02
8	8.4E+01	4.6E+02
9	3.6E+02	9.0E+02
10	2.1E+01	6.0E+01

Notes: DOE regulations limit exposures to an inadvertent human intruder to no greater than 100 mrem/yr for chronic exposure (Post-driller resident) and 500 mrem for an acute or single event (Well driller) at a point in time 100 years after closure (DOE O 435.1)

B.5.4.2 U.S. Nuclear Regulatory Commission Requirements

A comparison of the radionuclide concentrations (before stabilization) in the residual waste in tank C-104 to the Class C upper limit concentration values is presented in Table B.5.10. The tank C-104 residual concentrations are discussed in more detail in Attachment B1. The comparison shows the long-lived radionuclides (specifically, alpha emitting TRU with $t_{1/2} > 5$ yr and plutonium-241) can greatly exceed the Class C upper limits. Table B.5.10 also shows the long-lived radionuclide sum-of-fractions is greater than 1, or an exceedance of 140 times.

The residual waste inventory estimates in tank C-104 were further evaluated for each of the cases (HNF-7989) using the Shyr and Bustard (1997) methodology to determine the minimum volume of grout that would be required to stabilize the residual waste and at the same time reduce the radiological constituent concentrations to a level that would not exceed Class C upper limits. This evaluation was performed to determine the feasibility of attaining Class C concentrations through stabilization of the residuals. The minimum depth of grout that would be required for each case is summarized in Table B.5.11.

Table B.5.10. Tank C-104 Residual Waste Concentrations Compared to the Class C Upper Limits

Long-Lived Radionuclides	Class C Upper Limits	Tank C-104 Residual Concentrations
Carbon-14	8 Ci/m^3	0.0002 Ci/m^3
Carbon-14 in activated metal	80 Ci/m^3	0 Ci/m^3
Nickel-59 in activated metal	220 Ci/m^3	0 Ci/m^3
Niobium-94 in activated metal	0.2 Ci/m^3	0 Ci/m^3
Technetium-99	3 Ci/m^3	0.005 Ci/m^3
Iodine-129	0.08 Ci/m^3	0.0007 Ci/m^3
Alpha emitting transuranic with $t_{1/2} > 5$ yr		
Neptunium-237	100 nCi/g	4.2 nCi/g
Plutonium-238,239,240	100 nCi/g	7,100 nCi/g
Americium-241,243	100 nCi/g	6,100 nCi/g
Curium-243 to 247	100 nCi/g	63 nCi/g
Berkelium-247	100 nCi/g	0 nCi/g
Californium-249 to 251	100 nCi/g	0 nCi/g
Plutonium-241	3,500 nCi/g	14,000 nCi/g
Curium-242	20,000 nCi/g	11.0 nCi/g
Short-Lived Radionuclides		
Nickel-63	700 Ci/m^3	0.69 Ci/m^3
Nickel-63 in activated metal	7,000 Ci/m^3	0 Ci/m^3
Strontium-90	7,000 Ci/m^3	1,100 Ci/m^3
Cesium-137	4,600 Ci/m^3	146 Ci/m^3
Sum-of-fractions for long-lived radionuclides	1.0	140
Sum-of-fractions for short-lived radionuclides	1.0	0.19

Table B.5.11. Minimum Level of Grout Required to Reduce Concentrations to Class C Upper Limits

Case	Residual Waste Volume (gal)	Minimum Level of Grout (in.)
1, 4, 5, 6, 7, 10	2,700	93
2	6,000	207
3	1,300	45
8	27,000	930
9	50,000	1,730

To obtain liters multiply gallons by 3.785.
To obtain centimeters multiply inches by 2.54.

B.5.5 REGULATORY COMPLIANCE RESULTS

This section describes the regulatory compliance for the results presented in Sections B.5.1 to B.5.4 for Cases 1 through 10. The methodology used for regulatory compliance analysis is presented in Section B.3.8. The following items are evaluated against the regulatory standards:

- Short-term human health risk to the worker MEI and the general public MEI from radiological and hazardous constituents
- Groundwater protection
- Long-term human health risk to the residential farmer and industrial worker from radiological and hazardous constituents for the peak time period of 2,600 years (over a 10,000-year period)
- Risk to DOE and NRC inadvertent human intruder
- HFFACO milestones.

B.5.5.1 Short-Term Human Health Risk Compliance

Short-term human health risks were evaluated based on operating the waste retrieval system to different end points in terms of residual waste volumes. Short-term human health risk is affected by variance in the duration of the waste retrieval operations; that is, the more waste retrieved, the longer the duration for waste retrieval and more exposure to workers and the public. Case 10, which assumes construction of an interim barrier, was considered separately because there is additional risk to workers resulting from constructing the barrier.

B.5.5.1.1 Routine Radiological Exposure During Retrieval Operations. The regulatory requirement for worker exposure based on annual whole body dose is 5.0 rem/yr (10 CFR 20; DOE Order 5480.11). Hanford Site Administrative Controls limit a worker's annual whole body

dose to 0.5 rem/yr (HSRCM-1). Worker radiological dose during routine waste retrieval operations will be carefully monitored to ensure levels do not exceed recommended standards. The functional requirement or "standard of practicality" in this instance is to demonstrate with worker dose estimates that waste from tank C-104 can be retrieved with appropriate time, distance, and shielding provisions in a manner that maintains worker doses within acceptable limits. The noninvolved worker and general public radiological LCF risk from normal operations do not exceed the regulatory requirement standard of 100 mrem/yr for all cases analyzed based on the assumptions and data in this report. Based on the results, no LCFs were reported for the general public or offsite receptor.

B.5.5.1.2 Routine Chemical Exposure During Retrieval Operations. Short-term chemical health impacts from normal operations would be below the regulatory standard for noncarcinogenics for all cases, based on available data and assumptions documented in this report. For carcinogenic risks from exposure, the ILCR for the noninvolved worker and public would be below the regulatory standard of 1.0×10^{-6}. The involved worker ILCR would be below the Washington State standard of 1.0×10^{-5} for multiple constituents (WAC 173-340) and below the federal standard of 1.0×10^{-4} (55 FR 8666).

B.5.5.2 Groundwater Protection Compliance

Groundwater quality requirements include compliance with EPA maximum contaminant levels (MCLs) (40 CFR 141), the DOE derived concentration guide (DOE Order 5400.5), and concentration limits under WAC 173-303-645. The most restrictive of these groundwater quality requirements are the EPA MCLs and are the only requirements discussed.

The CoC with the highest concentration level for the radionuclides in the groundwater is technetium-99. The highest chemical concentration is nitrate.

Technetium-99 is used as an indicator constituent as a result of its mobility in the environment (distribution coefficient of 0) and its long half-life. Technetium-99 will not exceed the EPA regulatory MCL (900 pCi/L) for any of the cases for the radionuclides. Nitrate exceeds the regulatory standard of 45 mg/L in Case 2. All other CoCs are below EPA MCLs, the DOE derived concentration guides, and state concentration limits.

B.5.5.3 Long-Term Human Health Risk Compliance

Long-term human health risks were evaluated based on the maximum groundwater concentration and the level of risk (i.e., ILCR and hazard index) as expressed in human health exposure to nine radiological constituents (technetium-99; selenium-79; iodine-129; carbon-14; and uranium-233, -234, -235, -236, and -238) and four chemical constituents (total uranium, chromate, nitrate, and nitrite). These constituents were chosen to evaluate long-term human health risks.

For carcinogenic risk, the level of protection provided under the regulations ranges from 1 in 10,000 (1.0×10^{-4}) to 1 in 1,000,000 (1.0×10^{-6}). For hazardous chemicals under residential or industrial scenarios Washington State requires ILCR not to be higher than 1.0×10^{-6} for individual contaminants and 1.0×10^{-5} for cumulative contaminants (WAC 173-340), while the

EPA requires the ILCR not to be higher than 1.0×10^{-4} (55 FR 8666). For noncarcinogenic risk a hazard index equal to or greater than one exceeds state and federal standards.

Regulatory standards may be exceeded for long-term human health risk and not for drinking water standards (DWSs) (40 CFR 141; EPA/822-B-96-002) as a result of water being used for bathing, washing food, irrigation, as well as drinking for the human health standard; while the DWS only assumes consumption. For example, the DWS for technetium-99 is 900 pCi/L and exposure to groundwater concentrations at this level would result in an ILCR of 2.3×10^{-4} for a residential farmer.

Based on available data and assumptions documented in this report, no exceedance of long-term human health risk standards occur for tank C-104 and the C tank farm for the industrial worker scenario. Exceedance of the hazard index standard does occur for tank C-104 in the residential farmer scenario in Cases 2, 8, and 9. Exceedances of ILCR and hazard index standards also occur for the C tank farm in all 10 cases for the residential farmer scenario.

B.5.5.4 Inadvertent Human Intruder Compliance

DOE regulations limit exposures to an inadvertent human intruder to no greater than 100 mrem/yr for chronic exposure and 500 mrem for an acute or single event at a point in time 100 years after closure (DOE O 435.1). A post-driller resident scenario is used to provide the bounding analysis for chronic exposure; a well-driller scenario is used to provide the bounding analysis for acute exposure. Results of the analysis (Table B.5.9) indicate that tank C-104 would meet the 500 mrem dose limit under all 10 waste retrieval cases but would exceed the 100 mrem/yr chronic dose limit under Cases 2, 6, 7, 8, and 9.

According to the results presented in Section B.5.4, the NRC standard for upper concentration limits for Class C LLW disposal would be exceeded for tank C-104 in all 10 waste retrieval cases if no additional actions were implemented. However, for all but Cases 8 and 9 the Class C limits could theoretically be met with stabilization of the residual waste with grout, assuming uniform mixing of the grout and the residual waste. The technological feasibility of uniformly mixing the required amount of grout with the residual waste is uncertain. Section B.6.0 addresses this uncertainty with respect to current NRC determinations at the DOE Savannah River Site.

B.5.5.5 HFFACO Milestone Compliance

The HFFACO Milestone M-45-03F states:

> Goals of this demonstration shall include the retrieval to safe storage of approximately 89 kg of plutonium (which represents approximately 17% of the total plutonium inventory within the SST system), and 99% of tank contents by volume (per DOE's Best-Basis Inventory data of 8/01/2000).

These 89 kg of plutonium criteria translates to retrieving 950,000 L (250,000 gal) of waste from tank C-104 (HNF-7989). The 99% of tank content by volume represent 9,960 L (2,630 gal) compared to 10,220 L (2,700 gal), which represents the HFFACO Milestone M-45-00 interim

retrieval goal of 360 ft^3. This 260-L (70-gal) difference is minor in comparison to the uncertainty associated with measuring residual waste volumes.

Cases 1, 2, 3, 4, 5, 6, 7, and 10 meet the Milestone M-45-03F demonstration goal of retrieving approximately 89 kg (196 lb) of plutonium from tank C-104. Adjusting for the inventory used in this RPE, the cases leaving no more than 22,700 L (6,000 gal) residual still meet the 89 kg (196 lb) retrieval of plutonium milestone.

B.6.0 CONCLUSIONS

This section provides the conclusions and recommendations relative to tank waste retrieval for tank C-104 based on the analysis of results presented in Section B.5.0. Section B.6.1 provides a summary of the conclusions as they relate to near-term waste retrieval efforts. Section B.6.2 provides a summary of the conclusions specific to the different areas of analysis.

B.6.1 SUMMARY CONCLUSIONS

The summary conclusions in the following sections are identified RPE findings that would influence waste retrieval and LDMM system criteria.

B.6.1.1 Tank C-104 Conclusions

The goal of the technology demonstration in tank C-104 is to demonstrate the limits of technology for the waste retrieval system and application and demonstration of the LDMM to waste retrieval. The HFFACO F&R document will identify the proposed methodology for demonstrating the limit of the technology. Because of the potential for leakage to occur during retrieval and the interrelationship between retrieval leakage and residual waste from a closure standpoint it is important to understand how the variation in residual waste volume and retrieval leakage volume influence the risk- and regulatory-based performance measures.

The final extent of retrieval is a tank farm closure issue; however, the extent of retrieval necessary to meet closure criteria as they are understood today should be considered in the F&R of the initial retrieval system. It is recognized that closure criteria have not been fully defined; however, the criteria as they are currently understood can be used to guide the development of a retrieval system. This approach does not preclude the retrieval of additional waste from the tank in the future as additional information is gathered during and after waste retrieval activities in the remaining C farm tanks and as closure criteria are established.

The performance measures that influence F&Rs for defining risk-based retrieval leak loss limits and the extent of retrieval (i.e., how much waste needs to be retrieved) for tank C-104 are driven by the inadvertent human intruder and regulatory waste classification performance measures. The inadvertent human intruder analysis indicates that with no retrieval leakage a residual waste volume less than or equal to 22,000 L (5,800 gal) would be required to meet the post-drilling resident DOE inadvertent human intruder dose of 100 mrem/yr (DOE performance standard). If leakage were to occur during retrieval, then the combination of residual waste and retrieval leakage could contribute to the intruder impacts. Figure B.6.1 shows the relationship between residual waste volume and retrieval leakage volume for the post-drilling resident waste site intruder at the performance standard of 100 mrem/yr. Figure B.6.1 shows that retrieving waste to the interim retrieval goal of 10,000 L (2,700 gal) of residual waste would allow up to 121,000 L (32,000 gal) of retrieval leakage loss without exceeding the 100 mrem/yr dose to the post-driller receptor. Figure B.6.1 also shows if retrieval leakage losses are minimized to 30,000 L (8,000 gal) (base case) the 100 mrem/yr dose to the post-driller receptor would not be exceeded if the residual waste is kept under 18,900 L (5,000 gal). For additional discussion of the inadvertent human intruder see Section B.5.4.

Figure B.6.1. DOE Inadvertent Human Intruder Post-Driller Threshold Dose (100 mrem/yr)



The intruder analysis also includes an evaluation of the various residual waste volumes against the NRC waste classification criteria in 10 CFR 61. The baseline closure strategy for the SSTs is to close the tank farms with the tanks and residual waste disposed of in place. This strategy requires DOE to assess the residual waste remaining in the tank following retrieval using the waste incidental to processing guidance in DOE O 435.1. The waste currently in tank C-104 exceeds the concentration based Class C limits. Thus, any amount of residual waste would exceed the concentration limits without pursuing a strategy to incorporate the residuals into a stabilized solid form (i.e., grout) at a concentration that does not exceed Class C limits or develop site specific Class C limits. While there is considerable uncertainty about the ability to mix or incorporate the residuals into a stabilized waste form or the degree to which mixing would be required, it is not necessary to resolve this issue prior to retrieving the waste.
The relationship between residual waste volume following stabilization or mixing and the Class C limits should be considered. The analysis results indicate that a residual waste volume of 10,000 L (2,700 gal) would need to be incorporated into a solid waste form of approximately 240 cm (93 in.) to meet Class C limits. There would be considerable technical uncertainty in trying to mix residual waste with this volume of grout or other stabilizing material.
This indicates that from the standpoint of reclassifying the residual waste as incidental waste using Class C limits and concentration averaging, the retrieval criteria measured as residual waste volume should be less than 10,000 L (2,700 gal).

The long-term human health risk analysis results show that for tank C-104 the risk from relatively large leakage volumes is below a risk threshold of 1.0×10^{-5}. When the risk allocation considerations are taken into account the retrieval leakage volume corresponding to the

tank C-104 risk budget is reduced. Using the allocation methodology identified in Section B.3.6.5 and the past leak ILCR of 2.0×10^{-8} the risk budget for C-104 is 1.3×10^{-6}. Using this risk budget and the risk associated with a residual waste volume of 10,000 L (2,700 gal), the performance measure for retrieval leakage using the residential farmer scenario would be approximately 130,000 L (36,000 gal).

B.6.1.2 C Tank Farm Conclusions

The DOE waste site intruder and the NRC waste classification issues discussed for tank C-104 are tank-specific and are not cumulative for the tank farm. The long-term human health risk performance measure and groundwater impacts are cumulative for the tank farm and thus need to be evaluated for the tank of interest and for the entire tank farm.

The groundwater impact and long-term human health risk analyses indicate that tank C-104 does not proportionally contribute to the C tank farm groundwater impacts and long-term human health risk under similar retrieval leakage and residual waste conditions. This indicates that the groundwater impacts and long-term human health risk on a tank farm level are not sensitive to changes in the performance of the waste retrieval system for tank C-104 from a residual waste volume or retrieval leakage perspective. Only under the larger residual volume cases does tank C-104 begin to proportionally contribute to the C tank farm groundwater impacts and human health risk.

B.6.2 CONCLUSIONS BY AREA OF ANALYSIS

Conclusions specfic to the areas of short-term human health risk, groundwater impacts, long-term human health risk, intruder risk, and regulatory compliance are provided in the following sections.

B.6.2.1 Short-Term Human Health Risk Conclusions

This section provides the conclusions reached in the short-term human health risk analysis for occupational risk, routine radiological risk, routine chemical risk, radiological accident risk, and chemical accident risk. Short-term human health risk analysis results are presented in Section B.5.1. Only the human health risk associated with retrieval operations and the construction of an interim barrier are calculated for comparison. The results of the analysis indicate that, overall, short-term human health risk is not a driver for establishing tank C-104 waste retrieval and LDMM system criteria. These differences are not significant in light of the inherent uncertainties in the analysis and assumptions.

B.6.2.1.1 Occupational Accident Conclusions. A comparison of the occupational risks (i.e., TRCs, LWCs, and fatalities) associated with the 10 waste retrieval cases and the additional health risk resulting from constructing an interim barrier results in the following conclusions.

- None of the waste retrieval cases result in a TRC, LWC, or fatality. Therefore, the analysis results indicate that this performance measure is not a driver for establishing waste retrieval and LDMM system criteria for tank C-104.

- As less sludge is retrieved from tank C-104 in comparison to the cases with 10,000 L (2,700 gal) residual waste (Cases 1, 4, 5, 6, 7, 10) the occupational risk from retrieval operations is reduced by 1% for Case 2, 10% for Case 8, and 20% for Case 9. As more sludge is retrieved the occupational risk from retrieved operations is increased by 10% as shown in Case 3.

- Adding the occupational risk from constructing an interim barrier for Case 10 increases the TRC, LWC, and fatality incidences by 100% as compared to the cases that assume 10,000 L (2,700 gal) residual waste without an interim barrier (Cases 1, 4, 5, 6, 7).

B.6.2.1.2 Routine Radiological Risk Conclusions. A comparison of the routine radiological risks (LCF) to the involved worker, noninvolved worker, and general public associated with the 10 waste retrieval cases and the additional health risk resulting from constructing an interim barrier results in the following conclusions.

- There is no LCF among the worker population, noninvolved worker population, or general public population resulting from waste retrieval operations. The LCF risk to the noninvolved worker MEI and general public MEI is very small (7.2×10^{-12}, 4.3×10^{-10}, respectively). The LCF risk to the involved worker is 2.0×10^{-4} and is based on the assumption that the MEI involved worker receives the administrative control dose of 500 mrem/yr. Therefore, the analysis results indicate that this performance measure is not a driver for establishing waste retrieval and LDMM system criteria for tank C-104.

- As less sludge is retrieved from tank C-104 in comparison to that assumed in the cases with 10,000 L (2,700 gal) residual waste (Cases 1, 4, 5, 6, 7, 10) the LCF risk from waste retrieval operations is reduced by as much as 20%. As more sludge is retrieved the LCF risk from waste retrieval operations is increased by 10% as shown in Case 3.

- Adding the LCF risk from constructing an interim barrier for Case 10 increases the LCF risk to the involved workers by 65% as compared to the cases that assume 10,000 L (2,700 gal) residual waste without an interim barrier (Cases 1, 4, 5, 6, 7).

B.6.2.1.3 Routine Chemical Risk Conclusions. A comparison of the routine carcinogenic health risks (ILCR) to the involved worker MEI, noninvolved worker MEI, and general public MEI during retrieval operations associated with the 10 waste retrieval cases results in the following conclusions.

- The ILCR for all the cases is small (i.e., less than 1.0×10^{-8}). Therefore, the analysis results indicate that this performance measure is not a driver for establishing waste retrieval and LDMM system criteria for tank C-104.

- As less sludge is retrieved from tank C-104 in comparison to that assumed in the cases with 10,000 L (2,700 gal) residual waste (Cases 1, 4, 5, 6, 7, 10) the ILCR risk from waste retrieval operations is reduced by 3% for Case 2, 10% for Case 8, and 20% for Case 9. As more sludge is retrieved the ILCR risk from waste retrieval operations is increased by 10% as shown in Case 3.

It should be noted that depending on the level of organic compounds contained in the sludge, operating plans should include a phased start-up of the waste retrieval system to limit the potential release of volatile organic compounds and/or ammonia emissions to within the prescribed limits. Such safeguards would help prevent a potential release that occurred with tank C-106 when the air permit limit was immediately exceeded when waste retrieval began (RPP-5687).

B.6.2.1.4 Radiological Accident Risk Conclusions. The severity of a given accident and the frequency of the accident are common to all 10 waste retrieval cases; however, the probability of the accident occurring varies slightly because of the slight variation in duration of operations between the cases. The variation is so slight that there is no change in frequency categories. Therefore, this performance measure is not a driver for establishing waste retrieval and LDMM system criteria for tank C-104.

B.6.2.1.5 Chemical Accident Risk Conclusions. The severity of a given accident and the frequency of the accident is the same for all 10 waste retrieval cases; however, the probability of the accident occurring varies slightly because of the slight variation in duration of operations between the cases. The variation is so slight that there is no change in frequency category. Therefore, this performance measure is not a driver for establishing waste retrieval and LDMM system criteria for tank C-104.

B.6.2.2 Groundwater Impact Conclusions

This section provides conclusions regarding the results of the groundwater impact analysis of the waste retrieval cases. Groundwater impact analysis results are presented in Section B.5.2. Conclusions are provided first for tank C-104 and then on a tank farm basis.

B.6.2.2.1 Tank C-104 Groundwater Impact Conclusions. The compliance status of tank C-104 relative to groundwater DWS-based regulations will be based on the combined groundwater contaminant concentration contributions from past tank releases, waste retrieval leak losses, and residual waste. The groundwater impacts from technetium-99, nitrate, iodine-129, and uranium-238 were estimated for all of the waste retrieval cases and it was found that the impacts associated with tank C-104 would all be below DWSs for these constituents for all cases. Of all the cases considered, Case 2 would come the closest to reaching or exceeding a DWS. The estimated groundwater impacts and associated DWSs (based on 40 CFR 141) for the composite of the three source terms (i.e., past tank releases, waste retrieval leak loss, and residual waste) for tank C-104 for Case 2 are as follows:

- Technetium-99 is 4.4 pCi/L (DWS 900 pCi/L)
- Nitrate is 0.7 mg/L (DWS 45 mg/L)
- Iodine-129 is 2.8×10^{-3} pCi/L (DWS 1 pCi/L)
- Uranium-238 is 3.3×10^{-3} pCi/L (DWS 6.7 pCi/L)

These estimated groundwater impacts associated with tank C-104 for Case 2 are below the DWS. The risk impacts, discussed in the next section, would be more restrictive because the estimated

risk is the sum of the risk from each contaminant. Thus, it would be possible to be below a DWS on a contaminant-by-contaminant basis but exceed a risk-based regulatory standard.

The results of the analysis indicate that this performance measure (i.e., DWSs) is not a driver for establishing waste retrieval and LDMM system criteria for tank C-104.

B.6.2.2.2 C Tank Farm Groundwater Impact Conclusions. The groundwater impact analysis results indicate that the composite groundwater impacts for the C tank farm are not sensitive to changes in the performance of the waste retrieval system for tank C-104 from a residual waste volume or retrieval leakage perspective. For instance, a 30,000-L (8,000-gal) retrieval leak from tank C-104 would have virtually no effect on the composite peak groundwater contaminant concentrations for the C tank farm (Case 1 compared to Case 5). The same is true for retrieval leaks of 150,000 L (40,000 gal) and 300,000 L (80,000 gal) from tank C-104 (Case 1 compared to Cases 6 and 7) in which there would be virtually no effect on the composite peak groundwater contaminant concentrations for the C tank farm. Leaving residual waste volumes of 100,000 L (27,000 gal) and 190,000 L (50,000 gal) in tank C-104 causes only very small increases in the composite peak groundwater contaminant concentration for the C tank farm compared to leaving only 10,200 L (2,700 gal) in tank C-104 (Case 1 compared to Cases 8 and 9). Likewise, reducing the residual waste volume in tank C-104 by approximately 50% from 10,200 L (2,700 gal) to 4,300 L (1,300 gal) would not provide a measurable change in the peak groundwater contaminant concentrations (Case 1 compared to Case 3).

From a tank farm perspective, several additional general conclusions can be drawn.
The composite peak groundwater contaminant concentrations for the C tank farm are more sensitive to changes in residual waste volume than to changes in retrieval leakage volume (Case 1 compared to Case 2 versus Case 1 compared to Case 4). The use of an interim barrier has a small overall effect on the composite peak groundwater contaminant concentrations for the C tank farm (Case 1 compared to Case 10). Lastly, under 40 CFR 141, only Case 2 exceeds the standard and only for nitrate. The estimated composite peak groundwater concentration for nitrate for Case 2 was 100 mg/L and the DWS is 45 mg/L. Over 99% of the nitrate in the composite concentration results from the residual assumed for this case.

B.6.2.3 Long-Term Human Health Risk Conclusions

This section provides the conclusions based on the results of long-term human health risk analysis. Long-term human health risk analysis results are presented in Section B.5.3.

B.6.2.3.1 Tank C-104 Long-Term Human Health Risk Conclusions. The compliance status of tank C-104 relative to risk-based regulatory standards will be based on the combined risk contributions from waste retrieval leak losses and residual waste remaining in the tank. Maintaining compliance within a given risk standard requires consideration of the risk contribution from residual waste and retrieval leakage. For a given risk level, the amount of residual waste decreases if the retrieval leakage volume increases. Conversely, the amount of leakage during retrieval has to be decreased as the amount of residual waste left in the tank is increased to ensure their combined risk does not exceed the allowable risk standard.
Figure B.6.2 shows the relationship between tank C-104 retrieval leakage volume and residual

waste volume for the industrial worker and residential farmer scenarios at several ILCR levels based on the analysis results for the 10 waste retrieval cases. Figure B.6.2 is truncated at 400,000 L (100,000 gal) of retrieval leak loss because of the scaling approach and the limited number of modeled leak loss volume cases from the AX tank farm from which the C tank farm is scaled.

Figure B.6.2. Industrial Worker and Residential Farmer ILCR Levels for Tank C-104 Retrieval Leakage Volume and Residual Waste Volume



Figure B.6.2 indicates that under the industrial worker scenario, tank C-104 does not exceed an ILCR of 1.0×10^{-6} even if very large retrieval leak losses occur or the amount of residual waste left in the tank is very large. Using the risk allocation methodology identified in Section 3 for the Residential Farmer scenario the risk budget for tank C-104 is 1.3×10^{-6} which is shown in Figure B.6.2.

For the industrial worker scenario, tank C-104 meets the Washington State human health cancer risk standards without retrieval efforts (ILCR = 2.1×10^{-6}). The retrieval standards for the residential farmer scenario are somewhat more restrictive. When the ILCR standard is applied to the C tank farm as a whole and apportioned across the tanks as discussed in Section B.3.0, the retrieval requirements are more restrictive, as shown in Figure B.6.2. For example, retrieval of tank C-104 down to the HFFACO interim retrieval goal (360 ft^3) would allow a 130,000 L (36,000 gal) leak and still remain within the apportioned risk limit of 1.3×10^{-6} for the residential farmer.

The results of the analysis indicate that the long-term risk performance measure can be used as one of the inputs for developing LDMM system criteria for tank C-104. The risk allocation methodology provides for allocation of retrieval leakage risk among the tanks. The uncertainties associated with the allocation methodology are discussed in Section B.6.3.

B.6.2.3.2 C Tank Farm Long-Term Human Health Risk Conclusions. The analysis results indicate that the long-term human health risk for the C tank farm as a whole is not sensitive to changes in the performance of the waste retrieval system for tank C-104 from a residual waste volume or retrieval leakage perspective. A 30,000-L (8,000-gal) retrieval leak from tank C-104 would have virtually no effect on the peak risk for the C tank farm (Case 1 compared to Case 5) and retrieval leaks of 150,000 L (40,000 gal) and 300,000 L (80,000 gal) from tank C-104 would have only minimal effects (Case 1 compared to Cases 6 and 7). Leaving residual waste volumes of 100,000 L (27,000 gal) and 190,000 L (50,000 gal) in tank C-104 causes only small increases in the peak risk for the C tank farm compared to leaving only 10,200 L (2,700 gal) in tank C-104 (Case 1 compared to Cases 8 and 9).

From a tank farm perspective, several additional general conclusions can be drawn. The peak risk for the C tank farm as a whole is more sensitive to changes in residual waste volume than to changes in retrieval leakage volume (Case 1 compared to Cases 2 and 4). The use of an interim barrier has a small overall effect on the peak risk for the C tank farm (Case 1 compared to Case 10). Lastly, under the industrial worker scenario, the peak risk for the C tank farm does not exceed the Washington State human health risk standards for any of the cases analyzed; under the residential farmer scenario all 10 waste retrieval cases exceed the standards.

B.6.2.4 Intruder Risk Conclusions

This section provides the conclusions based on the inadvertent human intruder analysis for the DOE intruder scenario and the NRC requirements. Intruder risk analysis results are presented in Section B.5.4.

B.6.2.4.1 U.S. Department of Energy Intruder Scenario Conclusions. DOE regulations require that exposure to the inadvertent human intruder do not exceed 500 mrem for an acute or single event (well driller) and 100 mrem in a year from chronic exposure (post-driller resident) (DOE O 435.1). A comparison of the well driller and post-driller resident doses to the DOE regulations for the various cases results in the following conclusions.

- None of the well driller cases exceed the 500 mrem acute dose limit set in DOE O 435.1. Case 9 has the greatest radiological impact (360 mrem) to the well driller.
- Cases 2, 6, 7, 8, and 9 exceed the 100 mrem chronic dose limit set in DOE O 435.1 for the post-driller resident; Cases 1, 3, 4, 5, and 10 do not.
- Tank C-104 exceeds the 100 mrem/yr chronic dose limit except for cases where the HFFACO-compliant residual waste volume of 10,000 L (2,700 gal) or less is coupled with the assumed baseline retrieval leakage volume of 30,000 L (8,000 gal) or less (Cases 1, 3, 4, 5, and 10).

B.6.2.4.2 U.S. Nuclear Regulatory Commission Requirement Conclusions. The analysis results indicate that this performance measure is a significant driver for establishing tank C-104 waste retrieval and LDMM system criteria. The NRC analysis results in the following conclusions.

- Mixing the residual waste with grout to achieve NRC Class C concentrations is uncertain for any of the 10 waste retrieval cases.
- Residual volumes approximately 1 order of magnitude smaller than the HFFACO interim retrieval goal of 360 ft^3 (Case 1) would be required to reach a point where stabilization of the residuals with approximately 25 cm (10 in.) of grout would meet NRC Class C limits.
- Site specific Class C limits will likely be required to address classification of the residual waste.

B.6.2.5 Regulatory Compliance Conclusions

This section addresses conclusions based on the results of regulatory compliance analysis. Regulatory compliance analysis results are presented in Section B.5.5. The regulatory compliance analysis involves the four performance measure areas of short-term human health risk, groundwater quality, long-term human health risk, and inadvertent human intrusion as well as other regulatory issues. Such issues include hazardous or dangerous waste management and disposal, radioactive waste management and disposal, and potential retrieval leak loss. Each issue is discussed regarding its ability to comply with applicable and relevant regulations. This section also addresses retrieval leak loss thresholds and residual waste thresholds based on compliance with the regulations using available data and assumptions.

The tank C-104 retrieval demonstration goals as specified in HFFACO Milestone M-45-03F are to remove to safe storage approximately 89 kg of plutonium and 99% of the tank C-104 contents by volume. The more restrictive of these two goals from a retrieval performance perspective is the removal of 99% of the tank contents by volume. Removing 89 kg of plutonium would require retrieving at least 950,000 L (250,000 gal) of waste from tank C-104, equating to a residual waste volume of approximately 49,000 L (13,000 gal). Removing 99% of the tank contents by volume would require retrieving at least 985,000 L (260,000 gal) of waste from tank C-104, equating to a maximum residual waste volume of 9,950 L (2,630 gal). A residual waste volume of 9,950 L (2,630 gal) would be slightly more restrictive (i.e., require more waste to be retrieved) than the Milestone M-45-00 interim retrieval goal of 360 ft^3 (10,000 L [2,700 gal]) of residual waste. However, given the precision of the available methods for quantifying residual waste volume, the two goals for all practical purposes are the same.

B.6.2.5.1 Short-Term Human Health Risk Compliance Conclusions. The short-term human health risks associated with routine retrieval operations assumed in each of the 10 waste retrieval cases do not exceed standards for the general public MEI. The incremental dose for the MEI at the Site boundary from tank C-104 retrieval operations (duration 30 days) is 1.8×10^{-8} rem/yr; therefore, the total is below the International Commission on Radiological Protection standard of 0.1 rem/yr (ICRP 1991).

B.6.2.5.2 Groundwater Protection Compliance Conclusions. Analysis results of the maximum groundwater concentration value for each CoC were compared to the EPA MCLs, DOE derived concentration guide, and 4 mrem effective dose equivalent concentrations for drinking water. Typically the EPA MCLs are the lowest regulatory standard. Nitrate is the only constituent to exceed the EPA MCLs in any of the 10 waste retrieval cases. The constituent with the highest groundwater concentration is nitrate at 100 mg/L in Case 2; the EPA MCL for nitrate is 45 mg/L (EPA/822-B-96-002).

B.6.2.5.3 Long-Term Human Health Risk Compliance Conclusions. Long-term human health risk standards may be exceeded even though groundwater quality standards (i.e., MCLs, derived concentration guide) are not exceeded because the groundwater quality standards are strictly based on drinking water ingestion, whereas the long-term human health risk calculations for future land use scenarios are based on multiple exposure pathways (e.g., drinking water ingestion, milk and meat ingestion, leafy vegetable ingestion). No exceedance of long-term human health risk occurs for tank C-104 and the C tank farm in the industrial worker scenario. The long-term human health risks associated with the residential farmer scenario exceed the Washington State standard of 1.0×10^{-5} ILCR and hazard index standard of 1.0 in all 10 waste retrieval cases for the C tank farm, but are below the EPA standard of 1.0×10^{-4} ILCR. Hazard index exceedance of 1.0 occurs for the residential farmer scenario for tank C-104 for Cases 2, 8, and 9.

B.6.2.5.4 Inadvertent Human Intrusion Compliance Conclusions. The analysis results indicate that Cases 2, 6, 7, 8, and 9 exceed the exposure performance objective for the post-driller resident (100 mrem/yr). Only cases with residual waste equal to or less than 10,000 L (2,700 gal) and no more than 30,000 L (8,000 gal) of waste retrieval leak losses do not exceed the chronic dose limit of 100 mrem/yr. The performance objective for the well driller indicates the performance objective for the acute dose (500 mrem/yr) is not exceeded for any case.

Under the NRC intruder scenario, used to establish Class C concentration limits for CoCs, none of the waste retrieval cases achieve satisfaction of the criteria. This issue becomes extremely important in determining waste retrieval goals in terms of closure decisions. Even if long-term human health risk is adequately addressed with most of the cases, none of the cases can meet the Class C LLW standard based on the criteria for incidental waste established by the NRC staff for the Savannah River Site tank closure (Travers 1999). The most significant regulatory issue relates to the LLW Class C standards for waste retrieval from tank C-104. The plutonium and americium concentrations established under 10 CFR 61 for class C limits exceed the criteria. Discussion in Section B.6.2.5.5 addresses this regulatory issue.

B.6.2.5.5 Additional Regulatory Issues. Conclusions related to regulatory issues beyond the four performance measure drivers are addressed in the following sections.

B.6.2.5.5.1 Residual Waste Issues. The NRC incidental waste criterion one specifies that:

> ...wastes have been processed (or will be processed) to remove key radionuclides to the maximum extent that is technically and economically practicable.

The first step in evaluating removal of radionuclides is establishing initial waste volumes and concentrations. Mechanical removal technologies remove bulk quantities of waste, but do not preferentially remove key radionuclides. Therefore, reduction of volume by waste removal may not change concentrations. Chemical treatment which removes key radionuclides may be added to the retrieval technology employed for tank C-104.

B.6.2.5.5.2 Inadvertent Human Intruder Scenario Issues. The NRC regulatory requirements for the classification of Class C LLW is analyzed for tank C-104. The analysis reveals that 10 m^3 (360 ft^3) of residual waste will only meet Class C standards when the residual waste is mixed with 240 cm (93 in.) of grout per the methodology established for the Savannah River Site. The NRC incidental waste Criterion 2 states that:

> ...wastes will be incorporated in a solid physical form at a concentration that does not exceed the applicable concentration limits for Class C low-level waste as set out in 10 CFR 61.

Using grout will ensure the waste will be in a solid physical form but uniformly mixing the residual with 240 cm (93 in.) of grout is a technical uncertainty. NRC staff recommends the following alternative waste classification be administered at the Savannah River Site for HLW tank residuals similar to that provided for in 10 CFR 61.58. The reclassification redefines the maximum allowable radionuclide concentration as follows: no radionuclide concentration shall exceed 10 times the value specified in Table 1 of 10 CFR 61.55, at 500 years following the proposed closure for each tank grouping, and no radionuclide concentration shall exceed the value specified in Table 2 Column 3 in 10 CFR 61.55. The procedure established in 10 CFR 61.55(a)(7) shall be followed such that the sum of the fractions for all Table 1 radionuclides shall not exceed 10, and the sum of the fractions for all Table 2 radionuclides shall not exceed 1. This standard is not attainable with tank C-104 because of the concentration of plutonium and americium in the residual.

If DOE is not able to demonstrate that the residual waste meets less than Class C limits, DOE may need to consider different regulatory options to have NRC determine that the residual is incidental waste. Other than the baseline approach, other options potentially available to DOE are as follows.

- **Disposal as incidental waste, site-specific Class C limits** – If the residual waste does not meet NRC Class C LLW limits and as a result of the residual waste being located 16.2 m (55 ft) belowground surface in the tanks, Hanford Site-specific Class C limits can be established to meet the NRC scenario for intruder construction. The NRC has authority to develop a Site-specific Class C limit under 10 CFR 61.

  Implementation of this approach is uncertain because the only regulatory precedent for NRC establishing site-specific Class C limits is the recent action at the Savannah River Site. Tank C-104 will not meet the Savannah River Site-specific limits. However, preliminary analysis in HNF-3428 indicates that Hanford Site-specific values can be developed and even the most problematic radionuclides in the Hanford Site SSTs are likely to meet the Class C performance objectives (i.e., dose limits) for the protection of inadvertent intruders.

- **Dispose as GTCC equivalent LLW** – The NRC does not rule out near-surface disposal of GTCC wastes. The NRC has, however, established the default option for GTCC as disposal in a geologic repository. The NRC states that (HNF-3428):

  > Disposal methods for GTCC waste must generally be more stringent than near-surface disposal. The proposed amendments to Part 61 specified that one "more stringent method would be geologic repository disposal. Other methods are not specified but are also left open to DOE, subject to Commission approval.

  This regulatory option is untested. The NRC has not established how it would determine if waste processing or facility design would be protective of intruders or the public and it is uncertain if the NRC or DOE would regulate onsite disposal. The NRC does not have authority to regulate the disposal of DOE LLW. However, *Low-Level Radioactive Waste Policy Amendments of 1985* grants the NRC legislative authority to license the DOE disposal of commercially generated GTCC LLW, and this situation could be viewed as an extension of that existing authority (HNF-3428). In this case, because the SST residual waste is GTCC LLW, the NRC could become the regulator for onsite disposal based on 10 CFR 61. A major strength of this option is the recognition that the waste does not meet the characteristics of LLW (i.e., it exceeds Class C limits), and yet the waste does not need to be disposed of in a deep geologic repository (i.e., it is not HLW).

B.6.3 UNCERTAINTIES

The long-term human health risk analysis presented in this RPE is based on inventory projections for what would remain in the C farm tanks following waste retrieval and leak losses that could occur during waste retrieval from all C farm tanks. The inventory estimates were developed using wash factors; there is some uncertainty with the tank-specific wash factors. Tank-specific chemical speciation modeling could provide a better basis for calculating residual waste inventories and potential retrieval leakage should be considered in future RPE analyses.

Future updates of the C tank farm RPE should consider specific contaminant transport simulations to reduce the uncertainties associated with scaling the results from DOE/RL-98-72. However, because the findings of this RPE indicate that the waste site intruder is the constraining performance measure and the RPE is a scoping-level evaluation, the uncertainty associated with scaling the contaminant transport is considered acceptable for making retrieval decisions.

DOE/RL-98-72 evaluates tank closure options that include demolition and removal of the tanks and contaminated soils from the tank farm. That study concludes the presence of retrieval leakage beneath the base of a tank would significantly add to worker doses from tank and soil excavation. The engineering approach developed for tank and soil excavation involves radiation workers operating shielded equipment. Remote operations are evaluated but would require substantial research and development efforts prior to deployment. Based on the AX tank farm analysis in DOE/RL-98-72 it can be concluded that large retrieval leak loss volumes could preclude clean closure due to the increased risk to workers.

The risk assessment performed for this RPE is based on best available information and data. The inventory estimates for retrieval leakage and residual waste are based on the current BBI

(BBI 2000) and a methodology designed to provide a best estimate for retrieval leakage concentrations and residual waste concentrations that considers tank-specific wash factors. Wash factors represent the fraction of a constituent that is expected to partition into the liquid phase during waste retrieval. Several different approaches were identified for estimating the post-retrieval residual waste inventory. The variation in results obtained using different methods is an uncertainty that warrants further evaluation. Source terms or release rates from the tank residuals are conservative in that no credit is taken for stabilization or incorporation of the tank residuals into grout (e.g., grouting the residuals). Additionally the tanks are assumed to completely degrade at the same time providing a conservative estimate of residual waste impacts across the tank farm. The contaminant transport methodology and results for the AX tank farm RPE (DOE/RL-98-72), which were used as the basis for scaling tank C-104 and C tank farm impacts, was reviewed by a number of individuals. The risk factors used in this tank C-104 RPE for the industrial worker and residential farmer exposure scenarios were taken from DOE/RL-98-72 and DOE/EIS-0189. Both of these documents underwent extensive review.

There are uncertainties associated with estimating retrieval leakage source terms. The approach used to calculate contaminant concentrations is based on calculating the volume of water required to reach a 5 Molar sodium concentrations. The 5 Molar sodium concentration is a value typically assumed for the waste transfer specification. In actual tank conditions the concentrations by be higher or lower or could vary during the retrieval operation. Chemical composition of water leachates from tank C-104 solids resulted in sodium concentrations of approximately 0.25 Molar and technetium-99 concentrations of 2.27×10^{-6} Ci/L (PNL-7297). This technetium-99 concentration is approximately 5 times lower than predicted using the wash factors.

The long-term impacts from ancillary equipment are not quantitatively addressed in this scoping level RPE. The contribution of the ancillary equipment to the tank farm closure inventory is an area that will require consideration in future versions of the C farm RPE and in performance assessment calculations for C farm closure. Currently there is no available data on the contaminant inventory in the C farm ancillary equipment.

Risk assessments are inherently uncertain in that a number of enabling assumptions and estimates have to be made to assess potential risks to a future site user. For a point estimate risk assessment the inputs used are typically conservative point estimates. Those conservative estimates combine to produce a conservative or bounding result. A stochastic uncertainty and sensitivity analysis was performed for the AX tank farm RPE (DOE/RL-98-72) to evaluate how variation and uncertainty in model input parameters translates into uncertainty in long-term human health risk projections. Both uncertainty (lack of knowledge about a parameter) and variability (naturally occurring variations such as receptor bodyweight) contribute to the overall risk uncertainty. Based on the sensitivity analysis results from DOE/RL-98-72 the input parameters, ranked in order from highest to lowest influence, were exposure, source term, and transport parameters. Based on DOE/RL-98-72 uncertainty analysis results it was observed that variation and uncertainty in the exposure parameters (e.g., milk consumption, water consumption, exposure duration) resulted in 2.5 orders of magnitude in overall uncertainty. The results of the DOE/RL-98-72 uncertainty analysis are generally applicable to this tank C-104

RPE in that the parameters that tended to dominate the uncertainty at the AX tank farm would be expected to drive the uncertainty at the C tank farm.

There are a number of transport model scale issues associated with scoping- level analyses. The approach used for this RPE was based on AX tank farm RPE because of the near proximity of the tank farms and similar subsurface conditions expected at each location. The model scale issues are with respect to the tank farm areas (the C tank farm is larger than the AX tank farm) and groundwater modeling approach which was based on a Site-scale model.

The AX RPE groundwater model has a grid spacing of 250 by 250 m (820 by 820 ft), which is appropriate for Site-scale evaluations designed to evaluate contaminant concentrations in the groundwater at a number of compliance points from the 200 areas to the Columbia River. It is however relatively coarse for local-scale evaluations at the tank farm. Because the AX RPE was a scoping-level analysis, a local scale model of the tank farm was not developed. This approach has some limitations when looking at compliance points at the tank farm boundary and is further compounded because the C tank farm is areally larger than the AX tank farm. Application of the modeling approach developed for the S tank farm RPE (RPP-7644) would be expected to yield higher contaminant concentrations in the groundwater and higher long-term risks at the tank farm fence line. It is likely that more detailed analyses will be completed in the future to support tank farm closure and these analyses will likely require optimization of the transport modeling approach to evaluate tank farm closure performance at a number of compliance points.

One of the conclusions drawn from the DOE/RL-98-72 uncertainty analysis was that additional data collection would provide limited reduction in the overall uncertainty and that the magnitude of the uncertainty should not be used to delay interim decisions to move forward with waste retrieval.

B.7.0 REFERENCES

10 CFR 20, "NRC Standards for Protection Against Radiation," *Code of Federal Regulations*, as amended.

10 CFR 50, "Policy Relating to the Siting of Fuel Reprocessing Plants and Related Waste Management Facilities," *Code of Federal Regulations*, as amended.

10 CFR 60, "Disposal of Radioactive Waste in Geological Repositories," *Code of Federal Regulations*, as amended.

10 CFR 61, "Licensing Requirements for Land Disposal of Radioactive Waste," *Code of Federal Regulations*, as amended.

10 CFR 193, "Environmental Standards for the Management, Storage, and Land Disposal of Low-Level Radioactive Waste Land Naturally Occurring Accelerator-Produced Radioactive Waste," *Code of Federal Regulations*, as amended.

40 CFR 141, "National Primary Drinking Water Regulations," *Code of Federal Regulations*, as amended.

40 CFR 191, "Environmental Radiation Protection Standards for Management and Disposal of Spent Nuclear Fuel, High-Level and Transuranic Radioactive Wastes," *Code of Federal Regulations*, as amended.

40 CFR 194, "Criteria for the Certification and Re-certification of the Waste Isolation Pilot Plant's Compliance with the 40 CFR 191 Disposal Regulations," *Code of Federal Regulations*, as amended.

40 CFR 260, "Hazardous Waste Management System: General," *Code of Federal Regulations*, as amended.

40 CFR 261, "Identification and Listing of Hazardous Waste," *Code of Federal Regulations*, as amended.

40 CFR 262, "Standards Applicable to Generators of Hazardous Waste," *Code of Federal Regulations*, as amended.

40 CFR 263, "Standards Applicable to Transporters of Hazardous Waste," *Code of Federal Regulations*, as amended.

40 CFR 264, "Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities," *Code of Federal Regulations*, as amended.

40 CFR 265, "Interim Status Standards for Owners and Operators of Hazardous Waste Treatment, Storage, and Disposal Facilities," *Code of Federal Regulations*, as amended.

40 CFR 266, "Standards for the Management of Specific Hazardous Wastes and Specific Types of Hazardous Waste Management Facilities," *Code of Federal Regulations*, as amended.

40 CFR 268, "Land Disposal Restrictions," *Code of Federal Regulations*, as amended.

40 CFR 270, "EPA Administered Permit Programs: The Hazardous Waste Permit Program," *Code of Federal Regulations*, as amended.

40 CFR 271, " Requirements for Authorization of State Hazardous Waste Programs," *Code of Federal Regulations*, as amended.

40 CFR 272, "Approved State Hazardous Waste Management Programs," *Code of Federal Regulations*, as amended.

40 CFR 273, "Standards for Universal Waste Management," *Code of Federal Regulations*, as amended.

40 CFR 279, "Standards for the Management of Used Oil," *Code of Federal Regulations*, as amended.

40 CFR 280, "Technical Standards and Corrective Action Requirements for Owners and Operators of Underground Storage Tanks (UST)," *Code of Federal Regulations*, as amended.

55 FR 8666, 1990, "National Oil and Hazardous Substances Pollution Contingency Plan," *Federal Register*, March 8.

65 FR 7319, 2000, "Establishment of the Hanford Reach National Monument," *Federal Register*, June 13.

Atomic Energy Act of 1954, 42 USC 2011 et seq., as amended.

BBI, 2000, *Best Basis Inventory*, August 1, 2000 revision accessed at http://www.hanford.gov/twrs/char.pub/ in December 2000.

Clean Air Act, Public Law 88-206, 42 USC 7401 et seq., as amended.

Clean Water Act, Public Law 95-217, 91 Stat. 1566 and Public Law 96-148, (December 1977).

Comprehensive Environmental Response, Compensation, and Liability Act of 1980, Public Law 96-150, 94 Stat. 2767, 42 USC 9601 et seq.

Dentler, M. E., 1995, "Toxicological Evaluation of Tank Waste Chemicals," Hanford Environmental Health Foundation Industrial Hygiene Assessments, Richland, Washington, January 13.

DOE, 1996, *Dangerous Waste Permit Application – Single-Shell Tank System*, Rev. 4, U.S. Department of Energy, Washington, D.C.

DOE/EIS-0189, 1996, *Tank Waste Remediation System, Hanford Site, Richland, Washington, Final Environmental Impact Statement*, U.S. Department of Energy and Washington State Department of Ecology, Washington, D.C.

DOE/EIS-0303D, 2000, *High-Level Waste Tank Closure Draft Environmental Impact Statement*, Department of Energy, Savannah River Operations Office, Aiken, South Carolina.

DOE M 435.1, 1997, *Radioactive Waste Management Manual*, U.S. Department of Energy, Washington, D.C.

DOE O 435.1, 1997, *Radioactive Waste Management*, U.S. Department of Energy, Washington, D.C.

DOE Order 5400.5, 1990, *Radiation Protection of the Public and the Environment*, U.S. Department of Energy, Washington, D.C.

DOE Order 5480.11, 1991, *Radiation Protection for Occupational Workers*, U.S. Department of Energy, Washington, D.C.

DOE/RL-89-16, 1996, *Single-Shell Tank Closure Work Plan*, Rev. 1, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

DOE/RL-91-45, 1995, *Hanford Site Risk Assessment Methodology*, Rev. 3, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

DOE/RL-93-33, 1996, *Focused Feasibility Study of Engineered Barriers for Waste Management Units in 200 Areas*, Rev. 0, U.S. Department of Energy, Office of Environmental Restoration and Waste Management, Richland, Washington

DOE/RL-98-72, 1999, *Retrieval Performance Evaluation Methodology for the AX Tank Farm*, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

DOE/RL-99-36, 1999, *Phase I RCRA Facility Investigation/Corrective Measures Study Work Plan for Single-Shell Tank Waste Management Areas*, Rev. 0, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

DOE-STD-3009-94, 1994, *Preparation Guide for U.S. Department of Energy Nonreactor Nuclear Facility Safety Analysis Reports*, U.S. Department of Energy, Washington, D.C.

Ecology, EPA, and DOE, 1989, *Hanford Federal Facility Agreement and Consent Order*, as amended, Washington State Department of Ecology, U.S. Environmental Protection Agency, and U.S. Department of Energy, Olympia, Washington.

Energy Reorganization Act of 1974, 42 USC 5842, as amended.

EPA-822-B-96-002, 1996, *Drinking Water Regulations and Health Advisories*, U.S. Environmental Protection Agency, Office of Water, Washington, D.C.

Federal Facility Compliance Act of 1992, Public Law 102-386, 42 USC 6921 et seq.

Fitzsimmons, T. and C. Clarke, 2000, "Final Determination Pursuant to the Hanford Federal Facility Agreement and Consent Order in the Matter of Hanford Site High-Level Radioactive Tank Waste Treatment Capacity Acquisition, Tank Waste Treatment and Associated Tank Waste Work Requirements" (letter to C. Huntoon, Assistant Secretary of EM; R. T. French, Manager of ORP; and K. Klein, Manager of RL, March 29), Office of Director of Washington State Department of Ecology and Office of Administrator of Region 10 U.S. Environmental Protection Agency, U.S. Department of Energy, Olympia, Washington.

Frei, M. W., 1996, *Issuance of Low-Level Waste Performance Assessment Guidance* (Memorandum to Distribution Issuing the Interim Format and Content Guide and Standard Review Plan for U.S. Department of Energy Low-Level Waste Disposal Facility Performance Assessments), U.S. Department of Energy, Washington, D.C.

GJO-HAN-18, 1998, *Vadose Zone Characterization Project at the Hanford Tank Farms: C Tank Farm Report*, U.S. Department of Energy, Grand Junction Projects Office, Grand Junction, Colorado.

GJO-HAN-18, 2000, *Vadose Zone Characterization Project at the Hanford Tank Farms Addendum to the C Tank Farm Report,* U.S. Department of Energy, Grand Junction Projects Office, Grand Junction, Colorado.

Hazardous and Solid Waste Amendments of 1984, Public Law 98-616, 42 USC 6979 et seq.

"Hazardous Waste Management Act," RCW 70.105, *Revised Code of Washington*, as amended.

HNF-3428, 1998, *Regulatory Closure Options for the Residue in the Hanford Site Single-Shell Tanks*, Rev. 0, Lockheed Martin Hanford Corporation, Richland, Washington.

HNF-3441, 1998, *AX Tank Farm Ancillary Equipment Study*, Rev. 0, COGEMA Engineering Corporation, Richland, Washington.

HNF-7989, 2001, *Enabling Assumptions and Calculations to Support the Tank C-104 Retrieval Performance Evaluation*, CH2M HILL Hanford Group, Inc., Richland, Washington.

HNF-EP-0182, 2000, *Waste Tank Summary Report for Month Ending September 30, 2000*, Rev. 150, CH2M HILL Hanford Group, Inc., Richland, Washington.

HNF-SD-WM-SAR-067, 1999, *Tank Waste Remediation System Final Safety Analysis Report*, Rev. 1, Fluor Hanford, Inc., Richland, Washington.

HSRCM-1, 1994, *Hanford Site Radiological Control Manual*, Westinghouse Hanford Company, Richland, Washington.

ICRP, 1991, *1990 Recommendation of the International Commission on Radiological Protection*, ICRP Publication 60, International Commission on Radiological Protection, Pergamon Press, New York, New York.

Land Disposal Program Flexibility Act of 1996, Public Law 104-119, 42 USC 6924 et seq.

LA-UR-00-4050, 2000, *Hanford Soil Inventory and Uncertainty Model*, Rev. 1, Los Alamos National Laboratory, Los Alamos, New Mexico.

LA-UR-96-3860, 1997, *Hanford Tank Chemical and Radionuclide Inventories: HDW Model*, Rev. 4, Los Alamos National Laboratory, Los Alamos, New Mexico.

Low-Level Waste Policy Amendments Act, Public Law 99-240, as amended.

"Model Toxics Control Act," RCW 70.105D, *Revised Code of Washington*, as amended.

National Environmental Policy Act of 1969, 42 USC 4321 et seq.

NRC, 1995, *Branch Technical Position on Concentration Averaging and Encapsulation*, U.S. Nuclear Regulatory Commission, Washington, D.C.

Nuclear Waste Policy Act of 1982, 42 USC 10101 et seq.

NUREG 1.145, 1982, *Atmospheric Dispersion Models for Potential Accident Consequences Assessment at Nuclear Power Plants*, U.S. Nuclear Regulatory Commission, Washington D.C.

NUREG/CR-5991, 1993, *PORFLOW: A Multifluid Multiphase Model for Simulating Flow, Heat Transfer, and Mass Transport in Fractured Porous Media, User's Manual – Version 2.41*, U.S. Nuclear Regulatory Commission, Washington, D.C.

Occupational Safety and Health Act of 1970, 29 USC 651 et seq.

Paperiello, C. J., 1997, "Classification of Hanford Low-Activity Tank Waste Fraction" (Letter to J. Kinzer, Assistant Manager, Office Tank Waste Remediation System, June 9), Office of Nuclear Material Safety and Safeguards, U.S. Nuclear Regulatory Commission, Richland, Washington.

PNL-6584, 1988, *GENII – The Hanford Environmental Radiation Dosimetry Software System*, Pacific Northwest Laboratory, Richland, Washington.

PNL-7297, 1990, *Hanford Waste Form Release and Sediment Interaction*, Pacific Northwest Laboratory, Richland, Washington.

PNL-10886, 1995, *Development of a Three-Dimensional Ground-Water Model of the Hanford Site Unconfined Aquifer System: FY 1995 Status Report*, Pacific Northwest Laboratory, Richland, Washington.

PNNL-11665, 1997, *Tritium Monitoring in Groundwater and Evaluation of Model Predictions for the Hanford Site 200 Area Effluent Treatment Facility*, Pacific National Northwest Laboratory, Richland, Washington.

PNNL-11800, 1998, *Composite Analysis for Low-Level Waste Disposal in the 200 Area Plateau of the Hanford Site*, Pacific Northwest National Laboratory, Richland, Washington.

PNNL-11801, 1997, *Three-Dimensional Analysis of Future Groundwater Flow Conditions and Contaminant Plume Transport in the Hanford Site Unconfined Aquifer System: FY 1996 and 1997 Status Report*, Pacific Northwest National Laboratory, Richland, Washington.

Reorganization Plan No. 3 of 1970, Special Message from the President to the Congress About Reorganization Plans to Establish the Environmental Protection Agency and the National Oceanic and Atmospheric Administration, Washington, D.C.

Resource Conservation and Recovery Act of 1976, 42 USC 6901 et seq.

Rosenthal, 1997, *Approaches to Closure of High-Level Mixed Waste Tanks Considering the Hazardous Waste Component of the Waste*, Colorado Center for Environmental Management, Denver, Colorado.

RPP-5687, 2000, *Waste Retrieval Sluicing System (WRSS) and Project W-320, Tank 241-C-106 Sluicing, Lessons Learned*, Rev. 0, CH2M HILL Hanford Group, Inc., Richland, Washington.

RPP-6843, 2000, *Preliminary Engineering Report for the 241-C-104 Retrieval System*, Rev. 0, CH2M HILL Hanford Group, Inc., Richland, Washington.

RPP-7807, 2000, *Single-Shell Tank C-104 Full Scale Sludge/Hard Heel Confined Sluicing and Robotic Technologies, Waste Retrieval Demonstration Functions and Requirements*, DRAFT, CH2M HILL Hanford Group, Inc., Richland, Washington.

Safe Drinking Water Act, Public Law 93-523, December 16, 1974, 88 Stat. 1660, Title 21.

Shyr, L. J. and L. D. Bustard, 1997, *Summary of Communication with DOE Tank Sites on Tank Closure Issues*, Sandia National Laboratories, Albuquerque, New Mexico.

Toxic Substances Control Act of 1976, 15 USC 2601, et seq.

Travers, W. D., 1999, "Classification of Savannah River Residual Tank Waste as Incidental" (Letter SECY-99-294 to The Commissioners, NRC, December 15), Office of Executive Director for Operations, U.S. Nuclear Regulatory Commission, Washington, D.C.

WAC 173-200, "Water Pollution Control Act," *Washington Administrative Code*, as amended.

WAC 173-303, "Dangerous Waste Regulations," *Washington Administrative Code*, as amended.

WAC 173-340, "The Model Toxics Control Act Cleanup Regulation," *Washington Administrative Code*, as amended.

"Water Pollution Control Act," RCW 90.48, *Revised Code of Washington*, as amended.

WDOH/320-015, 1997, *State of Washington Department of Health Interim Regulatory Guidance: Hanford Guidance for Radiological Cleanup*, Rev.1, Environmental Radiation Program, Washington State Department of Health.

WHC-EP-0645, 1995, *Performance Assessment for the Disposal of Low-Level Waste in the 200 West Burial Grounds*, Westinghouse Hanford Company, Richland, Washington.

WHC-SD-WM-ER-313, 1994, *Supporting Document for the Northeast Quadrant Historical Tank Content Estimate Report for C Tank Farm*, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

WHC-SD-WM-ER-349, 1994, *Historical Tank Content Estimate for the Northeast Quadrant of the Hanford 200 East Area*, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

This page intentionally left blank.

ATTACHMENT B1

RETRIEVAL AND RESIDUAL INVENTORY CALCULATIONS

This page intentionally left blank.

CONTENTS

B1.1.0 INTRODUCTION B1-1

B1.2.0 PAST TANK LEAKS B1-4

B1.3.0 TANK C-104 CALCULATIONS B1-5

B1.4.0 COMPOSITE SUPERNATE DEVELOPMENT B1-13

B1.5.0 REMAINING C FARM TANK CALCULATIONS B1-16

B1.6.0 REFERENCES B1-26

TABLES

B1.1. Estimated Inventories for C Farm Tanks Past Leaks B1-4
B1.2. Current Chemical Inventory in Tank C-104 ..... B1-7
B1.3. Current Radionuclide Inventory in Tank C-104 ..... B1-8
B1.4. Current Chemical Inventory in Tank AY-101 Supernate B1-9
B1.5. Current Radionuclide Inventory in Tank AY-101 Supernate B1-10
B1.6. Tank C-104 Inventories Leak Data B1-11
B1.7. Tank C-104 Inventories Heel Data B1-12
B1.8. Concentrations of Chemicals in Average Double-Shell Tank Supernate for C Farm Retrieval B1-14
B1.9. Concentrations of Radionuclides in Average Double-Shell Tank Supernate for C Farm Retrieval B1-15
B1.10. C Farm Tank Best-Basis Inventories B1-17
B1.11. C Farm Tank Post-Retrieval Heel Inventories (360 ft^3 for 100-Series Tanks, 30 ft^3 for 200-Series Tanks) B1-19
B1.12. C Farm Tank Post-Retrieval Heel Inventories (802 ft^3 for 100-Series Tanks, 80 ft^3 for 200-Series Tanks) B1-21
B1.13. Retrieval Leak Loss Inventory Estimates, Assuming Supernate as Retrieval Fluid B1-23
B1.14. Retrieval Leak Loss Inventory Estimates, Assuming Water as Retrieval Fluid B1-25

LIST OF TERMS

BBI	best-basis inventory
DST	double-shell tank
HFFACO	*Hanford Federal Facility Agreement and Consent Order*

B1.1.0 INTRODUCTION

Waste composition estimates were made for each of the C farm tanks, postulating waste tank contents after retrieval to the *Hanford Federal Facility Agreement and Consent Order* (HFFACO; Ecology et al. 1989) interim retrieval goal of 360 ft^3 for 100-series tanks and 30 ft^3 for 200-series tanks. Other residual waste heel amounts and leak loss inventories were calculated for tank C-104 to support the evaluation of the 10 cases presented in this document. These calculations provide input to the various performance measure analyses. The principal source of information for the estimates is the best-basis inventory (BBI) data (BBI 2000). The composition of waste in each tank was estimated for during waste retrieval and for several potential compositions of waste residuals after retrieval according to the waste retrieval cases evaluated in the main text.

The following are the basic assumptions used in making the waste inventory estimates.

1. Retrieval liquid requirement for each tank is based on the amount required to ensure the concentration of sodium is less than 5 Molar and the concentration of undissolved solids is less than 10 wt% in the waste solution transferred out of the tank.

2. An average double-shell tank (DST) supernate is used as the waste retrieval-sluicing medium for retrieval operations at all C farm tanks except tank C-104 (i.e., DST AY-101 supernate is planned to be used).

3. The baseline retrieval end point is as defined in the HFFACO; specifically, a wet sludge heel of 360 ft^3 (10,000 L [2,700 gal]) is assumed for 100-series tanks and 30 ft^3 (830 L [220 gal]) for 200-series tanks.

4. The initial conditions in the tanks are as defined in the BBI (BBI 2000).

5. The composite supernate will behave like water in its ability to dissolve heel solids, according to *Best-Basis Wash and Leak Factor Analysis* (HNF-3157) for each tank.

6. Post-retrieval residual waste will have the same physical characteristics (e.g., interstitial volume) as the dry waste heels left in the 200-series tanks of the C tank farm. Final heel porosity was calculated for the 200-series tanks to be 58.5%, which is comparable to *Chemical Engineers' Handbook* (Perry 1963) values for similar solids (e.g., sand, dirt).

7. Tanks not yet interim stabilized will be interim stabilized prior to waste retrieval. Interim stabilization is defined for single-shell tanks as (HNF-EP-0182, Rev. 150):

   > A tank which contains less than 50,000 gal of drainable interstitial liquid and less than 5,000 gal of supernate liquid. If the tank is jet pumped to achieve interim stabilization, then the jet pump flow or saltwell screen inflow must also have been at or below 0.05 gpm before interim stabilization criteria is met.

8. Residual waste heel volumes less than or equal to the HFFACO interim retrieval goal (360 ft^3, 30 ft^3) will be double-rinsed with water to remove soluble contaminants introduced by using supernate as the retrieval fluid. Greater heel volumes were assumed abandoned because they would indicate a problem with the retrieval process.

The conventional units used in current Hanford Site documentation for tank compositions are used in the discussions and tables of this attachment. The units are as follows:

- Volumes – gallons
- Mass – kilograms
- Radionuclides – curies.

The values for volume had to be converted to liters to complete the inventory calculations reported in this attachment and then converted back to gallons when reported as calculation results.

The model for final waste composition is similar to sand left in a bucket. A bucket full of sand can still contain a certain additional volume of water. This is because there is space (interstitial volume) between the particles of sand. The calculation is designed to leave a sludge heel of some volume, saturated with either retrieval fluid or the final rinse fluid.

The calculation method used to estimate the residual waste inventories follows.

1. Calculate the amount of liquid needed to make a 10% w/w solids slurry with the amount of waste presently in the tanks (the 5 M sodium restriction did not apply to any of the C farm tanks).

2. Use the best-basis wash factor (a tank-specific value) to estimate the amount of solids that would dissolve into the total volume of retrieval fluid.

3. Calculate the retrieval fluid concentration. This is done by adding the three inventories (average supernate inventory [which is equal to the average supernate concentration times the amount of supernate introduced into the tank], the solids inventory fraction dissolved into the supernate (using best-basis wash factors) and inventory from liquid already in the tank [retrieved directly from the BBI]) and dividing the sum by the total amount of liquid required to retrieve the tank.

4. Reduce (by ratio) the new calculated volume of solids (diminished by dissolution into the retrieval fluid) to the desired residual waste heel volume.

5. Using an assumed average porosity calculated from dry sludge in 200-series tanks (see assumption 6 above) calculate the heel interstitial volume.

6. Using the final retrieval fluid concentration (calculated in step 3), calculate the heel inventory contribution of the final retrieval fluid filling the interstitial volume of the reduced heel volume (calculated in step 4).

7. If the final heel volume is calculated to be the HFFACO interim retrieval goal volume (which would leave approximately 2.54 cm [1 in.] of waste at the bottom of the tank) or less it is assumed that the heel would be washed to reduce inventory addition from the retrieval fluid (1:3 dilution). If the final heel volume calculated is greater than that allowed by HFFACO, the retrieval fluid filling the interstitial volume of the heel is left at full strength on the assumption that something would have gone wrong for the retrieval effort to be terminated early.

8. Final heel inventory is estimated as the sum of waste constituents calculated in step 4 plus the waste constituents from either step 6 or 7, depending on the final heel volume calculated for.

9. Retrieval leak loss inventory is found by multiplying the concentration of the retrieval fluid (calculated in step 3) times the volume leaked during retrieval.

This calculation method assumes that all the waste in the tank will be aggressively agitated to fully contact with the retrieval fluid during retrieval operations.

The balance of this Attachment will follow the format below:

B1.2.0 – Past Leaks

- List of CoC inventory from past leak data

B1.3.0 – C-104 Calculations

- Current chemical inventory of C-104
- Current radionuclide inventory of C-104
- Retrieval tank AY-101 supernate chemical inventory
- Retrieval tank AY-101 supernate radionuclide inventory
- CoC concentrations for final retrieval fluid
- CoC Inventory for C-104 residual heel case needs
- CoC Inventory for C-104 retrieval leak cases

B1.4.0 – Composite Supernate Development

- Reasons and method for developing a composite supernate
- Assumed chemical constituents of hypothetical composite supernate
- Assumed radionuclide constituents of hypothetical composite supernate

B1.5.0 – Remaining C-farm Tank Calculations

- Heel and leak loss inventory tables for CoCs

B1.6.0 – References

B1.2.0 PAST TANK LEAKS

Seven of the C farm tanks (C-101, C-110, C-111, C-201, C-202, C-203, and C-204) are classified as assumed leakers (HNF-EP-0182, Rev. 150). Best-estimate radiological and chemical inventories were developed for past tank leaks based on available process information regarding the type of waste that was stored in the tank or that was transferred at the time the leaks were believed to have occurred (LA-UR-00-4050). The tank waste releases were estimated based on location, timing, and leak volume information from HNF-EP-0182, Rev. 150. The leak compositions were defined using Hanford defined waste model waste streams (LA-UR-96-3860) and the supernate mixing model subroutine as a function of time (LA-UR-00-4050). Table B1.1 summarizes the past leak source term inventory estimates.

Table B1.1. Estimated Inventories for C Farm Tanks Past Leaks

CoCs	Units	Tank						
		241-C-101	241-C-110	241-C-111	241-C-201	241-C-202	241-C-203	241-C-204
Cr	kg	1.96E+02	8.10E+00	6.05E+00	9.27E-01	7.09E-01	7.61E-01	6.02E-01
Na	kg	8.97E+03	4.65E+02	1.26E+03	1.14E+02	8.61E+01	9.31E+01	7.38E+01
NO_2	kg	5.37E+03	1.55E+02	4.66E+02	8.84E+00	6.69E+00	7.22E+00	5.73E+00
NO_3	kg	6.29E+03	4.77E+02	1.36E+03	1.38E+02	1.05E+02	1.14E+02	9.01E+01
$U_{(TOTAL)}$	kg	1.41E+02	6.90E+00	1.13E+01	8.92E-03	6.77E-03	7.30E-03	5.77E-03
^{14}C	Ci	5.52E+00	7.27E-02	6.64E-03	8.04E-04	6.13E-04	6.62E-04	5.24E-04
^{79}Se	Ci	7.68E-01	4.94E-03	1.67E-02	3.53E-03	2.68E-03	2.90E-03	2.30E-03
^{99}Tc	Ci	3.86E+01	5.12E-01	4.66E-02	5.69E-03	4.30E-03	4.65E-03	3.69E-03
^{129}I	Ci	7.45E-02	9.92E-04	8.95E-05	1.10E-05	8.35E-06	9.01E-06	7.14E-06
^{233}U	Ci	7.18E-03	1.59E-02	6.31E-09	5.48E-12	4.16E-12	4.49E-12	3.57E-12
^{234}U	Ci	4.66E-02	2.73E-03	3.67E-03	2.98E-06	2.27E-06	2.45E-06	1.94E-06
^{235}U	Ci	1.98E-03	1.06E-04	1.58E-04	1.26E-07	9.55E-08	1.03E-07	8.19E-08
^{236}U	Ci	9.10E-04	1.22E-04	6.21E-05	6.96E-08	5.28E-08	5.70E-08	4.53E-08
^{238}U	Ci	4.72E-02	2.30E-03	3.76E-02	2.96E-06	2.25E-06	2.44E-06	1.93E-06

CoCs = contaminants of concern.

B1.3.0 TANK C-104 CALCULATIONS

The current plan is to retrieve waste from tank C-104 using supernate from tank AY-101. This retrieval is planned as a confined sluicing and robotic technologies waste retrieval demonstration (RPP-6843). Retrieval of tank C-104 is scheduled to occur in fiscal year 2008 (RPP-7087). Tank C-104 currently contains approximately 263,000 gal of sludge and no supernate (HNF-EP-0182, Rev. 150). Tank AY-101 currently contains about 94,000 gal of sludge (including interstitial liquid) and about 46,000 gal of supernate (HNF-EP-0182, Rev. 150). The current compositions of the sludge in tank C-104 and the supernate in tank AY-101 from the BBI data (BBI 2000) are shown in Tables B1.2 through B1.5.

The BBI is the best inventory available but there is still considerable uncertainty in tank specific values. This is primarily due to the impossibility of getting representative samples. Representative sampling requires essentially free access to the sampled body, in this case the tanks. Single-shell tanks have such restricted access, and contain such heterogeneous waste that representative sampling is not possible. The BBI was established to make the best of this difficult circumstance and provide the best possible inventory estimates based on sample data, historical performance, and an evaluative process.

A portion of the waste solids in tank C-104 will dissolve in the retrieval liquid and be transferred to tank AY-101, some will be retrieved as undissolved solids and transferred to tank AY-101, and a portion will remain in tank C-104 as a residual heel. Applying the best-basis wash factors to the components in tank C-104 provides an estimate of each component that will remain undissolved and how much will dissolve in the retrieval liquid. About 64% of the BBI inventory will remain as undissolved solids, so about 678,000 kg of solids will remain in tank C-104 or will be retrieved to tank AY-101. The amount of solids in the residual heels was calculated using a porosity of 58.5%. Therefore, the estimated amount of residual solids in the 2,700 gal of residual sludge in tank C-104 will be 12,723 kg and about 665,300 kg of solids will be removed as a slurry in the retrieval liquid and transferred to tank AY-101.

The HFFACO sets a goal of retrieving 89 kg (240 lb) of plutonium and 99% of the tank contents by volume. Removal of 99% of the original volume would leave a heel of 352 ft^3 (2,630 gal). This is basically the same as the common definition of 99% removal which leaves a heel of 360 ft^3 (2,700 gal), which would meet the goal of retrieving 89 kg (240 lb) of plutonium.

The amount of liquid that would be required for retrieval of 665,300 kg solids from tank C-104 would be greater than 1,000,000 gal based on the limitation of no greater than 10 wt% solids in solution transfers. This means that water will have to be added to tank AY-101 or tank C-104 in addition to the tank AY-101 supernate for retrieval of solids from tank C-104. However, a volume of more than 1,000,000 gal is not practical because that volume would exceed the capacity of tank AY-101. In actual practice, solids transferred out of tank C-104 will settle in tank AY-101 and the liquid will be recycled to tank C-104 to remove additional solids. Using this method, a smaller amount of liquid can be used without exceeding the 10 wt% limit in solution transferred between the tanks. Therefore, the maximum total amount of retrieval liquid would be the available 840,000-gal capacity of tank AY-101 (HNF-EP-0182, Rev. 150) plus the 46,000 gal of supernate now in tank AY-101 (HNF-EP-0182, Rev. 150) minus the solids

removed from tank C-104 (58,700 gal). This equates to a maximum total retrieval liquid volume of 735,300 gal. A value of 700,000 gal was used to calculate the concentrations of components in the retrieval liquid. The concentrations in the retrieval liquid is then the sum of the contributions from both tanks C-104 and AY-101 divided by the volume of approximately 700,000 gal.

Because retrieval will be a dynamic operation with several liquid additions and slurry transfers, it is difficult to predict a tank C-104 tank composition at the time of a potential leak.
The compositions of three potential leakage volumes are presented in Table B1.6.
The assumption made in Table B1.6 is that the liquid concentrations at the time of a leak are the same as the final concentrations in tank AY-101 after retrieval is completed.

Table B1.7 provides the calculated composition of the residual heel in tank C-104. Five residual heel calculations are presented: a 174 ft^3 (4,900 L [1,300 gal]) heel; a 360 ft^3 (10,000 L [2,700 gal]) heel; a 800 ft^3 (23,000 L [6,000 gal]) heel; a 3,600 ft^3 (100,000 L [27,000 gal]) heel; and a 6,700 ft^3 (190,000 L [50,000 gal]) heel. The values include both the solid heel and liquid heel after retrieval.

Table B1.2. Current Chemical Inventory in Tank C-104

Analyte	Inventory (kg)	Analyte	Inventory (kg)
Al	9.01E+04	NO_2	3.65E+04
Bi	4.17E+01	NO_3	1.96E+04
Ca	2.99E+03	OH	4.34E+05
Cl	8.00E+02	Pb	8.37E+02
Cr	1.46E+03	PO_4	3.21E+03
F	3.46E+04	Si	1.02E+04
Fe	2.79E+04	SO_4	3.42E+03
Hg	6.69E+01	Sr	8.74E+01
K	1.33E+03	TIC as CO_3	4.85E+04
La	4.87E+01	TOC	1.42E+04
Mn	7.01E+03	U_{TOTAL}	5.37E+04
Na	1.78E+05	Zr	6.49E+04
Ni	2.63E+03	TOTAL	1.04E+06

Source: BBI 2000.

Table B1.3. Current Radionuclide Inventory in Tank C-104

Analyte	Inventory (Ci)	Analyte	Inventory (Ci)
^{106}Ru	1.81E-04	^{236}U	6.80E-01
^{113}mCd	1.93E+01	^{237}Np	4.36E+00
^{125}Sb	1.76E+02	^{238}Pu	8.92E+02
^{126}Sn	1.72E+00	^{238}U	1.17E+01
^{129}I	7.49E-01	^{239}Pu	5.47E+03
^{134}Cs	4.50E-02	^{240}Pu	1.08E+03
^{137}Cs	9.55E+04	^{241}Am	6.34E+03
^{137}mBa	9.03E+04	^{241}Pu	1.48E+04
^{14}C	1.84E+00	^{242}Cm	1.19E+01
^{151}Sm	9.40E+03	^{242}Pu	4.87E-02
^{152}Eu	2.43E+00	^{243}Am	1.41E-02
^{154}Eu	1.10E+02	^{243}Cm	2.64E+00
^{155}Eu	8.00E+02	^{244}Cm	6.35E+01
^{226}Ra	6.27E-03	^{3}H	5.58E+01
^{227}Ac	1.09E+02	^{59}Ni	4.58E+00
^{228}Ra	2.26E+01	^{60}Co	2.72E+02
^{229}Th	9.41E-01	^{63}Ni	4.29E+02
^{231}Pa	2.39E+02	^{79}Se	6.37E+00
^{232}Th	2.35E-00	^{90}Sr	4.84E+05
^{232}U	2.00E+01	^{90}Y	4.84E+05
^{233}U	4.11E+02	^{93}mNb	9.90E+00
^{234}U	2.07E+01	^{93}Zr	1.17E+01
^{235}U	5.99E-01	^{99}Tc	2.48E+01
		TOTAL	1.20E+06

Source: BBI 2000.

Table B1.4. Current Chemical Inventory in Tank AY-101 Supernate

Analyte	Inventory (kg)	Analyte	Inventory (kg)
Al	2.11E-00	NO_2	6.14E+03
Bi	4.70E-00	NO_3	4.52E+03
Ca	3.43E+01	OH	4.06E+03
Cl	1.11E+02	Pb	4.55E-00
Cr	1.83E+01	PO_4	2.00E+02
F	3.03E+01	Si	2.09E-00
Fe	2.09E-00	SO_4	1.02E+03
Hg	0.00E+01	Sr	8.04E-03
K	7.43E+01	TIC as CO_3	5.99E+03
La	1.17E-01	TOC	8.32E+02
Mn	4.14E-01	U_{TOTAL}	5.29E+01
Na	9.03E+03	Zr	2.83E-01
Ni	1.03E+01	TOTAL	3.21E+04

Source: BBI 2000.

Table B1.5. Current Radionuclide Inventory in Tank AY-101 Supernate

Analyte	Inventory (Ci)	Analyte	Inventory (Ci)
^{106}Ru	3.54E-04	^{236}U	6.65E-04
^{113}mCd	4.29E-00	^{237}Np	2.00E-01
^{125}Sb	9.74E-00	^{238}Pu	2.12E-01
^{126}Sn	2.22E-01	^{238}U	1.77E-02
^{129}I	8.84E-04	^{239}Pu	1.90E-00
^{134}Cs	2.37E+01	^{240}Pu	5.75E-01
^{137}Cs	1.71E+04	^{241}Am	4.85E-00
^{137}mBa	1.62E+04	^{241}Pu	1.47E+01
^{14}C	5.22E-02	^{242}Cm	6.76E-03
^{151}Sm	5.18E+02	^{242}Pu	1.04E-04
^{152}Eu	2.76E-01	^{243}Am	4.95E-04
^{154}Eu	6.59E-00	^{243}Cm	7.90E-04
^{155}Eu	4.16E+01	^{244}Cm	2.99E-02
^{226}Ra	4.97E-06	^{3}H	1.94E-00
^{227}Ac	2.98E-05	^{59}Ni	7.80E-02
^{228}Ra	4.33E-03	^{60}Co	7.78E-00
^{229}Th	1.01E-04	^{63}Ni	7.71E-00
^{231}Pa	1.56E-04	^{79}Se	6.40E-02
^{232}Th	4.38E-04	^{90}Sr	3.29E+02
^{232}U	1.14E-02	^{90}Y	3.29E+02
^{233}U	4.36E-02	^{93}mNb	5.19E-01
^{234}U	1.94E-02	^{93}Zr	7.36E-01
^{235}U	7.86E-04	^{99}Tc	5.69E-00
		TOTAL	3.46E+04

Source: BBI 2000.

Table B1.6. Tank C-104 Inventories Leak Data

Constituent of Concern	Retrieval Leak Loss			
	4,000 gal	8,000 gal	40,000 gal	80,000 gal
Cr (kg)	8.9E-01	1.8E+00	8.9E+00	1.8E+01
Na (kg)	6.7E+02	1.3E+03	6.7E+03	1.3E+04
NO_2 (kg)	2.4E+02	4.9E+02	2.4E+03	4.9E+03
NO_3 (kg)	1.4E+02	2.8E+02	1.4E+03	2.8E+03
U_{TOTAL} (kg)	6.7E-01	1.3E+00	6.7E+00	1.3E+01
^{14}C (Ci)	1.0E-02	2.1E-02	1.0E-01	2.1E-01
^{60}Co (Ci)	1.1E-01	2.2E-01	1.1E+00	2.2E+00
^{63}Ni (Ci)	1.4E-01	2.9E-01	1.4E+00	2.9E+00
^{79}Se (Ci)	3.7E-02	7.4E-02	3.7E-01	7.4E-01
^{90}Sr (Ci)	9.1E+02	1.8E+03	9.1E+03	1.8E+04
^{90}Y (Ci)	9.1E+02	1.8E+03	9.1E+03	1.8E+04
^{99}Tc (Ci)	1.6E-01	3.2E-01	1.6E+00	3.2E+00
^{126}Sn (Ci)	3.0E-03	6.1E-03	3.0E-02	6.1E-02
^{129}I (Ci)	1.8E-03	3.6E-03	1.8E-02	3.6E-02
^{137}Cs (Ci)	4.0E+02	8.1E+02	4.0E+03	8.1E+03
^{137}mBa (Ci)	3.8E+02	7.6E+02	3.8E+03	7.6E+03
^{233}U (Ci)	3.1E-03	6.2E-03	3.1E-02	6.2E-02
^{234}U (Ci)	2.5E-04	5.1E-04	2.5E-03	5.1E-03
^{235}U (Ci)	8.6E-06	1.7E-05	8.6E-05	1.7E-04
^{236}U (Ci)	8.5E-06	1.7E-05	8.5E-05	1.7E-04
^{238}U (Ci)	1.8E-04	3.6E-04	1.8E-03	3.6E-03
^{238}Pu (Ci)	3.3E-03	6.6E-03	3.3E-02	6.6E-02
^{239}Pu (Ci)	2.4E-02	4.7E-02	2.4E-01	4.7E-01
^{240}Pu (Ci)	5.8E-03	1.2E-02	5.8E-02	1.2E-01
^{241}Pu (Ci)	1.2E-01	2.4E-01	1.2E+00	2.4E+00
^{242}Pu (Ci)	7.1E-07	1.4E-06	7.1E-06	1.4E-05
^{241}Am (Ci)	9.7E-02	1.9E-01	9.7E-01	1.9E+00
^{243}Am (Ci)	3.0E-06	6.0E-06	3.0E-05	6.0E-05
^{243}Cm (Ci)	2.6E-04	5.1E-04	2.6E-03	5.1E-03
^{244}Cm (Ci)	6.2E-03	1.2E-02	6.2E-02	1.2E-01

Table B1.7. Tank C-104 Inventories Heel Data

Constituents of Concern	Heel Volume				
	174 ft^3	360 ft^3	802 ft^3	3,600 ft^3	6,700 ft^3
Cr (kg)	1.1E+01	2.3E+01	5.1E+01	2.3E+02	4.3E+02
Na (kg)	6.2E+02	1.3E+03	3.3E+03	1.5E+04	2.7E+04
NO_2 (kg)	1.4E+01	2.8E+01	2.1E+02	9.6E+02	1.8E+03
NO_3 (kg)	7.7E+00	1.6E+01	1.2E+02	5.4E+02	1.0E+03
U_{TOTAL} (kg)	4.4E+02	9.2E+02	2.1E+03	9.2E+03	1.7E+04
^{14}C (Ci)	1.1E-03	2.3E-03	1.2E-02	5.3E-02	9.7E-02
^{60}Co (Ci)	2.2E+00	4.5E+00	1.0E+01	4.5E+01	8.4E+01
^{63}Ni (Ci)	3.4E+00	7.1E+00	1.6E+01	7.1E+01	1.3E+02
^{79}Se (Ci)	2.0E-03	4.2E-03	3.2E-03	1.5E-01	2.7E-01
^{90}Sr (Ci)	2.7E+03	5.7E+03	1.3E+04	6.0E+04	1.1E+05
^{90}Y (Ci)	2.7E+03	5.7E+03	1.3E+04	6.0E+04	1.1E+05
^{99}Tc (Ci)	2.7E-02	5.5E-02	2.2E-01	1.0E+00	1.9E+00
^{126}Sn (Ci)	1.2E-02	2.5E-02	5.7E-02	2.5E-01	4.7E-01
^{129}I (Ci)	3.7E-03	7.6E-03	1.8E-02	8.1E-02	1.5E-01
^{137}Cs (Ci)	3.7E+02	7.7E+02	2.0E+03	8.8E+03	1.6E+04
^{137}mBa (Ci)	3.5E+02	7.3E+02	1.9E+03	8.3E+03	1.5E+04
^{233}U (Ci)	3.4E+00	7.1E+00	1.6E+01	7.1E+01	1.3E+02
^{234}U (Ci)	1.7E-01	3.6E-01	7.9E-01	3.6E+00	6.6E+00
^{235}U (Ci)	5.0E-03	1.0E-02	2.3E-02	1.0E-01	1.9E-01
^{236}U (Ci)	5.6E-03	1.2E-02	2.6E-02	1.2E-01	2.2E-01
^{238}U (Ci)	9.7E-02	2.0E-01	4.5E-01	2.0E+00	3.7E+00
^{238}Pu (Ci)	7.4E+00	1.5E+01	3.4E+01	1.5E+02	2.8E+02
^{239}Pu (Ci)	4.5E+01	9.4E+01	2.1E+02	9.4E+02	1.7E+03
^{240}Pu (Ci)	8.9E+00	1.9E+01	4.1E+01	1.9E+02	3.4E+02
^{241}Pu (Ci)	1.2E+02	2.5E+02	5.7E+02	2.5E+03	4.7E+03
^{242}Pu (Ci)	4.0E-04	8.4E-04	1.9E-03	8.4E-03	1.6E-02
^{241}Am (Ci)	5.2E+01	1.1E+02	2.4E+02	1.1E+03	2.0E+03
^{243}Am (Ci)	1.2E-04	2.4E-04	5.4E-04	2.4E-03	4.5E-03
^{243}Cm (Ci)	2.2E-02	4.5E-02	9.9E-02	4.5E-01	8.3E-01
^{244}Cm (Ci)	5.2E-01	1.1E+00	2.4E+00	1.1E+01	2.0E+01

B1.4.0 COMPOSITE SUPERNATE DEVELOPMENT

To prevent generation of new volumes of liquid waste it was decided to calculate retrieval using existing supernate. Consequently, calculations of leakage during retrieval of the C farm tanks are based on using available DST supernate. A spreadsheet of Hanford Tank Waste Operation Simulator model projections of DST compositions during the time when C tank farm waste retrieval is planned was supplied by CH2M HILL Hanford Group, Inc.

Because there are no specific plans for which DST supernate will be used to retrieve C farm tanks (except for tank C-104), a DST supernate composite was calculated as an enabling assumption.

An average DST supernate composition used in the calculations was determined as follows.

1. All tanks on the spreadsheet with a sodium concentration greater than 4.1 Molar and less than 2.5 Molar were eliminated. This provides a mid-range average for sodium concentration.

2. Tanks SY-102 and SY-103 were eliminated because they are in the 200 West Area.

3. Values obviously much larger or smaller than other values for that component in the tank were eliminated.

4. No zero values were used.

5. Concentrations of the contaminants of concern were verified to be similar for all the tanks used in the average.

The values in the spreadsheet supplied were predicted quantities of each component.
These values were then converted to a concentration by dividing by the volume. Tables B1.8 and B1.9 provide the composition of the average DST supernate to be used in the calculations for retrieval liquid compositions during retrieval of the C farm tanks.

Table B1.8. Concentrations of Chemicals in Average Double-Shell Tank Supernate for C Farm Retrieval

Component	Concentration (g/L)	Component	Concentration (g/L)
Ag	5.1E-07	Mg	2.1E-06
Al	6.9E+00	Mn	2.1E-03
As	4.6E-07	Na	8.3E+01
Ba	7.0E-05	*Na Molarity (moles/L)*	*3.6*
Bi	7.3E-03	NH_3	3.2E-01
Ca	2.4E-02	Ni	1.6E-02
Cd	7.7E-06	NO_2	1.9E+01
Ce	2.3E-04	NO_3	8.8E+01
Cl	1.3E+00	OH Bound	2.8E+00
TIC as CO_3	2.6E+01	OH	4.4E+00
Cr	6.5E-01	Pb	8.3E-03
Cs	1.7E-03	PO_4	5.2E+00
Cu	4.9E-07	Si	5.3E-01
F	1.8E+00	SO_4	6.2E+00
Fe	3.4E-02	Sr	5.0E-03
H_2O	9.2E+02	TOC	9.8E-01
Hg	2.5E-04	U_{TOTAL}	9.0E-05
K	1.0E+00	V	6.2E-06
La	1.6E-04	Zr	2.4E-02
Li	1.3E-06		

Table B1.9. Concentrations of Radionuclides in Average Double-Shell Tank Supernate for C Farm Retrieval

Component	Concentration (g/L)	Component	Concentration (g/L)
^{106}Ru	3.8E-10	^{236}U	8.4E-10
^{113}mCd	6.5E-06	^{237}Np	5.2E-08
^{125}Sb	1.6E-05	^{238}Pu	3.9E-08
^{126}Sn	2.5E-07	^{238}U	2.7E-08
^{129}I	9.4E-08	^{239}Pu	1.4E-06
^{134}Cs	2.4E-06	^{240}Pu	2.3E-07
^{137}Cs	5.4E-02	^{241}Am	2.8E-06
^{137}mBa	5.3E-02	^{241}Pu	2.7E-06
^{14}C	7.5E-06	^{242}Cm	2.7E-08
^{151}Sm	4.0E-04	^{242}Pu	1.4E-11
^{152}Eu	2.4E-07	^{243}Am	3.3E-10
^{154}Eu	1.8E-05	^{243}Cm	2.6E-09
^{155}Eu	1.5E-05	^{244}Cm	3.0E-08
^{226}Ra	1.5E-11	^{3}H	4.6E-05
^{227}Ac	3.5E-11	^{59}Ni	1.4E-07
^{228}Ra	3.0E-08	^{60}Co	2.1E-06
^{229}Th	3.4E-10	^{63}Ni	1.4E-05
^{231}Pa	6.5E-10	^{79}Se	1.4E-06
^{232}Th	1.1E-09	^{90}Sr	1.3E-02
^{232}U	1.6E-08	^{90}Y	1.4E-02
^{233}U	6.2E-08	^{93}mNb	1.8E-06
^{234}U	2.7E-08	^{93}Zr	1.4E-06
^{235}U	1.1E-09	^{99}Tc	5.3E-05

B1.5.0 REMAINING C FARM TANK CALCULATIONS

The methodology for the inventory calculations for the rest of the C farm tanks was similar to the method used for tank C-104, with two principal differences.

1. An average supernate was used as the retrieval liquid. (The determination of the composition of this average supernate is described below.)

2. The amount of retrieval liquid used was based on not exceeding the limitation of 10 wt% solids in the solution transferred out of the tank. No limitation was placed on the retrieval liquid volume.

Because no wash factors were available with which to estimate the soluble components in the supernate retrieval medium, the wash factors associated with water as the retrieval medium were used. Tank-specific water wash factors have been developed for each component in the waste and are documented in the *Best-Basis Wash and Leach Factor Analysis* (HNF-3157). The wash factors were derived from a variety of sources, including analytical data, large-scale sludge washing experiments, thermodynamic solubility models, comparison of similar wastes, and the use of chemical analogs for certain chemicals and for most radionuclides.

This method for determining residual waste inventories was chosen because it relies on the same data currently being used in the Hanford Tank Waste Operation Simulator model to simulate all of the tank farm retrieval operations. The Hanford Tank Waste Operation Simulator model is not only being used to model various retrieval scenarios, but to estimate the volume and composition of waste derived from each tank and the amount of high-level and low-activity waste glass produced from each batch of tank waste.

Residual sludge heels were assumed to be physically similar to the dry heels left in the 200-series tanks, with a similar porosity. The average calculated heel porosity for the 200-series tanks is 58.5%, meaning that the final heel will be 58.5% interstitial liquid and 41.5% washed solids. The 58.5% volume was calculated to be filled with retrieval liquid, contributing the final retrieval liquid concentrations of chemical and radionuclide constituents for the estimated volume.

This method provides the basis for calculating the residual solids volume fraction and residual liquid volume fraction for each of the 100- and 200-series tanks. The results of the calculations are in Tables B1.10 through B1.13.

It is unlikely that tanks already designated as leakers or suspected leakers will be retrieved with supernate. Table B1.14 lists tank heel estimates assuming retrieval of tanks C-101, C-110, C-111, C-201, C-202, C-203, and C-204 using water as the retrieval fluid rather than supernate.

Table B1.10. C Farm Tank Best-Basis Inventories (2 Sheets)

Analyte	C-101	C-102	C-103	C-105	C-106	C-107	C-108	C-109	C-110	C-111	C-112	C-201	C-202	C-203	C-204
Cr (kg)	3.3E+02	8.8E+02	3.7E+02	6.1E+02	5.5E+01	9.3E+02	9.4E+01	7.2E+01	4.6E+02	3.2E+01	1.9E+02	4.4E-00	2.3E-00	7.9E-00	3.3E-00
Na (kg)	4.5E+04	1.4E+05	3.0E+04	4.7E+04	2.8E+03	8.0E+04	3.3E+04	2.5E+04	8.1E+04	7.6E+03	7.7E+04	8.8E+02	4.6E+02	1.6E+03	6.7E+02
NO_2 (kg)	5.3E+03	2.2E+04	1.1E+04	5.1E+03	1.4E+02	2.1E+04	8.7E+03	1.2E+04	6.7E+03	5.3E+03	3.6E+04	8.0E+01	2.0E+02	5.9E+01	2.5E+01
NO_3 (kg)	3.7E+04	6.7E+04	1.5E+03	6.8E+03	8.4E+00	5.2E+04	1.6E+04	1.2E+04	1.1E+05	1.1E+04	4.8E+04	4.3E+02	6.1E+02	2.2E+03	8.2E+02
U_{TOTAL} (kg)	5.1E+03	1.6E+04	2.1E+03	6.4E+03	1.6E+01	3.9E+03	1.5E+02	3.7E+03	2.1E+03	4.2E+03	3.6E+04	2.2E+00	1.1E+00	3.9E+00	1.6E+00
^{14}C (Ci)	2.8E-01	2.1E-01	2.0E-01	5.9E-01	2.0E-03	6.0E-01	6.8E-02	5.7E-03	3.1E-01	3.2E-02	2.7E+00	1.1E-02	1.1E-03	4.2E-02	2.2E-02
^{60}Co (Ci)	9.9E+01	6.1E+02	1.3E+03	1.9E+02	1.2E-03	7.5E+02	1.5E-02	3.3E-02	8.6E-03	9.1E-03	4.6E-02	1.4E-03	1.2E-03	1.9E-03	1.5E-03
^{63}Ni (Ci)	1.6E+00	4.0E+00	1.1E+03	2.0E+00	5.5E-02	4.6E+03	4.8E+01	4.7E+02	1.5E+00	2.0E+01	9.1E+02	4.2E+01	4.2E+01	4.2E+01	4.2E+01
^{79}Se (Ci)	1.3E-02	4.4E-02	5.3E+00	1.6E-02	4.3E-04	2.6E+01	1.4E-02	5.8E-02	1.8E+00	6.6E-03	2.4E-01	5.2E-03	4.9E-03	6.0E-03	5.5E-03
^{90}Sr (Ci)	2.7E+05	1.8E+05	1.9E+06	4.7E+05	2.5E+05	1.7E+06	9.5E+03	2.2E+05	4.6E+03	1.2E+06	1.3E+06	9.3E+02	1.5E+04	9.3E+03	7.1E+02
^{90}Y (Ci)	2.7E+05	1.8E+05	1.9E+06	4.7E+05	2.5E+05	1.7E+06	9.5E+03	2.2E+05	4.6E+03	1.2E+06	1.3E+06	9.3E+02	1.5E+04	9.3E+03	7.1E+02
^{99}Tc (Ci)	4.0E+01	1.2E+00	2.0E+02	6.5E+01	1.4E-02	1.1E+02	4.7E-01	3.1E+01	3.2E+01	2.2E-01	8.0E+01	1.7E-02	8.0E-03	4.3E-02	2.6E-02
^{126}Sn (Ci)	2.0E-02	6.2E-02	8.6E+00	2.5E-02	6.6E-04	4.1E+01	2.2E-02	9.0E-02	1.9E-02	1.0E-02	6.6E-02	8.3E-03	7.9E-03	9.5E-03	8.7E-03
^{129}I (Ci)	4.5E-02	2.6E-03	1.4E-02	6.5E-02	2.7E-05	7.8E-03	8.9E-04	1.5E-03	7.9E-04	4.1E-04	2.4E-03	3.2E-05	1.5E-05	8.1E-05	4.8E-05
^{137}Cs (Ci)	4.2E+04	6.3E+04	6.2E+04	8.1E+04	1.1E+04	3.1E+04	9.1E+04	2.4E+05	1.8E+04	1.2E+04	2.5E+05	1.8E+02	9.2E+01	3.2E+02	1.3E+02
^{137}mBa (Ci)	4.0E+04	5.9E+04	5.9E+04	7.7E+04	1.0E+04	2.9E+04	8.6E+04	2.2E+05	1.7E+04	1.2E+04	2.3E+05	1.7E+02	8.7E+01	3.0E+02	1.3E+02
^{233}U (Ci)	4.2E-01	3.4E+00	2.4E-01	3.7E-06	9.2E-09	1.3E-01	3.5E-08	8.8E-07	4.9E-07	1.3E-06	9.0E-01	5.1E-10	7.0E-10	9.1E-10	3.8E-10
^{234}U (Ci)	1.7E+00	5.4E+00	6.8E-01	2.1E+00	5.2E-03	1.3E+00	4.9E-02	1.2E+00	6.9E-01	1.4E+00	1.2E+01	7.1E-04	3.8E-04	1.3E-03	5.4E-04
^{235}U (Ci)	7.4E-02	2.3E-01	2.9E-02	8.9E-02	2.2E-04	5.7E-02	2.2E-03	5.5E-02	3.1E-02	6.2E-02	5.3E-01	3.2E-05	1.6E-05	5.8E-05	2.4E-05
^{236}U (Ci)	3.0E-02	1.5E-01	1.2E-02	3.6E-02	9.0E-05	1.2E-02	3.1E-04	7.9E-03	4.4E-03	1.2E-02	1.5E-01	4.6E-06	8.8E-06	8.2E-06	3.5E-06
^{238}U (Ci)	1.7E+00	5.2E+00	6.9E-01	2.1E+00	5.4E-03	1.3E+00	4.9E-02	1.2E+00	7.0E-01	1.4E+00	1.2E+01	7.2E-04	3.8E-04	1.3E-03	5.5E-04
^{238}Pu (Ci)	1.7E+01	1.7E+02	7.7E+01	7.5E+00	6.2E-01	3.8E+01	1.2E-02	2.2E+00	2.4E-01	3.2E+00	5.5E+00	2.8E+00	7.6E-01	5.8E-01	6.9E-03
^{239}Pu (Ci)	8.1E+02	5.9E+03	4.7E+03	4.8E+02	4.0E+01	1.2E+03	3.1E+00	9.2E+01	7.4E+01	2.1E+02	6.0E+01	1.2E+02	3.2E+01	2.5E+01	2.9E-01

Table B1.10. C Farm Tank Best-Basis Inventories (2 Sheets)

Analyte	C-101	C-102	C-103	C-105	C-106	C-107	C-108	C-109	C-110	C-111	C-112	C-201	C-202	C-203	C-204
^{240}Pu (Ci)	1.4E+02	1.1E+03	7.2E+02	7.3E+01	6.1E+00	2.1E+02	2.0E-01	1.5E+01	4.3E+00	3.2E+01	9.5E+00	1.9E+01	5.3E+00	4.1E+00	4.8E-02
^{241}Pu (Ci)	1.3E+03	1.3E+04	5.6E+03	5.5E+02	4.5E+01	2.8E+03	2.6E-01	1.6E+02	2.8E+00	2.3E+02	8.3E+01	2.0E+02	5.5E+01	4.2E+01	5.0E-01
^{242}Pu (Ci)	4.0E-03	5.0E-02	2.3E-02	2.1E-03	1.7E-04	1.5E-02	1.1E-06	7.7E-04	8.5E-06	8.9E-04	3.0E-04	9.9E-04	2.7E-04	2.1E-04	2.5E-06
^{241}Am (Ci)	4.9E+02	1.5E+03	9.1E+02	9.8E+02	1.8E+01	1.6E+03	1.2E-01	4.5E+01	2.1E-02	1.2E-01	2.2E+02	4.0E+01	1.1E+01	8.3E+00	9.9E-02
^{243}Am (Ci)	4.3E-03	1.4E-01	2.1E-02	9.2E-03	1.8E-04	8.4E-02	7.9E-07	1.1E-03	6.0E-08	9.6E-07	5.0E-03	9.6E-04	2.6E-04	2.0E-04	2.4E-06
^{243}Cm (Ci)	2.0E-01	2.7E+00	7.5E-02	2.6E-01	5.2E-03	1.2E-01	5.1E-05	4.0E-03	3.6E-07	3.8E-05	3.6E-02	3.5E-03	9.6E-04	7.3E-04	8.7E-06
^{244}Cm (Ci)	1.6E-01	5.9E+01	5.2E-01	4.4E-01	9.0E-03	4.9E+00	1.9E-05	1.9E-03	9.1E-07	3.8E-05	8.7E-01	1.7E-03	4.7E-04	3.6E-04	4.2E-06

Source: BBI 2000.

Table B1.11. C Farm Tank Post-Retrieval Heel Inventories (360 ft^3 for 100-Series Tanks, 30 ft^3 for 200-Series Tanks) (2 Sheets)

Analyte	C-101	C-102	C-103	C-105	C-106	C-107	C-108	C-109	C-110	C-111	C-112	C-201	C-202	C-203	C-204
Cr (kg)	2.0E+01	1.3E+01	2.1E+01	1.5E+01	2.2E+01	1.9E+01	4.2E-00	2.6E-00	1.9E+01	2.1E-00	4.8E-00	8.1E-02	8.1E-02	7.8E-02	7.6E-02
Na (kg)	1.0E+03	7.5E+02	1.5E+03	1.2E+03	3.9E+03	2.0E+03	1.7E+03	6.8E+02	1.5E+03	1.8E+02	1.0E+03	1.1E+01	1.1E+01	1.0E+01	1.0E+01
NO_2 (kg)	3.2E+01	3.1E+01	2.9E+01	2.9E+01	1.0E+01	3.4E+01	4.1E+01	5.6E+01	7.1E+01	3.2E+01	8.3E+01	2.3E+00	2.8E+00	2.2E+00	2.2E+00
NO_3 (kg)	1.6E+02	1.3E+02	9.5E+01	1.2E+02	1.2E+00	1.2E+03	1.4E+02	1.6E+02	1.0E+03	2.1E+02	2.4E+02	1.1E+01	1.2E+01	1.1E+01	1.1E+01
U_{TOTAL} (kg)	4.6E+02	3.3E+02	6.9E+01	2.7E+02	3.9E+01	9.1E+01	1.7E+01	3.7E+02	1.6E+02	3.3E+02	2.2E+03	2.7E-01	2.8E-01	2.0E-01	1.2E-01
^{14}C (Ci)	1.1E-02	9.8E-03	8.4E-03	8.6E-04	2.2E-02	1.9E-02	1.0E-02	9.8E-03	9.8E-03	1.0E-02	1.5E-02	8.6E-04	8.4E-04	8.7E-04	8.6E-04
^{60}Co (Ci)	8.8E+00	1.3E+01	7.1E+01	7.9E+00	3.0E-01	2.3E+01	4.7E-03	6.0E-03	3.2E-03	3.6E-03	5.1E-03	4.3E-04	5.3E-04	3.3E-04	3.5E-04
^{63}Ni (Ci)	1.6E-01	1.0E-01	5.8E+01	9.0E-02	1.4E+01	1.4E+02	6.2E+00	4.7E+01	1.4E-01	1.6E+00	5.3E+01	5.8E+00	1.0E+01	2.1E+00	3.0E+00
^{79}Se (Ci)	1.9E-03	1.8E-03	5.6E-03	1.9E-06	3.2E-02	2.1E-02	1.9E-03	2.3E-03	3.7E-03	1.9E-03	2.9E-03	1.7E-04	1.7E-04	1.6E-04	1.6E-04
^{90}Sr (Ci)	2.4E+04	3.8E+03	1.0E+05	2.1E+04	9.4E+04	5.1E+04	1.2E+03	2.2E+04	3.7E+02	8.7E+04	7.7E+04	6.7E+01	1.8E+03	2.4E+02	2.8E+01
^{90}Y (Ci)	2.4E+04	3.8E+03	1.0E+05	2.1E+04	9.4E+04	5.1E+04	1.2E+03	2.2E+04	3.7E+02	8.7E+04	7.7E+04	6.7E+01	1.8E+03	2.4E+02	2.8E+01
^{99}Tc (Ci)	4.3E-01	7.1E-02	2.1E-01	1.0E+00	8.1E+00	1.4E+00	7.1E-02	9.0E-01	3.0E-01	7.1E-02	1.4E+00	6.0E-03	6.0E-03	6.0E-03	6.0E-03
^{126}Sn (Ci)	2.0E-03	1.5E-03	4.8E-01	8.3E-04	3.0E-01	1.2E+00	3.0E-03	9.3E-03	1.7E-03	1.1E-03	4.4E-03	1.2E-03	2.0E-03	5.1E-04	6.6E-04
^{129}I (Ci)	2.5E-03	1.5E-04	1.1E-04	1.7E-07	5.3E-03	1.3E-04	1.3E-04	1.7E-04	1.1E-04	1.3E-04	1.7E-04	1.1E-05	1.1E-05	1.1E-05	1.1E-05
^{137}Cs (Ci)	1.1E+03	4.2E+02	2.9E+03	3.3E+03	5.6E+03	6.7E+02	1.1E+04	2.4E+04	7.0E+02	8.6E+01	1.3E+04	1.7E+01	6.4E+00	6.3E+00	6.2E+00
^{137}mBa (Ci)	1.0E+03	4.0E+02	2.7E+03	3.1E+03	5.3E+03	6.3E+02	1.1E+04	2.2E+04	6.6E+02	8.4E+01	1.2E+04	1.6E+01	6.3E+00	6.2E+00	6.1E+00
^{233}U (Ci)	3.8E-02	7.2E-02	8.0E-03	2.4E-07	1.4E-02	3.1E-03	8.2E-05	8.1E-05	7.4E-05	8.3E-05	5.3E-02	6.9E-06	6.9E-06	6.9E-06	6.9E-06
^{234}U (Ci)	1.5E-01	1.2E-01	2.3E-02	8.7E-02	1.3E-02	3.0E-02	5.6E-03	1.2E-01	5.2E-02	1.1E-01	7.1E-01	9.3E-05	9.6E-05	6.8E-05	4.2E-05
^{235}U (Ci)	6.7E-03	4.8E-03	9.7E-04	3.7E-03	5.5E-04	1.3E-03	2.5E-04	5.5E-03	2.4E-03	4.9E-03	3.1E-02	4.2E-06	4.0E-06	3.0E-06	1.9E-06
^{236}U (Ci)	2.7E-03	3.2E-03	4.2E-04	1.5E-03	3.5E-04	2.9E-04	3.7E-05	7.9E-04	3.4E-04	9.7E-04	8.8E-03	6.7E-07	2.3E-06	5.1E-07	3.5E-07
^{238}U (Ci)	1.5E-01	1.1E-01	2.3E-02	9.0E-02	1.3E-02	3.0E-02	5.7E-03	1.2E-01	5.3E-02	1.1E-01	7.2E-01	9.4E-05	9.5E-05	6.9E-05	4.3E-05
^{238}Pu (Ci)	1.5E+00	3.6E+00	4.3E+00	3.3E-01	2.3E-01	1.2E+00	1.6E-03	2.1E-01	1.8E-02	2.5E-01	3.3E-01	3.9E-01	1.9E-01	2.9E-02	5.0E-04
^{239}Pu (Ci)	7.3E+01	1.3E+02	2.6E+02	2.1E+01	1.5E+01	3.5E+01	3.9E-01	9.1E+00	5.6E+00	1.6E+01	3.6E+00	1.6E+01	7.9E+00	1.2E+00	2.1E-02

Table B1.11. C Farm Tank Post-Retrieval Heel Inventories (360 ft^3 for 100-Series Tanks, 30 ft^3 for 200-Series Tanks) (2 Sheets)

Analyte	C-101	C-102	C-103	C-105	C-106	C-107	C-108	C-109	C-110	C-111	C-112	C-201	C-202	C-203	C-204
^{240}Pu (Ci)	1.2E+01	2.3E+01	4.0E+01	3.2E+00	2.2E+00	6.4E+00	2.5E-02	1.5E+00	3.3E-01	2.5E+00	5.8E-01	2.7E+00	1.3E+00	2.0E-01	3.5E-03
^{241}Pu (Ci)	1.2E+02	2.8E+02	3.1E+02	2.4E+01	1.7E+01	8.4E+01	3.6E-02	1.5E+01	2.1E-01	1.8E+01	5.0E+00	2.8E+01	1.4E+01	2.1E+00	3.6E-02
^{242}Pu (Ci)	3.6E-04	1.1E-03	1.3E-03	9.2E-05	6.6E-05	4.4E-04	1.5E-07	7.6E-05	6.6E-07	7.0E-05	1.8E-05	1.4E-04	6.6E-05	1.0E-05	1.8E-07
^{241}Am (Ci)	4.3E+01	3.0E+01	5.0E+01	1.1E+01	9.6E+00	3.8E+01	1.7E-02	4.5E+00	5.0E-03	1.3E-02	1.3E+01	5.6E+00	2.7E+00	4.2E-01	7.5E-03
^{243}Am (Ci)	3.7E-04	2.8E-03	1.2E-03	1.0E-04	1.3E-04	2.0E-03	5.3E-07	1.1E-04	4.0E-07	5.2E-07	3.1E-04	1.3E-04	6.4E-05	1.0E-05	2.1E-07
^{243}Cm (Ci)	1.8E-02	5.6E-02	4.2E-03	1.2E-02	2.2E-03	3.7E-03	9.8E-06	4.1E-04	3.2E-06	6.4E-06	2.1E-03	3.1E-04	3.6E-06	8.1E-07	3.0E-07
^{244}Cm (Ci)	1.4E-02	1.2E+00	2.9E-02	2.0E-02	1.4E-02	1.5E-01	4.2E-05	2.3E-04	3.6E-05	4.3E-05	5.1E-02	1.5E-04	4.9E-06	3.6E-06	3.3E-06

Table B1.12. C Farm Tank Post-Retrieval Heel Inventories (802 ft^3 for 100-Series Tanks, 80 ft^3 for 200-Series Tanks) (2 Sheets)

Analyte	C-101	C-102	C-103	C-105	C-106	C-107	C-108	C-109	C-110	C-111	C-112	C-201	C-202	C-203	C-204
Cr (kg)	5.2E+01	3.5E+01	5.2E+01	4.1E+01	5.0E+01	5.0E+01	1.7E+01	1.3E+01	4.9E+01	1.1E+01	1.8E+01	6.3E-01	6.3E-01	6.1E-01	5.9E-01
Na (kg)	3.5E+03	2.7E+03	4.1E+03	3.6E+03	8.8E+03	5.4E+03	5.0E+03	2.6E+03	4.7E+03	1.3E+03	3.5E+03	8.6E+01	8.5E+01	8.2E+01	7.8E+01
NO_2 (kg)	3.2E+02	3.1E+02	2.8E+02	2.8E+02	4.8E+01	3.3E+02	4.0E+02	4.4E+02	3.8E+02	3.1E+02	6.1E+02	1.8E+01	2.2E+01	1.7E+01	1.7E+01
NO_3 (kg)	1.6E+03	1.3E+03	9.3E+02	1.2E+03	4.4E+00	3.6E+03	1.4E+03	1.4E+03	3.9E+03	1.4E+03	1.7E+03	8.3E+01	9.3E+01	8.9E+01	8.3E+01
U_{TOTAL} (kg)	1.0E+03	7.3E+02	1.6E+02	6.0E+02	8.8E+01	2.0E+02	3.8E+01	8.3E+02	3.5E+02	7.4E+02	4.8E+03	4.9E-01	4.9E-01	3.5E-01	2.1E-01
^{14}C (Ci)	1.0E-01	9.5E-02	8.0E-02	2.0E-03	4.9E-02	1.2E-01	9.8E-02	9.6E-02	9.2E-02	9.8E-02	1.3E-01	6.7E-03	6.6E-03	6.8E-03	6.7E-03
^{60}Co (Ci)	2.0E+01	2.8E+01	1.6E+02	1.8E+01	6.7E-01	5.2E+01	3.2E-02	3.5E-02	2.6E-02	3.0E-02	3.3E-02	2.2E-03	2.4E-03	2.0E-03	2.1E-03
^{63}Ni (Ci)	5.0E-01	3.6E-01	1.3E+02	2.0E-01	3.1E+01	3.1E+02	1.4E+01	1.0E+02	4.3E-01	3.7E+00	1.2E+02	1.0E+01	1.8E+01	3.7E+00	5.4E+00
^{79}Se (Ci)	1.9E-02	1.8E-02	5.5E-02	1.8E-05	7.2E-02	1.4E-01	1.8E-02	2.0E-02	3.6E-02	1.8E-02	2.2E-02	1.3E-03	1.4E-03	1.3E-03	1.3E-03
^{90}Sr (Ci)	5.4E+04	8.6E+03	2.3E+05	4.6E+04	2.1E+05	1.1E+05	2.9E+03	5.0E+04	9.4E+02	1.9E+05	1.7E+05	1.3E+02	3.4E+03	4.5E+02	6.0E+01
^{90}Y (Ci)	5.4E+04	8.6E+03	2.3E+05	4.6E+04	2.1E+05	1.1E+05	2.9E+03	5.0E+04	9.5E+02	1.9E+05	1.7E+05	1.3E+02	3.4E+03	4.5E+02	6.0E+01
^{99}Tc (Ci)	1.9E+00	6.8E-01	2.1E+00	2.3E+00	1.8E+01	3.8E+00	7.0E-01	2.8E+00	1.4E+00	7.0E-01	4.0E+00	4.7E-02	4.7E-02	4.7E-02	4.7E-02
^{126}Sn (Ci)	7.0E-03	5.8E-03	1.1E+00	1.8E-03	6.7E-01	2.7E+00	9.1E-03	2.3E-02	6.1E-03	5.0E-03	1.2E-02	2.3E-03	3.6E-03	1.1E-03	1.3E-03
^{129}I (Ci)	6.8E-03	1.3E-03	1.1E-03	1.6E-06	1.2E-02	1.2E-03	1.2E-03	1.3E-03	1.1E-03	1.2E-03	1.3E-03	8.3E-05	8.3E-05	8.3E-05	8.3E-05
^{137}Cs (Ci)	3.2E+03	1.6E+03	6.9E+03	7.3E+03	1.2E+04	2.1E+03	2.6E+04	5.3E+04	2.1E+03	8.4E+02	2.9E+04	6.8E+01	5.0E+01	4.9E+01	4.9E+01
^{137}mBa (Ci)	3.1E+03	1.5E+03	6.5E+03	6.9E+03	1.2E+04	2.0E+03	2.4E+04	5.0E+04	2.0E+03	8.2E+02	2.7E+04	6.6E+01	4.9E+01	4.8E+01	4.8E+01
^{233}U (Ci)	8.5E-02	1.6E-01	1.9E-02	1.1E-06	3.2E-02	7.6E-03	8.1E-04	8.0E-04	7.2E-04	8.1E-04	1.2E-01	5.4E-05	5.4E-05	5.4E-05	5.4E-05
^{234}U (Ci)	3.4E-01	2.6E-01	5.2E-02	1.9E-01	3.0E-02	6.8E-02	1.3E-02	2.7E-01	1.2E-01	2.4E-01	1.6E+00	1.8E-04	1.9E-04	1.4E-04	9.3E-05
^{235}U (Ci)	1.5E-02	1.1E-02	2.2E-03	8.3E-03	1.2E-03	3.0E-03	5.8E-04	1.2E-02	5.3E-03	1.1E-02	6.9E-02	8.2E-06	7.9E-06	6.2E-06	4.1E-06
^{236}U (Ci)	6.0E-03	7.2E-03	9.6E-04	3.4E-03	7.7E-04	6.6E-04	9.1E-05	1.8E-03	7.6E-04	2.2E-03	2.0E-02	1.8E-06	4.6E-06	1.5E-06	1.2E-06
^{238}U (Ci)	3.4E-01	2.4E-01	5.3E-02	2.0E-01	2.9E-02	6.9E-02	1.3E-02	2.8E-01	1.2E-01	2.5E-01	1.6E+00	1.9E-04	1.9E-04	1.4E-04	9.4E-05
^{238}Pu (Ci)	3.3E+00	8.1E+00	9.6E+00	7.4E-01	5.2E-01	2.6E+00	3.9E-03	4.8E-01	4.0E-02	5.6E-01	7.4E-01	6.9E-01	3.3E-01	5.2E-02	9.2E-04
^{239}Pu (Ci)	1.6E+02	2.8E+02	5.8E+02	4.7E+01	3.3E+01	7.8E+01	8.7E-01	2.0E+01	1.2E+01	3.7E+01	8.1E+00	2.9E+01	1.4E+01	2.2E+00	3.9E-02

Table B1.12. C Farm Tank Post-Retrieval Heel Inventories (802 ft^3 for 100-Series Tanks, 80 ft^3 for 200-Series Tanks) (2 Sheets)

Analyte	C-101	C-102	C-103	C-105	C-106	C-107	C-108	C-109	C-110	C-111	C-112	C-201	C-202	C-203	C-204
^{240}Pu (Ci)	2.7E+01	5.1E+01	9.0E+01	7.2E+00	5.0E+00	1.4E+01	5.8E-02	3.3E+00	7.4E-01	5.5E+00	1.3E+00	4.8E+00	2.3E+00	3.6E-01	6.3E-03
^{241}Pu (Ci)	2.6E+02	6.2E+02	7.0E+02	5.4E+01	3.8E+01	1.9E+02	1.1E-01	3.4E+01	5.0E-01	4.1E+01	1.1E+01	5.0E+01	2.4E+01	3.7E+00	6.6E-02
^{242}Pu (Ci)	8.1E-04	2.4E-03	2.8E-03	2.1E-04	1.5E-04	9.8E-04	4.7E-07	1.7E-04	1.6E-06	1.6E-04	4.1E-05	2.4E-04	1.2E-04	1.8E-05	3.3E-07
^{241}Am (Ci)	9.5E+01	6.7E+01	1.1E+02	2.4E+01	2.1E+01	8.5E+01	6.6E-02	9.9E+00	3.7E-02	5.8E-02	3.0E+01	9.9E+00	4.7E+00	7.4E-01	1.5E-02
^{243}Am (Ci)	8.3E-04	6.3E-03	2.6E-03	2.3E-04	2.9E-04	4.5E-03	4.5E-06	2.4E-04	3.9E-06	4.5E-06	6.8E-04	2.4E-04	1.1E-04	1.8E-05	6.0E-07
^{243}Cm (Ci)	3.9E-02	1.2E-01	9.4E-03	2.6E-02	5.0E-03	8.2E-03	4.8E-05	9.3E-04	3.1E-05	4.1E-05	4.8E-03	5.7E-04	2.8E-05	6.3E-06	2.4E-06
^{244}Cm (Ci)	3.2E-02	2.8E+00	6.5E-02	4.3E-02	3.0E-02	3.3E-01	3.9E-04	8.1E-04	3.5E-04	4.0E-04	1.1E-01	3.0E-04	3.9E-05	2.8E-05	2.6E-05

Table B1.13. Retrieval Leak Loss Inventory Estimates, Assuming Supernate as Retrieval Fluid (2 Sheets)

Analyte	C-101	C-102	C-103	C-105	C-106	C-107	C-108	C-109	C-110	C-111	C-112	C-201	C-202	C-203	C-204
Leakage (gal)	**8,000**	**8,000**	**8,000**	**8,000**	**8,000**	**8,000**	**8,000**	**8,000**	**8,000**	**8,000**	**8,000**	**800**	**800**	**800**	**800**
Cr (kg)	2.3E+01	2.1E+01	1.6E+01	2.3E+01	2.8E-01	2.2E+01	2.2E+01	2.1E+01	2.3E+01	2.0E+01	2.2E+01	2.2E-00	2.2E-00	2.1E-00	2.1E+00
Na (kg)	3.5E+03	3.1E+03	2.1E+03	2.8E+03	5.5E+02	2.6E+03	3.3E+03	3.1E+03	3.8E+03	2.7E+03	3.7E+03	3.0E+02	2.9E+02	2.8E+02	2.7E+02
NO_2 (kg)	7.2E+02	7.0E+02	6.4E+02	6.4E+02	7.7E+01	7.6E+02	9.2E+02	9.3E+02	6.7E+02	7.1E+02	1.3E+03	6.2E+01	7.7E+01	5.9E+01	5.9E+01
NO_3 (kg)	3.7E+03	3.0E+03	2.1E+03	2.7E+03	5.0E+00	2.7E+03	3.2E+03	2.9E+03	4.8E+03	2.9E+03	3.5E+03	2.9E+02	3.2E+02	3.1E+02	2.9E+02
U_{TOTAL} (kg)	1.5E+00	1.1E+00	1.5E+01	4.8E+00	4.6E+00	8.9E+00	5.9E-01	8.7E-01	2.2E+00	2.7E-03	2.8E+01	1.1E-02	3.1E-04	2.9E-04	2.9E-04
^{14}C (Ci)	2.3E-01	2.2E-01	1.8E-01	2.3E-01	1.9E-01	2.2E-01	2.2E-01	2.2E-01	2.1E-01	2.2E-01	2.7E-01	2.3E-02	2.3E-02	2.3E-02	2.3E-02
^{60}Co (Ci)	1.2E-01	1.5E-01	4.0E-01	1.5E-01	4.2E-02	6.2E-02	6.3E-02	6.2E-02	5.7E-02	6.4E-02	6.4E-02	6.4E-03	6.4E-03	6.4E-03	6.4E-03
^{63}Ni (Ci)	4.0E-01	3.9E-01	6.1E-01	4.0E-01	2.0E+00	3.9E-01	4.1E-01	4.8E-01	3.6E-01	4.0E-01	1.5E+00	4.1E-02	4.1E-02	4.1E-02	4.1E-02
^{79}Se (Ci)	4.2E-02	4.1E-02	1.3E-01	4.2E-02	2.8E-02	2.9E-01	4.2E-02	4.3E-02	8.3E-02	4.2E-02	4.6E-02	4.5E-03	4.7E-03	4.4E-03	4.4E-03
^{90}Sr (Ci)	6.3E+02	4.2E+02	3.2E+02	4.1E+02	1.3E+01	4.2E+02	3.9E+02	4.0E+02	3.6E+02	1.8E+03	5.3E+02	6.4E+01	7.1E+02	1.3E+02	5.0E+01
^{90}Y (Ci)	6.4E+02	4.3E+02	3.3E+02	4.2E+02	1.3E+01	4.4E+02	4.0E+02	4.1E+02	3.7E+02	1.8E+03	5.4E+02	6.6E+01	7.2E+02	1.3E+02	5.1E+01
^{99}Tc (Ci)	2.6E+00	1.5E+00	4.7E+00	2.2E+00	1.3E+00	2.2E+00	1.6E+00	2.3E+00	2.2E+00	1.6E+00	2.7E+00	1.6E-01	1.6E-01	1.6E-01	1.6E-01
^{126}Sn (Ci)	7.4E-03	7.1E-03	7.0E-03	7.4E-03	4.2E-02	2.1E-02	7.3E-03	7.2E-03	6.6E-03	7.3E-03	7.3E-03	7.4E-04	7.4E-04	7.4E-04	7.4E-04
^{129}I (Ci)	3.4E-03	2.7E-03	2.5E-03	3.7E-03	2.6E-03	2.8E-03	2.8E-03	2.8E-03	2.5E-03	2.8E-03	2.8E-03	2.9E-04	2.9E-04	2.9E-04	2.9E-04
^{137}Cs (Ci)	2.5E+03	1.9E+03	1.5E+03	1.7E+03	4.9E+02	1.7E+03	1.8E+03	1.7E+03	1.7E+03	1.9E+03	2.5E+03	1.7E+02	1.7E+02	1.7E+02	1.7E+02
^{137}mBa (Ci)	2.4E+03	1.8E+03	1.5E+03	1.7E+03	4.6E+02	1.7E+03	1.7E+03	1.6E+03	1.7E+03	1.9E+03	2.4E+03	1.7E+02	1.7E+02	1.7E+02	1.6E+02
^{233}U (Ci)	2.0E-03	2.0E-03	3.1E-03	1.8E-03	2.0E-03	2.1E-03	1.8E-03	1.8E-03	1.7E-03	1.8E-03	2.5E-03	1.9E-04	1.9E-04	1.9E-04	1.9E-04
^{234}U (Ci)	1.3E-03	1.1E-03	5.4E-03	2.4E-03	1.6E-03	3.7E-03	9.9E-04	1.1E-03	1.4E-03	8.0E-04	1.0E-02	8.5E-05	8.1E-05	8.1E-05	8.1E-05
^{235}U (Ci)	5.6E-05	4.8E-05	2.3E-04	1.0E-04	6.7E-05	1.6E-04	4.2E-05	4.6E-05	6.3E-05	3.4E-05	4.4E-04	3.6E-06	3.4E-06	3.4E-06	3.4E-06
^{236}U (Ci)	3.4E-05	3.5E-05	1.1E-04	5.2E-05	4.4E-05	5.3E-05	2.6E-05	2.6E-05	2.7E-05	2.5E-05	1.4E-04	2.6E-06	2.5E-06	2.5E-06	2.5E-06
^{238}U (Ci)	1.3E-03	1.1E-03	5.5E-03	2.4E-03	1.6E-03	3.8E-03	9.9E-04	1.1E-03	1.5E-03	8.0E-04	1.0E-02	8.5E-05	8.1E-05	8.1E-05	8.1E-05
^{238}Pu (Ci)	1.4E-03	1.8E-03	1.4E-03	1.2E-03	3.7E-03	4.2E-03	1.2E-03	2.2E-03	1.3E-03	1.2E-03	2.8E-03	6.9E-04	1.3E-04	1.2E-04	1.2E-04

Table B1.13. Retrieval Leak Loss Inventory Estimates, Assuming Supernate as Retrieval Fluid (2 Sheets)

Analyte	C-101	C-102	C-103	C-105	C-106	C-107	C-108	C-109	C-110	C-111	C-112	C-201	C-202	C-203	C-204
^{239}Pu (Ci)	5.4E-02	6.2E-02	5.9E-02	4.7E-02	1.9E-01	1.3E-01	4.4E-02	8.5E-02	1.2E-01	4.2E-02	5.9E-02	2.8E-02	4.6E-03	4.3E-03	4.2E-03
^{240}Pu (Ci)	9.1E-03	1.1E-02	9.6E-03	7.8E-03	3.0E-02	2.4E-02	7.1E-03	1.4E-02	1.1E-02	7.0E-03	9.7E-03	4.7E-03	7.7E-04	7.2E-04	7.1E-04
^{241}Pu (Ci)	1.0E-01	1.3E-01	9.7E-02	8.7E-02	2.7E-01	3.0E-01	8.1E-02	1.5E-01	7.5E-02	8.2E-02	1.0E-01	5.0E-02	8.9E-03	8.4E-03	8.3E-03
^{242}Pu (Ci)	4.7E-07	5.8E-07	4.6E-07	4.3E-07	1.2E-06	1.6E-06	4.1E-07	7.7E-07	3.8E-07	4.1E-07	5.0E-07	2.5E-07	4.5E-08	4.3E-08	4.2E-08
^{241}Am (Ci)	6.1E-01	4.5E-01	1.6E-01	1.0E+01	4.3E-01	3.8E+00	8.4E-02	9.3E-02	7.5E-02	8.5E-02	1.3E-01	1.0E-02	8.9E-03	8.6E-03	8.6E-03
^{243}Am (Ci)	1.5E-05	4.4E-05	1.0E-05	1.1E-04	9.4E-06	2.0E-04	9.9E-06	1.0E-05	8.9E-06	1.0E-05	1.1E-05	1.0E-06	1.0E-06	1.0E-06	1.0E-06
^{243}Cm (Ci)	1.8E-04	4.0E-04	6.4E-05	8.4E-05	4.3E-05	8.8E-05	7.8E-05	7.8E-05	7.0E-05	7.9E-05	1.1E-04	7.8E-05	9.7E-05	2.2E-05	8.2E-06
^{244}Cm (Ci)	9.7E-04	8.1E-03	7.2E-04	8.9E-04	1.4E-03	1.3E-03	8.8E-04	8.7E-04	7.9E-04	8.9E-04	1.8E-03	1.2E-04	1.3E-04	9.7E-05	9.0E-05

Table B1.14. Retrieval Leak Loss Inventory Estimates, Assuming Water as Retrieval Fluid

Analyte	C-101	C-110	C-111	C-201	C-202	C-203	C-204
Leak Loss (gal)	**8,000**	**8,000**	**8,000**	**800**	**800**	**800**	**800**
Cr (kg)	3.5E+00	6.0E+00	4.1E-01	2.3E-01	2.1E-01	1.5E-01	9.1E-02
Na (kg)	1.0E+03	1.6E+03	1.7E+02	4.6E+01	4.2E+01	3.0E+01	1.8E+01
NO_2 (kg)	1.5E+02	1.5E+02	1.3E+02	4.2E+00	1.9E+01	1.1E+00	6.8E-01
NO_3 (kg)	1.1E+03	2.4E+03	2.4E+02	2.3E+01	5.6E+01	4.3E+01	2.2E+01
U_{TOTAL} (kg)	1.5E+00	2.2E+00	0.0E+00	1.1E-02	3.4E-05	1.8E-05	2.0E-05
^{14}C (Ci)	7.6E-03	7.6E-03	7.7E-04	6.0E-04	1.0E-04	8.1E-04	6.0E-04
^{60}Co (Ci)	6.0E-02	1.5E-07	6.2E-11	9.8E-09	9.6E-09	3.6E-09	3.4E-09
^{63}Ni (Ci)	7.5E-04	2.7E-05	1.4E-07	3.0E-04	3.3E-04	7.8E-05	9.0E-05
^{79}Se (Ci)	3.7E-04	4.5E-02	1.6E-04	2.8E-04	4.6E-04	1.1E-04	1.5E-04
^{90}Sr (Ci)	2.4E+02	4.9E+00	1.4E+03	2.5E+01	6.7E+02	8.9E+01	9.7E+00
^{90}Y (Ci)	2.4E+02	4.9E+00	1.4E+03	2.5E+01	6.7E+02	8.9E+01	9.7E+00
^{99}Tc (Ci)	1.0E+00	7.4E-01	5.4E-03	8.9E-04	7.3E-04	8.3E-04	7.0E-04
^{126}Sn (Ci)	4.4E-05	3.3E-05	1.1E-08	0.0E+00	5.2E-13	3.8E-09	4.4E-13
^{129}I (Ci)	5.5E-04	2.0E-05	1.0E-05	1.7E-06	1.4E-06	1.5E-06	1.3E-06
^{137}Cs (Ci)	9.0E+02	2.6E+02	3.0E+02	5.3E+00	8.5E+00	6.1E+00	3.7E+00
^{137}mBa (Ci)	8.5E+02	2.5E+02	2.8E+02	5.0E+00	8.0E+00	5.7E+00	3.5E+00
^{233}U (Ci)	1.3E-04	5.2E-10	0.0E+00	2.6E-12	2.1E-14	4.2E-15	4.6E-15
^{234}U (Ci)	5.1E-04	7.3E-04	0.0E+00	3.6E-06	1.1E-08	6.0E-09	6.5E-09
^{235}U (Ci)	2.2E-05	3.3E-05	0.0E+00	1.6E-07	4.7E-10	2.7E-10	2.9E-10
^{236}U (Ci)	8.9E-06	4.7E-06	0.0E+00	2.3E-08	2.6E-10	3.8E-11	4.2E-11
^{238}U (Ci)	5.1E-04	7.4E-04	0.0E+00	3.7E-06	1.1E-08	6.0E-09	6.6E-09
^{238}Pu (Ci)	2.7E-04	2.7E-04	1.0E-05	5.8E-04	9.4E-06	2.9E-06	1.6E-06
^{239}Pu (Ci)	1.3E-02	8.6E-02	6.7E-04	2.4E-02	4.0E-04	1.2E-04	6.8E-05
^{240}Pu (Ci)	2.2E-03	5.0E-03	1.0E-04	4.0E-03	6.5E-05	2.0E-05	1.1E-05
^{241}Pu (Ci)	2.1E-02	3.2E-03	7.4E-04	4.2E-02	6.8E-04	2.1E-04	1.2E-04
^{242}Pu (Ci)	6.4E-08	9.9E-09	2.8E-09	2.0E-07	3.3E-09	1.0E-09	5.7E-10
^{241}Am (Ci)	5.2E-01	1.7E-05	0.0E+00	1.6E-03	3.2E-04	3.8E-05	1.2E-06
^{243}Am (Ci)	4.6E-06	4.7E-11	0.0E+00	3.8E-08	7.8E-09	9.2E-10	2.8E-11
^{243}Cm (Ci)	1.0E-04	7.3E-10	5.3E-09	7.0E-05	8.9E-05	1.4E-05	2.4E-07
^{244}Cm (Ci)	8.2E-05	1.9E-09	5.4E-09	3.4E-05	4.3E-05	6.8E-06	1.2E-07

B1.6.0 REFERENCES

BBI, 2000, *Best Basis Inventory*, August 1, 2000 revision accessed at http://twins.pnl.gov:8001/data/datamenu.htm in December 2000.

Ecology, EPA, and DOE, 1989, *Hanford Federal Facility Agreement and Consent Order*, as amended, Washington State Department of Ecology, U.S. Environmental Protection Agency, and U.S. Department of Energy, Olympia, Washington.

GE, 1996, *Nuclides and Isotopes*, Fifteenth Edition, GE Nuclear Energy, San Jose, California.

HNF-3157, 1999, *Best-Basis Wash and Leach Factor Analysis*, Revision 0A, COGEMA Engineering, Richland, Washington.

HNF-EP-0182, 2000, *Waste Tank Summary Report for Month Ending September 30, 2000*, Rev. 150, CH2M HILL Hanford Group, Inc., Richland, Washington.

LA-UR-00-4050, 2000, *Hanford Soil Inventory and Uncertainty Model*, Rev. 1, Los Alamos National Laboratory, Los Alamos, New Mexico.

LA-UR-96-3860, 1997, *Hanford Tank Chemical and Radionuclide Inventories: HDW Model*, Rev. 4, Los Alamos National Laboratory, Los Alamos, New Mexico.

Perry, J. H., 1963, *Chemical Engineers' Handbook*, Fourth Edition, McGraw-Hill Book Company, New York, New York.

PNNL-13364, 2000, *Inorganic and Radiochemical Analysis of 241-C-104 Tank Waste*, Pacific Northwest National Laboratory, Richland, Washington.

RPP-6843, 2000, *Preliminary Engineering Report for the 241-C-104 Retrieval System*, Rev. 0, Numatec Hanford Corporation, Richland, Washington.

RPP-7087, 2000, *Single-Shell Tank Retrieval Sequence: Fiscal Year 2000 Update*, Rev. 0, Numatec Hanford Corporation, Richland, Washington.

SD-CP-TI-077, 1985, *ORIGIN2 Prediction of N Reactor Fuel Fission Product Composition*, Rockwell Hanford Operations, Richland, Washington.

ATTACHMENT B2

COPY OF RPP-6696 APPENDIX D: COMPARISON OF SUBSURFACE CONDITIONS BETWEEN THE AX AND C TANK FARMS THAT POTENTIALLY AFFECT SCALING IMPACT ASSESSMENT RESULTS

NOTE: This appendix is an exact reproduction of Appendix D to RPP-6696, 2000, *Data to Support Tank C-106 Waste Retrieval Determination*, Rev. 0, CH2M HILL Hanford Group, Inc., Richland, Washington.

This page intentionally left blank.

TABLE OF CONTENTS

D.1.0 INTRODUCTION B2-1

D.2.0 SUBSURFACE CONDITIONS B2-2
- D.2.1 VADOSE ZONE CHARACTERISTICS BASED ON OBSERVATIONS DURING TANK FARM CONSTRUCTION AND DRY WELL INSTALLATION B2-2
- D.2.2 VADOSE ZONE CHARACTERISTICS ASSUMED IN THE TWRS EIS B2-4
- D.2.3 VADOSE ZONE CHARACTERISTICS ASSUMED IN THE COMPOSITE ANALYSIS B2-4

D.3.0 EVALUATION OF DATA B2-8

D.4.0 REFERENCES B2-10

FIGURES

D.2.1. Location of the AX and C Tank Farms B2-3
D.2.2. Conceptual Profiles of the Vadose Zone for the AX Tank Farm (Source Area 4ESS) and the C Tank Farm (Source Area 2ESS) B2-6

TABLES

D.2.1. Point-by-Point Comparison of Subsurface Characteristics Between the AX and C Tank Farms Based on ARH-LD-128 and ARH-LD-132 ..... B2-2
D.2.2. Comparison of Vadose Zone Sediment Designations and Thickness Between the AX and C Tank Farms Based on DOE/EIS-0189 ..... B2-4
D.2.3. Hydraulic and Transport Parameter Values Assumed for Vadose Zone Sediments at the AX and C Tank Farms B2-5
D.2.4. Point-by-Point Comparison of Physical and Vadose Zone Characteristics Between the AX and C Tank Farms Based on PNNL-11800 ..... B2-7
D.2.5. Sediment Types and Hydraulic Parameter Values Used in PNNL-11800 ..... B2-7
D.3.1. Time to Contaminant First Arrival and Time to Contaminant Peak Concentration for AX and C Tank Sources Considered in DOE/EIS-0189 ..... B2-8

This page intentionally left blank.

APPENDIX D

COMPARISON OF SUBSURFACE CONDITIONS BETWEEN THE AX AND C TANK FARMS THAT POTENTIALLY AFFECT SCALING IMPACT ASSESSMENT RESULTS

D.1.0 INTRODUCTION

This appendix discusses the applicability of using the AX tank farm impact assessment results as presented in the *Retrieval Performance Evaluation Methodology for the AX Tank Farm* (DOE/RL-98-72) as the basis for an analog for estimating groundwater impacts at the C tank farm. In so doing, documented subsurface conditions at both tank farms and recent analyses involving both tank farms are reviewed. A comparison of subsurface conditions for the two tank farms is presented in Section D.2.0. Evaluation of the implications that the subsurface conditions have on potential contaminant transport at the two tank farms is provided in Section D.3.0.

D.2.0 SUBSURFACE CONDITIONS

Both tank farms are located near the eastern boundary of the 200 East Area (Figure D.2.1). The C tank farm is approximately 175 m (575 ft) northeast of the AX tank farm at the closest point or 224 m (735 ft) from center of C tank farm to center of AX tank farm. The following subsections provide a comparison of summary-level data, information, assumptions developed by selected studies of the two tank farms.

D.2.1 VADOSE ZONE CHARACTERISTICS BASED ON OBSERVATIONS DURING TANK FARM CONSTRUCTION AND DRY WELL INSTALLATION

The first comprehensive stratigraphic descriptions of the vadose zone beneath the AX and C tank farms are provided in ARH-LD-128 and ARH-LD-132, respectively. Both of these reports are authored by the same individuals which helps ensure consistent interpretation of field data. The data available at the time of the report consisted primarily of drill cuttings from the installation of dry wells around each tank in the tank farms and mapping of the side walls of the excavation that was created during tank farm construction. The dry wells were generally drilled to depths of 30.5 m to 41.1 m (100 to 135 ft). Drill cuttings for the lower vadose zone (i.e., below depth of 41.1 m [135 ft]) are scarce and are limited to nearby groundwater monitoring wells which are much fewer than the dry wells that surround the tanks.

A comparison of subsurface characteristics between the two tank farms based on these two reports is provided in Table D.2.1.

This early work indicates variability beneath each tank farm with respect to sediment thickness based on several cross section plates included in the report. The Ringold Formation thickness, which is generally finer-grained than the overlying Hanford formation, is about 25.6 m (84 ft) less at the AX tank farm than at C tank farm.

Table D.2.1. Point-by-Point Comparison of Subsurface Characteristics Between the AX and C Tank Farms Based on ARH-LD-128 and ARH-LD-132

AX Tank Farm Subsurface Characteristic	C Tank Farm Subsurface Characteristic
1. Three major stratigraphic units • Columbia River Basalt • Ringold Formation • Glaciofluvial sediments	1. Three major stratigraphic units • Columbia River Basalt • Ringold Formation • Glaciofluvial sediments
2. Basalt surface elevation at 100.6 m (330 ft) msl	2. Basalt surface elevation at 91.5 m (300 ft) msl
3. Ringold thickness of 6.1 m (20 ft)	3. Ringold thickness of 31.7 m (104 ft) (middle Ringold only, both upper and lower Ringold are missing)
4. Water table was at 122.9 m (403 ft) msl, 62.2 m (204 ft) below base of tanks	4. Water table was at 124.4 m (408 ft) msl, 68.0 m (223 ft) below base of tanks.
5. Some clastic dikes were detected but they could not be mapped.	5. Some clastic dikes were detected but they could not be mapped.
6. Vadose zone thickness of 86.13 m (282.5 ft)[1]	6. Vadose zone thickness of 78.6 m (257.8 ft)*

* Estimate of vadose zone thickness is calculated as the difference in the water level elevation as shown in the table and the groundsurface elevation as reported in PNNL-11800 which is 209 m (685.52 ft) msl for the AX tank farm and 203 m (665.84 ft) msl for the C tank farm.

msl = mean sea level.

Figure D.2.1. Location of the AX and C Tank Farms



Source: PNNL-13116

D.2.2 VADOSE ZONE CHARACTERISTICS ASSUMED IN THE TWRS EIS

The *Tank Waste Remediation System, Hanford Site, Richland, Washington, Final Environmental Impact Statement* (DOE/EIS-0189) developed models of vadose zone contaminant transport for both of these tank farms as part of the groundwater impacts evaluation. DOE/EIS-0189 aggregated tank farms into source areas based on similarities in subsurface conditions and type of tank. The AX and C tank farms were aggregated into source areas 4ESS and 2ESS, respectively. A comparison of vadose zone material types and thickness between the two tank farms based on DOE/EIS-0189 is provided in Table D.2.2. Stratigraphic profiles of the two source areas from DOE/EIS-0189 are shown on Figure D.2.2.

The hydraulic properties associated with the three material properties identified at the two tank farms are provided in Table D.2.3.

Table D.2.2. Comparison of Vadose Zone Sediment Designations and Thickness Between the AX and C Tank Farms Based on DOE/EIS-0189

AX Tank Farm Subsurface Characteristic (Source Area 4ESS)	C Tank Farm Subsurface Characteristic (Source Area 2ESS)
Total vadose zone thickness 75 m (246 ft)	Total vadose zone thickness 75 m (246 ft)
Tank depth 0 to 17 m (0 to 55.8 ft) bgs	Tank depth 0 to 12 m (0 to 39.4 ft) bgs
Hanford upper gravels (Material Type 2) 0 to 10 m (0 to 32.8 ft) bgs	Hanford upper gravels (Material Type 2) 10 to 15 m (32.8 to 49.2 ft) bgs
Hanford sandy sequence (Material Type 1) 10 to 72 m (32.8 to 236.2) bgs	Hanford sandy sequence (Material Type 1) 15 to 75+ m (49.2 to 246 ft) bgs
Hanford lower gravels (Material Type 2) 72 to 74 m (236.2 to 242.7) bgs	Hanford lower gravels (Material Type 2) Not present
Ringold (Material Type 3) 74 m + (242.7 ft +)	Ringold (Material Type 3) Not present

Source: DOE/EIS-0189, Table F.2.3.1

bgs = below ground surface.

D.2.3 VADOSE ZONE CHARACTERISTICS ASSUMED IN THE COMPOSITE ANALYSIS

The *Composite Analysis for Low-Level Waste Disposal in the 200 Area Plateau of the Hanford Site* (PNNL-11800) developed models of vadose zone contaminant transport for all waste sites on the 200 Area plateau including both of the AX and C tank farms as part of the assessment of cumulative groundwater impacts. The PNNL-11800 vadose zone models were one-dimensional and the primary mechanism for transport through the vadose zone was water flow in response to gravitational and capillary forces. The stratigraphy and associated hydraulic parameter values used in the models were defined as a set of strata and parameter values consistent with the nearest available well log. The different sediment types were each assigned hydraulic properties and were assumed to be uniform within the sediment type. Preferential flow was not considered.

Table D.2.3. Hydraulic and Transport Parameter Values Assumed for Vadose Zone Sediments at the AX and C Tank Farms

Hydraulic Parameter	Material Type 1 Hanford Sandy Sequence	Material Type 2 Hanford Upper or Lower Gravels	Material Type 3 Ringold
Saturated Hydraulic Conductivity, K_s (m/day)	4,330	1,320	0.66
Saturated water content, θ_s (cm^3/cm^3)	0.42	0.358	0.32
Residual water content, θ_r (cm^3/cm^3)	0.023	0.021	0.025
Specific retention, θ_{wr} (cm^3/cm^3)	0.055	0.059	0.078
Van Genuchten Parameters (Dimensionless)			
α	19.43	2.9	1.76
β	1.868	1.613	1.338
γ	0.465	0.38	0.253
Transport Parameters			
Bulk density, ρ_B (g/cm^3)	1.6	1.76	1.64
Longitudinal dispersivity, α_L (m)	0.5	0.101	0.06

Source: DOE/EIS-0189, Tables F.2.3.3 and F.2.3.5

Note: The DOE/EIS-0189 analysis used a one-dimensional vadose zone modeling approach, which did not require an estimate of transverse dispersivity.

A comparison of selected physical and vadose zone material types and thickness between the two tank farms based on PNNL-11800 is provided in Table D.2.4.

The hydraulic parameter values assumed in PNNL-11800 for the four sediment types are provided in Table D.2.5.

Figure D.2.2. Conceptual Profiles of the Vadose Zone for the AX Tank Farm (Source Area 4ESS) and the C Tank Farm (Source Area 2ESS)



Source: DOE/EIS-0189

Table D.2.4. Point-by-Point Comparison of Physical and Vadose Zone Characteristics Between the AX and C Tank Farms Based on PNNL-11800

AX Tank Farm Physical and Subsurface Characteristics	C Tank Farm Physical and Subsurface Characteristics
Ground surface elevation (m) 209	Ground surface elevation (m) 203
Water table elevation (m) 122	Water table elevation (m) 122
Nearest available well log 299-E25-2	Nearest available well log 299-E26-8
[1]Total vadose zone thickness 87 m (285.4 ft)	[1]Total vadose zone thickness 81 m (265.7 ft)
Number of sediment types: 4	Number of sediment types: 4
First (upper) layer name and thickness: Hanford Gravel 10 m (32.8 ft)	First (upper) layer name and thickness: Hanford Gravel 10 m (32.8 ft)
Second layer name and thickness: Hanford Sand 6 m	Second layer name and thickness: Hanford Sand 6 m
Third layer name and thickness: Lower Hanford Gravel 60 m (196.8)	Third layer name and thickness: Lower Hanford Gravel 44 m (144.3 ft)
Fourth layer name and thickness: Ringold 36 m (118 ft)	Fourth layer name and thickness: Ringold 14 m (45.9 ft)

Source: PNNL-11800, Table 4.3 and Table 4.6.
Note: Thickness based on difference between surface elevation and water table elevation.

Table D.2.5. Sediment Types and Hydraulic Parameter Values Used in PNNL-11800

Sediment Name	Van Genuchten alpha	Van Genuchten n (1/cm)	Residual Water Content (cm^3/cm^3)	Saturated Water Content (cm^3/cm^3)	Saturated Hydraulic Conductivity (cm/s)	Bulk Density (g/cm^3)	Gravel %
Hanford Gravel	8.11E-03	1.58	0.0146	0.119	1.76E-03	1.97	41.7
Hanford Sand	1.30E-01	2.1	0.0257	0.337	1.19E-02	1.78	17.3
Lower Hanford Gravel	8.11E-03	1.58	0.0146	0.119	1.76E-03	1.97	41.7
Ringold	8.19E-03	1.53	0.0262	0.124	3.97E-04	2.04	43.3

Source: PNNL-11800, Table 4.7

D.3.0 EVALUATION OF DATA

The most detailed stratigraphic information is based on field observations and examination of drill cuttings from the initial tank farm construction and dry well installation (ARH-LD-128 and ARH-LD-132). The tank farms are about 175 m (575 ft) apart, which is a relatively close proximity. The stratigraphic characteristics (e.g., layers, thickness, continuity, and slope) within each tank farm are heterogeneous as revealed by the geologic cross sections for each tank farm (ARH-LD-128 and ARH-LD-132). The same geologic processes are responsible for the stratigraphic characteristics at each tank farm and the degree of stratigraphic heterogeneity appears similar between tank farm.

Detailed subsurface investigations, such as the *Resource Conservation and Recovery Act of 1976* field investigations at the waste management area S-SX (HNF-5085), have not been initiated at either of the tank farms therefore direct measurements of existing contamination and of hydraulic parameter values have not been collected. This lack of data combined with the natural variability of the sediments result in a large uncertainty of subsurface conditions at both tank farms. This has generally been acknowledged in the documents that attempted to predict contaminant transport in the vadose zone at these two tank farms (DOE/EIS-0189 and PNNL-11800) and has forced an approach that includes some generalization of sediment thicknesses and hydraulic properties. Even though there is variability in sediment thicknesses within and between the tank farms, the predominant characteristics are very similar. These predominant characteristics are the overall vadose zone thickness and the generalized sequence of sediments.

DOE/EIS-0189 provides a comparison of vadose zone contaminant transport for the two tank farms for selected scenarios. Table D.3.1 provides a comparison between the AX and C tank farms of time to contaminant first arrival and time to contaminant peak concentration for selected scenarios considered in DOE/EIS-1089.

Table D.3.1. Time to Contaminant First Arrival and Time to Contaminant Peak Concentration for AX and C Tank Sources Considered in DOE/EIS-0189

Tank Farm, alternative, and distribution coefficient	Time of First Arrival, (years)	Time to Peak Concentration, (years)
AX tank farm (Source area 4ESS) In Situ Fill and Cap alternative, K_d=0	2,330	5,940
C tank farm (Source area 2ESS) In Situ Fill and Cap alternative, K_d=0	2,450	4,080
AX tank farm (Source area 4ESS) No Action alternative, K_d=0	140	230
C tank farm (Source area 2ESS) No Action alternative, K_d=0	140	210
AX tank farm (Source area 4ESS) No Action alternative, K_d=1	1,040	2,040
C tank farm (Source area 2ESS) No Action alternative, K_d=1	1,210	2,180

Notes: K_d is the distribution coefficient (mL/g). The distribution coefficient is a "lumped parameter," which attempts to simulate all geochemical solution-sediment-pore water reactions as an equilibrium adsorption-desorption system

These results, as summarized in Table D.3.1, indicate that there is no significant difference in vadose zone travel time at the two tank farms. The In Situ Fill and Cap alternative included a Hanford barrier that greatly restricted infiltration compared to the No Action alternative, which did not include a barrier.

D.4.0 REFERENCES

ARH-LD-128, 1976, *Geology of the 241-AX Tank Farm*, Atlantic Richfield Hanford Company, Richland, Washington.

ARH-LD-132, 1976, *Geology of the 241-C Tank Farm*, Atlantic Richfield Hanford Company, Richland, Washington.

DOE/EIS-0189, 1996, *Tank Waste Remediation System, Hanford Site, Richland, Washington, Final Environmental Impact Statement*, U.S. Department of Energy, Washington, D.C.

DOE-RL-98-72, 1998, *Retrieval Performance Evaluation Methodology for the AX Tank Farm*, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

HNF-5085, 2000, *Site-Specific SST Phase 1 RFI/CMS Work Plan Addendum for WMA S-SX*, Rev. 1, CH2M HILL Hanford Group, Inc., Richland, Washington.

PNNL-11800, 1998, *Composite Analysis for Low-Level Waste Disposal in the 200 Area Plateau of the Hanford Site*, Pacific Northwest National Laboratory, Richland, Washington.

PNNL-13116, 2000, *Hanford Site Groundwater Monitoring for Fiscal Year 1999*, Pacific Northwest National Laboratory, Richland, Washington.

Resource Conservation and Recovery Act of 1976, Public Law 94-580, 90 Stat. 2795, 42 USC 901 et seq.

MANAGEMENT SELF ASSESSMENT SALTCAKE DISSOLUTION U-107

1.0 Maintenance

1.1 Maintenance procedure requirements (both start-up and operational) are identified, maintenance procedures are issued and Maintenance personnel are trained on procedures.

Completed_____ Completed with Exception_____

Remarks: (attach procedure list, as applicable)

Maintenance Manager_____ Date_____

1.2 Maintenance support personnel have been identified, trained, and are ready to support Saltcake dissolution activities.

Completed_____ Completed with Exception_____

Remarks: (attach training status documents, as applicable)

Maintenance Manager_____ Date_____

1.3 A walkdown of the systems and area has been performed just prior to start-up of the saltwell dissolution system. There are no last minute issues or concerns which may require resolution prior to commencing dissolution activities.

Completed_____ Completed with exception _____

Remarks:

Maintenance Manager _____ Date _____

MANAGEMENT SELF ASSESSMENT SALTCAKE DISSOLUTION TANK U-107

2.0 Production Control

2.1 Work packages necessary to support saltcake dissolution are identified and completed. This includes any upgrades and equipment installation necessary to support this dissolution sytem start.

Completed _____ Completed with Exception_____

Remarks: (attach work package list, as applicable)

Production Control Manager_____ Date_____

2.2 Maintenance (preventive/predictive) periodicity is identified and requirements are current and entered in JCS-PMS.

Completed_____ Completed with Exception_____

Remarks: (attach PM/S printout, as applicable)

Production Control Manager_____ Date_____

MANAGEMENT SELF ASSESSMENT SALTCAKE DISSOLUTION TANK U-107

3.0 Training

3.1 All Operators, Operations Engineers (OE's), and Persons-in-Charge (PIC's) associated with the start up of the Saltcake dissolution system are qualified, and training requirements are current.

Completed_____ Completed with Exception_____

Remarks:

Operations Manager_____ Date_____

MANAGEMENT SELF ASSESSMENT SALTCAKE DISSOLUTION TANK U-107

4.0 Engineering

4.1 If required, a USQ screening/determination, evaluation, and PRC approval has been completed.

Completed_____ Completed with Exception_____

Remarks:

Engineering Manager_____ Date_____

4.2 Saltcake dissolution Engineering Change Notices (ECN) have been signed off or documented as "work complete" as applicable to facilitate operations.

Completed_____ Completed with Exception_____

Remarks:

Engineering Manager_____ Date_____

4.3 Engineering has identified TSR requirements external to Interim Stabilization activities to determine impact of saltcake dissolution. Verification that Saltcake dissolution can commence without affecting the facility's ability to operate within the TSRs, has been completed.

Completed_____ Completed with Exception_____

Remarks:

Engineering Manager_____ Date_____

MANAGEMENT SELF ASSESSMENT SALTCAKE DISSOLUTION TANK U-107

4.4 Maintenance material (spare parts & consumables) requirements have been identified and are available for issue.

Completed_____ Completed with Exception_____

Remarks:

Engineering Manager_____ Date_____

4.5 A walkdown of the systems and area has been performed just prior to start-up of the saltcake dissolution system. There are no last minute issues or concerns which may require resolution prior to commencing saltwell dissolution activities.

Completed_____ Completed with exception _____

Remarks:

Engineering Manager _____ Date _____

4.6 The preventative maintenance database has been updated to support equipment calibrations and functional tests required for system operation.

Completed _____ Completed with exception _____

Remarks:

Engineering Manager _____ Date _____

4.7 Direction to Operations on system operation requirements has been provided in the form of Process Memo, if required.

Completed _____ Completed with exception _____

Remarks:

Engineering Manager _____ Date_____

MANAGEMENT SELF ASSESSMENT SALTCAKE DISSOLUTION TANK U-107

4.8 Outstanding ECNs from U-107 pump start and infastructure upgrades have been reviewed and or closed as appropriate to facilitate saltcake dissolution operation.

Completed _____ Completed with exception_____

Remarks:

Engineering Manager _____ Date_____

MANAGENENT SELF ASSESSMENT SALTCAKE DISSOLUTION TANK U-107

5.0 Environmental

5.1 Environmental permitting and approval applications, including: Notices of Intent, Notices of Construction per State Department of Health, Notices of Construction per State Department of Ecology, etc., are submitted. Applicable environmental permits and approvals are received and requirements are implemented in the appropriate documents.

Completed_____ Completed with Exception_____

Remarks:

Environmental Assurance Manager_____ Date_____

5.2 Environmental Assurance has approved proceeding with start-up.

Completed_____ Completed with Exception_____

Remarks:

Environmental Assurance Manager_____ Date_____

5.3 All required environmental operating documents are prepared (training plan, contingency plan, emergency preparedness, inspection schedule(s), etc.).

Completed_____ Completed with Exception_____

Remarks:

Environmental Assurance Manager_____ Date_____

MANAGENENT SELF ASSESSMENT SALTCAKE DISSOLUTION TANK U-107

5.4 A waste compatibility assessment has been completed which ensures that the liquid pumped from SST is compatible with the contents of the receiving DST.

Completed_____ Completed with Exception_____

Remarks:

Environmental Assurance Manager_____ Date_____

5.5 A walkdown of the systems and area has been performed just prior to start-up of the saltcake dissolution system. There are no last minute issues or concerns which may require resolution prior to commencing saltcake dissolution activities.

Completed_____ Completed with exception _____

Remarks:

Environmental Assurance Manager _____ Date _____

MANAGEMENT SELF ASSESSMENT SALTCAKE DISSOLUTION TANK U-107

6.0 Quality Assurance

6.1 A representative sample of parts and equipment with enhanced Quality requirements (QL-1 and QL-2) have been identified and assessed to ensure that the quality characteristics have been verified and documented by Quality Control. Additionally, verify from a sample of parts which were procured from a qualified vendor that the vendor was on the ESL and that appropriate inspections were in place to verify the parts meet the design criteria. List those items checked.

Completed_____ Completed with exception_____

Remarks:

Quality Assurance Manager _____ Date_____

6.2 A post job review of a selected sample of work packages required for start-up of this dissolution system has been completed. All administrative requirements are in compliance. The packages reviewed are properly completed, reviewed, approved, and the package indicates that all work is complete. List those packages checked.

Complete _____ Complete with exception _____

Remarks:

Quality Assurance Manager _____Date _____

6.3 A walkdown of the systems and area has been performed just prior to start-up of the saltcake dissolution system. There are no last minute quality issues or concerns which may require resolution prior to commencing saltcake dissolution activities.

Completed_____ Completed with exception _____

Remarks:

Quality Assurance Manager _____ Date _____

MANAGEMENT SELF ASSESSMENT SALTCAKE DISSOLUTION TANK U-107

6.4 A representative sample of completed ECNs have been audited to ensure that the ECNs are incorporated into the saltcake dissolution equipment. Provide a list of applicable ECNs that were checked for incorporation with associated work packages. Ensure that the work packages referenced on the ECNs are complete and fully implement the ECN.

Complete _____ Complete with exception _____

Remarks:

Quality Assurance Manager _____ Date _____

6.5 The Operating procedures have been checked to verify that the equipment has been labeled and is consistent with the nomenclature for the Saltcake dissolution system being started. List procedures checked.

Complete _____ Complete with exception _____

Remarks:

Quality Assurance Manager _____ Date _____

6.6 Review a selected sample of completed fabrication packages for assemblies utilized for startup of this dissolution system. List those packages reviewed and the observations made with each.

Complete _____ Complete with exception _____

Remarks:

Quality Assurance Manager_____ Date_____

MANAGEMENT SELF ASSESSMENT SALTCAKE DISSOLUTION TANK U-107

7.0 Radiological Controls

7.1 Radiological Controls management has identified the staff necessary to support Saltcake dissolution operation/support activities and the HPT staff is trained and qualified.

Completed_____ Completed with Exception_____

Remarks:

Radiological Controls Manager_____Date_____

7.2 Radiological Controls has conducted the required surveys and sampling (air, water, etc.) and provided the required posting(s) including baseline survey data.

Completed_____ Completed with Exception_____

Remarks:

Radiological Controls Manager_____Date_____

7.3 A walkdown of the systems and area has been performed just prior to start-up of the saltcake dissolution system. There are no last minute issues or concerns which may require resolution prior to commencing saltcake dissolution activities.

Completed_____ Completed with exception _____

Remarks:

Radiological Controls Manager _____ Date _____

MANAGEMENT SELF ASSESSMENT SALTCAKE DISSOLUTION TANK U-107

7.4 All preventative maintenance (PM) sheets have been updated to verify that surveys required for NOC compliance are in place. Additionally, a pre-survey has been completed for baseline information.

Completed _____ Completed with exception _____

Remarks

Radiological Controls Manager _____ Date _____

MANAGEMENT SELF ASSESSMENT SALTCAKE DISSOLUTION TAN U-107

8.0 Safety

~~8.1 Safety has reviewed previously identified safety issues and has verified no unresolved issues remain.~~

~~Completed_____ Completed with Exception_____~~

~~Remarks:~~

~~Safety Manager_____ Date_____~~

8.1 Safety personnel have conducted a walk down of the work area for the Saltcake dissolution installation and have determined that all potential safety hazards for industrial safety have been addressed or mitigated. No conditions exist which will present unusual or significant hazards to Tank Farm personnel during start-up or operation of installed Saltcake dissolution equipment.

Completed _____ Completed with exception _____

Remarks:

Safety Manager _____ Date_____

MANAGEMENT SELF ASSESSMENT SALTCAKE DISSOLUTION TANK U-107

9.0 Operations

9.1 Operations has verified that all outstanding work packages requiring completion are closed prior to commencing saltcake dissolution activities, including, but not limited to:

- Topographical mapping system
- Water addition system

Completed_____ Completed with Exception_____

Remarks:

Operations Manager_____ Date_____

9.2 Operations has verified that outstanding corrective actions from prior occurrence reports/critiques which could impact start-up of saltcake dissolution activities are complete.

Completed_____ Completed with Exception_____

Remarks:

Operations Manager_____ Date_____

9.3 Operations has verified that open actions from U-107 saltwell pumping Management Self Assessment which impacts the starting of saltcake dissolution activities are complete.

Completed_____ Completed with Exception_____

Remarks:

Operations Manager_____ Date_____

MANAGEMENT SELF ASSESSMENT SALTCAKE DISSOLUTION TANK U-107

9.4 Review previously identified deficiencies for Interim Stabilization and verify that no DTS action requests are Open or In Process which might impact successful operation of the saltcake dissolution system.

Completed _____ Completed with exception _____

Remarks:

Operations Manager _____ Date _____

9.5 The Required Reading Program has been reviewed and is up to date. Affected personnel have read and initialed all assigned reading.

Completed _____ Completed with Exception _____

Remark:

Operations Manager _____ Date _____

9.6 The Shift Manager's Logs have been reviewed for any open issues (Red Arrow entries) which could effect operation of the saltcake dissolution system.

Completed _____ Completed with exception _____

Remarks:

Operations Manager _____ Date _____

9.7 A walkdown of the systems and area has been performed just prior to start-up of the saltcake dissolution system. There are no last minute issues or concerns which may require resolution prior to commencing saltcake dissolution activities.

Completed_____ Completed with exception _____

Remarks:

Operations Manager _____ Date_____

9.8 Operations has completed the Level of Review scoresheet per the requirements of HNF-IP-0842, Vol. XIII, Section 3.1 (if applicable) and determined that a Routine Readiness Review is the appropriate level of review to start this saltcake dissolution system.

Completed _____ Completed with exception _____

Remarks:

Operations Manager _____ Date _____

9.9 Verify operational procedures have been prepared or updated and approved for operation of the saltcake dissolution equipment.