

S

0049667

ENGINEERING CHANGE NOTICE

Page 1 of 2

1. ECN 643820

Proj.
ECN

| | | | |
|--|--|---|---|
| 2. ECN Category (mark one) <input type="checkbox"/> Supplemental <input checked="" type="checkbox"/> Direct Revision <input type="checkbox"/> Change ECN <input type="checkbox"/> Temporary <input type="checkbox"/> Standby <input type="checkbox"/> Supersedeure <input type="checkbox"/> Cancel/Void | 3. Originator's Name, Organization, MSIN, and Telephone No. James N. Strode, Models and Inventory, R2-11, 373-1280 | 4. USQ Required? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | 5. Date 08/18/98 |
| | 6. Project Title/No./Work Order No. Operational Waste Volume Project | 7. Bldg./Sys./Fac. No. N/A | 8. Approval Designator N/A |
| | 9. Document Numbers Changed by this ECN (includes sheet no. and rev.) HNF-SD-WM-ER-029, Rev. 23 | 10. Related ECN No(s). See Block 12 | 11. Related PO No. N/A |
| 12a. Modification Work <input type="checkbox"/> Yes (fill out Blk. 12b) <input checked="" type="checkbox"/> No (NA Blks. 12b, 12c, 12d) | 12b. Work Package No. N/A | 12c. Modification Work Complete N/A Design Authority/Cog. Engineer Signature & Date | 12d. Restored to Original Condition (Temp. or Standby ECN only) N/A Design Authority/Cog. Engineer Signature & Date |
| 13a. Description of Change This document updates Revision 23 by incorporating changed facility schedule assumptions, as well as waste generation rates and volumes which have occurred since the publication of Revision 23. All the values in this document will be updated several times per year. Continued from Block 10: ECN-603360, ECN-189210, ECN-166505, ECN-606102, ECN-631389, and ECN-635540. | | | |
| 13b. Design Baseline Document? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | | | |
| 14a. Justification (mark one) Criteria Change <input checked="" type="checkbox"/> Design Improvement <input type="checkbox"/> Environmental <input type="checkbox"/> Facility Deactivation <input type="checkbox"/> As-Found <input type="checkbox"/> Facilitate Const <input type="checkbox"/> Const. Error/Omission <input type="checkbox"/> Design Error/Omission <input type="checkbox"/> | | | |
| 14b. Justification Details See Block 13a above. | | | |
| 15. Distribution (include name, MSIN, and no. of copies) See attached distribution. | | | |

RELEASE STAMP

DATE:

STA: 4

HANFORD
RELEASEID:
2

AUG 20 1998

| ENGINEERING CHANGE NOTICE | | | | Page 2 of 2 | 1. ECN (Use no. from pg. 1) ECN-643820 | | | | | | | | | | | |
|---|---|---|------------|--|---|--------------|--|------------|--------------------------|----|------------|---------|--------------------------|----|---------|---|
| 16. Design Verification Required <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | 17. Cost Impact <table style="width: 100%; border: none;"> <tr> <th colspan="2" style="text-align: center;">ENGINEERING</th> <th colspan="2" style="text-align: center;">CONSTRUCTION</th> </tr> <tr> <td style="width: 30%;">Additional</td> <td style="width: 10%;"><input type="checkbox"/></td> <td style="width: 10%;">\$</td> <td style="width: 50%;">Additional</td> </tr> <tr> <td>Savings</td> <td><input type="checkbox"/></td> <td>\$</td> <td>Savings</td> </tr> </table> | | | ENGINEERING | | CONSTRUCTION | | Additional | <input type="checkbox"/> | \$ | Additional | Savings | <input type="checkbox"/> | \$ | Savings | 18. Schedule Impact (days) Improvement <input type="checkbox"/> Delay <input type="checkbox"/> |
| ENGINEERING | | CONSTRUCTION | | | | | | | | | | | | | | |
| Additional | <input type="checkbox"/> | \$ | Additional | | | | | | | | | | | | | |
| Savings | <input type="checkbox"/> | \$ | Savings | | | | | | | | | | | | | |
| 19. Change Impact Review: Indicate the related documents (other than the engineering documents identified on Side 1) that will be affected by the change described in Block 13. Enter the affected document number in Block 20. | | | | | | | | | | | | | | | | |
| SDD/DD <input type="checkbox"/> Functional Design Criteria <input type="checkbox"/> Operating Specification <input type="checkbox"/> Criticality Specification <input type="checkbox"/> Conceptual Design Report <input type="checkbox"/> Equipment Spec. <input type="checkbox"/> Const. Spec. <input type="checkbox"/> Procurement Spec. <input type="checkbox"/> Vendor Information <input type="checkbox"/> OM Manual <input type="checkbox"/> FSAR/SAR <input type="checkbox"/> Safety Equipment List <input type="checkbox"/> Radiation Work Permit <input type="checkbox"/> Environmental Impact Statement <input type="checkbox"/> Environmental Report <input type="checkbox"/> Environmental Permit <input type="checkbox"/> | Seismic/Stress Analysis <input type="checkbox"/> Stress/Design Report <input type="checkbox"/> Interface Control Drawing <input type="checkbox"/> Calibration Procedure <input type="checkbox"/> Installation Procedure <input type="checkbox"/> Maintenance Procedure <input type="checkbox"/> Engineering Procedure <input type="checkbox"/> Operating Instruction <input type="checkbox"/> Operating Procedure <input type="checkbox"/> Operational Safety Requirement <input type="checkbox"/> IEFD Drawing <input type="checkbox"/> Cell Arrangement Drawing <input type="checkbox"/> Essential Material Specification <input type="checkbox"/> Fac. Proc. Samp. Schedule <input type="checkbox"/> Inspection Plan <input type="checkbox"/> Inventory Adjustment Request <input type="checkbox"/> | Tank Calibration Manual <input type="checkbox"/> Health Physics Procedure <input type="checkbox"/> Spares Multiple Unit Listing <input type="checkbox"/> Test Procedures/Specification <input type="checkbox"/> Component Index <input type="checkbox"/> ASME Coded Item <input type="checkbox"/> Human Factor Consideration <input type="checkbox"/> Computer Software <input type="checkbox"/> Electric Circuit Schedule <input type="checkbox"/> ICRS Procedure <input type="checkbox"/> Process Control Manual/Plan <input type="checkbox"/> Process Flow Chart <input type="checkbox"/> Purchase Requisition <input type="checkbox"/> Tickler File <input type="checkbox"/> | | | | | | | | | | | | | | |
| 20. Other Affected Documents: (NOTE: Documents listed below will not be revised by this ECN.) Signatures below indicate that the signing organization has been notified of other affected documents listed below. | | | | | | | | | | | | | | | | |
| Document Number/Revision | | Document Number/Revision | | Document Number/Revision | | | | | | | | | | | | |
| N/A | | | | | | | | | | | | | | | | |
| 21. Approvals | | | | | | | | | | | | | | | | |
| Signature | | Date | | Signature | | | | | | | | | | | | |
| Design Authority | | | | Design Agent | | | | | | | | | | | | |
| Cog. Eng. J.N. Strode/V.C. Boyles <i>J.N. Strode</i> | | <u>8/19/98</u> | | PE | | | | | | | | | | | | |
| Cog. Mgr. K.M. Hodgson <i>K.M. Hodgson</i> | | <u>8/19/98</u> | | QA | | | | | | | | | | | | |
| QA | | | | Safety | | | | | | | | | | | | |
| Safety | | | | Design | | | | | | | | | | | | |
| Environ. | | | | Environ. | | | | | | | | | | | | |
| Other J.G. Kristofzski, Process Engineering <i>J.G. Kristofzski</i> | | <u>8/20/98</u> | | Other | | | | | | | | | | | | |
| D.I. Allen, Tank Waste Operations <i>D.I. Allen</i> | | <u>8/19/98</u> | | | | | | | | | | | | | | |
| R.K. Bloom, Liquid Waste Processing Facilities <i>R.K. Bloom</i> | | <u>8/19/98</u> | | DEPARTMENT OF ENERGY | | | | | | | | | | | | |
| B.G. Erlandson, Environmental <i>B.G. Erlandson</i> | | <u>8/19/98</u> | | Signature or a Control Number that tracks the Approval Signature | | | | | | | | | | | | |
| R. L. Treat, Tank Waste Retrieval <i>R. L. Treat</i> | | <u>8/19/98</u> | | ADDITIONAL | | | | | | | | | | | | |

Operation Waste Volume Projection

J.N. Strode/V.C. Boyles
Lockheed Martin Hanford, Corp., Richland, WA 99352
U.S. Department of Energy Contract DE-AC06-96RL13200

EDT/ECN: ECN-643820 UC: 2070
Org Code: 7A140 Charge Code: N16C1
B&R Code: EW 3120074 Total Pages: 93

Key Words: Waste Volume Projection, Tank Space Management Board, Waste Volume Reduction, Double-Shell Tank, Evaporator, LERF

Abstract: Waste receipts to the double-shell tank system are analyzed and wastes through the year 2015 are projected based on generation trends of the past 12 months. A computer simulation of site operations is performed, which results in projections of tank fill schedules, tank transfers, evaporator operations, tank retrieval, and aging waste tank usage.

This projection incorporates current budget planning and the clean-up schedule of the Tri-Party Agreement. Assumptions were current as of July, 1998.

TRADEMARK DISCLAIMER. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.


Printed in the United States of America. To obtain copies of this document, contact: Document Control Services, P.O. Box 950, Mailstop H6-08, Richland WA 99352, Phone (509) 372-2420; Fax (509) 376-4989.

L. Jot

Release Approval

AUG 20 1998

Date



Approved for Public Release

OPERATIONAL WASTE VOLUME PROJECTION

JULY 1998

Prepared by

J. N. Strode
V. C. Boyles

This Page Intentionally Left Blank

TABLE OF CONTENTS

| | | |
|--------------------|---|-----|
| 1.0 | SUMMARY | 1 |
| 2.0 | INTRODUCTION | 7 |
| 2.1 | Purpose | 7 |
| 2.2 | Methodology | 7 |
| 3.0 | GENERAL FACILITY DESCRIPTIONS AND ASSUMPTIONS | 9 |
| 3.1 | B Plant/WESF | 9 |
| 3.2 | 242-A Evaporator and LERF | 10 |
| 3.3 | Grout | 13 |
| 3.4 | Effluent Treatment Facility | 13 |
| 3.5 | PFP | 13 |
| 3.6 | PUREX | 14 |
| 3.7 | S Plant | 14 |
| 3.8 | Salt Well Liquid Pumping | 15 |
| 3.9 | Single-Shell Tank Solids Retrieval | 17 |
| 3.10 | T Plant | 17 |
| 3.11 | Tank Farms | 18 |
| 3.12 | UO ₃ Facility | 21 |
| 3.13 | Waste Sampling and Characterization Facility (WSCF) | 21 |
| 3.14 | 100 Area | 21 |
| 3.15 | 300 Area | 22 |
| 3.16 | 400 Area | 22 |
| 3.17 | Phase 1B Privatization Processing | 23 |
| 3.18 | Phase 2 Privatization Processing | 28 |
| 3.19 | Watch List/Safety | 28 |
| 3.20 | Spare/Contingency Space | 29 |
| 3.21 | Waste Segregation | 29 |
| 3.22 | Loss of DST Space | 30 |
| 3.23 | New DST Construction | 30 |
| 3.24 | DST Tank Solids Levels | 30 |
| 3.25 | IMUST Wastes | 31 |
| 3.26 | Assumption Summary | 31 |
| 4.0 | ASSUMPTIONS FOR PROJECTION CASES 2 AND 3 | 36 |
| 4.1 | Projection Case 2 Assumptions | 36 |
| 4.2 | Projection Case 3 Assumptions | 38 |
| 5.0 | RESULTS AND CONCLUSIONS | 39 |
| 5.1 | Projection Case 1 Results and Conclusions | 42 |
| 5.2 | Projection Case 2 Results and Conclusions | 67 |
| 5.3 | Projection Case 3 Results and Conclusions | 71 |
| 5.4 | Actual Waste Generation Compared to Management Limits | 73 |
| 6.0 | SPACE SAVING ALTERNATIVES | 79 |
| 7.0 | BIBLIOGRAPHY | 81 |
| APPENDICES | | |
| Acronyms | | A-2 |

TABLE OF CONTENTS (CONTINUED)

FIGURES

| | |
|--|----|
| 1. Comparison of the Tank Requirements for the 1998 Projection Cases | 3 |
| 2. Methodology of the OWVP | 7 |
| 3. Double-Shell Tank Requirements for Case 1--TPA Compliant | 45 |
| 4. Double-Shell Tank Inventory and Space for the Case 1 Projection | 47 |
| 5. Facility Waste Generation Graphic | 51 |
| 6. Tank Fill Graphic | 51 |
| 7. Tank Levels During the Short Range Projection | 53 |
| 8. Simplified Schematic of Current and Planned Routings | 54 |
| 9. Dilute Receiver Tanks and 242-A Evaporator Operations | 58 |
| 10. PUREX Facility Waste Generation and Tank Levels | 60 |
| 11. West Area Waste Generation and SY Tank Levels | 61 |
| 12. B Plant and Hanford Facility Waste | 62 |
| 13. AP Farm Tank Levels | 63 |
| 14. AN Farm Tank Levels | 64 |
| 15. Aging Tank Requirements | 65 |
| 16. Aging Waste Tank Usage | 66 |
| 17. Double-Shell Tank Requirements for the Case 2 Projection | 68 |
| 18. Double-Shell Tank Requirements for the Case 3 Projection | 72 |
| 19. Monthly Facility Generations | 75 |
| 20. Comparison of Monthly Average Waste Generation to Target Rate | 76 |
| 21. Monthly Contributions from SWL Pumping | 77 |
| 22. Contributions from Facility TCO | 78 |

TABLES

| | |
|---|----|
| 1. Summary of Assumptions For the 1998 Projection Cases | 4 |
| 2. Risk Assessment Summary for Waste Volume Projections | 5 |
| 3. Historical Evaporator Campaigns Since the 1994 Restart | 12 |
| 4. Salt Well Pumping Schedule for Case 1 (TPA Complaint Case) | 16 |
| 5. Current Operational Tanks and Usage | 19 |
| 6. Summary of In-Tank Washing Activities | 26 |
| 7. Estimated Waste Quantity Processed for Case 1 | 26 |
| 8. Projected Processing Schedule for Phase 1B for Case 1 | 27 |
| 9. Waste Compatibility Matrix | 30 |
| 10. DST Solids Levels (Kgal) | 31 |
| 11. Assumption Matrix | 32 |
| 12. Projected Processing Schedule for Case 2 | 37 |
| 13. Salt Well Pumping Schedule for Case 2 | 38 |
| 14. Spreadsheet of Waste Additions and Reductions for Case 1 | 46 |
| 15. Projected Tank Usage on 9/2001 for the Case 1 Projection | 50 |
| 16. Evaporator WVR and LERF Additions for the Case 1 Projection | 55 |
| 17. Evaporator Campaign Schedule for the Case 1 Projection | 56 |
| 18. Evaporator WVR and LERF Additions for the Case 2 Projection | 69 |
| 19. Evaporator Campaign Schedule for the Case 2 Projection | 70 |
| 20. Comparison of Average Monthly Waste Generation Rates | 73 |

1.0 SUMMARY

The Operational Waste Volume Projection (OWVP) presents a basis for evaluating future Double-Shell Tank (DST) space through FY 2015. This report presents a projected range of tank needs which is used to generate recommendations regarding site activities, waste management activities, facility requirements, and the need to build additional double-shell tanks. This document presents the results of three distinct projections cases. Operating assumptions for the three cases were established prior to July 1998. Operating assumptions and results are summarized below:

- o Case 1 (TPA Compliant) presents projected DST needs based on TPA milestones, TWRS program planning, and the current operational assumptions. The TPA Compliant Case exceeds available space by one tank in FY 2001, by up to two tanks in FY 2005-2007, and by up to seven tanks by FY 2012. Options to reduce the tank space shortage in FY 2012 and beyond include adjusting the SST solids retrieval schedule to match available space or increasing the Phase 1B or Phase 2 processing rates. Please see Section 5.1 for more details.
- o Case 2 presents projected DST needs based on the assumptions received for the May 27, 1998 Alternative Case (DeLozier, 1998) without SST solids retrieval. The May 27, 1998 Alternative Case delayed waste treatment to FY 2006. However, Case 2 delivers additional feed beyond the minimum order quantities through FY 2016. This projection was designed to identify the space available for SST solids retrieval. Please see Section 5.2 for more details.
- o Case 3 was based on the same assumptions as Case 2 and includes TPA Compliant SST solids retrieval schedule from Case 1. As expected, this projection exceeds available space by FY 2004 due to SST solids retrieval. The tank space needs for this projection clearly show that SST solids retrieval should not be started until approximately FY 2007 and that the rate of retrieval should be reduced to match the slower waste treatment schedule built into this projection.

A comparison of the projected tank space needs required for the three projection cases is depicted in Figure 1. Key assumptions for the three projection cases are summarized in Table 1. Differences in assumptions have been highlighted. Detailed assumptions and space saving alternatives are presented later in this document. A brief summary of the risks associated with these projections is provided in Table 2. Additional information and references for Table 2 can be found later in this document by referring to the section listed under comments. At a minimum, this DST space forecast will be updated annually with the latest information available regarding the estimated volume of waste requiring storage in the DSTs.

Areas Requiring Management Consideration

Facility waste minimization requirements initiated by the Tank Space Management Board (TSMB) helped to guarantee tank space availability prior to the 242-A Evaporator restart in FY 1994. However, considering the possibility of future tank space shortages, the Terminal Clean-out (TCO) and monthly waste

generations will continually need to be minimized. The DST Waste Inventory Control Group is a group which meets on a monthly basis to review projected waste generations, waste transfers, and tank configuration control. Issues that cannot be resolved by this group will be elevated to the Feed Process Senior Management board. Should a tank space shortage occur during the projection period (Figure 1), the shortage could be solved using a combination of the following actions (see Section 6.0 for a more complete listing):

- o delay the Single-Shell Tank (SST) interim stabilization
- o delay the SST solids retrieval
- o accelerate processing and vitrification of waste
- o establish Phase 2 contract terms for privatization to require rates of retrieval and processing equivalent to TPA rates
- o construct new double-shell tanks

Approximately 6-8 years are required to build additional double-shell tanks (DSTs). The TPA Compliant Case presented in this document projects that tank space needs will be at or exceed the available space during the FY 2005-2007 and FY 2011-2014 timeframes. With the proposed delay in the treatment schedule for LAW and HLW, there will be a definite DST space problem if the SST retrieval schedule does not change. There is still time to resolve the tank space shortage issue and as the new RL and TPA agreements are better understood, a new OWVP projection will be completed. In addition, a number of space saving options are presented to rectify the tank space shortage. This document is recommending that further review of the final privatization contract be conducted and the space saving options, the budget, and the projection assumptions be monitored closely over the next year. In the event additional tanks are needed as a result of the proposed privatization schedule, there will be adequate time next year to prepare for the additional tanks.




Figure 1. Comparison of Tank Requirements for 7/98 Projection Cases

Table 1. Summary of Assumptions For the 1998 Projection Cases (references in Sect. 3)

| Facility or Project | Case 1 Assumptions | Case 2 Assumptions | Case 3 Assumptions |
|---|---|---|---|
| Total Monthly Facility Generations | 15.2-16.6 Kgal/month | 15.2-16.6 Kgal/month | 15.2-16.6 Kgal/month |
| PUREX Misc After TCO Completed | 5 Kgal/year DN | 5 Kgal/year DN | 5 Kgal/year DN |
| B Plant TCO | TCO Complete FY 1998 (103 Kgal) | TCO Complete FY 1998 (103 Kgal) | TCO Complete FY 1998 (103 Kgal) |
| 100N Area TCO | Wastes sent to ERDF | Wastes sent to ERDF | Wastes sent to ERDF |
| 100K Area TCO | TCO FY 2003 (0.35 Mgal DN) | TCO FY 2003 (0.35 Mgal DN) | TCO FY 2003 (0.35 Mgal DN) |
| 105 F & H Basin Cleanout | TCO FY00-05 (0.24 Mgal DN) | TCO FY00-05 (0.24 Mgal DN) | TCO FY00-05 (0.24 Mgal DN) |
| Evaporator Operation Outage | Operates as required through 2015 except for one year outage in FY 2004 | Operates as required through 2015 except for one year outage in FY 2004 | Operates as required through 2015 except for one year outage in FY 2004 |
| Liquid Effluent Treatment Facility Rate (Mgal/Year) | 50 | 50 | 50 |
| SST Stabilization Porosity Saltcake/Sludge Complexed SWL Volume Pumped | 50%/21% 1.64 Mgal 5.36 Mgal (1998-2000) | 50%/21% 1.64 Mgal 5.36 Mgal (1998-2004) | 50%/21% 1.64 Mgal 5.36 Mgal (1998-2004) |
| PPF Stabilization | 27 Kgal (FY 1998-2006) | 27 Kgal (FY 1998-2006) | 27 Kgal (FY 1998-2006) |
| Tank 101-SY Processing Dilution | No Dilution until 1/2007 | No Dilution until 1/2008 | No Dilution until 1/2008 |
| Tank 103-SY Processing Dilution | No Dilution until 5/2007 | No Dilution until 4/2010 | No Dilution until 4/2010 |
| SST Solids Retrieval 106-C solids (start; receiver tank) SST Solids Retrieval Start Rate SST Waste Retrieval Complete SST Site Closure Complete | TPA Compliant 9/1998; Tank 102-AY 12/2003 2.8 Mgal in FY 2004-2005; 3.6 Mgal in FY 2006-2007; FY 2018 FY 2024 | No SST Solids Retrieval--determine space available. | TPA Complaint 9/1998; Tank 102-AY 12/2003 2.8 Mgal in FY 2004-2005; 3.6 Mgal in FY 2006-2007; FY 2018 FY 2024 |
| Phase 1B Privatization Processing startup | 06/2002 | 05/2006 | 05/2006 |
| LAW Processing Rate (Mgal/Yr) | 2.03 in 1st Year (6/2002-5/2003) 2.22 in 2nd Year | 2.0 in 1st Year (5/2006-4/2007) 2.0 in 2nd Year | 2.0 in 1st Year (5/2006-4/2007) 2.0 in 2nd Year |
| Phase 1 Extension | Yes - Through Maximum Order Quantities | Yes - Through FY 2016 | Yes - Through FY 2016 |
| LAW Vendor Feed Tanks LAW Intermediate Feed Staging Tanks Sr/TRU & Entrained Solids Receipt Tank Aging Waste Supernate Receipt Tank | 2 2 1 0 | 1 2 1 1 | 1 2 1 1 |
| Phase 2 Privatization Maximum Processing Rate, Mgal/Yr @ 7M Na Maximum Processing Rate, Mgal/Yr @ 5M Na HLW Vitrification startup HLW Return Tanks | 2011 17.2 24.1 2013 3 | Not included by end of FY 2015 | Not included by end of FY 2015 |
| In-Tank Washing (FY 1998-2004) Consolidate NCAW solids Consolidate NCAW supernates to | Case 8 Modified (Sect. 3.17) No 101-AY + 1 DST | Not included. Vendor washes NCAW solids. | Not included. Vendor washes NCAW solids. |
| Evaporation Limit for Wastes--SpG | 1.41 | 1.41 | 1.41 |
| Spare Space | 2.28 | 2.28 | 2.28 |
| Contingency Tank | None | None | None |
| Loss of DST Space | None | None | None |

Table 2. Risk Assessment Summary for Waste Volume Projections

| RISK ASSESSMENT SUMMARY FOR WASTE VOLUME PROJECTIONS | | | | | | | | | |
|--|---|-----|----|------------------------------|-------|----------------------------------|--|---------|--|
| Technical/Program Basis for Waste Volume Projections | Confidence of Basis Being Accurate | | | Waste Volume Impact if Wrong | | | Consequence if Assumption Wrong | | COMMENTS |
| | HIGH | MED | LO | MAJOR | MINOR | QUANTITY | MAJOR | MINIMAL | |
| Remaining SWL pumping volume is ~5.36 Mgal without flush or dilution | | X | | X | | Dependent on magnitude of change | X | | Delay TPA milestones; Large concentrated volume; see Section 3.8; Could prevent initial feed staging for Phase 1 LAW Privatization |
| CC waste will not solubilize the TRU sludge in Tank 102-SY | | X | | X | | Dependent on magnitude of change | X | | Could delay SWL pumping TPA milestones; see Section 3.8 |
| 242-A Evaporator available with one outage in FY 2004 | X | | | X | | Dependent on magnitude of change | X | | Tank Space Projections based on concentrated volumes; see Section 3.2 |
| Evaporation limit for new DSSF will be SpG of 1.41 | | X | | X | | Dependent on magnitude of change | X | | Reduction in SpG could be required by safety; Section 3.2 |
| Facility generations will not exceed TPA Compliant Case levels | | X | | | X | Dependent on magnitude of change | | X | Small concentrated volume; could delay site cleanup; see Section 3.0 |
| Facility TCO volumes: 100 Areas <0.6 Mgal | | X | | | X | Dependent on magnitude of change | | X | Could delay site cleanup; see Section 3.0 |
| No loss of DST space | X | | | X | | 1 mgal/tank | X | | see Section 3.22 |
| LAW Phase 1 treatment starts FY02; ~2.2 Mgal/yr | | | X | X | | Dependent on magnitude of change | X | | Could delay SST solids retrieval (TPA); Section 3.17 |
| LAW Phase 2 treatment starts FY11; 24.1 Mgal/yr | | | X | X | | Dependent on magnitude of change | X | | Could delay SST solids retrieval (TPA); Section 3.18 |
| Crossite transfer lines are available | X | | | X | | Dependent on magnitude of change | X | | Could delay SWL pumping TPA milestones and/or site cleanup; see Section 3.11 |
| Use Grout in emergencies to free up 2-3 Mgal of space | | X | | X | | Dependent on magnitude of change | X | | DOE and public acceptance unlikely; see Sections 3.3 & 5.1 |
| No volume set aside for upsets or new streams | | X | | | X | Dependent on magnitude of change | X | | Consequences depend on volume, composition, and timing see Section 3.20 |

This Page Intentionally Left Blank

2.0 INTRODUCTION

2.1 Purpose

The purpose of the Operational Waste Volume Projection (OWVP) is to present a basis for evaluating future Double-Shell Tank (DST) needs to meet Tri-Party Agreement (TPA) Milestones M-46-00 and M-46-01. Milestone M-46-00 states that an OWVP report shall be prepared and issued annually evaluating DST needs. Milestone M-46-01 requires the Tank Waste Remediation System (TWRS), to review and recommend whether or not to build additional DSTs on an annual basis.

This report presents a projected range of tank needs which is used to generate recommendations regarding site activities, waste management activities, facility requirements, and the need to build additional DSTs. This document presents the results of three projected cases which represent varying degrees of tank space demands. All projected cases incorporate the "privatization" of waste treatment and disposal. The term "privatization" refers to the DOE strategy for phased retrieval and treatment of Hanford tank wastes which would use private contractors to design, permit, build, operate, and deactivate the facilities for waste treatment and immobilization (DOE, 1995). Case 1 is intended to present tank space needs based on all TPA milestones, TWRS program planning, and current operational assumptions. Cases 2 and 3 have a later starting date for treatment than Case 1. Case 2 does not include single-shell (SST) solids retrieval. Operating assumptions for the three cases were established prior to July 1998. Need dates for new DST construction, tank retrievals, facility schedules, waste generation reductions, conflicts in meeting TPA milestones (WDOE, 1994; WHC, 1996a; WHC, 1996b), and funding priorities can then be reviewed in relation to tank space availability.

2.2 Methodology

The process followed in preparing an OWVP is shown in Figure 2, below.




Figure 2. Methodology of the OWVP

The process of updating the OWVP begins with the request for updated facility or project "assumptions" from each of the operating facilities and projects that will contribute waste to DST inventory. The term "assumption" in this document refers to engineering inputs or bases supplied by the facilities based on their future operational plans (determined by budget, DOE directive, TPA milestones, etc.). Typical assumptions include operating schedules, waste generation rates, stream compositions, modes of operation, etc. The operating facilities and projects provide estimates of volume, composition, and radionuclide content data for each distinct waste stream exiting the facility. In addition to the projected facility waste generation rates, the processing schedules of each of the plants are factored into the projection. For the Plutonium-Uranium Extraction (PUREX) facility, B Plant, and 100 Area facilities the projected volumes of waste generated from Terminal Clean-out (TCO) are estimated and entered. For the Plutonium Finishing Plant (PFP), 300 Area, 400 Area, and Tank Farms, monthly waste generations are entered from facility inputs and/or actual observed generation rates. These projected waste generation rates and plant schedules are used to project waste volumes that each plant will be producing per month or year. The composition data is used to calculate Waste Volume Reduction Factors (WVRFs) and to determine waste segregation requirements (due to chemical, radionuclide, or heat content). The WVRF (Riley, 1988) is defined as the percent of water (by volume) that can be removed from a waste stream to achieve a certain interim waste form such as double-shell slurry feed. From the facility assumptions, a matrix of basic assumptions for the three cases to be incorporated into the OWVP projections were prepared and presented to Hanford contractor management and program office for approval.

Once the projection cases have been approved, the database of past waste gains, transfers, and evaporations is updated with data from the most recent months of Tank Farm operations. The early years of the projection are simulated in more detail than the later years. In the first period of the projection, monthly waste volumes are predicted. For the last years of the projection, yearly waste volumes are predicted.

The processing sequence in the simulation is designed to model the actual activities in the tank farms. After a dilute receiver tank is filled with waste, the contents are transferred to an available holding tank, sampled (sampling and analysis require four months), and transferred to the 242-A Evaporator feed tank (Tank 241-AW-102¹) for evaporation. After dilute waste is concentrated in the 242-A Evaporator, it is sent to a slurry receiver tank (Tank 106-AW) as Double-Shell Slurry Feed (DSSF) which will eventually be disposed of through the Low-Activity Waste (LAW) processing and vitrification process.

The processing sequence for the Neutralized Current Acid Waste (NCAW) solids is for the solids to be washed in-tank and then immobilized in the High-Level Waste (HLW) vitrification plant. The separated supernates and washes will be pretreated to form high-level and low-activity waste streams. The HLW vitrification facility will incorporate high-level and transuranic (TRU) wastes into a glass matrix for disposal. The low-activity waste stream will be sent to LAW vitrification for final disposal.

¹ Waste tanks are hereafter referred to in an abbreviated form; for example, Tank 102-AW.

3.0 GENERAL FACILITY DESCRIPTIONS AND ASSUMPTIONS

A brief description of the facilities and projects pertinent to the Case 1 projection are listed in the following section. Assumptions unique to the Case 2 and Case 3 projections are described in Section 4. Facility operating dates, waste generation volumes, WVRFs, flushes, and other pertinent assumptions are described. This information has been summarized for each of the three cases in Table 11, which is included at the end of this section. The spreadsheet for the Case 1 projection (Section 5.1) lists the waste generations for each year for facilities that presented a range of waste generation rates (e.g., T Plant varied from 1.4 to 2.7 Kgal/month during the period FY 1998-2015).

This year, there has been an attempt to totally integrate the OWVP and Disposal Engineering assumptions and the integration is good through the end of Phase 1 (circa FY 2011). Phase 1 processing assumptions, tank usage, and the order of processing were furnished by Disposal Engineering (Kirkbride, 1997) and are consistent between the two projects. The SST solids schedules and Phase 2 assumptions used in this document were drafts furnished by Disposal Engineering. Phase 2 assumptions furnished by Disposal Engineering consisted of waste workoff rates (Wittman, 1997a and 1997b). The HLW return refers to the entrained solids returned to Tank 107-AP from the private contractors during Phase 1. Since the detailed amount and nature of this stream were not available, an entire DST was allocated to their storage. This stream includes Sr/TRU for Case 1, but only entrained solids for Cases 2 and 3. The OWVP and Disposal Engineering assumptions will be further integrated in next year's OWVP document.

3.1 B Plant/WESF

B Plant was constructed in 1945 to recover plutonium by the bismuth phosphate process. The facility was refurbished in 1967 to recover cesium and strontium byproducts from the high level waste tanks (Simmons, 1998). In 1974, the Waste Encapsulation and Storage Facility (WESF), was constructed on the west end of B Plant to support B Plant's mission. WESF's original mission was to encapsulate, cool, store, and monitor the high heat generating cesium and strontium capsules. The byproduct recovery mission was completed in FY 1984 after which B Plant was considered for waste processing. B Plant is no longer considered a viable option for processing of Hanford tank waste and is presently transitioning to shutdown in FY 1998.

B Plant discharges a low-level miscellaneous waste stream (dilute non-complexed waste) resulting from cell drainage, vessel clean-out, condensate collection, etc. Future TCO activities will generate wastes that can be separated into three categories (Smith, 1994): 1) aqueous phase waste generated during organic solvent removal (may be complexed waste); 2) dilute non-complexed (DN) waste; and 3) uncharacterized waste resulting from vessel flushing (assumed to be DN waste). Uncharacterized wastes will be characterized when they are produced.

For all projection cases, it was assumed that plant stabilization would be completed in 1998 and that the remaining volume of waste would be 103 Kgal (Simmons, 1998). When B Plant has completed TCO, WESF will continue to

generate approximately 5 Kgal/year of waste from 1998-2028. The WVRF to evaporate either B Plant miscellaneous or TCO waste to DSSF is 99% (Sederburg, 1995). No flushes are anticipated for B Plant miscellaneous or TCO streams based on their dilute nature and lack of solids.

All three cases in this document were based on the waste generations described above. The upper waste rate supplied by B Plant engineers (Simmons, 1998) would have increased the remaining B Plant TCO volume from 103 Kgal to 140 Kgal.

3.2 242-A Evaporator and LERF

The 242-A Evaporator was restarted on April 15, 1994. To understand the projection model for the 242-A Evaporator, it is necessary to understand the waste flow during evaporator operation and the simulation model. Waste from the dilute holding tanks are transferred into the evaporator feed tank (Tank 102-AW). Waste in the feed tank is then transferred to the 242-A Evaporator for boil-down. In the evaporator operation, four to six months is required for wastes to be sampled and analyzed per Evaporator DQO requirements (Von Barga, 1995) before they can be evaporated.

- o This projection model assumed that the 242-A Evaporator would operate in a "Linked Run" process mode (Guthrie, 1993). A "Linked Run" is a continuous operation of the 242-A Evaporator, made possible by simultaneously transferring from the DST's to the Evaporator feed tank (Tank 102-AW).
- o A period of four months is required from the time a holding tank is filled with dilute wastes before the waste can be evaporated. This period allows time for sampling, analysis, documentation, and facility preparation (Guthrie, 1997b).
- o In the computer simulation, dilute waste is transferred to the evaporator feed tank (Tank 102-AW) for evaporation. Provided the waste has not reached its concentration limit, evaporation is continued until the maximum Waste Volume Reduction (WVR) is achieved.
- o The desired WVR for each 242-A Evaporator campaign is determined by boil-down studies, computer simulation, and/or process control sampling. The concentration of waste increases after each pass through the Evaporator until it reaches a concentration level consistent with engineering studies. The waste volume projection model of the 242-A Evaporator operation used in these projections cases produced DSSF with a specific gravity of 1.41. Upon reaching the desired concentration level, the concentrated waste is transferred to the evaporator receiver tank (Tank 106-AW). At the end of a campaign or when Tank 106-AW has been filled, DSSF is transferred to another DST holding tank.
- o The Liquid Effluent Retention Facility (LERF) has a 6.5 million gallon storage capacity (Basin 42) for evaporator process condensate (Guthrie, 1997a).

- o The ratio of process condensate sent to LERF for every gallon of Waste Volume Reduction (WVR) for Evaporator Campaigns 94-1, 94-2, and 95-1 was 1.29, 1.24, and 1.26, respectively (Guthrie, 1996). The evaporator seal water and demister spray upgrade could reduce future process condensate production to 1.15 gallon of condensate/gallon of WVR which would lower the value used for future projections. This projection used a value of 1.20 gallon of condensate/gallon of WVR (Guthrie, 1997b). The Effluent Treatment Facility started to process the condensate stored in LERF Basins 42 and 43 in November 1995 and processed all stored condensate by August 1996 (Wagner 1996). Since the Effluent Treatment Facility has a capacity of approximately 50 Mgal/year (Wagner, 1996), it was assumed that LERF capacity would not limit future evaporator operations.
- o The maximum monthly WVR during Evaporator operation should be approximately 1500 kgal/month based on a near optimum Campaign 94-2 and 96-1 performance with approximately a 50% initial WVR per pass through the evaporator (Guthrie, 1997b).
- o An average evaporation rate of 500 Kgal/month (Guthrie, 1997b) was used in this simulation taking in to consideration:
 - the 242-A Evaporator historical processing rates
 - downtime between campaigns
 - waste characterization
 - staging and tank transfers
- o The simulation used in this projection evaporates all dilute wastes to a concentrated interim storage form in the same year that a tank has been filled. This assumption is valid if the evaporator is operating and the yearly waste generation rate has not exceeded the annual WVR limit of the evaporator. Historically, dilute wastes were concentrated to near the aluminate boundary which would produce concentrated wastes with a specific gravity which could range from 1.3 to 1.67. However, it has been noted that all of the DSTs currently on the Flammable Gas Watch List (i.e., tanks with safety concerns related to hydrogen build-up) have specific gravities greater than 1.4 (Reynolds, 1994). To avoid production of future Flammable Gas Watch List tanks, it has been proposed that all future waste concentrations should be limited to a specific gravity of 1.41 unless additional technical evaluation shows flammable gas will not build-up (Fowler, 1995 and Mulkey, 1997).

The waste volume projection model of the 242-A Evaporator operation used in projections thru 1994, typically produced DSSF with a specific gravity of 1.50-1.55. Reducing these wastes to a specific gravity of 1.41 could increase waste storage volumes by approximately 22-35 percent, depending on the chemical composition of the waste. Although the evaporation limit for concentrated wastes was a specific gravity of 1.41, the first five evaporator campaigns in Table 3 (94-1 thru 97-1) produced concentrated wastes with a specific gravity close to 1.3 (Guthrie, 1997a). Evaporator campaign 97-2 did evaporate waste to a specific gravity of approximately 1.4. This document projects DST needs based on the evaporation of wastes to a specific gravity limit of 1.41.

- o The waste volume reductions achieved by the 242-A Evaporator since its restart in 1994 are summarized in Table 3.

Table 3. Historical Evaporator Campaigns Since the 1994 Restart

| Campaign | Start Date | Waste Source | Waste Feed Type | Approximate WVR, Mgal |
|----------|------------|--|-----------------|-----------------------|
| 94-1 | 4/94 | 102-AW, 106-AW, & 103-AP | DN | 2.42 |
| 94-2 | 9/94 | 102-AW, 106-AW, 101-AP, 107-AP, & 108-AP | DN | 2.79 |
| 95-1 | 6/95 | 102-AW, 106-AW, 107-AP, & 108-AP | DN | 2.16 |
| 96-1 | 5/96 | 102-SY, 105-AW, & 102-AY | DN | 1.12 |
| 97-1 | 3/97 | 101-AN | DN-SWL | 0.4 |
| 97-2 | 9/97 | 101-AY and 106-AN | DC | 0.7 |

- o No evaporator campaigns were projected for FY 1998. A cold run to be completed by September 1998 will add 50-65 Kgal of water to DSTs.
- o The next evaporator campaign (99-1) will start in March 1999, to evaporate dilute waste from Tanks 102-AY, 106-AP, 101-AN, and 108-AP.
- o All projection cases assumed that evaporation capability would be available annually to evaporate all dilute wastes except for the one year outage in FY 2004. The annual evaporation of dilute waste minimizes tank space requirements and allows site cleanup activities to continue unabated. [Late Note: The life of the 242-A Evaporator will be extended through the end of Phase I (2018). Evaporator upgrades will be completed by 2005. It is assumed that the Phase II waste processing contractor will provide evaporator capability during Phase II Operations. (O'Toole, 1998).]
- o Previous projections assumed that the 242-A Evaporator would require a 1 year outage for maintenance and or upgrades every 10 years based on a 10 year design life of the 242-A Evaporator (Miskho, 1990). All three projection cases assumed a one year outage in FY 2004 (Guthrie, 1997b).
- o Evaporator certification training runs prior to evaporator operation will add approximately 50 Kgal to tank farms and 50 Kgal to the LERF and will occur on a bi-yearly basis (Guthrie, 1997b). The training run in April 1995, added 57 Kgal to DSTs.
- o Evaporator flushing after each campaign was previously projected to add 35 Kgal/campaign (Haigh, 1992). Actual flushes for the first three campaigns completed since April 1995 have varied from 27 to 58 kgal/campaign.
- o For the years 1999-2004, it was estimated that 1 to 2 campaigns would be required each year based on waste generations, segregation requirements, and tank space availability. The additional yearly campaigns would be needed to evaporate the anticipated increased SWL (complexed and non-complexed) and TCO wastes. The WVR for evaporation of these flushes to DSSF was 99 (Sederburg, 1995).

3.3 Grout

- o No additional Grout Vaults are scheduled to be poured at the Hanford site. TWRS program planning requires that all tank wastes be separated into low-activity and high-activity fractions and each fraction be immobilized into suitable waste forms for ultimate disposal. Tanks that were originally designated and set aside as grout feed tanks were used for other purposes.

3.4 Effluent Treatment Facility

- o A new facility called the Effluent Treatment Facility (ETF) started operation in November 1995 to process the stored evaporator condensate from the LERF, newly generated evaporator condensate, and aqueous waste water containing low specific radioactivity (Wagner, 1996). Treated effluent is discharged to the State Approved Land Disposal Site (SALDS), north of the 200 West Area. This site was chosen to allow tritium to decay away before the groundwater migration reaches the Columbia River. The ETF does not remove tritium because no feasible production-scale tritium removal technology presently exists. The ETF has a capacity to treat 50 Mgal/year for future feeds. The ETF should not send any streams to DSTs.

3.5 PFP

The Plutonium Finishing Plant (PFP) is a facility in the 200 West Area which houses the processes and supporting operations for (Funston, 1997):

- 1) stabilization of reactive solid residues by muffle furnace calcination (OPERATIONAL);
- 2) shipping, receiving and storage of special nuclear materials (OPERATIONAL);
- 3) analytical and development laboratories (OPERATIONAL);
- 4) treatment and handling of PFP liquid wastes destined for tank farms and the ETF (OPERATIONAL).

An Environmental Impact Statement (EIS) was issued for public comment in November 1995 covering the PFP facility stabilization and clean out. The PFP EIS and Record of Decision (ROD) was published in May 1996. The waste volume projections are based on the preferred alternatives identified in the EIS for facility cleanout and stabilization. The volume of waste anticipated to be produced for the TPA Compliant Case is developed from the existing waste generation rate at PFP (100 untreated gallons/month), and the anticipated use of a direct denitration vertical calciner coupled with an ion exchange processing system currently being developed and tested by the development laboratories. The vertical calciner is the most promising technology for plutonium residue stabilization and facility clean out. All projection cases projected that PFP stabilization and clean out would generate 27 Kgal of additional waste from 1998 through 2006 (Funston, 1997). The WVRF to evaporate PFP wastes to DSSF is 81% (Sederburg, 1995). Flush volumes for PFP stabilization waste streams is 22 per cent (flushes of waste transfer lines from PFP to 244-TX and from 244-TX to Tank 102-SY).

The percent solids experienced in past PFP waste generations are listed below (Barrington, 1991):

| | |
|-----------------------|------|
| % Solids in PRF waste | 3.5% |
| % Solids in RMC waste | 4.4% |
| % Solids in lab waste | 4.5% |

3.6 PUREX

The Plutonium Uranium Extraction (PUREX) Facility was used to separate irradiated N Reactor fuel into plutonium nitrate, uranyl nitrate hexahydrate (UNH), neptunium nitrate, and waste products. The main processing operations involved dissolution of cladding and irradiated fuel, solvent extraction and conversion of plutonium nitrate to plutonium oxide. Acid recovery, solvent treatment systems, and off-gas treatment supported the major processes.

The deactivation of PUREX was completed in FY 1997 and the waste transfer system has been deactivated. However, condensate is collected in the PUREX main stack catch tank (216-A-TK-2) and the #2 Filter catch tank (V11-1). This accumulation would result in approximately 5 Kgal of dilute waste being transferred to tank farms once per year (Eiholzer, 1997).

All three projection cases projected 5 Kgal/year of waste additions from PUREX. Based on the average waste composition presented for PUREX TCO wastes, the WVRP for evaporation of PUREX TCO wastes to DSSF is 99% (Sederburg, 1995). Flush volumes for PUREX TCO waste streams are 10 per cent.

3.7 S Plant

S Plant (or 222-S Labs) is a dedicated laboratory facility. The Laboratory currently provides analytical chemistry services in support of Hanford processing plants and tank characterization. Emphasis is on waste management processing plants, environmental monitoring programs, B Plant, Tank Farms, 242-A Evaporator, Waste Encapsulation Storage Facility (WESF), Plutonium Finishing Plant (PFP), research support activities, and essential materials. Most of the radioactive liquid waste generated at the laboratory complex originates from analytical activities performed within the 222-S Laboratory in support of tank characterization (Tollefson, 1998). Radioactive and radioactive hazardous (mixed) wastes generated by the 222-S Laboratory are discharged to the 219-S Waste Handling Facility. Dilute, non-complexed wastes are currently being transferred via pipeline to Tank 102-SY. Projected S Plant monthly waste generations rates (Tollefson, 1998) were approximately 1.0 to 1.7 Kgal/month for FY 1998 through 2028 for all projection cases. Based on the waste composition presented for 222-S Laboratory wastes, the WVRP for evaporation of 222-S miscellaneous wastes to DSSF is 99% (Sederburg, 1995). Flush volumes for 222-S waste streams is 22 per cent.

3.8 Salt Well Liquid Pumping

Salt Well Liquid (SWL) pumping will occur for single-shell tanks (SSTs) which have 50,000 gallons or more of drainable interstitial liquid. Pumping is scheduled to stop when the output rate decreases to 0.05 gallons per minute. SWL pumping assumptions for all three projection cases are listed below:

- o A 50 percent saltcake porosity/21 percent sludge porosity were used to estimate the remaining SWL volume, resulting in a remaining volume of 5.36 million gallons (Brown, 1996) without flush and dilution. The pumping schedules used for this year's projections are covered later in this section. The WVRF for evaporation of dilute non-complexed (DN) SWL to DSSF is 47% (Sederburg, 1995). The WVRF for evaporation of dilute complexed (DC) SWL to Complexant Concentrate (CC) is 10% (Sederburg, 1995). [Late Note: Estimate of remaining SWL volume could be increasing to 6.2 million gallons without flush (Schreiber, 1998).]
- o It was projected that dilution and flushing of the salt well liquid and transfer lines would generate approximately 1.53 Mgal (28 percent) of water. The WVRF used for this flush is 99% (Sederburg, 1995).
- o Approximately 1.64 Mgal (30 percent) of the total SWL volume is complexed based on available analytical information.
- o Based on the latest SWL pumping project plan (Ross, 1998), Tanks 101-AN, 106-AP, and 108-AP were used as the 200 East Area receiver tanks.
- o Pumping SWL in West Area presents special problems due both to the limited tank space available and due to the transuranic (TRU) heel in Tank 102-SY. Tanks 101-SY and 103-SY contain complexed waste and are also designated as Watch List Tanks. Addition of waste to Watch List tanks is prohibited unless a safer alternative cannot be found.

Therefore, Tank 102-SY was designated as the West Area SWL receiver for both non-complexed and complexed SWL. Tank 102-SY contains approximately 123 Kgal of TRU solids (Table 10) that are not scheduled to be retrieved until January 2006. Historically, complexed waste and TRU wastes have been segregated to minimize the amount of waste requiring more expensive disposal and to comply with U.S. Department of Energy (DOE) Order 5820.2A. The Hanford Site has implemented this order by segregating waste that was considered complexed (greater than 10 grams/liter total organic carbon) from TRU waste sludge (Reynolds, 1995). The schedule presented in Table 4 would require pumping complexed SWL over the sludge in Tank 102-SY in order to meet TPA milestones for the years 1998-2000. Studies are being conducted to resolve this issue and to determine exactly how much of the waste in the 200 West Area are complexed (Estey, 1996). Some options include--delaying complexed SWL pumping in West Area until Tank 102-SY solids are retrieved; accelerating the retrieval of the TRU solids from Tank 102-SY; dilution and retrieval of the waste from either Tank 101-SY or 103-SY to free up additional tank space; conduct experiments to prove the

complexed SWL can be added to the TRU solids in Tank 102-SY without solubilizing the TRU; or use a DCRT to pump complexed SWL to East Area without sending the waste to Tank 102-SY. In this projection, the complexed wastes are shown being pumped to Tank 102-SY to meet the current TPA schedule.

- o For projection Case 1 (TPA Compliant Case), it was assumed that all SWL would be pumped from FY 1998 through the end of FY 2000 to meet TPA milestone M-41-00 (volume for Tank 106-C included with single shell tank solids retrieval). Historical pumping volumes and the projected SWL pumping volumes (without flush) for Case 1 are presented in Table 4. [Late Note--SWL pumping schedules, volumes, and budgets are currently being reviewed with Ecology to determine which SWL pumping schedules are actually achievable.]

Table 4. Salt Well Pumping Schedule for Case 1 (TPA Complaint Case)

| Salt Well Pumping Schedule for 50% Saltcake/21% Sludge Porosity (Brown, 1996) | | | | | |
|---|-----------|----------|-----------|----------|-----------|
| FISCAL YEAR | EAST AREA | | WEST AREA | | TOTALS |
| | DN | DC | DN | DC | |
| Historical SWL Pumping 1989-1997 | | | | | |
| 1989 | 55 KGAL | 0 KGAL | 0 KGAL | 17 KGAL | 72 KGAL |
| 1990 | 44 KGAL | 0 KGAL | 0 KGAL | 0 KGAL | 44 KGAL |
| 1991 | 227 KGAL | 0 KGAL | 0 KGAL | 0 KGAL | 227 KGAL |
| 1992 | 121 KGAL | 0 KGAL | 0 KGAL | 0 KGAL | 121 KGAL |
| 1993 | 0 KGAL | 0 KGAL | 37 KGAL | 0 KGAL | 37 KGAL |
| 1994 | 189 KGAL | 0 KGAL | 32 KGAL | 0 KGAL | 221 KGAL |
| 1995 | 194 KGAL | 105 KGAL | 18 KGAL | 0 KGAL | 317 KGAL |
| 1996 | 22 KGAL | 0 KGAL | 218 KGAL | 0 KGAL | 240 KGAL |
| 1997 | 23 KGAL | 0 KGAL | 140 KGAL | 0 KGAL | 163 KGAL |
| Projected SWL Pumping 1998-2000 (without flush) | | | | | |
| 1998 | 0 KGAL | 0 KGAL | 238 KGAL | 0 KGAL | 238 KGAL |
| 1999 | 803 KGAL | 696 KGAL | 1013 KGAL | 0 KGAL | 2512 KGAL |
| 2000 | 15 KGAL | 67 KGAL | 1677 KGAL | 874 KGAL | 2633 KGAL |
| TOTAL 1998-2000 | 818 KGAL | 763 KGAL | 2928 KGAL | 874 KGAL | 5383 KGAL |

- o For projection Cases 2 and 3, it was assumed that SWL pumping would be completed by the end of FY 2004 (Ross, 1998). The projected pumping volumes for Cases 2 and 3 are presented in Section 4.1.

3.9 Single-Shell Tank Solids Retrieval

- o This projection assumed that the retrieval of Tank 106-C solids would be started in September 1998 and completed by June 1999 (Kirch, 1997). Initially, approximately 170 Kgal of solids would be retrieved. Retrieval of Tank 106-C solids will require approximately a 3:1 ratio of dilution water to solids (Estey, 1994). Solids retrieved from Tank 106-C will be stored in Tank 102-AY.
- o Approximately 11.9 Mgal of sludge and 22.9 Mgal of saltcake will be retrieved from SSTs (Hanlon, 1998). Dilution of these solids for retrieval and processing results in a total retrieved volume of approximately 108 Mgal (Penwell, 1998a).
- o Saltcake would be diluted to 5 M Na and sludge will be diluted to 10 weight percent solids (Kirkbride, 1997). Approximately a 3:1 ratio of dilution water to solids will be required for the retrieval of the remaining SST solids. It is further assumed that all solids will be removed from the SSTs and that SST site closure will be complete by FY 2024 (M-45-06).
- o For projection cases 1 and 3, the retrieval schedule for SST solids is based on information received from Disposal Engineering (Penwell, 1998a) which will start retrieval in December 2003 (M-45-03-T1) and was completed by the end of FY 2018 (TPA milestone). The retrieved volume of waste for this case is approximately 2.8 Mgal for FY 2004-2005 and an additional 3.6 Mgal for FY 2006-2007. By the end of FY 2013, this year's schedule would retrieve 10.9 Mgal more waste than the schedule used for the 1997 OWVP. The larger volume retrieved by the end of FY 2013 was caused in part by the restriction to retrieve one SST/farm at a time with the exception of TX farm, which can have two simultaneous retrievals after completion of the TY farm retrieval. This restriction on the number of SSTs to be retrieved at one time has caused more waste to be retrieved earlier (Penwell, 1998b). The as retrieved volumes for the remaining SST solids are shown in the spreadsheet for the TPA Compliant Case (Section 5.1) and are based on retrieval at 5 M Na.

3.10 T Plant

T Plant's primary mission is decontamination and treatment of radiologically and chemically contaminated waste and equipment located throughout the Hanford site (McDonald, 1997). T Plant also provides inspection and repackaging services to various Hanford facilities. The 2706-T Low-Level Decontamination Facility (where low-level equipment decontamination is performed) is an approved decontamination facility that commenced operation in September 1994. Limited 221-T canyon decontamination activities (primarily Tank Farms long-length contaminated equipment) were initiated in 1995.

T Plant is currently testing new decontamination techniques (ice blasting and CO₂ decontamination systems) which have reduced liquid waste generations from

those reported previously. Dilute, non-complexed wastes collected at T Plant during decontamination, repackaging, condensate collection, or railcar certification are currently being transported to 204-AR vault via railcar. These wastes contain approximately 5 volume percent solids (McDonald, 1997). Projected T Plant monthly waste generations (McDonald, 1997) were based on a combination of anticipated work loads and actual observed generation rates. The projected volumes supplied by T Plant engineers ranged from 1.4 Kgal/month to 2.7 Kgal/month (the exact waste volume generation used for each year is shown in the spreadsheet for the TPA Compliant Case--Section 5.1). All three projection cases used the same generation rates. The WVRF for evaporation of T Plant miscellaneous wastes to DSSF is 99% (Sederburg, 1995). Flush volumes for T Plant waste streams are 22 per cent.

3.11 Tank Farms

There are currently 28 double-shell tanks (DSTs) used to receive, store, and evaporate the liquid wastes generated at the Hanford facilities to an interim waste form. The interim waste form (e.g., DSSF) is currently stored in tank farms awaiting processing and vitrification for final disposal. Tank farm waste generation sources and operational considerations are listed below for the aging and non-aging waste tanks. Tank Farm waste generations are primarily from line, cross-site, and air-lift circulator flushes.

Aging Double-Shell Tanks

Four of the DSTs (AY and AZ farms) are designated as aging waste tanks and were designed to store high-heat wastes (e.g., NCAW wastes or wastes containing high-heat loads due to the presence of ^{90}Sr or ^{137}Cs). The aging waste tanks are equipped with condensers and air-lift circulators. The purpose of the condensers is to handle the vapors from primary tank vent systems when hot liquid is present. Condensates are collected in catch tanks (e.g., 151-AZ, 152-AX, or TK-417) and returned either to an aging waste tank or to a dilute receiver tank. The air-lift circulators aid in suspending NCAW solids and in heat removal. Air-lift circulators require periodic flushing (approximately once/week) to prevent clogging when they are operating. When the air-lift circulators are not operating, flushing is less frequent.

Aging waste tank operation assumptions used in all three projections follow:

- o Aging waste tanks can be used for storage of dilute non-aging waste.
- o It is assumed that there will be no additional aging waste produced by the Hanford facilities. However, certain wastes containing high ^{90}Sr or ^{137}Cs contents may require storage in aging waste tanks due to their radioactivity. HLW returns to DSTs during Phase 2 processing will be stored in three aging waste tanks (see section 3.18 for more detail).
- o Single-shell tank (SST) solids retrieved from Tank 106-C will be stored in an aging DST (Tank 102-AY) due to the high heat content of the solids.
- o One million gallons of aging tank space is kept available for receiving the contents of an aging waste tank, in the unlikely event of a tank leak (Department of Energy order 5820.2A).

- o Tank 102-AY was designated as the 200 East Area dilute receiver for non-complexed wastes through mid FY 1996 and then Tank 106-AP was designated as the 200 East Area dilute receiver. This change allowed Tank 102-AY to be used to store the solids retrieved from Tank 106-C. Tank 106-AP is currently receiving direct transfers of wastes from B Plant and rail or truck shipments via 204-AR vault from S Plant, T Plant, 100 Area, 300 Area, and 400 Area. Tank 106-AP is also receiving non-complexed SWL.

Non-Aging Double-Shell Tanks

The remaining 24 DSTs are called non-aging waste tanks and are used to store wastes that do not contain high-heat loads in accordance with applicable operational and waste segregation policies. Non-aging waste tank operation assumptions are as follows:

- o Approximately 66 Kgal of caustic will be added to Tank 107-AN in FY 2000 to mitigate the low caustic condition in the tank for all projection cases (Carothers, 1998).
- o Current operational tank usage for this projection are summarized in Table 5. Projected Tank usage will be covered in Section 5.

Table 5. Current Operational Tanks and Usage

| Operation | Designated Tank |
|--------------------------------------|--|
| Evaporator Feed Tank | Tank 102-AW |
| Evaporator Receiver Tank | Tank 106-AW (tank level varies) |
| 200 East Dilute Receiver Tank | Tank 105-AW (PUREX direct transfers; 100 Area wastes) |
| 200 East Dilute Receiver Tank | Tank 106-AP (FY 1998-2000) |
| 200 West Dilute Receiver Tank | Tank 102-SY (FY 1998-2015) |
| 200 East SWL Receiver (DN) | Tank 101-AN and 106-AP (FY1998-2000) |
| 200 East SWL Receiver (DC) | Tank 108-AP (FY 1998-2000) |
| 200 West SWL Receiver (DN) | Tank 102-SY |
| 200 West SWL Receiver (DC) | Tank 102-SY |
| Private Contractor Feed Tanks | Tanks 106-AP and 108-AP (~FY 2001) |
| Intermediate Staging Tanks | Tanks 102-AP and 104-AP (~FY 2001) |
| Sr/TRU/Entrained Solids Return Waste | Tank 107-AP (~6/2002) |
| Dilute Feed Staging | Tanks 104-AP, 107-AP; Tank 104-AN (~FY 2002) |
| Spare Tank Space | Tank 103-AP (1998-1999); distributed space from mid FY 1999 on |

- o Starting in FY 1999, 0.72 Mgal of operational space in the evaporator Feed and Receipt Tanks (Tanks 102-AW and 106-AW) was used as spare space (Awadalla, 1995) in all three projection cases.

- o It was assumed that the TRU solids in Tank 102-SY would be retrieved to Tank 105-AW starting in January 2006. The NCRW solids in Tank 105-AW were not combined with the solids in Tank 103-AW in this projection.
- o Flushes are generated during the receipt of waste transfers either from railroad tank cars, tanker trucks, or after tank to tank transfers. Percent flushes are included with a description of each of the facility generations in Section 3.
- o Tank 106-AP is currently receiving direct transfers of wastes from B Plant and rail or truck shipments via 204-AR vault from S Plant, T Plant, 100 Area, 300 Area, and 400 Area.
- o Tank 108-AP will be used as the complexed SWL receiver and Tanks 101-AN and 106-AP as the non-complexed SWL receivers in 200 East Area (Ross, 1998).

Projected waste generations for Tank Farms were based on a combination of previously observed waste generation rates and anticipated operational needs that are explained below:

- o Tank Farm water additions to DSTs. Tank Farms waste generation rates and flushing activities generally increase with the restart of the 242-A Evaporator due to the additional waste transfers. The 242-A Evaporator was restarted in April 1994. During the period April 1994 through May 1995, the average monthly waste generation rate for Tank Farms was 10.92 Kgal/month. The average monthly waste generation for Tank Farms during FY 1997 was 2.7 Kgal/month. The target rate set for Tank Farms waste generations was 10 Kgal/month. All three projection cases estimated that Tank Farms would generate 10 Kgal/month or 120 Kgal/year to cover transfer line and air-lift circulator flushes. The WVR for evaporation of these flushes to DSSF was 99% (Sederburg, 1995).
- o Cross-site Transfers. All projection cases assumed that either the existing cross-site transfer line or the new cross-site transfer line (Project W-058, operational in FY 1998) would be available to allow cross-site transfer of SWL, facility generations, DST solids from Tank 102-SY and/or SST solids. It was assumed that all wastes containing solids would be cross-sited via the new line which has inline pumps to Tank 104-AN. Without operable cross-site lines many of the TPA milestones involving West area wastes could not be achieved.

Previous projections have estimated that 50 Kgal of water (35 Kgal testing + 20 Kgal for transfer) would be needed for cross-site transfers. In this projection the water addition for cross-sites was reduced to 35 Kgal/transfer due to waste minimization actions defined for the FY 1995 transfer. During the period 1998-2001, approximately two cross-sites would be needed each year due to the volume of SWL being pumped. Based on the projected cross-site testing and transfers anticipated, 70 Kgal/year was projected for the period FY 1998-2001. All three projection cases used the same volumes for cross-site transfer line tests and flushes. The WVR for evaporation of these flushes to DSSF was 99% (Sederburg, 1995).

- o Tank Fill Limits (except for special tank fill considerations):
 - AY, AZ Tanks: 980 Kgal
 - All other DSTs: 1140 Kgal
- o The assumptions used to simulate tank transfers in this projection are listed below:
 - Tank 102-SY: 1082 Kgal in the tank, and PRF not operating, pumped down to 358 Kgal until TRU solids have been removed.
 - Tank 102-AY: Start transfer at 900 Kgal.
 - Tank 105-AW and other dilute receivers: Start transfer at 1000 Kgal, pump down to 50 Kgal above solids.

3.12 UO₃ Facility

Deactivation of the UO₃ Facility is complete and therefore, no waste will be sent to DSTs.

3.13 Waste Sampling and Characterization Facility (WSCF)

The Waste Sampling and Characterization Facility (WSCF) was started in FY 1994. This projection assumed that WSCF would send its waste to ETF and not to DSTs (Collins, 1996).

3.14 100 Area

100-N Basin

The 100-N Basin was constructed in 1963 to receive irradiated fuel assemblies discharged from the N Reactor for the purpose of inspection, storage, and preparation for shipment. In 1988 the N Reactor was placed in a "cold standby" status (shutdown but capable of restarting). In 1989 all nuclear fuel was removed from N Basin and transferred to K Basin. In 1991 the Department of Energy-Richland (DOE-RL) directed Westinghouse to begin deactivation activities. A significant quantity of radioactively contaminated equipment, hardware, debris, and sediment have accumulated in 100-N Basin that will need to be removed. It was assumed that deactivation of the N Basin would not send any wastes to DSTs but wastes would instead be transferred to the Environmental Restoration Disposal Facility (ERDF) (Logan, 1998).

100-K Basin

Fuel handling operations have resulted in some cladding damage to N-Reactor fuel. Subsequent fuel oxidation resulted in fuel and fission products accumulating in fuel canisters and in K Basin where the fuel handling occurred. Aluminum oxide, iron oxide, concrete grit, and other debris has accumulated and mixed with the fuel corrosion products to form a sludge on the basin floor. Approximately 350 Kgal of water and sediment (approximately 18.5 Kgal of sediment) will be transferred to DSTs (Alderman, 1997). New schedules project that these wastes will be transferred to Tank 105-AW in FY 2003. [Late Note--transfer date for 100K wastes may be changed to FY 2005 (Honeyman, 1998b)]. The above generations for 100-K Basin cleanout were used in all three projection cases. [Late Note: The options to dispose of 100-K wastes are being reviewed and may change in the future. One option would dissolve the solids in acid, destroy polychlorinated biphenyls (PCBs), blend with

depleted uranium, and neutralize before sending the wastes to tank farms--this option would increase the liquid and solid volumes sent to tank farms.]

105-F & 105-H Basins

Plans to cleanout the 105-F and 105-H Basins are still being reviewed and the date of cleanout is uncertain due to funding. The projected plan is to clean out the 40,000 gallons in 105-F in the year 2000 and the 200,000 gallons from 105-H in the year 2005 (Mihalic, 1997). These assumptions for 105-F and 105-H Basin cleanout were used for all three projection cases.

The WVRP for evaporation of all 100 Area Basin wastes to DSSF is 99% (Sederburg, 1995). Flush volume for 100 Area wastes is 44 per cent.

3.15 300 Area

Facilities in the 300 Area are used primarily for research and development activities or for analytical support. Some waste received in FY 1995 was generated by decon of facilities. Liquid wastes from the various 300 Area Facilities are transferred to the 340 Facility. Liquid wastes collected at the 340 Facility are transferred to 204-AR vault in 20,000 gallon railroad tank cars (after September 1998, shipments will likely be via a truck tanker due to the pending cessation of rail service (Halgren, 1997)). In the future, the 340 Facility will be closed and a new facility will be installed for Pacific Northwest National Laboratory to transfer wastes from its 300 Area facilities to the DSTs. Facilities in the 300 Area sent 26 Kgal of waste (includes flush) to DSTs (2.2 Kgal/month) in FY 1997. All three projections predicted that 2.3 Kgal/month of miscellaneous waste would be generated from 300 Area facilities during FY 1998. Projected waste generations for FY 1999 and beyond varied from 0.33 to 1.4 Kgal/month. Based on the chemical composition supplied for 300 Area waste streams, the WVRP for evaporation of 300 Area miscellaneous wastes to DSSF is 94% (Sederburg, 1995). Flush volume for 300 Area waste streams is 44 per cent.

3.16 400 Area

There are three major facilities in the 400 Area (Dillhoff, 1997). These include the Fast Flux Test Facility (FFTF), the Maintenance and Storage Facility (MASF), and the Fuel and Material Examination Facility (FMEF). Radioactive liquid waste is primarily generated in conjunction with the removal of residual sodium from reactor components or with decontamination activities. A phased process was begun in December 1993 to place the FFTF into a radiologically and industrially safe shutdown condition. Shutdown of the FFTF has increased the amount of liquid waste generated by the plant's Sodium Removal System. Approximately 11 Kgal of wastes were received from 400 Area in FY 1994-1995 (~0.5 Kgal/month). All three projection cases projected a 7 Kgal shipment of miscellaneous waste would be generated from 400 Area facilities every third year starting in FY 1999. The WVRP for evaporation of 400 Area miscellaneous wastes to DSSF is 94% (Sederburg, 1995). Flush volume for 300 Area waste streams is 44 per cent.

3.17 Phase 1B Privatization Processing

- o Privatization Concept. The revised DOE strategy for treatment of Hanford tank wastes, termed "privatization," would use private contractors to design, permit, build, operate, and decommission the facilities for waste treatment and immobilization (DOE, 1995). Final details of the privatization work will not be developed until later in the process and the assumptions listed below are subject to change. As currently proposed, privatization would be divided into two phases. Phase 1B would include privatization of waste tank supernatant processing, Low-Activity Waste (LAW) immobilization, and an optional High-Level Waste (HLW) immobilization (Washenfelter, 1996b) by private contractors. The scale of processing during Phase 1B of privatization has been established to demonstrate the technical and commercial capability. Phase 2 of privatization would include additional tank waste retrieval, supernatant processing, sludge/solid processing, LAW immobilization, HLW immobilization, disposition of encapsulated Cs/Sr, and interim storage of immobilized waste (Washenfelter, 1996 and Kirkbride, 1997). The schedule listed below was used for the Case 1 projection. Cases 2 and 3 used a different treatment schedule which is presented in Section 4.0 along with the other assumptions unique to these projection cases.
- o Phase 1B Schedule. The target schedule for Phase 1B is summarized below (used for Case 1 projection only):

| | |
|---------------------|---------------------------|
| -Start construction | December 31, 1999 |
| -Operations | June 1, 2002-June 1, 2011 |
- o Intermediate Feed Staging Tanks. Tanks 102-AP and 104-AP were used for intermediate staging of wastes by the Project Hanford Management Contractor (PHMC). The intermediate feed staging tanks were assumed to be fully operational on 10/1/2000.
- o Privatization Contractor Feed Tanks. Wastes from Tanks 102-AP and 104-AP will be transferred to Tanks 106-AP and 108-AP, respectively. Tanks 106-AP and 108-AP will be used as privatization contractor feed tanks or vendor feed tanks. At the time these tanks were transferred to the private contractors they remain in use by the PHMC Team for waste management activities (Kirkbride, 1997).
- o HLW Processing and Immobilization. Phase 1B processing of tank waste sludges would be conducted within existing DSTs and would involve sludges in Tanks 101-AZ, 102-AZ, 102-AY, and the high heat solids retrieved from single-shell tank 106-C. The NCAW supernates removed prior to in-tank washing of the NCAW solids, could not be combined into a single aging tank (Tank 101-AY) due to the 5 M Na limit but would be concentrated and sent to Tank 101-AY and an additional non-aging tank (Powell, 1996b). The in-tank washing assumptions summarized in Table 6 and presented below were obtained from Disposal Engineering (Kirkbride, 1997).

In Revision 21 of this document, it was assumed that all NCAW solids and the 106-C solids would be combined into one aging waste tank (Tank 102-AZ) and that all NCAW supernates would be concentrated into one aging waste tank (Tank 101-AZ). Since that document was published, studies have been completed which looked at numerous sludge washing/combination options (Powell, 1996a). The alternatives for consolidating high heat sludges have been reviewed by a decision board comprised of Hanford contractor management, a DOE/RL representative, and a WDOE representative. It was concluded that consolidating all the sludges into a single tank would require modifications to the tank farm safety basis. The preliminary decision reached was not to consolidate all the high heat sludges into a single tank. The selected alternative (Alternative 8 Modified) would wash the sludges in the tanks they reside in without additional consolidation of solids.

o In-Tank Washing of Tank 101-AZ Sludge

The first step of in-tank washing for the Case 1 projection involved the decanting of supernatant from Tank 101-AZ to Tank 101-AY in August 2000. The decanted aging waste supernate from Tank 101-AZ would require storage in an aging waste tank due to its heat content.

Approximately 146,000 gallons of wash solution (0.1 M sodium hydroxide, 0.011 M sodium nitrate) would be added in August 2000. The solids would be mobilized with mixer pumps, settled for one month, and the wash would be decanted in January 2001 to a non-aging DST.

The washed NCAW solids would then be sampled to determine the effectiveness of the washing process. This washing operation would be conducted a total of three times during the period August 2000 through January 2001. The washed solids were covered with a cover solution in January 2001 that would be used to mix and transfer the washed solids to the private contractors for disposal during the period May 2002 through January 2003.

o In-Tank Washing of Tank 102-AZ Sludge

The supernatant from Tank 102-AZ will be concentrated in-tank and then decanted in September 2001. A portion of this supernatant would go to Tank 101-AY with the remainder going to non-aging DSTs. Due to questions about the allowable final Na concentration and the amount of heat in the supernatant, storage of the remaining supernatant could require one or two additional DSTs (Powell, 1996a and 1996b). In projection Case 1, it was assumed that the NCAW supernatant would be stored in Tank 101-AY plus one additional non-aging DST.

Approximately 213,000 gallons of wash solution (0.1 M sodium hydroxide, 0.011 M sodium nitrate) would be added in September 2001. The solids would be mobilized with mixer pumps, settled for one month, and the wash would be decanted in April 2002 to a non-aging DST.

The washed NCAW solids would then be sampled to determine the effectiveness of the washing process. This washing process would be conducted a total of four times during the period September 2001 to

April 2002. Again, the washed solids would be covered with a cover solution in April 2002 that would be used to mix and transfer the washed solids to the private contractors for disposal during the period September 2003 to June 2004.

o In-Tank Washing of Tank 102-AY/Tank 106-C Sludges

The solids from Tank 102-AY/Tank 106-C would be transferred to Tank 101-AZ for in-tank washing in February 2003. Approximately 320,000 gallons of wash solution (0.1 M sodium hydroxide, 0.011 M sodium nitrate) would be added in February 2003. The solids would be mobilized with mixer pumps, settled for one month, and the washes would be decanted to a non-aging DST for further evaporation.

The washed NCAW solids would then be sampled to determine the effectiveness of the washing process. This washing process would be conducted a total of two times during the period February 2003 through May 2003. Again, the washed solids would be covered with a cover solution that would be used to mix and transfer the washed solids to the private contractors for disposal during the period March 2005 through August 2007.

o In-Tank Washing of Tank 104-C Sludges

Tank 104-C solids would be retrieved to Tank 102-AY in August 2004. These solids would be transferred to Tank 102-AZ for washing in August 2005. Washing of the Tank 104-C solids would be conducted during the period October 2006 through January 2007. Again, the washed solids would be covered with a cover solution that would be used to mix and transfer the washed solids to the private contractors for disposal during the period April 2008 through July 2009.

All three projection cases assumed that approximately 340 metric tons of high-level waste oxides would be transferred to the vendor for immobilization during the period June 2002 through August 2009. It was assumed that this action would process all solids from Tanks 101-AZ, 102-AZ, 102-AY, 106-C, and 104-C. The private contractor would provide a tank for receipt of the washed sludges; existing DSTs would not be used for these functions (Washenfelder, 1996b). In-tank washing activities and waste work-off schedules are summarized in Table 6 (Slaathaug, 1998).

Table 6. Summary of In-Tank Washing Activities

| Date | In-Tank Washing Activity |
|---------------------------|--|
| September 1998-June 1999 | Complete retrieval of Tank 106-C solids into Tank 102-AZ. |
| Aug. 2000 | Decant the NCAW supernate from Tank 101-AZ to Tank 101-AZ. |
| Aug. 2000-Jan. 2001 | Wash NCAW solids in Tank 101-AZ three times. |
| September 2001 | Decant Tank 102-AZ supernatant to Tank 101-AZ and one other non-aging DST. |
| September 2001-April 2002 | Wash NCAW solids in Tank 102-AZ four times. |
| May 2002-January 2003 | Transfer Tank 101-AZ NCAW solids to contractors. |
| September 2003-June 2004 | Transfer Tank 102-AZ NCAW solids to contractors. |
| February 2003 | Transfer solids (102-AZ/106-C) from Tank 102-AZ to Tank 101-AZ |
| February 2003-May 2003 | Wash solids (102-AZ/106-C) in Tank 101-AZ. |
| March 2005-August 2007 | Transfer Tank 102-AZ/106-C solids from Tank 101-AZ to contractors. |
| August 2005 | Transfer Tank 104-C solids from Tank 102-AZ to Tank 102-AZ. |
| October 2006-January 2007 | Wash solids (104-C) in Tank 102-AZ. |
| April 2008-July 2009 | Transfer Tank 102-AZ solids (104-C) to contractors |

- o Low-Activity Waste (LAW) Treatment. The current DOE strategy calls for a demonstration of LAW treatment and immobilization by private vendors at a rate dependent on the type of waste being processed. Envelope A feed is typically double-shell slurry feed (DSSF), double-shell slurry (DSS), or dilute non-complexed waste (DN). Envelope B feed is NCAW supernate. Envelope C feed is typically complexant concentrate (CC). Minimum and maximum processing quantities for each contractor as well as the approximate quantity of sodium processed for the Case 1 projection is listed Table 7 (Honeyman, 1998a).

Table 7. Estimated Waste Quantity Processed for Case 1

| Waste Type | Minimum Amount Processed for Two Contractors (Metric Tons Sodium) | Maximum Amount Processed for Two Contractors (Metric Tons Sodium) | Approximate Quantity Processed for Projection Case 1. (Metric Tons Sodium) |
|-------------|---|---|--|
| Envelope A | 5200 | 9800 | ~5399 |
| Envelope B | 200 | 2000 | ~234 |
| Envelope C | 200 | 4800 | ~4578 |
| Total A+B+C | --- | 10200 | <10,200 |

- o Schedule for LAW Processing. The schedule used for processing of LAW for projection Case 1 is summarized in Table 8 (Honeyman, 1998a). Dates shown are the date the wastes are transferred to the intermediate feed staging tank and not the actual processing date. Actual processing of wastes begins in June 2002. Tank dilutions, contractor number, and multiple batches are not shown. This schedule was developed from input supplied by Disposal Engineering (Slaathaug, 1998). Solids are left in the tanks when wastes are retrieved for LAW processing.
- o Storage of Separated TRU and Entrained Solids. For projection Case 1, entrained solids and transuranic (TRU) elements removed from LAW waste by the private contractors were assumed to be returned to one DST for storage--Tank 107-AP. Wastes from this tank are later transferred to Tank 101-AZ for subsequent disposal.

Table 8. Projected Processing Schedule for Phase 1B for Case 1

| Tank | Waste Type | Envelope | Volume with solids (Kgal) | Approximate Quantity of Na Delivered (MT Na) | Existing or Future Waste | Transfer Date for Processing |
|------------------|----------------|----------|---------------------------|--|--------------------------|------------------------------|
| 105-AN | DSSF | A | 1128 | ~1027 | Existing | 3/2001 |
| 104-AN | DSSF | A | 1057 | ~1070 | Existing | 10/2001 |
| 101-AW | DSSF | A | 1128 | ~ 856 | Existing | 1/2003 |
| 103-AN | DSS | A | 957 | ~1170 | Existing | 10/2003 |
| 101-AP 104-AW | DSSF | A | ~2116 | ~1276 | Future | 6/2004 |
| 101-AY | NCAW Supernate | B | 215 OF 978 | ~ 234 | Future | 3/2005 |
| 107-AN | CC | C | 1057 | ~ 782 | Existing | 4/2006 |
| 102-AN | CC | C | 1079 | ~ 954 | Existing | 8/2006 |
| 106-AN | CC | C | 1088 | ~ 822 | Future | 12/2006 |
| 101-SY | CC | C | 1114 | ~1230 | Existing | 1/2007 |
| 103-SY | CC | C | 747 | ~ 789 | Existing | 8/2007 |

3.18 Phase 2 Privatization Processing

- o The scale of processing during Phase 1B of privatization has been established to demonstrate the technical and commercial capability. Phase 2 of privatization would include the remaining tank waste retrieval, supernatant processing, sludge/solid processing, LAW immobilization, HLW immobilization, disposition of encapsulated Cs/Sr, and interim storage of immobilized waste (Washenfelter, 1996b). The proposed target schedule for Phase 2 processing is summarized below:

| | |
|---|-----------|
| Contract Award | 2004 |
| Design, permitting, licensing, construction, and startup | |
| -Low-Activity Wastes | 2005-2011 |
| -High-Level Wastes | 2005-2013 |
| Operations | |
| -Low-Activity Wastes | 2011-2021 |
| -High-Level Wastes | 2013-2028 |
| Estimated Maximum Processing Rates (Wittman, 1997a and 1997B) | |
| -Liquid Wastes, Mgal/yr @ 7M Na | 17.2 |
| -Liquid Wastes, Mgal/yr @ 5M Na | 24.1 |
| -Solid Wastes, Mgal/yr (5M Na or 10 wt% solids) | 1.55 |

Processing rates will ramp up during Phase 2--1/3 full rate the first year, 2/3 full rate the second year, and full rate the third year. Three aging waste tanks will be needed to store HLW returns from Phase 2 processing.

3.19 Watch List/Safety

- o All three projection cases assumed that agitation using a mixer pump would continue to be used for mitigation of the flammable gas buildup in Tank 101-SY. It was assumed that Tanks 101-SY and 103-SY would not require dilution until just prior to retrieval for processing which was scheduled to start in Phase 1B. Tank 101-SY was diluted to approximately 7 M Na and transferred to Tank 102-SY by January 2007. The retrieved Tank 101-SY wastes were transferred from Tank 102-SY to Tank 104-AN and then to Tanks 102-AN and 107-AN. Tank 103-SY was diluted up to approximately 7 M Na and transferred to Tank 102-SY by August 2007. Tank 103-SY wastes were transferred from Tank 102-SY to Tank 104-AN and then to Tanks 102-AN and 107-AN.

All three projection cases assume that timely permission is obtained to remove waste from watch-list tanks used as LAW feed sources and to remove the watch-list designation from that tank immediately after retrieval.

All three cases assume that the authorization basis is amended to support all activities related to Phase 1B activities (for example, LAW feed staging and delivery, HLW feed staging and delivery, return of Sr/TRU and entrained solids, etc.

3.20 Spare/Contingency Space

- o Spare space is space reserved in case of a leak in a double-shell tank per DOE Order 5820.2A. Contingency space has historically been set aside to account for possible inaccuracies in the WVP software when projecting waste generations and/or waste volume reduction factors.

A total of 2.28 million gallons (one aging and one non-aging tank) of spare/contingency space was reserved for all three projection cases. From FY 1999 on, 0.72 million gallons of the operational space in Tanks 102-AW and 106-AW was designated as part of the 2.28 million gallons of spare space (Awadalla, 1995) in all three projection cases. The remaining 1.56 million gallons of space was distributed spare space.

3.21 Waste Segregation

Waste segregation and compatibility are requirements of DOE Order 5820.2A (DOE, 1990) and WAC 173-303-395 (Dangerous Waste Regulations). The overriding purpose of waste segregation and compatibility are to ensure the safety of waste storage and tank farms operations; to minimize future processing costs; and to comply with DOE Order 5820.2A and WAC 173-303-393. Wastes that are typically segregated include:

- Phosphate Wastes--dilute phosphate (DP) or concentrated phosphate (CP).
- Wastes Containing High Organic Concentrations--dilute complexed (DC) or complexant concentrate (CC).
- TRU containing wastes--Neutralized Cladding Removal Wastes (NCRW solids) or PFP solids (PT).
- Watch list tank wastes to prevent inadvertent commingling with other wastes.
- Pretreated waste streams.
- Washed NCAW solids, etc.
- Concentrated interim waste types--e.g., double-shell slurry feed (DSSF) or double-shell slurry (DSS) need to be separated from dilute wastes to prevent the need to reconcentrate.
- Wastes exhibiting exothermic reactions.

All three projections assume that current waste segregation practices are observed (if possible) with the exception of SWL pumping in 200 West Area as discussed in Section 3.8. Waste segregation practices are summarized in Table 9 (Fowler, 1995). For projection Case 1, non-complexed and complexed SWL wastes in 200 East Area are mixed for evaporation purposes beginning in FY 2000.

Table 9. Waste Compatibility Matrix

| | | Receiver Waste Type | | | | | | | |
|-------------------------|---------------------|---------------------|------|----|----|--------------|----|------|----|
| | | DN | DSSF | DC | CC | (PD) NCRW | PT | NCAW | CP |
| Source Waste Type | DN | X | X | X | X | X | X | X | X |
| | DSSF | X | X | | | | | | |
| | DC | | | X | X* | | | | |
| | CC | | | X* | X | | | | |
| | (PD) NCRW SOLIDS | X | | | | X | X | | |
| | (PT) PFP SOLIDS | X | | | | X | X | | |
| | NCAW | | | | | | | X | |
| | CP | | | | | | | | X |

(*) Adding CC to DC is permitted but would not ordinarily be done. The volume of combined waste which would need to be evaporated would be increased, resulting in increased evaporation costs.

3.22 Loss of DST Space

Corrosion studies completed to date (Anantatmula and Ohl, 1996) show a 40-60% chance of a pit corrosion failure occurring in a DST by FY 2028. Some of the corrosion potential could be mitigated by maintaining a corrosion control program for the DSTs. In all three projection cases, it was assumed that none of the DSTs would be removed from service by the end of FY 2015.

3.23 New DST Construction

All three projection cases assumed that no new DSTs would be constructed by 2015.

3.24 DST Tank Solids Levels

Solids levels in the DSTs are shown in Table 10 (Hanlon, 1998; Estey and Guthrie, 1996; Stauffer, 1997; and Carothers, 1997b). Solids levels have been estimated for the tanks marked with an asterisk (*) based on the previous solids level measurement and the percent solids in facility generations that have been added to the tank since the last solids level measurement. Tanks with no solids level listed have either not been measured or have a minimal solids volume. The total DST solids used for this projection was approximately 5 Mgal.

Table 10. DST Solids Levels (Kgal)

| TANK | SOLIDS | TANK | SOLIDS | TANK | SOLIDS | TANK | SOLIDS |
|--------|--------|--------|--------|--------|--------|---------|--------|
| 101-AY | 108 | 101-AN | 33 | 101-AP | | 101-AW | 306 |
| 102-AY | 22 | 102-AN | 89 | 102-AP | | 102-AW | 40 |
| 101-AZ | 50 | 103-AN | 410 | 103-AP | 1 | 103-AW* | 487 |
| 102-AZ | 104 | 104-AN | 449 | 104-AP | | 104-AW* | 390 |
| 101-SY | 605 | 105-AN | 489 | 105-AP | 154 | 105-AW | 286 |
| 102-SY | 123 | 106-AN | 17 | 106-AP | | 106-AW | 228 |
| 103-SY | 362 | 107-AN | 247 | 107-AP | | | |
| | | | | 108-AP | | | |

3.25 IMUST Wastes

Approximately 500 kilogallons of wastes are projected to be received from Inactive Miscellaneous Underground Storage Tanks (IMUSTs) between FY 2011 and 2015 (Wacek, 1996). This is a new waste type added to these projections.

3.26 Assumption Summary

Assumptions used for all cases are presented in Table 11. Differences in assumptions between the three cases have been highlighted.

**Table 11. Assumption Matrix
For the 1998 Operational Waste Volume Projection
(All Years are Fiscal Years)**

| | <u>Case 1</u> | <u>Case 2</u> | <u>Case 3</u> |
|-----------------------------|--------------------|--------------------|--------------------|
| <u>Meets TPA Milestones</u> | Yes | No | No |
| <u>Facility Generations</u> | | | |
| Total Limit, Kgal/mo | 15.2-16.6 | 15.2-16.6 | 15.2-16.6 |
| <u>PUREX</u> | | | |
| Yearly Rate, Kgal/yr | 5 | 5 | 5 |
| TCO Scheduled | Completed | Completed | Completed |
| TCO Volume, Kgal | 0 | 0 | 0 |
| Flush for TCO | --- | --- | --- |
| WVRF for TCO (to DSSF) | 99 | 99 | 99 |
| <u>B Plant</u> | | | |
| TCO Completed | 1998 | 1998 | 1998 |
| TCO Volume, Kgal DN | 103(remaining) | 103(remaining) | 103(remaining) |
| Flush for TCO | 10% | 10% | 10% |
| WVRF for TCO (to DSSF) | 99 | 99 | 99 |
| <u>WESF</u> | | | |
| Monthly Rate, Kgal/mo | 0.5(1998-2028) | 0.5(1998-2028) | 0.5(1998-2028) |
| Flush for misc. waste | 0% | 0% | 0% |
| WVRF, misc. waste(to DSSF) | 99 | 99 | 99 |
| <u>S Plant</u> | | | |
| Monthly Rate, Kgal/mo | 1.0 to 1.7 | 1.0 to 1.7 | 1.0 to 1.7 |
| Flush for misc. waste | 22% | 22% | 22% |
| WVRF, misc. waste(to DSSF) | 99 | 99 | 99 |
| <u>T Plant</u> | | | |
| Monthly Rate, Kgal/mo | 1.4 to 2.7 | 1.4 to 2.7 | 1.4 to 2.7 |
| Flush for misc. waste | 22% | 22% | 22% |
| WVRF, misc. waste(to DSSF) | 99 | 99 | 99 |
| <u>300 Area</u> | | | |
| Monthly Rate, Kgal/mo | 2.3 (1998) | 2.3 (1998) | 2.3 (1998) |
| Monthly Rate, Kgal/mo | 0.33 to 1.4 (1998) | 0.33 to 1.4 (1998) | 0.33 to 1.4 (1998) |
| Flush for misc. waste | 44% | 44% | 44% |
| WVRF, misc. waste(to DSSF) | 94 | 94 | 94 |
| <u>400 Area</u> | | | |
| Rate, Kgal-every 3rd yr | 7(1999) | 7(1999) | 7(1999) |
| Flush for misc. waste | 44% | 44% | 44% |
| WVRF, misc. waste(to DSSF) | 94 | 94 | 94 |
| <u>WSCF</u> | | | |
| Monthly Rate, Kgal/mo | 0.0 | 0.0 | 0.0 |
| <u>Tank Farms</u> | | | |
| Monthly Rate, Kgal/mo | 10 | 10 | 10 |
| WVRF, flushes (to DSSF) | 99 | 99 | 99 |

**Table 11. Assumption Matrix
For the 1998 Operational Waste Volume Projection
(continued)**

| | Case 1 | Case 2 | Case 3 |
|---------------------------------------|------------------|------------------|------------------|
| <u>IMUST Wastes</u> | | | |
| Tot. Volume, Kgal (2011-15) | 500 | 500 | 500 |
| <u>100 Area</u> | | | |
| 100-N | | | |
| TCO Scheduled | 1998 | 1998 | 1998 |
| TCO Waste Received | N/A-send to ERDF | N/A-send to ERDF | N/A-send to ERDF |
| TCO Volume, Kgal | 0 | 0 | 0 |
| 100-K Basin Cleanout | | | |
| TCO Scheduled | 2003 | 2003 | 2003 |
| TCO Volume, Kgal | 350 | 350 | 350 |
| 105-F & 105-H Basin | | | |
| TCO waste in 2000, Kgal | 40 | 40 | 40 |
| TCO waste in 2005, Kgal | 200 | 200 | 200 |
| Flush, ALL 100 Area Waste | 44% | 44% | 44% |
| WVRF, ALL TCO waste(to DSSF) | 99 | 99 | 99 |
| <u>Tank 107-AN Caustic Addition</u> | | | |
| Addition in FY 2000 (Kgal) | 66 | 66 | 66 |
| <u>Salt Well Liquid Pumping</u> | | | |
| Volume remaining (Mgal) | 5.36 | 5.36 | 5.36 |
| Volume to be pumped in 1998 | 0.24 | 0.24 | 0.24 |
| West Area Receiver | Tank 102-SY | Tank 102-SY | Tank 102-SY |
| Start Complexed SWL in 200W | 1999 | 2002 | 2002 |
| Pumping Completion, FY | 2000 | 2004 | 2004 |
| Dilute Complexed SWL (Mgal) | 1.64 | 1.64 | 1.64 |
| Porosity saltcake/sludge | 50%/21% | 50%/21% | 50%/21% |
| Flush for SWL Pumping | 28% | 28% | 28% |
| WVRF, non-complexed (to DSSF) | 47 | 47 | 47 |
| WVRF, complexed (to DSSF) | 10 | 10 | 10 |
| <u>Single-Shell Tank (SST) Solids</u> | | | |
| Tank 106-C Retrieval | 9/1998 | 9/1998 | 9/1998 |
| Tank 104-C Retrieval | 8/2004 | 8/2005 | 8/2005 |
| # Tanks to store 106-C solids | 1 | 1 | 1 |
| Start Remaining SST Retvl | 2004 | N/A | 2004 |
| Tank Farm Closure start | 2018 | N/A | 2018 |
| Approximate Dilution Ratio | 3:1 | 3:1 | 3:1 |
| Retrieved Vol 2004-2005(Mgal) | 2.8 | N/A | 2.8 |
| Retrieved Vol 2006-2007(Mgal) | 3.6 | N/A | 3.6 |
| Meets TPA Milestones | Yes | N/A | Yes |
| No. SSTs Retrieved | 149 | N/A | 149 |
| Sludge Retrieved (Mgal) | 12.2 | 12.2 | 12.2 |
| Saltcake Retrieved (Mgal) | 23.4 | 23.4 | 23.4 |

**Table 11. Assumption Matrix
For the 1998 Operational Waste Volume Projection
(continued)**

| | <u>Case 1</u> | <u>Case 2</u> | <u>Case 3</u> |
|--|---------------|---------------|---------------|
| <u>PFP Stabilization</u> | | | |
| Dates | 1998-2006 | 1998-2006 | 1998-2006 |
| Volume, Kgal | 27 | 27 | 27 |
| Flush | 22% | 22% | 22% |
| WVRF | 81 | 81 | 81 |
| <u>Evaporator</u> | | | |
| 242-A Shutdown | ~2011 | ~2011 | ~2011 |
| New Evaporator (Privatize) | 2011 | 2011 | 2011 |
| Next Outage Date | 2004 (1 Yr) | 2004 (1 Yr) | 2004 (1 Yr) |
| Training Vol. (bi-yearly) | 50 | 50 | 50 |
| Ave. Evap Rate, Kgal/mo | 500 | 500 | 500 |
| Evaporation Product | dDSSF | dDSSF | dDSSF |
| Evaporation Limit (g/ml) | 1.41 | 1.41 | 1.41 |
| LERF capacity (Mgal) | 13 | 13 | 13 |
| Gal. condensate/gal. WVR | 1.20 | 1.20 | 1.20 |
| Yearly evaporation of DN (except for scheduled outage) | Yes | Yes | Yes |
| <u>Effluent Treatment Facility</u> | | | |
| Rate (Mgal/year) | 50 | 50 | 50 |
| <u>Watch List/Safety</u> | | | |
| 101-SY Retrieval | 1/2007 | 1/2008 | 1/2008 |
| 103-SY Retrieval | 8/2007 | 8/2010 | 1/2010 |
| <u>Spare/Contingency Space</u> | | | |
| Spare Space, Mgal | 2.28 | 2.28 | 2.28 |
| Use 0.72 Mgal of Operational space in 106-AW as part of spare space from 1999 on | Yes | Yes | Yes |
| Contingency space, Mgal | None | None | None |
| -date | N/A | N/A | N/A |
| <u>Waste Segregation/DST Solids</u> | | | |
| Total DST solids (Mgal) | 5 | 5 | 5 |
| Store DSSF on NCRW solids | Yes | Yes | Yes |
| Store DSSF on NCAW solids | No | No | No |
| Segregate Complexed wastes | If Possible | If Possible | If Possible |
| <u>Loss of DST Space</u> | | | |
| Number Tanks Removed from Service | None | None | None |
| <u>New DST Construction</u> | | | |
| Date Constructed | None N/A | None N/A | None N/A |
| <u>New Cross-Site Transfer Line</u> | | | |
| Start Construction (TPA) | 11/1995 | 11/1995 | 11/1995 |
| New line operational | Yes | Yes | Yes |
| Old line operational | Yes | Yes | Yes |

**Table 11. Assumption Matrix
For the 1998 Operational Waste Volume Projection
(continued)**

| | <u>Case 1</u> | <u>Case 2</u> | <u>Case 3</u> |
|---|--------------------------|--------------------|--------------------|
| DST Retrieval | | | |
| 102-SY solids retrieved to 200 East Area | 1/2006 | 1/2008 | 1/2008 |
| Consolidation of NCRW solids in 103-AW & 105-AW | No | No | No |
| Phase 1B Privatization Processing | | | |
| HLW Processing start | 11/2000 | 6/2004 | 6/2004 |
| HLW Vitrification start | 6/2002 | 11/2004 | 11/2004 |
| LAW Processing start | 6/2002 | 6/2004 | 6/2004 |
| LAW Vitrification start | 6/2002 | 5/2006 | 5/2006 |
| Phase 1 treatment ends | 6/2011 | 12/2016 (extended) | 12/2016 (extended) |
| Phase 1 Extension | Yes - Through | Yes - Through | Yes - Through |
| Maximum Order Quantities | | FY 2016 | FY 2016 |
| LAW Delivery Rate | 1460 MT Na/yr | 1100 MT Na/yr | 1100 MT Na/yr |
| HLW Delivery Rate | 60 MT NVOL/yr | 92 MT NVOL/yr | 92 MT NVOL/yr |
| Total Processed Quantities: | | | |
| Envelope A (MT Na) | ~5399 | 7010 | 7010 |
| Envelope B (MT Na) | ~234 | 556 | 556 |
| Envelope C (MT Na) | ~4577 | 4310 | 4310 |
| Staging/Characterization time per tank | 100 days | 100 days | 100 days |
| Approximate Concentration of retrieved DSSF, CC | 7 M, Na | 7 M, Na | 7 M, Na |
| LAW Retrieval Schedule--Dates to stage first five batches: | | | |
| Batch 1 | 105-AN(3/2001) | 107-AN(7/2005) | 107-AN(7/2005) |
| Batch 2 | 104-AN(10/2001) | 105-AN(7/2006) | 105-AN(7/2006) |
| Batch 3 | 101-AW(1/2003) | 102-AN(3/2007) | 102-AN(3/2007) |
| Batch 4 | 103-AN(10/2003) | 104-AN(12/2007) | 104-AN(12/2007) |
| Batch 5 | 101-AP & 104-AW(5/2004) | 101-AW(10/2008) | 101-AW(10/2008) |
| Intermediate Feed Staging Tank | 2 | 2 | 2 |
| Number of LAW Contractors | 2 | 1 | 1 |
| Vendor Feed Tank | 2 | 1 | 1 |
| Pretreated NCAW Receipt Tank | 0 | 1 | 1 |
| NCAW supernatant prestage Tank | 1 | 0 | 0 |
| Entr. Solid Receipt Tanks | 1 | 1 | 1 |
| Phase 2 Privatization Processing | | | |
| Contract Award | 2005 | N/A | N/A |
| LAW Operations | 2011-2021 | N/A | N/A |
| HLW Operations | 2013-2028 | N/A | N/A |
| HLW Return Tanks | 3 | 3 | 3 |
| Includes New Evaporator | Yes | Yes | Yes |
| Step Processing Rates--1/3 first year; 2/3 second year; then full rate | | | |
| Maximum Processing Rates | | | |
| LAW, Mgal/yr @7M Na | 17.2 | N/A | N/A |
| LAW, Mgal/yr @5M Na | 24.1 | N/A | N/A |
| HLW, Mgal/yr @5M Na | 1.55 | N/A | N/A |
| In-Tank Washing | | | |
| In-tank Washing of NCAW | Yes | No | No |
| Consolid. of NCAW solids | No | No | No |

4.0 ASSUMPTIONS FOR PROJECTION CASES 2 AND 3

Case 1 (TPA Compliant) is meant to project DST needs based on established TPA milestones, TWRS program planning, and the most realistic operational assumptions (described in Section 3). Case 1 presents a basis for evaluating future DST space needs through the end of FY 2015. This report presents a projected range of tank needs which is used to generate recommendations regarding site activities, waste management activities, facility requirements, and the need to build additional double-shell tanks. This document presents the results of three projection cases. Operating assumptions for the three projection cases were established by July 1998.

The Case 2 and Case 3 projections present a range of operational assumptions meant to determine the impact of changes in the disposal program on DST needs. The Case 2 and Case 3 projections do not present a lower or an upper limit on double-shell tank needs which could vary significantly depending on the assumption changes. The following section will describe assumptions specific to the Case 2 and Case 3 projections. These assumptions are also summarized in Table 11.

Projection Case 2 presents projected DST space needs based on the May 27, 1998 Alternative Case (DeLozier, 1998) without SST solids retrieval. Case 2 delivers additional feed beyond the minimum order quantities through FY 2016. The May 27, 1998 Alternative Case included a treatment schedule being considered for privatization and an alternative SWL pumping schedule (Ross, 1998). One of the purposes of this projection was to identify the space available for SST solids retrieval. Projection Case 3 uses the same assumptions for retrieval and SWL pumping as Case 2 but also includes the TPA compliant SST solids retrieval schedule from Case 1. Additional details of the assumptions for these projection cases are included in the following sections.

4.1 Projection Case 2 Assumptions

Assumptions for projection Case 2 are the same as those for the Case 1 except for the following:

- o Alternative Treatment Schedule. The extended treatment schedule used in this projection (Waldo, 1998 and Peters, 1998) was designed to identify how much DST space would be freed up if the alternative treatment schedule (DeLozier, 1998) was extended thru FY 2016. One of the purposes of this projection was to identify the space available for SST solids retrieval. For this reason, this projection did not include any SST solids retrieval other than the retrieval of solids from Tanks 106-C and 104-C. These solids were projected to be retrieved to Tank 102-AY. The schedule used for processing of LAW is summarized in Table 12.

Table 12. Projected Processing Schedule for Case 2

| Tank | Waste Type | Envelope | Volume with solids (Kgal) | Approximate Quantity of Na Delivered (MT Na) | Existing or Future Waste | End Transfer Date for Processing |
|--------|---------------------------------|----------|---------------------------|--|--------------------------|----------------------------------|
| 107-AN | CC | C | 1057 | ~ 782 | Existing | 7/2005 |
| 105-AN | DSSF | A | 1128 | ~1027 | Existing | 7/2006 |
| 102-AN | CC | C | 1079 | ~ 954 | Existing | 3/2007 |
| 104-AN | DSSF | A | 1057 | ~1070 | Existing | 12/2007 |
| 101-AW | DSSF | A | 1128 | ~ 856 | Existing | 10/2008 |
| 103-AN | DSS | A | 957 | ~1170 | Existing | 7/2009 |
| 108-AP | NCAW Supernate (101-AZ, 102-AZ) | B | 978 | ~ 556 | Existing | 4/2011 |
| 101-SY | CC | C | 1114 | ~1230 | Existing | 3/2008 |
| 103-SY | CC | C | 747 | ~ 789 | Existing | 10/2011 |
| 103-AP | CC | C | 1111 | ~ 898 | Future | 3/2013 |
| 101-AN | DSSF | A | 1080 | ~ 912 | Future | 12/2013 |
| 101-AP | DSSF | A | 1112 | ~ 956 | Future | 10/2014 |
| 105-AP | DSSF | A | 1106 | ~ 804 | Future | 7/2015 |
| 107-AN | DSSF | A | 1000 | ~ 700 | Future | 2/2016 |

The alternative treatment schedule considered for privatization in May 1998 (DeLozier, 1998) did not include direction on Phase 2 waste treatment. Since projection cases 2 and 3 included an extension of Phase 1 processing into FY 2016, no Phase 2 waste treatment was considered. Note that feeds in the table above listed after Tank 108-AP (NCAW supernates) are extensions beyond the Phase 1 minimum order quantities.

The May 1998 treatment schedule (DeLozier, 1998) also included a number of other key changes as compared to Case 1 that are summarized below:

1. No in-tank washing of NCAW solids. It was assumed that NCAW slurries would be transferred to the privatization contractor who would perform any solids/liquid separations and washing. It was assumed that the NCAW supernate would be returned to Tank 108-AP.
 2. Only one tank would be used to feed wastes to the contractor--Tank 106-AP.
 3. Envelope limits were modified.
- o SWL Pumping Volume. For projection Cases 2 and 3, it was assumed that SWL pumping would be completed by the end of FY 2004 (Ross, 1998). The projected pumping volumes (without flush) for Cases 2 and 3 are presented in Table 13. Cases 2 and 3 used the same amount of flush (approximately 1.53 Mgal) and the same WVRFs that were listed for Case 1 in Section 3.8.

Table 13. Salt Well Pumping Schedule for Case 2

| Salt Well Pumping Schedule for 50% Saltcake/21% Sludge Porosity (Brown, 1996) | | | | | |
|--|-----------|----------|-----------|----------|-----------|
| FISCAL YEAR | EAST AREA | | WEST AREA | | TOTALS |
| | DN | DC | DN | DC | |
| Projected SWL Pumping 1998-2000 (without flush) | | | | | |
| 1998 | 0 KGAL | 0 KGAL | 238 KGAL | 0 KGAL | 238 KGAL |
| 1999 | 0 KGAL | 38 KGAL | 730 KGAL | 0 KGAL | 768 KGAL |
| 2000 | 597 KGAL | 398 KGAL | 332 KGAL | 0 KGAL | 1327 KGAL |
| 2001 | 206 KGAL | 260 KGAL | 551 KGAL | 0 KGAL | 1017 KGAL |
| 2002 | 15 KGAL | 67 KGAL | 577 KGAL | 182 KGAL | 841 KGAL |
| 2003 | 0 KGAL | 0 KGAL | 499 KGAL | 577 KGAL | 1076 KGAL |
| 2004 | 0 KGAL | 0 KGAL | 1 KGAL | 115 KGAL | 116 KGAL |
| TOTALS | 818 KGAL | 763 KGAL | 2908 KGAL | 874 KGAL | 5363 KGAL |

4.2 Projection Case 3 Assumptions

Assumptions for the Case 3 projection are the same as those for the Case 2 projection except that the Case 3 projection includes the TPA compliant SST solids retrieval schedule defined for Case 1 (see Section 3.9). This retrieval schedule for SST solids was based on a file received from Disposal Engineering (Penwell, 1998a) which started retrieval in December 2003 (M-45-03-T1) and completed retrieval by the end of FY 2018 (TPA milestone). The retrieved volume of waste for this case is approximately 2.8 Mgal for FY 2004-2005 and an additional 3.6 Mgal for FY 2006-2007.

5.0 RESULTS AND CONCLUSIONS

The results of a waste volume projection can be used to forecast tank space needs versus time, forecast evaporator operation, forecast needed LAW processing and disposal rates, HLW processing and disposal, analyze tank space issues for aging and non-aging waste tanks, predict tank usage, or to determine the need and schedule for retrievals or cross-site transfers. To predict tank space needs, a graphic is produced showing tank count versus time as compared to the available space. Generations and evaporations for the near term (thru 2000) are modeled on a monthly basis whereas the remainder of the projection is typically modeled on an annual basis.

All projection cases assume that dilute waste will be evaporated to DSSF in the year they are produced, provided an evaporator is operational and the WVR limit of the evaporator has not been exceeded. In later parts of the projections when tank space becomes tight due to processing needs and/or the amount of SST solids being retrieved, the evaporator is assumed to operate yearly even if volumes are small in order to minimize waste storage needs. Long range projection graphics for the three projection cases are presented in Sections 5.1, 5.2, and 5.3. Short range graphics, tank usage graphics, evaporator WVR data, and a spreadsheet showing inputs/outputs have been included for the Case 1 projection (TPA Compliant) only.

This year's projection cases incorporate several space saving assumptions. These space saving alternatives reduce the need to build additional DSTs but add additional risks to the TWRS program. These actions and some of the risks are listed below:

- o Waste generation rates and TCO volumes have been reduced compared to those used in Rev. 23.
- o It was assumed that agitation using a mixer pump would continue to be used for mitigation of the flammable gas buildup in Tank 101-SY. It was assumed that neither Tank 101-SY or 103-SY would require dilution until just prior to retrieval for processing during Phase 1B processing.

If the mixer pump option was not available to meet the flammable gas buildup and a 1:1 dilution was required at a future date the increase in tank space to dilute both Tanks 101-SY and 103-SY would be approximately 1.9 million gallons.

- o In Revision 21 of this document, it was assumed that all NCRW and PFP solids could be consolidated into one DST (Awadalla, 1995). In Revs. 22 and 23 of this document, it was assumed that the solids in Tanks 103-AW and 105-AW would not be combined. However, the PFP solids from Tank 102-SY and the solids from the 100 Area TCO activities were combined into Tank 105-AW. To further minimize the impact of this non consolidation of solids compared to Revision 21, this year's projections assumed that slurry feed (DSSF) could be stored on top of the solids in Tanks 103-AW and 104-AW. The acceptability of this assumption is still being reviewed.
- o Spare space is space reserved in case of a leak in a double-shell tank per DOE Order 5820.2A. Contingency space has historically been set

aside to account for possible inaccuracies in the WVP software when projecting waste generations and/or waste volume reduction factors. A total of 2.28 million gallons (one aging and one non-aging tank) of spare/contingency space was reserved for all three projection cases. This space is distributed space from FY 1999 on. Operational space in Tanks 102-AW and 106-AW was used to provide 0.72 Mgal of the required 2.28 Mgal of spare/contingency space from FY 1999 on (Awadalla, 1995). This assumption change reduces operational space which may create operational/space problems during the period when SST solids are being retrieved.

- o Tank 102-SY was used to pump complexed SWL in West area starting in FY 2000 for Case 1 in order to meet TPA milestones for SWL pumping completion. Retrieval of the TRU solids in this tank is not scheduled until January 2006 (Case 1) or until January 2008 (Cases 2 and 3). Segregation issues involving contacting complexed SWL with the TRU heel in Tank 102-SY may make this assumption impossible which could delay SWL pumping TPA milestones (see Section 3.8 for more on SWL pumping).
- o These projections assumed that dilute non-complexed waste could be evaporated to a specific gravity (SpG) of 1.41 rather than the previous 1.35 limit used in the 1995 projection, L9503A (Awadalla, 1995). Analysis has shown that as long as the SpG remains at 1.41 or less that there will not be a buildup of flammable gas in the DSTs (Fowler, 1995). Evaporating the waste to a SpG of 1.41 would save approximately 2/3 of a tank by the end of the projection as compared to the 1995 projection, L9503A.
- o Some double-shell tanks are nearing their design life. None of this year's projections provide for the loss of any DST space through 2015. The volume of this impact would be approximately one million gallons if one DST is lost. Spare space would be used if a loss of a double-shell tank should occur.
- o All three projections assumed that evaporator capacity would be available on an annual basis from FY 1998-2015 except for a one year outage in FY 2004. A reduction in evaporation capacity during years when space is tight or when waste receipts are high could result in a tank space shortage.
- o The Privatization contracts state that each Privatization Contractor will modify their assigned feed tank (Tank 106-AP or Tank 108-AP) and supporting systems. Due to DST tank space limitations, the current feed staging plans and OWVP projections continue to use these tanks for waste management during the same time frame that tank modifications and turnover are expected to occur.
- o The PHMC team will need to use Tanks 102-AP and 104-AP for waste management during the same time frame that Project W-211 is preparing them for use as intermediate feed staging tanks.

- o All three projection cases assume that timely permission is obtained to remove waste from watch-list tanks used as LAW feed sources and to remove the watch-list designation from that tank immediately after retrieval. This means that tanks are immediately available for unrestricted use.

The space saving actions listed above reduce the need for construction of new DST space that was recommended based on a previous projection (Rev. 20) but introduce additional uncertainties and risks into the overall TWRS program. If many of these items are not possible or if waste generations exceed those used in this projection, it may be necessary to either delay site cleanup activities, delay TPA milestones (e.g., SWL pumping and/or SST solids retrieval), increase the waste processing rate, or build additional tank space in order to avoid exceeding the available DST space. Additional studies are currently in progress to address and solve the issues that have been identified.

Results of the projection cases and the projected tank space needs are included in the following sections.

5.1 Projection Case 1 Results and Conclusions

Assumptions for the Case 1 projection represent the current planning basis for TWRS programs to meet TPA commitments. Projected tank space needs for the Case 1 projection are shown in Figure 3. The Case 1 projection exceeds available space by one tank in FY 2001, by up to two tanks in FY 2005-2007, and by up to seven tanks by FY 2012. The one tank space shortage in FY 2001 could be eliminated by using fewer tanks to pump SWL in 200 East Area. This projection assumed that Tanks 101-AN and 106-AP would be used to pump non-complexed waste in 200 East Area while Tank 108-AP would be used to pump complexed SWL in 200 East Area. Pumping the non-complexed SWL to one tank in 200 East Area would free up one tank for storage of the DSSF being produced, thus eliminating the one tank shortage. The tank space shortage in FY 2005-2006 results from trying to retrieve a relatively large volume of SST solids through Tank 102-SY before the TRU solids residing in Tank 102-SY have been removed and at a time when Tank 102-SY is being used to retrieve wastes from Tanks 101-SY and 103-SY. Options to meet or avoid the need for extra space in 200 West Area during FY 2005-2006 include the following:

- o Accelerate both the removal of the TRU solids from the bottom of Tank 102-SY and the retrieval of wastes from Tanks 101-SY and 103-SY to a date preceding the start of SST solids retrieval in 200 West Area (FY 2007). This should provide space in Tank 102-SY to handle the early SST solids retrieval schedule. This could also mean that the wastes in Tanks 101-SY and 103-SY would have to be pretreated at an earlier date in the Phase 1B schedule.
- o Reduce the amount of SST solids waste retrieved in 200 West Area until after Tank 102-SY has been cleaned out and Tanks 101-SY and 103-SY have been retrieved (after August 2007) and/or reduce the SST solids retrieval schedule (may delay TPA milestones).
- o Delay SWL pumping to reduce tank space needs (delays TPA milestone). One of the 200 West Area tanks would still have to be diluted and moved to 200 East Area to provide space where it is needed. This means that up to 2.8 million gallons of SWL (assumed WVRF of 47%) might have to be delayed to accommodate the diluted volume of Tank 103-SY (current inventory 747 Kgal; assumed 1:1 dilution).
- o Increase Phase 1B processing rates to free up additional tank space. Since the space is needed in West Area, one of the tanks in West Area would have to be moved earlier in the Phase 1B schedule. Tank 103-SY has only a total of 747 Kgal and the final diluted volume would be smaller.
- o Build additional tanks. Should the projection require building new tanks, approximately six to eight years lead time would be required to provide additional storage tanks. Since we have the lead time, the decision to add storage capacity can be delayed until tank space needs are re-evaluated in 1999. Annual evaluation of tank space needs and the decisions on additional storage capacity are required by the M-46 series Tri-Party Agreement Milestones.

Options to meet or avoid the need for extra space needed during FY 2011-2015 include the following:

- o Reduce the amount of SST solids waste retrieval volume during FY 2011-2015 (may delay TPA milestones). The SST solids retrieval schedule used for projection Cases 1 and 3 would retrieve 10.9 Mgal more waste by the end of FY 2013 than the schedule used for the 1997 OWVP. There is still ample time in future years to thoroughly review the SST solids retrieval schedule to avoid some of this shortage.
- o Delay SWL pumping to reduce tank space (delays TPA milestones).
- o Increase Phase 1B and/or Phase 2 processing rates to free up additional tank space.
- o Build additional tanks.

A spreadsheet summarizing the waste generations, evaporator WVR, and processing requirements for the Case 1 projection has been added to this document and is included as Table 14. This spreadsheet is included to present a global view of how the various inputs and outputs affect tank space. This spreadsheet is useful to review waste inventories and waste receipts but cannot accurately predict the dynamics of tank usage or the full impact of partially filled tanks on tank space needs. Information on the amount and nature of HLW returns to the aging waste tanks was not available when these projections were completed. The HLW return volumes and workoffs shown in this document are estimates only and are likely to change.

The projected tank inventories and tank space usage for the Case 1 projection (TPA Compliant) as of September 2001 are included in Table 15.

Figure 4 shows the waste additions and available space in a bar graph format to allow the user to more easily visualize the tank space usage. Numbered comments have been added to the bar graph explaining the inventory changes. These comments follow the figure. During the period when SST solids are being retrieved and pretreated (full Phase 2 processing rate will pretreat a full tank of SST solids waste in less than one month), some of the tanks are being filled and pretreated (up to twice) within the same fiscal year. These tanks will show up as "empty" in the graphic because they have been filled and pretreated within the same fiscal year and their inventory at the end of the year has been reduced to a heel. Thus, the bar graph misleads the user into believing that most of the space dedicated to SST solids retrieval is not needed. The space is actually needed to allow staging and processing of the SST solids wastes. Retrieval and processing rates are high enough in FY 2011-2015 that it is difficult to retrieve the wastes, allow the 100 days assumed for characterization, and pretreat at the specified processing rate.

No new tanks are needed in the next 6-8 years but tank space is critical in the FY 2005-2006 timeframes if some of the space saving options mentioned above are exercised. Space saving options will continue to be reviewed. It takes 6-8 years to build additional tanks so the tight space seen in the 2005-2006 timeframe will be monitored closely next year to see if new tanks are needed. Several options are being investigated and reviewed for next year's submittal of the OWVP.

Efforts will be made next fiscal year to accelerate retrieval of the tanks in SY farm earlier as mentioned in the above options. This action will not impact TPA milestones. The other options will also be looked at further. By completing

one of the options, the projected tank space needs could be reduced to fit the available space. Lockheed Martin Hanford Company is concerned about the projected tank space shortage in FY 2011-2015 and beyond but appropriate time is available to review the assumptions and projected tank space in later years.





Figure 3. Double-Shell Tank Requirements for Case 1--TPA Compliant

Table 14. Spreadsheet of Waste Additions and Reductions for Case 1

| FISCAL YEAR | 1997 | 1998 | 1999 | 2000 | 2001 | 2002 | 2003 | 2004 | 2005 | 2006 | 2007 | 2008 | 2009 | 2010 | 2011 | 2012 | 2013 | 2014 | 2015 |
|--|-------|-------|-------|-------|-------|-------|-------|-------|-------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| STARTING INVENTORY | 19048 | 18353 | 18572 | 19735 | 23043 | 23384 | 23419 | 22713 | 23955 | 23025 | 21318 | 23516 | 21845 | 21575 | 24049 | 28590 | 29144 | 24504 | 18078 |
| SPACE UTILIZATION | | | | | | | | | | | | | | | | | | | |
| Spare Space | 2280 | 2280 | 2280 | 2280 | 2280 | 2280 | 2280 | 2280 | 2280 | 2280 | 2280 | 2280 | 2280 | 2280 | 2280 | 2280 | 2280 | 2280 | 2280 |
| Watchlist Space | 702 | 702 | 702 | 691 | 691 | 608 | 924 | 411 | 411 | 411 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Contingency Space | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Segregated Space | 2493 | 3350 | 2730 | 1064 | 2123 | 2603 | 2873 | 2023 | 1902 | 2795 | 1751 | 963 | 30 | 30 | 30 | 0 | 0 | 0 | 0 |
| Priority Operational Space | 3042 | 2261 | 2373 | 4435 | 4329 | 4452 | 4380 | 4609 | 5803 | 6493 | 6003 | 6355 | 4120 | 3932 | 4882 | 6719 | 10298 | 12245 | 17854 |
| NEW WASTE ADDITIONS | | | | | | | | | | | | | | | | | | | |
| B Plant/WSCF | 12 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| S Plant | 4 | 20 | 16 | 16 | 16 | 15 | 15 | 15 | 15 | 15 | 15 | 12 | 12 | 12 | 12 | 12 | 12 | 12 | 12 |
| T Plant | 14 | 17 | 17 | 24 | 24 | 24 | 25 | 25 | 25 | 25 | 26 | 26 | 26 | 27 | 27 | 27 | 27 | 28 | 28 |
| 300/400 Areas | 16 | 28 | 23 | 5 | 4 | 12 | 5 | 5 | 12 | 5 | 5 | 12 | 5 | 5 | 12 | 5 | 5 | 12 | 5 |
| TCO | 38 | 109 | 5 | 45 | 5 | 5 | 355 | 5 | 205 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 |
| Flushes | 327 | 100 | 635 | 1102 | 212 | 49 | 184 | 10 | 100 | 110 | 110 | 112 | 109 | 109 | 112 | 109 | 109 | 112 | 109 |
| SWL Pumping | 131 | 237 | 1813 | 3346 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Tank Farms | 75 | 170 | 190 | 180 | 225 | 205 | 200 | 170 | 155 | 205 | 155 | 205 | 155 | 205 | 155 | 205 | 155 | 205 | 155 |
| SST Retrieval | 0 | 0 | 750 | 0 | 0 | 0 | 0 | 2217 | 1199 | 839 | 2771 | 1410 | 1742 | 2417 | 8644 | 13529 | 16483 | 15861 | 12362 |
| PFP | 0 | 5 | 12 | 3 | 2 | 1 | 1 | 1 | 1 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Inventory | 0 | 0 | 0 | 65 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Retrieval Water | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 426 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Everything Else | 64 | 5 | 175 | 5 | 5 | 14 | 50 | 373 | 122 | 59 | 14 | 5 | 21 | 5 | 105 | 105 | 105 | 105 | 105 |
| Pretreatment Dilution | 0 | 0 | 0 | 0 | 326 | 428 | 653 | 709 | 0 | 626 | 1436 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| In-Tank Wasting | 0 | 0 | 0 | 146 | 647 | 750 | 1155 | 0 | 0 | 0 | 826 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| NEW WASTE ADDITIONS TOTAL | 681 | 691 | 3636 | 4938 | 1466 | 1503 | 2643 | 3530 | 1834 | 2316 | 5363 | 1787 | 2075 | 2785 | 9072 | 13997 | 16901 | 16340 | 12781 |
| TOTAL WASTE BEFORE EVAP | 19729 | 19044 | 22207 | 24674 | 24509 | 24887 | 26062 | 26243 | 25789 | 25341 | 26680 | 25304 | 23920 | 24361 | 33121 | 42586 | 46044 | 40846 | 30858 |
| EVAPORATOR WVR | -1074 | -72 | -2472 | -1631 | -1125 | -668 | -1033 | 0 | -642 | -1714 | -586 | -982 | -361 | -312 | -350 | -334 | -389 | -338 | -395 |
| CUM EVAPORATOR WVR | -1074 | -1146 | -3618 | -5249 | -6374 | -7042 | -8075 | -8075 | -8717 | -10431 | -11017 | -11999 | -12360 | -12672 | -13022 | -13356 | -13745 | -14083 | -14478 |
| Loss due to Change of Instruments | -15 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Loss due to (Burp, Lance Evap, Surface Change, Inst, etc.) | -276 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Outflow to SST Wash Facility | 0 | -400 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Adjust waste layers due to new solids meas. | -11 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Low activity waste | 0 | 0 | 0 | 0 | 0 | -651 | -1999 | -2120 | -1973 | -2011 | -2288 | -2319 | -1668 | 0 | -4181 | -13108 | -21151 | -22430 | -21302 |
| High Level Waste Contractor | 0 | 0 | 0 | 0 | 0 | -149 | -317 | -168 | -149 | -298 | -290 | -158 | -316 | 0 | 0 | 0 | 0 | 0 | 0 |
| EVAP AND OUTFLOWS TOTAL: | -1376 | -472 | -2472 | -1631 | -1125 | -1468 | -3349 | -2288 | -2764 | -4023 | -3164 | -3459 | -2345 | -312 | -4531 | -13442 | -21540 | -22768 | -21697 |
| NET INVENTORY CHANGE | -695 | 219 | 1164 | 3307 | 341 | 35 | -706 | 1242 | -930 | -1707 | 2199 | -1672 | -270 | 2473 | 4541 | 555 | -4639 | -6428 | -8916 |
| END OF YEAR INVENTORY | 18353 | 18572 | 19735 | 23043 | 23384 | 23419 | 22713 | 23955 | 23025 | 21318 | 23516 | 21845 | 21575 | 24049 | 28590 | 29144 | 24504 | 18078 | 9161 |
| TOTAL CAPACITY | 26870 | 27165 | 27820 | 31513 | 32807 | 33360 | 33170 | 33278 | 33421 | 33297 | 33550 | 31443 | 28005 | 30291 | 35782 | 38143 | 37082 | 32603 | 29295 |
| | 24 | 24 | 25 | 28 | 29 | 30 | 30 | 30 | 30 | 30 | 30 | 28 | 25 | 27 | 32 | 34 | 33 | 29 | 26 |

* Evaporation of 72 kgal in FY98 is the in-tank evaporation of Tank 102-AZ



Comments for Figure 4--Double-Shell Tank Inventory and Space for the TPA Compliant Case

This bar chart graphic is meant to show the increase and decrease in the various waste categories or waste types for this year's Case 1 projection. Tank space needs for "in-tank washing" have been included. Spare and processing receipt tanks are not shown. Beginning in 1999, a portion of the evaporator operational space maintained in Tanks 102-AW and 106-AW (abbreviated 2AW and 6AW on Figure 4) will also be considered as spare space to decrease tank space needs. Levels of Dilute Non-complexed waste (DN) in the dilute receiver and evaporator tanks will vary with time. The bar for each year depicts the tank space needs for the end of that fiscal year and may not show tank space changes occurring during the fiscal year, especially if the tank inventory has been removed prior to the end of the fiscal year.

Numbered Comments for "Tank Inventory and Space" Graphic

1. "Watch List" (WL) tank inventories are constant from 1995-2000. In FY 2001, the contents of Tank 105-AN are diluted and transferred to the intermediate staging tanks to supply feed for Phase 1B processing.
2. Space above Neutralized Cladding Removal Waste (NCRW) solids is routinely used to store Dilute Non-complexed (DN) waste. For clarity, the graph shows this DN inventory in with the other DN inventory toward the top of the graph. (i.e, to ascertain "free" space, add the space shown in the NCRW group to that shown in the DN group).
3. Space above PFP Tru (PT) solids is used to store DN waste, (see note 2). It is assumed that complexed salt well liquid pumping in 200 West Area would be added to Tank 102-SY before the PT (PFP TRU) solids were retrieved (see note 9).
4. The slight decrease in the NCAW category from 1997-2002 is caused by in-tank concentration of the NCAW supernates.
5. In 1997 there is an increase in space above the Dilute Complexed (DC) waste inventory. This results from pumping the DC waste from Tank 101-AY (980 Kgal) to other tanks prior to and during evaporation (Tanks 108-AP, 106-AN, and 102-AW), thus creating more net headspace. Reduction in the DC waste inventory in 1997 was caused by an evaporation. Evaporation is necessary to cleanout Tank 101-AY for pre-staging of Envelope B feed and to reduce storage volume.
6. The CC (or DSSF) group shows increases in inventory over time due to the evaporation of dilute complexed wastes. When a CC tank becomes full, a new tank must be added, which obviously has empty space in it. This is shown graphically year-to-year with step increases in the number of CC tanks and variations in the available space shown in the group. Increase in CC volumes occur due to Salt Well Liquid (SWL) pumping. In 2005, the large increase in the number of tanks in the CC group is caused by staging CC wastes into the processing staging tanks.

7. The changes in NCAW inventory and tank needs starting in 2000 were partially caused by in-tank washing of the NCAW solids. The final result of the operations were completed by the end of FY 2006 but the NCAW solids vitrification is not completed until FY 2009 (See Table 6 for additional detail). The increase in tank count in FY 2004 is caused by staging aging waste supernate into processing feed tanks which are then temporarily counted as part of this group. The increase in inventory from 2009 on is caused by the slow accumulation of either Sr/TRU entrained solids.
8. Retrieval of Single-Shell Tank (SST) solids was started in FY 2004. Initial SST solids were stored in Tanks 101-AN and 102-SY.
9. Decrease in DSSF inventory in FY 2004 results from Phase 1B processing. The DSSF category actually shows a slight increase in inventory and tank count as waste staging occurs in FY 2002-2003. By 2004, the workoff due to processing has decreased the inventory and tank count.
10. The PT (PFP TRU) solids from Tank 102-SY were cross-sited to Tank 105-AW beginning January 2006. Therefore, the PT waste category and space are eliminated in FY 2006.
11. Increase in CC inventory and tank count in 2006 is caused by dilution and staging of watch list waste from Tank 107-AN for processing in Phase 1B. The tank count remains at a high level for the CC group (staging tanks classified as CC group during use) until CC wastes have been worked off.
12. By FY 2013, the Phase 2 processing is operating at full capacity and is working off wastes faster than SST solids volumes are being retrieved. All the tanks in the SST Solids (SSTS) category contained waste at some time during the year (some have been filled and emptied twice) but by the end of the Fiscal Year the tanks happen to be empty and the ending inventory is much lower than the tank capacity for this group. Thus, the bar graph misleads the user into believing that most of the space dedicated to SST solids retrieval is not needed. The space is actually needed to allow staging and processing of the SST solids wastes. Retrieval and processing rates are high enough in FY 2014-2015 that it is difficult to retrieve the wastes, allow the 100 days assumed for characterization, and pretreat at the specified processing rate.

Table 15. Projected Tank Usage on 9/2001 for the Case 1 Projection

| Tank | Liquid (Kgal) | Solids (Kgal) | Total (Kgal) | Comment/Projected Usage for Tank as of 9/2001 |
|--------|---------------|---------------|--------------|---|
| 101-AY | 892 | 108 | 1000 | Received NCAW supernate from 1AZ starting 8/2000 & from 2AZ starting 9/2001 |
| 102-AY | 955 | 22 | 977 | Received C-106 solids starting 9/1998 |
| 101-AZ | 296 | 50 | 346 | Start in-tank washing 8/2000 by decanting to 1AY |
| 102-AZ | 290 | 104 | 394 | Start in-tank washing 9/2001 by decanting to 1AY |
| 101-SY | 516 | 605 | 1121 | CC/SL inventory; watch list (WL) tank |
| 102-SY | 823 | 123 | 946 | DN/PT inventory; 200 West Area SWL and dilute receiver |
| 103-SY | 386 | 362 | 748 | CC/SL inventory; WL tank |
| 101-AW | 820 | 306 | 1126 | DSSF/SL inventory; WL tank; third tank to be pretreated |
| 102-AW | 63 | 40 | 103 | Evaporator feed tank |
| 103-AW | 653 | 487 | 1140 | DSSF/PD solids; "topped off" w/ DSSF in 10/1999 |
| 104-AW | 750 | 390 | 1140 | Refilled w/ DSSF in FY 2000 |
| 105-AW | 117 | 286 | 403 | DN heel/PD solids; receives all 100 Area wastes & solids from 9/1997-2005; dilute receiver FY 2001 |
| 106-AW | 803 | 228 | 1031 | Evaporator slurry receiver tank |
| 101-AN | 150 | 33 | 183 | SWL-DC receiver until end of FY 2000 |
| 102-AN | 984 | 89 | 1073 | CC (TRU) inventory |
| 103-AN | 549 | 410 | 959 | DSS inventory; WL tank |
| 104-AN | 606 | 449 | 1055 | DSSF inventory; WL tank; second tank to be pretreated |
| 105-AN | 619 | 489 | 1108 | DSSF inventory; WL tank; first tank to be pretreated; 200 East Area dilute receiver FY 2002 on |
| 106-AN | 1093 | 17 | 1110 | Received CP waste from 2AP in 5/2000 |
| 107-AN | 872 | 247 | 1119 | CC (TRU)/SL inventory |
| 101-AP | 1140 | | 1140 | Filled w/ DSSF by 9/2000 |
| 102-AP | 28 | | 28 | SF inventory; processing intermediate staging tank FY 2001 on; heel in tank residual from 5AN which was transferred to 6AP |
| 103-AP | 1139 | 1 | 1140 | spare tank until 3/1999; receives concentrated waste early FY 1999 on |
| 104-AP | 28 | | 28 | Stage DN for evaporation until 9/2000; processing intermediate staging tank 10/2000 on; residual heel in tank from 4AN which was moved to 8AP |
| 105-AP | 986 | 154 | 1140 | Filled w/ DSSF by 2/2000; |
| 106-AP | 755 | 4 | 759 | SWL-DN receiver and dilute receiver in E. Area until 10/2000; vendor staging tank 10/2000 on |
| 107-AP | 329 | | 329 | Stage DN for evaporation; entrained solids return tank from 6/2002 on |
| 108-AP | 748 | 8 | 756 | Stage DC for evaporation; vendor staging tank 10/2000 on |

Interpretation of Short Range Projection Results

This section provides an interpretation of detailed short range projection results. The OWVP presents certain information in the form of graphics. A number of these graphics show 12 months of historical operations and 24 months of projected operations. Most of the vertical axis represents thousands of gallons of waste generated. An example of this type of graphic is the facility waste generation graphic. The volume generated per month for each facility is depicted on a facility waste generation graph. An example of the facility waste generation graph for PUREX waste is shown below (Figure 5).




Figure 5. Facility Waste Generation Graphic

In the computer simulation, facility waste streams are routed to a receiver tank. A tank fill graphic shows the filling of the receiver tank and is on the same page as the facility waste generation graph of the waste stream it receives. The tank fill graphic shows the rate a specific tank is filled with waste. Usually when a receiver tank is full, waste is transferred to a holding tank. This waste is either evaporated or stored for future disposal. For every transfer out of a tank, there is a corresponding receipt of the same volume into another tank or facility. For every evaporation out of a tank there is a corresponding receipt of the more concentrated waste in the receiving tank and an increase in the condensate from the 242-A Evaporator being sent to the LERF.

An example of this type of graph (a tank fill graphic) for Tank 105-AW is shown below (Figure 6).




Figure 6. Tank Fill Graphic

The accuracy of this projection is directly related to the facility supplied assumptions. Some of the major assumptions are listed below:

- o Process operating schedules define the planned dates of plant operations or deactivation activities. These assumptions are consistent with the TWRS program planning. Volumes and schedules for the various Hanford facilities for the three projection cases are presented in Sections 3 and 4.
- o Plant waste generation assumptions define the volume and type of waste that will be generated by the plants. These assumptions result from an analysis of recent waste generation history and future plans specified by the plants. Most waste streams volumes are projected based on historical data and/or facility supplied operating schedules. Section 5.4 includes a comparison of actual waste receipts to the new facility waste generation targets for the period October 1996 to September 30, 1997.

Tank roles and waste routings define the use of tanks in the system. For example, a tank will be designated to act as receiver of the PUREX facility miscellaneous waste (Tank 105-AW), while other tanks will store concentrated waste.

The graphics depicted on the next few pages summarize the short range projection results for Projection Case 1. Figure 7 shows the role of each tank for a period of four years. It should be noted that if a tank has several transfers in or out of the tank in one month, no fluctuation in the tank level may appear. This is because the graphic program plots tank levels as of the last day of the month and any changes that occur during the month are not shown. The simplified routing schematic shown in Figure 8 depicts the assumptions that are made about the routing of waste from the plants to the tanks and from tanks to the facilities.





Figure 7. Tank Levels During the Short Range Projection

Figure 8. Simplified Schematic of Current and Planned Routings



The results of this projection are forecasts of evaporator operations, LAW processing and disposal, HLW processing and disposal, and an analysis of tank space issues for aging and non-aging waste tanks.

Evaporator WVR and LERF Condensate

Schedule and operational considerations presented in Section 3 result in the following Evaporator Waste Volume Reduction (WVR) and LERF Condensate production volumes for the Case 1 projection. The ratio of process condensate sent to LERF for every gallon of Waste Volume Reduction (WVR) for Evaporator Campaigns 94-1, 94-2, and 95-1 was 1.29, 1.24, and 1.26, respectively (Guthrie, 1996). The evaporator seal water and demister spray upgrade could reduce future process condensate production to 1.15 gallon of condensate/gallon of WVR which would lower the value used for future projections. This projection used a value of 1.20 gallon of condensate/gallon of WVR (Guthrie, 1997b) to project future condensate production recorded in Table 16. The waste sources, campaign schedule, and concentrated waste receiver tanks used in this projection are summarized Table 17.

Table 16. Evaporator WVR and LERF Additions for the Case 1 Projection

| FISCAL YEAR | EVAPORATOR WVR (KGAL) | CONDENSATE TO LERF (KGAL) |
|-------------|--------------------------|------------------------------|
| 1998 | 0 | 0 |
| 1999 | 2470 | 2960 |
| 2000 | 1630 | 1960 |
| 2001 | 1130 | 1360 |
| 2002 | 670 | 800 |
| 2003 | 1030 | 1240 |
| 2004 | 0 | 0 |
| 2005 | 640 | 770 |
| 2006 | 1710 | 2050 |
| 2007 | 590 | 710 |
| 2008 | 980 | 1180 |
| 2009 | 360 | 430 |
| 2010 | 310 | 370 |
| 2011 | 350 | 420 |
| 2012 | 330 | 400 |
| 2013 | 390 | 470 |
| 2014 | 340 | 410 |
| 2015 | 400 | 480 |

Table 17. Evaporator Campaign Schedule for the Case 1 Projection

| Campaign | Start Date | Staging Tank(s) | Source | Waste Feed Type | Feed Volume (Kgal) | Receiver Tank |
|----------|--|------------------|------------------------|-----------------|--------------------|-------------------|
| FY98 | Cold Run. Concentrated wastes from 106-AW (Campaign 97-2) transferred to 103-AP. | | | | | |
| 99-1 | 3/99 | Direct to 102-AW | 102-AY, 106-AP, 108-AP | DN | 1000+ | 105-AP |
| 99-2 | 8/99 | 107-AP | 102-SY & 106-AP | DN-SWL & DN | 1000+ | 105-AP |
| | 9/99 | Direct to 102-AW | 104-AW | DN | 700 | 105-AP 104-AW |
| 00-1 | 3/00 | 104-AP | 102-SY & 106-AP | DN-SWL & DN | 1000+ | 104-AW 101-AP |
| 00-2 | 6/00 | 107-AP | 102-SY | DN-SWL & DN | 1000+ | 101-AP |
| 00-3 | 9/00 | 104-AP | 102-SY | DC-SWL | 1000+ | 101-AP 103-AP |
| | 10/00 | 107-AP | 102-SY, 101-AN, 105-AW | DN/DC-SWL & DN | 1000+ | 103-AP 101-AQ* |
| 01-1 | 2/01 | 107-AP | 102-SY & 108-AP | DN/DC-SWL | 1000+ | 101-AQ* |
| 01-2 | 6/01 | 107-AP | 106-AP & 108-AP | DN/DC-SWL | 1000+ | 105-AN |
| 02-1 | 11/01 | 105-AN | 105-AW & 101-AN | DN & DN-SWL | 1000+ | 105-AN |

Note: Tank 101-AP is characterized and once the contents are found to be suitable, the DSSF contents are stored on top of the solids in Tanks 103-AW and 104-AW in early FY 2000. This allows Tank 101-AP to be refilled later in FY 2000. This method should allow topping off Tanks 103-AW and 104-AW with DSSF with less likelihood of producing another watch list tank than direct transfers from Tank 106-AW.
*Tank 101-AQ used to store DSSF in FY 2001 is an overflow tank.

See Figure 9 for dilute receiver tanks, evaporator WVR, and the 242-A Evaporator operating schedules for the Case 1 projection.

Based on the 50 Mgal/year treatment capacity for the ETF, the ETF should have no problem processing the projected evaporator condensates thru 2015. There should be sufficient LERF and DST space for storage of Hanford facilities generated waste and condensates between FY 1998 and the end of 2015, provided:

- the 242-A Evaporator schedule is achieved
- the amount of condensate sent to LERF does not grossly exceed the 1.2 gallon condensate/gallon WVR factor
- facilities stay within their respective generation limits
- no unexpected waste receipts are received in the DSTs




Figure 9. Dilute Receiver Tanks and 242-A Evaporator Operations

NON-AGING TANK SPACE

In later parts of the projections when tank space becomes tight due to processing needs and/or the amount of SST solids being retrieved, the evaporator is assumed to operate yearly to minimize waste storage needs and to decrease the volume of retrieved SST solids waste. Tank space pinches occurring between FY 2000 and FY 2015 (Figure 3) are caused by a combination of factors, including:

- o SWL pumping (SST stabilization) volumes pumped by the end of FY 2000 and the use of three tanks in 200 East Area to pump SWL
- o Four tanks are designated for staging wastes for Phase 1B processing--two vendor tanks (Tanks 106-AP and 108-AP) and two intermediate staging tanks (Tanks 102-AP and 104-AP)
- o The large volume of SST solids retrieved beginning in FY 2004
- o The decision not to operate the Grout Facility has eliminated an early means of freeing up DST space
- o The decision not to consolidate NCAW solids has increased the DST space needs from 2001 on
- o Overlap of retrieval of wastes from Tanks 101-SY, 102-SY, and 103-SY with the retrieval of SST solids in 200 West Area

Figures 10 through 14 show the operation of most of the DST waste tanks for the Case 1 projection.




Figure 10. PUREX Facility Waste Generations and Tank Levels

OP10




Figure 11. West Area Waste Generations and Tank Levels





Figure 1.2. B Plant and Hanford Facility Waste




Figure 13. AP Tank Farm Levels




Figure 14. AN Tank Farm Levels

AGING WASTE TANK SPACE

It is assumed that the PUREX facility will not restart. With PUREX not restarting only two aging waste tanks (Tanks 101-AZ and 102-AZ) are required to store existing aging waste.

One additional aging waste tank will be required to retrieve and store the contents of Tank 106-C (a SST containing high heat waste). Waste from Tank 106-C is assumed to be retrieved to Tank 102-AZ from September 1998 thru June 1999. Tank 102-AZ is also used to retrieve the SST solids from Tank 104-C beginning in FY 2004.

In Revision 21 of this document, it was assumed that all NCAW solids and the 106-C solids would be combined into one aging waste tank (Tank 102-AZ) and that all NCAW supernates would be concentrated into one aging waste tank (Tank 101-AZ). Since that document was published, studies have been completed which looked at numerous sludge washing/combination options (Powell, 1996a). The alternatives for consolidating high heat sludges have been reviewed by a decision board comprised of Hanford contractor management, a DOE/RL representative, and a WDOE representative. It was concluded that consolidating all the sludges into a single tank would require modifications to the tank farm safety basis. The preliminary decision reached was not to consolidate all the high heat sludges into a single tank. The selected alternative (Alternative 8 Modified) would wash the sludges in the tanks they reside in without additional consolidation of solids. The NCAW supernates could not be combined into a single aging tank (Tank 101-AZ) due to the 5 M Na limit but would be concentrated and sent to Tank 101-AZ and an additional non-aging tank (Powell, 1996b). This action has increased DST needs from FY 2001 as compared to Revision 21 DST space needs.

A graph of aging waste tank space requirements as a function of time is presented in Figure 15. The uses of each individual aging waste tank for the TPA Compliant Case are shown in Figure 16.





Figure 15. Aging Tank Requirements

Figure 16. Aging Waste Tank Usage



5.2 Projection Case 2 Results and Conclusions

Tank space needs for the Case 2 projection are shown in Figure 17. The tank space needs for this projection clearly show that a delayed start of waste treatment will require a delay in the rate of SST solids retrieval. Tank space needs reach a maximum of 28 tanks in FY 2006 and then begin to decrease as wastes are processed. The tank space needs for this projection indicate that SST solids retrieval should not be started until approximately FY 2007. By the end of 2015, 15 tanks are being used meaning that 13 tanks are available for SST solids retrieval.

For projection Case 2, using a value of 1.20 gallon of condensate/gallon of WVR (Guthrie, 1997b) to project future condensate production results in the WVR and LERF additions reported in Table 18. The waste sources, campaign schedule, and concentrated waste receiver tanks used in the Case 2 projection are summarized Table 19.




Figure 17. Double-Shell Tank Requirements for Case 2

Table 18. Evaporator WVR and LERF Additions for the Case 2 Projection

| FISCAL YEAR | EVAPORATOR WVR (KGAL) | CONDENSATE TO LERF (KGAL) |
|-------------|--------------------------|------------------------------|
| 1998 | 0 | 0 |
| 1999 | 2490 | 2990 |
| 2000 | 650 | 780 |
| 2001 | 800 | 960 |
| 2002 | 570 | 680 |
| 2003 | 1700 | 2040 |
| 2004 | 0 | 0 |
| 2005 | 1080 | 1300 |
| 2006 | 910 | 1090 |
| 2007 | 540 | 650 |
| 2008 | 640 | 770 |
| 2009 | 920 | 1100 |
| 2010 | 430 | 520 |
| 2011 | 460 | 550 |
| 2012 | 330 | 400 |
| 2013 | 390 | 470 |
| 2014 | 340 | 410 |
| 2015 | 400 | 480 |

Table 19. Evaporator Campaign Schedule for the Case 2 Projection

| Campaign | Start Date | Staging Tank(s) | Source | Waste Feed Type | Feed Volume (Kgal) | Receiver Tank |
|----------|--|------------------|------------------------|-----------------|--------------------|----------------------------|
| FY98 | Cold Run. Concentrated wastes from 106-AW (Campaign 97-2) transferred to 103-AP. | | | | | |
| 99-1 | 3/99 | Direct to 102-AW | 102-SY, 106-AP, 108-AP | DN | 1000+ | 105-AP |
| 99-2 | 8/99 | 107-AP | 102-SY & 106-AP | DN-SWL & DN | 1000+ | 105-AP |
| | 9/99 | Direct to 102-AW | 104-AW | DN | 700 | 105-AP |
| 00-1 | 7/00 | 104-AP | 102-SY & 106-AP | DN-SWL & DN | 1000+ | 105-AP 104-AW 101-AP |
| 01-1 | 2/01 | 107-AP | 102-SY & 101-AN | DN-SWL | 1000+ | 101-AP |
| 01-2 | 7/01 | 107-AP | 106-AP & 108-AP | DN-SWL & DC-SWL | 1000+ | 101-AP 101-AY |
| 02-1 | 11/01 | 104-AP | 105-AW, 101-AN, 102-SY | DN & DN/DC-SWL | 1000+ | 101-AY 103-AP |
| 03-1 | 11/02 | 104-AP | 102-SY, 106-AP, 105-AW | DN/DC-SWL & DN | 1000+ | 103-AP |
| 03-2 | 5/03 | 104-AP | 102-SY & 105-AW | DN/DC-SWL & DN | 1000+ | 103-AP 101-AN |
| 03-3 | 9/03 | 104-AP | 102-SY & 105-AW | DN/DC-SWL & DN | 1000+ | 101-AN |
| FY04 | Evaporator outage is scheduled for FY 2004. | | | | | |

5.3 Projection Case 3 Results and Conclusions

Tank space needs for the Case 3 projection are shown in Figure 18. The tank space needs for this projection clearly show that a delayed start of waste treatment will require a delay in the rate of SST solids retrieval. Tank space requirements exceed available space by the end of FY 2004 due to SST solids retrieval. The tank space needs for this projection clearly show that SST solids retrieval should not be started until approximately FY 2007 and that the rate of retrieval would have to be reduced to match the slower waste treatment schedule built into this projection.




Figure 18. Double-Shell Tank Requirements for Case 3

5.4 Actual Waste Generation Compared to Management Limits

During the Tank Space Management Board (TSMB) meeting on August 7, 1991, the need to establish new facility waste generation limits was discussed with the Hanford facility representatives based on additional delays in the 242-A Evaporator restart. A new total monthly waste generation rate of 64 Kgal/month was adopted based on: discussions with facility representatives, the average monthly waste generation rate for each facility during FY 1991, and the need to provide contingency space for potential delays in the 242-A Evaporator restart.

Facility generation limits were not established for high priority waste generations, which were assigned to "Priority Space". These generations included the PFP stabilization campaign (safety), SWL pumping (TPA milestone), and the 242-A Evaporator (space necessary for the mini-run and restart).


New average monthly waste generation targets have been established for this projection with waste generations being reduced by the facilities (references and discussion in Section 3). Table 20 presents a comparison of the previous limits established for each facility, the newly established target rates for this projection, and the actual average monthly waste generation rate (Kgal/month) for the period October 1996 through September 30, 1997. B Plant is currently in a terminal cleanout (TCO) mode and therefore does not have a monthly target waste generation for miscellaneous waste generations for Rev. 24. TCO at the PUREX facility was completed last year but the facility will be sending 5 Kgal/year of collected condensate to Tank Farms.

Table 20. Comparison of Average Monthly Waste Generation Rates (Kgal/month)

| FACILITY | 64 KGAL/MONTH MANAGEMENT LIMIT FROM OWVP REV. 20 | FACILITY TARGET FOR REV. 23 # | AVERAGE MONTHLY FACILITY GENERATIONS (10/96 - 9/97) |
|-----------------|---|--|--|
| TANK FARMS | 10.0 | 10.0 | 2.7 |
| B PLANT | 23.0 | N/A-TCO MODE | N/A-TCO MODE |
| WESF | N/A | 1.7 | With B PLANT |
| PUREX | N/A | 0.4 | N/A-TCO MODE |
| PFP | N/A | 0.4 | N/A |
| T PLANT | 6.0 | 1.4 | 1.4 |
| S PLANT | 5.0 | 2.1 | 0.6 |
| 300 AREA | 5.0 | 4.2 | 2.2 |
| 400 AREA | 0.0 | 0.2 | 0.0 |
| TOTAL | 64.0 | 20.4 | 6.9 |

Monthly Totals do not include Terminal Clean-out Volumes or SWL Pumping

Due to the commendable efforts by the Hanford facilities, all waste generators are at or below their new waste generation target for the period October 1996 through September 30, 1997. A comparison of the volumes of waste entering the DST tank space for that time period is compared graphically to the various targets or projected generations in Figures 19-22.



NOTE: THIS GRAPHIC DEPICTS CONTRIBUTIONS FROM FACILITY GENERATIONS; TERMINAL CLEAN-OUT AND SWL PUMPING IS NOT SHOWN

** B-PLANT LISTED UNDER TERMINAL CLEAN-OUT FROM 10/96.

Figure 19. Comparison of Facility Generations to "TARGET"




Figure 20. Comparison of Monthly Average Waste Generation To Target Rate




Figure 21. Contributions From Salt Well Liquid Pumping




Figure 22. Contributions From TCO (June 30, 1998)

6.0 SPACE SAVING ALTERNATIVES

In the near term, space saving alternatives include waste minimization, continued availability of the 242-A Evaporator, LERF availability, and the operation of the ETF. These alternatives must be considered because new inputs to the system may develop (e.g., unexpected new waste streams or a leaking SST or DST).

Should a tank space shortage develop in the period 1998 through 2015, response to the shortage for the TPA Compliant Case must be in one of three areas. The inflows to the system must be reduced, the outflows to the system must be increased (or started earlier), or the available tank space increased. Inflows to the system include miscellaneous facility waste generations, TCO wastes, in-tank washing, dilution of Tanks 101-SY and 103-SY (for processing), processing, SWL pumping, and SST solids retrieval. Outflows include the 242-A Evaporator and waste disposal (processing and vitrification). Increasing the tank space available could be done by building more tanks (a six to eight year task), mixing segregated waste types (which would gain about half a million gallons of space), or operating without reserved spare tank space. A cost/benefit analysis needs to be completed to determine the best alternative.

In addition to minimizing waste generations, other actions could be pursued. The list below includes many actions which can result in tank space savings or economization, and can serve as a starting point in a tank space optimization program.

PUREX Facility

- TCO of PUREX was completed in FY 1997. Therefore, waste reductions for PUREX will not be a viable option.

B Plant

- Continue to reduce waste being generated at B Plant
- Reduce or eliminate flush volumes following low-level waste transfers to DSTs

Plutonium Finishing Plant

- Continue to reduce waste being generated at PFP (only 27 Kgal of total waste are scheduled to be generated from FY 1998-2006)

6.0 SPACE SAVING ALTERNATIVES (CONTINUED)

Tank Farms

- Continue to reduce waste being added to DSTs
- Continue waste accountability and minimization controls
- Develop a total waste cutoff plan
- Increase the 5 M Na limitation on aging waste tanks
- Use dilute waste for retrieval, air lift circulator flushes, line flushes, etc.
- Increase the WVR of the 242-A Evaporator
- Accelerate plans to consolidate solids from Tanks 102-SY into Tank 105-AW
- Delay SWL pumping
- Build new tanks
- Accept loss of waste segregation (used as a last resort)
- Store facility generated waste in designated "spare tank space" (used in an extreme emergency)
- Improve efficiency of the 242-A Evaporator
- Solidify treated waste and dispose of as low level waste in burial grounds
- Consolidate NCAW and Tank 106-C solids in one aging tank with one additional aging tank being used to combine NCAW supernates (requires modification of safety basis).
- Increase the heat limit on non-aging DSTs to allow either the Tank 106-C wastes or the supernate from Tank 101-AZ to be stored in a non-aging DSTs if the in-tank washing consolidations are not allowed
- Concentrate DSSF to Double-Shell Slurry (DSS). Experience with Tank 101-SY makes this alternative highly unlikely.
- Store waste in single-shell tanks (used in an extreme emergency; would require approval by DOE, EPA, and Ecology)
- Store waste in facility storage tanks or portable tanks such as railcars (used in an extreme emergency; total space available is small compared to the contents of a DST)
- Upgrade single-shell tanks by adding a liner to allow storage of waste

Grout

- Reinstate the Grout Disposal Program (unlikely to occur; considered an emergency option only)
- Grout the existing waste in Tanks 102-AP and 101-AW

7.0 BIBLIOGRAPHY

- Alderman, C. J., December 22, 1997, Letter (DESH-9761844) to K. M. Hodgson, "Waste Volume Projection for 100 K Area Facilities for the Period FY 1998-2028."
- Anantatmula, R. P. and Ohl, P. C., June 28, 1996, WHC-SD-WM-ER-0585, Rev. 0, "DST Remaining Useful Life Estimates."
- Awadalla, N. G., April 19, 1995, WHC-SD-W236A-ER-021, Rev. 1, "Multi-Function Waste Tank Facility, Phase Out Basis."
- Barrington, C. A., May 7, 1991, Letter to J. G. Propson, "Plutonium Finishing Plant Waste Volume Projection for Fiscal Years 1991 - 2015."
- Brown, R. G., May 1996, WHC-SD-W236A-ES-012, Rev. 1, "Multi-Function Waste Tank Facility Path Forward Engineering Analysis Technical Task 3.3, Single-Shell Tank Contents."
- Carothers, K. G., May 7, 1998, Personal Communication with J. N. Strode, Caustic Addition to Tank 107-AN--5/7/98.
- Carothers, K. G., March 26, 1997b, cc: Mail Message to J. N. Strode, Solids Level--107-AN.
- Certa, P. J. and D. L. Penwell, Received July 13, 1995, Personal Communication--Hardcopy of Retrieval Sequence RE087SST.TXT for "2C3-087"--Ramped Pretreatment.
- Certa, P. J., et. al., August 1996, WHC-SD-WM-RPT-224, Rev. 0, "Low-Level Waste Feed Staging Plan."
- DeLozier, M. P., June 15, 1998, Letter (LMHC-9854671A R1) to A. M. Umek, "Subcontract Number 80232764-9-K001, Evaluation of Tank Waste Disposal Alternative Within Privatization."
- Dillhoff, T. A., December 4, 1997, Letter (BWHC-9761103) to J. N. Strode, "Waste Volume Projection Assumptions for 400 Area for the Period Fiscal Years 1998-2028."
- DOE Order RL 5820.2A, August 1990, Radioactive Waste Management, Waste Management Div., U.S. Department of Energy, Richland, Washington.
- DOE 1995, January 24, 1995, memorandum from T. P. Grumbly, Assistant Secretary for Environmental Management to the Department of Energy Secretary, U. S. Department of Energy, Washington, D. C., "Proceed with privatization of Hanford tank waste treatment by consulting with regulators, the Hanford Advisory Board, and other stakeholders, and to establish a full-time DOE task force to carry out the necessary procurement steps to implement privatization."
- Eiholzer, Sean M., March 4, 1997, cc: Mail Message to J. N. Strode, "Re: PUREX Waste Generations."

7.0 BIBLIOGRAPHY (CONTINUED)

Estey, S. D., May 31, 1994, WHC-SD-W320-TI-002, Rev. 0A, "Project W-320 Tank 241-C-106 Sluicing Process Flowsheet."

Estey, S. D. and Guthrie, M. D., March 29, 1996, Internal Memo (74A10-96-029) to N. G. Awadalla, "Data Analysis and Criteria Development to Prevent Accumulation of DST Waste With Unacceptable Gas Retention Behavior."

Estey, S. D., April 1996, WHC-SD-WM-TI-747, Rev. 0, "TRU Activity and Complexed Waste Considerations for 200 West Area SST Interim Stabilization Planning."

Fowler, K. D., April 1995, WHC-SD-WM-OCD-015, Rev. 1, "Tank Farm Waste Transfer Compatibility Program."

Funston, G. A., December 23, 1997, Letter (15530-GAF-064) to K. M. Hodgson, "Plutonium Finishing Plant Waste Volume Projection for the Period Fiscal Year 1998-2028."

Guthrie, M. D., August 18, 1983, Letter to G. M. Koreski and J. N. Strode, "Assumptions for the Operational Waste Volume Projection (for the 242-A Evaporator)."

Guthrie, M. D., January 26, 1996, Internal Memo (77310-96-005) to J. N. Strode, "1996 242-A Evaporator Waste Projection Assumptions."

Guthrie, M. D., July 29, 1997a, cc: Mail Message to J. N. Strode, "OWVP Review."

Guthrie, M. D., December 18, 1997b, Letter (WMH-9761781) to J. N. Strode, "242-A Evaporator 1998 Operational Waste Volume Projection."

Haigh, P. G., January 21, 1992, Personal Communication.

Halgren, D. L., December 31, 1997, Letter (WMH-9762066) to K. M. Hodgson, "Radioactive Waste Volume Projections for 340 Waste Handling Facility for the Period of Fiscal Year 1998-2001."

Hanlon, B. M., May 1998, WHC-EP-0182-120, "Waste Tank Summary Report for Month Ending March 31, 1998."

Honeyman, J. O., January 1998a, HNF-2021, Rev. 1, "Management Assessment of Tank Waste Remediation System Contractor Readiness to Proceed with Phase 1B Privatization."

7.0 BIBLIOGRAPHY (CONTINUED)

Honeyman, J. O., May 13, 1998b, cc: Mail Message to J. G. Kristofzski, et. al., "K-Basin Sludge Processing Schedule Slipping."

Kirch, N. W., April 28, 1997, Personal Communication.

Kirkbride, R. A., et. al., July 1997, HNF-SD-WM-SP-012 Revision 0-Draft, "Tank Waste Remediation System Operation and Utilization Plan."

Logan, T. E., January 7, 1998, Letter (054545) to B. K. Hampton, "Operational Waste Volume Projection for the 100N Area."

McDonald, K. M., December 10, 1997, Letter (WMH-9761497) to James N. Strode, "Waste Volume Projection Assumptions for T Plant for the Period Fiscal Year 1998-2028."

Miskho, G. J. and D. A. Turner, August 1990, WHC-EP-0342, Addendum 15, "Hanford Site Specific-Stream Reports."

Mihalic, M. A., December-17, 1997, Letter (050844) to E. S. McGinley, II, "Waste Volume Projection Assumptions for 105-F and 105-H Basins for Fiscal Year 1997 through 2028."

Mulkey, C. M. and Miller, M. S., June 1997, HNF-SD-WM-DQO-001, Rev. 2, "Data Quality Objectives for Tank Farm Waste."

O'Toole, S. D., August 17, 1998, cc: Mail Message to J. N. Strode, "RE: Evaporator Capability."

Penwell, D. L., July 16, 1998a, cc: Mail Message to J. N. Strode, "Here is the updated file for the OWVP." (TPA Compliant SST Solids Retrieval File).

Penwell, D. L., August 17, 1998b, cc: Mail Message to J. N. Strode, "Words for the 1998 OWVP."

Peters, B. P., July 15, 1998, cc: Mail Message to J. N. Strode, "LAW Transfers for OWVP runs."

Powell, W. J., January 22, 1996, WHC-SD-WM-ER-532, Rev.0, "Neutralized Current Acid Waste Consolidation Management Plan."

Powell, W. J., February 23, 1996, cc: Mail Message to W. B. Barton, "Modified NCAW Alternative 8."

Reynolds, D. A., March 8, 1994, Presentation at the Meeting- Assumption Changes for the Operational Waste Volume Projection.

Reynolds, D. A., May 3, 1995, WHC-SD-W236A-ES-015, Rev. 0, "Waste Segregation Analysis for Salt Well Pumping the the 200 West Area - Task 3.4."

Riley, D. C. et al, March 1988, SD-WM-TI-309, Rev. 1, "Waste Generation and Processing Rates with Volume Reduction Factors - 1988."

7.0 BIBLIOGRAPHY (CONTINUED)

- Ross, W. E., et. al., May 1998, HNF-2358, Rev. 1, "Single-Shell Interim Stabilization Project Plan."
- Schreiber, R. D. and S. A. Barker, July 1998, HNF-2974, Rev. 0, "Updated Jet Pump Durations for Interim Stabilization of Remaining Single-Shell Tanks."
- Sederburg, J. P., April 1995, WHC-SD-WM-TI-690, Rev. 0, "Waste Volume Reduction Factors for Potential 242-A Evaporator Feed."
- "Shelton, L. W. Jr., July 28, 1995, cc: Mail Message to J. N. Strode, "Tank Inventories."
- Simmons, F. M., January 5, 1998, Letter (16D00-98-FMS-001) to J. N. Strode, B Plant/Waste Encapsulation and Storage Facility Assumptions for Waste Volume Projections for 1998 through 2028."
- Slaathaug, E. J., May 27, 1998, cc: Mail Message to J. S. Garfield, et. al., "Transfer File for Strode."
- Smith, D. K., February 25, 1994, Internal Memo (16500-94-DKS-023) to G. M. Koreski/J. N. Strode, "B Plant Comments on the Assumptions for the Operational Waste Volume Projection."
- Stauffer, L. A., April 3, 1997, Interoffice Memo to B. A. Hanlon, "Solids Levels for Tanks 241-AN-103, 241-AN-104, 241-AN-105, 241-AW-101, and 241-SY-103."
- Tollefson, K. S., January 8, 1998, Letter (WMH 9850159) to K. M. Hodgson, "Update to S-Plant and Waste Sampling and Characterization Facility Waste Volume Projection Assumptions."
- Von Bargaen, B. H., April 25, 1995, WHC-SD-WM-DQO-014, Rev. 1, "242A Evaporator/Lerf Data Quality Objective."
- Wacek, H. J., June 28, 1996, cc: Mail Message, "Operational Waste Volume Projection Assumptions for 1996."
- Wagner, R. N., January 29, 1996, cc: Mail Message to J. N. Strode, "(ETF) WVP Assumptions."
- Waldo, T. L., II, June 1, 1998, cc: Mail Message to J. N. Strode, "What If Case #2 Transfer List Revision 3."
- Washenfelder, D. J., June 26, 1996a, DSI to W. B. Barton, "Revised Attachment 1 to Internal Memo Titled "Revised TWRS Disposal Program Assumptions for Operational Waste Volume Projection-73410-96-013".
- Washenfelder, D. J., July 29, 1996b, DSI to W. B. Barton, "Revised Attachment 1 and 2 to Internal Memo Titled "Revised TWRS Disposal Program Assumptions for Operational Waste Volume Projection-73410-96-013".

7.0 BIBLIOGRAPHY (CONTINUED)

Washington State Department of Ecology (WDOE), U.S. Environmental Protection Agency, and U. S. Department of Energy, Fourth Amendment, January 1994, "Hanford Federal Facility Agreement and Consent Order" (Tri-Party Agreement).

WHC 1996a, July 3, 1996, "Federal Facility Agreement and Consent Order Change Control Form," Change Number M-60-95-03.

WHC 1996b, July 3, 1996, "Federal Facility Agreement and Consent Order Change Control Form," Change Number M-50-95-01.

Wittman, R. S., June 27, 1997, cc: Mail Message to J. N. Strode, "Effective PhsII Processing Rates." (Phase 2 Processing Rate for 5 M Na)

Wittman, R. S., June 27, 1997, cc: Mail Message to J. N. Strode, "Re: Phase 2 Schedule." (Phase 2 Processing Rate for 7 M Na)

APPENDIX

APPENDIX. Acronyms

| | |
|-----------------|---|
| ASD | - ammonia scrubber distillate from |
| ASF | - ammonia scrubber feed from |
| AW | - aging waste, also called NCAW |
| BCP | - B Plant process condensate |
| CC | - complexant concentrate waste |
| CP | - concentrated phosphate waste |
| DC | - dilute complexed waste |
| DCRT | - doubly contained receiver tank |
| DN | - dilute non-complexed waste |
| DOE | - U.S. Department of Energy |
| DP | - dilute phosphate waste |
| DSS | - double-shell slurry (most concentrated double-shell tank waste) |
| DSSF | - double-shell slurry feed |
| DST | - double-shell tank |
| EIS | - Environmental Impact Study |
| FFTF | - Fast Flux Test Facility |
| FSAR | - Facility Safety Analysis Report |
| FY | - fiscal year |
| GTF | - Grout Treatment Facility |
| HFW | - Hanford facility waste (waste produced at 100, 300, 400 areas) |
| HLW | - High Level Waste |
| IPM | - Initial Pretreatment Module |
| IX | - ion-exchange |
| KGAL | - kilogallon (1000 gallons) |
| LERF | - Liquid Effluent Retention Facility |
| LETf | - Liquid Effluent Treatment Facility |
| LAW | - Low Activity Waste |
| MOTU | - metric tons of uranium |
| NCAW | - neutralized current acid waste |
| NCRW | - neutralized cladding removal waste |
| OWVP | - Operational Waste Volume Projection |
| NEA | - National Environmental Policy Act |
| NSF | - New Pretreatment Facility |
| NEV | - New Pretreatment Vault |
| NVOL | - Non-volatile oxide less sodium and silicon |
| PAD | - process distillate discharge from PUREX |
| PFP | - Plutonium Finishing Plant |
| PRF | - Plutonium Reclamation Facility |
| PAW | - phosphate/sulfate waste |
| PHMC | - Project Hanford Management Contractor |
| PUREX | - Plutonium-Uranium Extraction |
| RMC | - Remote Mechanical C Line |
| SpG | - Specific Gravity |
| SST | - single-shell tank |
| SWL | - salt well liquid |
| TCO | - terminal clean-out |
| TOE | - total operating efficiency |
| TPA | - Tri-Party Agreement |
| TRU | - transuranic |
| TRUEX | - Transuranic Extraction Process |
| TSMB | - Tank Space Management Board |
| UO ₂ | - Uranium Oxide Facility |
| WSCF | - Waste Sampling and Characterization Facility |
| WVR | - waste volume reduction |

DISTRIBUTION SHEET

| | | |
|--|----------------------------------|--------------------|
| To Distribution | From Models and Inventory | Page 1 of 4 |
| | | Date 08/18/98 |
| Project Title/Work Order HNF-SD-WM-ER-029, Rev. 24, "Operational Waste Volume Projection" | | EDT No. N/A |
| | | ECN No. ECN-643820 |

| Name | MSIN | Text With All Attach. | Text Only | Attach./ Appendix Only | EDT/ECN Only |
|------|------|-----------------------------|-----------|------------------------------|-----------------|
|------|------|-----------------------------|-----------|------------------------------|-----------------|

ONSITE

B & W Hanford, Corp.

| | | |
|-----------------|-------|---|
| E. G. Backlund | T5-54 | X |
| G. G. Bergquist | T5-55 | X |
| D. M. Bogen | T5-50 | X |
| W. W. Bowen | N2-13 | X |
| T. A. Dillhoff | N2-57 | X |
| S. M. Eiholzer | L1-03 | X |
| P. R. Ethington | L1-05 | X |
| S. D. Godfrey | S4-49 | X |
| W. A. Peiffer | S6-15 | X |
| D. K. Smith | S6-81 | X |
| E. C. Vogt | R3-56 | X |
| B. L. Wallace | S6-51 | X |
| C. D. Wollam | R3-56 | X |

Bechtel Hanford, Inc.

| | | |
|--------------------|-------|---|
| M. E. Greenidge | X5-54 | X |
| P. W. Griffin | X5-53 | X |
| J. J. McGuire | X5-53 | X |
| D. L. Schilperoort | X8-29 | X |

Department of Energy - Richland Operations

| | | |
|---------------|-------|---|
| M. L. Ramsay | S7-54 | X |
| A. B. Sidpara | S7-54 | X |
| C. D. West | S7-53 | X |
| D. D. Wodrich | S7-50 | X |

Duke Engineering Services of Hanford, Inc.

| | | |
|----------------|-------|---|
| C. J. Alderman | X3-85 | X |
| J. W. Bloom | H6-12 | X |
| G. D. Forehand | R3-86 | X |
| D. P. Mendoza | R1-43 | X |
| D. J. Watson | X3-79 | X |

Fluor Daniel Hanford

| | | |
|--------------------|-------|---|
| G. R. Franz | S7-40 | X |
| G. T. Frater | K9-46 | X |
| M. A. McLaughlin | G3-27 | X |
| A. M. Umek | S7-40 | X |
| D. J. Washenfelter | S7-40 | X |
| J. D. Williams | S7-40 | X |
| R. B. Wurz | T5-20 | X |

DISTRIBUTION SHEET

| | | |
|--|----------------------|--------------------|
| To | From | Page 2 of 4 |
| Distribution | Models and Inventory | Date 08/18/98 |
| Project Title/Work Order | | EDT No. N/A |
| HNF-SD-WM-ER-029, Rev. 24, "Operational Waste Volume Projection" | | ECN No. ECN-643820 |

| Name | MSIN | Text With All Attach. | Text Only | Attach./ Appendix Only | EDT/ECN Only |
|---------------------------------------|-------|-----------------------------|-----------|------------------------------|-----------------|
| <u>Fluor Daniel Northwest</u> | | | | | |
| P. Felise | E6-69 | X | | | |
| <u>Lockheed Martin Hanford, Corp.</u> | | | | | |
| D. I. Allen | R2-50 | X | | | |
| J. N. Appel | H6-37 | X | | | |
| J. J. Badden | T4-07 | X | | | |
| D. G. Baide | S5-05 | X | | | |
| W. B. Barton | R2-12 | X | | | |
| P. A. Baynes | H8-71 | X | | | |
| L. E. Borneman | R1-90 | X | | | |
| V. C. Boyles <u>ICB 8/19/98</u> | R2-11 | X | | | |
| D. L. Burt | R2-54 | X | | | |
| J. W. Cammann | R2-11 | X | | | |
| K. G. Carothers | R2-12 | X | | | |
| R. A. Dodd | S5-07 | X | | | |
| J. N. Doeler | T4-07 | X | | | |
| D. G. Erlandson | R2-36 | X | | | |
| K. A. Gasper | H6-37 | X | | | |
| G. J. Gauck | T4-07 | X | | | |
| M. L. Grygiel | H8-71 | X | | | |
| K. M. Hodgson <u>KMA</u> | R2-11 | X | | | |
| J. O. Honeyman | G3-21 | X | | | |
| R. D. Jensen | G3-21 | X | | | |
| J. Jo | R2-12 | X | | | |
| N. W. Kirch | R2-11 | X | | | |
| G. M. Koreski | R2-11 | X | | | |
| J. G. Kristofzski | R2-12 | X | | | |
| M. J. Kupfer | H5-49 | X | | | |
| W. E. Meeuwesen | S5-05 | X | | | |
| L. C. Mercado | T4-08 | X | | | |
| C. H. Mulkey | R1-51 | X | | | |
| R. J. Murkowski | H5-03 | X | | | |
| S. M. O'Toole | G3-21 | X | | | |
| M. A. Payne | S7-84 | X | | | |
| R. S. Popielarczyk | R2-38 | X | | | |
| R. W. Powell | H5-03 | X | | | |
| R. E. Raymond | S7-12 | X | | | |
| D. W. Reberger | S5-13 | X | | | |
| S. H. Rafaey | R1-56 | X | | | |
| W. E. Ross | S5-07 | X | | | |
| D. J. Saueressig | S8-05 | X | | | |
| J. S. Schofield | S7-12 | X | | | |
| G. A. Stanton, Jr. | S7-21 | X | | | |
| J. N. Strode <u>JNS</u> | R2-11 | 10 | | | |

DISTRIBUTION SHEET

| | | |
|--|----------------------|--------------------|
| To | From | Page 3 of 4 |
| Distribution | Models and Inventory | Date 08/18/98 |
| Project Title/Work Order | | EDT No. N/A |
| HNF-SD-WM-ER-029, Rev. 24. "Operational Waste Volume Projection" | | ECN No. ECN-643820 |

| Name | MSIN | Text With All Attach. | Text Only | Attach./ Appendix Only | EDT/ECN Only |
|------|------|-----------------------------|-----------|------------------------------|-----------------|
|------|------|-----------------------------|-----------|------------------------------|-----------------|

Lockheed Martin Hanford, Corp. - continued

| | | |
|-----------------|-------|---|
| G. R. Tardiff | S5-05 | X |
| K. S. Tollefson | R1-51 | X |
| J. A. Voogd | H5-03 | X |
| R. A. Watrous | H5-27 | X |
| R. D. Wojtasek | G3-21 | X |
| B. D. Zimmerman | H6-35 | X |
| TCSRC | R1-10 | X |

Lockheed Martin Services, Inc.

| | | |
|---------------|-------|---|
| Central Files | B1-07 | X |
|---------------|-------|---|

MACTEC

| | | |
|----------------|-------|---|
| R. L. Treat | H5-03 | X |
| D. S. Rewinkel | S7-40 | X |

Numatec Hanford Corp.

| | | |
|---------------------|-------|---|
| P. J. Certa | H5-61 | X |
| J. S. Garfield | H5-49 | X |
| J. P. Harris III | R1-49 | X |
| R. A. Kirkbride | H5-27 | X |
| S. C. Klimper | H6-35 | X |
| J. P. Marshall, Jr. | H5-61 | X |
| R. M. Orme | H5-27 | X |
| G. L. Parsons | R3-47 | X |
| C. A. Rieck | S2-48 | X |
| W. W. Rutherford | R3-25 | X |
| J. P. Sloughter | H5-49 | X |
| J. E. Van Beek | S2-48 | X |

Pacific Northwest National Laboratory

| | | |
|---------------|-------|---|
| K. D. Wiemers | K6-51 | X |
|---------------|-------|---|

Waste Management Federal Services of Hanford

| | | |
|---------------|-------|---|
| R. R. Bloom | S6-71 | X |
| S. L. Brey | T6-12 | X |
| D. L. Flyckt | S6-71 | X |
| J. E. Geary | S6-71 | X |
| C. K. Girres | T3-01 | X |
| L. D. Goodwin | T6-12 | X |
| M. D. Guthrie | S6-72 | X |
| J. A. Harris | T6-12 | X |
| D. W. Lindsey | S6-71 | X |
| S. S. Lowe | H6-29 | X |
| R. J. Nicklas | S6-72 | X |

DISTRIBUTION SHEET

| | | |
|--|----------------------|--------------------|
| To | From | Page 4 of 4 |
| Distribution | Models and Inventory | Date 08/18/98 |
| Project Title/Work Order | | EDT No. N/A |
| HNF-SD-WM-ER-029, Rev. 24, "Operational Waste Volume Projection" | | ECN No. ECN-643820 |

| Name | MSIN | Text With All Attach. | Text Only | Attach./ Appendix Only | EDT/ECN Only |
|------|------|-----------------------------|-----------|------------------------------|-----------------|
|------|------|-----------------------------|-----------|------------------------------|-----------------|

Waste Management Federal Services of Hanford - continued

| | | | | | |
|-------------------|-------|---|--|--|--|
| B. H. Von Bargaen | S6-72 | X | | | |
| G. L. Walley | T6-20 | X | | | |

Westinghouse Hanford Company

| | | | | | |
|---------------|-------|---|--|--|--|
| J. C. Midgett | B2-01 | X | | | |
|---------------|-------|---|--|--|--|

OFFSITE

Washington State Department of Ecology

| | | | | | |
|-------------|-------|---|--|--|--|
| S. McKinney | B5-18 | X | | | |
|-------------|-------|---|--|--|--|