

APR 19 1993

11

ENGINEERING DATA TRANSMITTAL

Page 1 of 1

1. EDT



142075

Station #12

2. To: (Receiving Organization) Distribution		3. From: (Originating Organization) Geosciences		4. Related EDT No.: NA	
5. Proj./Prog./Dept./Div.: ER		6. Cog. Engr.: J.A. Caggiano		7. Purchase Order No.: NA	
8. Originator Remarks: Release to file				9. Equip./Component No.: NA	
				10. System/Bldg./Facility: NA	
11. Receiver Remarks:				12. Major Assm. Dwg. No.: NA	
				13. Permit/Permit Application No.: NA	
				14. Required Response Date: 4/16/93	

15. DATA TRANSMITTED					(F)	(G)	(H)	(I)
(A) Item No.	(B) Document/Drawing No.	(C) Sheet No.	(D) Rev. No.	(E) Title or Description of Data Transmitted	Impact Level	Reason for Trans- mittal	Originator Dispo- sition	Receiver Dispo- sition
1	WHC-SD-EN-TI-147		0	Hydrologic Testing at the Single-Shell Tanks, 1989	4	1/2	1	

16. KEY					
Impact Level (F)		Reason for Transmittal (G)			Disposition (H) & (I)
1, 2, 3, or 4 (see MRP5.43)		1. Approval 2. Release 3. Information	4. Review 5. Post-Review 6. Dist. (Receipt/Acknow. Required)	1. Approved 2. Approved w/comment 3. Disapproved w/comment	4. Reviewed no/comment 5. Reviewed w/comment 6. Receipt acknowledged

(G)	(H)	17. SIGNATURE/DISTRIBUTION (See Impact Level for required signatures)								(G)	(H)
Reason	Disp.	(J) Name	(K) Signature	(L) Date	(M) MSIN	(J) Name	(K) Signature	(L) Date	(M) MSIN	Reason	Disp.
1/2	1	Cog. Eng. J.A. Caggiano		4/15/93	H6-06	ERC			H6-07	2	
1/2	1	Cog. Mgr. R.L. Jackson		4/15/93	H6-06						
		QA									
		Safety									
		Env.									
3		EDMC (2)			H6-08						
3		CENTRAL Files (2)			L8-04						

18. J.A. Caggiano Signature of EDT Originator Date 4/15/93		19. Authorized Representative Date for Receiving Organization		20. Ronald L. Jackson Cognizant/Project Engineer's Manager Date 4/15/93		21. DOE APPROVAL (if required) Ltr. No. <input type="checkbox"/> Approved <input type="checkbox"/> Approved w/comments <input type="checkbox"/> Disapproved w/comments	
--	--	---	--	---	--	--	--

INSTRUCTIONS FOR COMPLETION OF THE ENGINEERING DATA TRANSMITTAL

(USE BLACK INK OR TYPE)

BLOCK	TITLE	
(1)*	EDT	● Enter the assigned EDT number.
(2)	To: (Receiving Organization)	● Enter the individual's name, title of the organization, or entity (e.g., Distribution) that the EDT is being transmitted to.
(3)	From: (Originating Organization)	● Enter the title of the organization originating and transmitting the EDT.
(4)	Related EDT	● Enter EDT numbers which relate to the data being transmitted.
(5)*	Project/Program/Dept./Div.	● Enter the Project/Program/Department/Division title or Project/Program acronym or Project Number, Work Order Number or Organization Code.
(6)	Cognizant/Project Engineer	● Enter the name of the individual identified as being responsible for coordinating disposition of the EDT.
(7)	Purchase Order No.	● Enter related Purchase Order (P.O.) Number, if available.
(8)*	Originator Remarks	● Enter special or additional comments concerning transmittal, or "Key" retrieval words may be entered.
(9)	Equipment/Component No.	● Enter equipment/component number of affected item, if appropriate.
(10)	System/Bldg./Facility	● Enter appropriate system, building or facility number, if appropriate.
(11)	Receiver Remarks	● Enter special or additional comments concerning transmittal.
(12)	Major Asm. Dwg. No.	● Enter applicable drawing number of major assembly, if appropriate.
(13)	Permit/Permit Application No.	● Enter applicable permit or permit application number, if appropriate.
(14)	Required Response Date	● Enter the date a response is required from individuals identified in Block 17 (Signature/Distribution).
(15)*	Date Transmitted	
	(A)* Item Number	● Enter sequential number, beginning with 1, of the information listed on EDT.
	(B)* Document/Drawing No.	● Enter the unique identification number assigned to the document or drawing being transmitted.
	(C)* Sheet No.	● Enter the sheet number of the information being transmitted. If no sheet number, leave blank.
	(D)* Rev. No.	● Enter the revision number of the information being transmitted. If no revision number, leave blank.
	(E) Title or Description of Data Transmitted	● Enter the title of the document or drawing or a brief description of the subject if no title is identified.
	(F) Impact Level	● Enter the appropriate Impact Level (Block 15). Use NA for non-engineering documents.
	(G) Reason for Submittal	● Enter the appropriate code to identify the purpose of the data transmittal (see Block 16).
	(H) Originator Disposition	● Enter the appropriate disposition code (see Block 16).
	(I) Receiver Disposition	● Enter the appropriate disposition code (see Block 16).
(16)	Key	● Number codes used in completion of Blocks 15 (G), (H), and (I), and 17 (G), (H) (Signature/Distribution).
(17)	Signature/Distribution	
	(G) Reason	● Enter the code of the reason for transmittal (Block 16).
	(H) Disposition	● Enter the code for the disposition (Block 16).
	(J) Name	● Enter the signature of the individual completing the Disposition 17 (H) and the Transmittal.
	(L) Date	● Enter date signature is obtained.
	(M) MSIN	● Enter MSIN. Note: If Distribution Sheet is used, show entire distribution (including that indicated on Page 1 of the EDT) on the Distribution Sheet.
(18)	Signature of EDT Originator	● Enter the signature and date of the individual originating the EDT (entered prior to transmittal to Receiving Organization). If the EDT originator is the Cognizant/Project Engineer, sign both Blocks 17 and 18.
(19)	Authorized Representative for Receiving Organization	● Enter the signature and date of the individual identified by the Receiving Organization as authorized to approve disposition of the EDT and acceptance of the data transmitted, as applicable.
(20)*	Cognizant/Project Manager	● Enter the signature and date of the Cognizant/Project Engineer's manager. (This signature is authorization for release.)
(21)	DOE Approval	● Enter DOE approval (if required) by letter number and indicate DOE action.


*Asterisk denote the required minimum items checked by Configuration Documentation prior to release; these are the minimum release requirements.

SUPPORTING DOCUMENT

1. Total Pages 260

2. Title Hydrologic Testing at the Single-Shell Tanks, 1989	3. Number WHC-SD-EN-TI-147	4. Rev No. 0
5. Key Words SST testing hydrology groundwater APPROVED FOR PUBLIC RELEASE <i>U.S. 4/19/93</i>	6. Author Name: J.A. Caggiano <i>[Signature]</i> Signature Organization/Charge Code 81235/R4GD1	
7. Abstract WHC, 1993, <i>Hydrologic Testing of the Single-Shell Tanks, 1989</i> , prepared by Pacific Northwest Laboratory, Richland, Washington, for Westinghouse Hanford Company, Richland, Washington.		
8. PURPOSE AND USE OF DOCUMENT - This document was prepared for use within the U.S. Department of Energy and its contractors. It is to be used only to perform, direct, or integrate work under U.S. Department of Energy contracts. This document is not approved for public release until reviewed. PATENT STATUS - This document copy, since it is transmitted in advance of patent clearance, is made available in confidence solely for use in performance of work under contracts with the U.S. Department of Energy. This document is not to be published nor its contents otherwise disseminated or used for purposes other than specified above before patent approval or such release or use has been secured, upon request, from the Patent Counsel, U.S. Department of Energy Field Office, Richland, WA. DISCLAIMER - This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, nor any of their contractors, subcontractors or their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or any third party's use or the results of such use of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.	10. RELEASE STAMP <div data-bbox="1015 970 1461 1217" style="border: 1px solid black; padding: 5px; text-align: center;">OFFICIAL RELEASE BY WHC DATE APR 19 1993 <i>Station #12</i></div>	
9. Impact Level <i>30-4</i>		

THIS PAGE INTENTIONALLY
LEFT BLANK



601 116116

SUMMARY

The Pacific Northwest Laboratory (PNL) conducted slug tests in 10 wells adjacent to single-shell tanks in the 200 Areas for Westinghouse Hanford Company. Data from the tests were analyzed to determine best estimates for equivalent hydraulic conductivities and corresponding transmissivities. All of the wells tested were open to the uppermost part of the unconfined aquifer. ~~But~~ well 299-E33-33 was open to the Hanford formation; wells 299-E24-19, 299-E25-40, 299-E25-41, 299-E27-13, 299-E27-14, and 299-E27-15 were open to the undifferentiated Hanford/Ringold Formation; and wells 299-W10-15 and 299-W10-16 were open to the Ringold Formation. Data from well 299-E27-12 could not be analyzed.

The best estimate of equivalent hydraulic conductivity of the test interval at well 299-E33-33 is 320 ft/d. The corresponding transmissivity of the test interval at this well is 5400 ft²/d. The best estimates of equivalent hydraulic conductivity of the test interval at wells 299-E24-19, 299-E25-40, 299-E25-41, 299-E27-13, 299-E27-14, and 299-E27-15 range from 24 to 390 ft/d. Corresponding transmissivities of the test interval at these six wells range from 330 to 5600 ft²/d. The best estimate of equivalent hydraulic conductivity of the test interval at wells 299-W10-15 and 299-W10-16 is 33 ft/d. Corresponding transmissivities of the test interval at these two wells range from 530 to 540 ft²/d. Estimates of equivalent hydraulic conductivity and transmissivity could not be determined for well 299-E27-12. A summary of the best estimates for transmissivity and equivalent hydraulic conductivity is presented in Table S.1.

Some of the assumptions required by the methods used to analyze the slug test data were not fully met. The rapid water-level response observed in most of the 200-East Area tests, where the aquifer is highly permeable, may have introduced turbulent flow conditions. The analytical results determined from these tests must, therefore, be used with some caution because the assumption inherent in the analytical method requires laminar (Darcian) flow conditions. Other assumptions violated that may have influenced the

TABLE S.1. Summary of Best Estimates of Transmissivity and Equivalent Hydraulic Conductivity for Wells Near the Single-Shell Tanks in the 200 Areas

<u>Well Name</u>	<u>Area</u>	<u>Analysis Method</u>	<u>Transmissivity, (a) ft²/d</u>	<u>Equivalent Hydraulic Conductivity, ft/d</u>
299-E24-19	200-East	Bouwer and Rice (1976)	1700	110
299-E25-40	200-East	Bouwer and Rice (1976)	1100	70
299-E25-41	200-East	Bouwer and Rice (1976)	330	24
299-E27-12	200-East	Data Not Analyzable	-	-
299-E27-13	200-East	Bouwer and Rice (1976)	2500	180
299-E27-14	200-East	Bouwer and Rice (1976)	2600	160
299-E27-15	200-East	Bouwer and Rice (1976)	5600	390
299-E33-33	200-East	Bouwer and Rice (1976)	5400	320
299-W10-15	200-West	Bouwer and Rice (1976)	530	33
299-W10-16	200-West	Bouwer and Rice (1976)	540	33

(a) Transmissivity was calculated by multiplying equivalent hydraulic conductivity by the thickness of the test interval, which varied slightly from well to well.

analytical results from all tests conducted include the assumptions that require a fully developed well and an instantaneous initial water-level change.

CONTENTS

SUMMARY	iii
1.0 INTRODUCTION	1.1
2.0 FIELD EQUIPMENT USED	2.1
SLUGGING ROD	2.1
FIELD INSTRUMENTATION	2.1
LIMITATIONS OF EQUIPMENT	2.2
3.0 METHODS OF ANALYSIS	3.1
BOUWER AND RICE METHOD	3.1
COOPER ET AL. METHOD	3.3
MAJOR LIMITATIONS	3.3
4.0 HYDROLOGIC TEST AND PARAMETER EVALUATION	4.1
GENERAL WELL CONSTRUCTION	4.1
GENERAL TEST PERFORMANCE	4.1
GENERAL DATA ANALYSIS	4.2
WELL 299-E24-19	4.3
Stratigraphy	4.3
Test Performance and Data Analysis	4.3
Summary of Test Results	4.5
WELL 299-E25-40	4.6
Stratigraphy	4.6
Test Performance and Data Analysis	4.6
Summary of Test Results	4.8
WELL 299-E25-41	4.9
Stratigraphy	4.9

931301B.032

931301B.032

Test Performance and Data Analysis	4.9
Summary of Test Results	4.12
WELL 299-E27-12	4.14
Stratigraphy	4.14
Test Performance and Data Analysis	4.14
WELL 299-E27-13	4.15
Stratigraphy	4.15
Test Performance and Data Analysis	4.16
Summary of Test Results	4.17
WELL 299-E27-14	4.17
Stratigraphy	4.18
Test Performance and Data Analysis	4.18
Summary of Test Results	4.20
WELL 299-E27-15	4.21
Stratigraphy	4.22
Test Performance and Data Analysis	4.22
Summary of Test Results	4.23
WELL 299-E33-33	4.24
Stratigraphy	4.24
Test Performance and Data Analysis	4.24
Summary of Test Results	4.26
WELL 299-W10-15	4.27
Stratigraphy	4.27
Test Performance and Data Analysis	4.27
Summary of Test Results	4.29

9313018.0396

9313018.0396

WELL 299-W10-16	4.30
Stratigraphy	4.30
Test Performance and Data Analysis	4.30
Summary of Test Results	4.33
5.0 REFERENCES	5.1
APPENDIX A - TEST DATA AND ANALYSIS FOR WELL 299-E24-19	A.1
APPENDIX B - TEST DATA AND ANALYSIS FOR WELL 299-E25-40	B.1
APPENDIX C - TEST DATA AND ANALYSIS FOR WELL 299-E25-41	C.1
APPENDIX D - TEST DATA AND ANALYSIS FOR WELL 299-E27-12	D.1
APPENDIX E - TEST DATA AND ANALYSIS FOR WELL 299-E27-13	E.1
APPENDIX F - TEST DATA AND ANALYSIS FOR WELL 299-E27-14	F.1
APPENDIX G - TEST DATA AND ANALYSIS FOR WELL 299-E27-15	G.1
APPENDIX H - TEST DATA AND ANALYSIS FOR WELL 299-E33-33	H.1
APPENDIX I - TEST DATA AND ANALYSIS FOR WELL 299-W10-15	I.1
APPENDIX J - TEST DATA AND ANALYSIS FOR WELL 299-W10-16	J.1

FIGURES

1.1	Locations of Wells Near Waste Management Area A-AX in the 200-East Area	1.2
1.2	Locations of Wells Near Waste Management Area B-BX-BY in the 200-East Area	1.3
1.3	Locations of Wells Near Waste Management Area C in the 200-East Area	1.4
1.4	Locations of Wells Near Waste Management Area T in the 200-West Area	1.5

9313018.0398

9313018.0398

TABLES

S.1	Summary of Best Estimates of Transmissivity and Equivalent Hydraulic Conductivity for Wells Near the Single-Shell Tanks in the 200 Areas	iv
1.1	Wells in Which Slug Tests Were Conducted	1.1
2.1	Slugging Rods Dimensions, Volumes, and Theoretical Displacement.	2.1
2.2	Schedule of the Time-Interval Sequence for Data Collection	2.2
4.1	Summary of Hydraulic Property Values Determined for Tests Performed in Well 299-E24-19	4.5
4.2	Summary of Hydraulic Property Values Determined for Tests Performed in Well 299-E25-40	4.8
4.3	Summary of Hydraulic Property Values Determined for Tests Performed in Well 299-E25-41	4.13
4.4	Summary of Hydraulic Property Values Determined for Tests Performed in Well 299-E27-13	4.18
4.5	Summary of Hydraulic Property Values Determined for Tests Performed in Well 299-E27-14	4.21
4.6	Summary of Hydraulic Property Values Determined for Tests Performed in Well 299-E27-15	4.24
4.7	Summary of Hydraulic Property Values Determined for Tests Performed in Well 299-E33-33	4.26
4.8	Summary of Hydraulic Property Values Determined for Tests Performed in Well 299-W10-15	4.29
4.9	Summary of Hydraulic Property Values Determined for Tests Performed in Well 299-W10-16	4.34

9313018.036

**THIS PAGE INTENTIONALLY
LEFT BLANK**

2025 01/06/23

1.0 INTRODUCTION

Hydrologic tests were conducted in 10 of the 12 newly drilled wells near single-shell tank farms in the 200 Areas between September and November 1989. The wells were designed to monitor ground water beneath these tank farms as required by the Resource Conservation and Recovery Act (RCRA). The Pacific Northwest Laboratory^(a) conducted the tests as part of a larger RCRA drilling effort funded by Westinghouse Hanford Company. The tests are considered "opportunistic" in that the wells were not designed specifically for aquifer testing for the given aquifer conditions. However, the hydraulic property estimates derived from the tests can be used, provided the assumptions required in the analytical solution are not significantly violated.

The purpose of the hydrologic tests was to provide estimates of transmissivity and hydraulic conductivity of the uppermost part of the unconfined aquifer. Estimates of transmissivity and hydraulic conductivity were determined from 9 of the 10 wells tested. (The 10 wells tested are listed in Table 1.1.) Estimates could not be determined from slug tests performed in 1 of the 10 wells, well 299-E27-12 in the 200-East Area. In addition, slug testing was not performed in wells 299-E33-31 and 299-E33-32, also in the 200-East Area. These 2 wells, with the 10 that were tested, compose the 12 newly drilled wells. The locations of the wells tested are shown in Figures 1.1 through 1.4.

TABLE 1.1. Wells in Which Slug Tests Were Conducted

<u>200-East Area</u>	<u>200-West Area</u>
299-E24-19	299-W10-15
299-E25-40	299-W10-16
299-E25-41	
299-E27-12	
299-E27-14	
299-E27-15	
299-E33-33	

(a) The Pacific Northwest Laboratory is operated for the U.S. Department of Energy by Battelle Memorial Institute under Contract DE-AC06-76RLO 1830.




FIGURE 1.1. Locations of Wells Near Waste Management Area A-AX in the 200-East Area





FIGURE 1.2. Locations of Wells Near Waste Management Area B-BX-BY in the 200-East Area




FIGURE 1.3. Locations of Wells Near Waste Management Area C in the 200-East Area





FIGURE 1.4. Locations of Wells Near Waste Management Area T in the 200-West Area

Hydrologic testing was limited to slug tests because it eliminates the need to purge large volumes of water, which must be contained for chemical sample analyses prior to proper disposal.

This report discusses the field equipment used to conduct the tests and the methods used to analyze the test data. The test results are then evaluated and calculated estimates presented.

9313018.0405

9313018.0405

2.0 FIELD EQUIPMENT USED

Slug tests were conducted by quickly raising or lowering a slugging rod in the well to displace the water column and recording the water-level response with a pressure transducer data-logger system. The procedure (AT-6) that describes this technique is discussed in detail in PNL (1989). The description of the field equipment is provided below.

SLUGGING ROD

Two sizes of slugging rods were used in conducting the slug tests, one 6 ft in length and one 8 ft in length. The diameter of the 6-ft rod was 0.19 ft (2-1/4 in.), and the diameter of the 8-ft rod was 0.24 ft (2-7/8 in.). Dimensions of each rod are presented in Table 2.1, with the theoretical maximum change in water level the rods will cause in a 4-in.-inside-diameter well. Each slugging rod consisted of a carbon steel pipe, which was partially filled with sand and sealed at both ends. A rebar hook was welded to the top to allow attachment of a wire-line cable. A Kaiser Engineers Hanford's (KEH) pump-setting rig was used to raise and lower the slugging rod for each slug test.

FIELD INSTRUMENTATION

The water-level changes during the slug tests were measured and recorded with a 10-psi pressure transducer data-logger system. The transducer was lowered to the bottom of the well and connected with a cable to a data logger at the surface. The data logger recorded the water-level changes at the manufacturer's preset time intervals, which approximated a logarithmic scale.

TABLE 2.1. Slugging Rods Dimensions, Volumes, and Theoretical Displacement

<u>Rod Size</u>	<u>Length, ft</u>	<u>Diameter, ft</u>	<u>Volume, ft³</u>	<u>Theoretical Water-Level Displacement in 4-in.-dia Well, ft</u>
6-ft rod	6.00	0.19	0.17	1.90
8-ft rod	8.05	0.24	0.36	4.17

The schedule of the preset time intervals for all the tests conducted are shown in Table 2.2. The reference water level for each test was the equilibrated water level measured in the well before the test. A sequential test number displayed by the data logger to be in the range 0 to 9 was assigned to each test to identify it from other tests conducted at the same well. The test number was incremented by one to the next higher number before conducting the next test. The first test for each well does not necessarily begin with 0. The test number for each test is shown in the data output in the Appendixes.

LIMITATIONS OF EQUIPMENT

The existing well design and test equipment presented a number of limitations to the performance of the slug tests and analysis of the data. These limitations included

- a maximum possible water-level change of 4.17 ft with the 8-ft slug and 1.90 ft with the 6-ft slug
- possible erroneous water-level measurements because of transducer movement during introduction or removal of the slugging rod
- data acquisition limitations associated with the pressure transducer data-logger systems (e.g., determining the initial water-level change and the time of test initiation accurately).

TABLE 2.2. Schedule of the Time-Interval Sequence for Data Collection

<u>Cycle</u>	<u>Elapsed Time</u>	<u>Time Interval</u>
1	0-2 sec	0.2 sec
2	2-20 sec	1 sec
3	20-120 sec	5 sec
4	2-10 min	30 sec
5	10-100 min	2 min

3.0 METHODS OF ANALYSIS

The Bouwer and Rice (1976) and Cooper et al. (1967) methods were used to analyze aquifer slug test data. An update to the Bouwer and Rice method was published by Bouwer (1989). These methods are discussed below.

BOUWER AND RICE METHOD

The Bouwer and Rice method (Bouwer and Rice 1976) was designed to estimate the hydraulic conductivity of an unconfined aquifer in the close vicinity of the borehole. This method can be applied to slug tests conducted in the screened or open portion of wells that partially or fully penetrate the aquifer. This method can also be used to estimate hydraulic conductivity of confined, semiconfined, or stratified aquifers (Bouwer 1989).

The following are important assumptions in applying the Bouwer and Rice method:

- The aquifer is homogeneous and isotropic.
- Drawdown of the water table near the well is negligible.
- Head losses as water enters the well (well losses) are negligible.
- The well is fully developed.
- The initial change in water level is instantaneous.
- Flow in the capillary fringe is ignored.

One of the well geometry parameters used in the Bouwer and Rice calculations is the casing radius, r_c . If the water-level fall or rise occurs within the casing, the actual radius of the casing is used for this value. If the water-level rise or fall occurs in the screened interval of the well, the casing radius must be corrected for the thickness and porosity of the filter pack. The water-level changes for all the tested wells discussed in this report occurred within the screened interval. The equation to correct for the radius, r_c , as presented in Bouwer (1989) is

$$r_c = [r_s^2 + p(r_f^2 - r_s^2)]^{1/2} \quad (1)$$

where r_s is the radius of the well screen in feet, p is the estimated porosity of the filter pack, and r_f is the radius of the well screen and filter pack in feet.

The Bouwer and Rice analytical equation used to calculate the hydraulic conductivity, K , between the limits Y_0 , the intercept, at $t = 0$ and Y_t at t on a semilogarithmic plot of the water-level change (Y_t) versus time (t) is

$$K = \frac{r_c^2 \ln(R_e/r_w)}{2 L_e} \frac{1}{t} \ln \frac{Y_0}{Y_t} \quad (2)$$

where r_c = corrected radius of the screened interval, ft

R_e = effective radius equivalent to the radial distance over which the head loss is dissipated in the flow system, ft

r_w = radial distance between the well center and the undisturbed aquifer, ft

L_e = length of the tested (screened) interval, ft.

The term R_e , expressed as $\ln(R_e/r_w)$, is a function of the well and aquifer geometry and is evaluated from results of an analog analysis performed by Bouwer and Rice (1976). The form of the equation to calculate this term, including the determination of dimensionless parameters used in this equation, is presented in Bouwer (1989).

During slug withdrawal tests, anomalies are sometimes observed in the early portion of the rate of water-level recovery. These anomalies, referred to as the "double straight line effect," are due to drainage of a filter pack or developed zone around the well screen after the water level is lowered (Bouwer 1989). The early data can be ignored and the second straight line, which is more representative of the undisturbed aquifer, can be used for calculating the hydraulic conductivity.

9313018.0409

COOPER ET AL. METHOD

The Cooper et al. method (1967) was designed to estimate the transmissivity of a confined aquifer in the close vicinity of a borehole. The method involves fitting a semilogarithmic plot of change in head (H) divided by the initial change in head (H_0) versus time to one of a set of type curves established for an instantaneous water-level change in a well of finite diameter. Additional type curves for the analysis of test data were generated by Papadopolus et al. (1973).

Important assumptions in applying the Cooper et al. method, in addition to those assumptions stated previously for the Bouwer and Rice method, are 1) the well is screened (or open) throughout the full thickness of the aquifer, and 2) confined aquifer conditions exist.

The Cooper et al. method may be used to analyze tests conducted in wells that partially penetrate an aquifer, provided that flow is essentially two-dimensional (i.e., essentially no vertical flow) within the stressed zone of the aquifer during the test. The determined value of transmissivity from tests conducted in wells that partially penetrate the aquifer represents the stressed (saturated screen) interval (Cooper et al. 1967). This method may also be applied to tests exhibiting unconfined aquifer conditions provided that the saturated thickness is uniform (Walter and Thompson 1982).

MAJOR LIMITATIONS

One limitation to analyzing the test data is that turbulence may have been present during the earliest portion of the test. Data from most of the 200-East Area slug tests indicate that the water-level response as a result of injecting or withdrawing the slugging rod was extremely rapid. The length of time for the water level to return to its pretest level was on the order of 10 sec or less. This rapid response may introduce turbulent flow inside the well, particularly during the early part of the test. Turbulence may cause errors in data collection by the pressure-measuring instrument. Methods commonly used to analyze slug test data assume Darcian (laminar) flow.

Turbulence within a pipe occurs at a Reynolds number of 2000 or greater (Roberson and Crowe 1985). The equation that relates Reynolds number to velocity is

$$Re = VD/\mu \quad (3)$$

where Re = Reynolds number

V = velocity, ft/sec

D = pipe diameter, ft

μ = kinematic viscosity of water, ft²/sec.

To determine when turbulent flow conditions exist, estimates for the parameters were used to solve for Equation (3). The value reported for kinematic viscosity of water at 50°F is 1.41E-5 ft²/sec (Roberson and Crowe 1985). The inside well-screen diameter for all wells tested is 4 in. Substituting these values into Equation (3) and rearranging yields a velocity of 8.46E-2 ft/sec.

Velocity of flow exceeded 8.46E-2 ft/sec during the earliest part of all the tests (e.g., 0 to 2 sec). This velocity indicates that turbulent flow conditions may have existed during the earliest part of the tests before giving way to laminar flow conditions during the latter part of the tests. This change may be particularly true for most of those tests conducted in the 200-East Area, where the stress-induced water level responded rapidly because of high permeability in aquifer conditions. The analytical results determined from tests conducted under these conditions must, therefore, be used with some caution.

The entrance velocity must also be calculated to determine the presence of head losses associated with turbulent flow through the screen during the early part of the test. Head losses generally occur if the entrance velocity through the screen exceeds 0.1 ft/sec. The entrance velocity can be determined by dividing the total open area of the test interval into the volume of water entering the well per unit time.

The data from slug withdrawal test #2 at well 299-E33-33 was used to calculate the entrance velocity. The open area of 28.5 in.²/ft (the open area of the inner and outer screen according to Johnson Filtration Systems, Inc.) multiplied by the length of the test interval ("saturated" screen interval) of 17.0 ft equals a total open area of 3.36 ft². The volume of water that entered the well between 0.0133 min (0.8 sec) and 0.0333 min (2 sec) after the data logger was initiated, during which the water level rose 0.78 ft, was calculated to be 0.068 ft³. This volume divided by the increment of time associated with the change in water level equals the flow rate, or 0.057 ft³/sec. This value divided by the total open area of 3.36 ft² equals 0.017 ft/sec, the entrance velocity of water through the screen during the early part of the test. This value of entrance velocity does not exceed the value of 0.1 ft/sec. Therefore, head losses associated with flow through the screen immediately following the imposed stress were negligible. Head losses were, therefore, negligible in the other wells in which tests were conducted because the water-level response during test #2 in well 299-E33-33 equilibrated more quickly than did the water-level responses observed during the tests conducted in the other wells.

Another limitation in analyzing the test data is erroneous water-level changes observed at the beginning of some of the tests. Water-level fluctuations were observed at the beginning of some of the tests in which some of the recorded values exceeded the theoretical water-level displacement expected, calculated using the dimensions of the slugging rods. This excessive displacement indicates that these fluctuations may be a result of erroneous water-level measurements caused by a fluid column of air and water created when the slugging rod was removed from the water. Also, these fluctuations may possibly be caused by induced inertial effects.

Another important limitation in analyzing the test data is that all the wells were not developed before conducting the slug tests. Because the wells were not developed, the calculated values of transmissivity and hydraulic conductivity may be biased. In an undeveloped well, aquifer materials adjacent to the borehole may be disturbed as a result of the drilling technique

used. The hard-tool drilling technique may introduce fines into the aquifer adjacent to the borehole thereby causing a zone of reduced or "altered" formation hydraulic conductivity.

For slug injection tests, the equilibrium water level was below the top of the screen. A sudden rise in the water level will induce flow not only into the aquifer, but also through the vadose zone above the water table. Flow through the vadose zone increases the rate of water-level decline and, hence, leads to an overestimation of transmissivity and hydraulic conductivity for the slug injection tests (Bouwer 1989). Therefore, for this well configuration, slug injection tests are less reliable than slug withdrawal tests for estimating these hydraulic parameters.

An inherent limitation of slug testing is the small area of investigation of the aquifer due to a small stress applied to the aquifer system. Application of slug testing is restricted to aquifers of low to moderate transmissivity.

4.0 HYDROLOGIC TEST AND PARAMETER EVALUATION

The data collected for each slug test were analyzed to determine the hydrologic parameters (transmissivity and hydraulic conductivity). This section presents a summary of the types of tests conducted for each well, method of analysis, and the calculated values of transmissivity and hydraulic conductivity. Field records, data-logger output, graphs of the data, and as-built diagrams for the completed well are provided in Appendixes A through J. The details of the tests for each well are discussed below.

GENERAL WELL CONSTRUCTION

All tested wells were completed with 10-slot Channel Pack[®](a) screens (4-in. inside diameter) surrounded by a 2-in.-thick 16-30 or 20-40 filter pack. The open area of the Channel Pack screens was 28.5 in.²/ft. The screened interval extended from approximately 5 ft above to approximately 15 ft below the top of the aquifer. The porosity of the filter pack is estimated to be 30%. As-built diagrams for each of the wells are presented in the Appendixes.

GENERAL TEST PERFORMANCE

Slug tests were conducted in eight wells in the 200-East Area and two wells in the 200-West Area. All slug tests were performed after the wells were completed, but before they were developed. Multiple slug tests were conducted in most of the wells to increase the likelihood of obtaining a quality data set. It was crucial to coordinate the start of data collection with the initial change in head because the water level was expected to recover exceptionally quickly. The slug withdrawal tests generally provided better quality data to analyze than did the slug injection tests. The water levels were checked for stability between each test.

(a) Channel Pack is a registered trademark of Johnson Filtration Systems, Inc., St. Paul, Minnesota.

GENERAL DATA ANALYSIS

Values of transmissivity and hydraulic conductivity were determined from most of the slug withdrawal test data and a few of the slug injection test data using the Bouwer and Rice analytical method. The Cooper et al. method can be used in some cases, but provides less reliable results because either 1) the portion of the data "representative" of the aquifer materials is non-unique and can be analyzed using several type curves, or 2) the observed value of H_0 , which is important for the analysis, could not be determined accurately. In several tests conducted in highly permeable zones, the observed value of H_0 was not known because the data logger was activated slightly later than initiation of the slugging rod (i.e., t_0 is not known). For other tests where t_0 is known, the observed value of H_0 was not known and could not be determined accurately because of water-level oscillations exhibited at the beginning of the tests.

The observed initial water-level change, Y_0 , used in the Bouwer and Rice equation for analyzing the data is less important than H_0 for the Cooper et al. method. The importance in using the Bouwer and Rice method lies in fitting a linear straight line through the data most "representative" of the aquifer formation adjacent to the borehole and taking the y-intercept as Y_0 . Small errors in this value have no significant affect in calculating hydraulic conductivity because Y_0 enters Equation (2) as a logarithmic value. However, for the Cooper et al. method, the shape of the data curve, and therefore the result, is heavily dependent on the value of H_0 . The Bouwer and Rice method was, therefore, more appropriate for analyzing the test data than the Cooper et al. method.

The theoretical initial water-level change for most of the 200-East Area tests was much larger than the observed value. For these tests, the water level began responding to the imposed stress before the slugging rod was fully withdrawn from or injected into the water column. In applying the Bouwer and Rice method where t_0 is known, or where it was evident that the filter-pack material influenced the early part of the test, the linear best-fit straight line of the data was projected to the intercept to determine Y_0 . A correction was, therefore, applied to the elapsed times, t_e , recorded by

9313018-0415

the data logger to account for the difference between the initiation of the data logger and the determined time, t_0 . In those tests where t_0 was not known, t_0 was assumed to be the time when the observed initial water-level change occurred just before the water level returned exponentially to its pretest level. For these tests, the projected values of Y_0 were approximately the same as the observed values.

The equivalent hydraulic conductivity is an average value for hydraulic conductivity over the entire effective test interval (i.e., "saturated" screen interval). Individual stratigraphic zones within the test interval may possess higher or lower hydraulic conductivities than that calculated for the effective test interval.

WELL 299-E24-19

This well is located on the southwestern edge of the A Tank Farms in the 200-East Area (see Figure 1.1). Refer to Appendix A for the as-built diagram, field records, data-logger output, and graphs of the data.

Stratigraphy

The screened interval is presumed to lie within the undifferentiated sediments of the Hanford/Ringold Formation. The lithology of this interval is a sandy gravel, sand, and muddy sandy gravel. The full saturated thickness of the sediments above the basalt at this location is inferred to be 95 ft, based on available geologic information in Jensen et al. (1989). The bottom of the aquifer is presumed to be the top of the Elephant Mountain Basalt.

Test Performance and Data Analysis

Two slug injection and two slug withdrawal tests were performed on October 2, 1989. The depth of the screened interval was reported to be approximately 280 to 301 ft below land surface. Before conducting the tests, the depth to the "static" water level was determined to be approximately 285 ft below land surface. Therefore, the tests were conducted within the screened interval.

During the slug injection tests (#0 and #8), there was difficulty with the slugging rod "hanging up" in the well, resulting in a water-level change that was not instantaneous. This change caused the water levels to respond before the slugging rod was fully submerged. Data collected from the slug injection tests were not usable for analysis.

For both of the withdrawal tests (tests #1 and #9), withdrawal of the slugging rod yielded an observed initial water-level change of approximately 1.6 ft. The water level fully returned to its pretest level within 17 sec for test #1 and 13 sec for test #9.

The observed initial water-level change for each test was much less than the theoretical value of 4.17 ft, calculated using the dimensions of the 8-ft slugging rod. This difference indicates that formation water was entering the well during withdrawal of the slugging rod. Although this condition violates the assumption requiring an instantaneous water-level change, it does not necessarily invalidate the results. However, the analytical results may be less reliable because of the error in determining the parameters (i.e., Y_0 , Y_t , t , H_0) used in the analytical equations.

The data indicate that initiation of the data logger occurred slightly later than withdrawal of the slugging rod because the equilibrium (reference) water level was "missed." The actual initial water-level change may be slightly higher. However, this difference does not significantly influence the analytical results using the Bouwer and Rice equation. The value of t_0 is, therefore, assumed to be elapsed time, $t_e = 0$.

The slug withdrawal data could not be analyzed with the Cooper et al. method because the values for H_0 for the tests could not be determined accurately. However, the slug withdrawal data for tests #1 and #9 were analyzed with the Bouwer and Rice method. Semilogarithmic plots of the water-level change versus elapsed time are shown in Appendix A. The data on the graph were approximated with a linear best-fit straight line. The data for $t < 9$ sec (0.15 min) was used to approximate the straight line for test #1, and $t < 3$ sec (0.05 min) was used to approximate the straight line for test #9. The approximated best-fit lines were projected to the Y_t intercept at time $t_0 = 0$. These projected values were used for Y_0 in the Bouwer and Rice

9313018.0417

equation. The projected values of Y_0 were determined to be 1.63 ft for test #1 and 1.58 ft for test #9, close to the observed values of 1.61 and 1.60 ft, respectively.

A summary of the parameters substituted into the Bouwer and Rice equation is presented in Appendix A.

Summary of Test Results

Values of transmissivity and equivalent hydraulic conductivity from the analytical method applied for each of the slug tests are summarized in Table 4.1. The hydraulic properties are determined solely for the entire test interval. The best estimates of these hydraulic properties are determined to be most representative of the test interval.

Analyses of the slug withdrawal data for tests #1 and #9 using the Bouwer and Rice method yielded hydraulic conductivity values of approximately 120 and 100 ft/d, respectively. The best estimate of the equivalent hydraulic conductivity, an average of these values, was determined to be 110 ft/d. The values of hydraulic conductivity multiplied by the thickness of the test interval of 15.6 ft yielded values of transmissivity of approximately

TABLE 4.1. Summary of Hydraulic Property Values Determined for Tests Performed in Well 299-E24-19

<u>Test Method</u>	<u>Analysis Method</u>	<u>Transmissivity, (a) ft²/d</u>	<u>Equivalent Hydraulic Conductivity, ft/d</u>
Slug Withdrawal (Test #1)	Bouwer and Rice (1976)	1800	120
Slug Withdrawal (Test #9)	Bouwer and Rice (1976)	1600	100
Slug Injection (Tests #0 and #8)	Data Not Analyzable	-	-
Best Estimate		<u>1700</u>	<u>110</u>

(a) Transmissivity was calculated by multiplying equivalent hydraulic conductivity by the thickness of the test interval (i.e., 15.6 ft).

1800 and 1600 ft²/d, respectively, for the upper part of the aquifer. The best estimate of transmissivity, an average of these values, was determined to be 1700 ft²/d.

WELL 299-E25-40

This well is located on the east side of the A Tank Farm in the 200-East Area (see Figure 1.1). Refer to Appendix B for the as-built diagram, field records, data-logger output, and graphs of the data.

Stratigraphy

The screened interval is presumed to lie within undifferentiated sediments of the Hanford/Ringold Formation. The lithology of this interval is a sandy gravel and slightly gravelly sand. The full saturated thickness of the sediments above the basalt at this location is inferred to be 95 ft, based on available geologic information in Jensen et al. (1989). The bottom of the aquifer is presumed to be the top of the Elephant Mountain Basalt.

Test Performance and Data Analysis

Two slug injection and two slug withdrawal tests were conducted on September 29, 1989. The depth of the screened interval was reported to be approximately 252 to 273 ft below land surface. Before conducting the tests, the depth to the "static" water level was determined to be approximately 257 ft below land surface. Therefore, the tests were conducted within the screened interval.

Data from the slug injection tests (tests #0 and #2) are not usable for analysis because the slugging rod was not lowered into the water quickly enough. The assumption that requires an instantaneous water-level change at the beginning of the test was grossly violated.

For both of the two withdrawal tests (tests #1 and #3), withdrawal of the slugging rod produced similar results. Test #1 produced an observed initial water-level change of 1.31 ft. The water level for this test fully recovered to its pretest level within 35 sec. Withdrawal of the slugging

rod for test #3 produced an observed initial water-level change of 1.18 ft. The water level for this test fully recovered to its pretest level within 35 sec.

The observed initial water-level change for each test was much less than the theoretical water-level displacement of 4.17 ft expected, calculated using the dimensions of the 8-ft slugging rod. This difference indicates that formation water was entering the well during withdrawal of the slugging rod. Although this condition violates the assumption requiring an instantaneous water-level change, it does not necessarily invalidate the results. However, the analytical results may be less reliable because of the error in determining the parameters (i.e., Y_0 , Y_t , t , H_0) used in the analytical equations.

The data indicate that initiation of the data logger occurred slightly later than withdrawal of the slugging rod because the equilibrium (reference) water level was "missed." The actual initial water-level change may be slightly higher. However, this difference does not significantly influence the analytical results using the Bouwer and Rice equation. The value of t_0 is, therefore, assumed to be elapsed time, $t_e = 0$.

The data could not be analyzed with the Cooper et al. method because the values of H_0 for the tests could not be determined. However, the slug withdrawal data for tests #1 and #3 were analyzed with the Bouwer and Rice method. Semilogarithmic plots of the water-level change versus time since the slugging rod was withdrawn are shown in Appendix B. The early portion of the data for $t < 3$ sec (0.05 min) for each of the tests shows a steeper slope than the data for $t > 3$ sec. These steeper slopes during the early portion of the tests are influenced by the filter-pack material adjacent to the well screen. The later-time straight line is considered to be "representative" of the aquifer sediments adjacent to the borehole.

The data on the graphs were approximated with linear best-fit straight lines. For test #1, a straight-line approximation of the data for $2 < t < 10$ sec was projected to the Y_t intercept at time $t_0 = 0$. This projected value, 1.02 ft, was used for Y_0 in the Bouwer and Rice equation. For test #3, a straight-line approximation of the data for $3 < t < 9$ sec was

projected to the Y_t intercept at time $t_0 = 0$. This projected value for test #3, 0.83 ft, was used for Y_0 in the Bouwer and Rice equation.

A summary of the parameters substituted in the Bouwer and Rice equation is presented in Appendix B.

Summary of Test Results

Values of transmissivity and equivalent hydraulic conductivity from the analytical method applied for each of the slug tests are summarized in Table 4.2. The hydraulic properties are determined solely for the entire test interval. The best estimates of these hydraulic properties are determined to be most representative of the test interval.

Hydraulic conductivity values of approximately 64 and 75 ft/d for slug withdrawal tests #1 and #3, respectively, were calculated using the Bouwer and Rice method. These values of hydraulic conductivity multiplied by the thickness of the test interval of 16.1 ft provide values of transmissivity for the upper part of the aquifer. The best estimate of equivalent hydraulic conductivity, an average of these calculated values, was determined to be 71 ft/d. Transmissivity values were calculated to be approximately 1000 and

TABLE 4.2. Summary of Hydraulic Property Values Determined for Tests Performed in Well 299-E25-40

<u>Test Method</u>	<u>Analysis Method</u>	<u>Transmissivity, (a) ft²/d</u>	<u>Equivalent Hydraulic Conductivity, ft/d</u>
Slug Withdrawal (Test #1)	Bouwer and Rice (1976)	1000	64
Slug Withdrawal (Test #3)	Bouwer and Rice (1976)	1200	75
Slug Injection (Tests #0 and #2)	Data Not Analyzable	-	-
Best Estimate		<u>1100</u>	<u>70</u>

(a) Transmissivity was calculated by multiplying equivalent hydraulic conductivity by the thickness of the test interval (i.e., 16.1 ft).

1200 ft²/d for tests #1 and #3, respectively. The best estimate of transmissivity, an average of these calculated values, was determined to be 1100 ft²/d.

WELL 299-E25-41

This well is located on the east side of the A Tank Farm in the 200-East Area (see Figure 1.1). Refer to Appendix C for the as-built diagram, field records, data-logger output, and graphs of the data.

Stratigraphy

The screened interval is presumed to lie within the undifferentiated sediments of the Hanford/Ringold Formation. The lithology of this interval is a sandy gravel, muddy sandy gravel, and sandy mud. The full saturated thickness of the sediments above the basalt at this location is inferred to be 95 ft, based on available geologic information in Jensen et al. (1989). The bottom of the aquifer is presumed to be the top of the Elephant Mountain Basalt.

Test Performance and Data Analysis

Two slug injection and two slug withdrawal tests were conducted on September 29, 1989. The depth of the screened interval was reported to be approximately 255 to 276 ft below land surface. Before conducting the tests, the depth to the "static" water level was determined to be approximately 262 ft below land surface. Therefore, the tests were conducted within the screened interval.

Slug Injection Tests (#4 and #6)

Injection of the slugging rod yielded an observed initial water-level change of 0.94 ft for test #4. The observed initial water-level change for test #6 was 0.81 ft, but then rose to 1.42 ft after 4 sec (0.0666 min) before falling exponentially. This rise in water level between 0 and 4 sec indicates that initiation of the data logger occurred before the slugging rod was fully submersed. The water level returned to its pretest level within 0.3 min for test #4 and 5.5 min for test #6.

The observed initial water-level change for each test was less than the theoretical water-level displacement of 4.17 ft expected, calculated using the dimensions of the 8-ft slugging rod. This difference indicates that water in the borehole flowed through the screen into the formation during injection of the slugging rod. Although this condition violates the assumption requiring an instantaneous water-level change, it does not necessarily invalidate the results. However, the analytical results may be less reliable because of the error in determining the parameters (i.e., Y_0 , Y_t , t , H_0) used in the analytical equations.

The data indicate that initiation of the data logger occurred slightly later than injection of the slugging rod for test #4 because the equilibrium (reference) water level was "missed." The actual initial water-level change may be slightly higher. However, this difference does not significantly influence the analytical results using the Bouwer and Rice equation. The value of t_0 is, therefore, assumed to be elapsed time, $t_e = 0$.

A correction was applied to the elapsed times for injection test #6 because of the water-level rise caused by the injection of the slugging rod at the beginning of the test. An elapsed time of 0.0666 min (4 sec) was subtracted from all the elapsed times so that $t_0 = 0$ at $t_e = 4$ sec. The data indicate that initiation of the data logger occurred slightly later than the start of injection of the slugging rod because the equilibrium (reference) water level was "missed" at the beginning of the test. Because t_0 is not exactly known, t_0 is assumed to be the elapsed time, $t_e = 4$ sec, when the maximum observed water-level change occurred just before the water level recovered exponentially.

The slug injection data for tests #4 and #6 were analyzed with the Bouwer and Rice method. Semilogarithmic plots of the water-level change versus time (corrected time for test #6) since the slugging rod was injected are shown in Appendix C. The data on the graphs were approximated with linear best-fit straight lines. The early portion of the data for $t < 0.0333$ min (2 sec) was used to approximate a best-fit line for test #4, and data for $0.1 \text{ min} < t < 0.2166 \text{ min}$ was used to approximate a best-fit line

9313018-0423

for test #6. The latter part of the data indicate a curvi-linear relationship in which a number of "apparent" straight lines could be fit. Therefore, these portions of the graphs were not used to approximate the straight lines. The linear best-fit straight lines were projected to the Y_t intercepts at $t = 0$. These intercepts were used for Y_0 in the Bouwer and Rice equation and were determined to be 0.89 ft for test #4 and 1.02 ft for test #6.

A summary of the parameters substituted in the Bouwer and Rice equation is presented in Appendix C.

Slug Withdrawal Tests (#5 and #7)

Data from the withdrawal tests produced similar results. However, removal of the slugging rod during the first withdrawal test (test #5) pinched the transducer cable, causing the transducer to move upward. This upward movement caused the recording of the water-level change to appear greater than the actual water-level change. An arithmetic plot of the data indicates that the transducer moved approximately 1.9 ft. Between 5.5 and 6 min after the slug was withdrawn, the transducer returned to its original position.

For analysis of the data from test #5, all the values corresponding to elapsed times less than 6 min were corrected 1.9 ft to account for movement of the transducer. Application of this correction yielded an observed initial water-level change of approximately 2.55 ft. The water level for this test fully returned to its pretest level within 6.5 min.

Withdrawal of the slugging rod for the second withdrawal test (#7) yielded an observed initial water-level change of 3.27 ft. The water level fully returned to its pretest level within 3.5 min.

The observed initial water-level change for each test was less than the theoretical water-level displacement of 4.17 ft expected, calculated using the dimensions of the 8-ft slugging rod. This difference indicates that formation water was entering the well during withdrawal of the slugging rod. Although this condition violates the assumption requiring an instantaneous water-level change, it does not necessarily invalidate the results.

9313018.042

However, the analytical results may be less reliable because of the error in determining the parameters (i.e., Y_0 , Y_t , t , H_0) used in the analytical equations.

The data indicate that initiation of the data logger occurred slightly later than withdrawal of the slugging rod because the equilibrium (reference) water level was "missed." The actual initial water-level change may be slightly higher. However, this difference does not significantly influence the analytical results using the Bouwer and Rice equation. The value of t_0 is, therefore, assumed to be elapsed time, $t_e = 0$.

The data could not be analyzed with the Cooper et al. method because the values of H_0 for the tests could not be determined accurately. However, the slug withdrawal data for tests #5 and #7 were analyzed with the Bouwer and Rice method. Semilogarithmic plots of the water-level change versus time since the slugging rod was withdrawn are shown in Appendix C. The data on the graphs were approximated with linear best-fit straight lines. For withdrawal test #5, the early portion of the data for $0.08 < t < 0.15$ min was used to approximate a best-fit line. For withdrawal test #7, the early portion of the data for $t < 0.3$ min was used to approximate a best-fit line. The latter part of the data (i.e., $t > 0.3$ min for test #7 and $t > 0.15$ min for test #5) indicate a curvi-linear relationship in which a number of "apparent" straight lines could be fit. Therefore, these portions of the graphs were not used to approximate the straight lines. The linear best-fit straight lines were projected to the Y_t intercepts at $t_0 = 0$. These intercepts were used for Y_0 in the Bouwer and Rice equation and were determined to be 1.86 ft for test #5 and 3.18 ft for test #7.

A summary of the parameters substituted in the Bouwer and Rice equation is presented in Appendix C.

Summary of Test Results

Values of transmissivity and equivalent hydraulic conductivity from the analytical method applied for each of the slug tests are summarized in Table 4.3. The hydraulic properties are determined solely for the entire test interval. The best estimates of these hydraulic properties are determined to be most representative of the test interval.

TABLE 4.3. Summary of Hydraulic Property Values Determined for Tests Performed in Well 299-E25-41

<u>Test Method</u>	<u>Analysis Method</u>	<u>Transmissivity, (a) ft²/d</u>	<u>Equivalent Hydraulic Conductivity, ft/d</u>
Slug Withdrawal (Test #5)	Bouwer and Rice (1976)	290	21
Slug Withdrawal (Test #7)	Bouwer and Rice (1976)	330	24
Slug Injection (Test #4)	Bouwer and Rice (1976)	2500(b)	180
Slug Injection (Test #6)	Bouwer and Rice (1976)	1100(b)	82
Best Estimate		<u>330</u>	<u>24</u>

- (a) Transmissivity was calculated by multiplying equivalent hydraulic conductivity by the thickness of the test interval (i.e., 16.1 ft).
 (b) Analytical results from the slug injection tests are considered to be overestimates of the test interval.

Analysis of the slug injection data using the Bouwer and Rice method yielded values of hydraulic conductivity of 180 and 82 ft/d for tests #4 and #6, respectively. These values of hydraulic conductivity multiplied by the thickness of the interval tested of 13.8 ft yielded values of transmissivity of approximately 2500 and 1100 ft²/d, respectively, for the upper part of the aquifer.

Analysis of the slug withdrawal data using the Bouwer and Rice method yielded hydraulic conductivity values of approximately 21 and 24 ft/d for test #5 and #7, respectively. These values of hydraulic conductivity multiplied by the thickness of the test interval of 13.8 ft yielded values of transmissivity of approximately 290 and 330 ft²/d, respectively, for the upper part of the aquifer.

The best estimates for transmissivity and equivalent hydraulic conductivity were determined to be those from slug withdrawal test #7 because the

value of Y_0 for this test was closest to the theoretical displacement calculated using the dimensions of the 8-ft slugging rod. Also, the analytical results from the slug injection tests are considered to be overestimates of the test interval because the fall of the water level occurred through the vadose zone above the water table. The rate of fall of the water level in the well caused by inflow into the vadose zone is greater than the fall of the water level in the well caused by inflow into the saturated zone. The best estimate for transmissivity was determined to be $330 \text{ ft}^2/\text{d}$, and the best estimate for equivalent hydraulic conductivity was determined to be 24 ft/d .

WELL 299-E27-12

This well is located on the western corner of the C Tank Farm in the 200-East Area (see Figure 1.3). Refer to Appendix D for the as-built diagram, field records, data-logger output, and graphs of the data.

Stratigraphy

The screened interval is presumed to lie within the undifferentiated sediments of the Hanford/Ringold Formation. The lithology of this interval is a sandy gravel and a muddy sandy gravel. The full saturated thickness of the sediments above the basalt at this location is inferred to be roughly 50 ft, based on available geologic information in Jensen et al. (1989). The bottom of the aquifer is presumed to be the top of the Elephant Mountain Basalt.

Test Performance and Data Analysis

Two slug injection tests and two slug withdrawal tests were conducted on October 19, 1989. An additional slug withdrawal test was conducted on October 20, 1989. The depth of the screened interval was reported to be approximately 251 to 271 ft below land surface. Before conducting the tests, the depth to the "static" water level was determined to be approximately 253 ft below land surface. Therefore, the tests were conducted within the screened interval.

Arithmetic plots of the data for the slug injection tests (tests #4 and #6) are shown in Appendix D. The water level appears to have oscillated

about the equilibrium water level before attenuating to its pretest level. An exponential fall in the water level was not observed. The oscillations attenuated within 3 sec for test #4 and within 4 sec for test #6.

Data from the slug injection tests are not usable for analysis because the slugging rod was not lowered into the water quickly enough to allow for an exponential fall in the water level during the early part of the test. The assumption that requires an instantaneous water-level change was grossly violated.

The water-level responded extremely quickly in other slug tests conducted at this well and in tests conducted at other wells in the 200-East Area. The exponential fall in the water level during the slug injection tests, as "seen" by the aquifer, possibly dissipated before the water-level fluctuations, an artifact of injecting the slugging rod, attenuated.

Arithmetic plots of the data for the slug withdrawal tests (tests #0, #5, and #7) are shown in Appendix D. The response of the water level in each of these tests was similar. The data indicate that the observed initial water-level change is much less than the theoretical value of 1.90 ft, calculated using the dimensions of the 6-ft slugging rod. The assumption that requires an instantaneous water-level change is, therefore, grossly violated. The data for these tests cannot be analyzed.

WELL 299-E27-13

This well is located on the southwestern side of the C Tank Farm in the 200-East Area (see Figure 1.3). Refer to Appendix E for the as-built diagram, field records, data-logger output, and graphs of the data.

Stratigraphy

The screened interval is presumed to lie within the undifferentiated sediments of the Hanford/Ringold Formation. The lithology of this interval is a gravel and a sandy gravel. The full saturated thickness of the sediments above the basalt at this location is inferred to be roughly 50 ft, based on available geologic information in Jensen et al. (1989). The bottom of the aquifer is presumed to be the top of the Elephant Mountain Basalt.

Test Performance and Data Analysis

Two slug withdrawal tests were performed with the 6-ft slugging rod on October 20, 1989. The depth of the screened interval was reported to be approximately 254 to 275 ft below land surface. Before conducting the tests, the depth to the "static" water level was determined to be approximately 261 ft below land surface. Therefore, the tests were conducted within the screened interval.

Withdrawal of the slugging rod yielded observed initial water-level changes of 0.53 ft for test #1 and 1.07 ft for test #2, both occurring at an elapsed time of 0.4 sec (0.0066 min) after initiation of the data logger. The water level returned to the pretest level within 5 and 11 sec, respectively.

The data indicate that the initial water-level change is much less than the theoretical water-level displacement of 1.90 ft expected, calculated using the dimensions of the 6-ft slugging rod. This difference indicates that formation water was entering the well during withdrawal of the slugging rod. Although this condition violates the assumption requiring an instantaneous water-level change, it does not necessarily invalidate the results. However, the analytical results may be less reliable because of the error in determining the parameters (i.e., Y_0 , Y_t , t , H_0) used in the analytical equations.

The slug withdrawal data could not be analyzed with the Cooper et al. method because the values of H_0 for the tests could not be determined accurately. However, the slug withdrawal data for tests #1 and #2 were analyzed with the Bouwer and Rice method. Semilogarithmic plots of the water-level change versus time since the slugging rod was withdrawn are shown in Appendix E. For the analysis, a correction was applied to the elapsed times to eliminate effects of the slugging rod as it was being withdrawn. Four tenths of a second was subtracted from all the elapsed times for each of the tests so that $t_0 = 0$ at $t_e = 0.4$ sec. Initiation of the data logger must have occurred a fraction of a second later than the start of withdrawal of the slugging rod because the data indicate that the equilibrium (reference) water

level was "missed" at the beginning of the test. Because t_0 is not exactly known, t_0 is assumed to be the time, $t_e = 0.4$ sec, when the maximum observed water-level change occurred.

The data on the graphs were approximated with linear best-fit straight lines. For test #1, a straight-line approximation of the data for time less than approximately 1 sec was projected to the Y_t intercept at time $t_0 = 0$. For test #2, a straight-line approximation of the data for $t < 6.6$ sec was projected to the Y_t intercept at time $t_0 = 0$. These projected values, 0.56 ft for test #1 and 1.07 ft for test #2, were used for Y_0 in the Bouwer and Rice equation.

A summary of the parameters substituted into the Bouwer and Rice equation is presented in Appendix E.

Summary of Test Results

Values of transmissivity and equivalent hydraulic conductivity from the analytical methods applied for each of the slug tests are summarized in Table 4.4. The hydraulic properties were determined solely for the entire test interval. The best estimates of these hydraulic properties are determined to be most representative of the test interval.

Analysis of the slug withdrawal data using the Bouwer and Rice method yielded values of hydraulic conductivity of 410 ft/d for test #1 and 180 ft/d for test #2. These values of hydraulic conductivity multiplied by the thickness of the test interval of 13.9 ft yielded values of transmissivity of 5700 and 2500 ft²/d, respectively, for the upper part of the aquifer.

The values from test #2 are considered to be the best estimates of transmissivity and equivalent hydraulic conductivity of the test interval because the value of Y_0 used in the calculations is closer to the theoretical value, calculated using the dimensions of the slugging rod.

WELL 299-E27-14

This well is located on the southeastern side of C the Tank Farm in the 200-East Area (see Figure 1.3). Refer to Appendix F for the as-built diagram, field records, data-logger output, and graphs of the data.

TABLE 4.4. Summary of Hydraulic Property Values Determined for Tests Performed in Well 299-E27-13

<u>Test Method</u>	<u>Analysis Method</u>	<u>Transmissivity, (a) ft²/d</u>	<u>Equivalent Hydraulic Conductivity, ft/d</u>
Slug Withdrawal (Test #1)	Bouwer and Rice (1976)	5700	410
Slug Withdrawal (Test #2)	Bouwer and Rice (1976)	2500	180
Best Estimate		<u>2500</u>	<u>180</u>

(a) Transmissivity was calculated by multiplying equivalent hydraulic conductivity by the thickness of the test interval (i.e., 13.9 ft).

Stratigraphy

The screened interval is presumed to lie within the undifferentiated sediments of the Hanford/Ringold Formation. The lithology of this interval is a sand, gravelly sand, and sandy gravel. The full saturated thickness of the sediments above the basalt at this location is inferred to be roughly 50 ft, based on available geologic information in Jensen et al. (1989). The bottom of the aquifer is presumed to be the top of the Elephant Mountain Basalt.

Test Performance and Data Analysis

Three slug withdrawal tests (tests #3, #4, and #5) were performed on October 20, 1989. The depth of the screened interval was reported to be approximately 246 to 267 ft below land surface. Before conducting the tests, the depth to the "static" water level was determined to be approximately 250 ft below land surface. Therefore, the tests were conducted within the screened interval.

The water level oscillated at the beginning of each of the tests before it recovered exponentially with time. For test #3, the data show that the data logger recorded a value of -4.69 ft at an elapsed time of 0.4 sec (0.0066 min) after initiation of the data logger. This change in water level

is much greater than the theoretical water-level displacement of 1.9 ft expected with the 6-ft slugging rod in a 4-in.-dia well. This difference indicates that the fluctuations in water level at the beginning of the tests may be the result of erroneous water-level measurements caused by a fluid column of air and water created at the instant the slugging rod was withdrawn. These fluctuations may also be influenced by induced inertial effects.

The data indicate that the observed initial water-level change for test #3 (just before the water level began to rise exponentially) was 1.54 ft. The water level returned to its pretest level within 11 sec. The observed initial water-level change for test #5 (just before the water level began to rise exponentially) was 1.08 ft. The water level returned to its pretest level within 10 sec.

For test #4, the observed initial water-level change was over 4 ft before rising exponentially. The water level rose to and leveled off at 2.66 ft below the equilibrium water level 17 sec into the test and then gradually rose to its pretest level within 7 min. This observed initial water-level change of over 4 ft is much greater than the theoretical water-level displacement of 1.9 ft expected with the 6-ft slugging rod. The water-level response recorded by the data logger after 17 sec does not resemble the responses recorded for tests #3 and #5. The data for test #4 are suspect and may be the result of upward movement of the transducer during withdrawal of the slugging rod. This upward movement would cause the water-level changes to appear greater than the actual water-level changes. To correct for this movement, 2.66 ft was added to the recorded values. Only those data for $t < 17$ sec were analyzed.

The slug withdrawal data could not be analyzed with the Cooper et al. method because the values of H_0 for the tests could not be determined accurately. However, the slug withdrawal data for tests #3, #4, and #5 were analyzed using the Bouwer and Rice method. Semilogarithmic plots of the water-level change versus time since the slugging rod was withdrawn are shown in Appendix F. For test #3 and #4, a correction was applied to the elapsed times because of the time difference between initiation of the data logger

9313018.042

and withdrawal of the slugging rod. The data indicate that the slugging rod was withdrawn between 0.2 sec (0.0033 min) and 0.4 sec (0.0066 min) elapsed time, t_e , for test #3 and between 0.6 sec (0.0099 min) and 0.8 sec (0.0133 min) elapsed time for test #4. The time the slugging rod was withdrawn, t_0 , is chosen as a midpoint between these elapsed times (i.e., $t_0 = 0$ at $t_e = 0.3$ sec for test #3 and $t_0 = 0$ at $t_e = 0.7$ sec for test #4). Therefore, 0.3 and 0.7 sec were subtracted from all the elapsed times for tests #3 and #4, respectively.

For test #5, the data indicate that the slugging rod was withdrawn before the data logger was initiated because the equilibrium water level was "missed." The elapsed times for test #5 were shifted 1.2 sec in the positive direction so that the exponential portion of the data for test #5 matches the exponential portion of the data for test #3. The correction of 0.3 sec applied to test #3 to account for the time difference between initiation of the data logger and the withdrawal of the slugging rod was also applied to the data for test #5, yielding a net positive shift of 0.9 sec for test #5. These corrections allow some consistency between the analyses for each test.

The times, t_0 , for tests #3 and #4 are known because the data logger was initiated before the slugging rod was withdrawn (i.e., the data logger recorded the equilibrium water level). Therefore, a linear best-fit straight line through the data can be projected to the Y_t intercept at $t_0 = 0$. The value at the intercept, Y_0 , was determined to be 2.86 ft for test #3 and 3.42 ft for test #4. For test #5, Y_0 was determined to be 3.28 ft. These values were used for the calculations in the Bouwer and Rice equation. The data for which the straight lines were fit were 2.7 sec $< t < 6.7$ sec for test #3, 3.3 sec $< t < 8.3$ sec for test #4, and $t < 9$ sec for test #5.

A summary of the parameters substituted into the Bouwer and Rice equation for each test is presented in Appendix F.

Summary of Test Results

A summary of slug test results for each of the tests is presented in Table 4.5. The hydraulic properties are determined solely for the entire test interval. The best estimates of these hydraulic properties are determined to be most representative of the test interval.

9313018-0433

TABLE 4.5. Summary of Hydraulic Property Values Determined for Tests Performed in Well 299-E27-14

<u>Test Method</u>	<u>Analysis Method</u>	<u>Transmissivity, (a) ft²/d</u>	<u>Equivalent Hydraulic Conductivity, ft/d</u>
Slug Withdrawal (Test #3)	Bouwer and Rice (1976)	2600	160
Slug Withdrawal (Test #4)	Bouwer and Rice (1976)	2400	150
Slug Withdrawal (Test #5)	Bouwer and Rice (1976)	2900	180
Best Estimate		<u>2600</u>	<u>160</u>

(a) Transmissivity was calculated by multiplying equivalent hydraulic conductivity by the thickness of the test interval (i.e., 16.0 ft).

Analyses of the slug withdrawal data using the Bouwer and Rice method yielded values of hydraulic conductivity of 160, 150, and 180 ft/d for tests #3, #4, and #5, respectively. These values of hydraulic conductivity multiplied by the thickness of the test interval of 16.0 ft yielded values of transmissivity of 2600, 2400, and 2900 ft²/d, respectively, for the upper part of the aquifer.

The best estimates of transmissivity and equivalent hydraulic conductivity of the test interval are those values determined from test #3 because of possible errors associated with shifting the data for tests #4 and #5. The best estimate for transmissivity is 2600 ft²/d, and the best estimate for equivalent hydraulic conductivity is 160 ft/d.

WELL 299-E27-15

This well is located on the northwestern side of the C Tank Farm in the 200-East Area (see Figure 1.3). Refer to Appendix G for the field records, raw data, graphs of the data, and as-built diagrams.

Stratigraphy

The screened interval is presumed to lie within the undifferentiated sediments of the Hanford/Ringold Formation. The lithology of this interval is a muddy sandy gravel. The full saturated thickness of the sediments above the basalt at this location is inferred to be roughly 50 ft, based on available geologic information in Jensen et al. (1989). The bottom of the aquifer is presumed to be the top of the Elephant Mountain Basalt.

Test Performance and Data Analysis

Two slug injection tests and two slug withdrawal tests were conducted on October 19, 1989. The depth of the screened interval was reported to be approximately 241 to 261 ft below land surface. Before conducting the tests, the depth to the "static" water level was determined to be approximately 245 ft below land surface. Therefore, the tests were conducted within the screened interval.

Data from the slug injection tests (tests #0 and #2) are not usable for analysis because the slugging rod was not lowered into the water quickly enough. The assumption requiring an instantaneous initial water-level change was grossly violated.

Withdrawal of the slugging rod during test #1 yielded an observed initial water-level change of approximately 1 ft at an elapsed time of 0.6 sec after the data logger was initiated. After that time, the water level returned to its pretest level within 6.4 sec.

The data for test #1 indicate that the initial water-level change is much less than the theoretical water-level displacement of 1.90 ft expected, calculated using the dimensions of the 6-ft slugging rod. This difference indicates that formation water was entering the well during withdrawal of the slugging rod. Although this condition violates the assumption requiring an instantaneous water-level change, it does not necessarily invalidate the results. However, the analytical results may be less reliable because of the error in determining the parameters (i.e., Y_0 , Y_t , t , H_0) used in the analytical equations.

9313018.0435

The slug withdrawal data could not be analyzed with the Cooper et al. method because the value of H_0 for the test could not be accurately determined. However, the data for test #1 were analyzed with the Bouwer and Rice method. A semilogarithmic plot of water-level change versus time since the slugging rod was withdrawn is shown in Appendix G. A correction was applied to the elapsed times to eliminate the effects from withdrawal of the slugging rod at the beginning of the test. An elapsed time of 0.0099 min (0.6 sec) was subtracted from all the elapsed times so that $t_0 = 0$ at $t_e = 0.6$ sec. Initiation of the data logger occurred slightly later than the start of withdrawal of the slugging rod because the data indicate that the equilibrium (reference) water level was "missed" at the beginning of the test. Because t_0 is not exactly known, t_0 is assumed to be the elapsed time, $t_e = 0.6$ sec, when the maximum observed water-level change occurred.

The data on the graph were approximated with a linear best-fit straight line. A straight-line approximation of the data for time less than 0.0234 min (1.4 sec) was projected to the Y_t intercept at time $t_0 = 0$. This projected value, 0.96 ft, was used for Y_0 in the Bouwer and Rice equation.

A summary of the parameters substituted into the Bouwer and Rice equation is presented in Appendix G.

Summary of Test Results

A summary of the slug test results is presented in Table 4.6. The hydraulic properties are determined solely for the entire test interval. The best estimates of these hydraulic properties are determined to be most representative of the test interval.

Analysis of the slug withdrawal data using the Bouwer and Rice method yielded a hydraulic conductivity value of approximately 390 ft/d for test #1. This value of hydraulic conductivity multiplied by the thickness of the test interval of 14.3 ft yielded a transmissivity of approximately 5600 ft²/d for the upper part of the aquifer.

Withdrawal of the slugging rod during test #3 occurred late with respect to initiation of the data logger, yielding data during the data collection sequence of a 1-sec time interval. This rate of data collection is

TABLE 4.6. Summary of Hydraulic Property Values Determined for Tests Performed in Well 299-E27-15

<u>Test Method</u>	<u>Analysis Method</u>	<u>Transmissivity, (a) ft²/d</u>	<u>Equivalent Hydraulic Conductivity, ft/d</u>
Slug Withdrawal (Test #1)	Bouwer and Rice (1976)	5600	390
Slug Withdrawal (Test #3)	Insufficient Data	-	-
Slug Injection (Tests #0 and #2)	Data Not Analyzable	-	-
Best Estimate		<u>5600</u>	<u>390</u>

(a) Transmissivity was calculated by multiplying equivalent hydraulic conductivity by the thickness of the test interval (i.e., 14.3 ft).

insufficient for analysis because of a lack of data collected during the early portion of the test after the slugging rod was withdrawn.

WELL 299-E33-33

This well is located east of the B Tank Farms in the 200-East Area (see Figure 1.2). Refer to Appendix H for the as-built diagram, field records, data-logger output, and graphs of the data.

Stratigraphy

The screened interval is presumed to lie within the Hanford formation. The lithology of this interval is a muddy sandy gravel. The full saturated thickness of the sediments above the basalt at this location is 20 ft. The bottom of the aquifer, which is the top of the underlying Elephant Mountain basalt, was encountered at this well.

Test Performance and Data Analysis

Two slug injection tests and one slug withdrawal test were conducted on September 27, 1989. The depth of the screened interval was reported to be approximately 227 to 248 ft below land surface. Before conducting the tests,

the depth to the "static" water level was determined to be approximately 232 ft below land surface. Therefore, the tests were conducted within the screened interval.

Data from the slug injection tests (tests #0 and #1) are not usable for analysis because the slugging rod was not lowered into the water quickly enough. The assumption requiring an instantaneous initial water-level change was grossly violated.

The withdrawal test (test #2) yielded an observed initial water-level change of approximately 1.2 ft at an elapsed time of 0.8 sec after the data logger was initiated. The water level returned approximately to its pretest level in less than 5 sec. The water level did not return exactly to its pretest level possibly because the transducer moved during the test.

The observed initial water-level change is much less than the theoretical water-level displacement of 4.17 ft expected, calculated using the dimensions of the 8-ft slugging rod. In addition, the slugging rod was still being withdrawn after the data logger was initiated, as indicated by the decline in water level between 0 and 0.8 sec elapsed time. This difference indicates that formation water was entering the well during withdrawal of the slugging rod. Although this condition violates the assumption requiring an instantaneous water-level change, it does not necessarily invalidate the results. However, the analytical results may be less reliable because of the error in determining the parameters (i.e., Y_0 , Y_t , t , H_0) used in the analytical equations.

The slug withdrawal data could not be analyzed with the Cooper et al. method because the value of H_0 for the test could not be determined accurately. However, the slug withdrawal data for test #2 were analyzed with the Bouwer and Rice method. A semilogarithmic plot of the water-level change versus time since the slugging rod was removed is shown in Appendix H. A correction was applied to the elapsed times to eliminate the effects from withdrawal of the slugging rod at the beginning of the test. An elapsed time of 0.0133 min (0.8 sec) was subtracted from all the elapsed times so that $t_0 = 0$ at $t_e = 0.8$ sec. Initiation of the data logger must have occurred slightly later than the start of withdrawal of the slugging rod because the

9313018.043

data indicate that the equilibrium (reference) water level was "missed" at the beginning of the test. Because t_0 is not exactly known, t_0 is assumed to be the elapsed time, $t_e = 0.8$ sec, when the maximum observed water-level change occurred.

The data on the graph were approximated with a linear best-fit straight line. A straight-line approximation of the data for time less than approximately 0.02 min (1.2 sec) was projected to the Y_t intercept at time $t_0 = 0$. This projected value, 1.20 ft, was used for Y_0 in the Bouwer and Rice equation. The observed value for Y_0 was 1.19 ft.

Summary of Test Results

A summary of slug test results is presented in Table 4.7. The hydraulic properties are determined solely for the entire test interval. The best estimates of these hydraulic properties are determined to be most representative of the test interval.

Analysis of the slug withdrawal data for test #2 using the Bouwer and Rice method yielded a hydraulic conductivity value of approximately 320 ft/d.

TABLE 4.7. Summary of Hydraulic Property Values Determined for Tests Performed in Well 299-E33-33

<u>Test Method</u>	<u>Analysis Method</u>	<u>Transmissivity, (a) ft²/d</u>	<u>Equivalent Hydraulic Conductivity, ft/d</u>
Slug Withdrawal (Test #2)	Bouwer and Rice (1976)	5400	320
Slug Injection (Tests #0 and #1)	Data Not Analyzable	-	-
Best Estimate		<u>5400</u>	<u>320</u>

(a) Transmissivity was calculated by multiplying equivalent hydraulic conductivity by the thickness of the test interval (i.e., 17.0 ft).

The value of hydraulic conductivity multiplied by the thickness of the test interval of 17.0 ft yielded a transmissivity of approximately 5400 ft²/d for the upper part of the aquifer.

These values are considered to be the best (and only) estimates of transmissivity and equivalent hydraulic conductivity of the test interval.

WELL 299-W10-15

This well is located on the north side of the T Tank Farm in the 200-West Area (see Figure 1.4). Refer to Appendix I for the as-built diagram, field records, data-logger output, and graphs of the data.

Stratigraphy

The screened interval is presumed to lie within the middle unit of the Ringold Formation. The lithology of this interval is a sandy gravel. The full saturated thickness of the sediments above the basalt at this location is inferred to be 275 ft, based on available geologic information in Jensen et al. (1989). The bottom of the aquifer is presumed to be either the top of one of the fine-grained units of the Ringold Formation or the top of the underlying Elephant Mountain Basalt.

Test Performance and Data Analysis

Two slug withdrawal tests were performed on November 3, 1989, both producing similar results. The depth of the screened interval was reported to be approximately 201 to 222 ft below land surface. Before conducting the tests, the depth to the "static" water level was determined to be approximately 206 ft below land surface. Therefore, the tests were conducted within the screened interval.

The water level oscillated at the beginning of each of the tests before it recovered exponentially with time. The data show that the data logger recorded values of -7.52 ft at an elapsed time of 0.4 sec (0.0033 min) after initiation of the data logger for test #2 and -15.19 ft at an elapsed time of 0.6 sec (0.0099 min) after initiation of the data logger for test #3. These changes in water level are much greater than the theoretical water-level displacement of 1.9 ft expected with the 6-ft slugging rod in a 4-in.-dia well.

9313018.0416

These recorded values indicate that the fluctuations in water level may be the result of erroneous water-level measurements caused by a fluid column of air and water created at the instant the slugging rod was withdrawn. These fluctuations may also be influenced by induced inertial effects.

An arithmetic plot of the data indicates that the observed initial water-level change was 1.97 ft for test #2 and 1.93 ft for test #3. These initial values are close to the theoretical water-level displacement of 1.90 ft expected, calculated using the dimensions of the slugging rod. The water level fully returned to its pretest level within 58 sec for test #2 and 53 sec for test #3.

A correction was applied to the elapsed times because of the time difference between initiation of the data logger and withdrawal of the slugging rod. For test #2, the data indicate that the slugging rod was withdrawn between 0.2 sec (0.0033 min) and 0.4 sec (0.0066 min) elapsed time, t_e . The time the slugging rod was withdrawn, t_0 , is chosen as a midpoint between these elapsed times (i.e., $t_0 = 0$ at $t_e = 0.3$ sec). For test #3, the slugging rod was withdrawn between 0.4 sec (0.0066 min) and 0.6 sec (0.0099 min) elapsed time. The t_0 value for test #3 is 0.5 sec. Therefore, 0.3 and 0.5 sec were subtracted from all the elapsed times for tests #2 and #3, respectively, for analysis.

Hydraulic property values could not be determined from the Cooper et al. analytical method. The portion of the data considered to be "representative" of the aquifer materials is non-unique and can be analyzed using several type curves. However, the data for tests #2 and #3 were analyzed with the Bouwer and Rice method. Semilogarithmic plots of the water-level change versus time (i.e., corrected time) since the slugging rod was removed are shown in Appendix I. The data on the graphs were approximated with linear best-fit straight lines. The latter part of the data (i.e., $t > 30$ sec for tests #2 and #3) indicate a curvi-linear relationship and therefore were not used to approximate the straight lines. The approximated best-fit lines were projected to the Y_t intercept at time $t_0 = 0$. These projected values at the intercept, 2.15 ft for test #2 and 2.13 ft for test #3, were used for Y_0 in the Bouwer and Rice equation.

A summary of the parameters substituted into the Bouwer and Rice equation is presented in Appendix I.

Summary of Test Results

Values of transmissivity and equivalent hydraulic conductivity from the analytical methods applied for each of the slug tests are summarized in Table 4.8. The hydraulic properties are determined solely for the entire test interval. The best estimates of these hydraulic properties are determined to be most representative of the test interval.

Hydraulic conductivity values of 32 and 34 ft/d were calculated for tests #2 and #3, respectively, using the Bouwer and Rice equation. These values of hydraulic conductivity multiplied by the thickness of the test interval of 15.8 ft yielded values of transmissivity of approximately 510 and 540 ft²/d, respectively, for the upper part of the aquifer.

TABLE 4.8. Summary of Hydraulic Property Values Determined for Tests Performed in Well 299-W10-15

<u>Test Method</u>	<u>Analysis Method</u>	<u>Transmissivity, (a) ft²/d</u>	<u>Equivalent Hydraulic Conductivity, ft/d</u>
Slug Withdrawal (Test #2)	Bouwer and Rice (1976)	510	32
Slug Withdrawal (Test #3)	Bouwer and Rice (1976)	540	34
Slug Withdrawal (Test #2)	Cooper et al. (1967)	Non-unique Solution	
Slug Withdrawal (Test #3)	Cooper et al. (1967)	Non-unique Solution	
Best Estimate		<u>530</u>	<u>33</u>

(a) Transmissivity was calculated by multiplying equivalent hydraulic conductivity by the thickness of the test interval (i.e., 15.8 ft).

The best estimate of transmissivity, an average value, was determined to be 530 ft²/d. The best estimate of equivalent hydraulic conductivity, an average value, was determined to be 33 ft/d.

WELL 299-W10-16

This well is located on the south side of the T Tank Farm in the 200-West Area (see Figure 1.4). Refer to Appendix J for the as-built diagram, field records, data-logger output, and graphs of the data.

Stratigraphy

The screened interval is presumed to lie within the middle unit of the Ringold Formation. The lithology of this interval is a sandy gravel. The full saturated thickness of the sediments above the basalt at this location is inferred to be 275 ft, based on available geologic information in Jensen et al. (1989). The bottom of the aquifer is presumed to be either the top of one of the fine-grained units of the Ringold Formation or the top of the underlying Elephant Mountain Basalt.

Test Performance and Data Analysis

One slug withdrawal and one slug injection test were performed on October 30, 1989. The depth of the screened interval was reported to be approximately 198 to 219 ft below land surface. Before conducting the tests, the depth to the "static" water level was determined to be approximately 203 ft below land surface. Therefore, the tests were conducted within the screened interval.

The water level oscillated at the beginning of each of the tests before it recovered exponentially with time. The data show that the data logger recorded a value of -8.46 ft at an elapsed time of 0.8 sec (0.0133 min) after initiation of the data logger for the withdrawal test (test #3). This change in water level is greater than the theoretical water-level displacement of 1.9 ft expected with the 6-ft slugging rod in a 4-in.-dia well. This difference indicates that the fluctuations in water level may be the result of erroneous water-level measurements caused by a fluid column of air and water

created at the instant the slugging rod was withdrawn. These fluctuations may also be influenced by induced inertial effects.

An arithmetic plot of the data for withdrawal test #3 indicates that the observed initial water-level change was 1.65 ft. This value is less than the theoretical water-level displacement of 1.90 ft expected, calculated using the dimensions of the 6-ft slugging rod. This difference indicates that formation water was entering the well during withdrawal of the slugging rod. Although this condition violates the assumption requiring an instantaneous water-level change, it does not necessarily invalidate the results. However, the analytical results may be less reliable because of the error in determining the parameters (i.e., Y_0 , Y_t , t , H_0) used in the analytical equations. The water level fully recovered to its pretest level within 82 sec.

For the slug withdrawal test, a correction was applied to the recorded elapsed times because of the time difference between initiation of the data logger and withdrawal of the slugging rod. For this test, the data indicate that the slugging rod was withdrawn between 0.6 sec (0.0099 min) and 0.8 sec (0.0133 min) elapsed time. The time the slugging rod was withdrawn, t_0 , is chosen as a midpoint between these elapsed times (i.e., $t_0 = 0$ at $t_e = 0.7$ sec). Therefore, 0.7 sec was subtracted from all the elapsed time values for test #3 for analysis.

The data for test #3 were analyzed with the Bouwer and Rice methods. A semilogarithmic plot of the water-level change versus time (i.e., corrected time) since the slugging rod was removed is shown in Appendix J. The early portion of the data ($t < 25$ sec) on the graph was approximated with a linear best-fit straight line. For $t > 25$ sec, the data indicate a curvi-linear relationship and therefore were not used to approximate the straight line. The approximated best-fit line was projected to the Y_t intercept at time $t_0 = 0$. This projected value at the intercept, 2.05 ft, was used for Y_0 in the Bouwer and Rice equation.

The Bouwer and Rice method yielded an equivalent hydraulic conductivity of approximately 33 ft/d for test #3. This value of equivalent hydraulic conductivity multiplied by the thickness of the test interval of 16.4 ft

yielded a value of transmissivity of $540 \text{ ft}^2/\text{d}$ for the upper part of the aquifer. A summary of the parameters substituted into the Bouwer and Rice equation is presented in Appendix J.

For slug injection test #2, water-level fluctuations occurred at the beginning of the test. The data logger recorded values greater than the theoretical water-level displacement of 1.9 ft expected at the beginning of the test. This difference indicates that these fluctuations may be the result of erroneous water-level measurements caused by a fluid column of air and water created at the instant the slugging rod was injected. These fluctuations may also be influenced by induced inertial effects.

An arithmetic plot of the data indicates that the observed initial water-level change (just before recovering exponentially) was 0.85 ft for injection test #2. This value is less than the theoretical water-level displacement of 1.90 ft expected, calculated using the dimensions of the 6-ft slugging rod. This difference indicates that borehole water flowed through the screen into the formation during injection of the slugging rod. Although this condition violates the assumption requiring an instantaneous water-level change, it does not necessarily invalidate the results. However, the analytical results may be less reliable because of the error in determining the parameters (i.e., Y_0 , Y_t , t , H_0) used in the analytical equations.

The water level recovered to its pretest level within approximately 45 sec. However, the water level did not recover exactly to its pretest level, possibly because the transducer moved during injection of the slugging rod.

A correction was applied to the slug injection test data because of the water-level fluctuations that occurred at the beginning of the test. An elapsed time of 0.05 min (3 sec) was subtracted from all the elapsed times so that $t_0 = 0$ at $t_e = 3$ sec. Initiation of the data logger must have occurred slightly later than injection of the slugging rod because the data indicate that the equilibrium (reference) water level was "missed" at the beginning of the test. Because t_0 is not exactly known, t_0 is assumed to be the elapsed time, $t_e = 3$ sec, when the maximum observed water-level change occurred just before the water level recovered exponentially.

9313018.0445

The data for test #2 were analyzed with the Bouwer and Rice method. A semilogarithmic plot of the water-level change versus time (i.e., corrected time) since the slugging rod was injected is shown in Appendix J. The early portion of the data ($t < 9$ sec) on the graph was approximated with a linear best-fit straight line. For $t > 9$ sec, the data indicate a curvi-linear relationship and therefore were not used to approximate the straight line. The approximated best-fit line was projected to the Y_t intercept at time $t_0 = 0$. This projected value at the intercept, 0.91 ft, was used for Y_0 in the Bouwer and Rice equation.

A summary of the parameters substituted into the Bouwer and Rice equation is presented in Appendix J.

Summary of Test Results

Values of transmissivity and equivalent hydraulic conductivity from the analytical methods applied for each of the slug tests are summarized in Table 4.9. The hydraulic properties are determined solely for the entire test interval. The best estimates of these hydraulic properties are determined to be most representative of the test interval.

The Bouwer and Rice method yielded an equivalent hydraulic conductivity of approximately 41 ft/d for test #2. This value of equivalent hydraulic conductivity multiplied by the thickness of the test interval of 16.4 ft yielded a value of transmissivity of 670 ft²/d for the upper part of the aquifer.

The best estimate of transmissivity was determined to be 540 ft²/d, the value calculated from the slug withdrawal test (test #3). The results from this test are considered to yield the best estimates of the hydraulic properties because the observed initial water-level change was closer to the theoretical water-level displacement of 1.9 ft expected with the 6-ft slugging rod. Smaller differences between the observed and theoretical water-level displacement reduced the error in the calculations.

In addition, the analytical results from the slug injection test are considered to be overestimates of the test interval because the fall of the water level occurred through the vadose zone above the water table. The

TABLE 4.9. Summary of Hydraulic Property Values Determined for Tests Performed in Well 299-W10-16

<u>Test Method</u>	<u>Analysis Method</u>	<u>Transmissivity, (a) ft²/d</u>	<u>Equivalent Hydraulic Conductivity, ft/d</u>
Slug Injection (Test #2)	Bouwer and Rice (1976)	670(b)	41
Slug Withdrawal (Test #3)	Bouwer and Rice (1976)	540	33
Slug Injection (Test #2)	Cooper et al. (1967)	Non-unique Solution	
Slug Withdrawal (Test #3)	Cooper et al. (1967)	Non-unique Solution	
Best Estimate		<u>540</u>	<u>33</u>

- (a) Transmissivity was calculated by multiplying equivalent hydraulic conductivity by the thickness of the test interval (i.e., 16.4 ft).
 (b) Analytical results from the slug injection tests are considered to be overestimates of the test interval.

rate of fall of the water level in the well caused by inflow into the vadose zone is greater than the fall of the water level in the well caused by inflow into the saturated zone.

The best estimate of equivalent hydraulic conductivity was determined to be 33 ft/d.

Hydraulic property values could not be determined from the slug withdrawal test (#3) using the Cooper et al. analytical method. The portion of the data considered to be "representative" of the aquifer materials is non-unique and can be analyzed using several type curves. The slug injection test (#2) data could not be analyzed with the Cooper et al. method because the value of H_0 for the test could not be determined accurately.

9313018-0447

5.0 REFERENCES

Bouwer, H. 1989. "The Bouwer and Rice Slug Test - An Update." Ground Water 27(3):304-309.

Bouwer, H., and R. C. Rice. 1976. "A Slug Test for Determining Hydraulic Conductivity of Unconfined Aquifers With Completely or Partially Penetrating Wells." Water Resources Research 12(3):423-428.

Cooper, H. H., Jr., J. D. Bredehoeft, and I. S. Papadopoulos. 1967. "Response of a Finite-Diameter Well to an Instantaneous Charge of Water." Water Resources Research 3(1):263-269.

Jensen, E. J., S. P. Airhart, M. A. Chamness, T. J. Gilmore, D. R. Newcomer, and K. R. Oster. 1989. 40 CFR 265 Interim-Status Ground-Water Monitoring Plan for the Single-Shell Tanks. WHC-SD-EN-AP-012, prepared by Pacific Northwest Laboratory for Westinghouse Hanford Company, Richland, Washington.

Papadopoulos, S. S., J. D. Bredehoeft, and H. H. Cooper, Jr. 1973. "On the Analysis of 'Slug Test' Data." Water Resources Research 9(4):1087-1089.

PNL. 1989. Procedures for Ground-Water Investigations. PNL-6894, Pacific Northwest Laboratory, Richland, Washington.

Roberson, J. A., and C. T. Crowe. 1985. Engineering Fluid Mechanics. 3rd ed., Houghton Mifflin Company, Boston, Massachusetts.

Walter, G. R., and G. M. Thompson. 1982. "A Repeated Pulse Technique for Determining the Hydraulic Properties of Tight Formations." Ground Water 20(2):186-193.

9313018.044

APPENDIX A

TEST DATA AND ANALYSIS FOR WELL 299-E24-19

9313018.04"

APPENDIX A

TEST DATA AND ANALYSIS FOR WELL 299-E24-19

This appendix contains the as-built diagram for the well construction, Slug Test Record Form, Aquifer Test Data Sheets, Equipment Record Forms, Electronic Data Control Forms, and accompanying data logs and plots for well 299-E24-19.

9313018.D4C

9313018.D4C



AS-BUILT DIAGRAM

Well Number 299-E24-19Geologist GEOFFIN, AIRHART,
LUBRECHT, KENNEDYPage 1 of 3Reviewed by J. E. McElroyDate 12-8-99

Construction Data		Depth in Feet	Geologic/Hydrologic Data	
Description	Diagram		Diagram Litho.	Lithologic Description
151' 10" OF 10" CARBON	[Cross-hatched pattern]	5'	- - -	MUDDY SAND
STEEL CASING		10'	0 - 0 - 0	GRAVELLY MUDDY SAND
	[Cross-hatched pattern]	15'	0 0 0	GRAVELLY SAND
302' 6" OF 8" CARBON		20'		SAND
STEEL CASING	[Cross-hatched pattern]	25'	0 0	SLIGHTLY GRAVELLY SAND
		30'	0 0 0	SANDY GRAVEL
290.57' OF 4" STAINLESS	[Cross-hatched pattern]	35'	0 0 0	" "
STEEL CASING		40'	0 0 0	" "
	[Cross-hatched pattern]	45'	0 0 0	GRAVELLY SAND
		50'	0 0 0	SANDY GRAVEL
	[Cross-hatched pattern]	55'	0 0 0	" "
		60'	- - -	MUDDY SAND @ 50'
	[Cross-hatched pattern]	65'		SAND
		70'	0 0 0	"
	[Cross-hatched pattern]	75'	0 0 0	GRAVELLY SAND
		80'	0 0 0	"
	[Cross-hatched pattern]	85'	0 0 0	"
		90'	0 0 0	"
	[Cross-hatched pattern]	95'	0 0 0	SANDY GRAVEL
		100'	0 0 0	"
	[Cross-hatched pattern]	105'	0 0 0	"
		110'	0 0 0	GRAVELLY SAND
	[Cross-hatched pattern]	115'	0 0 0	"
		120'	0 0 0	"
	[Cross-hatched pattern]	125'	0 0 0	SAND
		130'		"

A-1800-186 (3/87)

9313018.0451



AS-BUILT DIAGRAM

Well Number 299-E24-19 Geologist GOODWIN AIRHART Page 2 of 3
LUBBERT, KENNEDY
 Reviewed by V.C. McShan Date 12-5-89


Construction Data		Depth in Feet	Geologic/Hydrologic Data	
Description	Diagram		Diagram Litho.	Lithologic Description
151' 10" OF 10" CARBON		135'		SLIGHTLY GRAVELLY SAND
STEEL CASING WITH DRIVE		140'		"
SHAFT		145'		SAND
		150'		SLIGHTLY GRAVELLY SAND
302' 6" OF 8" CARBON		155'		SAND
STEEL CASING		160'		"
		165'		"
230.57' OF 4" STAINLESS		170'		"
STEEL CASING		175'		"
		180'		"
		185'		"
		190'		ENCOUNTERED 350-400 GPM @ 187'
		195'		NO CONTAM. DETECTED 191'-194'
		200'		350-400 GPM @ 195'
		205'		NO CONTAM. DETECTED @ 200'
		210'		"
		215'		"
		220'		"
		225'		"
		230'		"
		235'		"
		240'		"
		245'		"
		250'		SLIGHTLY GRAVELLY SAND
		255'		GRAVELLY SAND
		260'		SAND





AS-BUILT DIAGRAM


Date 12-5-89


COMPLETION SYMBOLS:


 CEMENT GROUT

 BENTONITE CRUMBLES

 BENTONITE PELLETS

 SILICA SAND

 CASING JOINTS

 CASING CENTRALIZER

Data for Well E24-19Pumping Well

Observation Wells _____

Location 200 East Area, A Tank Farm.

Type of Aquifer Test Sim Injection / Withdrawal

How Q Measured 2

How Q Measured _____
How W.L.'s Measured Steel tape 1/2 in. ± 0.014 ^{thinner (3 in. S.H.)} Depth of Pump/Airpipe _____

Rad./Dist. or/From Pumping Well 2"

Meas. Point for W.L.'s Top of 4" casing

Elevation of Meas. Point

Depth of Pump/Airpipe _____

Pump On: date 7/1/00 time 12:00

Pump Off: date _____ time _____

Duration of Aquifer Test _____

Time t = _____ at t' = 0					Water Level Data Static Water Level <u>286.32' below TOC</u>				Discharge		Recorded By	Comments
Day	Clock Time	t	t'	VR	Reading	Conversions or Corrections	Water Level	s or s'	Reading	Q		
192	1003				277	-0.68	286.32					D/B = 299.3 + 2.5 = 301.8 in T.
												TOC is 0.9' above ground
	1035				Ref = 0 @ 13.63'		Scale = 9.99		offset = 0.0			Step # 8
												T. L. S. D. L. S/N 259198
												Data Logger S/N 1KB-701
												DRN
	1040				Drop Slug (Slug hung up - it was totally submerged within 10 sec.)							
	1050				Stopped logging data							DRN
					ref = 0 @ 13.67'		Scale = 9.99		offset = 0.0			Step # 9
	1058				Withdraw Slug (pulled it fast just before next cycle)							
	1109				Stop logging data							DRN
<hr/>												
					Switch to a different datalogger because all step numbers are filled							Data Logger 1KB-700
<hr/>												
					Step # 0	ref = 0 @ 13.73'	Scale = 9.99		offset = 0.0			
	1118				Drop Slug ref = 0 @ 13.73' (Slug dropped slowly so it won't hang)							
	1129				Stop logging data							DRN
					Test # 1	ref = 0 @ 13.74'						
	1132				Withdraw Slug (pulled it fast just before next cycle)							
	1140				Stop logging data							DRN
✓	1155				Extracted one soil core - water was a little dirty							
<hr/>												
DANIEL NEWCOMER 10/2/89												

333013-041

Location 200 East Area, A Tank Farm Date of Test 10/2/89
 Well Number 299-E24-19 Procedure Number PNL-MA-567
AT-6 Rev 0
 Type of Test(s) Slug Injection / Withdrawal
 Personnel Conducting Test D.R. Newcomer

WELL CONFIGURATION

Well Depth 300.9' below ground surface Borehole Diameter 8"
 Well Casing Inside Diameter 4" Well Screen Inside Diameter 4"
 Length of Screened Interval 15.6' (below water) Depth of Screen 279.65' to 300.68' below ground
282' - 301' DR. # 10/26/89
 Comments Well is undeveloped

SLUG INFORMATION


Slug Construction Materials Carbon steel
 Length of Slug 8.05' Diameter of Slug 0.24'
 Comments _____
 Volume of Attachments (if applicable) _____

MEASUREMENT EQUIPMENT INFORMATION

	Make	Model	Serial Number
Electric Tape			
Steel Tape	Lufkin	Super Hi-way Nubian	L300-14
Data logger	In Situ	SE1000B	1KB-701, 1KB-700 (See Aquifer Test Data Sheet)
Transducer	Druck	PTX-161D	259198
Other			

Darrell Newcomer 10/2/89

Equipment Record Form for the Installation and Removal of Data Loggers and Pressure Transducers

Initial Check: <i>ok</i>		
Purpose of Installation: <i>To monitor slug injection / withdrawal test responses</i>		
Monitored Hydrologic Unit or Water Body: <i>Uppermost Unconfined Aquifer (Hanford formation)</i>		
Date/Time of Installation: <i>10/2/89 1:015 hrs.</i>		Procedure Followed: <i>PNL-MA-567 WL-4, Rev 0</i>
Data Logger Make/Model: <i>In Situ / SE1000B</i>		
Serial No.: <i>1KB-701 1KB-700</i>	Number of Channels Used: <i>1</i>	
Pressure Transducer Make/Model: <i>Druck / PTX-161D</i>	Full Scale Range: <i>10 psi</i>	Well No.: <i>299-E24-19</i>
	Serial No.: <i>259198</i>	Depth: <i>~200' below ground surface</i>
Pressure Transducer Make/Model:	Full Scale Range:	Well No.:
	Serial No.:	Depth:
Description of Data Logger Installation and Well Head Configuration: 		
Comments: <i>Slug was positioned into place above the water before placing the transducer down the well. Switch to a different datalogger—after first set of tests because the step numbers were filled—and could the data could not be dumped in the field (see Aquifer Test Data Sheet).</i>		
Equipment Installed By <i>Darrell Newcomer</i>		
Date/Time of Equipment Removal: <i>10/2/89 1145 hrs.</i>		
Decontamination-Procedure (if required):		
Equipment Removed By <i>Darrell Newcomer</i>		

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 10/2/89, 1040 hrs.DATE AND END TIME OF DATA ACQUISITION 10/2/89, 1050 hrs.WELL NUMBER 299-E24-19TYPE OF TEST OR DATA Slug TestTYPE AND IDENTIFICATION NUMBER OF DATA LOGGER In Situ
Hermit SE1000B Serial # 1KB-701TEST NUMBER 8CHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED feetNUMBER OF PAGES ATTACHED 2COMMENTS: Test 8 = Submerge Slug

_____DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

Darrell Newman, Scientist
Name, title10/3/89
Date

9313018.0457

Well: 299-E24-19
Test Date: October 2, 1989
Start Time: 10:40

SE1000B
Environmental Logger
10/02 15:38

Unit# 00701 Test# 8

INPUT 1: Level (F)

Reference 0.00
Scale factor 9.99
Offset 0.00

Elapsed Time, Value,
min ft

0.0000 0.17
0.0033 0.17
0.0066 0.19
0.0099 0.19
0.0133 0.19
0.0166 0.14
0.0200 0.11
0.0233 0.11
0.0266 0.08
0.0300 0.05
0.0333 0.03
0.0500 0.01
0.0666 0.01
0.0833 0.01
0.1000 0.01
0.1166 0.01
0.1333 0.01
0.1500 0.01
0.1666 0.01
0.1833 0.00
0.2000 0.01
0.2166 0.02
0.2333 0.01
0.2500 0.90
0.2666 0.31
0.2833 0.07
0.3000 0.00
0.3166 0.03
0.3333 0.23
0.4167 0.00
0.5000 0.03
0.5833 0.02

0.6667 0.01
0.7500 0.01
0.8333 0.02
0.9167 0.01
1.0000 0.02
1.0833 0.02
1.1667 0.02
1.2500 0.01
1.3333 0.02
1.4166 0.01
1.5000 0.01
1.5833 0.02
1.6667 0.02
1.7500 0.02
1.8333 0.01
1.9167 0.02
2.0000 0.02
2.5000 0.02
3.0000 0.02
3.5000 0.02
4.0000 0.02
4.5000 0.02
5.0000 0.02
5.5000 0.02
6.0000 0.02
6.5000 0.03
7.0000 0.03
7.5000 0.03
8.0000 0.03
8.5000 0.03
9.0000 0.03
9.5000 0.03
10.0000 0.03

END

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 10/2/89, 1058 hrs.DATE AND END TIME OF DATA ACQUISITION 10/2/89, 1108 hrs.WELL NUMBER 299-E24-19TYPE OF TEST OR DATA Slug TestTYPE AND IDENTIFICATION NUMBER OF DATA LOGGER In Situ
Hermit SE1000B Serial # 1KB-701TEST NUMBER 9CHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED feetNUMBER OF PAGES ATTACHED 2COMMENTS:
Test 9 = Withdraw Slug

DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

Darrell Newcomer, Scientist 10/3/89
Name, title Date

9313018.0459

9313018.0459

Well: 299-E24-19
Test Date: October 2, 1989
Start Time: 10:58

SE1000B
Environmental Logger
10/02 15:40

Unit# 00701 Test# 9

INPUT 1: Level (F)

Reference 0.00
Scale factor 9.99
Offset 0.00

Elapsed Time, Value,
min ft

0.0000	- 1.60
0.0033	- 1.50
0.0066	- 1.39
0.0099	- 1.31
0.0133	- 1.25
0.0166	- 1.18
0.0200	- 1.10
0.0233	- 1.05
0.0266	- 1.00
0.0300	- 0.95
0.0333	- 0.88
0.0500	- 0.65
0.0666	- 0.46
0.0833	- 0.35
0.1000	- 0.25
0.1166	- 0.17
0.1333	- 0.12
0.1500	- 0.08
0.1666	- 0.05
0.1833	- 0.03
0.2000	- 0.01
0.2166	- 0.00
0.2333	0.00
0.2500	0.00
0.2666	0.00
0.2833	0.01
0.3000	0.01
0.3166	0.01
0.3333	0.02
0.4167	0.02
0.5000	0.02
0.5833	0.02

0.6667	0.02
0.7500	0.01
0.8333	0.01
0.9167	0.01
1.0000	0.02
1.0833	0.02
1.1667	0.02
1.2500	0.02
1.3333	0.02
1.4166	0.02
1.5000	0.02
1.5833	0.02
1.6667	0.02
1.7500	0.02
1.8333	0.02
1.9167	0.02
2.0000	0.02
2.5000	0.02
3.0000	0.02
3.5000	0.02
4.0000	0.02
4.5000	0.02
5.0000	0.02
5.5000	0.02
6.0000	0.02
6.5000	0.02
7.0000	0.02
7.5000	0.03
8.0000	0.03
8.5000	0.02
9.0000	0.02
9.5000	0.02
10.0000	0.02

END

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 10/2/89, 1118 hrs.DATE AND END TIME OF DATA ACQUISITION 10/2/89, 1128 hrs.WELL NUMBER 299-E24-19TYPE OF TEST OR DATA Slug TestTYPE AND IDENTIFICATION NUMBER OF DATA LOGGER In SituHermit SE1000B Serial # 1KB-700TEST NUMBER ØCHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED feetNUMBER OF PAGES ATTACHED 2

COMMENTS:

Test Ø = Submerge Slug

DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

Darrell Newman, Scientist
Name, title.10/3/89
Date

Well: 299-E24-19
Test Date: October 2, 1989
Start Time: 11:18

SE1000B
Environmental Logger
10/02 15:44

Unit# 00700 Test# 0

INPUT 1: Level (F)

Reference 0.00
Scale factor 9.99
Offset 0.00

Elapsed Time, min	Value, ft
0.0000	0.31
0.0033	0.31
0.0066	0.30
0.0099	0.32
0.0133	0.31
0.0166	0.32
0.0200	0.31
0.0233	0.33
0.0266	0.32
0.0300	0.32
0.0333	0.35
0.0500	0.33
0.0666	0.39
0.0833	0.41
0.1000	0.40
0.1166	0.40
0.1333	0.41
0.1500	0.23
0.1666	0.29
0.1833	0.00
0.2000	0.01
0.2166	0.03
0.2333	0.00
0.2500	- 0.03
0.2666	- 0.08
0.2833	0.09
0.3000	- 0.00
0.3166	0.00
0.3333	0.00
0.4167	0.00
0.5000	0.00
0.5833	0.00

0.6667	0.00
0.7500	0.00
0.8333	0.00
0.9167	0.00
1.0000	0.00
1.0833	0.00
1.1667	0.00
1.2500	0.00
1.3333	0.00
1.4166	0.00
1.5000	0.00
1.5833	0.00
1.6667	0.00
1.7500	0.00
1.8333	0.00
1.9167	0.00
2.0000	0.00
2.5000	0.00
3.0000	0.00
3.5000	0.00
4.0000	0.00
4.5000	0.00
5.0000	0.00
5.5000	0.00
6.0000	0.00
6.5000	0.00
7.0000	0.00
7.5000	0.00
8.0000	0.00
8.5000	0.00
9.0000	0.00
9.5000	0.00
10.0000	0.00
END	

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 10/2/89, 1132 hrs.DATE AND END TIME OF DATA ACQUISITION 10/2/89, 1140 hrs.WELL NUMBER 299-E24-19TYPE OF TEST OR DATA Slug TestTYPE AND IDENTIFICATION NUMBER OF DATA LOGGER In Situ
Hermit SE1000B Serial # 1KB-700TEST NUMBER 1CHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED feetNUMBER OF PAGES ATTACHED 2

COMMENTS:

Test 1 = Withdraw Slug

_____DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

Darrell Newcomer, Scientist
Name, title10/3/89
Date

9313018.0463

Well: 299-E24-19
Test Date: October 2, 1989
Start Time: 11:32

SE1000B
Environmental Logger
10/02 15:46

Unit# 00700 Test# 1

INPUT 1: Level (F)

Reference 0.00
Scale factor 9.99
Offset 0.00

Elapsed Time, Value,
min ft

0.0000	- 1.61
0.0033	- 1.51
0.0066	- 1.41
0.0099	- 1.33
0.0133	- 1.25
0.0166	- 1.17
0.0200	- 1.11
0.0233	- 1.05
0.0266	- 0.98
0.0300	- 0.93
0.0333	- 0.87
0.0500	- 0.64
0.0666	- 0.45
0.0833	- 0.33
0.1000	- 0.23
0.1166	- 0.17
0.1333	- 0.12
0.1500	- 0.09
0.1666	- 0.06
0.1833	- 0.04
0.2000	- 0.03
0.2166	- 0.02
0.2333	- 0.01
0.2500	- 0.01
0.2666	- 0.01
0.2833	- 0.00
0.3000	- 0.00
0.3166	- 0.00
0.3333	- 0.00
0.4167	- 0.00
0.5000	- 0.00


0.5833	- 0.00
0.6667	- 0.00
0.7500	- 0.00
0.8333	- 0.00
0.9167	- 0.00
1.0000	- 0.00
1.0833	- 0.00
1.1667	- 0.00
1.2500	- 0.00
1.3333	- 0.00
1.4166	- 0.00
1.5000	- 0.00
1.5833	- 0.00
1.6667	- 0.00
1.7500	- 0.00
1.8333	- 0.00
1.9167	- 0.00
2.0000	- 0.00
2.5000	- 0.00
3.0000	- 0.00
3.5000	- 0.00
4.0000	0.00
4.5000	0.00
5.0000	0.00
5.5000	- 0.00
6.0000	- 0.00
6.5000	0.00
7.0000	- 0.00
7.5000	0.00
8.0000	- 0.00

END

9313018.046"

9313018.046"


9313018.0465



A.16

9313018.0465

A.17



WELL 299-E24-19, SLUG WITHDRAWAL TEST #1

THE BELOW HYDRAULIC CONDUCTIVITY VALUE WAS CALCULATED
USING THE BOUWER AND RICE SLUG TEST METHOD.

SOURCE= "THE BOUWER AND RICE SLUG TEST-AN UPDATE"
GROUND WATER, VOL 27, NO. 3, MAY-JUNE 1989.

RADIUS OF CASING USED IN CALCULATIONS HAS BEEN
CORRECTED FOR THE THICKNESS OF GRAVEL OR SAND
PACK DUE TO WATER LEVEL CHANGES IN THE SCREEN OR
OPEN INTERVAL OF WELL.

Rc (ft)	Rw (ft)	Le (ft)	Lw (ft)	H (ft)
---------	---------	---------	---------	--------

.2297	.3333	15.6000	15.6000	95.0000
-------	-------	---------	---------	---------

Le/Rw = 46.8000000

A= 3.0229800

B= 4.898688E-001

C= 2.6137240

SANDPACK POROSITY= 3.000000E-001

t (min)= 5.000000E-002

1/t= 20.0000000

Yo= (ft) 1.6300000

Yt= (ft) 6.200000E-001

1/t ln(Yo/Yt)= 19.3323200

ln[(H-Lw)/Rw]= 5.4731110

ln(Re/Rw)= 2.4515670


K (ft/day) = 115.4481000

T OF THE SATURATED SCREEN INTERVAL

(ft²/day)= 1800.9900000

931301B.D4C

A.19



931301B.D4C

WELL 299-E24-19, SLUG WITHDRAWAL TEST #9

THE BELOW HYDRAULIC CONDUCTIVITY VALUE WAS CALCULATED
USING THE BOUWER AND RICE SLUG TEST METHOD.

SOURCE= "THE BOUWER AND RICE SLUG TEST-AN UPDATE"
GROUND WATER, VOL 27, NO. 3, MAY-JUNE 1989.

RADIUS OF CASING USED IN CALCULATIONS HAS BEEN
CORRECTED FOR THE THICKNESS OF GRAVEL OR SAND
PACK DUE TO WATER LEVEL CHANGES IN THE SCREEN OR
OPEN INTERVAL OF WELL.

Rc (ft)	Rw (ft)	Le (ft)	Lw (ft)	H (ft)
.2297	.3333	15.6000	15.6000	95.0000

Le/Rw = 46.8000000

A= 3.0229800

B= 4.898688E-001

C= 2.6137240

SANDPACK POROSITY= 3.000000E-001

t (min)= 5.000000E-002

1/t= 20.0000000

Yo= (ft) 1.5800000

Yt= (ft) 6.600000E-001

1/t ln(Yo/Yt)= 17.4588100

ln[(H-Lw)/Rw]= 5.4731110

ln(Re/Rw)= 2.4515670

K (ft/day) = 104.2599000

T OF THE SATURATED SCREEN INTERVAL

(ft²/day)= 1626.4540000

9313018.1469

APPENDIX B

TEST DATA AND ANALYSIS FOR WELL 299-E25-40

THIS PAGE INTENTIONALLY
LEFT BLANK

9313018.047

THIS PAGE INTENTIONALLY
LEFT BLANK

010518

APPENDIX B

TEST DATA AND ANALYSIS FOR WELL 299-E25-40

This appendix contains the as-built diagram for the well construction, Slug Test Record Form, Aquifer Test Data Sheets, Equipment Record Forms, Electronic Data Control Forms, and accompanying data logs and plots for well 299-E25-40.

9313018.047

9313018.047



AS-BUILT DIAGRAM

Well Number 299-E25-40 Geologist MOLLOCK GORDON Page 1 of 3Reviewed by V. McShane Date 12-4-89

Construction Data		Depth in Feet	Geologic/Hydrologic Data	
Description	Diagram		Diagram Litho.	Lithologic Description
143.7' OF 10" CARBON		5		SAND (Tr. Gravel)
STEEL CASING		10		SAND
CEMENT GROUT		15		SAND
		20		SAND (Tr. Gravel)
273.1' OF 8" CARBON		25		"
STEEL CASING		30		"
		35		"
		40		SANDY GRAVEL
		45		SAND
FACUTRY INSTALLED CENTRALIZERS		50		"
		55		"
		60		"
253.25' of		65		SLIGHTLY GRAVELLY SAND
4" DIA STAINLESS STEEL CASING		70		SL. Gravelly SAND
		75		SANDY GRAVEL
		80		Gravelly SAND
		85		Gravelly SAND
8-20 BENTONITE		90		Gravelly SAND
		95		Gravelly SAND
		100		SAND
		105		SAND
		110		SAND
		115		SAND
		120		SAND
		125		SAND
		130		SAND

9313018.0472



AS-BUILT DIAGRAM

Well Number 299-E25-40 Geologist M.O. Lubrecht, Goodwin Page 2 of 3Reviewed by V. Z. McElhan Date 12-4-89

Construction Data		Depth in Feet	Geologic/Hydrologic Data	
Description	Diagram		Diagram Litho.	Lithologic Description
10" DIA. CARBON STEEL		135		SAND
CASING 0' - 143.7'		140		SAND
		145		SAND
		150		SAND
8" DIA. CARBON STEEL		155		"
CASING 0' - 273.1'		160		"
		165		Slightly Gravelly SAND
		170		"
		175		SAND
		180		"
		185		"
		190		"
		195		SANDY GRAVEL
		200		" "
		205		" "
		210		SLIGHTLY GRAVELLY SAND
		215		" " "
		220		SAND
		225		"
8-20 BENTONITE		230		"
		235		"
		240		"
3/8" VOLCLAY TABLETS		245		"
		250		SLIGHTLY MUDDY SAND
14-30 CO. SILICA SAND		255		MUD
		260		SLIGHTLY GRAVELLY SAND

Well Number 299-E25-40 Geologist LUBRECHT, GOODWIN Page 3 of 3

Reviewed by W. L. McLean

Date 12-4-89

[illegible]

WHC-SD-EN-TI-147, Rev. 0

page 1 of 1

Data for Well E 25-40

Pumping Well

Observation Wells -

Location 200 East A Tank Farms
Type of Aquifer Test Slug Injection/Withdrawal
How Q Measured -

How Q Measured _____
How W.L.'s Measured Steel tape L3 or 14 transducer (Insitu)
Depth of Pu _____

Rad / Dist (of) From Pumping Well 2"

Meas. Point for W.L.'s Top of 4" casing

Elevation of Meas. Point

Depth of Pump/Airpipe

Pump On: date time

Pump Off: date 1 time

Duration of Aquifer Test 1

Time				Water Level Data		Discharge	Recorded By	Comments			
t =	at t' = 0			Static Water Level	258.13' below Top						
Day	Clock Time	t	t'	1/t'	Reading	Conversions or Corrections	Water Level	s or s'	Reading	Q	
9/29	13:00				258.13'	Transducer set to bottom of well					Transducer 262361
					274.43	Depth to bottom					Data logger JKB-701
	13:03				16.22	reference on X & E					well Transducer Reading
	1310				16.22	is ref scale = 9.99 offset = 0.0					DAN Set slug a few inches above water
	1311					slug immersed a couple of seconds later					slug immersed
	13:28					Test # 1 dropping slug					well
						Test # 1 stopped					
	13:36				16.16	reference set to 0					
	1332										withdrawn slug
	1342					Test # 1 stopped					
	1343				16.17	reference set to 0					
	1345					slug dropped					
	1355					Test # 2 stopped					
	1356				16.18	reference set to 0					
	1359					slug pulled					
	1410					Test # 3 stopped					
	1419					Depth to bottom is 274.8' from Top of 4" casing					
						Stickup of 4" casing is 1.2' from ground surface					
Darrell McNamee 9/29/89											
William E. Cronin 9/29/89											

Darrell McCreone 9/29/89

William A. Davis 9/29/89

Location 200 East, A Tank Farm Date of Test 9/29/89
 Well Number 299-E25-40 Procedure Number PNL-MA-567 AT-6, Rev 0
 Type of Test(s) Slug Injection / Withdrawal
 Personnel Conducting Test D.R. Newcomer, Bill Cronin

WELL CONFIGURATION

Well Depth 270.6' below ground surface Borehole Diameter 8"
 Well Casing Inside Diameter 4" Well Screen Inside Diameter 4"
 Length of Screened Interval 16.1' (below water) Depth of Screen 252' - 273'
 Comments Well is undeveloped

SLUG INFORMATION


Slug Construction Materials Carbon steel
 Length of Slug 8.05' Diameter of Slug 0.24'
 Comments _____
 Volume of Attachments (if applicable) _____

MEASUREMENT EQUIPMENT INFORMATION

	Make	Model	Serial Number
Electric Tape			
Steel Tape	Lufkin	Super Hiway Nubian	L 300-14
Data logger	In Situ	SE1000 B	26-361 1KB-701
Transducer	Druck	PTX-161 D	262361
Other			

Darrell Newcomer 9/29/89

Equipment Record Form for the Installation and Removal of Data Loggers and Pressure Transducers

Initial Check: <i>OK</i>		
Purpose of Installation: <i>To monitor slug injection/withdrawal test responses</i>		
Monitored Hydrologic Unit or Water Body: <i>Saturated Screen Interval of Uppermost Unconfined Aquifer (Hanford formation)</i>		
Date/Time of Installation: <i>9/29/89 1300 hrs.</i>		Procedure Followed: <i>PHL-MH-567 WL-4, Rev 0</i>
Data Logger Make/Model: <i>In Situ / SE1000 B</i>		
Serial No.: <i>1 KB-701</i>	Number of Channels Used: <i>1</i>	
Pressure Transducer Make/Model: <i>Druck / PTX-161 D</i>	Full Scale Range: <i>10 psi</i>	Well No.: <i>299-E25-40</i>
	Serial No.: <i>262361</i>	Depth:
Pressure Transducer Make/Model:	Full Scale Range:	Well No.:
	Serial No.:	Depth:
Description of Data Logger Installation and Well Head Configuration:  <i>Stickup of 4" casing is 1.2 ft. above ground surface</i>		
Comments: <i>Slug was positioned into place above the water before placing the transducer down the well.</i>		
Equipment Installed By <i>D.R. Newcomer, Bill Cronin</i>		
Date/Time of Equipment Removal: <i>9/29/89 1415 hrs.</i>		
Decontamination Procedure (if required):		
Equipment Removed By <i>D.R. Newcomer, Bill Cronin</i>		

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 9/29/89 13:11DATE AND END TIME OF DATA ACQUISITION 9/29/89 13:27WELL NUMBER E25-40TYPE OF TEST OR DATA Slug testTYPE AND IDENTIFICATION NUMBER OF DATA LOGGER Analog
Hermet 1000S, Serial # 1KB-701TEST NUMBER 0CHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED ftNUMBER OF PAGES ATTACHED 2COMMENTS: Test 0 = Submerging Slug

DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

William E. Cox, Hydrologist
Name, title10/2/89
Date

9313018.0478

Well: 299-E25-40
 Test Date: September 29, 1989
 Start Time: 13:11

SE1000B
 Environmental Logger
 09/29 16:22

Unit# 00701 Test# 0

INPUT 1: Level (F)

Reference 0.00
 Scale factor 9.99
 Offset 0.00

Elapsed Time, Value,
 min ft

0.0000	- 0.00
0.0033	- 0.00
0.0066	- 0.00
0.0099	- 0.00
0.0133	- 0.00
0.0166	0.70
0.0200	0.09
0.0233	0.60
0.0266	0.76
0.0300	0.78
0.0333	2.01
0.0500	0.45
0.0666	0.81
0.0833	0.28
0.1000	0.15
0.1166	0.10
0.1333	0.08
0.1500	0.06
0.1666	0.05
0.1833	0.05
0.2000	0.04
0.2166	0.04
0.2333	0.03
0.2500	0.03
0.2666	0.02
0.2833	0.02
0.3000	0.02
0.3166	0.01
0.3333	0.01
0.4167	0.01
0.5000	0.00
0.5833	0.00

0.6667	0.00
0.7500	0.00
0.8333	0.00
0.9167	0.00
1.0000	- 0.00
1.0833	- 0.00
1.1667	- 0.00
1.2500	- 0.00
1.3333	- 0.00
1.4166	- 0.00
1.5000	- 0.00
1.5833	- 0.00
1.6667	- 0.00
1.7500	- 0.00
1.8333	- 0.00
1.9167	- 0.00
2.0000	- 0.01
2.5000	- 0.01
3.0000	- 0.01
3.5000	- 0.02
4.0000	- 0.02
4.5000	- 0.02
5.0000	- 0.02
5.5000	- 0.02
6.0000	- 0.02
6.5000	- 0.02
7.0000	- 0.02
7.5000	- 0.03
8.0000	- 0.03
8.5000	- 0.03
9.0000	- 0.03
9.5000	- 0.03
10.0000	- 0.03
12.0000	- 0.04
14.0000	- 0.04
16.0000	- 0.05

END

9313018.047

9313018.047

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 9/29/89 13:31
DATE AND END TIME OF DATA ACQUISITION 9/29/89 13:41
WELL NUMBER F25-40
TYPE OF TEST OR DATA Slug Test
TYPE AND IDENTIFICATION NUMBER OF DATA LOGGER Hermit 1000B, Serial # 1KB-701
TEST NUMBER 1
CHANNEL OR INPUT NUMBER 1
UNITS OF VALUES RECORDED ft
NUMBER OF PAGES ATTACHED 2
COMMENTS: Test 1 = Lifting Slug.

DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

William E Cronin, Hydrologist
Name, title

10/2/89
Date

Well: 299-E25-40
 Test Date: September 29, 1989
 Start Time: 13:31

SE1000B
 Environmental Logger
 09/29 16:25

Unit# 00701 Test# 1

INPUT 1: Level (F)

Reference 0.00
 Scale factor 9.99
 Offset 0.00

Elapsed Time, Value,
 min ft

0.0000	- 1.31
0.0033	- 1.21
0.0066	- 1.10
0.0099	- 1.01
0.0133	- 0.95
0.0166	- 0.91
0.0200	- 0.89
0.0233	- 0.83
0.0266	- 0.79
0.0300	- 0.75
0.0333	- 0.72
0.0500	- 0.59
0.0666	- 0.48
0.0833	- 0.40
0.1000	- 0.34
0.1166	- 0.28
0.1333	- 0.24
0.1500	- 0.20
0.1666	- 0.17
0.1833	- 0.15
0.2000	- 0.13
0.2166	- 0.11
0.2333	- 0.10
0.2500	- 0.08
0.2666	- 0.07
0.2833	- 0.06
0.3000	- 0.05
0.3166	- 0.05
0.3333	- 0.05
0.4167	- 0.02
0.5000	- 0.01
0.5833	- 0.00

0.6667	- 0.00
0.7500	- 0.00
0.8333	0.00
0.9167	0.00
1.0000	0.00
1.0833	0.00
1.1667	0.00
1.2500	0.00
1.3333	0.00
1.4166	0.00
1.5000	0.00
1.5833	0.00
1.6667	0.00
1.7500	0.00
1.8333	0.00
1.9167	0.01
2.0000	0.00
2.5000	0.00
3.0000	0.01
3.5000	0.00
4.0000	0.00
4.5000	0.00
5.0000	0.00
5.5000	0.00
6.0000	0.00
6.5000	0.00
7.0000	0.00
7.5000	0.00
8.0000	0.00
8.5000	0.00
9.0000	0.00
9.5000	0.00
10.0000	0.00

END

9313018.048

9313018.048

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 9/29/89 13:45DATE AND END TIME OF DATA ACQUISITION 9/29/89 13:55WELL NUMBER E25-40TYPE OF TEST OR DATA slug testTYPE AND IDENTIFICATION NUMBER OF DATA LOGGER Amstar
Hermet 1000B, serial # 1KB-701TEST NUMBER 2CHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED ftNUMBER OF PAGES ATTACHED 2COMMENTS: Test 2 = Submerging slug.DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

William E. Curran, Hydrologist 10/2/89
Name, title Date

931301B.0482

Well: 299-E25-40
 Test Date: September 29, 1989
 Start Time: 13:45

SE1000B
 Environmental Logger
 09/29 16:28

Unit# 00701 Test# 2

INPUT 1: Level (F)

Reference 0.00
 Scale factor 9.99
 Offset 0.00

Elapsed Time, min	Value, ft
0.0000	0.36
0.0033	0.33
0.0066	0.29
0.0099	0.25
0.0133	0.22
0.0166	0.20
0.0200	0.20
0.0233	0.18
0.0266	0.17
0.0300	0.15
0.0333	0.14
0.0500	0.11
0.0666	0.10
0.0833	0.09
0.1000	0.08
0.1166	0.07
0.1333	0.07
0.1500	0.06
0.1666	0.06
0.1833	0.06
0.2000	0.05
0.2166	0.05
0.2333	0.05
0.2500	0.05
0.2666	0.04
0.2833	0.04
0.3000	0.04
0.3166	0.04
0.3333	0.04
0.4167	0.03
0.5000	0.02
0.5833	0.02

0.6667	0.02
0.7500	0.02
0.8333	0.01
0.9167	0.01
1.0000	0.01
1.0833	0.01
1.1667	0.01
1.2500	0.00
1.3333	0.01
1.4166	0.00
1.5000	0.00
1.5833	0.00
1.6667	0.00
1.7500	0.00
1.8333	0.00
1.9167	0.00
2.0000	0.00
2.5000	0.00
3.0000	0.00
3.5000	0.00
4.0000	0.00
4.5000	0.00
5.0000	0.00
5.5000	0.00
6.0000	0.00
6.5000	0.00
7.0000	0.00
7.5000	0.00
8.0000	0.00
8.5000	0.00
9.0000	0.00
9.5000	0.00
10.0000	0.00

END

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 9/29/89 16:30 13:59DATE AND END TIME OF DATA ACQUISITION 9/29/89 16:40 14:09WELL NUMBER E25-40TYPE OF TEST OR DATA Slug testTYPE AND IDENTIFICATION NUMBER OF DATA LOGGER In Situ
Hemut 1000B, serial # 1KB-701TEST NUMBER 3CHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED ftNUMBER OF PAGES ATTACHED 2COMMENTS: Test 3 = Lifting Slug

_____DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

William E. Cronin, Psychologist 10/2/89
Name, title Date

Well: 299-E25-40
Test Date: September 29, 1989
Start Time: 13:59

SE1000B
Environmental Logger
09/29 16:30

Unit# 00701 Test# 3

INPUT 1: Level (F)

Reference 0.00
Scale factor 9.99
Offset 0.00

Elapsed Time, Value,
min ft

0.0000	- 1.18
0.0033	- 1.08
0.0066	- 0.99
0.0099	- 0.91
0.0133	- 0.84
0.0166	- 0.78
0.0200	- 0.73
0.0233	- 0.69
0.0266	- 0.65
0.0300	- 0.61
0.0333	- 0.58
0.0500	- 0.44
0.0666	- 0.35
0.0833	- 0.28
0.1000	- 0.23
0.1166	- 0.18
0.1333	- 0.15
0.1500	- 0.13
0.1666	- 0.11
0.1833	- 0.09
0.2000	- 0.08
0.2166	- 0.06
0.2333	- 0.06
0.2500	- 0.05
0.2666	- 0.04
0.2833	- 0.04
0.3000	- 0.03
0.3166	- 0.03
0.3333	- 0.03
0.4167	- 0.01
0.5000	- 0.00
0.5833	- 0.00


0.6667	- 0.00
0.7500	0.00
0.8333	0.00
0.9167	0.00
1.0000	0.00
1.0833	0.00
1.1667	0.00
1.2500	0.00
1.3333	0.00
1.4166	0.00
1.5000	0.00
1.5833	0.00
1.6667	0.00
1.7500	0.00
1.8333	0.00
1.9167	0.00
2.0000	0.00
2.5000	0.00
3.0000	0.00
3.5000	0.00
4.0000	0.00
4.5000	0.00
5.0000	0.00
5.5000	0.00
6.0000	0.00
6.5000	0.00
7.0000	0.00
7.5000	0.00
8.0000	0.00
8.5000	0.00
9.0000	0.00
9.5000	0.00
10.0000	0.00

END

9313013.D4C

9313013.D4C

931301B.0486



B.16

MHC-SD-EN-TI-147, Rev. 0

ooooo WELL 299-E25-40, SLUG WITHDRAWAL TEST #1

Y_o PROJECTED = 1.02 ft

Y_o OBSERVED = 1.31 ft


r_e = 0.2297 ft

LINEAR BEST FIT LINE; $\log_{10}(Y) = -4.77x + 0.01$

$$K = (r_e^2 \ln(R_e/r_w) / 2L_e t) \cdot \ln(Y_o/Y_1)$$

$$K = ((0.2297)^2 (2.48) / 2(16.1)(0.10)) \cdot \ln(1.02/0.34)$$

$$K = 64 \text{ ft/day}$$



WELL 299-E25-40, SLUG WITHDRAWAL TEST #1

 THE BELOW HYDRAULIC CONDUCTIVITY VALUE WAS CALCULATED
 USING THE BOUWER AND RICE SLUG TEST METHOD.
 SOURCE= "THE BOUWER AND RICE SLUG TEST-AN UPDATE"
 GROUND WATER, VOL 27, NO. 3, MAY-JUNE 1989.

 RADIUS OF CASING USED IN CALCULATIONS HAS BEEN
 CORRECTED FOR THE THICKNESS OF GRAVEL OR SAND
 PACK DUE TO WATER LEVEL CHANGES IN THE SCREEN OR
 OPEN INTERVAL OF WELL.


Rc (ft)	Rw (ft)	Le (ft)	Lw (ft)	H (ft)
.2297	.3333	16.1000	16.1000	95.0000

 Le/Rw = 48.3000000
 A= 3.0530930
 B= 4.990199E-001
 C= 2.6454010
 SANDPACK POROSITY= 3.000000E-001
 t (min)= 1.000000E-001
 1/t= 10.0000000
 Yo= (ft) 1.0200000
 Yt= (ft) 3.400000E-001
 1/t ln(Yo/Yt)= 10.9861200
 ln[(H-Lw)/Rw]= 5.4667940
 ln(Re/Rw)= 2.4790210


K (ft/day) = 64.2809700

T OF THE SATURATED SCREEN INTERVAL
 (ft²/day)= 1034.9240000

9313018.046



8.19



WELL 299-E25-40, SLUG WITHDRAWAL TEST #3

 THE BELOW HYDRAULIC CONDUCTIVITY VALUE WAS CALCULATED
 USING THE BOUWER AND RICE SLUG TEST METHOD.

SOURCE= "THE BOUWER AND RICE SLUG TEST-AN UPDATE"
 GROUND WATER, VOL 27, NO. 3, MAY-JUNE 1989.

 RADIUS OF CASING USED IN CALCULATIONS HAS BEEN
 CORRECTED FOR THE THICKNESS OF GRAVEL OR SAND
 PACK DUE TO WATER LEVEL CHANGES IN THE SCREEN OR
 OPEN INTERVAL OF WELL.

Rc (ft)	Rw (ft)	Le (ft)	Lw (ft)	H (ft)
.2297	.3333	16.1000	16.1000	95.0000

Le/Rw = 48.3000000

A= 3.0530930

B= 4.990199E-001

C= 2.6454010

SANDPACK POROSITY= 3.000000E-001

t (min)= 1.000000E-001

1/t= 10.0000000

Yo= (ft) 8.300000E-001

Yt= (ft) 2.300000E-001

1/t ln(Yo/Yt)= 12.8334600

ln[(H-Lw)/Rw]= 5.4667940

ln(Re/Rw)= 2.4790210

K (ft/day) = 75.0899400

T OF THE SATURATED SCREEN INTERVAL
 (ft²/day)= 1208.9480000

9313018.046

APPENDIX C

TEST DATA AND ANALYSIS FOR WELL 299-E25-41

9313018.0400

APPENDIX C

TEST DATA AND ANALYSIS FOR WELL 299-E25-41

This appendix contains the as-built diagram for the well construction, Slug Test Record Form, Aquifer Test Data Sheets, Equipment Record Forms, Electronic Data Control Forms, and accompanying data logs and plots for well 299-E25-41.

93/30/18.14

93/30/18.14



AS-BUILT DIAGRAM

Well Number 299-E25-41

Geologist M. Lubrecht

Page 1 of 4

Reviewed by W.C. Smith

Date 12-7-89

Construction Data		Depth in Feet	Geologic/Hydrologic Data	
Description	Diagram		Diagram Litho.	Lithologic Description
10" CARBON STEEL CASING		5		SAND
0-136' 1 1/2" (TEMPORARY)		10		SAND
		15		Sl. Muddy SAND
		20		Sandy GRAVEL
280' 3" of 8" CARBON		25		Sandy GRAVEL
STEEL CASING		30		SAND
		35		SAND
		40		Muddy Sandy GRAVEL
257.000 4" STAINLESS		45		Sl. Gravelly SAND
STEEL CASING		50		SAND
		55		SAND
		60		Sl. Gravelly SAND
		65		Sl. Gravelly SAND
		70		Gravelly SAND
		75		Gravelly SAND
		80		Sl. Gravelly SAND
		85		Gravelly SAND
		90		Gravelly SAND
		95		Gravelly SAND
		100		SAND
		105		SAND
		110		SAND
		115		SAND
		120		Interbedded SAND & muddy S. SAND
		125		Interbedded SAND & m. S. SAND
		130		SAND



AS-BUILT DIAGRAM

Well Number 299 - E25 - 41 Geologist M. LUBBECHT Page 2 of 3

Reviewed by W. C. McShane Date 12-7-89

Construction Data		Depth in Feet	Geologic/Hydrologic Data	
Description	Diagram		Diagram Litho.	Lithologic Description
139' 7 1/2" OF 10" CARBON STEEL CASING		135		SAND
		140		"
		145		"
280' 3" OF 8" CARBON STEEL CASING		150		"
		155		"
		160		"
		165		"
257.43' OF 4" STAINLESS STEEL CASING		170		"
		175		"
		180		slightly Gravelly SAND
		185		"
		190		SAND
		195		"
		200		SANDY GRAVEL
		205		SANDY GRAVEL
		210		GRAVELLY SAND
		215		"
		220		MUDDY SANDY GRAVEL
		225		"
		230		GRAVELLY SAND
		235		"
		240		"
		245		"
		250		"
		255		SANDY MUD
		260		"

Well Number 299-E25-41 Geologist M. LUBRICH Page 3 of 3

Reviewed by V.L. Mathan Date 12-7-89

A-1800-186 (3/87)

Aquifer Test Data

WHC-SD-EN-TI-147, Rev. 0

page 1 of 1
 Data for Well 2-EL-5
 Pumping Well 3-EL-5
 Observation Wells -

Location 200 East A Tank Forms
 Type of Aquifer Test Slug Injection/withdrawal

How Q Measured -

How W.L.'s Measured Steel tape L300-14, transducer (in situ)

Depth of Pump/Airpipe -

Rad. Dist. to From Pumping Well 2"

Pump On: date - time -

Meas. Point for W.L.'s top of 4" casing

Pump Off: date - time -

Elevation of Meas. Point -

Duration of Aquifer Test -

Top of 4" casing is 5.2' above ground surface

Time				Water Level Data					Discharge		Recorded By	Comments	
t = _____ at t' = 0				Static Water Level <u>267.41</u> from TOC									
Day	Clock Time	t	t'	t/t'	Reading	Conversions or Corrections	Water Level	s or s'		Reading	Q		
9/29	1433				267.41							DRN	
	1442				14.11								Transducer reading
					Drop slug at Test # 4								
	1445				Bottom of slug set at 265' from TOC								
	1446				Ref = 0 @ 14.03'								
	1450				Slug is dropped (couple seconds late)								
	1501				Test # 4 stopped								
					Test # 5 pull slug								DRN
	1502				14.02 → Reference set to 0								
	1505				slug pulled								
	1515				test stopped								
					Serial # transducer → 262361								
					Serial # Data Logger → 1KB-701								
10/2					Reset Slug into position (1 foot above static)								XD Cable got caught on slug
10/2					Ref set to 0 @ 13.86'								DRN
	0326				Drop Slug at 10.1								
	0336				Stop logging data								
					Set Ref = 0 @ 13.37'								DRN
	0840				Withdraw Slug (Pulled it out fast)								right out long cycle
	0948				Stop logging data								DRN
					D/B is 279.0' from top of casing								

Location 200 East A-Tank Farm Date of Test 9-29-89, 10-2-89
 Well Number 299-E25-41 Procedure Number PNL-MA-567
AT-6, Rev 0
 Type of Test(s) Slug Injection / Withdrawal
 Personnel Conducting Test Darrell Newcomer, Bill Cronin

WELL CONFIGURATION

Well Depth 273.8' Borehole Diameter 8"
 Well Casing Inside Diameter 4" Well Screen Inside Diameter 4"
 Length of Screened Interval 13.8' (below water) Depth of Screen 255'-276'
 Comments Cable connecting transducer to data logger got pinched by slug before conducting slug tests on 10/2/89. Well is undeveloped

SLUG INFORMATION

Slug Construction Materials Carbon steel
 Length of Slug 8.05' Diameter of Slug 0.24'
 Comments _____
 Volume of Attachments (if applicable) _____

MEASUREMENT EQUIPMENT INFORMATION

	Make	Model	Serial Number
Electric Tape			
Steel Tape	Lufkin	Super Hi-way Nubian	L300-14
Data logger	In Situ	SE1000 B	1KB-701
Transducer	Druck	PTX-161D	262361
Other			

Darrell Newcomer 10/2/89

Equipment Record Form for the Installation and Removal of Data Loggers and Pressure Transducers

Initial Check: <i>OK</i>		
Purpose of Installation: <i>To monitor slug injection / withdrawal test responses</i>		
Monitored Hydrologic Unit or Water Body: <i>Uppermost Unconfined Aquifer (Hanford formation)</i>		
Date/Time of Installation: <i>9/29/89 1430 hrs.</i>	Procedure Followed: <i>PNL-MA-567 WL-4, Rev D</i>	
Data Logger Make/Model: <i>In Situ / SE1000 B</i>		
Serial No.: <i>1KB-701</i>	Number of Channels Used: <i>1</i>	
Pressure Transducer Make/Model: <i>Druck / PTX-161D</i>	Full Scale Range: <i>10 psi</i>	Well No.: <i>299-E25-41</i>
	Serial No.: <i>262361</i>	Depth: <i>~276' below ground surface</i>
Pressure Transducer Make/Model:	Full Scale Range:	Well No.:
	Serial No.:	Depth:
Description of Data Logger Installation and Well Head Configuration: 		
Comments: <i>Slug was positioned into place above the water DAN before placing the transducer down the well. Slug had to be repositioned ^{transducer} during tests on 10/2/89 because slug pinched cable. Transducer and slug had to be taken out of well and reset.</i>		
Equipment Installed By <i>D. R. Newcomer, Bill Cronin</i>		
Date/Time of Equipment Removal: <i>10/2/89 0900 hrs.</i>		
Decontamination Procedure (if required):		
Equipment Removed By <i>D. R. Newcomer, Bill Cronin</i>		

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 9/29/89, 14:50DATE AND END TIME OF DATA ACQUISITION 9/29/89, 15:00WELL NUMBER E25-41TYPE OF TEST OR DATA Slug testTYPE AND IDENTIFICATION NUMBER OF DATA LOGGER On Site
Hermit 1000B, Serial # 1KB-701TEST NUMBER 4CHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED ftNUMBER OF PAGES ATTACHED 2COMMENTS: Test 4 = Submerging slug.

_____DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

William E. Cronin, Hydrologist 10/2/89
Name, title Date

Well: 299-E25-41
 Test Date: September 29, 1989
 Start Time: 14:50

SE1000B
 Environmental Logger
 09/29 16:33

Unit# 00701 Test# 4

INPUT 1: Level (F)

Reference 0.00
 Scale factor 9.99
 Offset 0.00

Elapsed Time, Value,
 min ft

0.0000	0.94
0.0033	0.83
0.0066	0.74
0.0099	0.67
0.0133	0.61
0.0166	0.56
0.0200	0.51
0.0233	0.46
0.0266	0.42
0.0300	0.39
0.0333	0.36
0.0500	0.24
0.0666	0.17
0.0833	0.12
0.1000	0.09
0.1166	0.06
0.1333	0.05
0.1500	0.04
0.1666	0.03
0.1833	0.02
0.2000	0.02
0.2166	0.01
0.2333	0.01
0.2500	0.01
0.2666	0.01
0.2833	0.01
0.3000	0.00
0.3166	0.00
0.3333	0.00
0.4167	0.00
0.5000	0.00
0.5833	0.00

0.6667	0.00
0.7500	0.00
0.8333	0.00
0.9167	0.00
1.0000	0.00
1.0833	0.00
1.1667	0.00
1.2500	0.00
1.3333	- 0.00
1.4166	- 0.00
1.5000	- 0.00
1.5833	- 0.00
1.6667	- 0.00
1.7500	- 0.00
1.8333	- 0.00
1.9167	- 0.00
2.0000	- 0.00
2.5000	- 0.00
3.0000	- 0.00
3.5000	- 0.00
4.0000	- 0.00
4.5000	- 0.00
5.0000	- 0.00
5.5000	- 0.01
6.0000	- 0.01
6.5000	0.00
7.0000	- 0.01
7.5000	- 0.01
8.0000	- 0.01
8.5000	- 0.00
9.0000	- 0.01
9.5000	- 0.01
10.0000	- 0.01

END

9313018.057

9313018.057

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 9/29/89 ~~16:35~~ ^{15:05}DATE AND END TIME OF DATA ACQUISITION 9/29/89 16:45 ^{15:10}WELL NUMBER E25-41TYPE OF TEST OR DATA slug testTYPE AND IDENTIFICATION NUMBER OF DATA LOGGER In situ
Hermet 1000B, serial # 1KB-701TEST NUMBER 5CHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED ftNUMBER OF PAGES ATTACHED 2

COMMENTS:

Test 5 = Lifting slug

DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

William E Cronin, Hydrologist

Name, title

10/2/89

Date

Well: 299-E25-41
Test Date: September 29, 1989
Start Time: 15:05

SE1000B
Environmental Logger
09/29 16:35

Unit# 00701 Test# 5

INPUT 1: Level (F)

Reference 0.00
Scale factor 9.99
Offset 0.00

Elapsed Time, Value,
min ft

0.0000	- 4.32
0.0033	- 4.49
0.0066	- 4.34
0.0099	- 4.46
0.0133	- 4.45
0.0166	- 4.38
0.0200	- 4.29
0.0233	- 4.15
0.0266	- 3.94
0.0300	- 3.84
0.0333	- 3.81
0.0500	- 3.63
0.0666	- 3.48
0.0833	- 3.38
0.1000	- 3.29
0.1166	- 3.22
0.1333	- 3.15
0.1500	- 3.10
0.1666	- 3.06
0.1833	- 3.02
0.2000	- 2.98
0.2166	- 2.95
0.2333	- 2.86
0.2500	- 2.83
0.2666	- 2.80
0.2833	- 2.78
0.3000	- 2.76
0.3166	- 2.74
0.3333	- 2.72
0.4167	- 2.65
0.5000	- 2.60

0.5833	- 2.56
0.6667	- 2.55
0.7500	- 2.53
0.8333	- 2.52
0.9167	- 2.51
1.0000	- 2.49
1.0833	- 2.48
1.1667	- 2.48
1.2500	- 2.47
1.3333	- 2.47
1.4166	- 2.46
1.5000	- 2.45
1.5833	- 2.44
1.6667	- 2.43
1.7500	- 2.42
1.8333	- 2.41
1.9167	- 2.40
2.0000	- 2.39
2.5000	- 2.32
3.0000	- 2.23
3.5000	- 2.19
4.0000	- 2.17
4.5000	- 2.14
5.0000	- 2.02
5.5000	- 1.96
6.0000	- 0.03
6.5000	0.00
7.0000	0.00
7.5000	0.00
8.0000	- 0.00
8.5000	- 0.00
9.0000	- 0.00
9.5000	- 0.00
10.0000	- 0.00

END

9313018.05

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 10/2/89 0826 hrsDATE AND END TIME OF DATA ACQUISITION 10/2/89 0836 hrsWELL NUMBER 299-E25-41TYPE OF TEST OR DATA Slug Injection TestTYPE AND IDENTIFICATION NUMBER OF DATA LOGGER In SituHermit SE1000B Serial # 1KB-701TEST NUMBER 6CHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED feetNUMBER OF PAGES ATTACHED 3

COMMENTS:

Test 6 = Submerge Slug

DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

Darrell Newcomer Scientist
Name, title10/3/89
Date

4050-9106166

4050-9106166

Well: 299-E25-41
 Test Date: October 2, 1989
 Start Time: 08:26

SE1000B
 Environmental Logger
 10/02 14:42

Unit# 00701 Test# 6

INPUT 1: Level (F)

Reference 0.00
 Scale factor 9.99
 Offset 0.00

Elapsed Time, Value,
 min ft

0.0000	0.81
0.0033	0.81
0.0066	0.81
0.0099	0.77
0.0133	0.72
0.0166	0.94
0.0200	0.88
0.0233	0.84
0.0266	1.01
0.0300	1.21
0.0333	1.09
0.0500	1.21
0.0666	1.42
0.0833	1.35
0.1000	0.61
0.1166	0.60
0.1333	0.46
0.1500	0.36
0.1666	0.28
0.1833	0.23
0.2000	0.19
0.2166	0.16
0.2333	0.14
0.2500	0.12
0.2666	0.11
0.2833	0.10
0.3000	0.09
0.3166	0.08
0.3333	0.08
0.4167	0.06
0.5000	0.05

0.5833	0.05
0.6667	0.05
0.7500	0.04
0.8333	0.04
0.9167	0.04
1.0000	0.03
1.0833	0.03
1.1667	0.03
1.2500	0.02
1.3333	0.02
1.4166	0.02
1.5000	0.02
1.5833	0.02
1.6667	0.02
1.7500	0.01
1.8333	0.01
1.9167	0.01
2.0000	0.01
2.5000	0.01
3.0000	0.01
3.5000	0.01
4.0000	0.01
4.5000	0.01
5.0000	0.01
5.5000	0.00
6.0000	0.00
6.5000	0.00
7.0000	0.00
7.5000	0.00
8.0000	0.00
8.5000	0.00
9.0000	0.01
9.5000	0.00
10.0000	0.00

END

9313018.050

9313018.050

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 10/2/89, 0840 hrs.DATE AND END TIME OF DATA ACQUISITION 10/2/89, 0848 hrs.WELL NUMBER 299-E25-41TYPE OF TEST OR DATA Slug withdrawal testTYPE AND IDENTIFICATION NUMBER OF DATA LOGGER In SituHermet SE1000B Serial # JKB-701TEST NUMBER 7CHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED feetNUMBER OF PAGES ATTACHED 2

COMMENTS:

Test 7 = Lifting slug

DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

Barrel Newman, Scientist
Name, title10/3/89
Date

9313018.0506

Well: 299-E25-41
Test Date: October 2, 1989
Start Time: 08:40

SE1000B
Environmental Logger
10/02 14:46

Unit# 00701 Test# 7

INPUT 1: Level (F)

Reference 0.00
Scale factor 9.99
Offset 0.00

Elapsed Time, min	Value, ft
0.0000	3.27
0.0033	3.27
0.0066	3.24
0.0099	3.21
0.0133	3.06
0.0166	3.02
0.0200	2.95
0.0233	2.93
0.0266	2.92
0.0300	2.84
0.0333	2.81
0.0500	2.63
0.0666	2.47
0.0833	2.32
0.1000	2.19
0.1166	2.06
0.1333	1.93
0.1500	1.82
0.1666	1.72
0.1833	1.62
0.2000	1.52
0.2166	1.43
0.2333	1.34
0.2500	1.27
0.2666	1.19
0.2833	1.12
0.3000	1.06
0.3166	1.00
0.3333	0.95
0.4167	0.72
0.5000	0.56
0.5833	0.45


0.6667	0.36
0.7500	0.31
0.8333	0.26
0.9167	0.22
1.0000	0.19
1.0833	0.16
1.1667	0.14
1.2500	0.13
1.3333	0.11
1.4166	0.10
1.5000	0.09
1.5833	0.08
1.6667	0.07
1.7500	0.06
1.8333	0.06
1.9167	0.05
2.0000	0.05
2.5000	0.02
3.0000	0.01
3.5000	0.00
4.0000	0.00
4.5000	0.00
5.0000	0.00
5.5000	0.00
6.0000	0.00
6.5000	0.00
7.0000	0.00
7.5000	0.00

END


9313018.155

9313018.155

C.16



C.17



WELL 299-E25-41, SLUG WITHDRAWAL TEST #5, Yt SHIFT =1.96 ft

THE BELOW HYDRAULIC CONDUCTIVITY VALUE WAS CALCULATED
USING THE BOUWER AND RICE SLUG TEST METHOD.

SOURCE= "THE BOUWER AND RICE SLUG TEST-AN UPDATE"
GROUND WATER, VOL 27, NO. 3, MAY-JUNE 1989.

RADIUS OF CASING USED IN CALCULATIONS HAS BEEN
CORRECTED FOR THE THICKNESS OF GRAVEL OR SAND
PACK DUE TO WATER LEVEL CHANGES IN THE SCREEN OR
OPEN INTERVAL OF WELL.

Rc (ft)	Rw (ft)	Le (ft)	Lw (ft)	H (ft)
---------	---------	---------	---------	--------

.2297	.3333	13.8000	13.8000	95.0000
-------	-------	---------	---------	---------

Le/Rw = 41.4000000

A= 2.8792960

B= 4.568365E-001

C= 2.4968560

SANDPACK POROSITY= 3.000000E-001

t (min)= 2.000000E-001

1/t= 5.0000000

Yo= (ft) 1.8600000

Yt= (ft) 9.600000E-001

1/t ln(Yo/Yt)= 3.3069920

ln[(H-Lw)/Rw]= 5.4955270

ln(Re/Rw)= 2.3494690

K (ft/day) = 21.3947600


T OF THE SATURATED SCREEN INTERVAL

(ft²/day)= 295.2477000

0150 0106136

9313018.05''


C.19



MHC-SD-EN-TI-147, Rev. 0

9313018.05''

C.20



WELL 299-E25-41, SLUG WITHDRAWAL TEST #7

 THE BELOW HYDRAULIC CONDUCTIVITY VALUE WAS CALCULATED
 USING THE BOUWER AND RICE SLUG TEST METHOD.

SOURCE= "THE BOUWER AND RICE SLUG TEST-AN UPDATE"
 GROUND WATER, VOL 27, NO. 3, MAY-JUNE 1989.


 RADIUS OF CASING USED IN CALCULATIONS HAS BEEN
 CORRECTED FOR THE THICKNESS OF GRAVEL OR SAND
 PACK DUE TO WATER LEVEL CHANGES IN THE SCREEN OR
 OPEN INTERVAL OF WELL.

Rc (ft)	Rw (ft)	Le (ft)	Lw (ft)	H (ft)
.2297	.3333	13.8000	13.8000	95.0000

Le/Rw = 41.4000000
 A= 2.8792960
 B= 4.568365E-001
 C= 2.4968560
 SANDPACK POROSITY= 3.000000E-001
 t (min)= 2.500000E-001
 1/t= 4.0000000
 Yo= (ft) 3.1800000
 Yt= (ft) 1.2700000
 1/t ln(Yo/Yt)= 3.6714570
 ln[(H-Lw)/Rw]= 5.4955270
 ln(Re/Rw)= 2.3494690


K (ft/day) = 23.7527200

T OF THE SATURATED SCREEN INTERVAL
 (ft²/day)= 327.7876000



C.22

C.23



WELL 299-E25-41, SLUG INJECTION TEST #4

 THE BELOW HYDRAULIC CONDUCTIVITY VALUE WAS CALCULATED
 USING THE BOUWER AND RICE SLUG TEST METHOD.

SOURCE= "THE BOUWER AND RICE SLUG TEST-AN UPDATE"
 GROUND WATER, VOL 27, NO. 3, MAY-JUNE 1989.

 RADIUS OF CASING USED IN CALCULATIONS HAS BEEN
 CORRECTED FOR THE THICKNESS OF GRAVEL OR SAND
 PACK DUE TO WATER LEVEL CHANGES IN THE SCREEN OR
 OPEN INTERVAL OF WELL.

Rc (ft)	Rw (ft)	Le (ft)	Lw (ft)	H (ft)
.2297	.3333	13.8000	13.8000	95.0000


Le/Rw = 41.4000000
 A= 2.8792960
 B= 4.568365E-001
 C= 2.4968560
 SANDPACK POROSITY= 3.000000E-001
 t (min)= 2.500000E-002
 1/t= 40.0000000
 Yo= (ft) 8.900000E-001
 Yt= (ft) 4.400000E-001
 1/t ln(Yo/Yt)= 28.1778700
 ln[(H-Lw)/Rw]= 5.4955270
 ln(Re/Rw)= 2.3494690

 K (ft/day) = 182.2982000

T OF THE SATURATED SCREEN INTERVAL
 (ft2/day)= 2515.7150000

9313018.0516


9313018.0517



C.25

9313018.0517

00000 WELL 299-E25-41, SLUG INJECTION TEST #6



WELL 299-E25-41, SLUG INJECTION TEST #6

 THE BELOW HYDRAULIC CONDUCTIVITY VALUE WAS CALCULATED
 USING THE BOUWER AND RICE SLUG TEST METHOD.

SOURCE= "THE BOUWER AND RICE SLUG TEST-AN UPDATE"
 GROUND WATER, VOL 27, NO. 3, MAY-JUNE 1989.

 RADIUS OF CASING USED IN CALCULATIONS HAS BEEN
 CORRECTED FOR THE THICKNESS OF GRAVEL OR SAND
 PACK DUE TO WATER LEVEL CHANGES IN THE SCREEN OR
 OPEN INTERVAL OF WELL.

Rc (ft)	Rw (ft)	Le (ft)	Lw (ft)	H (ft)
.2297	.3333	13.8000	13.8000	95.0000

Le/Rw = 41.4000000
 A= 2.8792960
 B= 4.568365E-001
 C= 2.4968560
 SANDPACK POROSITY= 3.000000E-001
 t (min)= 8.000000E-002
 1/t= 12.5000000
 Yo= (ft) 1.0200000
 Yt= (ft) 3.700000E-001
 1/t ln(Yo/Yt)= 12.6756900
 ln[(H-Lw)/Rw]= 5.4955270
 ln(Re/Rw)= 2.3494690

 K (ft/day) = 82.0060400

T OF THE SATURATED SCREEN INTERVAL
 (ft²/day)= 1131.6830000

9313018.051

APPENDIX D

TEST DATA AND ANALYSIS FOR WELL 299-E27-12

9313018.0522

APPENDIX D

TEST DATA AND ANALYSIS FOR WELL 299-E27-12

This appendix contains the as-built diagram for the well construction, Slug Test Record Form, Aquifer Test Data Sheets, Equipment Record Forms, Electronic Data Control Forms, and accompanying data logs and plots for well 299-E27-12.

9313018.05

9313018.05



Pacific Northwest Laboratories

AS-BUILT DIAGRAM

Well Number 299-E27-12 Geologist R Miller Page 1 of 3Reviewed by W. McElhan Date 12-7-89

Construction Data		Depth in Feet	Geologic/Hydrologic Data	
Description	Diagram		Diagram Litho.	Lithologic Description
temporary 10" Ø carbon steel casing w/ drive shoe from +1.0' to -127' 2 1/2"		5		Gravelly SAND
		10		"
		15		Gravelly SAND + mud.
		20		Gravelly SAND
		25		"
		30		"
		35		Sand
		40		"
		45		"
		50		"
		55		"
		60		"
		65		"
		70		"
		75		Gravelly SAND
		80		"
		85		"
		90		"
		95		"
		100		"
		105		"
		110		"
		115		"
		120		SAND
		125		Gravelly SAND (cobbles)
		130		SAND (capped)

PWL-MA 567, DO-1, Rev 0

A-1800-186 (3/87)

9313018.0522



AS-BUILT DIAGRAM

Well Number 299-E27-12 Geologist R.M.L. Page 2 of 3Reviewed by J.L. McElhaney Date 12-7-89

Construction Data		Depth in Feet	Geologic/Hydrologic Data	
Description	Diagram		Diagram Litho.	Lithologic Description
temporary 8" carbon steel casing w/ drive shoe from +3'6" to 268'7" (272'1")		135		SAND (sl. cemented)
		140		sl. gravelly SAND
		145		"
		150		"
		155		"
		160		SANDY GRAVEL
		165		sl. gravelly SAND
250.32' of 4" DIA. STAINLESS STEEL CASING		170		SAND
		175		"
		180		"
		185		"
		190		"
		195		"
		200		"
		205		"
		210		"
		215		"
		220		"
		225		"
		230		Gravelly Sandy MUD @ 225-10" thick Muddy Sandy GRAVEL
		235		Sandy GRAVEL
		240		"
		245		"
21.03' of 4" DIA CHANNEL PACK SCREEN (10 SLOT)		250		Muddy Sandy GRAVEL
		255		" (wet)
		260		Sandy GRAVEL

FWL-MA567, C-0-1, Rev 0

A-1800-186 (3/87)

9313018.1522

Well Number 299-E27-12 Geologist R. Miller Page 3 of 3

Reviewed by W.E. McEwan Date 12-7-89

[illegible]

4250-8103136

Observation Wells

stand - up. 3.3 ft. to top of ped.

D.5

9310313.50

Equipment Record Form for the Installation and Removal of Data Loggers and Pressure Transducers

Initial Check: <u>JV LAR</u>		
Purpose of Installation: <u>monitored WL changes during slug test</u>		
Monitored Hydrologic Unit or Water Body: <u>sat. screened int.</u>		
Date/Time of Installation: <u>10/19/89 1330</u>	Procedure Followed: <u>WL-4</u>	
Data Logger Make/Model: <u>Germit SE1000B</u>		
Serial No.: <u>1KB-701</u>	Number of Channels Used: <u>1</u>	
Pressure Transducer Make/Model: <u>In situ PTx 161D</u>	Full Scale Range: <u>10psi</u>	Well No.: <u>299-E2712</u>
	Serial No.: <u>259198</u>	Depth: <u>14.9 below rock</u>
Pressure Transducer Make/Model:	Full Scale Range:	Well No.:
	Serial No.:	Depth:
Description of Data Logger Installation and Well Head Configuration: 		
Comments:		
Equipment Installed By <u>J.V. Borshee</u>		
Date/Time of Equipment Removal: <u>D. Logger removed 10/20 21500</u>		
Decontamination Procedure (if required):		
Equipment Removed By <u>JVBorshee</u>		

Location C-TAUX'S Date of Test 10/19/89
 Well Number 299-F27-12 Procedure Number AT-6
 Type of Test(s) Slug
 Personnel Conducting Test Borgese

WELL CONFIGURATION

Well Depth 271.5 TOC Borehole Diameter 8"
 Well Casing Inside Diameter 4" Well Screen Inside Diameter 4"
 Length of Screened Interval 10" 20" Depth of Screen 251-271
 Comments Well is undeveloped

SLUG INFORMATION

Slug Construction Materials carbon steel
 Length of Slug 6' Diameter of Slug 2.25"
 Comments _____
 Volume of Attachments (if applicable) _____

MEASUREMENT EQUIPMENT INFORMATION

	Make	Model	Serial Number
Electric Tape			
Steel Tape	see	aquifer	test form
Data logger	and	equipment	used
Transducer	form.		
Other			

JUB 10/20/89

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 10/19/89 1425
DATE AND END TIME OF DATA ACQUISITION " 1436
WELL NUMBER 299-E27-12
TYPE OF TEST OR DATA slug injection
TYPE AND IDENTIFICATION NUMBER OF DATA LOGGER Hermit SE1000B 1KB-701
TEST NUMBER X 4
CHANNEL OR INPUT NUMBER 1
UNITS OF VALUES RECORDED ft from ref. level
NUMBER OF PAGES ATTACHED 2
COMMENTS: Started DL late

DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

J. Bayl Scientist 10/20/89
Name, title Date

9313018.0528

Well: 299-E27-12
Test Date: October 19, 1989
Start time: 14:25

SE1000B
Environmental Logger
10/19 16:52

Unit# 00701 Test# 4

INPUT 1: Level (F)

Reference 0.00
Scale factor 9.99
Offset - 0.01

Elapsed Time, Value,
min ft

0.0000 0.30
0.0033 - 0.50
0.0066 - 0.14
0.0099 0.18
0.0133 - 0.13
0.0166 0.05
0.0200 0.00
0.0233 0.02
0.0266 0.02
0.0300 0.02
0.0333 0.03
0.0500 - 0.00
0.0666 0.00
0.0833 0.00
0.1000 0.00
0.1166 0.00
0.1333 0.00
0.1500 0.00
0.1666 0.00
0.1833 0.00
0.2000 0.00
0.2166 0.00
0.2333 0.00
0.2500 0.00
0.2666 0.00
0.2833 0.00
0.3000 0.00
0.3166 0.00
0.3333 0.00
0.4167 0.00
0.5000 0.00

0.5833 0.00
0.6667 0.00
0.7500 0.00
0.8333 0.00
0.9167 0.00
1.0000 0.00
1.0833 0.00
1.1667 0.00
1.2500 0.00
1.3333 0.00
1.4166 0.00
1.5000 0.00
1.5833 0.00
1.6667 0.00
1.7500 0.00
1.8333 0.00
1.9167 0.00
2.0000 0.00
2.5000 0.00
3.0000 0.00
3.5000 0.00
4.0000 0.00
4.5000 0.00
5.0000 0.00
5.5000 0.00
6.0000 0.00
6.5000 0.00
7.0000 0.00
7.5000 0.00
8.0000 0.00
8.5000 0.00
9.0000 0.00
9.5000 0.00
10.0000 0.00

END

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 10/19/89 1439
DATE AND END TIME OF DATA ACQUISITION " 1449
WELL NUMBER 299-E27-12
TYPE OF TEST OR DATA Slug WD
TYPE AND IDENTIFICATION NUMBER OF DATA LOGGER Hermit SE1000B 1KB-701
TEST NUMBER 5
CHANNEL OR INPUT NUMBER 1
UNITS OF VALUES RECORDED ft from ref. level
NUMBER OF PAGES ATTACHED 2
COMMENTS: Started DL late

DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

J. V. Eng Lee Scientist 10/20/89
Name, title Date

Well: 299-E27-12
Test Date: October 19, 1989
Start Time: 14:39

SE1000B
Environmental Logger
10/19 16:53

Unit# 00701 Test# 5

INPUT 1: Level (F)

Reference 0.00
Scale factor 9.99
Offset - 0.01

Elapsed Time, Value,
min ft

0.0000	- 0.15
0.0033	- 0.31
0.0066	- 0.34
0.0099	- 0.32
0.0133	- 0.26
0.0166	- 0.17
0.0200	- 0.09
0.0233	- 0.02
0.0266	0.01
0.0300	0.03
0.0333	0.03
0.0500	0.00
0.0666	- 0.00
0.0833	- 0.00
0.1000	- 0.00
0.1166	- 0.00
0.1333	- 0.00
0.1500	- 0.00
0.1666	- 0.00
0.1833	- 0.00
0.2000	- 0.00
0.2166	- 0.00
0.2333	- 0.00
0.2500	- 0.00
0.2666	- 0.00
0.2833	- 0.00
0.3000	- 0.00
0.3166	- 0.00
0.3333	- 0.00
0.4167	- 0.00
0.5000	- 0.00

0.5833	- 0.00
0.6667	- 0.00
0.7500	- 0.00
0.8333	- 0.00
0.9167	- 0.00
1.0000	- 0.00
1.0833	- 0.00
1.1667	- 0.00
1.2500	- 0.00
1.3333	- 0.00
1.4166	- 0.00
1.5000	- 0.00
1.5833	- 0.00
1.6667	- 0.00
1.7500	- 0.00
1.8333	- 0.00
1.9167	- 0.00
2.0000	- 0.00
2.5000	- 0.00
3.0000	- 0.00
3.5000	- 0.00
4.0000	- 0.00
4.5000	- 0.00
5.0000	- 0.00
5.5000	- 0.00
6.0000	- 0.00
6.5000	- 0.00
7.0000	- 0.00
7.5000	- 0.00
8.0000	- 0.00
8.5000	- 0.00
9.0000	- 0.00
9.5000	- 0.00
10.0000	- 0.00

END

9313018.052

9313018.052

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 10/14/89 1453
 DATE AND END TIME OF DATA ACQUISITION " 1503
 WELL NUMBER 299-EJ7-12
 TYPE OF TEST OR DATA slug injection
 TYPE AND IDENTIFICATION NUMBER OF DATA LOGGER Sumit SE1000B 1KB-701
 TEST NUMBER 6
 CHANNEL OR INPUT NUMBER 1
 UNITS OF VALUES RECORDED # from ref. level
 NUMBER OF PAGES ATTACHED 2

COMMENTS:

DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

J.V. Boyle Sumit 10/20/89
 Name, title Date

9313018.0532

Well: 299-E27-12
 Test Date: October 19, 1989
 Start Time: 14:53

SE1000B
 Environmental Logger
 10/19 16:55

Unit# 00701 Test# 6

INPUT 1: Level (F)

Reference 0.00
 Scale factor 9.99
 Offset 0.01

Elapsed Time, Value,
 min ft

 0.0000 0.55
 0.0033 0.57
 0.0066 0.56
 0.0099 0.51
 0.0133 0.51
 0.0166 0.52
 0.0200 0.21
 0.0233 0.35
 0.0266 0.54
 0.0300 0.06
 0.0333 0.23
 0.0500 0.03
 0.0666 0.01
 0.0833 0.00
 0.1000 0.00
 0.1166 0.00
 0.1333 0.00
 0.1500 0.00
 0.1666 0.00
 0.1833 0.00
 0.2000 0.00
 0.2166 0.00
 0.2333 0.00
 0.2500 0.00
 0.2666 0.00
 0.2833 0.00
 0.3000 0.00
 0.3166 0.00
 0.3333 0.00
 0.4167 0.00
 0.5000 0.00

0.5833 0.00
 0.6667 0.00
 0.7500 0.00
 0.8333 0.00
 0.9167 0.00
 1.0000 0.00
 1.0833 0.00
 1.1667 0.00
 1.2500 0.00
 1.3333 0.00
 1.4166 0.00
 1.5000 0.00
 1.5833 0.00
 1.6667 0.00
 1.7500 0.00
 1.8333 0.00
 1.9167 0.00
 2.0000 0.00
 2.5000 0.00
 3.0000 0.00
 3.5000 0.00
 4.0000 0.00
 4.5000 0.00
 5.0000 0.00
 5.5000 0.00
 6.0000 0.00
 6.5000 0.00
 7.0000 0.00
 7.5000 0.00
 8.0000 0.00
 8.5000 0.00
 9.0000 0.00
 9.5000 0.00
 10.0000 0.00

END

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 10/19/89 1506
DATE AND END TIME OF DATA ACQUISITION 10/19/89 1516
WELL NUMBER 299-E27-12
TYPE OF TEST OR DATA Slug W/D
TYPE AND IDENTIFICATION NUMBER OF DATA LOGGER Hermit SE1000B 1KB-70'
TEST NUMBER 7
CHANNEL OR INPUT NUMBER 1
UNITS OF VALUES RECORDED ft from ref. level
NUMBER OF PAGES ATTACHED 2
COMMENTS: started D Logon later

DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

Jane V Byles Scientist 10/20/89
Name, title Date

Well: 299-E27-12
 Test Date: October 19, 1989
 Start Time: 15:06

SE1000B
 Environmental Logger
 10/19 16:57

Unit# 00701 Test# 7

INPUT 1: Level (F)

Reference 0.00
 Scale factor 9.99
 Offset - 0.01

Elapsed Time, Value,
 min ft

0.0000	- 0.24
0.0033	- 0.31
0.0066	- 0.28
0.0099	- 0.20
0.0133	- 0.13
0.0166	- 0.06
0.0200	0.00
0.0233	0.03
0.0266	0.05
0.0300	0.06
0.0333	0.03
0.0500	0.00
0.0666	0.00
0.0833	0.01
0.1000	0.00
0.1166	0.00
0.1333	0.00
0.1500	0.00
0.1666	0.00
0.1833	0.00
0.2000	0.00
0.2166	0.00
0.2333	0.00
0.2500	0.00
0.2666	0.00
0.2833	0.00
0.3000	0.00
0.3166	0.00
0.3333	0.00
0.4167	0.00
0.5000	0.00

0.5833	0.00
0.6667	0.00
0.7500	0.00
0.8333	0.00
0.9167	0.00
1.0000	0.00
1.0833	0.00
1.1667	0.00
1.2500	0.00
1.3333	0.00
1.4166	0.00
1.5000	0.00
1.5833	0.00
1.6667	0.00
1.7500	0.00
1.8333	0.00
1.9167	0.00
2.0000	0.00
2.5000	0.00
3.0000	0.00
3.5000	0.00
4.0000	0.00
4.5000	0.00
5.0000	0.00
5.5000	0.00
6.0000	0.00
6.5000	0.00
7.0000	0.00
7.5000	0.00
8.0000	0.00
8.5000	0.00
9.0000	0.00
9.5000	0.00
10.0000	0.00

END

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 10/20/89 0743 hrs
 DATE AND END TIME OF DATA ACQUISITION 10/20/89 0753 hrs
 WELL NUMBER 29-E27-12
 TYPE OF TEST OR DATA Slug w/d
 TYPE AND IDENTIFICATION NUMBER OF DATA LOGGER In Situ
Hermit SE1000 B, S/N 1KB-701
 TEST NUMBER 0
 CHANNEL OR INPUT NUMBER 1
 UNITS OF VALUES RECORDED ft
 NUMBER OF PAGES ATTACHED 2
 COMMENTS:
Test 0 = Withdraw Slug

DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

Darrell Newcomer, Scientist
 Name, title

10/20/89
 Date

9313018.0536

Well: 299-E27-12
 Test Date: October 20, 1989
 Start Time: 07:43

SE1000B
 Environmental Logger
 10/20 15:54

Unit# 00701 Test# 0

INPUT 1: Level (F)

Reference 0.00
 Scale factor 9.99
 Offset - 0.01


Elapsed Time, Value,
 min ft

0.0000	- 0.25
0.0033	- 0.24
0.0066	- 0.20
0.0099	- 0.15
0.0133	- 0.09
0.0166	- 0.02
0.0200	0.00
0.0233	0.04
0.0266	0.10
0.0300	0.08
0.0333	0.05
0.0500	0.00
0.0666	- 0.00
0.0833	0.00
0.1000	0.00
0.1166	0.00
0.1333	0.00
0.1500	- 0.00
0.1666	- 0.00
0.1833	- 0.00
0.2000	- 0.00
0.2166	- 0.00
0.2333	- 0.00
0.2500	- 0.00
0.2666	- 0.00
0.2833	- 0.00
0.3000	- 0.00
0.3166	- 0.00
0.3333	- 0.00
0.4167	- 0.00
0.5000	- 0.00


0.5833	- 0.00
0.6667	- 0.00
0.7500	- 0.00
0.8333	- 0.00
0.9167	- 0.00
1.0000	- 0.00
1.0833	- 0.00
1.1667	- 0.00
1.2500	- 0.00
1.3333	- 0.00
1.4166	- 0.00
1.5000	- 0.00
1.5833	- 0.00
1.6667	- 0.00
1.7500	- 0.00
1.8333	- 0.00
1.9167	- 0.00
2.0000	- 0.00
2.5000	- 0.00
3.0000	- 0.00
3.5000	- 0.00
4.0000	- 0.00
4.5000	- 0.00
5.0000	- 0.00
5.5000	- 0.00
6.0000	- 0.01
6.5000	- 0.01
7.0000	- 0.01
7.5000	- 0.01
8.0000	- 0.01
8.5000	- 0.01
9.0000	- 0.01
9.5000	- 0.01
10.0000	- 0.01

END

9313018.052



D.18



D.19

APPENDIX E

TEST DATA AND ANALYSIS FOR WELL 299-E27-13

9313018.05"

APPENDIX E

TEST DATA AND ANALYSIS FOR WELL 299-E27-13

This appendix contains the as-built diagram for the well construction, Slug Test Record Form, Aquifer Test Data Sheets, Equipment Record Forms, Electronic Data Control Forms, and accompanying data logs and plots for well 299-E27-13.

9313018.051

9313018.02A



Battelle

Pacific Northwest Laboratories

AS-BUILT DIAGRAM

Well Number 299-E27-13 Geologist Ian Kennedy Page 1 of 3Reviewed by JT. McShan Date 12-6-89

Construction Data		Depth in Feet	Geologic/Hydrologic Data	
Description	Diagram		Diagram Litho.	Lithologic Description
10" diameter temporary casing shoe with drive shoe from 0' to 138'-6"		5		Sandy Gravel
		10		"
		15		Slightly gravelly, medium sand
		20		gravelly sand
		25		"
8" diameter temporary casing shoe with drive shoe from 1'-6 3/4" to 277'-1 3/4"		30		Sandy gravel
		35		"
		40		Sand
		45		"
		50		"
255.45' of 4" DIA. STAINLESS STEEL CASING		55		"
		60		"
		65		Slightly gravelly sand
		70		" " "
		75		" " "
		80		Sand
		85		Slightly gravelly sand
		90		" " "
		95		" " "
		100		gravelly sand
		105		" "
		110		"
		115		Slightly gravelly sand
		120		Sand
		125		"
		130		

9313018.0542



AS-BUILT DIAGRAM

Well Number 299-E27-13Geologist Jan KennedyPage 2 of 3Reviewed by V.L. McShanDate 12-6-89

Construction Data		Depth in Feet	Geologic/Hydrologic Data	
Description	Diagram		Diagram Litho.	Lithologic Description
133' 6 1/8" of 10" CARBON STEEL CASING		135'		Sand
		140'		"
		145'		"
		150'		"
276' 8 1/8" of 8" CARBON STEEL CASING		155'		Sandy gravelly sand
		160'		Gravelly sand
		165'		Slightly gravelly sand
		170'		Sand
299.45' of 4" STAINLESS STEEL CASING		175'		"
		180'		"
		185'		Slightly gravelly sand
		190'		Slightly gravelly sand
		195'		" " "
		200'		" " "
		205'		Sand
		210'		Slightly gravelly sand
		215'		Gravelly sand
		220'		" "
		225'		Sand
		230'		Sand
		235'		Sand
		240'		Sandy Gravel
		245'		" "
		250'		" "
		255'		" "
		260'		" "

PNL M4567 D2-1, 12V.0

A-1800-186 (3/87)

9313018.05

Well Number 299-E27-13 Geologist Tan Kennedy Page 3 of 3

Reviewed by V.L. McShane Date 12-6-89

PNL MAS67 CO-1, rev.0

Data for Well 299-E27-13Pumping Well -

Observation Wells

Location 200 East, C Tonk Farm

Type of Aquifer Test Slug TestHow Q Measured —

How W.L.'s Measured E_{tape} (S/N 12174), τ_{trans}

Rad/Dist of From Pumping Well 2 "

Meas. Point for W.L.'s Top of 4" casing

Elevation of Meas. Point _____

Depth of Pump/Airpipe

Pump On: date time

Pump Off: date time

Duration of Aquifer Test

Top of 4" I.D. casing is 1.8 ft. above ground surface

Time				Water Level Data				Discharge		Recorded By	Comments	
t = _____ at t' = 0				Static Water Level _____								
Day	Clock Time	t	t'	t/t'	Reading	Conversions or Corrections	Water Level s or s'	Reading	Q			
10/20	0820									DRN	Set up rig	
	0826				262.34'						E-tape	
	0832				D/B = 273.70' + 2.4' = 276.17'							Steel tape #L 300-14
	0840				Set slug below static water							
	0844				13.86'	set ref = 0	TEST # 1				Trans.	
	0846					Pull slug						
	0856					Stop datalogger						
						Set slug below static water						
	0857				13.88'	ref = 0	TEST # 2				Trans.	
	0900					Pull slug						
	0910					Stop test						
	0925				Withdraw a bail load							
Darrell Newcomer 10/20/89												

Harrell Newcomer 10/20/49

Location 200 East, C Tank Farm Date of Test 10/20/89
 Well Number 299-E27-13 Procedure Number PNL-M-567
AT-6, Rev 0
 Type of Test(s) Slug Withdrawal Test
 Personnel Conducting Test D. R. Newcomer

WELL CONFIGURATION

Well Depth 274.37' below land surface Borehole Diameter 8"
 Well Casing Inside Diameter 4" Well Screen Inside Diameter 4"
 Length of Screened Interval 13.91' (below water) Depth of Screen 274.68' - 253.68' bbs.
 Comments Well is undeveloped

SLUG INFORMATION

Slug Construction Materials Carbon steel
 Length of Slug 6.0' Diameter of Slug 2 1/4"
 Comments _____
 Volume of Attachments (if applicable) _____

MEASUREMENT EQUIPMENT INFORMATION


	Make	Model	Serial Number
Electric Tape	Slope Indicator	51453	12174
Steel Tape	Lufkin	Super-Hiway Nubian	L300-14
Data logger	In Situ	Hermit SE 1000 B	1KB-761
Transducer	Druck	PTX-161D	259198
Other			

Darrell Newcomer 10/20/89

9313018.0546

9313018.0546

Equipment Record Form for the Installation and Removal of Data Loggers and Pressure Transducers

Initial Check: <i>ok</i>		
Purpose of Installation: <i>To monitor slug withdrawal test response</i>		
Monitored Hydrologic Unit or Water Body: <i>Uppermost Unconfined Aquifer</i>		
Date/Time of Installation: <i>10/20/89 0840 hrs.</i>	Procedure Followed: <i>PNL-MA-567 WL-4, Rev 0</i>	
Data Logger Make/Model: <i>In Situ / SE1000 B</i>		
Serial No.: <i>1KB-701</i>	Number of Channels Used: <i>1</i>	
Pressure Transducer Make/Model: <i>Druck / PTX-161 D</i>	Full Scale Range: <i>10 psi</i>	Well No.: <i>299-E27-13</i>
	Serial No.: <i>259198</i>	Depth: <i>~274.4' below LS.</i>
Pressure Transducer Make/Model:	Full Scale Range:	Well No.:
	Serial No.:	Depth:
Description of Data Logger Installation and Well Head Configuration:  <i>Stickup of 4" casing is 1.8' above land surface.</i>		
Comments: <i>Slug was positioned above the water before placing transducer down to the bottom of the well. Slug was then lowered into position below water. Cement pad has not been poured yet.</i>		
Equipment Installed By <i>D. R. Newcomer</i>		
Date/Time of Equipment Removal: <i>10/20/89 0915 hrs.</i>		
Decontamination Procedure (if required):		
Equipment Removed By <i>D. R. Newcomer</i>		

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 10/20/89 0846 hrs.DATE AND END TIME OF DATA ACQUISITION 10/20/89 0856 hrs.WELL NUMBER 299 - E27-13TYPE OF TEST OR DATA Slug TestTYPE AND IDENTIFICATION NUMBER OF DATA LOGGER In SituHermit SE1000 B , S/N 1KB-701TEST NUMBER 1CHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED ftNUMBER OF PAGES ATTACHED 2

COMMENTS:

Test 1 = Withdraw SlugDATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

Darrell Penner, Scientist
Name, title10/20/89
Date

9313018.0548

9313018.0548

Well: 299-E27-13
Test Date: October 20, 1989
Start Time: 08:46

SE1000B
Environmental Logger
10/20 15:57

Unit# 00701 Test# 1

INPUT 1: Level (F)

Reference 0.00
Scale factor 9.99
Offset - 0.01

Elapsed Time, Value,
min ft

0.0000	- 0.23
0.0033	- 0.10
0.0066	- 0.53
0.0099	- 0.46
0.0133	- 0.36
0.0166	- 0.30
0.0200	- 0.24
0.0233	- 0.20
0.0266	- 0.17
0.0300	- 0.15
0.0333	- 0.14
0.0500	- 0.06
0.0666	- 0.01
0.0833	- 0.00
0.1000	0.00
0.1166	0.00
0.1333	0.00
0.1500	0.00
0.1666	0.00
0.1833	0.00
0.2000	0.00
0.2166	0.00
0.2333	0.00
0.2500	0.00
0.2666	0.00
0.2833	0.00
0.3000	0.00
0.3166	0.00
0.3333	0.00
0.4167	0.00
0.5000	0.00

0.5833	0.00
0.6667	0.00
0.7500	0.00
0.8333	0.00
0.9167	0.00
1.0000	0.00
1.0833	0.00
1.1667	0.00
1.2500	0.00
1.3333	0.00
1.4166	0.00
1.5000	0.00
1.5833	0.00
1.6667	0.00
1.7500	0.00
1.8333	0.00
1.9167	0.00
2.0000	0.00
2.5000	0.01
3.0000	0.01
3.5000	0.00
4.0000	0.01
4.5000	0.01
5.0000	0.01
5.5000	0.01
6.0000	0.01
6.5000	0.01
7.0000	0.01
7.5000	0.01
8.0000	0.01
8.5000	0.01
9.0000	0.01
9.5000	0.01
10.0000	0.01

END

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 10/20/89 9:00DATE AND END TIME OF DATA ACQUISITION 10/20/89 0910 hrs.WELL NUMBER 244-E27-13TYPE OF TEST OR DATA Slug TestTYPE AND IDENTIFICATION NUMBER OF DATA LOGGER In Situ
Hermit SE1000 B S/N 1KB-701TEST NUMBER 2CHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED ftNUMBER OF PAGES ATTACHED 2COMMENTS:
Test 2 = Withdraw Slug

_____DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

Darrell Newcome, Scientist 10/20/89
Name, title Date0550 0103136
9313018.0550

Well: 299-E27-13
 Test Date: October 20, 1989
 Start Time: 09:00

SE1000B
 Environmental Logger
 10/20 15:59

Unit# 00701 Test# 2

INPUT 1: Level (F)


Reference 0.00
 Scale factor 9.99
 Offset - 0.01

Elapsed Time, Value,
 min ft

 0.0000 0.07
 0.0033 - 0.74
 0.0066 - 1.07
 0.0099 - 1.02
 0.0133 - 0.89
 0.0166 - 0.79
 0.0200 - 0.72
 0.0233 - 0.64
 0.0266 - 0.58
 0.0300 - 0.54
 0.0333 - 0.49
 0.0500 - 0.31
 0.0666 - 0.20
 0.0833 - 0.13
 0.1000 - 0.08
 0.1166 - 0.05
 0.1333 - 0.03
 0.1500 - 0.02
 0.1666 - 0.01
 0.1833 - 0.00
 0.2000 - 0.00
 0.2166 - 0.00
 0.2333 0.00
 0.2500 0.00
 0.2666 0.00
 0.2833 0.00
 0.3000 0.00
 0.3166 0.00
 0.3333 0.00
 0.4167 0.00
 0.5000 0.00

0.5833 0.00
 0.6667 0.00
 0.7500 0.00
 0.8333 0.00
 0.9167 0.00
 1.0000 0.00
 1.0833 0.00
 1.1667 0.00
 1.2500 0.00
 1.3333 0.00
 1.4166 0.00
 1.5000 0.00
 1.5833 0.00
 1.6667 0.00
 1.7500 0.00
 1.8333 0.00
 1.9167 0.00
 2.0000 0.00
 2.5000 0.00
 3.0000 0.00
 3.5000 0.00
 4.0000 0.00
 4.5000 0.00
 5.0000 0.00
 5.5000 0.00
 6.0000 0.00
 6.5000 0.00
 7.0000 0.00
 7.5000 0.00
 8.0000 0.00
 8.5000 0.00
 9.0000 0.00
 9.5000 0.00
 10.0000 0.00
 END

E.12



ooooo WELL 299-E27-13, SLUG WITHDRAWAL TEST #1

Y_o PROJECTED = 0.56 ft

Y_o OBSERVED = 0.53 ft

$r_c = 0.2297$ ft


EXPONENTIAL BEST FIT LINE; $Y = e^{(-61.84X)} * 0.56$

$K = (r_c^2 \ln(R_e/r_w) / 2L_e t) * \ln(Y_o/Y_t)$

$K = ((0.2297)^2 (2.41) / 2(13.9)(0.01)) * \ln(0.56/0.30)$

$K = 410$ ft/day

WATER LEVEL CHANGE (Y_t), (ft)



WELL 299-E27-13, SLUG WITHDRAWAL TEST #1

 THE BELOW HYDRAULIC CONDUCTIVITY VALUE WAS CALCULATED
 USING THE BOUWER AND RICE SLUG TEST METHOD.

SOURCE= "THE BOUWER AND RICE SLUG TEST-AN UPDATE"
 GROUND WATER, VOL 27, NO. 3, MAY-JUNE 1989.

 RADIUS OF CASING USED IN CALCULATIONS HAS BEEN
 CORRECTED FOR THE THICKNESS OF GRAVEL OR SAND
 PACK DUE TO WATER LEVEL CHANGES IN THE SCREEN OR
 OPEN INTERVAL OF WELL.

Rc (ft)	Rw (ft)	Le (ft)	Lw (ft)	H (ft)
.2297	.3333	13.9100	13.9100	50.0000

Le/Rw = 41.7300000
 A= 2.8929200
 B= 4.568365E-001
 C= 2.4968560
 SANDPACK POROSITY= 3.000000E-001
 t (min)= 1.000000E-002
 1/t= 100.0000000
 Yo= (ft) 5.600000E-001
 Yt= (ft) 3.000000E-001
 1/t ln(Yo/Yt)= 62.4154300
 ln[(H-Lw)/Rw]= 4.6846280
 ln(Re/Rw)= 2.4072070

K (ft/day) = 410.4576000

T OF THE SATURATED SCREEN INTERVAL
 (ft2/day)= 5709.4660000

9313018.0554

ooooo WELL 299-E27-13, SLUG WITHDRAWAL TEST #2

Y_o PROJECTED = 1.07 ft

Y_o OBSERVED = 1.07 ft


$r_e = 0.2297$ ft

LINEAR BEST FIT LINE; $\log_{10}(Y) = -12.16x + 0.03$

$$K = (r_e^2 \ln(R_e/r_w) / 2L_s t) + \ln(Y_o/Y_i)$$

$$K = ((0.2297)^2 (2.41) / 2(13.9)(0.04)) + \ln(1.07/0.35)$$

$$K = 184 \text{ ft/day}$$



WELL 299-E27-13, SLUG WITHDRAWAL TEST #2

THE BELOW HYDRAULIC CONDUCTIVITY VALUE WAS CALCULATED
USING THE BOUWER AND RICE SLUG TEST METHOD.

SOURCE= "THE BOUWER AND RICE SLUG TEST-AN UPDATE"
GROUND WATER, VOL 27, NO. 3, MAY-JUNE 1989.

RADIUS OF CASING USED IN CALCULATIONS HAS BEEN
CORRECTED FOR THE THICKNESS OF GRAVEL OR SAND
PACK DUE TO WATER LEVEL CHANGES IN THE SCREEN OR
OPEN INTERVAL OF WELL.

Rc (ft)	Rw (ft)	Le (ft)	Lw (ft)	H (ft)
.2297	.3333	13.9100	13.9100	50.0000

Le/Rw = 41.7300000
A= 2.8929200
B= 4.568365E-001
C= 2.4968560
SANDPACK POROSITY= 3.000000E-001
t (min)= 4.000000E-002
1/t= 25.0000000
Yo= (ft) 1.0700000
Yt= (ft) 3.500000E-001
1/t ln(Yo/Yt)= 27.9370200
ln[(H-Lw)/Rw]= 4.6846280
ln(Re/Rw)= 2.4072080

K (ft/day) = 183.7176000

T OF THE SATURATED SCREEN INTERVAL
(ft²/day)= 2555.5120000

APPENDIX F

TEST DATA AND ANALYSIS FOR WELL 299-E27-14

THIS PAGE INTENTIONALLY
LEFT BLANK

9313018.05F

**THIS PAGE INTENTIONALLY
LEFT BLANK**

APPENDIX F

TEST DATA AND ANALYSIS FOR WELL 299-E27-14

This appendix contains the as-built diagram for the well construction, Slug Test Record Form, Aquifer Test Data Sheets, Equipment Record Forms, Electronic Data Control Forms, and accompanying data logs and plots for well 299-E27-14.

9313018.D51

9313018.D51



AS-BUILT DIAGRAM

Well Number Z99-E27-1A Geologist R. Miller Page 1 of 3Reviewed by V. E. Erickson Date 12-7-89

Construction Data		Depth in Feet	Geologic/Hydrologic Data	
Description	Diagram		Diagram Litho.	Lithologic Description
temporary 10" dia carbon steel casing from to 137'-7"		5		Muddy SAND
		10		"
		15		Gravely SAND
		20		Sandy GRAVEL
		25		"
		30		"
		35		"
		40		"
		45		SAND
		50		48-49' Slightly Muddy SAND - wet SAND
		55		"
		60		"
		65		"
		70		Sandy GRAVEL
		75		" "
		80		" "
		85		" "
		90		GRAVELLY SAND
		95		SAND (CLAY LENS 94' to 94.5')
		100		Slightly Muddy SAND
		105		SAND
		110		SAND
		115		SAND
		120		SAND
		125		SAND
		130		SAND

9313018.0559

9313018.0559



AS-BUILT DIAGRAM

Well Number 299-E27-14 Geologist M. Lubrecht Page 2 of 3Reviewed by V.I. Mublan Date 12-7-89

Construction Data		Depth in Feet	Geologic/Hydrologic Data	
Description	Diagram		Diagram Litho.	Lithologic Description
		135		SAND
End 10" @ 137'-7"		140		slightly gravelly SAND
		145		Gravelly SAND
		150		SAND
		155		"
		160		slightly gravelly SAND
		165		SAND
		170		gravelly SAND
		175		"
		180		"
8" ca. bore hole top		185		"
Casing		190		"
		195		"
246.48' of 4" Type 304		200		sl. gravelly SAND
S.H.S. Stainless Steel		205		SAND
Casing		210		SAND
		215		SAND
		220		"
		225		"
		230		muddy sandy Gravel
		235		sandy Gravel
		240		"
		245		muddy sandy Gravel
		250		sandy Gravel
		255		"
		260		Gravelly SAND

FNL-MA 567, DO-1, Rev 0

A-1800-188 (3/87)









9313018.056"



AS-BUILT DIAGRAM

Well Number 299-E27-14 Geologist M. D. Lubrecht Page 3 of 3

Reviewed by W.L. Macklin Date 12-7-89

Construction Data		Depth in Feet	Geologic/Hydrologic Data	
Description	Diagram		Diagram Litho.	Lithologic Description
End 8" casing @ 267.1'		265'		Sand -
T.D. @ 266.05'				T.D. = 266.8'
21' OF 4" DIA. 10 SLOT CHANNEL PACK SCREEN (STAINLESS STEEL)				COMPLETION DEPTH = 266.83
COMPLETION SYMBOLS:				
				
CEMENT GROUT				
				
GRAVULAR BENTONITE				
				
BENTONITE PELLETS				
				
SILICA SAND				
				
CASING JOINT				
				
CASING CENTRALIZER				

9313018-0561

2010

page 1 of 1

Observation Wells

Top of 4" casing is 255 ft. above ground surface

350-3103138

Darrell Newcomb 10/20/89

Location 200 East, C Tank Farm Date of Test 10/20/89
Well Number 299-E27-14 Procedure Number PNL-MA-567
AT-6, Rev 0
Type of Test(s) Slug Withdrawal Test
Personnel Conducting Test D.R. Newcomer, Darrell Ludke, KEH driller

WELL CONFIGURATION

Well Depth ~265.6' below ground surface Borehole Diameter 8"
Well Casing Inside Diameter 4" Well Screen Inside Diameter 4"
Length of Screened Interval 16.0' (below water) Depth of Screen 266.8' - 245.8' b.l.s.
Comments Well is undeveloped; cement pad has not been poured

SLUG INFORMATION


Slug Construction Materials Carbon Steel Casing
Length of Slug 6.0' Diameter of Slug 2 1/4"
Comments _____
Volume of Attachments (if applicable) _____

MEASUREMENT EQUIPMENT INFORMATION

	Make	Model	Serial Number
Electric Tape	<i>Slope Indicator</i>	<i>51453</i>	<i>12174</i>
Steel Tape	<i>Lufkin</i>	<i>Super Hi-way Nubian</i>	<i>L300-14</i>
Data logger	<i>In Situ</i>	<i>SE1000 B Hermit</i>	<i>1KB-701</i>
Transducer	<i>Druck</i>	<i>PTX-161D</i>	<i>259198</i>
Other			

Darrell Newcomer, 10/20/89

Equipment Record Form for the Installation and Removal of Data Loggers and Pressure Transducers

Initial Check: <i>OK</i>		
Purpose of Installation: <i>To monitor water levels during slug test</i>		
Monitored Hydrologic Unit or Water Body: <i>Upper Unconfined Aquifer within saturated screen interval</i>		
Date/Time of Installation: <i>10/20/89 10:17 hrs</i>		Procedure Followed: <i>PUL-MA-567 WL-4, Rev. 0</i>
Data Logger Make/Model: <i>In Situ / Hermit SE 1000 B</i>		
Serial No.: <i>1KB-701</i>	Number of Channels Used: <i>1</i>	
Pressure Transducer Make/Model: <i>Druck / PTX-161D</i>	Full Scale Range: <i>10 psi</i>	Well No.: <i>299-E27-14</i>
	Serial No.: <i>259198</i>	Depth: <i>~266' below land surface</i>
Pressure Transducer Make/Model:	Full Scale Range:	Well No.:
	Serial No.:	Depth:
Description of Data Logger Installation and Well Head Configuration:  <i>Stickup of 4" casing is 0.55' above land surface</i>		
Comments: <i>Slug was positioned above water before placing the transducer down to bottom. Slug was then lowered into position below water. Water level was allowed to stabilize.</i>		
Equipment Installed By <i>D.R. Newcomer</i>		
Date/Time of Equipment Removal: <i>10/20/89 1705 hrs.</i>		
Decontamination Procedure (if required):		
Equipment Removed By <i>D.R. Newcomer</i>		

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 10/20/89 1020 hrs.DATE AND END TIME OF DATA ACQUISITION 10/20/89 1030 hrsWELL NUMBER 299 - E27-14TYPE OF TEST OR DATA Slug TestTYPE AND IDENTIFICATION NUMBER OF DATA LOGGER In Situ
Hermit SE1000 B , S/N 1KB-701TEST NUMBER 3CHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED ftNUMBER OF PAGES ATTACHED 2

COMMENTS:

Test 3 = Withdraw SlugDATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

Darrell Newcomer, Scientist
Name, title10/20/89
Date

Well: 299-E27-14
 Test Date: October 20, 1989
 Start Time: 10:20

SE1000B
 Environmental Logger
 10/20 16:01

Unit# 00701 Test# 3

INPUT 1: Level (F)

Reference 0.00
 Scale factor 9.99
 Offset - 0.01

Elapsed Time, Value,
 min ft

0.0000	0.00
0.0033	0.00
0.0066	- 4.69
0.0099	0.16
0.0133	1.21
0.0166	- 1.66
0.0200	0.03
0.0233	- 0.82
0.0266	- 0.75
0.0300	- 1.21
0.0333	- 1.54
0.0500	- 0.85
0.0666	- 0.54
0.0833	- 0.34
0.1000	- 0.22
0.1166	- 0.14
0.1333	- 0.08
0.1500	- 0.05
0.1666	- 0.03
0.1833	- 0.02
0.2000	- 0.01
0.2166	- 0.00
0.2333	- 0.00
0.2500	0.00
0.2666	0.00
0.2833	0.00
0.3000	0.00
0.3166	0.00
0.3333	0.00
0.4167	0.00
0.5000	0.00

0.5833	0.00
0.6667	0.00
0.7500	0.00
0.8333	0.00
0.9167	0.00
1.0000	0.00
1.0833	0.00
1.1667	0.00
1.2500	0.00
1.3333	0.00
1.4166	0.00
1.5000	0.00
1.5833	0.00
1.6667	0.00
1.7500	0.00
1.8333	0.00
1.9167	0.00
2.0000	0.00
2.5000	0.00
3.0000	0.00
3.5000	0.00
4.0000	0.00
4.5000	0.00
5.0000	0.00
5.5000	0.00
6.0000	0.00
6.5000	0.00
7.0000	0.00
7.5000	0.00
8.0000	0.00
8.5000	0.00
9.0000	0.00
9.5000	0.00
10.0000	0.00

END

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 10/20/89 1035 hrs.DATE AND END TIME OF DATA ACQUISITION 10/20/89 1047 hrs.WELL NUMBER 299-E27-14TYPE OF TEST OR DATA Slug TestTYPE AND IDENTIFICATION NUMBER OF DATA LOGGER In Situ
Hermit SE1000 B , S/N 1KB-701TEST NUMBER 4CHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED ftNUMBER OF PAGES ATTACHED 2COMMENTS:
Test 4 = Withdraw Slug

_____DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

Darrell Marcones, Scientist 10/20/89
Name, title Date

9313018.0567

Well: 299-E27-14
Test Date: October 20, 1989
Start Time: 10:35

SE1000B
Environmental Logger
10/20 16:02

Unit# 00701 Test# 4

INPUT 1: Level (F)

Reference 0.00
Scale factor 9.99
Offset - 0.01

Elapsed Time, Value,
min ft

0.0000	0.00
0.0033	- 0.00
0.0066	- 0.00
0.0099	- 0.00
0.0133	- 3.67
0.0166	- 0.19
0.0200	0.59
0.0233	- 3.87
0.0266	- 3.00
0.0300	- 4.47
0.0333	- 4.09
0.0500	- 4.32
0.0666	- 3.57
0.0833	- 3.25
0.1000	- 3.05
0.1166	- 2.92
0.1333	- 2.83
0.1500	- 2.78
0.1666	- 2.75
0.1833	- 2.72
0.2000	- 2.71
0.2166	- 2.69
0.2333	- 2.68
0.2500	- 2.67
0.2666	- 2.67
0.2833	- 2.66
0.3000	- 2.66
0.3166	- 2.66
0.3333	- 2.65
0.4167	- 2.63
0.5000	- 2.61

0.5833	- 2.58
0.6667	- 2.56
0.7500	- 2.54
0.8333	- 2.53
0.9167	- 2.50
1.0000	- 2.48
1.0833	- 2.47
1.1667	- 2.45
1.2500	- 2.42
1.3333	- 2.37
1.4166	- 2.35
1.5000	- 2.33
1.5833	- 2.32
1.6667	- 2.30
1.7500	- 2.26
1.8333	- 2.24
1.9167	- 2.21
2.0000	- 2.19
2.5000	- 2.03
3.0000	- 1.92
3.5000	- 1.77
4.0000	- 1.60
4.5000	- 1.29
5.0000	- 1.00
5.5000	- 0.83
6.0000	- 0.73
6.5000	- 0.53
7.0000	0.00
7.5000	- 0.00
8.0000	- 0.00
8.5000	- 0.00
9.0000	- 0.00
9.5000	- 0.00
10.0000	- 0.00
12.0000	- 0.02

END

9313018.0550

9313018.0550

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 10/20/89 1052 hrs.DATE AND END TIME OF DATA ACQUISITION 10/20/89 1102 hrs.WELL NUMBER 299 - E27-MTYPE OF TEST OR DATA Slug TestTYPE AND IDENTIFICATION NUMBER OF DATA LOGGER In SituHermit SE1000 B S/N 1KB-701TEST NUMBER 5CHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED FtNUMBER OF PAGES ATTACHED 2COMMENTS: Test 5 = Withdraw SlugDATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

Darrell Newcomes, Scientist 10/20/89
Name, title Date

9313018.0569

Well: 299-E27-14
Test Date: October 20, 1989
Start Time: 10:52

SE1000B
Environmental Logger
10/20 16:04

Unit# 00701 Test# 5

INPUT 1: Level (F)


Reference 0.00
Scale factor 9.99
Offset - 0.01

Elapsed Time, Value,
min ft

0.0000 - 0.80
0.0033 - 1.35
0.0066 - 0.28
0.0099 - 0.11
0.0133 - 0.49
0.0166 - 1.84
0.0200 - 1.01
0.0233 - 1.08
0.0266 - 0.95
0.0300 - 0.85
0.0333 - 0.77
0.0500 - 0.46
0.0666 - 0.28
0.0833 - 0.17
0.1000 - 0.10
0.1166 - 0.06
0.1333 - 0.04
0.1500 - 0.02
0.1666 - 0.01
0.1833 - 0.00
0.2000 - 0.00
0.2166 - 0.00
0.2333 - 0.00
0.2500 0.00
0.2666 0.00
0.2833 0.00
0.3000 0.00
0.3166 0.00
0.3333 0.00
0.4167 0.00
0.5000 0.00

0.5833 0.00
0.6667 0.00
0.7500 0.00
0.8333 0.00
0.9167 0.00
1.0000 0.00
1.0833 0.00
1.1667 0.00
1.2500 0.00
1.3333 0.00
1.4166 0.00
1.5000 0.00
1.5833 0.00
1.6667 0.00
1.7500 0.00
1.8333 0.00
1.9167 0.00
2.0000 0.00
2.5000 0.00
3.0000 0.00
3.5000 0.00
4.0000 0.00
4.5000 0.00
5.0000 0.00
5.5000 0.00
6.0000 0.00
6.5000 0.01
7.0000 0.00
7.5000 0.01
8.0000 0.00
8.5000 0.00
9.0000 0.00
9.5000 0.00
10.0000 0.00

END



9313018.057

00000 WELL 299-E27-14, SLUG WITHDRAWAL TEST #3

Y_o PROJECTED = 2.86 ft
 Y_o OBSERVED = 1.54 ft


$r_e = 0.2297$ ft

LINEAR BEST FIT LINE; $\log_{10}(Y) = -11.74x + 0.46$

$$K = (r_e^2 \ln(R_e/r_w) / 2L_e t) + \ln(Y_o/Y_1)$$

$$K = ((0.2297)^2 (2.53) / 2(16.0)(0.04)) + \ln(2.86/0.97)$$

$$K = 162 \text{ ft/day}$$



F.15

9313018.0253

WELL 299-E27-14, SLUG WITHDRAWAL TEST #3

 THE BELOW HYDRAULIC CONDUCTIVITY VALUE WAS CALCULATED
 USING THE BOUWER AND RICE SLUG TEST METHOD.

SOURCE= "THE BOUWER AND RICE SLUG TEST-AN UPDATE"
 GROUND WATER, VOL 27, NO. 3, MAY-JUNE 1989.

 RADIUS OF CASING USED IN CALCULATIONS HAS BEEN
 CORRECTED FOR THE THICKNESS OF GRAVEL OR SAND
 PACK DUE TO WATER LEVEL CHANGES IN THE SCREEN OR
 OPEN INTERVAL OF WELL.


Rc (ft)	Rw (ft)	Le (ft)	Lw (ft)	H (ft)
.2297	.3333	16.0000	16.0000	50.0000

Le/Rw = 48.0000000
 A= 3.0530930
 B= 4.990199E-001
 C= 2.6303630
 SANDPACK POROSITY= 3.000000E-001
 t (min)= 4.000000E-002
 1/t= 25.0000000
 Yo= (ft) 2.8600000
 Yt= (ft) 9.700000E-001
 1/t ln(Yo/Yt)= 27.0320200
 ln[(H-Lw)/Rw]= 4.6249730
 ln(Re/Rw)= 2.5262860

 K (ft/day) = 162.1902000

T OF THE SATURATED SCREEN INTERVAL
 (ft²/day)= 2595.0440000

9313018.0573



WELL 299-E27-14, SLUG WITHDRAWAL TEST #5, TIME SHIFT= 0.015 min

 THE BELOW HYDRAULIC CONDUCTIVITY VALUE WAS CALCULATED
 USING THE BOUWER AND RICE SLUG TEST METHOD.

SOURCE= "THE BOUWER AND RICE SLUG TEST-AN UPDATE"
 GROUND WATER, VOL 27, NO. 3, MAY-JUNE 1989.

 RADIUS OF CASING USED IN CALCULATIONS HAS BEEN
 CORRECTED FOR THE THICKNESS OF GRAVEL OR SAND
 PACK DUE TO WATER LEVEL CHANGES IN THE SCREEN OR
 OPEN INTERVAL OF WELL.


Rc (ft)	Rw (ft)	Le (ft)	Lw (ft)	H (ft)
.2297	.3333	16.0000	16.0000	50.0000

Le/Rw = 48.0000000
 A= 3.0530930
 B= 4.990199E-001
 C= 2.6303630
 SANDPACK POROSITY= 3.000000E-001
 t (min)= 6.000000E-002
 1/t= 16.6666700
 Yo= (ft) 3.2800000
 Yt= (ft) 5.400000E-001
 1/t ln(Yo/Yt)= 30.0671600
 ln[(H-Lw)/Rw]= 4.6249730
 ln(Re/Rw)= 2.5262860

 K (ft/day) = 180.4008000

T OF THE SATURATED SCREEN INTERVAL
 (ft²/day)= 2886.4140000

931301B.05



F.19

MHC-SD-EN-TI-147, Rev. 0

931301B.05

WELL 299-E27-14, SLUG WITHDRAWAL TEST #4, WATER LEVEL CHANGE SHIFT= -2.66 ft

 THE BELOW HYDRAULIC CONDUCTIVITY VALUE WAS CALCULATED
 USING THE BOUWER AND RICE SLUG TEST METHOD.

SOURCE= "THE BOUWER AND RICE SLUG TEST-AN UPDATE"
 GROUND WATER, VOL 27, NO. 3, MAY-JUNE 1989.


 RADIUS OF CASING USED IN CALCULATIONS HAS BEEN
 CORRECTED FOR THE THICKNESS OF GRAVEL OR SAND
 PACK DUE TO WATER LEVEL CHANGES IN THE SCREEN OR
 OPEN INTERVAL OF WELL.

Rc (ft)	Rw (ft)	Le (ft)	Lw (ft)	H (ft)
.2297	.3333	16.0000	16.0000	50.0000

Le/Rw = 48.0000000
 A= 3.0530930
 B= 4.990199E-001
 C= 2.6303630
 SANDPACK POROSITY= 3.000000E-001
 t (min)= 1.000000E-001
 1/t= 10.0000000
 Yo= (ft) 3.4200000
 Yt= (ft) 3.000000E-001
 1/t ln(Yo/Yt)= 24.3361300
 ln[(H-Lw)/Rw]= 4.6249730
 ln(Re/Rw)= 2.5262860

 K (ft/day) = 146.0151000

T OF THE SATURATED SCREEN INTERVAL
 (ft²/day)= 2336.2410000



APPENDIX G

TEST DATA AND ANALYSIS FOR WELL 299-E27-15

9313018.057

APPENDIX G

TEST DATA AND ANALYSIS FOR WELL 299-E27-15

This appendix contains the as-built diagram for the well construction, Slug Test Record Form, Aquifer Test Data Sheets, Equipment Record Forms, Electronic Data Control Forms, and accompanying data logs and plots for well 299-E27-15.

9313018.056

9313018.056



AS-BUILT DIAGRAM

Well Number 299-E27-15 Geologist Jan Kennedy / Miller Page 1 of 2Reviewed by J. McElmer Date 12-7-89

Construction Data		Depth in Feet	Geologic/Hydrologic Data	
Description	Diagram		Diagram Litho.	Lithologic Description
temporary 10" carbon steel temporary casing w/ drive shoe from +1' to 128' 1/2" (129' 5 1/2")		5		SAND
		10		"
		15		sandy gravel
		20		sand
		25		"
temporary 8" carbon steel casing w/ drive shoe from +2.25' to 261.87' bbs (264.12')		30		Gravelly sand
		35		slightly gravelly sand
		40		Sand
240.46' of 4" stainless steel casing		45		Slightly gravelly sand
		50		"
		55		Sand (to gravel)
		60		"
		65		"
		70		"
		75		"
		80		"
		85		"
		90		"
		95		"
		100		Gravelly SAND
		105		"
		110		"
		115		"
		120		"
		125		"
		130		"

9313018.0581



Pacific Northwest Laboratories

AS-BUILT DIAGRAM

Well Number 299-E27-15Geologist Kennedy / MillerPage 2 of 2Reviewed by V.E. McKelveyDate 12-7-89

Construction Data		Depth in Feet	Geologic/Hydrologic Data	
Description	Diagram		Diagram Litho.	Lithologic Description
temporary 6" carbon steel casing		135		Sandy Gravel
into bore size		140		Sand
		145		Slightly Gravelly Sand
240.45' or 4"		150		"
STAINLESS STEEL CASING		155		Sand
		160		Slightly gravelly sand
		165		"
		170		Sandy GRAVEL
		175		Gravelly SAND
		180		SAND
		185		"
		190		"
		195		"
		200		"
X Cement Grout		205		"
8-20 mesh Bentonite Grumbles		210		"
1/4" bentonite Pellets		215		"
16-30 mesh Silica Sand		220		"
		225		"
volcanic pellets (1/4")		230		Sandy GRAVEL
		235		"
		240		"
Colorado Silica Sand		245		Muddy Sandy GRAVEL
4" stainless steel		250		"
10 slot channel pack		255		"
(21')		260		"

PNL-MA-567-DC-1-rev-0

TD 262.54'

A-1800-186 (3/87)

9313018.155

Equipment Record Form for the Installation and Removal of Data Loggers and Pressure Transducers

Initial Check: <u>IN LAB</u>		
Purpose of Installation: <u>monitored WL changes during slug tests</u>		
Monitored Hydrologic Unit or Water Body: <u>saturated screened interval</u>		
Date/Time of Installation: <u>5/19/89 1020</u>		Procedure Followed: <u>WL-4</u>
Data Logger Make/Model: <u>Hermit SE 1000B</u>		
Serial No.: <u>1KB-701</u>	Number of Channels Used: <u>1</u>	
Pressure Transducer Make/Model: <u>In situ PTX-161D</u>	Full Scale Range: <u>10 psi</u>	Well No.: <u>299-E27-15</u>
	Serial No.: <u>259198</u>	Depth: <u>13.7 ft below water</u>
Pressure Transducer Make/Model:	Full Scale Range:	Well No.:
	Serial No.:	Depth:
Description of Data Logger Installation and Well Head Configuration: 		
Comments:		
Equipment Installed By <u>DR. Nowman</u>		
Date/Time of Equipment Removal: <u>10/19/89 1230</u>		
Decontamination Procedure (if required): <u>N/A</u>		
Equipment Removed By <u>JV Borglund</u>		

Location 1 - TANK 2 - EAST Date of Test 10/19/89
 Well Number 244-E27-15 Procedure Number AT-6
 Type of Test(s) Slug
 Personnel Conducting Test Borg Lee Newcomer

WELL CONFIGURATION

Well Depth 261' TOC Borehole Diameter 4" 8"
 Well Casing Inside Diameter 4" Well Screen Inside Diameter 4"
 Length of Screened Interval ~~10-65~~ 20' Depth of Screen ~~261~~ 241
 Comments Well is undeveloped

SLUG INFORMATION

Slug Construction Materials carbon steel
 Length of Slug 6' Diameter of Slug 2.25 inch
 Comments _____
 Volume of Attachments (if applicable) _____

MEASUREMENT EQUIPMENT INFORMATION

	Make	Model	Serial Number
Electric Tape	su	As test form	
Steel Tape			
Data logger	and	equipment record form.	
Transducer			JVB 10/20/89
Other			

9313018-0585

9313018-0585

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 10/19/89 21152 (1152)DATE AND END TIME OF DATA ACQUISITION 10/19/89 1237WELL NUMBER 299 - E27-15TYPE OF TEST OR DATA Slug Injection

TYPE AND IDENTIFICATION NUMBER OF DATA LOGGER

Hermit SE 1000 R 1KB-701TEST NUMBER 0CHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED Ft from ref. levelNUMBER OF PAGES ATTACHED 2

COMMENTS:

Date Logger started late.DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

James V. Borchers, Supervisor 10/20/89
Name, title Date

9313018.056

Well: 299-E27-15
 Test Date: October 19, 1989
 Start Time: 11:56

SE1000B
 Environmental Logger
 10/19 16:44

Unit# 00701 Test# 0

INPUT 1: Level (F)

Reference 0.00
 Scale factor 9.99
 Offset - 0.01

Elapsed Time, Value,
 min ft

0.0000	- 0.00	0.5833	0.00
0.0033	- 0.00	0.6667	0.00
0.0066	- 0.00	0.7500	0.00
0.0099	- 0.00	0.8333	0.00
0.0133	- 0.00	0.9167	0.00
0.0166	- 0.00	1.0000	0.00
0.0200	- 0.00	1.0833	0.00
0.0233	- 0.00	1.1667	0.00
0.0266	- 0.00	1.2500	0.00
0.0300	- 0.00	1.3333	0.00
0.0333	- 0.00	1.4166	0.00
0.0500	- 0.00	1.5000	0.00
0.0666	0.28	1.5833	0.00
0.0833	1.08	1.6667	0.00
0.1000	- 0.57	1.7500	0.00
0.1166	0.10	1.8333	0.00
0.1333	0.00	1.9167	0.00
0.1500	0.00	2.0000	0.00
0.1666	0.00	2.5000	0.00
0.1833	0.00	3.0000	0.00
0.2000	0.00	3.5000	0.00
0.2166	0.00	4.0000	0.00
0.2333	0.00	4.5000	0.00
0.2500	0.00	5.0000	0.00
0.2666	0.00	5.5000	0.00
0.2833	0.00	6.0000	0.00
0.3000	0.00	6.5000	0.00
0.3166	0.00	7.0000	0.00
0.3333	0.00	7.5000	0.00
0.4167	0.00	8.0000	0.00
0.5000	0.00	8.5000	0.00
		9.0000	0.00
		9.5000	0.00
		10.0000	0.00
		12.0000	0.01
		14.0000	0.01
		16.0000	0.01
		18.0000	0.01
		20.0000	0.01
		22.0000	0.01
		24.0000	0.01
		26.0000	0.01
		28.0000	0.01
		30.0000	0.01
		32.0000	0.01
		34.0000	0.02
		36.0000	0.02
		38.0000	0.02
		40.0000	0.02
		END	

9313018.0587

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 10/19/89 1241
DATE AND END TIME OF DATA ACQUISITION " 1257
WELL NUMBER 299-E27-15
TYPE OF TEST OR DATA Slug WD
TYPE AND IDENTIFICATION NUMBER OF DATA LOGGER Hermit SE1000B 1KB-701
TEST NUMBER 1
CHANNEL OR INPUT NUMBER 1
UNITS OF VALUES RECORDED ft from ref. level
NUMBER OF PAGES ATTACHED 2

COMMENTS:

DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

Jane V. Byler Scientist 10/20/89
Name, title Date

Well: 299-E27-15
 Test Date: October 19, 1989
 Start Time: 12:41

SE1000B
 Environmental Logger
 10/19 16:46

Unit# 00701 Test# 1

INPUT 1: Level (F)

Reference 0.00
 Scale factor 9.99
 Offset - 0.01

Elapsed Time, Value,
 min ft

0.0000	- 0.06
0.0033	- 0.51
0.0066	- 0.74
0.0099	- 1.01
0.0133	- 0.78
0.0166	- 0.64
0.0200	- 0.52
0.0233	- 0.42
0.0266	- 0.35
0.0300	- 0.26
0.0333	- 0.22
0.0500	- 0.09
0.0666	- 0.04
0.0833	- 0.02
0.1000	- 0.02
0.1166	- 0.01
0.1333	- 0.01
0.1500	- 0.01
0.1666	- 0.01
0.1833	- 0.01
0.2000	- 0.01
0.2166	- 0.01
0.2333	- 0.01
0.2500	- 0.01
0.2666	- 0.01
0.2833	- 0.01
0.3000	- 0.01
0.3166	- 0.01
0.3333	- 0.01
0.4167	- 0.01
0.5000	- 0.01

0.5833	- 0.01
0.6667	- 0.01
0.7500	- 0.01
0.8333	- 0.01
0.9167	- 0.01
1.0000	- 0.01
1.0833	- 0.01
1.1667	- 0.01
1.2500	- 0.01
1.3333	- 0.01
1.4166	- 0.01
1.5000	- 0.01
1.5833	- 0.01
1.6667	- 0.01
1.7500	- 0.01
1.8333	- 0.01
1.9167	- 0.01
2.0000	- 0.01
2.5000	- 0.01
3.0000	- 0.01
3.5000	- 0.01
4.0000	- 0.01
4.5000	- 0.01
5.0000	- 0.01
5.5000	- 0.01
6.0000	- 0.01
6.5000	- 0.00
7.0000	- 0.00
7.5000	- 0.00
8.0000	- 0.00
8.5000	- 0.00
9.0000	- 0.00
9.5000	- 0.00
10.0000	- 0.00
12.0000	- 0.00
14.0000	- 0.00
16.0000	- 0.00

END

9313018.0589

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 10/19/89 1301DATE AND END TIME OF DATA ACQUISITION " 1323WELL NUMBER 299-E27-15TYPE OF TEST OR DATA Slug ~~was~~ injectionTYPE AND IDENTIFICATION NUMBER OF DATA LOGGER Hermit SE1000B 1KB-701TEST NUMBER 2CHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED ft from ref. levelNUMBER OF PAGES ATTACHED 2

COMMENTS:

STARTED Recording Late

DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

J.V. Borglese Scientist 10/20/89
Name, title Date

Well: 299-E27-15
 Test Date: October 19, 1989
 Start Time: 13:01

SE1000B
 Environmental Logger
 10/19 16:48

Unit# 00701 Test# 2

INPUT 1: Level (F)

Reference 0.00
 Scale factor 9.99
 Offset - 0.01

Elapsed Time, Value,
 min ft

0.0000	1.25	0.5833	0.01
0.0033	1.65	0.6667	0.01
0.0066	- 1.03	0.7500	0.01
0.0099	- 0.14	0.8333	0.01
0.0133	- 0.03	0.9167	0.01
0.0166	0.00	1.0000	0.01
0.0200	0.02	1.0833	0.01
0.0233	0.03	1.1667	0.01
0.0266	0.02	1.2500	0.01
0.0300	0.02	1.3333	0.01
0.0333	0.01	1.4166	0.01
0.0500	0.00	1.5000	0.01
0.0666	0.00	1.5833	0.01
0.0833	0.01	1.6667	0.01
0.1000	0.01	1.7500	0.01
0.1166	0.01	1.8333	0.01
0.1333	0.01	1.9167	0.01
0.1500	0.01	2.0000	0.01
0.1666	0.01	2.5000	0.01
0.1833	0.01	3.0000	0.01
0.2000	0.01	3.5000	0.00
0.2166	0.01	4.0000	0.01
0.2333	0.01	4.5000	0.00
0.2500	0.01	5.0000	0.00
0.2666	0.01	5.5000	0.00
0.2833	0.01	6.0000	0.00
0.3000	0.01	6.5000	0.00
0.3166	0.01	7.0000	0.00
0.3333	0.01	7.5000	0.00
0.4167	0.01	8.0000	0.00
0.5000	0.01	8.5000	0.00
		9.0000	0.00
		9.5000	0.00
		10.0000	0.00
		12.0000	0.00
		14.0000	0.00
		16.0000	0.00
		18.0000	0.00
		20.0000	0.00
		22.0000	0.00

END

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 10/19/89 1527
DATE AND END TIME OF DATA ACQUISITION " 1327 1339
WELL NUMBER 299-E27-15
TYPE OF TEST OR DATA slug WD
TYPE AND IDENTIFICATION NUMBER OF DATA LOGGER Hermit SE10008 KB-701
TEST NUMBER 3
CHANNEL OR INPUT NUMBER 1
UNITS OF VALUES RECORDED ft from ref. level
NUMBER OF PAGES ATTACHED 2
COMMENTS:
Trans. hung up

DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

Gene V. Boylue, Superintendent 10/20/89
Name, title Date

Well: 299-E27-15
 Test Date: October 19, 1989
 Start Time: 13:27

SE1000B
 Environmental Logger
 10/19 16:49

Unit# 00701 Test# 3

INPUT 1: Level (F)

Reference 0.00
 Scale factor 9.99
 Offset - 0.01

Elapsed Time, Value,
 min ft


 0.0000 - 1.06
 0.0033 - 1.06
 0.0066 - 1.06
 0.0099 - 1.06
 0.0133 - 1.06
 0.0166 - 1.06
 0.0200 - 1.06
 0.0233 - 1.06
 0.0266 - 1.06
 0.0300 - 1.06
 0.0333 - 1.07
 0.0500 - 1.07
 0.0666 - 1.07
 0.0833 - 2.32
 0.1000 - 1.19
 0.1166 - 1.89
 0.1333 - 1.37
 0.1500 - 1.17
 0.1666 - 1.10
 0.1833 - 1.08
 0.2000 - 1.08
 0.2166 - 1.07
 0.2333 - 1.07
 0.2500 - 1.07
 0.2666 - 1.07
 0.2833 - 1.07
 0.3000 - 1.07
 0.3166 - 1.07
 0.3333 - 1.07
 0.4167 - 1.07
 0.5000 - 1.07

0.5833 - 1.07
 0.6667 - 1.07
 0.7500 - 1.07
 0.8333 - 1.07
 0.9167 - 1.07
 1.0000 - 1.07
 1.0833 - 1.07
 1.1667 - 1.07
 1.2500 - 1.07
 1.3333 - 1.06
 1.4166 - 1.06
 1.5000 - 1.06
 1.5833 - 1.06
 1.6667 - 1.06
 1.7500 - 1.06
 1.8333 - 1.06
 1.9167 - 1.06
 2.0000 - 1.06
 2.5000 - 1.06
 3.0000 - 1.06
 3.5000 - 1.06
 4.0000 - 1.06
 4.5000 - 1.06
 5.0000 - 1.06
 5.5000 - 1.06
 6.0000 - 1.06
 6.5000 - 1.06
 7.0000 - 1.06
 7.5000 - 1.06
 8.0000 - 1.06
 8.5000 - 1.06
 9.0000 - 1.06
 9.5000 - 1.06
 10.0000 - 1.06
 12.0000 - 1.07

END

9313018.0593

9313018.05"




G.15

WMC-SD-EN-TI-147, Rev. 0

9313018.05"

ooooo WELL 299-E27-15, SLUG WITHDRAWAL TEST #1



WELL 299-E27-15, SLUG WITHDRAWAL TEST #1

 THE BELOW HYDRAULIC CONDUCTIVITY VALUE WAS CALCULATED
 USING THE BOUWER AND RICE SLUG TEST METHOD.
 SOURCE= "THE BOUWER AND RICE SLUG TEST-AN UPDATE"
 GROUND WATER, VOL 27, NO. 3, MAY-JUNE 1989.

 RADIUS OF CASING USED IN CALCULATIONS HAS BEEN
 CORRECTED FOR THE THICKNESS OF GRAVEL OR SAND
 PACK DUE TO WATER LEVEL CHANGES IN THE SCREEN OR
 OPEN INTERVAL OF WELL.

Rc (ft)	Rw (ft)	Le (ft)	Lw (ft)	H (ft)
.2297	.3333	14.3000	14.3000	50.0000

Le/Rw = 42.9000000
 A= 2.9202500
 B= 4.656601E-001
 C= 2.5309510
 SANDPACK POROSITY= 3.000000E-001
 t (min)= 2.500000E-002
 1/t= 40.0000000
 Yo= (ft) 9.600000E-001
 Yt= (ft) 2.100000E-001
 1/t ln(Yo/Yt)= 60.7930300
 ln[(H-Lw)/Rw]= 4.6737630
 ln(Re/Rw)= 2.4304660

K (ft/day) = 392.6369000

T OF THE SATURATED SCREEN INTERVAL
 (ft²/day)= 5614.7080000

9313018.05

APPENDIX H

TEST DATA AND ANALYSIS FOR WELL 299-E33-33

9313018.05

APPENDIX H

TEST DATA AND ANALYSIS FOR WELL 299-E33-33

This appendix contains the as-built diagram for the well construction, Slug Test Record Form, Aquifer Test Data Sheets, Equipment Record Forms, Electronic Data Control Forms, and accompanying data logs and plots for well 299-E33-33.

9313018.050

9313018.050



AS-BUILT DIAGRAM

Well Number 299-E33-33 Geologist GOODWIN JENSEN Page 1 of 2
BRANDEN BEAGER
 Reviewed by W.L. McSham Date 12-19-89

Construction Data		Depth in Feet	Geologic/Hydrologic Data	
Description	Diagram		Diagram Litho.	Lithologic Description
		5		MUDDY SANDY GRAVEL
154' 1/4" OF 10" CARBON		10		SANDY GRAVEL
STEEL CASING (REMOVED)		15		" "
CEMENT GROUT		20		" "
		25		" "
253' 7/8" OF 8" CARBON		30		" "
STEEL CASING (REMOVED)		35		GRAVELLY SAND
		40		SAND
		45		"
227.77'		50		"
4" DIA. STAINLESS STEEL CASING		55		"
		60		"
		65		SLIGHTLY GRAVELLY SAND
		70		" " "
		75		SAND
		80		SLIGHTLY GRAVELLY SAND
		85		GRAVELLY SAND
		90		SLIGHTLY GRAVELLY SAND
		95		SLIGHTLY MUDDY SAND
		100		SAND
		105		"
		110		"
		115		SLIGHTLY MUDDY SAND
		120		SAND
		125		"
		130		"
FACTORY INSTALLED CENTRALIZERS				

6650 0106136



AS-BUILT DIAGRAM

Well Number 299-E33-33Geologist GOODWIN JENSEN
BRANDENBERGERPage 2 of 2Reviewed by J. L. McLeanDate 12-19-89

Construction Data		Depth in Feet	Geologic/Hydrologic Data	
Description	Diagram		Diagram Litho.	Lithologic Description
154' 1/2" OF 10" CARBON		135		SLIGHTLY GRAVELLY SAND
STEEL CASING WITH DRIVE		140		" " "
SHOE (REMOVED)		145		" " "
		150		SAND
227.77'		155		SLIGHTLY GRAVELLY SAND
4" DIA. STAINLESS STEEL		160		157' MUD 3" THICK
CASING		165		" " "
		170		SL. GRAVELLY MUDDY SAND
		175		SLIGHTLY MUDDY SAND
		180		" " "
FACTORY INSTALLED		185		MUDDY SAND
CENTRALIZERS		190		SL. GRAVELLY MUDDY SAND
		195		" " "
8-20 BENTONITE CRUMBLES		200		GRAVELLY MUDDY SAND
		205		SAND
		210		MUDDY SAND
		215		SAND
		220		MUDDY SANDY GRAVEL
1/4" VOLCLAY PELLETS		225		" " "
		230		" " "
		235		" " "
20-40 CO. SILICA SAND		240		" " "
		245		" " "
21" STAINLESS STEEL, 4"		250		" " "
10-SLOT CHANNEL PACK		252'		HIT BASALT @ 252'
		252'		

9313018.06

Aquifer Test Data

page 1 of 1
 Data for Well E33-33
 Pumping Well E33-33 DRN 91
 Observation Wells N/A

Location 200 east, E33-33

Type of Aquifer Test slug injection/with drawal

How Q Measured —

How W.L.'s Measured oil tape - L306.14, datalogger/transducer 3/11 259198

Rad Dist of From Pumping Well 2"

Meas. Point for W.L.'s Top of 6" casing

Elevation of Meas. Point —

Depth of Pump/Airpipe —

Pump On: date — time —

Pump Off: date — time —

Duration of Aquifer Test —

Time t = _____ at t' = 0					Water Level Data Static Water Level <u>235.45 below TOC</u>				Discharge		Recorded By	Comments
Day	Clock Time	t	t'	t/t'	Reading	Conversions or Corrections	Water Level	s or s'	Reading	Q		
9/27	1044										WEL	8' 5/8" length slug
	1047				235.45							0.24 ft in diameter
	1056				235.45							
	11:22				transducer set for 16.19 ft							X D
					test 0 = drop slug							
	11:25				16.19							X D
	11:29				16.18	Reference						X D
	11:35				slug dropped							
	11:46				-10.1	slug fully recovered						X D
	11:56				stopped test							
					test 1 = test 0 redone dropped slug							
					test 2 =							
	1207				16.18	Reference						
					test 2 = full slugy test							
	12:50				16.17	Reference						X D
	2:53				pulled slug							
					Photo logs scanned #							1KB-701
	13:15				1 Boiler Volume Barreled = 1500 - sandy water							
	13:17				2nd Boiler Volume Barreled = 1500							
	13:26				2 Boiler Volumes							
✓					249.3 + 2.5 steel tape							Depth to bottom
					= 251.8' below TOC is depth to bottom							
William E. Cronin												
9/27/89												

Location 200 East, B Tank Farm Date of Test 9/27/89
 Well Number 299-E33-33 Procedure Number PNL-Ma-567 AT-6, Rev 0
 Type of Test(s) Slug Injection / Withdrawal
 Personnel Conducting Test Darrell Newcomer, Bill Cronin, Darrell Ludke (KEH)

WELL CONFIGURATION

Well Depth 248.8' below cement pad Borehole Diameter 8"
 Well Casing Inside Diameter 4" Well Screen Inside Diameter 4"
 Length of Screened Interval 17' (below water) Depth of Screen 227'-248'
 Comments Slug test conducted in undeveloped well

SLUG INFORMATION

Slug Construction Materials Carbon steel
 Length of Slug 8.05' Diameter of Slug 0.24'
 Comments _____
 Volume of Attachments (if applicable) _____

MEASUREMENT EQUIPMENT INFORMATION


	Make	Model	Serial Number
Electric Tape			
Steel Tape	Lufkin	Super Hi-Way Nubian	L 300-14
Data logger	In Situ	SE1000 B	1KB-701
Transducer	Druck	PTX-161D	259198
Other			

Darrell Newcomer 9/27/89

9313018.06

9313018.06

Equipment Record Form for the Installation and Removal of Data Loggers and Pressure Transducers

Initial Check: <i>ok</i>		
Purpose of Installation: <i>To monitor slug injection/withdrawal test responses</i>		
Monitored Hydrologic Unit or Water Body: <i>Uppermost Unconfined Aquifer (Hanford formation)</i>		
Date/Time of Installation: <i>9/27/89 1100 hrs</i>	Procedure Followed: <i>PXL-MH-567 WL-4, Rev 0</i>	
Data Logger Make/Model: <i>In Situ / SE1000 B</i>		
Serial No.: <i>1 KB-701</i>	Number of Channels Used: <i>1</i>	
Pressure Transducer Make/Model: <i>DRUCK / PTX-161D</i>	Full Scale Range: <i>10 psi</i>	Well No.: <i>299-E33-33</i>
	Serial No.: <i>257198</i>	Depth: <i>~2486 below cement,</i>
Pressure Transducer Make/Model:	Full Scale Range:	Well No.:
	Serial No.:	Depth:
Description of Data Logger Installation and Well Head Configuration:  <i>Stickup of 6" casing is ~3 feet.</i>		
Comments: <i>Slug was positioned into place above the water before placing the transducer down the well</i>		
Equipment Installed By <i>D.R. Newcomer, Bill Cronin</i>		
Date/Time of Equipment Removal: <i>9/27/89 1300 hrs.</i>		
Decontamination Procedure (if required):		
Equipment Removed By <i>Darrell R. Newcomer, Bill Cronin,</i>		

Darrell Newcomer 9/27/89

9313018.0603

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 9/27/89 11:35
DATE AND END TIME OF DATA ACQUISITION 9/27/89 11:55
WELL NUMBER E 33-33
TYPE OF TEST OR DATA Slug
TYPE AND IDENTIFICATION NUMBER OF DATA LOGGER In situ
Hermet Serial # 1KB-701
TEST NUMBER 0
CHANNEL OR INPUT NUMBER 1
UNITS OF VALUES RECORDED FT
NUMBER OF PAGES ATTACHED 2
COMMENTS: Test 0 = Submerging slug

DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

William E Cronin, Hydrologist
Name, title

9/28/89
Date

Well: 299-E33-33
 Test Date: September 27, 1989
 Start Time: 11:35

SE1000B
 Environmental Logger
 09/28 08:59

Unit# 00701 Test# 0

INPUT 1: Level (F)

Reference 0.00
 Scale factor 9.98
 Offset - 0.01

Elapsed Time, min	Value, ft
0.0000	- 0.01
0.0033	- 0.01
0.0066	- 0.01
0.0099	- 0.01
0.0133	- 0.01
0.0166	- 0.01
0.0200	- 0.00
0.0233	- 0.97
0.0266	0.52
0.0300	1.25
0.0333	1.19
0.0500	0.49
0.0666	- 0.00
0.0833	- 0.01
0.1000	- 0.00
0.1166	- 0.00
0.1333	- 0.00
0.1500	- 0.00
0.1666	- 0.00
0.1833	- 0.00
0.2000	- 0.00
0.2166	- 0.00
0.2333	- 0.00
0.2500	- 0.00
0.2666	- 0.00
0.2833	- 0.00
0.3000	- 0.00
0.3166	- 0.00
0.3333	- 0.00
0.4167	- 0.00
0.5000	- 0.00

0.5833	- 0.01
0.6667	- 0.01
0.7500	- 0.01
0.8333	- 0.01
0.9167	- 0.01
1.0000	- 0.01
1.0833	- 0.01
1.1667	- 0.01
1.2500	- 0.01
1.3333	- 0.01
1.4166	- 0.01
1.5000	- 0.01
1.5833	- 0.01
1.6667	- 0.01
1.7500	- 0.01
1.8333	- 0.01
1.9167	- 0.01
2.0000	- 0.01
2.5000	- 0.01
3.0000	- 0.01
3.5000	- 0.01
4.0000	- 0.01
4.5000	- 0.01
5.0000	- 0.01
5.5000	- 0.01
6.0000	- 0.01
6.5000	- 0.01
7.0000	- 0.01
7.5000	- 0.01
8.0000	- 0.01
8.5000	- 0.01
9.0000	- 0.01
9.5000	- 0.01
10.0000	- 0.01
12.0000	- 0.01
14.0000	- 0.01
16.0000	- 0.01
18.0000	- 0.01
20.0000	- 0.02

END

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 9/27/89 12:10DATE AND END TIME OF DATA ACQUISITION 9/27/89 12:20WELL NUMBER E 33 - 33TYPE OF TEST OR DATA SlugTYPE AND IDENTIFICATION NUMBER OF DATA LOGGER In Situ
Hermit, serial # 1KB-701TEST NUMBER 1CHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED f+NUMBER OF PAGES ATTACHED 2

COMMENTS: We wanted to drop the
slug again to make sure that
the transducer + data logger were
working properly. test 1 = submerging slug

DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

Nathan E. Crain, Psychologist 9/28/89
Name, title Date

Well: 299-E33-33
 Test Date: September 27, 1989
 Start Time: 12:10

SE1000B
 Environmental Logger
 09/28 09:01

Unit# 00701 Test# 1

INPUT 1: Level (F)

Reference 0.00
 Scale factor 9.98
 Offset - 0.01

Elapsed Time, Value,
 min ft

0.0000	0.08
0.0033	0.05
0.0066	0.03
0.0099	0.01
0.0133	0.39
0.0166	0.28
0.0200	0.18
0.0233	0.39
0.0266	0.36
0.0300	0.46
0.0333	0.45
0.0500	0.58
0.0666	0.50
0.0833	0.25
0.1000	- 1.37
0.1166	- 0.07
0.1333	0.03
0.1500	0.00
0.1666	0.01
0.1833	0.00
0.2000	0.00
0.2166	0.00
0.2333	0.00
0.2500	0.00
0.2666	0.00
0.2833	0.00
0.3000	0.00
0.3166	0.00
0.3333	0.00
0.4167	0.00
0.5000	0.00

0.5833	0.00
0.6667	0.00
0.7500	0.00
0.8333	0.00
0.9167	0.00
1.0000	0.00
1.0833	0.00
1.1667	0.00
1.2500	0.00
1.3333	0.00
1.4166	0.00
1.5000	0.00
1.5833	0.00
1.6667	0.00
1.7500	0.00
1.8333	- 0.00
1.9167	0.00
2.0000	0.00
2.5000	0.00
3.0000	0.00
3.5000	- 0.00
4.0000	- 0.00
4.5000	- 0.00
5.0000	- 0.00
5.5000	- 0.00
6.0000	- 0.00
6.5000	- 0.00
7.0000	- 0.00
7.5000	- 0.00
8.0000	- 0.00
8.5000	- 0.00
9.0000	- 0.00
9.5000	- 0.00
10.0000	- 0.00

END

931301B.0607

931301B.0607

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 9/27/87 12:53DATE AND END TIME OF DATA ACQUISITION 9/27/89 13:03WELL NUMBER 1E33-33TYPE OF TEST OR DATA slugTYPE AND IDENTIFICATION NUMBER OF DATA LOGGER Ch. Lata
Hermit, serial # 1KB-701TEST NUMBER 2CHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED ftNUMBER OF PAGES ATTACHED 2COMMENTS: Test 2 = Lifting slug.DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

William E. Cronin, Hydrologist 9/28/89
Name, title Date

Well: 299-E33-33
 Test Date: September 27, 1989
 Start Time: 12:53

SE1000B
 Environmental Logger
 09/28 09:04

Unit# 00701 Test# 2

INPUT 1: Level (F)

Reference 0.00
 Scale factor 9.98
 Offset - 0.01

Elapsed Time, Value,
 min ft

0.0000	- 1.07
0.0033	- 1.07
0.0066	- 1.10
0.0099	- 1.16
0.0133	- 1.19
0.0166	- 1.00
0.0200	- 0.86
0.0233	- 0.72
0.0266	- 0.60
0.0300	- 0.50
0.0333	- 0.41
0.0500	- 0.14
0.0666	- 0.03
0.0833	0.01
0.1000	0.03
0.1166	0.03
0.1333	0.04
0.1500	0.04
0.1666	0.04
0.1833	0.04
0.2000	0.04
0.2166	0.04
0.2333	0.04
0.2500	0.04
0.2666	0.04
0.2833	0.04
0.3000	0.04
0.3166	0.04
0.3333	0.04
0.4167	0.04
0.5000	0.04


0.5833	0.03
0.6667	0.03
0.7500	0.03
0.8333	0.03
0.9167	0.03
1.0000	0.03
1.0833	0.03
1.1667	0.03
1.2500	0.03
1.3333	0.03
1.4166	0.03
1.5000	0.03
1.5833	0.03
1.6667	0.03
1.7500	0.02
1.8333	0.02
1.9167	0.02
2.0000	0.02
2.5000	0.02
3.0000	0.02
3.5000	0.02
4.0000	0.02
4.5000	0.02
5.0000	0.02
5.5000	0.01
6.0000	0.01
6.5000	0.01
7.0000	0.01
7.5000	0.01
8.0000	0.01
8.5000	0.01
9.0000	0.01
9.5000	0.01
10.0000	0.01


END

9313018.1609

9313018.1609

H.13





WELL 299-E33-33, SLUG WITHDRAWAL TEST #2

 THE BELOW HYDRAULIC CONDUCTIVITY VALUE WAS CALCULATED
 USING THE BOUWER AND RICE SLUG TEST METHOD.

SOURCE= "THE BOUWER AND RICE SLUG TEST-AN UPDATE"
 GROUND WATER, VOL 27, NO. 3, MAY-JUNE 1989.

 RADIUS OF CASING USED IN CALCULATIONS HAS BEEN
 CORRECTED FOR THE THICKNESS OF GRAVEL OR SAND
 PACK DUE TO WATER LEVEL CHANGES IN THE SCREEN OR
 OPEN INTERVAL OF WELL.

Rc (ft)	Rw (ft)	Le (ft)	Lw (ft)	H (ft)
.2297	.3333	17.0000	17.0000	20.0000

Le/Rw = 51.0000000
 A= 3.1242380
 B= 5.126348E-001
 C= 2.7365890
 SANDPACK POROSITY= 3.000000E-001
 t (min)= 1.000000E-002
 1/t= 100.0000000
 Yo= (ft) 1.2000000
 Yt= (ft) 7.100000E-001
 1/t ln(Yo/Yt)= 52.4811900
 ln[(H-Lw)/Rw]= 2.1972250
 ln(Re/Rw)= 2.7539590

K (ft/day) = 323.0699000

T OF THE SATURATED SCREEN INTERVAL
 (ft2/day)= 5492.1880000

9313018.0613

APPENDIX I

TEST DATA AND ANALYSIS FOR WELL 299-W10-15

9313018.0613

APPENDIX I

TEST DATA AND ANALYSIS FOR WELL 299-W10-15

This appendix contains the as-built diagram for the well construction, Slug Test Record Form, Aquifer Test Data Sheets, Equipment Record Forms, Electronic Data Control Forms, and accompanying data logs and plots for well 299-W10-15.

9313013.06"

9313013.06"



AS-BUILT DIAGRAM

Well Number 299-W 10-15 Geologist BJORNSTAD, GILMORE Page 1 of 2
TEEL, AIRMAIT, GOODWIN, ETC.
 Reviewed by J. E. McShane Date 12-7-89

Construction Data		Depth in Feet	Geologic/Hydrologic Data	
Description	Diagram		Diagram Litho.	Lithologic Description
10' temporary casing - steel casing to 140'		5		Muddy sand ^{DB} drilling
		10		
		15		
		20		Sandy gravel
		25		
		30		Sand w/mud layers
		35		Sandy gravel
		40		Gravel
		45		Muddy sandy gravel
		50		
		55		Sandy gravel
		60		
		65		
		70		Gravelly sand
		75		Silty fn sand, laminated
		80		
		85		Muddy sand, calcareous dark brown
		90		
		95		76' switch to HT
		100		Cal. etc - calcareous cemented muddy sand
		105		
		110		
		115		
		120		
		125		

9313018.1615



AS-BUILT DIAGRAM

Well Number 299-W10-15 Geologist BJORNSTAD, GILMORE Page 2 of 2

TEEL, AIRHAULT, GOODWIN, ETC.

Reviewed by V.L. McShane

Date 12-7-89

Construction Data		Depth in Feet	Geologic/Hydrologic Data	
Description	Diagram		Diagram Litho.	Lithologic Description
		130		Caliche Δ gravels @ 132'
8" temporary carbon-steel casing to 222		150		Muddy Sandy Gravel
222.25' of type 304 4" stainless steel casing		175		Sand GRAVELLY SAND SANDY GRAVEL
21' OF 10 SLOT CONTINUOUS WRAP STAINLESS STEEL CHANNEL PACK SCREEN		200		
14-20 Mesh Col Silica Sand		220		DRILL DEPTH = 222.34'
				COMPLETION DEPTH = 221.95'
Volclay Pellets				
8-20 bentonite Crumbles				
Volclay Pure Gold Slurry				
Cement				

Data for Well 299-W10-15

Pumping Well -

Observation Wells - _____

Location 200 West, T Tank Farm

Type of Aquifer Test Slug Test

How Q Measured _____

How W.L.'s Measured Transducer, Steel tape #L500-03

Rad / Dist (of) From Pumping Well 2 "

Meas. Point for W.L.'s Top of 10" casing

Elevation of Meas. Point _____

Top of casing is 6' 8" above land surface

Depth of Pump/Airpipe 1

Pump On: date time

Pump Off: date time

Duration of Aquifer Test

Time		Water Level Data					Discharge		Recorded By	Comments
t = _____ at t' = 0		Static Water Level <u>212.71' below TOL</u>								
Day	Clock Time	t	t'	t/t'	Reading	Conversions or Corrections	Water Level	s or s	Reading	Q
11/3	1105				212.71					DRN
	1110				D/B = 226.2 + 2.47 = 228.67'					
	1130				Set slug and transducer in well					
	1135				15.94					↓ Transducer reading
					Set slug below water and allow water level to stabilize					
	1141				15.99	Set Ref = 0	Test #2			DRN
	1145				Pull slug (at log 1 cycle)					
	1158				Stop datalogger					Dump data to disk file: W10-15-2.SLG
	1234				16.00	Set Ref = 0	Test #3			
	1237				Pull slug (after log 1 cycle)					
✓	1248				Stop datalogger					↓ Dump data to disk file: W10-15-3.SLG

Darrell Newcomer 11/3/89

Darrell Newcomes 11/3/89

216-310-3333

Location 200 West, T Farm Date of Test 11/3/89
 Well Number 299-W10-15 Procedure Number PNL-MA-567 AT-6, Rev. 0
 Type of Test(s) Slug Test
 Personnel Conducting Test D. R. Newcomer, Darrell Ludke (KEH)

WELL CONFIGURATION

Well Depth ~222' b.l.s. Borehole Diameter 8"
 Well Casing Inside Diameter 4" Well Screen Inside Diameter 4"
 Length of Screened Interval ~15.8' below water Depth of Screen 200.8' to 221.8' b.l.s.
 Comments Well is undeveloped

SLUG INFORMATION


Slug Construction Materials Carbon steel
 Length of Slug 6.0' Diameter of Slug 2 1/4"
 Comments _____
 Volume of Attachments (if applicable) _____

MEASUREMENT EQUIPMENT INFORMATION

	Make	Model	Serial Number
Electric Tape			
Steel Tape	Lufkin	Super Hi-way Nubian	LS80-03
Data logger	In Situ	Hermit	1KB-700
Transducer	Druck	PTX-161D	259198
Other			

9313018.06

Equipment Record Form for the Installation and Removal of Data Loggers and Pressure Transducers

Initial Check: <i>OK</i>		
Purpose of Installation: <i>To monitor water levels during the slug test</i>		
Monitored Hydrologic Unit or Water Body: <i>Saturated screen interval within the upper part of the aquifer</i>		
Date/Time of Installation: <i>11/3/89 1130 hrs.</i>	Procedure Followed: <i>PNL-MA-567 WL-4, Rev 0</i>	
Data Logger Make/Model: <i>In Situ / Hermit SE1000B</i>		
Serial No.: <i>1KB-700</i>	Number of Channels Used: <i>1</i>	
Pressure Transducer Make/Model: <i>Druck / PTX-161D</i>	Full Scale Range: <i>10 psi</i>	Well No.: <i>299-W10-15</i>
	Serial No.: <i>259198</i>	Depth: <i>~222' b.l.s.</i>
Pressure Transducer Make/Model:	Full Scale Range:	Well No.:
	Serial No.:	Depth:
Description of Data Logger Installation and Well Head Configuration: 		
Comments: <i>Well has not been completed in the upper 75 ft. The 10" casing is not completely pulled out.</i> <i>The slug was placed a few feet above static water level before the transducer was lowered to the bottom of the well. The slug was then lowered below static and water level was allowed to stabilize.</i>		
Equipment Installed By <i>D. R. Newcomer</i>		
Date/Time of Equipment Removal: <i>11/3/89 1300 hrs.</i>		
Decontamination Procedure (if required):		
Equipment Removed By <i>D.R. Newcomer</i>		

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 11/3/89 1145 hrs.DATE AND END TIME OF DATA ACQUISITION 11/3/89 1157 hrs.WELL NUMBER 299-W10-15TYPE OF TEST OR DATA Slug TestTYPE AND IDENTIFICATION NUMBER OF DATA LOGGER In Situ Hermit
SE1000B S/N 1KB-700TEST NUMBER 2CHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED ftNUMBER OF PAGES ATTACHED 2

COMMENTS:

Test #2 = WithdrawalDATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

Darrell Newcomer, Scientist
Name, title11/3/89
Date

Well: 299-W10-15
Test Date: November 3, 1989
Start Time: 11:45

SE1000B
Environmental Logger
11/03 12:01

Unit# 00700 Test# 2

INPUT 1: Level (F)

Reference 0.00
Scale factor 9.99
Offset 0.01

Elapsed Time, min	Value, ft
0.0000	0.00
0.0033	0.00
0.0066	- 7.52
0.0099	0.15
0.0133	- 2.34
0.0166	- 0.89
0.0200	- 0.82
0.0233	- 0.83
0.0266	- 2.28
0.0300	- 1.97
0.0333	- 1.86
0.0500	- 1.68
0.0666	- 1.55
0.0833	- 1.43
0.1000	- 1.30
0.1166	- 1.19
0.1333	- 1.08
0.1500	- 0.99
0.1666	- 0.90
0.1833	- 0.82
0.2000	- 0.75
0.2166	- 0.69
0.2333	- 0.63
0.2500	- 0.57
0.2666	- 0.52
0.2833	- 0.48
0.3000	- 0.44
0.3166	- 0.41
0.3333	- 0.37
0.4167	- 0.24
0.5000	- 0.16

0.5833	- 0.11
0.6667	- 0.07
0.7500	- 0.04
0.8333	- 0.02
0.9167	- 0.01
1.0000	- 0.00
1.0833	0.00
1.1667	0.00
1.2500	0.01
1.3333	0.01
1.4166	0.01
1.5000	0.02
1.5833	0.03
1.6667	0.03
1.7500	0.03
1.8333	0.03
1.9167	0.04
2.0000	0.04
2.5000	0.05
3.0000	0.05
3.5000	0.05
4.0000	0.05
4.5000	0.05
5.0000	0.05
5.5000	0.05
6.0000	0.05
6.5000	0.05
7.0000	0.05
7.5000	0.05
8.0000	0.05
8.5000	0.05
9.0000	0.05
9.5000	0.05
10.0000	0.05
12.0000	0.05

END

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 11/3/89 1237 hrs.DATE AND END TIME OF DATA ACQUISITION 11/3/89 1247 hrs.WELL NUMBER 299-W10-15TYPE OF TEST OR DATA Slug TestTYPE AND IDENTIFICATION NUMBER OF DATA LOGGER In Situ
Hermit SE1000 B S/N 1KB-700TEST NUMBER 3CHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED ft.NUMBER OF PAGES ATTACHED 2

COMMENTS:

Test #3 = withdrawal TestDATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

Darrell Newcomer, Scientist
Name, title11/3/89
Date

Well: 299-W10-15
 Test Date: November 3, 1989
 Start Time: 12:37

SE1000B
 Environmental Logger
 11/03 12:52

Unit# 00700 Test# 3

INPUT 1: Level (F)

Reference 0.00
 Scale factor 9.99
 Offset 0.01


Elapsed Time, Value,
 min ft

0.0000	0.00
0.0033	0.00
0.0066	0.00
0.0099	- 15.19
0.0133	- 0.43
0.0166	- 1.64
0.0200	- 1.51
0.0233	- 0.32
0.0266	- 0.76
0.0300	- 1.87
0.0333	- 1.93
0.0500	- 1.67
0.0666	- 1.51
0.0833	- 1.37
0.1000	- 1.24
0.1166	- 1.14
0.1333	- 1.04
0.1500	- 0.93
0.1666	- 0.85
0.1833	- 0.77
0.2000	- 0.70
0.2166	- 0.64
0.2333	- 0.58
0.2500	- 0.52
0.2666	- 0.47
0.2833	- 0.43
0.3000	- 0.39
0.3166	- 0.35
0.3333	- 0.32
0.4167	- 0.20
0.5000	- 0.13

0.5833	- 0.08
0.6667	- 0.05
0.7500	- 0.02
0.8333	- 0.01
0.9167	0.00
1.0000	0.00
1.0833	0.01
1.1667	0.02
1.2500	0.02
1.3333	0.03
1.4166	0.03
1.5000	0.03
1.5833	0.04
1.6667	0.04
1.7500	0.04
1.8333	0.04
1.9167	0.05
2.0000	0.05
2.5000	0.05
3.0000	0.05
3.5000	0.05
4.0000	0.05
4.5000	0.05
5.0000	0.05
5.5000	0.05
6.0000	0.05
6.5000	0.05
7.0000	0.05
7.5000	0.05
8.0000	0.05
8.5000	0.05
9.0000	0.05
9.5000	0.05
10.0000	0.05


END

9313018.062"



I.11

9313018.062"



WELL 299-W10-15, SLUG WITHDRAWAL TEST #2

 THE BELOW HYDRAULIC CONDUCTIVITY VALUE WAS CALCULATED
 USING THE BOUWER AND RICE SLUG TEST METHOD.

SOURCE= "THE BOUWER AND RICE SLUG TEST-AN UPDATE"
 GROUND WATER, VOL 27, NO. 3, MAY-JUNE 1989.

RADIUS OF CASING USED IN CALCULATIONS HAS BEEN
 CORRECTED FOR THE THICKNESS OF GRAVEL OR SAND
 PACK DUE TO WATER LEVEL CHANGES IN THE SCREEN OR
 OPEN INTERVAL OF WELL.

Rc (ft)	Rw (ft)	Le (ft)	Lw (ft)	H (ft)
-----	-----	-----	-----	-----
.2297	.3333	15.8000	15.8000	275.0000

Le/Rw = 47.4000000

A= 3.0284980

B= 4.921462E-001

C= 2.6137240

SANDPACK POROSITY= 3.000000E-001

t (min)= 2.000000E-001

1/t= 5.0000000

Yo= (ft) 2.1500000

Yt= (ft) 7.300000E-001

1/t ln(Yo/Yt)= 5.4008930

ln[(H-Lw)/Rw]= 6.0000000


ln(Re/Rw)= 2.4315210


K (ft/day) = 31.5842200

T OF THE SATURATED SCREEN INTERVAL

(ft²/day)= 499.0307000

9313018.1626





1.15

ooooo WELL 299-W10-15, SLUG WITHDRAWAL TEST #3

Y_o PROJECTED = 2.13 ft
 Y_o OBSERVED = 1.93 ft


$r_c = 0.2297$ ft

LINEAR BEST FIT LINE; $\log_{10}(Y) = -2.53x + 0.33$

$$K = (r_c^2 \ln(R_e/r_w) / 2L_e t) + \ln(Y_o/Y_t)$$

$$K = ((0.2297)^2 (2.43) / 2(15.8)(0.20)) + \ln(2.13/0.66)$$

$$K = 34 \text{ ft/day}$$



WELL 299-W10-15, SLUG WITHDRAWAL TEST #3

 THE BELOW HYDRAULIC CONDUCTIVITY VALUE WAS CALCULATED
 USING THE BOUWER AND RICE SLUG TEST METHOD.

SOURCE= "THE BOUWER AND RICE SLUG TEST-AN UPDATE"
 GROUND WATER, VOL 27, NO. 3, MAY-JUNE 1989.


 RADIUS OF CASING USED IN CALCULATIONS HAS BEEN
 CORRECTED FOR THE THICKNESS OF GRAVEL OR SAND
 PACK DUE TO WATER LEVEL CHANGES IN THE SCREEN OR
 OPEN INTERVAL OF WELL.

Rc (ft)	Rw (ft)	Le (ft)	Lw (ft)	H (ft)
.2297	.3333	15.8000	15.8000	275.0000

Le/Rw = 47.4000000
 A= 3.0284980
 B= 4.921462E-001
 C= 2.6137240
 SANDPACK POROSITY= 3.000000E-001
 t (min)= 2.000000E-001
 1/t= 5.0000000
 Yo= (ft) 2.1300000
 Yt= (ft) 6.600000E-001
 1/t ln(Yo/Yt)= 5.8581870
 ln[(H-Lw)/Rw]= 6.0000000
 ln(Re/Rw)= 2.4315210

K (ft/day) = 34.2584600

T OF THE SATURATED SCREEN INTERVAL
 (ft2/day)= 541.2836000



APPENDIX J

TEST DATA AND ANALYSIS FOR WELL 299-W10-16

9313018.062

THIS PAGE INTENTIONALLY
LEFT BLANK

2025-01-16 10:18:18

APPENDIX J

TEST DATA AND ANALYSIS FOR WELL 299-W10-16

This appendix contains the as-built diagram for the well construction, Slug Test Record Form, Aquifer Test Data Sheets, Equipment Record Forms, Electronic Data Control Forms, and accompanying data logs and plots for well 299-W10-16.

20100315



AS-BUILT DIAGRAM

Well Number 299-W10-16 Geologist BLEGEN, BIRCH, TEEL, Page 1 of 2
BJORNSTAD, GILMORE, GOODWIN
 Reviewed by [Signature] Date 12-4-89

Construction Data		Depth in Feet	Geologic/Hydrologic Data	
Description	Diagram		Diagram Litho.	Lithologic Description
132' 11" OF 10" CARBON STEEL CASING		5		SAND
		10		MUDDY SAND
		15		MUDDY SANDY GRAVEL
		20		" " "
		25		GRAVEL
		30		MUDDY SANDY GRAVEL
		35		GRAVEL
		40		"
200.4' OF 4" STAINLESS STEEL CASING		45		"
		50		MUDDY SANDY GRAVEL
		55		SLIGHTLY GRAVELLY SAND
		60		GRAVELLY MUDDY SAND
		65		SLIGHTLY GRAVELLY SAND
		70		SAND
		75		"
		80		SLIGHTLY GRAVELLY SAND
		85		MUDDY SAND
		90		SANDY MUD
		95		SLIGHTLY GRAVELLY MUDDY SAND
		100		GRAVELLY MUDDY SAND
		105		" " "
		110		SANDY MUD
		115		"
		120		"
		125		SLIGHTLY MUDDY SAND
		130		SANDY GRAVEL

9313018-1634



AS-BUILT DIAGRAM

Well Number 299-W10-16 Geologist BLEGEN BIRCH TEEL Page 2 of 2
BJORNSTAD, GILMORE, GROWING
Reviewed by V.L. McShane Date 12-4-89

Construction Data		Depth in Feet	Geologic/Hydrologic Data	
Description	Diagram		Diagram Litho.	Lithologic Description
132' 11" of 10" CARBON STEEL CASING		135		MUDDY SANDY GRAVEL
		140		SANDY GRAVEL
		145		MUDDY SANDY GRAVEL
223' 0" of 8" CARBON STEEL CASING		150		" " "
		155		" " "
		160		SANDY GRAVEL
200.4' of 4" STAINLESS STEEL CASING		165		" "
		170		MUDDY SANDY GRAVEL
		175		SANDY GRAVEL
		180		" "
		185		" "
		190		MUDDY SANDY GRAVEL
		195		" " "
		200		SANDY GRAVEL
21' OF 10 SLOT CONTINUOUS WRAP STAINLESS STEEL CHANNEL PACK SCREEN		205		D/W 202.9' 10/25/89
		210		" "
		215		" "
		219		" "
				DRILLED DEPTH = 219.4'
				COMPLETION DEPTH = 219.8'
COMPLETION SYMBOLS:				
CEMENT GROUT				
GRANULAR BENTONITE				
BENTONITE PELLETS				
SILICA SAND				
CASING JOINT				
CASING CENTRALIZER				

Aquifer Test Data WHC-SD-EN-TI-147, Rev. 0

page 1 of 1

Pumping Well

Observation Wells

Type of Aquifer Test Slug Test

How Q Measured —

How W.L.'s Measured Transducer Steel Tape # L500-03

Depth of Pump/Airpipe

Rad./Dist. of From Pumping Well: 2"

Pump On: date time

Meas. Point for W.L.'s Top of 4" casing (1.6' a.l.s.)

Pump Off: date time

Elevation of Meas. Point _____

Duration of Aquifer Test. —[illegible]

10/31/89

Location 2-West, T Tank Farm Date of Test 10/30/89
 Well Number 299-W10-16 Procedure Number PNL-MA-567
AT-6, Rev 0
 Type of Test(s) Slug injection / withdrawal
 Personnel Conducting Test D.R. Newcomer, Darrell Ludke (KEH driller)

WELL CONFIGURATION

Well Depth 219.8' b/s Borehole Diameter 8"
 Well Casing Inside Diameter 4" Well Screen Inside Diameter 4"
 Length of Screened Interval ~~210'~~ 16.4' (below) Depth of Screen 219.3' b/s - 199.3' b/s
 Comments Well is undeveloped

SLUG INFORMATION

Slug Construction Materials Carbon Steel
 Length of Slug 6.0' Diameter of Slug 2 1/4"
 Comments _____
 Volume of Attachments (if applicable) _____


MEASUREMENT EQUIPMENT INFORMATION

	Make	Model	Serial Number
Electric Tape			
Steel Tape	Lufkin	Super Hi-way Nubian	L506-03
Data logger	In Situ	Hermit SE 1000B	1KB-700
Transducer	Druck	PTX-161D	259198
Other			

Darrell Newcomer 10/30/89

9313018.06

Equipment Record Form for the Installation and Removal of Data Loggers and Pressure Transducers

Initial Check: <i>OK</i>		
Purpose of Installation: <i>To monitor water levels during slug tests</i>		
Monitored Hydrologic Unit or Water Body: <i>Saturated screen interval within upper part of uppermost aquifer</i>		
Date/Time of Installation: <i>10/30/89 1325 hrs.</i>		Procedure Followed: <i>PNL-MA-567 WL-4, Rev 0</i>
Data Logger Make/Model: <i>In Situ / Hermit SE1000B</i>		
Serial No.: <i>1KB-700</i>	Number of Channels Used: <i>1</i>	
Pressure Transducer Make/Model: <i>Druck / PTX-161D</i>	Full Scale Range: <i>10 psi</i>	Well No.: <i>299-W10-16</i>
	Serial No.: <i>259198</i>	Depth: <i>219.9' below TOC (4" casing)</i>
Pressure Transducer Make/Model:	Full Scale Range:	Well No.:
	Serial No.:	Depth:
Description of Data Logger Installation and Well Head Configuration: 		
Comments: <i>slug was placed ~219' from top of 4" casing before dropping slug.</i>		
Equipment Installed By <i>D.R. Newcomer</i>		
Date/Time of Equipment Removal: <i>10/30/89 1420 hrs.</i>		
Decontamination Procedure (if required):		
Equipment Removed By <i>D.R. Newcomer</i>		

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 10/30/89 1340 hrs.DATE AND END TIME OF DATA ACQUISITION 10/30/89 1358 hrs.WELL NUMBER 299-W10-16TYPE OF TEST OR DATA Slug TestTYPE AND IDENTIFICATION NUMBER OF DATA LOGGER In Situ
Hermit SE1000B, S/N 1K8-700TEST NUMBER 2CHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED ftNUMBER OF PAGES ATTACHED 2COMMENTS:
Test #2 = Slug injection

DATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

Darrell Newcomes, Scientist 11/3/89
Name, title Date

Well: 299-W10-16
Test Date: October 30, 1989
Start Time: 13:40

SE1000B
Environmental Logger
10/30 14:00

Unit# 00700 Test# 2

INPUT 1: Level (F)

Reference 0.00
Scale factor 9.99
Offset 0.01

Elapsed Time, Value,
min ft

0.0000 2.89
0.0033 1.28
0.0066 2.62
0.0099 3.50
0.0133 3.07
0.0166 2.00
0.0200 2.63
0.0233 2.73
0.0266 2.96
0.0300 2.94
0.0333 2.48
0.0500 0.85
0.0666 0.82
0.0833 0.71
0.1000 0.63
0.1166 0.57
0.1333 0.50
0.1500 0.47
0.1666 0.38
0.1833 0.35
0.2000 0.31
0.2166 0.29
0.2333 0.26
0.2500 0.24
0.2666 0.23
0.2833 0.21
0.3000 0.20
0.3166 0.18
0.3333 0.17
0.4167 0.13
0.5000 0.11

0.5833 0.10
0.6667 0.09
0.7500 0.08
0.8333 0.08
0.9167 0.08
1.0000 0.07
1.0833 0.07
1.1667 0.07
1.2500 0.07
1.3333 0.06
1.4166 0.06
1.5000 0.06
1.5833 0.06
1.6667 0.06
1.7500 0.06
1.8333 0.06
1.9167 0.06
2.0000 0.06
2.5000 0.06
3.0000 0.05
3.5000 0.05
4.0000 0.05
4.5000 0.05
5.0000 0.05
5.5000 0.05
6.0000 0.05
6.5000 0.05
7.0000 0.05
7.5000 0.05
8.0000 0.05
8.5000 0.06
9.0000 0.06
9.5000 0.06
10.0000 0.06
12.0000 0.06
14.0000 0.06
16.0000 0.06
18.0000 0.06

END

9313018.0640

9313018.0640

(5/18/89, Rev. 0)

ELECTRONIC DATA CONTROL FORM

DATE AND START TIME OF DATA ACQUISITION 10/30/89 1407 hrs.DATE AND END TIME OF DATA ACQUISITION 10/30/89 1417 hrs.WELL NUMBER 299-W10-16TYPE OF TEST OR DATA Slug TestTYPE AND IDENTIFICATION NUMBER OF DATA LOGGER In SituHermit SE1000B, S/N 1KB-700TEST NUMBER ~~1~~^{DEV} 3CHANNEL OR INPUT NUMBER 1UNITS OF VALUES RECORDED ftNUMBER OF PAGES ATTACHED 2

COMMENTS:

Test 3 = slug withdrawalDATA VALIDATION STATEMENT:

The attached data represent the data as originally recorded on the data logger. Any exceptions and reasons for such are indicated in the comments section.

Darrell Newcomer, Scientist
Name, title11/3/89
Date

9313018.06

Well: 299-W10-16
 Test Date: October 30, 1989
 Start Time: 14:07

SE1000B
 Environmental Logger
 10/30 14:21

Unit# 00700 Test# 3

INPUT 1: Level (F)

Reference 0.00
 Scale factor 9.99
 Offset 0.01

Elapsed Time, Value,
 min ft


0.0000	0.00
0.0033	- 0.00
0.0066	- 0.00
0.0099	0.00
0.0133	- 8.46
0.0166	0.71
0.0200	0.41
0.0233	- 3.93
0.0266	- 0.11
0.0300	- 2.19
0.0333	- 0.55
0.0500	- 1.65
0.0666	- 1.61
0.0833	- 1.41
0.1000	- 1.27
0.1166	- 1.13
0.1333	- 1.02
0.1500	- 0.92
0.1666	- 0.83
0.1833	- 0.76
0.2000	- 0.69
0.2166	- 0.62
0.2333	- 0.57
0.2500	- 0.52
0.2666	- 0.47
0.2833	- 0.43
0.3000	- 0.39
0.3166	- 0.36
0.3333	- 0.33
0.4167	- 0.22
0.5000	- 0.15


0.5833	- 0.11
0.6667	- 0.07
0.7500	- 0.05
0.8333	- 0.04
0.9167	- 0.03
1.0000	- 0.02
1.0833	- 0.02
1.1667	- 0.01
1.2500	- 0.01
1.3333	- 0.01
1.4166	- 0.00
1.5000	- 0.00
1.5833	- 0.00
1.6667	- 0.00
1.7500	- 0.00
1.8333	0.00
1.9167	0.00
2.0000	0.00
2.5000	0.00
3.0000	0.00
3.5000	0.00
4.0000	0.01
4.5000	0.00
5.0000	0.01
5.5000	0.01
6.0000	0.01
6.5000	0.01
7.0000	0.00
7.5000	0.00
8.0000	0.01
8.5000	0.01
9.0000	0.01
9.5000	0.01
10.0000	0.01

END

9313018:0642

J.11





WELL 299-W10-16, SLUG INJECTION TEST #2

 THE BELOW HYDRAULIC CONDUCTIVITY VALUE WAS CALCULATED
 USING THE BOUWER AND RICE SLUG TEST METHOD.

SOURCE= "THE BOUWER AND RICE SLUG TEST-AN UPDATE"
 GROUND WATER, VOL 27, NO. 3, MAY-JUNE 1989.

 RADIUS OF CASING USED IN CALCULATIONS HAS BEEN
 CORRECTED FOR THE THICKNESS OF GRAVEL OR SAND
 PACK DUE TO WATER LEVEL CHANGES IN THE SCREEN OR
 OPEN INTERVAL OF WELL.

Rc (ft)	Rw (ft)	Le (ft)	Lw (ft)	H (ft)
.2297	.3333	16.4000	16.4000	275.0000

Le/Rw = 49.2000000

A= 3.0792260

B= 5.055397E-001

C= 2.6715220

SANDPACK POROSITY= 3.000000E-001

t (min)= 1.000000E-001

1/t= 10.0000000

Yo= (ft) 9.100000E-001

Yt= (ft) 4.400000E-001

1/t ln(Yo/Yt)= 7.2667000


ln[(H-Lw)/Rw]= 6.0000000

ln(Re/Rw)= 2.4595060

K (ft/day) = 41.4118800

T OF THE SATURATED SCREEN INTERVAL

(ft2/day)= 679.1549000



9313018.06117

○○○○○ WELL 299-W10-16, SLUG WITHDRAWAL TEST #3

 Y_o PROJECTED = 2.05 ft Y_o OBSERVED = 1.65 ft $r_e = 0.2297$ ftLINEAR BEST FIT LINE; $\log_{10}(Y) = -2.51x + 0.31$ $K = (r_e^2 \ln(R_e/r_w) / 2L_e t) * \ln(Y_o/Y_1)$ $K = ((0.2297)^2 (2.46) / 2(16.4)(0.20)) * \ln(2.05/0.65)$ $K = 33$ ft/dayWATER LEVEL CHANGE (Y_1), (ft) $Y_1 = 0.85$ ft $t = 0.2$ minTIME (t), (min)

J.15

MHC-SD-EN-TI-147, Rev. 0

9313018.06117

WELL 299-W10-16, SLUG WITHDRAWAL TEST #3

THE BELOW HYDRAULIC CONDUCTIVITY VALUE WAS CALCULATED
USING THE BOUWER AND RICE SLUG TEST METHOD.

SOURCE= "THE BOUWER AND RICE SLUG TEST-AN UPDATE"
GROUND WATER, VOL 27, NO. 3, MAY-JUNE 1989.


RADIUS OF CASING USED IN CALCULATIONS HAS BEEN
CORRECTED FOR THE THICKNESS OF GRAVEL OR SAND
PACK DUE TO WATER LEVEL CHANGES IN THE SCREEN OR
OPEN INTERVAL OF WELL.

Rc (ft)	Rw (ft)	Le (ft)	Lw (ft)	H (ft)
.2297	.3333	16.4000	16.4000	275.0000


Le/Rw = 49.2000000
A= 3.0792260
B= 5.055397E-001
C= 2.6715220
SANDPACK POROSITY= 3.000000E-001
t (min)= 2.000000E-001
1/t= 5.0000000
Yo= (ft) 2.0500000
Yt= (ft) 6.500000E-001
1/t ln(Yo/Yt)= 5.7431140
ln[(H-Lw)/Rw]= 6.0000000
ln(Re/Rw)= 2.4595060

K (ft/day) = 32.7291800

T OF THE SATURATED SCREEN INTERVAL
(ft²/day)= 536.7585000



Date Received: 4/7/93		INFORMATION RELEASE REQUEST		Reference: WHC-CM-3-4
Complete for all Types of Release				
Purpose <input type="checkbox"/> Speech or Presentation <input type="checkbox"/> Full Paper (Check only one suffix) <input type="checkbox"/> Summary <input type="checkbox"/> Abstract <input type="checkbox"/> Visual Aid <input type="checkbox"/> Speakers Bureau <input type="checkbox"/> Poster Session <input type="checkbox"/> Videotape		<input type="checkbox"/> Reference <input checked="" type="checkbox"/> Technical Report <input type="checkbox"/> Thesis or Dissertation <input type="checkbox"/> Manual <input type="checkbox"/> Brochure/Flier <input type="checkbox"/> Software/Database <input type="checkbox"/> Controlled Document <input type="checkbox"/> Other		ID Number (include revision, volume, etc.) WHC-SD-EN-TI-147, Rev. 0 List attachments. Date Release Required <p style="text-align: right;">4/9/93</p>
Title Hydrologic Testing at the Single-Shell Tanks, 1989			Unclassified Category UC-NA	Impact Level 4
New or novel (patentable) subject matter? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes If "Yes", has disclosure been submitted by WHC or other company? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes Disclosure No(s).		Information received from others in confidence, such as proprietary data, trade secrets, and/or inventions? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Identify)		
Copyrights? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes If "Yes", has written permission been granted? <input type="checkbox"/> No <input type="checkbox"/> Yes (Attach Permission)		Trademarks? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Identify)		
Complete for Speech or Presentation				
Title of Conference or Meeting NA		Group or Society Sponsoring NA		
Date(s) of Conference or Meeting NA	City/State NA	Will proceedings be published?	<input type="checkbox"/> Yes <input type="checkbox"/> No	
		Will material be handed out?	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	
Title of Journal NA				

CHECKLIST FOR SIGNATORIES				
view Required per WHC-CM-3-4	Yes	No	Reviewer - Signature Indicates Approval	
			Name (printed)	Signature Date
Classification/Unclassified/Controlled Nuclear Information	<input type="checkbox"/>	<input checked="" type="checkbox"/>	}	SW BERGIN <i>Sw Bergin</i> 4/12/93
Patent - General Counsel	<input checked="" type="checkbox"/>	<input type="checkbox"/>		
Legal - General Counsel	<input checked="" type="checkbox"/>	<input type="checkbox"/>		
Applied Technology/Export Controlled Information or International Program	<input type="checkbox"/>	<input checked="" type="checkbox"/>		
WHC Program/Project	<input type="checkbox"/>	<input checked="" type="checkbox"/>		
Communications	<input type="checkbox"/>	<input checked="" type="checkbox"/>		
RL Program/Project	<input type="checkbox"/>	<input checked="" type="checkbox"/>		
Publication Services	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	Approved per telecon w/ Katie Brown 4/13/93	
Other Program/Project	<input type="checkbox"/>	<input checked="" type="checkbox"/>		
Information conforms to all applicable requirements.			The above information is certified to be correct.	
References Available to Intended Audience	<input checked="" type="checkbox"/>	<input type="checkbox"/>	INFORMATION RELEASE ADMINISTRATION APPROVAL STAMP Stamp is required before release. Release is contingent upon resolution of mandatory comments. 	
Transmit to DOE-HQ/Office of Scientific and Technical Information	<input type="checkbox"/>	<input checked="" type="checkbox"/>		
Author/Requestor (Printed/Signature)		Date		
J.A. Caggiano <i>J.A. Caggiano</i>		4/6/93		
Intended Audience	<input type="checkbox"/> Internal <input type="checkbox"/> Sponsor <input checked="" type="checkbox"/> External			
sponsible Manager (Printed/Signature)	Date			
R.L. Jackson <i>R.L. Jackson</i>	4/4/93		Date Cancelled _____ Date Disapproved _____	