

0076183

D&D-35703  
Revision 0

# Cost Estimate for the Engineering Evaluation/Cost Analysis for BC Controlled Area Removal Action

Prepared for the U.S. Department of Energy  
Assistant Secretary for Environmental Management

Project Hanford Management Contractor for the  
U.S. Department of Energy under Contract DE-AC06-96RL13200

**FLUOR**<sup>®</sup>

*P.O. Box 1000*

*Richland, Washington*

**Approved for Public Release;  
Further Dissemination Unlimited**

# Cost Estimate for the Engineering Evaluation/Cost Analysis for BC Controlled Area Removal Action

B. J. Spilman  
Fluor Hanford, Inc.


Date Published  
November 2007

Prepared for the U.S. Department of Energy  
Assistant Secretary for Environmental Management

Project Hanford Management Contractor for the  
U.S. Department of Energy under Contract DE-AC06-96RL13200

**FLUOR**<sup>®</sup>

P.O. Box 1000  
Richland, Washington

 11/27/2007  
Release Approval Date

Approved for Public Release;  
Further Dissemination Unlimited

D&D-35703  
Revision 0

**TRADEMARK DISCLAIMER**

Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.

This report has been reproduced from the best available copy.

Printed in the United States of America

Date Received for Clearance Process (MM/DD/YYYY) 11/26/2007

## INFORMATION CLEARANCE FORM

**A. Information Category**

Abstract       Journal Article  
 Summary       Internet  
 Visual Aid       Software  
 Full Paper       Report  
 Other cost estimate

**B. Document Number** D&D 35703, Rev. 0

**C. Title**  
 Cost Estimate for the Engineering Evaluation/Cost Analysis for BC Controlled Area Removal Action

**D. Internet Address**

**E. Required Information (MANDATORY)**

1. Is document potentially Classified?  No  Yes  
G. J. McCleary *Gordon J. McCleary 11/15/07*  
 Manager Required (Print and Sign)

If Yes \_\_\_\_\_  
 ADC Required (Print and Sign)  No  Yes Classified

2. Official Use Only       No  Yes Exemption No. \_\_\_\_\_

3. Export Controlled Information       No  Yes OOU Exemption No. 3

4. UCNI       No  Yes

5. Applied Technology       No  Yes

6. Other (Specify) \_\_\_\_\_

**7. Does Information Contain the Following:**

a. New or Novel FH (Patentable) Subject Matter?  No  Yes  
 If "Yes", OOU Exemption No. 3  
 If "Yes", Disclosure No.: \_\_\_\_\_

b. Commercial Proprietary Information Received in Confidence, Such as Proprietary and/or Inventions?  
 No  Yes If "Yes", OOU Exemption No. 4

c. Corporate Privileged Information?       No  Yes  
 If "Yes", OOU Exemption No. 4

d. Government Privileged Information?       No  Yes  
 If "Yes", Exemption No. 5

e. Copyrights?       No  Yes If "Yes", Attach Permission.

f. Trademarks?       No  Yes If "Yes", Identify in Document.

8. Is Information requiring submission to OSTI?       No  Yes

9. Release Level?       Public  Limited

**F. Complete for a Journal Article**

1. Title of Journal \_\_\_\_\_

**G. Complete for a Presentation**

1. Title for Conference or Meeting \_\_\_\_\_

2. Group Sponsoring \_\_\_\_\_

3. Date of Conference \_\_\_\_\_

4. City/State \_\_\_\_\_

5. Will Information be Published in Proceedings?  No  Yes

6. Will Material be Handed Out?  No  Yes

**H. Information Owner/Author/Requestor**

B. J. Spilman *B. Spilman*  
 (Print and Sign)

**Responsible Manager**


G. J. McCleary *Gordon J. McCleary 11/15/07*  
 (Print and Sign)

Approval by Direct Report to FH President (Speech/Articles Only) \_\_\_\_\_  
 (Print and Sign)

I. Reviewers	Yes	Print	Signature	Public Y/N (If N, complete J)
General Counsel	<input checked="" type="checkbox"/>	S. B. Cherry	<i>S.B. Cherry</i>	<input checked="" type="radio"/> Y / N
Office of External Affairs	<input checked="" type="checkbox"/>	<i>D.J. Duran</i>	<i>D.J. Duran</i>	<input checked="" type="radio"/> Y / N
DOE-RL	<input type="checkbox"/>	_____	_____	Y / N
Other	<input checked="" type="checkbox"/>	J. D. Aardal	<i>Janis Aardal</i>	<input checked="" type="radio"/> Y / N
Other	<input type="checkbox"/>	_____	_____	Y / N

**J. Comments**

Information Owner Approval



If Additional Comments, Please Attach Separate Sheet

# ADMINISTRATIVE DOCUMENT PROCESSING AND APPROVAL

Page 1 of 1

<b>DOCUMENT TITLE:</b> Cost Estimate for the Engineering Evaluation/Cost Analysis for BC Controlled Area Removal Action	<b>OWNING ORGANIZATION/FACILITY:</b> FH Deactivation & Decommissioning Project
<b>Document Number:</b> D&D 35703	<b>Revision/Change Number:</b> 0

**DOCUMENT TYPE (Check Applicable)**

Plan   
  Report   
  Study   
  Description Document   
  Other cost estimate

**DOCUMENT ACTION**   
 New   
 Revision   
 Cancellation

**RESPONSIBLE CONTACTS**

Name	Phone Number
Author: B. J. Spilman	(509) 376-5105
Manager: G. J. McCleary	(509) 372-8385

**DOCUMENT CONTROL**

Does document contain scientific or technical information intended for public use?   
 Yes     No

Does document contain controlled-use information?   
 Yes     No

(\*Yes\* requires information clearance review in accordance with HNF-PRO-184)

**DOCUMENT REVISION SUMMARY**

NOTE: Provide a brief description or summary of the changes for the document listed.

**REVIEWERS**

Name (print)	Others
J. R. Seaver	D&D Project
L. D. Stefanski	D&D Project
G. B. Chronister	Soil & Water Rem/Groundwater

**APPROVAL SIGNATURES**

<b>Author:</b> <i>B. J. Spilman</i>	11/20/07	RELEASE / ISSUE NOV 27 2007 DATE: _____ STA: 15 HANFORD RELEASE ID: _____ 
<b>Name: (Print)</b> B. J. Spilman	11/20/07	
<b>Responsible Manager:</b> <i>G. J. McCleary</i>	_____	
<b>Name: (Print)</b> G. J. McCleary	Date	
<b>Other:</b>	_____	
<b>Name: (Print)</b>	Date	

**CONTENTS**

1  
2  
3  
4  
5  
6  
7  
8  
9  
10  
11  
12  
13  
14  
15  
16  
17  
18  
19  
20  
21  
22  
23  
24  
25  
26  
27  
28  
29  
30  
31  
32  
33

1.0	INTRODUCTION.....	1
1.1	Purpose/Scope .....	1
1.2	Process.....	1
2.0	ALTERNATIVE COST ESTIMATES.....	3
2.1	Alternative One – No Action.....	4
2.2	Alternative Two – Institutional Controls Supplemented by Monitored Natural Attenuation.....	4
2.3	Alternative Three – Remove, Treat and Disposal .....	4
3.0	ASSUMPTIONS .....	5
3.1	Global Assumptions .....	5
3.2	Detailed Assumptions by Alternative.....	6
3.2.1	Alternative One - No Action .....	6
3.2.2	Alternative Two - Monitored Natural Attenuation/Institutional Controls .....	6
3.2.3	Alternative Three - Removal, Treatment, and Disposal.....	7
3.2.4	Special Conditions .....	12
3.3	Cost Summary Tables for Alternatives 2 and 3 for the BC Controlled Area.....	13
4.0	SUMMARY OF COST FOR THE ENGINEERING ESTIMATE/COST ANALYSIS FOR BC CONTROLLED AREA (UPR-200-E-83) REMOVAL ACTION .....	14
5.0	REFERENCES.....	14

**TABLES**

Table 3-1.	Alternative 3 Planning and Development Basis for Estimate <sup>1</sup> .....	10
Table 3-2.	Adjusted Total Capital Cost from Referenced Estimate <sup>1</sup> .....	12
Table 3-3.	Total Costs of Haul Road not included in the BC Controlled Area Alternative 3 Costs.....	13
Table 3-4.	Site Summary Sheet for Alternative 2- Monitor Natural Attenuation and Institutional Controls.....	13
Table 3-5.	Site Summary Sheet for Alternative 2 – Remove, Treat, and Dispose.....	14
Table 4-1.	Cost Estimates for BC Controlled Area Removal Alternatives.....	14

**TERMS**

1		
2		
3		
4	CERCLA	<i>Comprehensive Environmental Response, Compensation, and Liability Act of</i>
5		<i>1980</i>
6	DOE	U.S. Department of Energy
7	EE/CA	engineering evaluation/cost analysis
8	EPC	engineering, procurement, and construction
9	ERDF	Environmental Restoration Disposal Facility
10	FH	Fluor Hanford, Inc.
11	HAMTC	Hanford Atomic Metal Trades Council
12	IC	institutional control
13	MNA	monitored natural attenuation
14	N/A	not applicable
15	OMB	U.S. Office of Management and Budget
16	OU	operable unit
17	PV	Present Value
18	QA	quality assurance
19	RTD	remove, treat, and dispose
20	S&M	surveillance and maintenance
21	TPC	total project cost
22		

1           **COST ESTIMATE FOR THE ENGINEERING EVALUATION/COST ANALYSIS**  
2                           **FOR BC CONTROLLED AREA REMOVAL ACTION**

3  
4   **1.0 INTRODUCTION**

5           **1.1 Purpose/Scope**

6           The purpose of this Present Value (PV) analysis is to evaluate the cost of removal action alternatives of  
7           the contaminated soil contained within the northern region of the BC Controlled Area. The  
8           BC Controlled Area waste site is part of the 200-UR-1 Unplanned Release Waste Group Operable Unit  
9           (OU). The northern region of the BC Controlled Area is located north of, and includes, the sand dunes  
10          that cross the controlled area from east to west. While the Northern BC Controlled Area does not include  
11          the BC Cribs and Trenches, it does include an area, referred to as "Zone A", which has the highest levels  
12          of contamination, and a "Zone B" area, which contains detectable amounts of contamination and is  
13          generally considered to be of lower risk levels.

14  
15          Alternatives evaluated are:

- 16          • Alternative One: No Action  
17          • Alternative Two: Monitored Natural Attenuation/Institutional Controls (MNA/IC)  
18          • Alternative Three: Remove, Treat, and Dispose (RTD).

19          Alternatives One and Two apply to the entire Northern BC Controlled Area. Alternative Three requires  
20          an approach that proposes removal of soil [to approximately 12-inches from Zone A and from select parts  
21          (hotspots)] of Zone B.

22          This PV analysis will be used for the engineering evaluation/cost analysis (EE/CA) (*Engineering*  
23          *Evaluation/Cost Analysis for the Northern Part of the BC Controlled Area (UPR-200-E-83)*,  
24          DOE/RL-2007-51) currently being prepared for the BC Controlled Area to determine the preferred  
25          removal action alternative.

26          **1.2 Process**

27          The PV analysis for the reference EE/CA is developed per guidance specified in EPA/540/R-00/002, "*A*  
28          *Guide to Developing and Documenting Cost Estimates During the Feasibility Study*", OSWER  
29          9355.0-75. PV analysis is a method to evaluate expenditures, either capital or Surveillance and  
30          Maintenance (S&M), which occur over different time periods. This standard methodology allows for cost  
31          comparisons of different remedial alternatives based on a single cost figure for each alternative. This  
32          single number, referred to as the present value, is the amount needed to be set aside at the initial point in  
33          time (base year) to assure that funds will be available in the future as they are needed, assuming certain  
34          economic conditions.

35          Consistent with guidance established by the U.S. Office of Management and Budget (OMB), PV analysis  
36          is used as the basis for comparing costs of cleanup alternatives under the *Comprehensive Environmental*  
37          *Response, Compensation, and Liability Act of 1980* (CERCLA) program (OMB 2006). The PV analysis  
38          is specified under CERCLA as the approach for establishing a common baseline to evaluate and compare  
39          alternatives that have costs occurring at different times, though actual costs could vary.

40          The present value analysis for each remedial alternative includes:

1 • Period of analysis

2 The period of analysis for the present-net-worth cost is 50 years for Alternative 2, MNA/IC and for  
3 Alternative 3, RTD.

4 • Cash outflows (payments) for each year of the project

5 Remedial action projects typically involve construction costs that are expended at the beginning of a  
6 project (e.g., capital costs) and costs in subsequent years that are required to implement and maintain  
7 the remedy after the initial construction period (e.g., annual S&M costs, periodic costs). The cost  
8 estimates for the capital and S&M expenditures provides a discriminator for deciding between similar  
9 protective and implemental alternatives for a specific waste site. Therefore, the costs are relational,  
10 not absolute costs and considered only for the evaluation of the alternatives.

11 NOTE: Generally, the capital cost portion uses a simplified approach, which defines the initial year  
12 as “year zero”, and an equal value per year over the length of construction. However, for this EE/CA,  
13 costs do not include sunk costs from previous years (FY2007) and the cash outflows will match the  
14 variable amounts presented in the reference Project Working Schedule.

15 • Discount rate to use in the present value calculation

16 Present value costs are calculated using the real discount rate published in Appendix C of  
17 OMB Circular No., A-94, Guidelines and Discount Rates for Benefit-Cost Analysis of Federal  
18 Programs, effective through January 2008. A discount rate of 3.0 percent is used for all alternatives.

19 • Present value (PV) (and non-discounted present value)

20 The comparison of Present Value and non-discounted present value costs are calculated for each  
21 alternative. PV and non-discounted present value requirements are:

22 – Present Value: For a stream or series of future payments, the total present value from 1 to n years  
23 would be calculated as:

$$PV_{total} = \sum_{t=1}^{t=n} \frac{X_t}{(1+i)^t}$$

24  
25

26 NOTE: See EPA/540/R-00/002, *A Guide to Developing and Documenting Cost Estimates During the*  
27 *Feasibility Study*, OSWER 9355.0-75 for exact details.

28 • Nondiscounted cost

29 The nondiscounted cost method displays the total costs occurring over the entire duration of an  
30 alternative, with no adjustment (or discounting) to reflect set aside cost based on an assumed discount  
31 rate.

32 NOTE: Because nondiscounted costs do not reflect the changing value of funds over time,  
33 presentation of this information under CERCLA is for information purposes only, not for purposes of  
34 selecting a response action alternative. Additionally, nondiscounted constant dollar costs are not  
35 considered the same as present day costs of remedial actions found in the Hanford baseline budget.

1 • Contingency: (Project Management Reserve)

2 Contingency is applied to the cost estimate to cover potential cost overruns. A contingency rate of  
3 8 percent was determined from a Risk Analysis performed by FH Project personnel. Based on  
4 Analysis of the Critical Risk list, Deterministic Cost (Total Project Cost) a 50% Cost Confidence was  
5 determined to be approximately \$3 million. Project Management Reserve (PMR) should be  
6 determined by the projects and planned in accordance with "Project Risk Management Planning  
7 Guidance", Document HNF-GD-29936.

8 • Economies

9 Economies associated with implementing multiple sites or groups with a common alternative or  
10 aggregated remediation are considered in the long-range planning of the reference basis of estimate.  
11 Potential areas of cost sharing to reduce overall remediation costs include the following:  
12 – Remediating all waste sites with a common preferred alternative at the same time  
13 – Sharing mobilization/demobilization costs  
14 – Sharing S&M costs  
15 – Sharing operation and maintenance costs  
16 – Sharing training costs.

17 Chapter 2.0 provides a basic breakdown of the cost types used to determine each alternative's present  
18 value costs.

19 Chapter 3.0 provides the level of detail necessary for independent review. The supporting capital,  
20 periodic and annual cost estimates prepared by Fluor Hanford, Inc. (FH) Project Controls Estimating  
21 department shall include a basis of estimate in accordance with Job bulletin # 7, "Work Instructions for  
22 Cost Estimate Development and Review", Rev 1 (6/2007).

23 **2.0 ALTERNATIVE COST ESTIMATES**

24 This chapter summarizes each alternatives scope and cost components used for determining their present  
25 value in terms of the remedial alternatives developed in the EE/CA.

26 List of alternatives includes:

- 27 • Alternative One: No Action
- 28 • Alternative Two: MNA/IC
- 29 • Alternative Three: RTD.

30 For the purpose of this EE/CA, the present-net-worth costs represent three cost types, which may include:

- 31 • Capital
  - 32 – Remediation (RTD) Engineering, Procurement, and Construction (EPC)
  - 33 – IC (Alternative Two only).
- 34 • Periodic
  - 35 – MNA
  - 36 – IC (Alternative Three only).
- 37 • Annual:
  - 38 – S&M.

1 **2.1 Alternative One – No Action**

2 The no-action alternative represents a situation where no legal restrictions, access controls, or active  
3 remedial measures are applied to the waste site. Taking no action implies “walking away from the waste  
4 site” and allowing the waste to remain in its current configuration, affected only by natural processes. No  
5 maintenance or other activities would be instituted or continued. The EE/CA describes the no-action  
6 alternative.

7 Because the no-action alternative assumes that no further actions will be taken at a waste site, costs are  
8 assumed zero.

9 **2.2 Alternative Two – Institutional Controls Supplemented by Monitored Natural Attenuation**

10 Chapter 5.0 of the EE/CA provides a description of the MNA/IC alternative. The cost details for this  
11 alternative are discussed in detail in Section 3.2.

12 The typical annual/periodic costs associated with alternative two are; IC, S&M, and MNA costs. The  
13 costs for these annual/periodic activities are estimated based on the location and size of the individual  
14 sites.

15 For the purpose of this alternative IC will be considered a capital one-time occurring cost. The duration  
16 for IC only considers the initial, “Year-zero” period. The annual/periodic calculations are based on the  
17 length of time required to reach the preliminary remediation goals.

18 For the purpose of this EE/CA, the annual/periodic activities have been revised to include only:

- 19 • IC
  - 20 – Non-engineering or legal/administrative measures
  - 21 – IC plans
  - 22 – Restrictive covenants
  - 23 – Property easements
  - 24 – Zoning
  - 25 – Deed notices
  - 26 – Advisories
  - 27 – Groundwater use restrictions
  - 28 – Site information databases.
- 29 • S&M
  - 30 – Radiation survey of the site perimeter
  - 31 – Signage repair.
- 32 • MNA
  - 33 – Not applicable (N/A).

34 The combined present-net-worth costs for IC, S&M, and MNA activities represent the present value cost  
35 for this alternative.

36 **2.3 Alternative Three – Remove, Treat and Disposal**

37 Chapter 5.0 of the EE/CA describes the RTD alternative. The details for the RTD system life cycle costs  
38 are discussed in detail in Section C3.3.

1 Controlled areas are excavated to the required depth and contaminated material is removed to the  
2 Environmental Restoration Disposal Facility (ERDF) for disposal. The scope of this alternative will  
3 complete the removal of approximately 330,000 tons of soil in the BC Control Zone Waste Site  
4 (UPR-200-E-83) as identified in DOE/RL-2003-24.

5 • A listing of this alternative major cost components are as follows:

6 – Capital

- 7     ▪ Remediation process system scope:
- 8     ▪ Project management
- 9     ▪ Mobilization and site preparation,
- 10    ▪ Regulatory document development,
- 11    ▪ Site soil excavation
- 12    ▪ Post excavation characterization
- 13    ▪ Re-vegetation of excavation site
- 14    ▪ Demobilization.

15 – Periodic

- 16     ▪ Natural attenuation monitoring (N/A)
- 17     ▪ IC activities
- 18     ▪ Annual site review report (5 yrs).

19 – S&M (N/A).

20  
21 The combined present-net-worth costs for the capital construction activities and, IC activities represent  
22 the present-worth cost for this alternative.

23 **3.0 ASSUMPTIONS**

24 The remedial alternatives are discussed in detail in Chapters 5.0 and 6.0 of this EE/CA. This chapter  
25 provides backup information and assumptions used in developing the cost estimates of the remedial  
26 alternatives.

27 **3.1 Global Assumptions**

- 28 • General pricing is based on reference document: “FY 2008 AND LIFE-CYCLE BASELINE  
29 UPDATE PROJECT EXECUTION PLAN” Rev 0, May 15, 2007.
- 30 • Information contained within this estimate has been derived from historical experience with the  
31 management and support of similar projects. The units utilized may have been factored / adjusted by  
32 the estimator, superintendent, senior construction engineer, and task leads, as appropriate, to reflect  
33 influences by the contract, work site, or other identified special conditions.
- 34 • The estimate includes discipline support, construction management, environmental expertise, and  
35 technical support.
- 36 • Sub-element pricing requirements specific to this EE/CA include:
  - 37 – Hanford Atomic Metal Trades Council (HAMTC) craft personnel (Plant Forces) labor rates for  
38 construction activities are fully burdened and based on approved FH planning rates for FY2008  
39 (unescalated).
  - 40 – FH labor rates for management, engineering, safety oversight, and technical support are based on  
41 the FH approved planning rates for fiscal year 2008 (unescalated).

- 1       – The non-labor resource rates are based on the FH approved planning rates for fiscal year 2008
- 2       (unescalated).
- 3       – Markups (Direct Cost Factors/Indirect Cost Factors)
- 4       – FY2008 burdened planning rates without escalation was used.

## 6    **3.2 Detailed Assumptions by Alternative**

### 7    **3.2.1 Alternative One - No Action**

8    The No-Action Alternative represents a situation where no legal restrictions, access controls, or active  
9    remedial measures are applied to the waste site. Taking no action implies “walking away from the waste  
10   site” and allowing the waste to remain in its current configuration, affected only by natural processes. No  
11   maintenance or IC are included in this alternative.

12   Because the No-Action Alternative assumes no further actions will be taken at a waste site, costs are  
13   assumed to be zero.

### 14   **3.2.2 Alternative Two - Monitored Natural Attenuation/Institutional Controls**

#### 15   Scope:

16   IC, which can have one-time or recurring costs (capital, annual operations and maintenance, or periodic),  
17   are non-engineering or legal/administrative measures to reduce or minimize the potential for exposure to  
18   site contamination or hazards by limiting or restricting site access.

19   Examples include IC plans, restrictive covenants, property easements, zoning, deed notices, advisories,  
20   groundwater use restrictions, and site information databases. An IC plan would describe the controls for a  
21   site and how they would be implemented. A site information database would provide a system for  
22   managing data necessary to characterize the current nature and extent of contamination. IC are  
23   project-specific costs that can be important components of a remedial alternative and as such, should  
24   generally be estimated separately from other costs, usually on a sub-element basis. IC may need to be  
25   updated or maintained, either annually or periodically.

26   The primary annual/periodic costs associated with this alternative are for the area perimeter radiological  
27   S&M natural attenuation. The costs for these annual/periodic activities were estimated based on the  
28   perimeter (50,000 feet) of the individual waste sites or groups.

29   The unit cost for S&M was assumed the same as the current unit cost for S&M activities conducted  
30   annually on the waste sites. The unit cost accounts for such activities as site radiation surveys, and repair  
31   of signage.

32   The costs associated with natural attenuation monitoring include radiological surveys of surface soils.  
33   The costs to perform radiological surveys of surface soils at waste sites are assumed similar to those for  
34   current survey practices at the sites and are included in the S&M costs. Costs are included for  
35   periodically replacing signs over 50-year duration.

#### 36   Basis of Estimate:

37   The IC cost model used for this alternative was developed by the FH Project Controls and Estimating  
38   department. The duration for IC only considers the initial, “year-zero” period. The annual/periodic  
39   activities were based on 50-year duration for alternatives two and three.

1 General Assumptions

2 The general assumptions for this alternative are as follows.

- 3 • Monuments/signs for IC and signage maintenance are included.
- 4 • The IC alternative consists of the following general activities: implementation of IC, site inspection  
5 and surveillance, MNA, reporting and site reviews.
- 6 • Site Reviews will be required every 5 years.

7 Special Conditions

8 NOTE: Typical EE/CA annual/periodic costs associated with this alternative are:

- 9 • IC
  - 10 – Non-engineering or legal/administrative measures
  - 11 – IC plans
  - 12 – Restrictive covenants
  - 13 – Property easements
  - 14 – Zoning
  - 15 – Deed notices
  - 16 – Advisories
  - 17 – Groundwater use restrictions
  - 18 – Site information databases.
- 19 • S&M
  - 20 – Site radiation surveys
  - 21 – Repair of the existing soil cover.
- 22 • MNA
  - 23 – Radiological surveys of surface soils
  - 24 – Spectral gamma logging of vadose-zone boreholes
  - 25 – Long-term groundwater monitoring.

26 **3.2.3 Alternative Three - Removal, Treatment, and Disposal**

27 Scope:

28 Controlled areas are excavated to the required depth and contaminated material is removed to the  
29 Environmental Restoration Disposal Facility (ERDF) for disposal. The general remediation scope  
30 activities include:

- 31 • Capital
  - 32 – Project Management
  - 33 – Regulatory document development
  - 34 – Obtain personnel to perform the excavation
  - 35 – Complete regulatory documentation allowing excavation
  - 36 – Mobilize equipment and personnel
  - 37 – Install monitoring and surveying equipment

- 1        - Identify area with near surface contamination in Area B of the BC Controlled Area,  
2        UPR-200-E-83 (Note: This was performed as part of the 200-UR-1 OU remedial investigation  
3        activities)
- 4        - Complete excavation of Area A and Area B hot spot removal at BC Controlled Area to a depth of  
5        1 foot and dispose of the material at ERDF
- 6        - Obtain samples and analysis
- 7        - Revegetate area
- 8        - De-mobilization
- 9        - Complete closeout documentation.

- 10      • Periodic:
  - 11        - MNA (N/A)
  - 12        - IC activities
  - 13        - Annual site review report (5 yrs).

- 14      • S&M (N/A).

15      The method of soil removal shall consider two (2) different approaches which create different equipment  
16      and labor mixes. The first approach is for a single mass (bulk) near surface soil excavation covering  
17      approximately 140 acres, identified as Zone A. The second approach will remove the approximately  
18      1,000 randomly located elevated surface contamination areas "hotspots" spread out over approximately  
19      3,700 acres. Additionally, the random excavation must consider old-growth conservation and avoid  
20      destruction of existing plant life by using the smallest footprint for sizing equipment whenever possible.

21      For the purpose of this estimate the production rate for each approach is:

- 22      • Mass excavation – 520 CY/Day
- 23      • Random" Spot" Excavation – 130 CY/Day.

24      The field work such as mob/demob, excavation, revegetation, and some for the post construction work  
25      will be contracted to the Plant Construction Forces Contractor or HAMTC. The Project Management,  
26      Radiological control technician support, sampling, and safety oversight will be performed by FH. The  
27      waste disposal work will be performed by the environmental restoration contractor responsible for ERDF.

28      Mobilization and startup include site training; mobilization of equipment and personnel; installation of  
29      temporary construction fences; construction of truck turnaround areas and access roads; and setting up  
30      office, change, and storage trailers with utilities, temporary survey structure, and decontamination areas.

31      Air sampling will be performed during the excavation of contaminated soil.

33      Soil sampling will be done for verification at the completion of excavation. The estimated costs include  
34      an allowance of \$1 million for obtaining sample analysis.

35      The haul truck handling and loading process starts at a preparation area where it is inspected. The haul  
36      truck proceeds to the loading area. After loading, the bed is covered and secured. The truck is moved to  
37      the survey area where it is inspected and surveyed for contamination. From there, the haul truck is  
38      weighed on a platform scale and then driven to the ERDF where the bed is unloaded from the truck.  
39      Eight trucks with seven in continuous use are required to support each contaminated excavation crew.

40      ERDF disposal fee, transportation, and handling costs are included in the estimate. A driver will move  
41      loaded trucks to ERDF. The estimated costs include the rental of the trucks used. For planning purposes,  
42      the capacity of a haul truck is 26 yd<sup>3</sup>.

1 No stockpile or backfill is anticipated.

2 Revegetation of the waste site includes planting native dry-land grass and seedlings. Disturbed site areas,  
3 such as around the waste site, staging areas, and access roads no longer needed will be replanted.

4 The FH Project Management team consists of a part-time project manager, with a full-time field  
5 supervisor and part-time engineering support. Quality assurance (QA), radiological control, and safety  
6 also provide oversight along with other support for contract management and project controls. The  
7 duration of this work is based on total project duration.

8 The FH contractor field supervisory team consists of a full-time construction manager and field  
9 supervisor, along with part-time QA, construction safety, and clerical support. The duration of this work  
10 is based on total project duration.

11 Demobilization includes demobilization of no longer needed equipment and personnel, removing  
12 temporary construction fences, access roads, office/change/storage trailers, temporary survey buildings,  
13 and decontamination areas.

14 Basis of Estimate

15 • The Majority of the Total Project Cost (TPC) for the capital construction scope of work for the RTD  
16 alternative of this EE/CA is based on the following references worksheets and schedules:  
17 – See table entitled Estimate Planning and Development (From BCR RL40-CP07-002, BC Control  
18 Area Excavation – Estimate Review Package).

19 • The methods used for preparing the cost estimate varied with the specific activities within the Work  
20 Breakdown Structure (WBS) (see the specific WBS Basis of Estimate). A combination of Analogy,  
21 Bottoms Up and Parametric estimating was used. In general, for Project Management and necessary  
22 engineering and regulatory documentation development analogous estimates were developed.  
23 Bottoms Up estimates were applied to field work.

24 • Where costs were unknown, past experience with the recent 200-W-42 pipeline removal and  
25 200 North projects were used to estimate values.

26 General Assumptions:

- 27 • The general assumptions for this alternative are as follows.
- 28 – Direct haul road will be available at no cost for soil shipment to ERDF.
  - 29 – The excavation sites will have contaminated waste removed.
  - 30 – The sides of the excavated area will be contoured to the average one-foot depth.
  - 31 – For excavation sites, overburden is not anticipated.
  - 32 – A highway truck with a water tank trailer is used to control dust during this activity.
  - 33 – No waste debris including concrete, pipe, etc. is anticipated.
  - 34 – The total volume and weight of excavated contaminated soil is approximately 236,907 CY or  
35 326,931 tons.
  - 36 – The duration of the Total Project is approximately 990 days or 4 (four) years.
  - 37 – The estimate assumes the timely approval of regulatory documents (e.g., EE/CA, sampling and  
38 analysis plan, action memorandum, remedial action work plan, etc.) by both U.S. Department of  
39 Energy (DOE) and the lead regulatory agency.
  - 40 – Failure to attain timely approvals will cause schedule delays, cost increases and possibly missed  
41 completion dates.
  - 42 – 26 cubic yard dump trucks will be used to dispose of material to ERDF.

- 1 - ERDF will support turn around of trucks to maintain an average of 720 tons per day.
- 2 - Acquisition of dump trucks can be completed prior to need date.
- 3 - Vegetation disposal will be accepted at ERDF.
- 4 - No obstructions will be detected during ground scan and/or excavation activities.
- 5 - No follow up requirements will be required due to the cultural historic review.
- 6 - No follow up requirements will be required due to the biological/ecological review.
- 7 - PFWR will come back as Building Trades.
- 8 - Hazard Characterization will be less than CAT 3.
- 9 - The site evaluation will not identify any issues.
- 10 - A maximum of 3 environmental air monitors will be required.
- 11 - No additional cost and duration due to equipment decontamination.
- 12 - Will excavate to a maximum of one foot in depth.
- 13 - Weather and equipment downtime will not impact the schedule and will not exceed 10% of the
- 14 labor cost.
- 15 - ERDF charges will not exceed the average cost per ton as calculated from the estimate provided
- 16 by WCH.
- 17 - Interface with US Ecology will not impact the schedule.
- 18 - Contamination levels will not require additional monitoring and/or personal protective
- 19 equipment.
- 20 - No backfill of site prior to revegetation.
- 21 - The site will be down-posted and signage removed at the end of the project.
- 22 - Revegetation was assumed to be a maximum of 22 pounds of seed and 810 seedlings per acre.
- 23 - Revegetation will not require watering.
- 24 - Site Reviews will be required every 5 years.
- 25

Table 3-1. Alternative 3 Planning and Development Basis for Estimate<sup>1</sup>.

<b>Excavation Crew</b>	
Labor - Staffing plan developed by project management team with previous experience at 200-W-42 and 200 North excavation projects.	4 x 10 work week 11 teamsters (8 for direct haul trucks and 2.5 for water trucks – dust suppression) 7 laborers 2 heavy equipment operators 6 health physics technicians 1 miscellaneous support
Materials	5% of labor for consumables 124,220 hours * average labor rate of \$64 per hour * 5% = \$397,504 Dust suppression equipment (\$145 per day * 580 Days = \$84,100) Soil Cement - \$2,500 per month * 21 months
Other Contractors	ERDF Support (\$1000 per month * 29 Months = \$29,000) FH Package and Ship BC Control Zone to ERDF (\$34.74 per ton x 326,932 tons = \$11,357,618)
Fuel	2 water trucks and average 7 haul trucks @ 20 gallons per day (20 gallons per day * 580 days * \$5 per gallon = \$522,000)
Excavation mitigation	Allowance of 10% labor cost for weather and mechanical delays - \$712,200
Adders/Overheads	

Table 3-1. Alternative 3 Planning and Development Basis for Estimate<sup>1</sup>.

<b>Rental Equipment</b>	
Materials	2 water truck @ \$6,941 ea = \$13,882 4 Light Plants @ \$588 ea = \$2,352 4 Portalettes @ \$470 ea = \$1,880 1 100 kwv generator @ \$1,765 1 scale @ \$1,106 1 Front End Loader @ \$13,000  Total monthly rental \$33,985 (\$33,985 * 29 months = \$985,565) Delivery costs \$15,000
	Haul trucks (8 haul trucks @ 7,500 per month * 29 months = \$1,740,000)
	70,000 gallon water wagon at \$20,000 a month for 23 months = \$460,000
<b>BC Crib BC Crib Control Zone Field Work Project Management</b>	
Labor - Staffing plan developed by project management team with previous experience at 200-W-42 and 200 North excavation projects.	FGG Project Engineer (.25) Waste Coordinator (1.0) Safety (.5) Clerical (.1) Field Work Supervisor (1.0) Rad Supervisor (.5 prep/1.0 field work) Director (.1) Project Manager (.25) Project Scheduler (.25 prep/.5 field work) Project Superintendent (.75) Work Package Planner (.25) Field Health Physicist (.5) Technical Health Physicist (.1) Industrial Hygienist (.5)
Materials	5% of labor for consumables
	Trailers @ \$800/month * 4 Trailers * 33 months = \$105,600
	Cell phone stipend @ \$250 per month * 31 months = \$7,750
	Remote internet @ \$100/month * 5 stations * 31 months = \$15,500
Subcontracts	Attendance in Training - \$750,960 <ul style="list-style-type: none"> <li>▪ 19 FTEs x 596 days x 8 hours a day x 5% at \$70 per hour = \$317,072</li> <li>▪ 6 HPTs and 1 HPT Supervisor x 596 days x 8 hours a day x 10% at \$80 per hour = \$267,008</li> <li>▪ Plus ~7 FTE's in PM x 596 days x 8 hours a day x 5% at \$100 per hour = \$166,880</li> </ul>
Other Direct Costs	Initial Training Course Cost - \$50,000

Table 3-1. Alternative 3 Planning and Development Basis for Estimate<sup>1</sup>,

<b>Laboratory Analysis</b>	
	Approximately twice the 200-W-42 Trench sampling costs have been entered as a ROM estimate. Actual post excavation sampling requirements will be determined at a later date and will require regulatory agreement.
<b>BC Control Revegetation</b>	
Contracts	<ul style="list-style-type: none"> <li>▪ Procure: 810 seedlings per acre * \$.50 per seedling * 150 acres = \$60,750</li> <li>▪ Plant: 810 seedling per acre * 1.20 * 150 acres = \$145,800</li> <li>▪ Seed with mulch and fertilizer 22 pounds per acre * \$70.00 per pond * 150 acres = \$231,000</li> </ul>

1 <sup>1</sup> From BCR RL40-CP07-002, BC Control Area Excavation - Estimate Review Package

2 **3.2.4 Special Conditions**

3 Alternative 3 costs includes adjustment of the reference estimate to meet the capital cost requirements  
 4 specific to this EE/CA resulted in a Total Capital Cost of.\$38,180,900 (Table 3-2).

Table 3-2. Adjusted Total Capital Cost from Referenced Estimate<sup>1</sup>

CAPITAL COST <sup>1</sup>	PERIOD
\$4,157,173	YEAR 0
\$14,431,542	YEAR 1
\$14,595,331	YEAR 2
\$4,996,854	YEAR 3
\$38,180,900 <sup>2</sup>	Total Capital Cost

<sup>1</sup> From BCR RL40-CP07-002, BC Control Area Excavation - Estimate Review Package

<sup>2</sup> Total Capital Costs reflects the following:

- Added revegetation costs (\$540,000) (YEAR 3), for increased area based on an estimated replacement ratio - 3:1 for compensatory mitigation.
- Includes Project Management Reserve (contingency) \$3,100,000.
- Deducted the haul road construction cost (\$355,300) (YEAR 0).

5  
 6 Cost adjustments were made for revegetation, project management reserve and the haul road to ERDF, as  
 7 summarized below.

8 Revegetation

9 A replacement ratio - 3:1 for compensatory mitigation was estimated based on an initial review. Specific  
 10 resources that will be subject to mitigation of adverse impacts are defined in the "Biological Resources  
 11 Management Plan", (BRMaP) for the Hanford Site.

12 Contingency - (Project Management Reserve)

13 The contingency rate was determined from a Risk Analysis performed by FH Project personnel. Project  
 14 personnel and risk analysis facilitators assessed the BC Controlled Area Excavation work scope for  
 15 exposure to risk and events that could cause the activity to exceed budgeted cost and schedule. The cost

1 and schedule confidence curves generated from the analysis display the probability of completing the  
2 project within the planned baseline and provide the basis to develop project management reserve.

3 The probability of completion of the lifecycle scope by August 26, 2011 is 50%. The probability of  
4 completion of the lifecycle scope within the \$35M unescalated budget is less than 1%. The application of  
5 \$3,100K of PMR will raise the cost confidence to the 50% desired level.

### 6 Haul Roads

7 The construction of a haul road between the BC Controlled area and the ERDF site is not included in the  
8 scope of the EE/CA. Detail costs of the haul road cost deductions are shown in the following Table 3-3:

Table 3-3. Total Costs of Haul Road not included in the BC Controlled Area Alternative 3 Costs.

CCL	Act ID	Data	(\$000)	
			FY2008	Grand Total
4.01.02.09 - Waste Site Remediation	BC0300 - Complete Prep for Haul Road	Sum of subtotal_burdened	32.7	32.7
		Sum of esc	0.0	0.0
		Sum of total_escalated	32.7	32.7
	BC0310 - Construct Haul Road	Sum of subtotal_burdened	322.6	322.6
		Sum of esc	0.0	0.0
		Sum of total_escalated	322.6	322.6
4.01.02.09 - Waste Site Remediation Sum of subtotal_burdened			355.3	355.3

### 10 3.3 Cost Summary Tables for Alternatives 2 and 3 for the BC Controlled Area

11 Tables 3-4 and 3-5 provide the summaries of the capital costs, periodic costs, non-discounted costs and  
12 present worth costs for Alternative 2 and Alternative 3.

13 Table 3-4. Site Summary Sheet for Alternative 2- Monitor Natural Attenuation and Institutional Controls.

Site	Alternative	Total Capital Cost	Non-Discounted Annual & Periodic Cost	Non-Discounted Cost	Total Present Worth Cost
BC CONTROLLED AREA	Alt 2 - MNA/IC <sup>1</sup>	\$35,400	\$1,839,583 <sup>2,3</sup>	\$1,874,983 <sup>3</sup>	\$976,051

<sup>1</sup> This alternative includes an annual perimeter survey of the BC Controlled Area Zone A and selected Zone B "hot spot" area, signage and reporting. Institutional controls (IC) typically include an IC plan, restrictive covenants, property easements, zonings, deed notices, advisories, groundwater use restrictions, site reviews, and site information databases.

<sup>2</sup> There is no existing clean soil cover and therefore no maintenance of the soil cover or additions of clean soil. No Vadose Zone or Ground Water Monitoring will be priced.

<sup>3</sup> Discount rate is a calculated annual multiplier of 3.0% and n = year (1 - 50).

Table 3-5. Site Summary Sheet for Alternative 2 – Remove, Treat, and Dispose.

Site	Alternative	Total Capital Cost <sup>3</sup>	Non-Discounted Annual & Periodic Cost	Non-Discounted Cost	Total Present Worth Cost
BC CONTROLLED AREA	Alt 3 - Remove Treat and Disposal <sup>1,2</sup>	\$38,180,900	\$180,000 <sup>4</sup>	\$38,360,900	\$36,583,609

<sup>1</sup> The RTD alternative includes the RTD of BC Controlled Area Zone A and selected Zone B higher contamination "hot spot" areas.

<sup>2</sup> Alternative also includes institutional controls (IC) typically include an IC plan, restrictive covenants, property easements, zonings, deed notices, advisories, groundwater use restrictions, site reviews, and site information databases.

<sup>3</sup> Total Capital Cost based on Table 3-2.

<sup>4</sup> There is no existing clean soil cover and therefore no maintenance of the soil cover or additions of clean soil. No Vadose Zone or Ground Water Monitoring will be priced.

<sup>5</sup> Discount rate is a calculated annual multiplier of 3.0% and n = year (1 - 50).

#### 4.0 SUMMARY OF COST FOR THE ENGINEERING ESTIMATE/COST ANALYSIS FOR BC CONTROLLED AREA (UPR-200-E-83) REMOVAL ACTION

The summary of the cost estimates for Alternatives 2 and 3 for the BC Controlled Area EE/CA is provided in Table 4-1.

Table 4-1. Cost Estimates for BC Controlled Area Removal Alternatives.

Cost Estimate	Alternative 1: No Action	Alternative 2: Monitored Natural Attenuation and Institutional Controls	Alternative 3: Remove, Treat, and Dispose
Present Net Worth	\$0	\$976,051	\$36,583,609
Non-Discounted Cost	\$0	\$1,874,983	\$38,360,900

#### 5.0 REFERENCES

DOE/EIS-0222-F, 1999, *Final Hanford Comprehensive Land-Use Plan Environmental Impact Statement*, U.S. Department of Energy, Washington, D.C.

DOE G 435.1-1, 1999, *Implementation Guide for Use with DOE M 435.1-1*, U.S. Department of Energy, Washington, D.C.

DOE/RL-2007-51, *Engineering Evaluation/Cost Analysis for the Northern Part of the BC Controlled Area (UPR-200-E-83)*, U.S. Department of Energy, Richland Operations Office, Richland, Washington.

EPA/540/R-00/002, 2000, *A Guide to Developing and Documenting Cost Estimates During the Feasibility Study*, OSWER 9355.0-75, U.S. Environmental Protection Agency, Washington, D.C.

Means, R. S., 2001, *ECHOS Environmental Remediation Cost Data – Unit Price*, 7th annual ed., Robert S. Means Company, Kingston, Massachusetts.

- 1 Means, R. S., 2007, *Facility Construction Cost Data*, 22th annual ed., Robert S. Means Company,  
2 Kingston, Massachusetts.
- 3 OMB Circular No. A-94, 2002, *Guidelines and Discount Rates for Benefit-Cost Analysis of Federal*  
4 *Programs*, Office of Management and Budget, Washington, D.C., as revised.
- 5 *Richardson's Process Plant Construction Estimating Standards*, Richardson Engineering Services, Inc.,  
6 Mesa, Arizona.
- 7 *Rental Rate Blue Book for Construction Equipment*, 2007, Equipment Watch, San Jose, California.
- 8 Site Stabilization Agreement for All Construction Work for the U.S. Department of Energy at the  
9 Hanford Site, 1984, as amended, commonly known as the Hanford Site Stabilization Agreement  
10 (original title, Site Stabilization Agreement, Hanford Site, between J. A. Jones Construction  
11 Services Company and Morrison-Knudsen Company, Inc., and the Building and Construction  
12 Trades Department of the AFL-CIO and its affiliated international unions, and the International  
13 Brotherhood of Teamsters, Chauffeurs, Warehousemen, and Helpers of America).
- 14 *Social Security Act of 1935*, 26 USC 21, et seq. (Federal Insurance Contributions Act).
- 15