START 9713530.2802 0046740

ENGINEERING CHANGE NOTICE

Page 1 of 2

1. ECN 635429

Proj. ECN

2. ECN Category (mark one)	3. Originator's Name, Organization, MSIN, and Telephone No.	4. USQ Required?	5. Date
Supplemental [] Direct Revision [X] Change ECN [] Temporary [] Standby [] Supersedure [] Cancel/Void []	Leela M. Sasaki, Data Assessment and Interpretation, R2-12, 373-1027	[] Yes [X] No	02/03/97
	6. Project Title/No./Work Order No. Tank 241-T-104	7. Bldg./Sys./Fac. No. 241-T-104	8. Approval Designator N/A
	9. Document Numbers Changed by this ECN (includes sheet no. and rev.) WHC-SD-WM-ER-372, Rev. 0	10. Related ECN No(s). N/A	11. Related PO No. N/A

12a. Modification Work	12b. Work Package No.	12c. Modification Work Complete	12d. Restored to Original Condition (Temp. or Standby ECN only)
[] Yes (fill out Blk. 12b) [X] No (NA Blks. 12b, 12c, 12d)	N/A	N/A Design Authority/Cog. Engineer Signature & Date	N/A Design Authority/Cog. Engineer Signature & Date

13a. Description of Change

13b. Design Baseline Document? [] Yes [X] No

This ECN was generated in order to revise the document to the new format per Department of Energy performance agreements.

FEB 1997 RECEIVED EDMC

14a. Justification (mark one)

Criteria Change	[]	Design Improvement	[]	Environmental	[]	Facility Deactivation	[]
As-Found	[X]	Facilitate Const	[]	Const. Error/Omission	[]	Design Error/Omission	[]

14b. Justification Details

This document was revised per Department of Energy performance agreements and direction from the Washington State Department of Ecology to revise 23 tank characterization reports (letter dated 7/6/95).

15. Distribution (include name, MSIN, and no. of copies)

See attached distribution.

RELEASE STAMP

DATE: STA: 4 ID:

FEB 04 1997

A-7900-013-2 (05/96) GEF095

A-7900-013-1

ENGINEERING CHANGE NOTICE

1. ECN (use no. from pg. 1) ECN-635429

16. Design Verification Required	17. Cost Impact				18. Schedule Impact (days)	
	ENGINEERING		CONSTRUCTION			
[] Yes	Additional	[] $	Additional	[] $	Improvement	[]
[X] No	Savings	[] $	Savings	[] $	Delay	[]

19. Change Impact Review: Indicate the related documents (other than the engineering documents identified on Side 1) that will be affected by the change described in Block 13. Enter the affected document number in Block 20.

SDD/DD	[]	Seismic/Stress Analysis	[]	Tank Calibration Manual	[]
Functional Design Criteria	[]	Stress/Design Report	[]	Health Physics Procedure	[]
Operating Specification	[]	Interface Control Drawing	[]	Spares Multiple Unit Listing	[]
Criticality Specification	[]	Calibration Procedure	[]	Test Procedures/Specification	[]
Conceptual Design Report	[]	Installation Procedure	[]	Component Index	[]
Equipment Spec.	[]	Maintenance Procedure	[]	ASME Coded Item	[]
Const. Spec.	[]	Engineering Procedure	[]	Human Factor Consideration	[]
Procurement Spec.	[]	Operating Instruction	[]	Computer Software	[]
Vendor Information	[]	Operating Procedure	[]	Electric Circuit Schedule	[]
OM Manual	[]	Operational Safety Requirement	[]	ICRS Procedure	[]
FSAR/SAR	[]	IEFD Drawing	[]	Process Control Manual/Plan	[]
Safety Equipment List	[]	Cell Arrangement Drawing	[]	Process Flow Chart	[]
Radiation Work Permit	[]	Essential Material Specification	[]	Purchase Requisition	[]
Environmental Impact Statement	[]	Fac. Proc. Samp. Schedule	[]	Tickler File	[]
Environmental Report	[]	Inspection Plan	[]		[]
Environmental Permit	[]	Inventory Adjustment Request	[]		[]

20. Other Affected Documents: (NOTE: Documents listed below will not be revised by this ECN.) Signatures below indicate that the signing organization has been notified of other affected documents listed below.

Document Number/Revision	Document Number/Revision	Document Number Revision
N/A		

21. Approvals

	Signature	Date		Signature	Date
Design Authority			Design Agent		
Cog. Eng. L.M. Sasaki	L M Sasaki	2/3/97	PE		
Cog. Mgr. K.M. Hall	Kathleen M. Hall	2/3/97	QA		
QA			Safety		
Safety			Design		
Environ.			Environ.		
Other R.J. Cash	L.M. Sasaki for R.J. Cash (approved per telecon)	2/3/97	Other		
N.W. Kirch	N W Kirch	2-3-97	DEPARTMENT OF ENERGY		
			Signature or a Control Number that tracks the Approval Signature		
			ADDITIONAL		

9713530.2803

HNF-SD-WM-ER-372, Rev. 1

Tank Characterization Report for Single-Shell Tank 241-T-104

Leela M. Sasaki
Lockheed Martin Hanford Corp., Richland, WA 99352
U.S. Department of Energy Contract DE-AC06-87RL10930

EDT/ECN: ECN-635429 UC: 2070
Org Code: 74620 Charge Code: N4G4C
B&R Code: EW 3120074 Total Pages: 195 KMA 2/4/97

Key Words: Waste Characterization, Single-Shell Tank, SST, Tank 241-T-104, Tank T-104, T-104, T Farm, Tank Characterization Report, TCR, Waste Inventory, TPA Milestone M-44

Abstract: This document summarizes the information on the historical uses, present status, and the sampling and analysis results of waste stored in Tank 241-T-104. This report supports the requirements of the Tri-Party Agreement Milestone M-44-05.

TRADEMARK DISCLAIMER. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise, does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof or its contractors or subcontractors.

Printed in the United States of America. To obtain copies of this document, contact: WHC/BCS Document Control Services, P.O. Box 1970, Mailstop H6-08, Richland WA 99352, Phone (509) 372-2420; Fax (509) 376-4989.

DATE
STA. 4
ID:
FEB 04 1997

Kara J Broz 2/4/97
Release Approval Date Release Stamp

Approved for Public Release

9713530.2804

RECORD OF REVISION	(1) Document Number HNF-SD-WM-ER-372	Page 1

(2) Title
Tank Characterization Report for Single-Shell Tank 241-T-104

CHANGE CONTROL RECORD

(3) Revision	(4) Description of Change - Replace, Add, and Delete Pages	Authorized for Release (5) Cog. Engr.	(6) Cog. Mgr. Date
0	(7) Initially released 09/29/94 on EDT-159087.	B.C. Simpson	C.S. Haller
1 RS	Incorporate per ECN-635429.	L.M. Sasaki L M Sasaki	K.M. Hall 2/3/97 Kathleen M. Hall

A-7320-005 (08/91) WEF168

9713530.2805

HNF-SD-WM-ER-372, Rev. 1
Formerly WHC-SD-WM-ER-372, Rev. 0
UC-2070

Tank Characterization Report for Single-Shell Tank 241-T-104

L. M. Sasaki
Lockheed Martin Hanford Corporation

J. D. Franklin
Los Alamos Technical Associates

J. L. Stroup
Fluor Daniel Northwest

L. Jensen
Numatec Hanford Corporation

R. T. Winward
Meier Associates

Date Published
January 1997

Prepared for the U.S. Department of Energy
Assistant Secretary for Environmental Management

Project Hanford Management Contractor for the
U.S. Department of Energy under Contract DE-AC06-96RL13200

Approved for public release; distribution is unlimited

CONTENTS

1.0 INTRODUCTION 1-1
1.1 SCOPE 1-1
1.2 TANK BACKGROUND 1-2

2.0 RESPONSE TO TECHNICAL ISSUES 2-1
2.1 SAFETY SCREENING 2-1
2.1.1 Exothermic Conditions (Energetics) 2-1
2.1.2 Flammable Gas 2-2
2.1.3 Criticality 2-2
2.2 OTHER TECHNICAL ISSUES 2-2
2.3 SUMMARY 2-3

3.0 BEST-BASIS INVENTORY ESTIMATE 3-1

4.0 RECOMMENDATIONS 4-1

5.0 REFERENCES 5-1

APPENDIXES

APPENDIX A: HISTORICAL TANK INFORMATION A-1

A1.0 CURRENT TANK STATUS A-3

A2.0 TANK DESIGN AND BACKGROUND A-4

A3.0 PROCESS KNOWLEDGE A-8
A3.1 WASTE TRANSFER HISTORY A-9
A3.2 HISTORICAL ESTIMATION OF TANK CONTENTS A-10

A4.0 SURVEILLANCE DATA A-14
A4.1 SURFACE-LEVEL READINGS A-14
A4.2 INTERNAL TANK TEMPERATURES A-14
A4.3 TANK 241-T-104 PHOTOGRAPHS A-15

A5.0 APPENDIX A REFERENCES A-18

CONTENTS (Continued)

APPENDIX B: SAMPLING OF TANK 241-T-104 . . . . . B-1

B1.0 TANK SAMPLING OVERVIEW B-3
B1.1 1992 CORE SAMPLING EVENT B-3
B1.1.1 Description of Sampling Event B-3
B1.1.2 Sample Handling B-5
B1.1.3 Sample Analysis B-9
B1.2 VAPOR PHASE MEASUREMENTS B-13
B1.3 DESCRIPTION OF HISTORICAL SAMPLING EVENT B-13

B2.0 ANALYTICAL RESULTS B-13
B2.1 OVERVIEW B-13
B2.2 TOTAL ALPHA ACTIVITY B-14
B2.3 THERMODYNAMIC ANALYSES B-14
B2.3.1 Thermogravimetric Analysis B-14
B2.3.2 Differential Scanning Calorimetry B-15
B2.4 PHYSICAL PROPERTIES B-15
B2.4.1 Density and Percent Solids B-15
B2.4.2 Particle Size B-16
B2.4.3 Rheology B-16
B2.5 INORGANIC ANALYSES B-17
B2.5.1 Inductively Coupled Plasma B-17
B2.5.2 Ion Chromatography B-17
B2.5.3 Total Uranium B-18
B2.5.4 Arsenic Selenium, and Mercury by Atomic Absorption Spectroscopy B-18
B2.5.5 Ammonia B-18
B2.5.6 Cyanide by Distillation and Spectroscopy B-18
B2.5.7 Nitrite by Spectrophotometry B-18
B2.5.8 pH B-18
B2.6 ORGANIC ANALYSES B-19
B2.6.1 Semivolatile and Volatile Organic Analysis B-19
B2.7 TOTAL INORGANIC AND ORGANIC CARBON B-19
B2.8 RADIONUCLIDES B-19
B2.8.1 Fission Products by Gamma Energy Analysis B-19
B2.8.2 Fission Products by Separation and Counting B-19
B2.8.3 Total Beta Activities by Proportional Counting B-20
B2.8.4 Transuranic Radionuclides by Separation and Counting B-20
B2.9 VAPOR PHASE MEASUREMENT B-20
B2.10 HISTORICAL SAMPLING RESULTS B-20
B2.11 ANALYTICAL DATA TABLES B-21

CONTENTS (Continued)

B3.0 ASSESSMENT OF CHARACTERIZATION RESULTS B-93
B3.1 FIELD OBSERVATIONS B-93
B3.2 QUALITY CONTROL ASSESSMENT B-93
B3.3 DATA CONSISTENCY CHECKS B-94
B3.3.1 Comparison of Results from Different Analytical Methods B-94
B3.3.2 Mass and Charge Balance B-96
B3.4 CALCULATION OF ANALYTICAL BASED MEANS AND INVENTORY B-98

B4.0 APPENDIX B REFERENCES B-106

APPENDIX C: STATISTICAL ANALYSIS FOR ISSUE RESOLUTION C-1

C1.0 STATISTICS FOR SAFETY SCREENING DQO C-3

C2.0 APPENDIX C REFERENCES C-4

APPENDIX D: EVALUATION TO ESTABLISH BEST-BASIS INVENTORY FOR TANK 241-T-104 . . . . . D-1

D1.0 CHEMICAL INFORMATION SOURCES D-3

D2.0 COMPARISON OF COMPONENT INVENTORY VALUES D-6

D3.0 REVIEW AND EVALUATION OF COMPONENT INVENTORIES D-6
D3.1 PROCESS KNOWLEDGE D-6
D3.2 HISTORICAL ESTIMATION OF THE CONTENTS OF TANK 241-T-104 . . . . . D-8
D3.3 PROCESS HISTORY ESTIMATION D-8
D3.4 CONTRIBUTING WASTE TYPES D-8
D3.5 TECHNICAL FLOWSHEET INFORMATION D-8
D3.6 EVALUATION OF COMPONENT INVENTORIES D-9
D3.6.1 Solids Concentration Factor and Partition Factors for First Cycle Bismuth Phosphate Waste in Tank 241-T-104 . . . . . D-10
D3.6.2 Inventory of Components Assumed to Precipitate 100 Percent . D-12

CONTENTS (Continued)

D4.0 DEFINE THE BEST-BASIS AND ESTABLISH COMPONENT INVENTORIES D-16

D5.0 APPENDIX D REFERENCES D-19

APPENDIX E: BIBLIOGRAPHY FOR TANK 241-T-104 . . . . . E-1

LIST OF FIGURES

A2-1. Riser Configuration for Tank 241-T-104 . . . . . A-6

A2-2. Tank Cross-Section A-7

A3-1. Tank Layer Model A-11

A4-1. Tank 241-T-104 Level History A-16

A4-2. Tank 241-T-104 High Temperature Plot A-17

LIST OF TABLES

1-1. Summary of Recent Sampling 1-2

1-2. Description of Tank 241-T-104. 1-3

2-1. Tank 241-T-104 Projected Heat Load 2-3

2-2. Summary of Screening Evaluation Results 2-3

3-1. Best-Basis Inventory Estimates for Nonradioactive Components in Tank 241-T-104 3-2

3-2. Best-Basis Inventory Estimates for Radioactive Components in Tank 241-T-104 3-3

4-1. Acceptance of Tank 241-T-104 Sampling and Analysis 4-1

LIST OF TABLES (Continued)

4-2. Acceptance of Evaluation of Characterization Data and Information for Tank 241-T-104 4-2

A1-1. Tank 241-T-104 Contents Status Summary A-4

A2-1. Tank 241-T-104 Risers A-8

A3-1. Tank 241-T-104 Major Transfers A-9

A3-2. Historical Tank Inventory Estimate A-12

B1-1. Integrated Data Quality Objective Requirements for Tank 241-T-104 . . . . . B-4

B1-2. Tank 241-T-104 Sample Description. B-6

B1-3. Tank 241-T-104 Sample Analysis Summary B-10

B2-1. Analytical Presentation Tables B-14

B2-2. Tank 241-T-104 Analytical Results: Total Alpha (Alpha) B-23

B2-3. Percent Water by TGA and Gravimetric Analysis. B-24

B2-4. Tank 241-T-104 Core 45 Physical Measurements B-28

B2-5. Tank 241-T-104 Analytical Results: Density (Physical Properties) B-28

B2-6. Tank 241-T-104 Particle Size Data B-30

B2-7. Shear Strength Results B-30

B2-8. Tank 241-T-104 Analytical Results: Aluminum (ICP) B-31

B2-9. Tank 241-T-104 Analytical Results: Antimony (ICP) B-32

B2-10. Tank 241-T-104 Analytical Results: Arsenic (ICP) B-33

B2-11. Tank 241-T-104 Analytical Results: Barium (ICP) B-34

B2-12. Tank 241-T-104 Analytical Results: Beryllium (ICP) B-35

LIST OF TABLES (Continued)

B2-13. Tank 241-T-104 Analytical Results: Bismuth (ICP) B-36

B2-14. Tank 241-T-104 Analytical Results: Boron (ICP) B-37

B2-15. Tank 241-T-104 Analytical Results: Cadmium (ICP) B-38

B2-16. Tank 241-T-104 Analytical Results: Calcium (ICP) B-39

B2-17. Tank 241-T-104 Analytical Results: Cerium (ICP) B-40

B2-18. Tank 241-T-104 Analytical Results: Chromium (ICP) B-41

B2-19. Tank 241-T-104 Analytical Results: Cobalt (ICP) B-42

B2-20. Tank 241-T-104 Analytical Results: Copper (ICP) B-43

B2-21. Tank 241-T-104 Analytical Results: Iron (ICP) B-44

B2-22. Tank 241-T-104 Analytical Results: Lanthanum (ICP) B-45

B2-23. Tank 241-T-104 Analytical Results: Lead (ICP) B-46

B2-24. Tank 241-T-104 Analytical Results: Magnesium (ICP) B-47

B2-25. Tank 241-T-104 Analytical Results: Manganese (ICP) B-48

B2-26. Tank 241-T-104 Analytical Results: Nickel (ICP) B-49

B2-27. Tank 241-T-104 Analytical Results: Phosphorus (ICP) B-50

B2-28. Tank 241-T-104 Analytical Results: Potassium (ICP) B-51

B2-29. Tank 241-T-104 Analytical Results: Selenium (ICP) B-52

B2-30. Tank 241-T-104 Analytical Results: Silicon (ICP) B-53

B2-31. Tank 241-T-104 Analytical Results: Silver (ICP) B-54

B2-32. Tank 241-T-104 Analytical Results: Sodium (ICP) B-55

B2-33. Tank 241-T-104 Analytical Results: Strontium (ICP) B-56

LIST OF TABLES (Continued)

B2-34. Tank 241-T-104 Analytical Results: Sulfur (ICP) B-57

B2-35. Tank 241-T-104 Analytical Results: Tin (ICP) B-58

B2-36. Tank 241-T-104 Analytical Results: Titanium (ICP) B-59

B2-37. Tank 241-T-104 Analytical Results: Zinc (ICP) B-60

B2-38. Tank 241-T-104 Analytical Results: Zirconium (ICP) B-61

B2-39. Tank 241-T-104 Analytical Results: Chloride (IC) B-62

B2-40. Tank 241-T-104 Analytical Results: Fluoride (IC) B-62

B2-41. Tank 241-T-104 Analytical Results: Nitrate (IC) B-63

B2-42. Tank 241-T-104 Analytical Results: Nitrite (IC) B-63

B2-43. Tank 241-T-104 Analytical Results: Phosphate (IC) B-64

B2-44. Tank 241-T-104 Analytical Results: Sulfate (IC) B-64

B2-45. Tank 241-T-104 Analytical Results: Total Uranium (LF) B-65

B2-46. Tank 241-T-104 Analytical Results: Arsenic (AA [As]) B-65

B2-47. Tank 241-T-104 Analytical Results: Selenium (AA [Se]) B-66

B2-48. Tank 241-T-104 Analytical Results: Mercury (CVAA [Hg]) B-66

B2-49. Tank 241-T-104 Analytical Results: Ammonia (Distillation) B-67

B2-50. Tank 241-T-104 Analytical Results: Cyanide (Spec [CN]) B-67

B2-51. Tank 241-T-104 Analytical Results: Nitrite (Spectrophotometric) B-68

B2-52. Tank 241-T-104 Analytical Results: pH Measurement (pH) B-68

B2-53. Tank 241-T-104 Analytical Results: Bis(2-ethylhexyl) phthalate (SVOA) B-69

B2-54. Tank 241-T-104 Analytical Results: Dodecane (SVOA) B-69

LIST OF TABLES (Continued)

B2-55. Tank 241-T-104 Analytical Results: Pentadecane (SVOA) B-69

B2-56. Tank 241-T-104 Analytical Results: Tetradecane (SVOA) B-70

B2-57. Tank 241-T-104 Analytical Results: Tridecane (SVOA) B-70

B2-58. Tank 241-T-104 Analytical Results: Non-Detected SVOA Analytes. B-71

B2-59. Tank 241-T-104 Analytical Results: Acetone (VOA) B-72

B2-60. Tank 241-T-104 Analytical Results: Hexamethyl Disiloxane (VOA) B-73

B2-61. Tank 241-T-104 Analytical Results: Methoxytrimethyl Silane (VOA) B-73

B2-62. Tank 241-T-104 Analytical Results: Methylenechloride (VOA) B-74

B2-63. Tank 241-T-104 Analytical Results: Toluene (VOA) B-75

B2-64. Tank 241-T-104 Analytical Results: Trimethyl Silanol (VOA) B-76

B2-65. Tank 241-T-104 Analytical Results: Non-Detected VOA Analytes B-77

B2-66. Tank 241-T-104 Analytical Results: Carbonate (TIC) B-78

B2-67. Tank 241-T-104 Analytical Results: Total Organic Carbon (Furnace Oxidation) B-78

B2-68. Tank 241-T-104 Analytical Results: Americium-241 (GEA) B-79

B2-69. Tank 241-T-104 Analytical Results: Cesium-137 (GEA) B-79

B2-70. Tank 241-T-104 Analytical Results: Cobalt-60 (GEA) B-80

B2-71. Tank 241-T-104 Analytical Results: Europium-154 (GEA) B-80

B2-72. Tank 241-T-104 Analytical Results: Europium-155 (GEA) B-81

B2-73. Tank 241-T-104 Analytical Results: Iodine-129 (I129) B-81

B2-74. Tank 241-T-104 Analytical Results: Carbon-14 (C14) B-82

LIST OF TABLES (Continued)

B2-75. Tank 241-T-104 Analytical Results: Tritium (Liq. Scin.) B-82

B2-76. Tank 241-T-104 Analytical Results: Selenium-79 (Se79) B-82

B2-77. Tank 241-T-104 Analytical Results: Technetium-99 (Te) B-83

B2-78. Tank 241-T-104 Analytical Results: Strontium-90 (Sr) B-83

B2-79. Tank 241-T-104 Analytical Results: Total Beta B-84

B2-80. Tank 241-T-104 Analytical Results: Americium-241 (Alpha Spec) B-84

B2-81. Tank 241-T-104 Analytical Results: Plutonium-238 (Alpha Spec) B-85

B2-82. Tank 241-T-104 Analytical Results: Plutonium-239/240 (Alpha Spec) B-85

B2-83. Tank 241-T-104 Analytical Results: Neptunium-237 (Np237) B-86

B2-84. Tank 241-T-104 Analytical Results: Pu238 to Pu ratio (Mass Spec.) B-86

B2-85. Tank 241-T-104 Analytical Results: Pu239 to Pu ratio (Mass Spec.) B-87

B2-86. Tank 241-T-104 Analytical Results: Pu240 to Pu ratio (Mass Spec.) B-87

B2-87. Tank 241-T-104 Analytical Results: Pu241 to Pu ratio (Mass Spec.) B-88

B2-88. Tank 241-T-104 Analytical Results: Pu242 to Pu ratio (Mass Spec.) B-88

B2-89. Tank 241-T-104 Analytical Results: U234 to U ratio (Mass Spec.) B-89

B2-90. Tank 241-T-104 Analytical Results: U235 to U ratio (Mass Spec.) B-89

B2-91. Tank 241-T-104 Analytical Results: U236 to U ratio (Mass Spec.) B-90

B2-92. Tank 241-T-104 Analytical Results: U238 to U ratio (Mass Spec.) B-90

B2-93. 1996 Evaluation of Tank Headspace Flammability B-91

B2-94. Physical Properties of 1979 Core Sample. B-91

B2-95. Chemical Characteristics of Composite of 1979 Core Sample B-92

LIST OF TABLES (Continued)

B3-1. Total Alpha Comparison B-95

B3-2. Total Beta Comparison B-96

B3-3. Cation Mass and Charge Data. B-97

B3-4. Anion Mass and Charge Data B-98

B3-5. Mass Balance Totals. B-98

B3-6. Tank Concentration From Composite Samples. B-99

B3-7. Tank 241-T-104 Core Recoveries. B-104

C1-1. One-Sided 95 Percent Confidence Interval Upper Limits for Total Alpha for Tank 241-T-104 . . . . . C-4

D2-1. Sample- and Historical Tank Content-Based Inventory Estimates for Nonradioactive Components D-4

D2-2. Sample- and Historical Tank Content-Based Inventory Estimates for Radioactive Components D-5

D3-1. Estimated Total Volume of Waste Types Received By Tank 241-T-104 . . . . . D-7

D3-2. Technical Flowsheet and Los Alamos National Laboratory Defined Waste Streams (Hanford Defined Waste Model) D-9

D3-3. Comparison of Selected Component Inventory Estimates for Tank 241-T-104 Waste D-13

D3-4. Comparisons Based on Fuel Production D-14

D4-1. Best-Basis Inventory Estimates for Nonradioactive Components in Tank 241-T-104 . . . . . D-17

D4-2. Best-Basis Inventory Estimates for Radioactive Components in Tank 241-T-104 . . . . . D-18

LIST OF TERMS

1C1	first cycle decontamination waste 1944-1949
1C2	first cycle decontamination waste 1950-1956
μCi/g	microcuries per gram
μeq/g	microequivalents per gram
μg/g	micrograms per gram
μg/mL	micrograms per milliliter
μm	micrometers
AA	atomic absorption
ANOVA	analysis of variance
ASTM	American Society for Testing and Materials
BDL	below detection limit
Btu/hr	British thermal units per hour
CF	concentration factor
Ci	curies
Ci/L	curies per liter
CI	confidence interval
cm	centimeters
CW	cladding waste
CVAA	cold vapor atomic absorption
DL	drainable liquid
DOE	U.S. Department of Energy
DQO	data quality objectives
DSC	differential scanning calorimetry
dynes/cm^2	dynes per square centimeter
Ecology	Washington State Department of Ecology
ft	feet
GEA	gamma energy analysis
GHAA	gaseous hydride atomic absorption
g	grams
g/L	grams per liter
g/mL	grams per milliliter
HDW	Hanford defined waste
HTCE	historical tank content estimate
IC	ion chromatography
ICP	inductively coupled plasma
ID	incomplete data
in.	inches
J/g	joules per gram
kg	kilograms

LIST OF TERMS (Continued)

kg/L	kilograms per liter
kgal	kilogallons
kL	kiloliters
LFL	lower flammability limit
LL	lower limit
LF	laser fluorimetry
m	meter
M	moles per liter
mL	milliliters
mm	millimeters
MT	metric tons
MTU	metric tons of uranium
n/a	not applicable
NA	not analyzed
n/d	not decided
NPH	normal paraffin hydrocarbon
n/r	not reviewed
NR	not reported
PF	partitioning factor
PHMC	Project Hanford Management Contractor
PNNL	Pacific Northwest National Laboratory
ppmv	parts per million volume
Pa	pascals
QC	quality control
REML	restricted maximum likelihood estimation
RPD	relative percent difference
SU	supernatant
SVOA	semivolatile organic analysis
SWLIQ	saltwell liquid waste
TCLP	toxic characteristic leach procedure
TCR	tank characterization report
TGA	thermogravimetric analysis
TIC	total inorganic carbon
TLM	tank layer model
TOC	total organic carbon
TWRS	Tank Waste Remediation System
UL	upper limit
VOA	volatile organic analysis
W	watts
WSTRS	waste status and transaction record summary
wt%	weight percent

1.0 INTRODUCTION

One of the major functions of the Tank Waste Remediation System (TWRS) is to characterize wastes in support of waste management and disposal activities at the Hanford Site. Analytical data from sampling and analysis, along with other available information about a tank, are compiled and maintained in a tank characterization report (TCR). This report and its appendices serve as the TCR for single-shell tank 241-T-104. The objectives of this report are: 1) to use characterization data in response to technical issues associated with 241-T-104 waste; and 2) to provide a standard characterization of this waste in terms of a best-basis inventory estimate. The response to technical issues is summarized in Section 2.0, and the best-basis inventory estimate is presented in Section 3.0. Recommendations regarding safety status and additional sampling needs are provided in Section 4.0. Supporting data and information are contained in the appendices. This report also supports the requirements of the *Hanford Federal Facility Agreement and Consent Order* (Ecology et al. 1996) milestone M-44-05.

1.1 SCOPE

Characterization information presented in this report originated from sample analyses and known existing (historical) sources. While the data quality objectives (DQOs) required that technical issues be resolved using results from recent sampling events (listed in Table 1-1), other information could be used to support (or challenge) conclusions derived from these results. Historical information for tank 241-T-104, provided in Appendix A, included surveillance information, records pertaining to waste transfers and tank operations, and expected tank contents derived from a process knowledge model.

The results from the recent sampling events listed in Table 1-1, as well as sample data obtained prior to 1989, are summarized in Appendix B. The results of the 1992 sampling events, also reported in the laboratory data package (Pool 1994), satisfied the data requirements specified in the waste characterization plan for this tank (Hill et al. 1991). The statistical analysis and numerical manipulation of data used in issue resolution are reported in Appendix C. Appendix D contains the evaluation to establish the best basis for the inventory estimate and the statistical analysis performed for this evaluation. A bibliography that resulted from an in-depth literature search of all known information sources applicable to tank 241-T-104 and its respective waste types is contained in Appendix E. The reports listed in Appendix E may be found in the Tank Characterization Resource Center.

Table 1-1. Summary of Recent Sampling

Sample/Date	Phase	Location	Segmentation	Percent Recovery	Mass (g)
Core sample August 1992	Solid	Riser 3	None. Core composites and some segments analyzed	81	1,408
		Riser 6		79	1,410
Vapor sample February 1996	Gas	Riser 8, tank headspace	n/a	n/a	n/a

Note:
n/a = not applicable

1.2 TANK BACKGROUND

Tank 241-T-104 is located in the 200 West Area T Tank Farm on the Hanford Site. It is the first tank in a three-tank cascade series. The tank went into service in March 1946, receiving first cycle decontamination waste from bismuth phosphate fuel separation operations at T Plant. Cascading began in the second quarter of 1948. With the exception of several transfers of supernatant to other single-shell tanks (241-TX-118, -TY-103, and -T-101) and double-shell tank 241-AW-102, the entire tank history consisted of receipt and cascade of first-cycle decontamination waste (1C1 - produced from 1944 until 1949, and 1C2 - produced from 1950 until 1956) from T Plant bismuth phosphate operations. The tank was removed from service in 1976, primary stabilized in 1978, and partially isolated in 1982. Pumping of supernatant to support stabilization began in March 1996, and as of September 30, 1996, 317 kL (83.8 kgal) of supernatant had been removed from the tank (Hanlon 1996).

A description of tank 241-T-104 is summarized in Table 1-2. The tank has an operating capacity of 2,010 kL (530 kgal), and presently contains an estimated 1,408 kL (372 kgal) of non-complexed waste (Hanlon 1996). The tank is not on the Watch List (Public Law 101-510).

Table 1-2. Description of Tank 241-T-104.

TANK DESCRIPTION	
Type	Single-shell
Constructed	1943-1944
In-service	March 1946
Diameter	22.9 m (75.0 ft)
Operating depth	5.2 m (17 ft)
Capacity	2,010 kL (530 kgal)
Bottom Shape	Dish
Ventilation	Passive
TANK STATUS	
Waste classification	Non-complexed
Total waste volume[1]	1,408 kL (372 kgal)
Supernatant volume	0 kL (0 kgal)
Saltcake volume	0 kL (0 kgal)
Sludge volume	1,408 kL (372 kgal)
Drainable interstitial liquid volume	182 kL (48 kgal)
TANK STATUS	
Waste surface level (10/2/96)	351.8 cm (138.5 in.)
Temperature (2/77 to 11/96)	11.5 °C (52.7 °F) to 25.6 °C (78 °F)
Integrity	Sound
Watch List	None
SAMPLING DATE	
Core samples	August 1992
SERVICE STATUS	
Declared inactive	Second quarter 1976
Primary stabilization	1978
Partially isolated	1982
Stabilization	Began March 1996, currently in progress

Note:

[1]Waste volume is estimated from surface-level measurements.

This page intentionally left blank.

2.0 RESPONSE TO TECHNICAL ISSUES

The following technical issue has been identified for tank 241-T-104 (Brown et al. 1996).

- Does the waste pose or contribute to any recognized potential safety problems?

The waste characterization plan (Hill et al. 1991) provides the types of sampling and analysis used to address the first of these issues. Data from the analysis of the 1992 core samples and tank headspace flammability measurements conducted in 1996, as well as available historical information, provided the means to respond to this issue. This response is detailed in the following sections. See Appendix B for sample and analysis data for tank 241-T-104.

In addition to the technical issue related to the safety of the tank, Brown et al. (1996) identifies the need to provide sample material from this tank to perform sludge washing studies in support of waste pretreatment.

2.1 SAFETY SCREENING

The data needed to screen the waste in tank 241-T-104 for potential safety problems are documented in *Tank Safety Screening Data Quality Objective* (Dukelow et al. 1995). These potential safety problems are: exothermic conditions in the waste; flammable gases in the waste and/or tank headspace; and criticality conditions in the waste. Each of these conditions is addressed separately below. Because tank 241-T-104 is not a Watch List tank, the safety screening DQO was the only safety-related DQO associated with the sampling effort. Tank 241-T-104 was sampled in 1992, prior to the existence of the safety screening DQO. However, data from the analyses may be used to fulfill the requirements of the DQO.

2.1.1 Exothermic Conditions (Energetics)

The first requirement outlined in the safety screening DQO is to ensure that there are not sufficient exothermic constituents (organic or ferrocyanide) in tank 241-T-104 to present a safety hazard. Although the safety screening DQO required that the waste sample profile be tested for energetics every 24 cm (9.5 in.) to determine if the energetics exceed the safety threshold limit, differential scanning calorimetry (DSC) analyses were performed on whole segments and composites. The threshold limit for energetics is 480 J/g on a dry weight basis. Results obtained using DSC indicated that no exotherms were apparent for any of the samples from cores 45 and 46 (Pool 1994).

Historically, there is no evidence that any exothermic agent should exist in this waste. Waste transfer records indicate that the major waste type expected to be in the tank is 1C1 and 1C2 sludge from the bismuth phosphate process (Agnew et al. 1996a). Neither of these waste types is expected to have organic or ferrocyanide constituents.

2.1.2 Flammable Gas

Vapor phase measurements were not taken when cores 45 and 46 were obtained, but were taken in the tank headspace in February 1996 in support of a riser preparation procedure (WHC 1996). No flammable gas was detected (0 percent of the lower flammability limit [LFL]). Data from these vapor phase measurements are presented in Appendix B.

2.1.3 Criticality

The safety threshold limit for criticality is 1 g ^{239}Pu per liter of waste. Assuming that all total alpha activity is from ^{239}Pu and using a measured density of 1.29 g/mL, 1 g/L of ^{239}Pu is equivalent to 47.7 μCi/g of total alpha activity. Waste samples were tested for total alpha activity for both composite samples from both cores. Concentrations in all samples were well below this limit. Additionally, as required by the DQO, the upper limit of the one-sided 95 percent confidence interval (CI) for these results was less than 1 g/L; therefore, criticality is not an issue for this tank. The method used to calculate confidence intervals is contained in Appendix C.

2.2 OTHER TECHNICAL ISSUES

A factor in assessing tank safety is the heat generation and temperature of the waste. Heat is generated in the tanks from radioactive decay. An estimate of the tank heat load based on the 1992 sample event (Pool 1994) was 50.2 W (171 Btu/hr). The heat load estimate based on the tank process history was 185 W (631 Btu/hr) (Agnew et al. 1996b). The heat load estimate based on the tank headspace temperature was 950 W (3,240 Btu/hr) (Kummerer 1995). All of these estimates are quite low, and are well below the limit of 11,700 W (40,000 Btu/hr) that separates high- and low-heat-load tanks (Smith 1986.) The major contributors to the tank heat load are listed in Table 2-1. Radionuclides were chosen for the heat load calculation based on measurement above the detection limit and for contribution to the heat load greater than 0.001 W.

Sludge samples from the tank 241-T-104 core samples were provided to the pretreatment program. Wash and leach factors for this and other tanks were determined and will be incorporated into the TWRS Technical Baseline, where wash factors will be used to estimate partitioning of the SST inventory into soluble and insoluble portions, and the leach factor will be used to estimate further removal of some analytes (Colton 1996).

2.3 SUMMARY

The results from all tank waste sample analyses performed to address tank safety screening issues showed that no primary analyte exceeded any of the safety decision threshold limits. Tank vapor sampling indicated no flammability concerns with the tank vapors. The results of the analyses are summarized in Table 2-2.

Table 2-1. Tank 241-T-104 Projected Heat Load.[1]

Radionuclide	Watts/Curie	Curies	Watts
^{241}Am	0.0328	30.5	1.03
^{137}Cs	0.00472	428	2.02
^{155}Eu	0.00248	7.35	0.0182
^{239}Pu	0.0305	269	8.20
^{240}Pu	0.0306	32.5	0.995
^{90}Sr	0.00670	5,650	37.9
Total watts			50.2

Note:

[1]Pool (1994)

Table 2-2. Summary of Screening Evaluation Results.

Issue	Sub-issue	Result
Safety screening	Energetics	No exotherms observed in any sample.
	Flammable gas	1996 vapor measurement reported 0 percent of LFL (combustible gas meter).
	Criticality	All analytical results and confidence interval limits were well below 47.7 μCi/g total alpha (within 95 percent confidence interval on each sample).

This page left blank intentionally.

3.0 BEST-BASIS INVENTORY ESTIMATE

Information about chemical, radiological, and/or physical properties is used to perform safety analyses, engineering evaluations, and risk assessment associated with waste management activities, as well as regulatory issues. These activities include overseeing tank farm operations and identifying, monitoring, and resolving safety issues associated with these operations and with the tank wastes. Disposal activities involve designing equipment, processes, and facilities for retrieving wastes and processing them into a form that is suitable for long-term storage.

Chemical and radiological inventory information is generally derived using three approaches: 1) component inventories are estimated using the results of sample analyses; 2) component inventories are predicted using the Hanford defined waste (HDW) model based on process knowledge and historical information; or 3) a tank-specific process estimate is made based on process flowsheets, reactor fuel data, essential material usage, and other operating data. Not surprisingly, the information derived from these different approaches is often inconsistent.

An effort is underway to provide waste inventory estimates that will serve as the standard characterization for the various waste management activities (Hodgson and LeClair 1996). As part of this effort, an evaluation of available chemical information for tank 241-T-104 was performed, including the following:

- Data from two 1992 core samples
- An inventory estimate generated by the HDW model (Agnew et al. 1996b)
- Evaluation of the 1C/cladding waste (CW) flowsheet and plant throughput comparisons.

Based on this evaluation, a best-basis inventory was developed. In general, the sample-based TCR results were preferred when they were reasonable and consistent with other results.

The best-basis inventory for tank 241-T-104 is presented in Tables 3-1 and 3-2. A complete discussion of the methods and assumptions used to derive the best-basis inventory is presented in Appendix D.

Table 3-1. Best-Basis Inventory Estimates for Nonradioactive Components in Tank 241-T-104 (November 19, 1996).[1]

Analyte	Total Inventory (kg)	Basis (S, M, or E)
Al	33,500	S
Bi	37,400	S
Ca	3,120	S
Cl	1,440	S
TIC as CO_3	5,970	M_H
Cr	1,860	S
F	18,400	S
Fe	19,000	S
Hg	26.2	M_H
K	191	S
La	0.0066	M_H
Mn	133	S
Na	134,000	S
Ni	22,600	S
NO_2	8,770	S
NO_3	125,000	S
OH	NR	
Pb	0.87	M_H
P as PO_4^2	162,000	S
Si	14,000	S
S as SO_4	8,390	S
Sr	213	S
TOC	NR	
U_{TOTAL}	1,930	S
Zr	80.6	S

Notes:

NR = Not reported
S = Sample-based
M_H = Hanford Defined Waste model-based
E = Engineering assessment-based

[1]Based on 1992 core samples (see Appendix B)

[2]Inductively coupled plasma (ICP) much higher than ion chromatography (IC)

Table 3-2. Best-Basis Inventory Estimates for Radioactive Components in Tank 241-T-104 (November 19, 1996).[1]

Analyte	Total Inventory (Ci)	Basis (S, M_H, or E)
^{90}Sr	5,650	S
^{137}Cs	428	S
^{155}Eu	7.35	S
^{234}U	0.140 kg	S
^{235}U	13.0 kg	S
^{236}U	0.130 kg	S
^{238}U	1920 kg	S
^{239}Pu	269	S
^{240}Pu	32.5	S
^{241}Am	30.5	S
^{241}Pu	184	S

Notes:

S = Sample-based
M_H = Hanford Defined Waste model-based
E = Engineering assessment-based

[1]Based on 1992 core samples (see Appendix B)

This page left blank intentionally.

4.0 RECOMMENDATIONS

The sampling and analysis activities performed for tank 241-T-104 have met all requirements for the tank safety screening DQO (Dukelow et al. 1995). All analytical results for the safety screening DQO are well within the safety notification limits. A characterization best-basis inventory was also developed for the tank contents.

Table 4-1 summarizes the status of Project Hanford Management Contractor (PHMC) Program Office review and acceptance of the sampling and analysis results reported in this characterization report. All DQO issues required to be addressed by sampling and analysis are listed in column one of Table 4-1. The second column indicates whether the requirements of the DQO were met by the sampling and analysis activities performed and is answered with a "yes" or a "no." The third column indicates concurrence and acceptance by the program in TWRS that is responsible for the DQO that the sampling and analysis activities performed adequately meet the needs of the DQO. A "Yes" or "No" in column three indicates acceptance or disapproval of the sampling and analysis information presented in the TCR. If the results/information have not yet been reviewed, "n/r" is shown in the column. If the results/information have been reviewed, but acceptance or disapproval has not been decided, "n/d" is shown in the column.

Table 4-1. Acceptance of Tank 241-T-104 Sampling and Analysis.

Issue	Evaluation Performed	PHMC Program Office Acceptance
Safety Screening DQO	Yes	Yes

Table 4-2 summarizes the status of PHMC Program Office review and acceptance of the evaluations and other characterization information contained in this report. The evaluation specifically outlined in this report is the evaluation to determine whether the tank is safe, conditionally safe, or unsafe. Column one lists the evaluations performed in this report. Columns two and three are in the same format as Table 4-1. The manner in which concurrence and acceptance are summarized is also the same as that in Table 4-1.

Table 4-2. Acceptance of Evaluation of Characterization Data and Information for Tank 241-T-104.

Issue	Evaluation Performed	PHMC Program Office Acceptance
Safety categorization (tank is safe)	Yes	Yes

5.0 REFERENCES

Agnew, S. F., R. A. Corbin, T. B. Duran, K. A. Jurgensen, T. P. Ortiz, and B. L. Young, 1996a, *Waste Status and Transaction Record Summary for the Northwest Quadrant of the Hanford 200 East Area*, WHC-SD-WM-TI-669, Rev. 1, Westinghouse Hanford Company, Richland, Washington.

Agnew, S. F., J. Boyer, R. A. Corbin, T. B. Duran, J. R. Fitzpatrick, K. A. Jurgensen, T. P. Ortiz, and B. L. Young, 1996b, *Hanford Tank Chemical and Radionuclide Inventories: HDW Model Rev. 3*, LA-UR-96-858, Los Alamos National Laboratory, Los Alamos, New Mexico.

Brown, T. M., S. J. Eberlein, J. W. Hunt, and T. J. Kunthara, 1996, *Tank Waste Characterization Basis*, WHC-SD-WM-TA-164, Rev. 2, Westinghouse Hanford Company, Richland, Washington.

Colton, N. G., 1996, *Status Report: Pretreatment Chemistry Evaluation - Wash and Leach Factors for the Single-Shell Tank Waste Inventory*, PNNL-11290, Pacific Northwest National Laboratory, Richland, Washington.

Dukelow, G. T., J. W. Hunt, H. Babad, and J. E. Meacham, 1995, *Tank Safety Screening Data Quality Objective*, WHC-SD-WM-SP-004, Rev. 2, Westinghouse Hanford Company, Richland, Washington.

Ecology, EPA and DOE, 1996, *Hanford Federal Facility Agreement and Consent Order,* as amended, Washington State Department of Ecology, U.S. Environmental Protection Agency, and U.S. Department of Energy, Olympia, Washington.

Hanlon, B. M., 1996, *Waste Tank Summary Report for Month Ending September 30, 1996*, WHC-EP-0182-102, Westinghouse Hanford Company, Richland, Washington.

Hill, J. G., W. I. Winters, B. C. Simpson, J. W. Buck, P. J. Chamberlain, and V. L. Hunter, 1991, *Waste Characterization Plan for the Hanford Site Single-Shell Tanks*, WHC-EP-0210, Rev. 3, Westinghouse Hanford Company, Richland, Washington.

Hodgson, K. M., and M. D. LeClair, 1996, *Work Plan for Defining a Standard Inventory Estimate for Wastes Stored in Hanford Site Underground Tanks*, WHC-SD-WM-WP-311, Rev. 1, Lockheed Martin Hanford Corporation, Richland, Washington.

Kummerer, M., 1995, *Topical Report on Heat Removal Characteristics of Waste Storage Tanks*, WHC-SD-WM-SARR-010, Rev. 1, Westinghouse Hanford Company, Richland, Washington.

Pool, K. N., 1994, *Single-Shell Tank Waste Characterization Tank 241-T-104, Core 45 and 46*, WHC-SD-WM-DP-032, Rev. 0A, Westinghouse Hanford Company, Richland, Washington.

Public Law 101-510, 1990, "Safety Measures for Waste Tanks at Hanford Nuclear Reservation," Section 3137 of *National Defense Authorization Act for Fiscal Year 1991*.

Smith, D. M., 1986, *Single-Shell Tank Isolation Safety Analysis Report*, WHC-SD-WM-SAR-006, Rev. 2, Westinghouse Hanford Company, Richland, Washington.

WHC, 1996, *T-104 Riser Preparation*, Work Package WS-95-00291, Westinghouse Hanford Company, Richland, Washington.

APPENDIX A

HISTORICAL TANK INFORMATION

This page intentionally left blank.

APPENDIX A

HISTORICAL TANK INFORMATION

Appendix A describes tank 241-T-104 based on historical information. For this report, historical information includes any information about the fill history, waste types, surveillance, or modeling data about the tank. This information is often useful for supporting or challenging conclusions based on sampling and analysis.

This appendix contains the following information:

- **Section A1**: Current status of the tank, including the current waste levels as well as the stabilization and isolation status of the tank.
- **Section A2**: Information about the design of the tank.
- **Section A3**: Process knowledge of the tank; i.e., the waste transfer history and the estimated contents of the tank based on modeling data.
- **Section A4**: Surveillance data for tank 241-T-104, including surface-level readings, temperatures, and a description of the waste surface based on photographs.
- **Section A5**: References for Appendix A.

Historical sampling results from a 1979 core sample and analysis effort are included in Appendix B.

A1.0 CURRENT TANK STATUS

As of September 30, 1996, tank 241-T-104 contained an estimated 1,408 kL (372 kgal) of non-complexed waste (Hanlon 1996). The total waste volume is estimated using a surface-level gauge. The volumes of the waste phases found in the tank are shown in Table A1-1.

The tank was removed from service in the second quarter of 1976, primary stabilized in 1978, and partially isolated in 1982. Stabilization of tank 241-T-104 began in March 1996, and was in progress at the time of the writing of this report. As of September 30, 1996, 317 kL (83.8 kgal) had been pumped from the tank (Hanlon 1996). The tank is classified as sound, is passively ventilated, and is not on the Watch List (Public Law 101-510).

Table A1-1. Tank 241-T-104 Contents Status Summary (Hanlon 1996).[1]

Waste Type	kL (kgal)
Total waste	1,408 (372)
Supernatant	0 (0)
Sludge	1,408 (372)
Saltcake	0 (0)
Drainable interstitial liquid	182 (48)
Drainable liquid remaining	182 (48)
Pumpable liquid remaining	170 (45)

Note:

[1]Hanlon (1996). For definitions and calculation methods refer to Appendix C of Hanlon.

A2.0 TANK DESIGN AND BACKGROUND

Tank 241-T-104 was constructed during 1943 and 1944. It is one of twelve 2,010-kL (530-kgal) tanks in T Farm. These tanks were designed for nonboiling waste with a maximum fluid temperature of 104 °C (220 °F). A typical T Farm tank contains 9 to 11 risers ranging in size from 10 cm (4 in.) to 1.1 m (42 in.) in diameter that provide surface-level access to the underground tank. Generally, there is one riser through the center of the tank dome and four or five each on opposite sides of the dome.

Tank 241-T-104 entered service in March 1946 and is first in a three-tank cascading series with tanks 241-T-105 and -T-106. These tanks are connected by a 7.6-cm (3-in.) cascade line. The bottom center elevation of tank 241-T-104 is 193.5 m (635 ft) above sea level. The tank cascades to tank 241-T-105 at 193.2 m (634 ft), which then cascades to tank 241-T-106, which has a bottom center elevation at 192.9 m (633 ft). The cascade overflow height is approximately 4.78 m (188 in.) from the tank bottom (as measured at the tank wall) and 60 cm (2 ft) below the top of the steel liner.

These single-shell tanks are constructed of 30-cm (1-ft)-thick reinforced concrete with a 6.4-mm (1/4-in.) mild carbon steel liner (ASTM A283 Grade C) on the bottom and sides and a 38-cm (1.25-ft)-thick domed concrete top. These tanks have a dished bottom with a 1.2-m (4-ft) radius knuckle, a diameter of 22.9 m (75.0 ft) and a 5.2-m (17-ft) operating depth. The tanks are set on a reinforced concrete foundation.

A three-ply cotton fabric waterproofing was applied over the foundation and the steel tank. Four coats of primer paint were sprayed on all exposed interior tank surfaces. Tank ceiling domes were covered with three applications of magnesium zinc fluorosilicate wash. Lead flashing was used to protect the joint where the steel liner meets the concrete dome. Asbestos gaskets were used to seal the access holes in the tank dome. The tanks were waterproofed on the sides and top with tar and gunite. Each tank was covered with approximately 2.1 m (7 ft) of overburden.

The surface level is monitored through riser 5. Riser 4 contains a thermocouple tree with 11 thermocouples attached at known elevations. Figure A2-1 is a plan view of the riser configuration. A list of tank 241-T-104 risers showing their sizes and general use is provided in Table A2-1.

A tank cross section showing the approximate waste level, along with a schematic of the tank equipment, is shown in Figure A2-2. Tank 241-T-104 has nine risers numbered 1 through 8, and 13. Risers 2, 3, 6, 7, and 13 are all 30 cm (12 in.) in diameter. Risers 1, 4, 5 and 8 are 10-cm (4 in.) in diameter. Risers 2, 3, 6, and 8 are tentatively available for sampling (Lipnicki 1996). Risers 2 and 3 are approximately 90 degrees counterclockwise from the inlet, and risers 6 and 8 are approximately 90 degrees clockwise from the inlet.

Tank 241-T-104 has four process inlet nozzles and one cascade overflow outlet located approximately 4.8 m (188 in.) from the tank bottom (as measured at the tank wall). Locations are shown on Figure A2-1.

Figure A2-1. Riser Configuration for Tank 241-T-104.





Figure A2-2. Tank Cross-Section

Table A2-1. Tank 241-T-104 Risers.[1]

Number	Diameter (inches)	Description and Comments
R1	4 in.	Liquid observation well (benchmarked 12/11/86)
R2	12 in.	Blind flange[2]
R3	12 in.	Flange[2]
R4	4 in.	Thermocouple tree
R5	4 in.	ENRAF gauge
R6	12 in.	Spare[2] (benchmarked 12/11/86)
R7	12 in.	Concrete plug
R8	4 in.	Breather filter[2]
R13	12 in.	Saltwell screen (benchmarked)
N1	3 in.	Outlet overflow nozzle
N2	3 in.	Process inlet nozzle
N3	3 in.	Process inlet nozzle
N4	3 in.	Process inlet nozzle
N5	3 in.	Process inlet nozzle

Notes:

[1]Alstad (1993), Tran (1993), Vitro Engineering (1979).

[2]Available for sampling (Lipnicki 1996).

A3.0 PROCESS KNOWLEDGE

The following sections: 1) provide information about the transfer history of tank 241-T-104; 2) describe the process wastes that made up the transfers; and 3) give an estimate of the current tank contents based on transfer history.

A3.1 WASTE TRANSFER HISTORY

Table A3-1 summarizes the waste transfer history of tank 241-T-104 (Agnew et al. 1996b). Waste was initially added to tank 241-T-104 in March 1946 with the addition of first cycle decontamination waste from the bismuth phosphate process (1C1) from T Plant. The tank was filled by August 1946. Cascading had not begun at this time, but did begin in the second quarter of 1948 with the addition to the tank of more 1C1 waste from T Plant. With the exception of a transfer of 227 kL (60 kgal) of supernatant to tank 241-TX-118 in the second quarter of 1951, the tank's activity consisted of cascading 1C2 waste from T Plant to tank 241-T-105 until the third quarter of 1954. Tank 241-TY-103 received 182 kL (48 kgal) of supernatant from tank 241-T-104 in the third quarter of 1969, tank 241-T-101 received 57 kL (15 kgal) in the first quarter of 1976, and tank 241-AW-102 received 144 kL (38 kgal) in the third quarter of 1992.

Table A3-1. Tank 241-T-104 Major Transfers.[1,2] (2 sheets)

Transfer Source	Transfer Destination	Waste Type	Time Period	Estimated Waste Volume	
				kL	kgal
T Plant		1C1	1946 - 1951	6,386	1,687
	241-T-105	1C1	1946 - 1951	-4,122	-1,089
	241-TX-118	SU	1951	-227	-60
T-Plant		1C2	1952 - 1954	6,711	1,773
	241-T-105	1C2	1952 - 1954	-6,832	-1,805
	241-TY-103	SU	1969	-182	-48
	241-T-101	SU	1976	-57	-15
	241-AW-102	SWLIQ	1992	-144	-38
4	244-TX[3]	SWLIQ	1996	-318	-84[4]

Table A3-1. Tank 241-T-104 Major Transfers.[1,2] (2 sheets)

Notes:

1C First-cycle decontamination waste from the $BiPO_4$ process (contains 10 percent of the fission products and 1 percent plutonium and often included cladding waste). 1C1 waste was produced from 1944 until 1949. 1C2 waste was produced from 1950 until 1956.

SU Supernatant (liquid considered free of contamination to the extent it could be pumped to a crib).

SWLIQ Saltwell liquid waste (dilute non-complexed liquid pumped from single-shell tanks to double-shell tanks).

[1]Agnew et al. (1996b)

[2]Because only major transfers are listed, the sum of these transfers will not equal the current tank waste volume.

[3]Saltwell liquid was pumped to double-contained receiver tank 244-TX and is destined for transfer to tank 241-SY-102.

[4]Volume transferred as of September 30, 1996.

A3.2 HISTORICAL ESTIMATION OF TANK CONTENTS

This section provides an estimate of the contents of tank 241-T-104 based on historical transfer data. The historical data used for this historical tank content estimate (HTCE) are the Hanford defined waste (HDW) list (Agnew et al. 1996a), the tank layer model (TLM) (Agnew et al. 1996a), and the waste status and transaction record summary (WSTRS) (Agnew et al. 1996b). The HTCEs are documented in *Hanford Tank Chemical and Radionuclide Inventories: HDW Model Rev. 3* (Agnew et al. 1996a). The WSTRS is a compilation of available waste transfer and volume status data. The HDW provides the assumed typical compositions for 50 separate waste types. In some cases, the available data are incomplete, reducing the usability of the transfer data and the modeling results derived from it. The TLM takes the WSTRS data, models the waste deposition processes, and, using data from the HDW, derives the primary waste layers in the tank. Thus, these model predictions can only be considered estimates that require further evaluation using analytical data.

Based on Agnew et al. (1996a) and Agnew et al. (1996b), tank 241-T-104 contains 704 kL (186 kgal) of 1C1 waste and 969 kL (256 kgal) of 1C2 waste. Because the estimate is for the tank contents as of the fourth quarter of 1993 and liquid has since been pumped from the tank, the HDW waste volume estimates are greater than the current waste volume in the tank. Figure A3-1 shows a graphical representation of the estimated waste type and volume

for the tank layer. The historical tank content estimate model predicts 1C1 waste to contain greater than 1.00 weight percent of sodium, bismuth, iron, hydroxide, nitrate, and phosphate; aluminum, calcium, nitrite, carbonate, sulfate, silicate, and fluoride are expected to be present in greater than 0.100 weight percent quantities. 1C2 waste is predicted to contain greater than 1 weight percent of sodium, aluminum, hydroxide, nitrate, and phosphate; bismuth, calcium, iron, carbonate, sulfate, silicate, and fluoride are expected to be present in greater than 0.100 weight percent quantities. Table A3-2 shows the historical estimate of the expected waste constituents and their concentrations.

Figure A3-1. Tank Layer Model.



Table A3-2. Historical Tank Inventory Estimate.[1,2] (2 sheets)

Total Inventory Estimate			
Physical Properties			
Total solid waste	2.11E+06 kg (445 kgal)		
Heat load	185 W (631 Btu/hr)		
Bulk density	1.25 g/mL		
Water wt%	72.7		
Total organic carbon wt% carbon (wet)	0.00379		
Chemical Constituents	**M**	**ppm**	**kg[3]**
Na^+	4.12	75,700	1.59E+05
Al^{3+}	0.699	15,100	31,700
Fe^{3+} (total Fe)	0.238	10,600	22,400
Cr^{3+}	0.00442	176	371
Bi^{3+}	0.0576	9,620	20,300
La^{3+}	2.81E-08	0.00312	0.00657
Hg^{2+}	7.75E-05	12.4	26.2
Zr (as $ZrO(OH)_2$)	0.00835	609	1,280
Pb^{2+}	2.50E-06	0.414	0.873
Ni^{2+}	0.00127	59.7	126
Sr^{2+}	9.36E-09	6.56E-04	0.00138
Mn^{4+}	1.07E-05	0.468	0.986
Ca^{2+}	0.0578	1,850	3,900
K^+	0.00311	97.3	205
OH^-	2.94	40,000	84,200
NO_3^-	0.395	19,600	41,200
NO_2^-	0.223	8,210	17,300
CO_3^{2-}	0.0590	2,830	5,970
PO_4^{3-}	1.06	80,700	1.70E+05
SO_4^{2-}	0.0490	3,760	7,930
Si (as SiO_3^{2-})	0.0555	1,250	2,630

Table A3-2. Historical Tank Inventory Estimate.[1,2] (2 sheets)

Total Inventory Estimate			
Chemical Constituents (Cont'd)	**M**	**ppm**	**kg[3]**
F^-	0.180	2,730	5,760
Cl^-	0.0142	402	847
citrate	8.84E-05	13.4	28.2
$EDTA^{4-}$	6.86E-05	15.8	33.3
$HEDTA^{3-}$	1.30E-04	28.6	60.2
glycolate	3.70E-04	22.2	46.7
acetate	2.21E-05	1.04	2.20
oxalate	2.40E-08	0.00169	0.00356
DBP	5.37E-05	11.4	24.1
butanol	5.37E-05	3.18	6.70
NH_3	5.42E-04	7.36	15.5
$Fe(CN)_6^{4-}$	0	0	0
Radiological Constituents	**Ci/L**	**μCi/g**	**Ci[3]**
Pu		0.0126	0.442 kg
U	6.34E-04 M	121 μg/g	254 kg
Cs	0.0226	18.1	38,100
Sr	5.52E-04	0.441	930

Notes:

[1]Agnew et al. (1996a)

[2]The HTCE predictions have not been validated and should be used with caution.

[3]Differences exist among the inventories in this column and the inventories calculated from the two sets of concentrations.

A4.0 SURVEILLANCE DATA

Tank 241-T-104 surveillance consists of surface-level measurements (liquid and solid), temperature monitoring inside the tank (waste and headspace), and leak detection well (drywell) monitoring for radioactivity outside the tank. Surveillance data provide the basis for determining tank integrity.

Liquid-level measurements can indicate if the tank has a major leak. Solid surface-level measurements provide an indication of physical changes and consistencies of the solid layers of a tank. Drywells located around the tank perimeter may show increased radioactivity due to leaks.

A4.1 SURFACE-LEVEL READINGS

Tank 241-T-104 is considered sound. Since January 1996, surface levels are measured quarterly through riser 5 using an ENRAF[1] gauge. Prior to January 1996, a manual tape was used to measure the waste surface level. The leak detection criteria for tank 241-T-104 are an increase of 5.1 cm (2.0 in) from the baseline value and no value for a decrease. From January 1993 to January 1996, readings ranged from 391.9 cm (154.3 in.) to 395.0 cm (155.5 in.). A level history graph of the volume measurements is presented in Figure A4-1. The surface-level plot indicates a steady waste level from January 1991 to January 1996. However, as discussed in Section A1.0, saltwell pumping began in March 1996 and the surface level has been decreasing as the liquid has been pumped. As of October 2, 1996, the measured waste level was 351.8 cm (138.5 in.).

Tank 241-T-104 has a liquid observation well, located in riser 1. The tank is monitored weekly with a neutron probe and on request with a gamma probe to determine the interstitial liquid level. The maximum deviations from the baseline are a 9 cm (0.3 ft) increase and a 12 cm (0.4 ft) decrease. Tank 241-T-104 has five identified drywells. Drywell 50-04-10 is active with readings above 50 counts per second and below 200 counts per second. Drywells 50-04-03, 50-04-07, and 50-04-08 were active prior to 1990 but currently have readings less than 50 counts per second (Brevick et al. 1995).

A4.2 INTERNAL TANK TEMPERATURES

Tank 241-T-104 has a single thermocouple tree with 11 thermocouples to monitor the waste temperature through riser 4. Thermocouple 1 is 36.6 cm (1.2 ft) from the bottom of the tank. Thermocouples 2 through 9 are spaced at 61-cm (2-ft) intervals above thermocouple 1. Thermocouples 9 though 11 are at 1.22-m (4-ft) intervals.

---

[1]Trademark of ENRAF Corporation, Houston, Texas.

Manual thermocouple readings are available between February 1, 1977 and July 1, 1995. Readings were recorded as often as quarterly in 1977 and 1978, but occurred less frequently for the later years. There are no manual thermocouple readings for 1979, 1982, 1984 through 1986, and 1990. On June 2, 1994, the Tank Monitoring and Control System began automatic recording of thermocouple measurements for thermocouples 1 through 8 and 11 on a daily basis. With few exceptions, the daily thermocouple readings are continual and non-suspect. There are no readings available for thermocouples 9 and 10 after July 1, 1995.

The average tank temperature from February 1977 to November 1996 is 17.9 °C (64.2 °F), the minimum is 11.5 °C (52.7 °F), and the maximum is 25.6 °C (78 °F). The average temperature for the past year was 17.5 °C (63.6 °F), the minimum was 11.5 °C (52.7 °F), and the maximum was 21.6 °C (70.88 °F). On November 5, 1996, the low temperature, 17.3 °C (63 °F) was from thermocouple 1, and the high temperature, 19.6 °C (67.3 °F), was from thermocouple 8. Plots of the thermocouple readings can be found in the supporting document for the HTCE (Brevick et al. 1995). Figure A4-2 shows a graph of the weekly high temperature.

A4.3 TANK 241-T-104 PHOTOGRAPHS

In the photographs taken in 1989, the waste in tank 241-T-104 appears uniform, with small puddles of yellow liquid. The waste is tan in color, and resembles wet paste. Indentations appear on the surface of the waste which may have been caused by gas bubbles. A manual tape, saltwell screen, thermowell, liquid observation well, and some nozzles are identified, as well as a discarded measurement tape on the surface of the waste. According to photographer's notes, a photograph taken in 1980 more clearly shows the tank walls, with tar rings. The photograph has not been located. Since the tank is currently being salt well liquid pumped, the photographs may not represent the current tank waste surface..

Figure A4-1. Tank 241-T-104 Level History.



Figure A4-2. Tank 241-T-104 High Temperature Plot.



A5.0 APPENDIX A REFERENCES

Agnew, S. F., J. Boyer, R. A. Corbin, T. B. Duran, J. R. Fitzpatrick, K. A. Jurgensen, T. P. Ortiz, and B. L. Young, 1996a, *Hanford Tank Chemical and Radionuclide Inventories: HDW Model Rev. 3*, LA-UR-96-858, Los Alamos National Laboratory, Los Alamos, New Mexico.

Agnew, S. F., R. A. Corbin, T. B. Duran, K. A. Jurgensen, T. P. Ortiz, and B. L. Young, 1996b, *Waste Status and Transaction Record Summary for the Northwest Quadrant of the Hanford 200 East Area*, WHC-SD-WM-TI-669, Rev. 1, Westinghouse Hanford Company, Richland, Washington.

Alstad, A. T., 1993, *Riser Configuration Document for Single-Shell Waste Tanks*, WHC-SD-WM-RE-TI-053, Rev. 9, Westinghouse Hanford Company, Richland, Washington.

Brevick, C. H., L. A. Gaddis, and W. W. Pickett, 1995, *Supporting Document for the Historical Tank Content Estimate for T Tank Farm*, WHC-SD-WM-ER-320, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

Hanlon, B. M., 1996, *Waste Tank Summary Report for Month Ending September 30, 1996*, WHC-EP-0182-102, Westinghouse Hanford Company, Richland, Washington.

Lipnicki, J., 1996, *Waste Tank Risers Available for Sampling*, WHC-SD-WM-TI-710, Rev. 3, Westinghouse Hanford Company, Richland, Washington.

Public Law 101-510, 1990, "Safety Measures for Waste Tanks at Hanford Nuclear Reservation," Section 3137 of *National Defense Authorization Act for Fiscal Year 1991*.

Tran, T. T., 1993, *Thermocouple Status Single-Shell and Double-Shell Waste Tanks*, WHC-SD-WM-TI-553, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

Vitro Engineering Corporation, 1979, *Piping Waste Tank Isolation 241-T-104*, Drawing Number H-2-73061, Vitro Engineering Corporation, Richland, Washington.

APPENDIX B

SAMPLING OF TANK 241-T-104

This page intentionally left blank.

APPENDIX B

SAMPLING OF TANK 241-T-104

Appendix B provides sampling and analysis information for each known sampling event for tank 241-T-104 and provides an assessment of the core sample results.

- **Section B1**: Tank Sampling Overview
- **Section B2**: Analytical Results
- **Section B3**: Interpretations of Characterization Results
- **Section B4**: References for Appendix B.

Future sampling of tank 241-T-104 will be appended to the above list.

B1.0 TANK SAMPLING OVERVIEW

This section describes the August 1992 core sampling and analysis events for tank 241-T-104. Core samples were obtained and analyzed to satisfy the requirements of the *Waste Characterization Plan for the Hanford Site Single-Shell Tanks* (Hill et al. 1991). Documentation for laboratory work in support of Hill et al. (1991) can be found in *Sampling and Analysis of Ten Single-Shell Tanks* Revs. 0 and 1 (Silvers 1991), *Technical Project Plan* (Smith 1992), and *Pacific Northwest Laboratory Single-Shell Tank Waste Characterization Project (16021) and Single-Shell Tank Safety Analysis Project (19091) Technical Project Plan* (Jones 1993). Further discussions of the sampling and analysis procedures can be found in the *Tank Characterization Reference Guide* (DeLorenzo et al. 1994). The results from these sample events were reported in Pool (1994) and are discussed in Section B2.0. Vapor phase measurements were made in 1996 and a core sample was taken from this tank in 1979.

B1.1 1992 CORE SAMPLING EVENT

B1.1.1 Description of Sampling Event

Two core samples were collected from tank 241-T-104. Core 45 was obtained from riser 3 on August 20 and 26, and core 46 was obtained from riser 6 on August 27 and 28, 1992.

The core samples were received at the 222-S Laboratory on September 14, 16, and 17, 1992. Core 45 was extruded September 29 through October 7, 1992. Core 46 was extruded October 7 through October 22, 1992. Seventeen unhomogenized segment samples (9 from core 45 and 8 from core 46), 4 core composite samples (2 from each core), a homogenization sample from segment 9 of each core, and 2 field blanks were shipped to Pacific Northwest National Laboratory (PNNL) for selected analyses. The samples arrived at PNNL November 19, 1992. The bulk of the analyses were performed at the Westinghouse Hanford Company 222-S Laboratory.

Core sampling was used because of the phase of the waste (solid versus liquid), the depth of the waste, and the expectation that a full vertical profile of the waste would be obtained. Normal paraffin hydrocarbon was used as hydrostatic head fluid. A vertical profile is used to satisfy the safety screening DQO. Safety screening analyses include: total alpha to determine criticality, DSC to ascertain the fuel energy value, and thermogravimetric analysis (TGA) to obtain the total moisture content. In addition, combustible gas meter readings in the tank headspace were required to measure vapor flammability. The current revision of the safety screening DQO (Dukelow et al. 1995) also requires bulk density measurements. Although the tank was sampled and analyzed before the existence of the safety screening DQO, the analytical results can be compared with the requirements of the DQO.

Sampling and analytical requirements from the safety screening DQO are summarized in Table B1-1.

Table B1-1. Integrated Data Quality Objective Requirements for Tank 241-T-104.[1]

Sampling Event	Applicable DQOs	Sampling Requirements	Analytical Requirements
Core sampling	Safety screening	Core samples from a minimum of two risers separated radially to the maximum extent possible.	▸Energetics ▸Moisture Content ▸Total Alpha
Combustible gas meter reading		Measurement in a minimum of one location within tank vapor space.	▸Flammable Gas Concentration

Note:

[1]Dukelow et al. (1995)

B1.1.2 Sample Handling

The statement of work was not strictly followed when characterizing drainable liquids. The statement of work requires that a liquid composite sample be prepared from all segments that have 25 mL or more drainable aqueous liquid, and that a full characterization be performed on that composite. The statement of work also includes a provision for cases when there are not enough segments containing greater than 25 mL drainable liquid to prepare approximately 100 mL of liquid composite. This provision states that when not enough sample can be obtained for a liquid composite, the liquid shall be blended back into the solid composite samples.

About 25 mL of aqueous drainable liquid were obtained for Core 46, segment 7. Because no other aqueous drainable liquid greater than 25 mL was collected from Core 46, the statement of work indicated that the liquid was to be blended into the solid composite samples. This procedure was not followed for Core 46 drainable liquids. Instead, the liquid was saved, and the solid composites were sent out for characterization without blending the liquid in. This resulted in an aqueous sample that did not have enough volume for a full characterization. Drainable liquids were recovered from other segments, but were either small volumes or found to consist primarily of normal paraffin hydrocarbon (NPH) used as a hydrostatic head fluid during sampling. Immiscibility tests and specific gravity measurements were used to determine if a liquid was NPH.

Because not enough liquid sample was available for a full characterization, analysis was prioritized, and the sample was analyzed until there was no longer enough sample left for further characterization work. Analyses not performed on the drainable liquid because of the limited sample volume are: NO_2 by spectrophotometry, mercury, arsenic, selenium, ammonia, SVOA, total uranium, total beta, ^{14}C, ^{3}H, ^{129}I, ^{237}Np, ^{79}Se, ^{90}Sr, ^{99}Tc, and ^{241}Am by atomic energy analysis. Table B1-2 presents a description of the core samples.

Segment 2 of core 46 was used to test homogenization techniques. Two composite samples were formed from cores 45 and 46.

Table B1-2. Tank 241-T-104 Sample Description.[1] (3 Sheets)

Segment	Weight (grams)	Sample Recovery (%)[2]	Sample Characteristics
Core 45, Riser 3			
1	15.66 (solids)	5	A tiny amount of liquid was recovered, but not enough to observe characteristics. The sampler contained a small amount (approximately 9 mL) of light brown, mud-like solids.
2	169.49 (solids)	90	The sampler was nearly filled with solids (168 mL), with portions of solids towards the top of the sampler separated by air gaps. The solids were light brown in color and creamy in consistency. The segment was homogeneous in appearance. There were no drainable liquids.
3	186.41 (solids)	100	The sampler was completely full of solids and had a small amount of drainable liquid, but not enough to observe characteristics. The solids were tan to light-brown in color, with a creamy consistency. The segment was homogeneous in appearance.
4	168.4 (solids)	75	No drainable liquids were recovered. The solids were tan to light brown in color and had a runny consistency. The segment was homogeneous in appearance. 140 mL of solids were recovered.
5	153.91 (solids)	95	The sampler was nearly full of solids (178 mL), with a trace of drainable liquid present. The solids were tan to light brown in color and had a soft, muddy consistency. The segment was homogeneous in appearance, with the exception of several places on the segment that were relatively more wet than others.
6	131.9 (solids)	75	140 mL of solids and approximately 10 mL (8.05 g) of liquid were recovered (consisting of mostly NPH) being drainable. Segment appeared moist and runny, and was light brown in color.

Table B1-2. Tank 241-T-104 Sample Description.[1] (3 Sheets)

Segment	Weight (grams)	Sample Recovery (%)[2]	Sample Characteristics
Core 45, Riser 3 (Cont'd)			
7	170.96 (solids) 11.64 (liquid)	94	10 mL of drainable liquid and 165 mL solids were recovered. Solids were light brown in color and had a consistency similar to the previous segment. It is hypothesized that the NPH is what makes the solid so runny.
8	184.56 (solids)	100	The sampler was completely full. A trace of drainable liquid was recovered. The appearance of the solids was much like all of the previous segments in color and consistency.
9	215.18 (solids)	100	The sampler was completely full of solids. No drainable liquids were recovered. Again, the appearance of the solids was much like all of the previous samples.
Core 46 Riser 6			
1	0	0	No sample was present in sampler. There were no drainable liquids.
2	211.8 (solids)	100	The sampler was completely full. No drainable liquids were recovered. Solids were tan to light brown in color and had the consistency of "melting ice cream". The segment was homogeneous in appearance from top to bottom.
3	111.88 (solids)	60	The sampler was completely full. 112 mL of solids and 75 mL (51.59 g) of drainable liquid were recovered and the remainder of the sampler was filled with liquid. The segment was broken in several places, with NPH filling the voids. The segment, although broken, was homogeneous in appearance. The solids were light brown in color and again had the consistency of "ice cream."
4	185.78 (solids) 3.08 (liquid)	100	The sampler was completely full of solids. Drainable liquids were recovered, but not enough to observe characteristics. The color and consistency of the solids were much like segment two of this core.

Table B1-2. Tank 241-T-104 Sample Description.[1] (3 Sheets)

Segment	Weight (grams)	Sample Recovery (%)[2]	Sample Characteristics
Core 46 Riser 6 (Cont'd)			
5	184.59 (solids)	100	The sampler was completely full of solids. No drainable liquids were recovered. Copious amounts of NPH saturated the solids. The solids were light brown in color and had the consistency of "cold ice cream". The segment was completely homogenous in appearance from top to bottom.
6	144.66 (solids)	65	122 mL of solids were recovered, and about 25 mL (18.66 g) drainable liquid, which consisted of mostly NPH. The solids were light brown in color and had the consistency of "clay". The segment was homogeneous in appearance with the exception of variations in NPH content. A tiny amount of liner liquid was recovered and discarded.
7	159.03 (solids) 32.50 (liquid)	98	159 mL of solids, and 25 mL aqueous liquid were recovered. The liquid was a murky light brown color. Solids were very much like segment 6, Core 46 in appearance (color, consistency, etc.); however, the solids from this segment appeared "mushy" at the top end, and became slightly thicker towards the bottom.
8	180.1 (solids)	90	168 mL solids and about 15 mL (13.43 g) drainable liquid existing in 2 phases were recovered. The drainable liquid was determined to be primarily NPH. Solids were light brown in color, and had a "mushy" consistency.
9	193.3 (solids)	100	The sampler was completely full of solids, with no drainable liquid. The solids were similar (in color and consistency) to all of the other segments in Core 46 and were saturated with NPH. The segment was homogeneous in appearance.

Note:

[1]Pool (1994)

B1.1.3 Sample Analysis

The analyses performed on the 1992 rotary core samples performed two functions: characterization of the waste in tank 241-T-104, and fulfillment of the requirements of the safety screening DQO. The characterization of the tank waste was performed to support regulatory, safety (waste reactivity) evaluation, performance assessment, waste retrieval and treatment technology development, supplemental environmental impact statement and closure activities (Hill et al. 1991). The analyses required by the safety screening DQO included analyses for thermal properties by DSC, moisture content by TGA, and content of fissile material by total alpha activity analysis. Moisture was also measured by gravimetry as a check on the accuracy of the TGA.

Total alpha activity measurements were performed on samples that had been fused in a solution of potassium hydroxide and then dissolved in acid. The resulting solution was then dried on a counting planchet and counted in an alpha proportional counter. Quality control tests included standards, spikes, blanks, and duplicate analyses.

Ion chromatography (IC) was performed on samples that had been prepared by a water digestion. Quality control tests included standards, spikes, blanks, and duplicate analyses.

Three preparation methods were used for the inductively coupled plasma (ICP) spectrometry analyses: fusion, acid digestion, and a water leach. Quality control tests included standards, blanks, spikes, and duplicate analyses.

All reported analyses were performed in accordance with approved laboratory procedures. A list of the sample numbers and applicable analyses is presented in Table B1-3. The procedure numbers are presented in the discussion in Section B2.0

Table B1-3. Tank 241-T-104 Sample Analysis Summary.[1] (3 Sheets)

Sample Phase	Sample Portion	Sample Number	Analyses
Core 45, Riser 3			
Solid	Solid composite	K-155	Gravimetric
		K-157	Gravimetric
		K-175	ICP (acid, fusion, water), IC, GHAA, CVAA, ammonia, carbonate, cyanide, TGA, pH, TOC, DSC, nitrite (spec), total U, GEA, total beta, ^{14}C, ^{129}I, ^{3}H, ^{237}Np, ^{79}Se, ^{90}Sr, ^{99}Tc $^{239/240}Pu$, ^{241}Am
		K-176	ICP (acid, fusion, water), IC, GHAA, CVAA, ammonia, carbonate, cyanide, TGA, pH, TOC, DSC, nitrite (spec), total U, GEA, total beta, ^{14}C, ^{129}I, ^{3}H, ^{237}Np, ^{79}Se, ^{90}Sr, ^{99}Tc $^{239/240}Pu$, ^{241}Am
		93-01809	Total alpha plutonium, weight percent solids, SVOA
		93-01810	Total alpha plutonium, weight percent solids, SVOA
	Segment 1	93-01790	VOA
	Segment 2	93-01791	Weight percent undissolved solid, weight percent solid
	Segment 3	93-01792	VOA
	Segment 4	93-01793	Weight percent undissolved solid, weight percent solid
	Segment 5	93-01794	VOA
	Segment 6	93-01795	Weight percent undissolved solid, weight percent solid
	Segment 7	93-01796	VOA
	Segment 8	93-01797	Weight percent undissolved solid, weight percent solid
	Segment 9	93-01798	VOA
	Segment 9	93-01807	Total alpha plutonium
		93-01808	Total alpha plutonium
		K-189	Total uranium
		K-196	TCLP (CVAA, ICP)
		K-199	TCLP (ICP)

Table B1-3. Tank 241-T-104 Sample Analysis Summary.[1] (3 Sheets)

Sample Phase	Sample Portion	Sample Number	Analyses
Core 45, Riser 3 Cont'd)			
Solid	Segments 1, 2, 3, 4, 5, 6, 7, 8, 9	K-67, 68, 69, 70, 71, 72, 74, 75, 76, 77, 78, 79, 81, 82, 83, 84, 85, 86	TGA, DSC
	Segments 2, 3, 4, 5, 6, 7, 8, 9	K-25, 27, 29, 33, 35, 37, 39, 42	Gravimetric
Core 46, Riser 6			
Liquid	Liquid composite (consisted of liquid from seg. 7 only)	K-204	ICP (acid, fusion, water), IC, cyanide, GEA, alpha spectrometry, TOC, ^{238}Pu, $^{239/240}$Pu, TGA, pH, TOC, specific gravity
Solid	Solid composite	K-159	Gravimetric
		K-161	Gravimetric
		K-179	ICP (acid, fusion, water), IC, GHAA, CVAA, ammonia, carbonate, cyanide, TGA, pH, TOC, DSC, total U, GEA, total beta, ^{14}C, ^{129}I, ^{3}H, ^{237}Np, ^{79}Se, ^{90}Sr, ^{99}Tc, $^{239/240}$Pu, ^{241}Am
		K-180	ICP (acid, fusion, water), IC, GHAA, CVAA, ammonia, carbonate, cyanide, TGA, pH, TOC, DSC, total U, GEA, total beta, ^{14}C, ^{129}I, ^{3}H, ^{237}Np, ^{79}Se, ^{90}Sr, ^{99}Tc, $^{239/240}$Pu, ^{241}Am
		93-01811	Total alpha plutonium, SVOA
		93-01812	Total alpha plutonium, weight percent solids, SVOA
	Segment 2	93-01799	VOA
		K-146	ICP (acid), GEA, total alpha
		K-147	ICP (acid), GEA, total alpha

Table B1-3. Tank 241-T-104 Sample Analysis Summary.[1] (3 Sheets)

Sample Phase	Sample Portion	Sample Number	Analyses
Core 46, Riser 6 Cont'd)			
Solid	Segment 3	93-01801	VOA
	Segment 4	93-01800	VOA
	Segment 5	93-01802	VOA
	Segment 6	93-01803	VOA
	Segment 7	93-01804	VOA
	Segment 8	93-01805	VOA
	Segment 9	93-01806	VOA
	Segments 2, 3, 4, 5, 6, 7, 8, 9	K-90, 91, 92, 93, 95, 96, 97, 98, 99, 100, 102, 103, 104, 105, 106, 107	TGA, DSC
	Segments 2, 3, 4, 5, 6, 7, 8, 9	K-46, 48, 53, 55, 57, 59, 62, 64	Gravimetric

Notes:

CVAA = cold vapor atomic absorption
DSC = differential scanning calorimetry
GEA = gamma energy analysis
GHAA = graphite hydride atomic absorption
IC = ion chromatography
ICP = inductively coupled plasma
SVOA = semi-volatile organic analysis
TCLP = toxic characteristic leach procedure
TGA = thermogravimetric analysis
TOC = total organic carbon
VOA = volatile organic analysis

[1]Pool (1994)

B1.2 VAPOR PHASE MEASUREMENTS

Vapor phase measurements were made on tank 241-T-104 in February 1996 as part of a riser preparation procedure (WHC 1996). Measurements were made for flammability, total organic carbon, oxygen, and ammonia at the riser 8 breather vent, within riser 8, and in the tank headspace beneath riser 8.

B1.3 DESCRIPTION OF HISTORICAL SAMPLING EVENT

Sampling data for tank 241-T-104 have been obtained for one core of nine segments, the results of which were reported in Horton (1979). The data are presented in Section B2.6. Pre-1989 analytical data have not been validated and should be used with caution. No information was available on the riser used for this core sampling event.

The segments appeared uniform in color, with a light brown color interspersed with reddish-brown flecks. The segments exhibited the consistency of soft putty, with the exception of segment nine, which contained a small amount of hard, gravel-like material. No stratification of aluminum compounds was apparent. The samples were subjected to a water leach, which resulted in water-soluble and water-insoluble fractions. These fractions were analyzed. Horton (1979) does not specify the method used to prepare the water-insoluble fraction for analysis, but it was probably a caustic fusion or acid digestion.

B2.0 ANALYTICAL RESULTS

B2.1 OVERVIEW

This section summarizes the sampling and analytical results associated with the August 1992 sampling and analysis of tank 241-T-104 as well as the results of the 1996 vapor measurements and the historical sampling event. The results of the analyses required by the safety screening DQO (total alpha activity, percent water, energetics, and density) are presented first, followed by the remaining characterization analyses, as listed in Table B2-1. The results of the 1992 core sampling event are documented in Pool (1994). Section B2.11 contains all analytical data tables.

Table B2-1. Analytical Presentation Tables.

Analysis	Table number
Total alpha activity	B2-2
Percent water	B2-3
Differential scanning calorimetry	Section B2.3.2
Physical, chemical and radiochemical analytical data	B2-4 through B2-92
Vapor measurements	B2-93
Historical sampling results	B2-94 and B2-95

B2.2 TOTAL ALPHA ACTIVITY

Analyses for total alpha activity were performed on the samples recovered from tank 241-T-104. The samples were prepared by fusion digestion per procedure LA-549-141 and analyzed according to procedure LA-508-101. Two fusions were prepared per sample (for duplicate results). Each fused dilution was analyzed twice, and the results were averaged and reported as one value. The highest result returned was 0.121 μCi/g. The sample results for total alpha are given in Table B2-2.

B2.3 THERMODYNAMIC ANALYSES

As required by the safety screening DQO, TGA and DSC were performed on the solids. Other physical tests performed included density of the sludge and of the centrifuged solids and supernatant, percent settled solids, volume and weight percent centrifuged solids, weight percent undissolved solids, and specific gravity of the one aqueous drainable liquid sample.

B2.3.1 Thermogravimetric Analysis

Thermogravimetric analysis measures the mass of a sample while its temperature is increased at a constant rate. Nitrogen is passed over the sample during heating to remove any released gases. Any decrease in the weight of a sample during TGA represents a loss of gaseous matter from the sample, either through evaporation or through a reaction that forms gas phase products. The moisture content is estimated by assuming that all TGA sample weight loss up to a certain temperature (typically 150 to 200 °C [300 to 390 °F]) is due to water evaporation. The temperature limit for moisture loss is chosen by the operator at an inflection point on the TGA plot. Other volatile matter fractions can often be differentiated by inflection points as well.

She

Tank 241-T-104 unhomogenized samples were analyzed directly by TGA using procedure LA-560-112 on a Mettler TG 50 instrument. The results varied from 41 to 69 weight percent on core 45 (with one exception) and between 52 and 76 weight percent on core 46. The TGA analyses were not initially run in duplicate because of time constraints. The duplicates were run at a later date. There was good agreement between primary and duplicate samples with the exception of sample K67 (core 45 segment 1) which exhibited a 29 percent RPD. The rerun was performed 79 days later. The original sample displayed moisture content of 47 weight percent; the rerun displayed 9.6 weight percent water. The difference was determined to be because of drying. Gravimetric analyses were performed on the 241-T-104 subsamples from this tank to assess the accuracy of the TGA results. The gravimetric analyses were thought to be more reliable than the TGA analyses because of the larger sample sizes and the resultant decrease in sensitivity to waste heterogeneity. Weight percent water by gravimetry varied from 63.9 to 72.5 weight percent for core 45, and from 64.5 to 74.7 weight percent for core 46. The TGA and gravimetric results are presented in Table B2-3.

B2.3.2 Differential Scanning Calorimetry

In a DSC analysis, heat absorbed or emitted by a substance is measured while the temperature of the sample is heated at a constant rate. Nitrogen is passed over the sample material to remove any gases being released. The onset temperature for an endothermic or exothermic event is determined graphically.

The DSC analyses for tank 241-T-104 were performed on whole segments and composites using procedure LA-560-112. No exothermic reactions were noted, and none of the DSC thermograms were integrated. Therefore, an upper limit of a 95 percent confidence interval on the mean for each sample was not calculated.

B2.4 PHYSICAL PROPERTIES

B2.4.1 Density and Percent Solids

The density measurements were carried out on the liquid and solid samples. The mean liquid density was 1.13 g/mL and the mean solid density was 1.29 g/mL. Percent solids were measured as volume percent and as weight percent, on settled solids and on centrifuged solids. Four different segments from core 45, numbers 2, 4, 6 and 8, were analyzed. The segment 2 sample was observed to be very different from the segment 4, 6, and 8 samples in that the weight percent solids result for segment two was 1.5 times the weight percent solids observed in the other 3 segments. The undissolved solids were calculated by subtracting the percentage of dissolved solids from the weight percent total solids. The results for

segments 4, 6, and 8 were similar, as shown in Table B2-4. Note also that the centrifuged solids and bulk sample densities were in contrast between segment 2 and segments 4, 6, and 8. Procedure PNL-ALO-504 was used to measure the weight percent solids.

Rough density estimates were made for each segment and drainable liquid sample by dividing the weight of the solids or drainable liquid recovered from each segment by its estimated volume. However, because of the large uncertainties associated with estimating the volumes, results varied widely.

B2.4.2 Particle Size

Particle size analyses are performed by passing a laser beam through a sample that has been suspended in a dispersant. The amount of light attenuated by the particles is a measure of the size and number of the particles in the sample. The particle size analyzer has a range of 0.5 to 150 μm, and is set up to give the short diameter of the particle, irrespective of the particle's shape. From these data, the number and volume probability densities are calculated. The number probability density is an indication of the average size of the particles based on the number of particles measured, whereas the volume probability density is an indication of the size of the particles that occupy most of the sample volume. A small difference between the number probability density and the volume probability density is an indication of relative uniformity of particle size; conversely, a large difference indicates that most of the sample volume is occupied by a few large particles and the remaining volume is occupied by many small particles. Table B2-6 lists the particle size analyses results, along with standard deviations. For all segments, a relatively large difference exists between the number and the volume probability densities. This shows a large range of particle size in the sample.

The chemical properties of the dispersant are vital to the particle size test in that the particles can be dissolved or additional particles can be precipitated in the dispersant, thereby changing their size or number. Drainable liquid, or 'mother liquor', is a suitable choice because it is in chemical equilibrium with the solid portion of the waste, and will neither precipitate the solids nor dissolve them. In the case of tank 241-T-104, water was used as the matrix. The choice to use water may have been made because the waste was relatively insoluble, and any error would likely be small.

Inspection of the tank 241-T-104 particle size data shows no discernable trends in the vertical variation of the data.

B2.4.3 Rheology

The shear strength of segments 2, 4, 6 and 8 was measured from core 45. Table B2-7 shows the shear strength of each segment.

Shear stress measurements were also made on the dilutions of segment samples at ambient temperature and 95 °C (203 °F). The water:sample 1:1 dilution at both temperatures exhibited yield pseudoplastic behavior, although segments 4, 6 and 8 had low yield points of <0.2 Pa and segment 2 had a yield point of 1 Pa. The viscosity of the sample decreased as the temperature was increased. The 3:1 dilutions for all segments exhibited Newtonian behavior.

B2.5 INORGANIC ANALYSES

Inductively coupled plasma spectroscopy was performed on the 1992 core samples to measure the concentrations of metals. Ion chromatography was used to measure the concentrations of anions. The concentration of each analyte is present in tables at the end of Section B2. The discussion accompanying each analytical method includes the digestion method, the analytical method, and comments about any problems with the analysis.

In each table, the "Mean" column is the average of the result and duplicate values. All values, including those below the detection level (denoted by the less-than symbol, "<"), were averaged. If both sample and duplicate values were non-detected, the mean is expressed as a non-detected value. If one value was detected while the other was not, the mean is expressed as a non-detected value. If both values were detected, the mean is expressed as a detected value.

B2.5.1 Inductively Coupled Plasma

The ICP analyses were performed per procedure LA-505-151 and were prepared by water, fusion, and acid digests. The concentrations of metals in the samples as measured by ICP are shown in Tables B2-8 through B2-38. The results from three preparation methods, water, fusion, and acid, are presented for the metals. Composite samples were prepared by acid digestion prior to analysis. Other samples were prepared by fusion with potassium hydroxide in a nickel crucible, or by a water leach. The nickel results for the ICP fusion analyses are biased high, because the samples were prepared in a nickel crucible by fusion using potassium hydroxide.

B2.5.2 Ion Chromatography

Samples for ion chromatography (IC) were prepared by water digestion and performed in duplicate per procedure LA-533-105. The concentrations of anions by IC are shown in Tables B2-39 through B2-44. Only water soluble anions could be measured. The presence and concentration of insoluble anions can be inferred from the ICP data in some cases (i.e., phosphate and sulfate).

B2.5.3 Total Uranium

Total uranium was measured on composites from both cores and on a segment from each core by laser phosphorescence, using procedure number LA-925-106. Results for the total uranium analysis are found in Table B2-45.

B2.5.4 Arsenic, Selenium, and Mercury by Atomic Absorption Spectroscopy

Arsenic and selenium were measured by gaseous hydride atomic absorption spectroscopy using procedure number LA-355-131. Mercury was measured by cold vapor atomic absorption spectroscopy using procedure number LA-325-104. In addition to measuring the concentrations of the metals in the tank waste, a toxic characteristic leaching profile test was used to measure the metals for their tendency to precipitate in or absorb on a sample container in a matrix with pH greater than 2. The concentrations of arsenic, selenium, and mercury as determined by atomic absorption spectroscopy may be found in Tables B2-46, B2-47, and B2-48.

B2.5.5 Ammonia

Ammonia was measured using the Kjeldahl method, procedure number LA-634-102. The ammonia concentration was measured on composites from both cores. The results were all less than the detection limit. Ammonia concentrations may be found in Table B2-49.

B2.5.6 Cyanide by Distillation and Spectroscopy

Cyanide was measured by a process of distillation and spectroscopy, using procedure number LA-695-102. Analytical results are presented in Table B2-50.

B2.5.7 Nitrite by Spectrophotometry

Nitrite was measured by spectrophotometry as a back-up for the IC analysis. Analytical results are presented in Table B2-51.

B2.5.8 pH

pH was measured using a pH electrode. Analytical results are presented in Table B2-52.

B2.6 ORGANIC ANALYSES

B2.6.1 Semivolatile and Volatile Organic Analysis

Semivolatile organic analysis (SVOA) was performed on the tank waste samples using procedure number PNL-ALO-344/345. Samples were extracted using procedure PNL-ALO-120, and were cleaned of hydrocarbons prior to analysis by procedure number PNL-ALO-122. Volatile organic analysis (VOA) was performed using procedure PNL-ALO-335 after being cleaned of hydrocarbons (mostly normal paraffin hydrocarbon) by procedure number PNL-ALO-121. Both semivolatile and volatile organic compounds were analyzed by gas chromatography/mass spectroscopy. Results for the SVOA analysis are presented in Tables B2-53 through B2-58. Those for the VOA analysis are presented in Tables B2-59 through B2-65.

B2.7 TOTAL INORGANIC AND ORGANIC CARBON

Total inorganic carbon (TIC) was measured using procedure number LA-344-105. Total organic carbon (TOC) was measured using procedure number LA-622-102. Analytical results for TIC and TOC may be found in Tables B2-66 and B2-67, respectively.

B2.8 RADIONUCLIDES

B2.8.1 Fission Products by Gamma Energy Analysis

Gamma energy analysis (GEA) was used to measure the activities of ^{241}Am, ^{137}Cs, ^{60}Co, ^{154}Eu, and ^{155}Eu, using procedure number LA-548-121. The samples were prepared by a fusion digestion method. Analytical results are presented in Tables B2-68, B2-69, B2-70, B2-71, and B2-72, respectively. ^{129}I was measured by gamma counting using procedure number LA-378-103. The results are presented in Table B2-73.

B2.8.2 Fission Products by Separation and Counting

Liquid scintillation and counting were used to measure the activities of ^{14}C, ^{3}H, ^{79}Se, and ^{99}Tc. The respective procedure numbers are LA-348-104, LA-218-113, LA-365-132, and LA-438-101. ^{3}H and ^{14}C were prepared for analysis using a water digestion; ^{79}Se and 99Tc were prepared using a fusion digestion. The analytical results for ^{14}C, ^{3}H, ^{79}Se, and ^{99}Tc are presented in Tables B2-74, B2-75, B2-76, and B2-77, respectively. ^{90}Sr was prepared for

analysis using a fusion digestion method, and was counted on a beta proportional counter. The procedure number for the ^{90}Sr analysis was LA-220-101, and the results are presented in Table B2-78.

B2.8.3 Total Beta Activities by Proportional Counting

Total beta activities are the measurements of the gross beta activities of the waste samples. The samples were prepared by a fusion digestion and were counted using procedure number LA-508-101. The results are presented in Tables B2-79.

B2.8.4 Transuranic Radionuclides by Separation and Counting

^{241}Am, ^{238}Pu, and $^{239/240}Pu$ were measured by alpha spectrometry on a fusion digested sample, procedure number LA-503-156 and presented in Tables B2-80, B2-81, and B2-82, respectively. ^{237}Np was measured after chemical separation by alpha proportional counting using procedure number LA-933-141, and the results of the analyses are presented in Table B2-83. Plutonium/uranium mass spectrometry was performed on a fusion digested sample using procedure number PNL 2.30.6. Results are presented in Tables B2-84 through B2-92.

B2.9 VAPOR PHASE MEASUREMENT

The vapor headspace of tank 241-T-104 was not evaluated for flammability when the 1992 core samples were taken. Vapor samples were, however, taken in February of 1996 as part of a riser preparation procedure (WHC 1996). The results are presented in Table B2-93.

B2.10 HISTORICAL SAMPLING RESULTS

An internal letter (Horton 1979) reported the results of the analysis of a nine-segment core from tank 241-T-104. The samples were taken after the tank was removed from service. The principal difference between the 1979 analytical results and those from the 1992 samples is probably the water content of the waste. The only activity the tank has undergone since it was placed out of service is saltwell pumping. The analytical results of the 1979 sample and analysis event are presented in Tables B2-94 and B2-95. The waste was described as having a light yellow color, interspersed with reddish-brown flecks. The samples exhibited a uniform putty-like texture, with the exception of segment 9, which contained a small amount of hard, gravel-like material.

B2.11 ANALYTICAL DATA TABLES

The quality control (QC) parameters assessed in conjunction with the tank 241-T-104 samples are listed below. The QC criteria were specified in Appendix D of the waste characterization plan (Hill et al. 1991). The criterion for matrix spikes was 75 to 125 percent recovery. Other QC criteria were established according to the analysis, the waste constituent, and the histories of the QC criteria. The relative percent difference (RPD) was used as a measure of precision. The RPD is defined as the absolute value of the difference between the sample and duplicate, divided by the average of the sample and duplicate, and multiplied by 100 percent. Sample and duplicate pairs in which any of the QC parameters did not meet the requirements are footnoted in the sample mean column of the data summary tables. The specific QC notations are defined in the following lists:

For non-radioactive constituents (other than VOA and SVOA):

1. Chain of custody
2. Holding times
3. Instrument calibration
4. Initial and continuing calibration verification
5. Analytical blanks
6. Preparation blanks
7. Interference check sample
8. Laboratory check sample
9. Duplicate analysis
10. Matrix spike or post-digestion spike
11. Retention time
12. Contract required detection limit
13. Serial dilution

For radioactive constituents:

1. Chain of custody
2. Instrument calibration
3. Efficiency checks
4. Background checks
5. Preparation blanks
6. Laboratory control sample
7. Duplicate analysis
8. Matrix spike/tracers/surrogates

For VOA and semi-VOA constituents:

1. Holding times
2. Surrogate recovery
3. Matrix spike/matrix spike duplicate
4. Blanks
5. gas chromatograph/mass spectrometer tune
6. Calibration
7. Internal standards
8. Instrument performance.

Table B2-2. Tank 241-T-104 Analytical Results: Total Alpha (Alpha).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			µCi/g	µCi/g	µCi/g
93-1807-H1	45:9	WHOLE	0.111	0.108	0.1095[QC:2,4,8]
93-1808-H1		WHOLE	0.0803	0.0743	0.0773[QC:2,4,8]
146	46:2	WHOLE	0.197	0.217	0.207
146		WHOLE	0.211	0.196	0.2035
93-1809-H1	Core 45 Composite	WHOLE	0.155	0.16	0.1575[QC:2,4,8]
93-1810-H1		WHOLE	0.155	0.0151	0.153[QC:2,4,8]
93-1811-H1	Core 46 Composite	WHOLE	0.155	0.156	0.1555[QC:2,4,8]
93-1812-H1		WHOLE	0.16	0.144	0.152[QC:2,4,8]
175	Core 45 Composite	WHOLE	0.101	0.103	0.102[QC:2,4,8]
176		WHOLE	0.106	0.107	0.1065[QC:2,4,8]
179	Core 46 Composite	WHOLE	0.115	0.121	0.118
180		WHOLE	0.11	0.109	0.1095

Table B2-3. Percent Water by TGA and Gravimetric Analysis.[1] (4 Sheets)

Sample Number	Sample Location	Temperature Range[2] (°C)	Result % H_2O	Duplicate % H_2O	Mean % H_2O
Thermogravimetric Analysis					
K67	45:1	ambient to 120 (ambient to 140)	40.9	54.5	47.7
K67[3]		ambient to 445 (ambient to 445)	9.52	9.72	9.62
K69	45:2	ambient to 145 (ambient to 150)	52.5	48.7	50.6
K70		ambient to 125 (ambient to 120)	40.6	41.1	40.85
K71	45:3	ambient to 140 (ambient to 150)	65.1	66.3	65.7
K72		ambient to 140 (ambient to 150)	68.7	69.3	69
K74	45:4	ambient to 140 (ambient to 140	43.8	42.7	43.25
K75		ambient to 160 (ambient to 125)	52.7	48.6	50.65
K76	45:5	ambient to 135 (ambient to 145)	54.5	53.8	54.15
K77		ambient to 110 (ambient to 130)	54.2	56.1	55.15
K78	45:6	ambient to 115 (ambient to 130)	62.7	64	63.35
K79		ambient to 120 (ambient to 120)	57.5	58.1	57.8
K81	45:7	ambient to 170 (ambient to 165)	57.7	52.9	55.3
K82		ILLEGIBLE (ambient to 160)	65.5	64.8	65.15

Table B2-3. Percent Water by TGA and Gravimetric Analysis.[1] (4 Sheets)

Sample Number	Sample Location	Temperature Range[2] (°C)	Result % H_2O	Duplicate % H_2O	Mean % H_2O
Thermogravimetric Analysis					
K83	45:8	ambient to 180 (ambient to 180)	59.6	60.2	59.9
K84		ambient to 190 (ambient to 190)	60.5	62.5	61.5
K85	45:9	ambient to 185 (ambient to 185)	64.2	64.9	64.55
K86		ambient to 195 (ambient to 195)	66.9	63.6	65.25
K90	46:2	ambient to 185 (ambient to 190)	62.5	58.9	60.7
K91		ambient to 180 (ambient to 190)	60.7	55.4	58.05
K92	46:3	ambient to 275 (ambient to 180)	68.1	61.6	64.85
K93		ambient to 110 (ambient to 110)	60.2	57.2	58.7
K95	46:4	ambient to 135 (ambient to 130)	68.3	73.62	70.96
K96		ambient to 145 (ambient to 140)	68.8	67.4	68.1
K97	46:5	ambient to 130 (ambient to 130)	73.1	76.3	74.7
K98		ambient to 135 (ambient to 285)	66.4	69.4	67.9
K100	46:6	ambient to 140 (ambient to 125)	68.9	67	67.95
K99		ambient to 125 (ambient to 125)	51.6	53.7	52.65

Table B2-3. Percent Water by TGA and Gravimetric Analysis.[1] (4 Sheets)

Sample Number	Sample Location	Temperature Range[2] (°C)	Result % H_2O	Duplicate % H_2O	Mean % H_2O
Thermogravimetric Analysis					
K102	46:7	ambient to 110 (ambient to 125)	61	63.6	62.3
K103		ambient to 145 (ambient to 105)	65.1	62.6	63.85
K104	46:8	ambient to 155 (ambient to 155)	59.7	70.6	65.15
K105		ambient to 155 (ambient to 140)	68.4	67.6	68
K106	46:9	ambient to 175 (ambient to 190)	61.9	60.4	61.15
K107		ambient to 200 (ambient to 140)	70.1	69.9	70
K175	Core 45 composite	ambient to 155 (ambient to 115)	67	67.2	67.1
K176		ambient to 145 (ambient to 145)	70.6	68.5	69.55
K179	Core 46 composite	ambient to 140 (ambient to 125)	63.9	64.4	64.15
K180		ambient to 135 (ambient to 150)	68.8	70.3	69.55
K204	Drainable liquid composite	(ambient to 125)	83.4	83.7	83.55

Table B2-3. Percent Water by TGA and Gravimetric Analysis.[1] (4 Sheets)

Sample Number	Sample Location	Temperature Range[2] (°C)	Result % H_2O	Duplicate % H_2O	Mean % H_2O
Gravimetric analysis					
K25	45:2	n/a	64.2	63.9	64.05
K27	45:3		70.2	70.1	70.15
K29	45:4		70.4	70.1	70.25
K33	45:5		70.1	69.5	69.8
K35	45:6		71.4	71.5	71.45
K37	45:7		70.4	71.1	70.75
K39	45:8		72.5	72.5	72.5
K42	45:9		71	71.5	71.25
K46	46:2		66.3	64.5	65.4
K48	46:4		74.7	73.6	74.15
K53	46:4		69	69.7	69.35
K55	46:5		69.8	69.9	69.85
K57	46:6		71.1	71	71.05
K59	46:7		70.9	71.4	71.15
K62	46:8		73.3	73.9	73.6
K64	46:9		70.1	69.7	69.9
K155	Core 45 composite		70.4	70.3	70.35
K157			70.5	70.1	70.3
K159	Core 46 composite		70.8	70.4	70.6
K161			70.9	70.8	70.85

Notes:

n/a = not applicable

[1]Pool (1994)

[2]Temperature ranges in parentheses are for the duplicate.

[3]Rerun performed approximately 10 weeks after original analysis. Sample had lost moisture through evaporation.

Table B2-4. Tank 241-T-104 Core 45 Physical Measurements.

		Segment Number			
Physical Property	Sample	2	4	6	8
Density (g/mL)	Sludge	1.42[1]	1.24[1]	1.24[1]	1.24[1]
	Centrifuged supernatant	1.13	1.12	1.13	1.12
	Centrifuged solids	1.52	1.33	1.31	1.30
Vol% settled solids		100	86.5	82.2	87.5
Wt% undissolved solids		39.7	21.9	23.6	23.2
Wt% solids		43.3	28.0	29.2	28.7
Vol% centrifuged solids		74.1	57.1	63.9	64.0
Wt% centrifuged solids		79.4	61.2	67.3	67.4

Note:
[1]PNNL 325 Laboratory results

Table B2-5. Tank 241-T-104 Analytical Results: Density (Physical Properties). (2 sheets)

Sample Location	Sample Portion	Result
Solids		g/mL
45: 1	WHOLE	1.74
45: 2	WHOLE	1.01
	WHOLE	1.42
45: 3	WHOLE	1
45: 4	WHOLE	1.2
	WHOLE	1.24
45: 5	WHOLE	0.086
45: 6	WHOLE	0.94
	WHOLE	1.24
45: 7	WHOLE	1.04

Table B2-5. Tank 241-T-104 Analytical Results: Density (Physical Properties). (2 sheets)

Sample Location	Sample Portion	Result
45: 8	WHOLE	0.99
	WHOLE	1.24
45: 9	WHOLE	1.15
46: 2	WHOLE	1.13
46: 3	WHOLE	1
46: 4	WHOLE	0.99
46: 5	WHOLE	0.99
46: 6	WHOLE	1.19
46: 7	WHOLE	1
46: 8	WHOLE	1.07
46: 9	WHOLE	1.03
Liquids		**g/mL**
45: 6	WHOLE	0.81
45: 7	WHOLE	1.16
46: 3	WHOLE	0.69
46: 6	WHOLE	0.75
46: 7	WHOLE	1.3
46: 8	WHOLE	0.9

Table B2-6. Tank 241-T-104 Particle Size Data.[1]

Sample Location	Probability Number Density (μm)	Standard Deviation (μm)	Probability Volume Density (μm)	Standard Deviation (μm)
45:1	1.04	0.78	9.08	11.1
45:2	1.08	0.82	37.9	41.4
45:3	1.25	1.40	46.8	32.8
45:4	1.13	0.97	31.0	28.0
45:5	1.03 1.05[2]	1.00 1.06[2]	30.8 33.8[2]	20.6 19.9[2]
45:6	1.15	1.02	27.9	29.1
45:7	1.01	0.81	34.4	36.7
45:8	1.04	0.73	6.12	61.05 5.39
45:9	1.06	1.06	27.4	22.7
46:2	1.04	0.85	50.9	39.5
46:3	1.07	0.86	12.8	18.7
46:4	1.01	0.81	23.4	30.7
46:5	0.99	0.78	49.0	51.3
46:6	1.13	0.91	20.2	22.0
46:7	0.95	0.68	6.81	7.97
46:8	0.81	0.38	5.14	4.73
46:9	1.05	0.81	16.1	19.8

Notes:

[1]Pool (1994)

[2]Duplicate sample of Core 45, Segment 5

Table B2-7. Shear Strength Results.

Segment Number	Shear Strength (dynes/cm^2)
2	18,800
4	3,500
6	< 500
8	13,800

Table B2-8. Tank 241-T-104 Analytical Results: Aluminum (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			**µg/g**	**µg/g**	**µg/g**
147[1]	46: 2	WHOLE	25,200	23,900	24,550[QC:4,8]
146[1]		WHOLE	23,900	24,100	24,000[QC:4,8]
175	Core 45 Composite	WHOLE	17,400	16,000	16,700[QC:8]
176		WHOLE	18,300	18,000	18,150[QC:4,8]
179	Core 46 Composite	WHOLE	15,500	14,800	15,150
180		WHOLE	15,000	14,900	14,950
Liquids: acid digest			**µg/mL**	**µg/mL**	**µg/mL**
204	Core 46 Composite	DL	3,160	---	3,160[QC:8,13]
Solids: fusion			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	17,800	18,000	17,900
176		WHOLE	17,300	17,000	17,150
179	Core 46 Composite	WHOLE	13,900	13,700	13,800[QC:4,10]
180		WHOLE	14,100	13,300	13,700[QC:4,10]
Solids: water digest			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	122	127	124.5[QC:7]
176		WHOLE	153	179	166[QC:7]
179	Core 46 Composite	WHOLE	164	162	163[QC:5]
180		WHOLE	181	176	178.5[QC:5]

Notes:

DL = Drainable liquid

[1]Homogenization test sample

Table B2-9. Tank 241-T-104 Analytical Results: Antimony (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			**µg/g**	**µg/g**	**µg/g**
147[1]	46: 2	WHOLE	< 34.7	< 35.2	< 34.95[QC:4,7,8]
146[1]		WHOLE	< 35	< 35.3	< 35.15[QC:4,7,8]
175	Core 45 Composite	WHOLE	< 33.7	< 34.2	< 33.95[QC:4,7]
176		WHOLE	< 48.8	< 51.7	< 50.25[QC:7,8]
179	Core 46 Composite	WHOLE	< 35.5	< 35.2	< 35.35[QC4,7,8]
180		WHOLE	< 35.2	< 35	< 35.1[QC:4,7,8]
Liquids: acid digest			**µg/mL**	**µg/mL**	**µg/mL**
204	Core 46 Composite	DL	< 3.56	---	< 3.56[QC:4,7]
Solids: fusion			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	< 176	< 176	< 176[QC:7]
176		WHOLE	< 177	< 177	< 177[QC:7]
179	Core 46 Composite	WHOLE	< 75.7	< 75.8	< 75.75[QC:4,7]
180		WHOLE	< 75.4	< 75.1	< 75.25[QC:4,7]
Solids: water digest			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	< 36.1	< 36.1	< 36.1[QC:7]
176		WHOLE	< 36.2	< 36.3	< 36.25[QC:7]
179	Core 46 Composite	WHOLE	< 36.2	< 36.2	< 36.2[QC:4,7]
180		WHOLE	< 35.6	< 35.9	< 35.75[QC:4,7]

Note:

[1]Homogenization test sample

Table B2-10. Tank 241-T-104 Analytical Results: Arsenic (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			**µg/g**	**µg/g**	**µg/g**
147[1]	46: 2	WHOLE	3.56	6.52	5.04[QC:7,9]
146[1]		WHOLE	4.19	< 3.07	< 3.63[QC:7,9]
175	Core 45 Composite	WHOLE	3.53	< 2.98	< 3.255[QC:7,9]
176		WHOLE	< 4.25	< 4.5	< 4.375[QC:7]
179	Core 46 Composite	WHOLE	< 3.09	3.95	< 3.52[QC:7,9]
180		WHOLE	3.34	< 3.05	< 3.195[QC:7,9]
Liquids: acid digest			**µg/mL**	**µg/mL**	**µg/mL**
204	Core 46 Composite	DL	0.615	---	0.615[QC:7]
Solids: fusion			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	< 15.3	< 15.3	< 15.3[QC:7]
176		WHOLE	< 15.4	< 15.4	< 15.4[QC:7]
179	Core 46 Composite	WHOLE	< 19.4	< 19.5	< 19.45[QC:7]
180		WHOLE	< 19.3	< 19.3	< 19.3[QC:7]
Solids: water digest			**µg/g**	**µg/g**	**µg/g**
61.05 175	Core 45 Composite	WHOLE	< 3.15	< 3.15	< 3.15[QC:7]
176		WHOLE	< 3.15	< 3.16	< 3.155[QC:7]
179	Core 46 Composite	WHOLE	3.77	< 3.16	< 3.465[QC:7]
180		WHOLE	< 3.1	< 3.12	< 3.11[QC:7]

Note:

[1]Homogenization test sample

Table B2-11. Tank 241-T-104 Analytical Results: Barium (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: TCLP leachate			µg/mL	µg/mL	µg/mL
199	Core 45 Composite	WHOLE	8.07	---	8.07
196		WHOLE	< 0.02	< 0.02	< 0.02
Solids: acid digest			µg/g	µg/g	µg/g
147[1]	46: 2	WHOLE	9.91	9.89	9.9[QC:7]
146[1]		WHOLE	9.3	9.69	9.495[QC:7]
175	Core 45 Composite	WHOLE	7.29	6.63	6.96[QC:7]
176		WHOLE	8.03	7.64	7.835[QC:7]
179	Core 46 Composite	WHOLE	7.62	7.41	7.515[QC:7]
180		WHOLE	8.17	8.36	8.265[QC:7]
Liquids: acid digest			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	2.08	---	2.08[QC:7]
Solids: fusion			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	9	7.98	8.49[QC:7]
176		WHOLE	9.79	8.28	9.035[QC:7]
179	Core 46 Composite	WHOLE	8.19	8.61	8.4[QC:7]
180		WHOLE	8.15	8.61	8.38[QC:7]
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	< 0.304	0.322	< 0.313[QC:7]
176		WHOLE	0.325	< 0.306	< 0.3155[QC:7]
179	Core 46 Composite	WHOLE	< 0.305	< 0.305	< 0.305[QC:7]
180		WHOLE	0.306	< 0.302	< 0.304[QC:7,9]

Note:

[1]Homogenization test sample

Table B2-12. Tank 241-T-104 Analytical Results: Beryllium (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			**µg/g**	**µg/g**	**µg/g**
147[1]	46: 2	WHOLE	< 0.293	< 0.297	< 0.295[QC:7]
146[1]		WHOLE	< 0.295	< 0.297	< 0.296[QC:7]
175	Core 45 Composite	WHOLE	< 0.284	< 0.288	< 0.286[QC:7]
176		WHOLE	< 0.411	< 0.435	< 0.423[QC:7]
179	Core 46 Composite	WHOLE	< 0.299	< 0.296	< 0.2975[QC:7]
180		WHOLE	< 0.296	< 0.295	< 0.2955
Liquids: acid digest			**µg/mL**	**µg/mL**	**µg/mL**
204	Core 46 Composite	DL	0.03	---	0.03
Solids: fusion			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	< 1.48	< 1.48	< 1.48[QC:7]
176		WHOLE	< 1.49	< 1.49	< 1.49[QC:7]
179	Core 46 Composite	WHOLE	< 1.49	< 1.5	< 1.495
180		WHOLE	< 1.49	< 1.48	< 1.485
Solids: water digest			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	< 0.304	< 0.304	< 0.304[QC:7]
176		WHOLE	< 0.305	< 0.306	< 0.3055[QC:7]
179	Core 46 Composite	WHOLE	< 0.305	< 0.305	< 0.305[QC:7]
180		WHOLE	< 0.3	< 0.302	< 0.301[QC:7]

Note:

[1]Homogenization test sample

Table B2-13. Tank 241-T-104 Analytical Results: Bismuth (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			µg/g	µg/g	µg/g
147[1]	46: 2	WHOLE	25,600	24,700	25,150[QC:4,7,8,9]
146[1]		WHOLE	24,200	23,600	23,900[QC:4,7,8]
175	Core 45 Composite	WHOLE	20,000	18,000	19,000[QC:4]
176		WHOLE	19,800	19,100	19,450[QC:4]
179	Core 46 Composite	WHOLE	18,500	17,700	18,100[QC:4,7]
180		WHOLE	18,700	19,200	18,950[QC:4,7]
Liquids: acid digest			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	485	---	485[QC:4,7]
Solids: fusion			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	18,300	19,100	18,700[QC:4]
176		WHOLE	17,700	18,700	18,200[QC:4]
179	Core 46 Composite	WHOLE	16,700	15,700	16,200[QC:4,7]
180		WHOLE	16,300	16,300	16,300[QC:4,7]
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	118	139	128.5[QC:4]
176		WHOLE	175	213	194[QC:4]
179	Core 46 Composite	WHOLE	176	170	173[QC:4,7,10]
180		WHOLE	198	156	177[QC:4,7,9,10]

Note:

[1]Homogenization test sample

Table B2-14. Tank 241-T-104 Analytical Results: Boron (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			µg/g	µg/g	µg/g
147[1]	46: 2	WHOLE	5.24	3.75	4.495[QC:5,7,8,9]
146[1]		WHOLE	9.99	3.99	6.99[QC:5,7,8,9]
175	Core 45 Composite	WHOLE	17.2	11.9	14.55[QC:7,8,9]
176		WHOLE	14.6	23.6	19.1[QC:7,8,9]
179	Core 46 Composite	WHOLE	10.5	19.6	15.05[QC:5,7,8,9]
180		WHOLE	13.5	14.1	13.8[QC:5,7,8]
Liquids: acid digest			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	7.64	---	7.64[QC:7,8,13]
Solids: fusion			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	< 9.37	< 9.39	< 9.38[QC:7]
176		WHOLE	< 9.44	< 9.44	< 9.44[QC:7]
179	Core 46 Composite	WHOLE	< 4.98	< 4.99	< 4.985[QC:7]
180		WHOLE	< 4.96	< 4.94	< 4.95[QC:7]
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	10.5	10.8	10.65[QC:7]
176		WHOLE	11.8	10.3	11.05[QC:7]
179	Core 46 Composite	WHOLE	12.3	12.7	12.5[QC:7]
180		WHOLE	11.8	11.6	11.7[QC:7]

Note:

[1]Homogenization test sample

Table B2-15. Tank 241-T-104 Analytical Results: Cadmium (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: TCLP leachate			**µg/mL**	**µg/mL**	**µg/mL**
199	Core 45 Composite	WHOLE	0.815	---	0.815
196		WHOLE	< 0.035	< 0.035	< 0.035
Solids: acid digest			**µg/g**	**µg/g**	**µg/g**
147[1]	46: 2	WHOLE	3.08	4.01	3.545[QC:7,9]
146[1]		WHOLE	2.63	2.84	2.735[QC:7]
175	Core 45 Composite	WHOLE	1.93	1.84	1.885[QC:7]
176		WHOLE	1.8	1.25	1.525[QC:7]
179	Core 46 Composite	WHOLE	1.47	1.84	1.655[QC:7,9]
180		WHOLE	1.71	1.7	1.705[QC:7]
Liquids: acid digest			**µg/mL**	**µg/mL**	**µg/mL**
204	Core 46 Composite	DL	0.278	---	0.278[QC:7]
Solids: fusion			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	3.88	< 3.46	< 3.67[QC:7]
176		WHOLE	4.57	< 3.48	< 4.025[QC:7]
179	Core 46 Composite	WHOLE	4.95	8.2	6.575[QC:6,7,9]
180		WHOLE	8.7	6.25	7.475[QC:6,7,9]
Solids: water digest			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	< 0.71	< 0.71	< 0.71[QC:7]
176		WHOLE	< 0.711	< 0.714	< 0.7125[QC:7]
179	Core 46 Composite	WHOLE	< 0.711	< 0.713	< 0.712[QC:7]
180		WHOLE	< 0.701	< 0.706	< 0.7035[QC:7]

Note:

[1]Homogenization test sample

Table B2-16. Tank 241-T-104 Analytical Results: Calcium (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			**µg/g**	**µg/g**	**µg/g**
147[1]	46: 2	WHOLE	395	400	397.5[QC:4,8,13]
146[1]		WHOLE	358	350	354[QC:4,8,13]
175	Core 45 Composite	WHOLE	215	192	203.5[QC:7,10,13]
176		WHOLE	247	247	247[QC:8,10,13]
179	Core 46 Composite	WHOLE	296	221	258.5[QC:5,7,8,9,10]
180		WHOLE	369	312	340.5[QC:5,7,8,10]
Liquids: acid digest			**µg/mL**	**µg/mL**	**µg/mL**
204	Core 46 Composite	DL	23.3	---	23.3[QC:7,8]
Solids: fusion			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	6,720	771	3,745.5[QC:7,9]
176		WHOLE	607	539	573[QC:7]
179	Core 46 Composite	WHOLE	575	997	786[QC:6,7,9]
180		WHOLE	801	577	689[QC:6,7,9]
Solids: water digest			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	191	154	172.5[QC:7,13]
176		WHOLE	192	196	194[QC:7,13]
179	Core 46 Composite	WHOLE	176	147	161.5[QC:5,7]
180		WHOLE	175	140	157.5[QC:5,7,9]

Note:

[1]Homogenization test sample

Table B2-17. Tank 241-T-104 Analytical Results: Cerium (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			µg/g	µg/g	µg/g
147[1]	46: 2	WHOLE	224	212	218[QC:4,7,13]
146[1]		WHOLE	212	209	210.5[QC:4,7,13]
175	Core 45 Composite	WHOLE	183	170	176.5[QC:4]
176		WHOLE	195	190	192.5[QC:4]
179	Core 46 Composite	WHOLE	197	192	194.5[QC:4,7,13]
180		WHOLE	209	217	213[QC:4,7,13]
Liquids: acid digest			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	15.6	---	15.6[QC:4,7,13]
Solids: fusion			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	144	131	137.5[QC:4]
176		WHOLE	235	158	196.5[QC:4]
179	Core 46 Composite	WHOLE	156	177	166.5[QC:4,7,13]
180		WHOLE	124	153	138.5[QC:4,7,9,13]
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	< 8.73	< 8.73	< 8.73[QC:4]
176		WHOLE	< 8.74	< 8.77	< 8.755[QC:4]
179	Core 46 Composite	WHOLE	< 8.74	< 8.75	< 8.745[QC:4,7]
180		WHOLE	< 8.61	< 8.67	< 8.64[QC:4,7]

Note:

[1]Homogenization test sample

Table B2-18. Tank 241-T-104 Analytical Results: Chromium (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: TCLP leachate			**µg/mL**	**µg/mL**	**µg/mL**
199	Core 45 Composite	WHOLE	8.52	---	8.52
196		WHOLE	6.35	6.22	6.285[QC:9]
Solids: acid digest			**µg/g**	**µg/g**	**µg/g**
147[1]	46: 2	WHOLE	1,120	1,040	1,080
146[1]		WHOLE	1,030	1,030	1,030
175	Core 45 Composite	WHOLE	895	792	843.5
176		WHOLE	912	886	899
179	Core 46 Composite	WHOLE	916	884	900
180		WHOLE	941	979	960
Liquids: acid digest			**µg/mL**	**µg/mL**	**µg/mL**
204	Core 46 Composite	DL	316	---	316
Solids: fusion			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	854	870	862
176		WHOLE	813	853	833
179	Core 46 Composite	WHOLE	852	848	850
180		WHOLE	957	885	921
Solids: water digest			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	140	132	136
176		WHOLE	141	144	142.5
179	Core 46 Composite	WHOLE	149	148	148.5
180		WHOLE	149	148	148.5

Note:

[1]Homogenization test sample

Table B2-19. Tank 241-T-104 Analytical Results: Cobalt (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			µg/g	µg/g	µg/g
147[1]	46: 2	WHOLE	1.65	1.66	1.655[QC:7]
146[1]		WHOLE	< 1.18	1.4	< 1.29[QC:7,9]
175	Core 45 Composite	WHOLE	1.36	1.44	1.4[QC:7]
176		WHOLE	1.8	< 1.74	< 1.77[QC:7]
179	Core 46 Composite	WHOLE	< 1.2	2.04	< 1.62[QC:7,9]
180		WHOLE	< 1.19	1.75	< 1.47[QC:7,9]
Liquids: acid digest			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	0.545	---	0.545
Solids: fusion			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	10.3	11.7	11
176		WHOLE	14.6	12.1	13.35
179	Core 46 Composite	WHOLE	< 9.46	< 9.48	< 9.47
180		WHOLE	< 9.42	< 9.39	< 9.405
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	< 1.22	< 1.22	< 1.22[QC:7]
176		WHOLE	< 1.22	< 1.22	< 1.22[QC:7]
179	Core 46 Composite	WHOLE	< 1.22	< 1.22	< 1.22[QC:7]
180		WHOLE	< 1.2	< 1.21	< 1.205[QC:7]

Note:

[1]Homogenization test sample

Table B2-20. Tank 241-T-104 Analytical Results: Copper (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			µg/g	µg/g	µg/g
147[1]	46: 2	WHOLE	6.78	8.85	7.815[QC:7,9]
146[1]		WHOLE	7.45	6.32	6.885[QC:7]
175	Core 45 Composite	WHOLE	11.9	11.4	11.65
176		WHOLE	13.7	13.1	13.4
179	Core 46 Composite	WHOLE	12.8	12.1	12.45[QC:13]
180		WHOLE	12.3	12.3	12.3[QC:13]
Liquids: acid digest			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	4.61	---	4.61
Solids: fusion			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	77.9	77.2	77.55
176		WHOLE	52.6	48.8	50.7
179	Core 46 Composite	WHOLE	14.3	49.5	31.9[QC:7,9]
180		WHOLE	42.9	44.4	43.65[QC:6]
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	< 0.609	< 0.609	< 0.609[QC:7]
176		WHOLE	< 0.61	< 0.612	< 0.611[QC:7]
179	Core 46 Composite	WHOLE	< 0.61	< 0.611	< 0.6105[QC:7]
180		WHOLE	< 0.601	< 0.605	< 0.603[QC:7]

Note:

[1]Homogenization test sample

Table B2-21. Tank 241-T-104 Analytical Results: Iron (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			µg/g	µg/g	µg/g
147[1]	46: 2	WHOLE	17,800	23,100	20,450[QC:9]
146[1]		WHOLE	13,800	14,800	14,300
175	Core 45 Composite	WHOLE	9,660	8,520	9,090
176		WHOLE	9,680	9,310	9,495
179	Core 46 Composite	WHOLE	8,540	8,300	8,420
180		WHOLE	9,140	8,980	9,060
Liquids: acid digest			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	1,520	---	1,520[QC:13]
Solids: fusion			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	9,410	10,100	9,755[QC:10]
176		WHOLE	8,960	9,350	9,155[QC:10]
179	Core 46 Composite	WHOLE	8,200	7,920	8,060
180		WHOLE	8,640	8,130	8,385
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	61.7	68.9	65.3[QC:10]
176		WHOLE	83.6	103	93.3[QC:9,10]
179	Core 46 Composite	WHOLE	81.3	81.7	81.5[QC:10]
180		WHOLE	91.6	74.7	83.15[QC:9,10]

Note:

[1]Homogenization test sample

Table B2-22. Tank 241-T-104 Analytical Results: Lanthanum (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			µg/g	µg/g	µg/g
147[1]	46: 2	WHOLE	< 2.05	< 2.08	< 2.065[QC:4,7]
146[1]		WHOLE	< 2.06	< 2.08	< 2.07[QC:4,7]
175	Core 45 Composite	WHOLE	< 1.99	< 2.02	< 2.005[QC:4]
176		WHOLE	< 2.88	< 3.05	< 2.965[QC:4]
179	Core 46 Composite	WHOLE	< 2.1	< 2.08	< 2.09[QC:4,7]
180		WHOLE	< 2.08	< 2.07	< 2.075[QC:4,7]
Liquids: acid digest			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	0.21	---	0.21[QC:4]
Solids: fusion			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	< 10.4	< 10.4	< 10.4[QC:4]
176		WHOLE	< 10.4	< 10.4	< 10.4[QC:4]
179	Core 46 Composite	WHOLE	< 9.96	< 9.98	< 9.97[QC:4]
180		WHOLE	< 9.92	< 9.88	< 9.9[QC:4]
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	< 2.13	< 2.13	< 2.13[QC:4]
176		WHOLE	< 2.13	< 2.14	< 2.135[QC:4]
179	Core 46 Composite	WHOLE	< 2.13	< 2.14	< 2.135[QC:4]
180		WHOLE	< 2.1	< 2.12	< 2.11[QC:4,7]

Note:

[1]Homogenization test sample

Table B2-23. Tank 241-T-104 Analytical Results: Lead (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: TCLP leachate			**µg/mL**	**µg/mL**	**µg/mL**
199	Core 45 Composite	WHOLE	5.09	---	5.09
196		WHOLE	< 0.39	< 0.39	< 0.39[QC:4,7]
Solids: acid digest			**µg/g**	**µg/g**	**µg/g**
147[1]	46: 2	WHOLE	141	120	130.5[QC:4,7]
146[1]		WHOLE	148	67.5	107.75[QC:4,7,9]
175	Core 45 Composite	WHOLE	85.3	50.5	67.9[QC:7,9,10]
176		WHOLE	42.3	40.3	41.3[QC:7,10]
179	Core 46 Composite	WHOLE	28.5	28.5	28.5[QC:7]
180		WHOLE	88.6	34.5	61.55[QC:7,12]
Liquids: acid digest			**µg/mL**	**µg/mL**	**µg/mL**
204	Core 46 Composite	DL	1.58	---	1.58[QC:4]
Solids: fusion			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	46.6	< 42	< 44.3[QC:7.,9]
176		WHOLE	90.8	< 42.2	< 66.5[QC:7,9]
179	Core 46 Composite	WHOLE	< 38.8	65.2	< 52[QC:7,9]
180		WHOLE	< 38.7	43.3	< 41[QC:7,9]
Solids: water digest			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	< 8.63	< 8.63	< 8.63[QC:7]
176		WHOLE	< 8.64	< 8.67	< 8.655[QC:7]
179	Core 46 Composite	WHOLE	< 8.64	< 8.65	< 8.645
180		WHOLE	< 8.51	< 8.57	< 8.54

Note:

[1]Homogenization test sample

Table B2-24. Tank 241-T-104 Analytical Results: Magnesium (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			µg/g	µg/g	µg/g
147[1]	46: 2	WHOLE	126	123	124.5[QC:7,13]
146[1]		WHOLE	122	103	112.5[QC:7,13]
175	Core 45 Composite	WHOLE	102	90.2	96.1
176		WHOLE	111	118	114.5[QC:7]
179	Core 46 Composite	WHOLE	99.9	99.8	99.85[QC:5,7]
180		WHOLE	103	104	103.5[QC:5,7]
Liquids: acid digest			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	22.3	---	22.3[QC:7,8]
Solids: fusion			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	267	131	199
176		WHOLE	125	123	124
179	Core 46 Composite	WHOLE	122	123	122.5[QC:6,7]
180		WHOLE	124	110	117[QC:6,7]
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	8.77	5.66	7.215
176		WHOLE	7.35	7.75	7.55
179	Core 46 Composite	WHOLE	4.4	4.68	4.54[QC:5,9]
180		WHOLE	5.23	4.62	4.925[QC:5,9]

Note:

[1]Homogenization test sample

Table B2-25. Tank 241-T-104 Analytical Results: Manganese (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			µg/g	µg/g	µg/g
147[1]	46: 2	WHOLE	69.1	84.7	76.9[QC:9]
146[1]		WHOLE	53	53.7	53.35
175	Core 45 Composite	WHOLE	32.8	28.7	30.75
176		WHOLE	31.9	30.4	31.15
179	Core 46 Composite	WHOLE	29.1	28.4	28.75
180		WHOLE	32.6	30.8	31.7
Liquids: acid digest			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	5.12	---	5.12
Solids: fusion			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	64.1	64.4	64.25
176		WHOLE	57.8	59.5	58.65
179	Core 46 Composite	WHOLE	47.1	68.9	58[QC:6,9]
180		WHOLE	69.4	63.1	66.25
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	< 0.304	< 0.304	< 0.304
176		WHOLE	0.395	0.401	0.398
179	Core 46 Composite	WHOLE	0.442	0.318	0.38
180		WHOLE	0.508	0.363	0.4355

Note:

[1]Homogenization test sample

Table B2-26. Tank 241-T-104 Analytical Results: Nickel (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			µg/g	µg/g	µg/g
147[1]	46: 2	WHOLE	9.35	10.1	9.725[QC:7]
146[1]		WHOLE	8.93	7.68	8.305[QC:7]
175	Core 45 Composite	WHOLE	10.8	11.3	11.05
176		WHOLE	9.01	7.9	8.455[QC:7]
179	Core 46 Composite	WHOLE	22.9	10.8	16.85[QC:7,9]
180		WHOLE	7.96	9.63	8.795[QC:7]
Liquids: acid digest			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	1.61	---	1.61[QC:7]
Solids: fusion			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	11,100	7,930	9,515[QC:7,9]
176		WHOLE	8,830	7,280	8,055[QC:7]
179	Core 46 Composite	WHOLE	5,830	13,200	9,515[QC:6,7,9]
180		WHOLE	17,700	11,900	14,800[QC:7,9]
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	< 1.83	< 1.83	< 1.83[QC:7]
176		WHOLE	< 1.83	< 1.84	< 1.835[QC:7]
179	Core 46 Composite	WHOLE	< 1.83	< 1.83	< 1.83[QC:7]
180		WHOLE	< 1.8	< 1.81	< 1.805[QC:7]

Note:

[1]Homogenization test sample

Table B2-27. Tank 241-T-104 Analytical Results: Phosphorus (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			**µg/g**	**µg/g**	**µg/g**
147[1]	46: 2	WHOLE	27,500	26,600	27,050[QC:4,7]
146[1]		WHOLE	27,100	28,100	27,600[QC:4,7]
175	Core 45 Composite	WHOLE	24,600	22,800	23,700[QC:4]
176		WHOLE	25,500	25,200	25,350[QC:4]
179	Core 46 Composite	WHOLE	23,700	23,000	23,350[QC:4,7]
180		WHOLE	23,400	23,800	23,600[QC:4,7]
Liquids: acid digest			**µg/mL**	**µg/mL**	**µg/mL**
204	Core 46 Composite	DL	10,700	---	10,700[QC:4,7,13]
Solids: fusion			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	26,300	26,100	26,200[QC:4]
176		WHOLE	27,700	27,100	27,400[QC:4]
179	Core 46 Composite	WHOLE	22,300	22,400	22,350[QC:4,7]
180		WHOLE	23,600	21,800	22,700[QC:4,7]
Solids: water digest			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	6,000	5,750	5,875[QC:4]
176		WHOLE	6,470	6,550	6,510[QC:4]
179	Core 46 Composite	WHOLE	6,840	6,580	6,710[QC:4,7]
180		WHOLE	6,530	6,530	6,530[QC:4,7]

Note:

[1]Homogenization test sample

Table B2-28. Tank 241-T-104 Analytical Results: Potassium (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			µg/g	µg/g	µg/g
147[1]	46: 2	WHOLE	90.6	91.2	90.9
146[1]		WHOLE	94.1	88.7	91.4
175	Core 45 Composite	WHOLE	83.4	94.2	88.8[QC:8]
176		WHOLE	90.6	94.7	92.65
179	Core 46 Composite	WHOLE	84.9	89.6	87.25
180		WHOLE	83.8	91.1	87.45
Liquids: acid digest			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	74.7	---	74.7
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	34.6	32.1	33.35
176		WHOLE	36.6	38.2	37.4
179	Core 46 Composite	WHOLE	36.8	37.4	37.1
180		WHOLE	41.4	30.4	35.9

Note:

[1]Homogenization test sample

Table B2-29. Tank 241-T-104 Analytical Results: Selenium (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			µg/g	µg/g	µg/g
147[1]	46: 2	WHOLE	34.5	30.4	32.45[QC:4,7]
146[1]		WHOLE	25.5	18.7	22.1[QC:4,7,9]
175	Core 45 Composite	WHOLE	< 12.4	15	< 13.7
176		WHOLE	28.4	< 19	< 23.7[QC:9]
179	Core 46 Composite	WHOLE	< 13.1	< 12.9	< 13[QC:4,7]
180		WHOLE	< 12.9	< 12.9	< 12.9[QC:4,7]
Liquids: acid digest			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	14.2	---	14.2[QC:4,13]
Solids: fusion			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	< 64.6	< 64.7	< 64.65[QC:7]
176		WHOLE	< 65.1	< 65.1	< 65.1[QC:7]
179	Core 46 Composite	WHOLE	< 70.2	< 70.4	< 70.3[QC:4]
180		WHOLE	< 69.9	< 69.7	< 69.8[QC:4]
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	< 13.3	< 13.3	< 13.3[QC:4,7]
176		WHOLE	< 13.3	< 13.4	< 13.35[QC:4,7]
179	Core 46 Composite	WHOLE	< 13.3	< 13.3	< 13.3[QC:4,7]
180		WHOLE	< 13.1	< 13.2	< 13.15[QC:4,7]

Note:

[1]Homogenization test sample

Table B2-30. Tank 241-T-104 Analytical Results: Silicon (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			µg/g	µg/g	µg/g
147[1]	46: 2	WHOLE	1,910	1,120	1,515[QC:4,8,9]
146[1]		WHOLE	1,370	1,100	1,235[QC:4,8,9]
175	Core 45 Composite	WHOLE	552	780	666[QC:7,8,9]
176		WHOLE	1,170	981	1,075.5[QC:8,10]
179	Core 46 Composite	WHOLE	1,200	1,110	1,155[QC:8]
180		WHOLE	1,170	1,170	1,170[QC:8]
Liquids: acid digest			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	631	---	631[QC:8,13]
Solids: fusion			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	6,770	7,160	6,965
176		WHOLE	6,270	6,590	6,430
179	Core 46 Composite	WHOLE	6,300	6,280	6,290
180		WHOLE	6,420	6,330	6,375
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	170	160	165[QC:7]
176		WHOLE	154	171	162.5[QC:7]
179	Core 46 Composite	WHOLE	190	157	173.5[QC:7,13]
180		WHOLE	174	160	167[QC:7]

Note:

[1]Homogenization test sample

Table B2-31. Tank 241-T-104 Analytical Results: Silver (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: TCLP leachate			**µg/mL**	**µg/mL**	**µg/mL**
199	Core 45 Composite	WHOLE	0.0688	---	0.0688
196		WHOLE	< 0.045	< 0.045	< 0.045[QC:4,7]
Solids: acid digest			**µg/g**	**µg/g**	**µg/g**
147[1]	46: 2	WHOLE	< 0.976	< 0.99	<0.983[QC:4,7,8,10]
146[1]		WHOLE	< 0.983	< 0.991	<0.987[QC:4,7,8,10]
175	Core 45 Composite	WHOLE	< 0.947	< 0.96	< 0.9535[QC:8,10]
176		WHOLE	< 1.37	< 1.45	< 1.41[QC:7,8,10]
179	Core 46 Composite	WHOLE	< 0.998	< 0.988	< 0.993[QC:8,10]
180		WHOLE	< 0.988	< 0.984	< 0.986[QC:8,10]
Liquids: acid digest			**µg/mL**	**µg/mL**	**µg/mL**
204	Core 46 Composite	DL	< 0.1	---	< 0.1[QC:4]
Solids: fusion			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	< 4.93	< 4.94	< 4.935
176		WHOLE	6.4	< 4.97	< 5.685[QC:9]
179	Core 46 Composite	WHOLE	< 4.48	< 4.49	< 4.485[QC:4,7]
180		WHOLE	< 4.46	< 4.45	< 4.455[QC:4,7]
Solids: water digest			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	2.51	< 1.01	< 1.76[QC:7,9]
176		WHOLE	< 1.02	< 1.02	< 1.02[QC:7]
179	Core 46 Composite	WHOLE	< 1.02	< 1.02	< 1.02[QC:7]
180		WHOLE	< 1	< 1.01	< 1.005[QC:7]

Note:

[1]Homogenization test sample

Table B2-32. Tank 241-T-104 Analytical Results: Sodium (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			**µg/g**	**µg/g**	**µg/g**
147[1]	46: 2	WHOLE	72,900	69,300	71,100[QC:8]
146[1]		WHOLE	68,800	69,600	69,200[QC:8]
175	Core 45 Composite	WHOLE	65,100	59,600	62,350[QC:8]
176		WHOLE	72,200	70,200	71,200[QC:8]
179	Core 46 Composite	WHOLE	63,600	61,700	62,650[QC:4,8]
180		WHOLE	61,600	62,000	61,800[QC:4,8]
Liquids: acid digest			**µg/mL**	**µg/mL**	**µg/mL**
204	Core 46 Composite	DL	55,400	---	55,400[QC:4,8,13]
Solids: fusion			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	63,800	65,100	64,450
176		WHOLE	61,700	62,700	62,200
179	Core 46 Composite	WHOLE	60,800	60,700	60,750[QC:4,10]
180		WHOLE	61,700	59,900	60,800[QC:4,10]
Solids: water digest			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	45,100	43,900	44,500
176		WHOLE	46,200	46,800	46,500
179	Core 46 Composite	WHOLE	48,400	47,100	47,750
180		WHOLE	47,500	47,100	47,300

Note:

[1]Homogenization test sample

Table B2-33. Tank 241-T-104 Analytical Results: Strontium (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			µg/g	µg/g	µg/g
147[1]	46: 2	WHOLE	126	121	123.5[QC:4,7]
146[1]		WHOLE	118	121	119.5[QC:4,7]
175	Core 45 Composite	WHOLE	92.1	82.1	87.1[QC:4]
176		WHOLE	97.8	94.8	96.3[QC:4]
179	Core 46 Composite	WHOLE	100	95.6	97.8[QC:4,7]
180		WHOLE	105	107	106[QC:4,7]
Liquids: acid digest			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	13.8	---	13.8[QC:4,7]
Solids: fusion			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	98.4	98	98.2[QC:4]
176		WHOLE	90	95.5	92.75[QC:4]
179	Core 46 Composite	WHOLE	99.9	99.3	99.6[QC:4.6.7]
180		WHOLE	107	105	106[QC:4.6.7]
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	1.46	1.07	1.265[QC:4]
176		WHOLE	1.26	1.54	1.4[QC:4]
179	Core 46 Composite	WHOLE	0.925	0.931	0.928[QC:4.7]
180		WHOLE	1.23	0.934	1.082[QC:4,7,9]

Note:

[1]Homogenization test sample

Table B2-34. Tank 241-T-104 Analytical Results: Sulfur (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			**µg/g**	**µg/g**	**µg/g**
147[1]	46: 2	WHOLE	1,180	1,100	1,140[QC:4,7]
146[1]		WHOLE	1,090	1,100	1,095[QC:4,7]
175	Core 45 Composite	WHOLE	1,310	1,180	1,245[QC:4]
176		WHOLE	1,370	1,320	1,345[QC:4]
179	Core 46 Composite	WHOLE	1,270	1,260	1,265[QC:4,7]
180		WHOLE	1,230	1,270	1,250[QC:4,7]
Liquids: acid digest			**µg/mL**	**µg/mL**	**µg/mL**
204	Core 46 Composite	DL	1,700		1,700
Solids: fusion			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	1,290	1,320	1,305[QC:4]
176		WHOLE	1,270	1,310	1,290[QC:4]
179	Core 46 Composite	WHOLE	1,230	1,230	1,230[QC:4,7]
180		WHOLE	1,280	1,200	1,240[QC:4,7]
Solids: water digest			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	1,270	1,200	1,235[QC:4]
176		WHOLE	1,310	1,310	1,310[QC:4]
179	Core 46 Composite	WHOLE	1,320	1,300	1,310[QC:4]
180		WHOLE	1,280	1,270	1,275[QC:4]

Note:

[1]Homogenization test sample

Table B2-35. Tank 241-T-104 Analytical Results: Tin (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			µg/g	µg/g	µg/g
147[1]	46: 2	WHOLE	15.4	15.8	15.6[QC:4,5]
146[1]		WHOLE	18.1	14.1	16.1[QC:4,5,9]
175	Core 45 Composite	WHOLE	10.6	9.37	9.985[QC:4]
176		WHOLE	13.2	16.1	14.65[QC:4]
179	Core 46 Composite	WHOLE	10.8	10.2	10.5[QC:4,5]
180		WHOLE	11	11.8	11.4[QC:4,5]
Liquids: acid digest			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	1.78	---	1.78[QC:4]
Solids: fusion			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	16.8	17.3	17.05[QC:4]
176		WHOLE	16.1	19.7	17.9[QC:4]
179	Core 46 Composite	WHOLE	< 8.96	< 8.98	< 8.97[QC:4]
180		WHOLE	< 8.93	< 8.89	< 8.91[QC:4]
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	< 1.62	< 1.62	< 1.62[QC:4]
176		WHOLE	< 1.63	< 1.63	< 1.63[QC:4]
179	Core 46 Composite	WHOLE	< 1.63	< 1.63	< 1.63[QC:4]
180		WHOLE	< 1.6	< 1.61	< 1.605[QC:4]

Note:

[1]Homogenization test sample

Table B2-36. Tank 241-T-104 Analytical Results: Titanium (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			**µg/g**	**µg/g**	**µg/g**
147[1]	46: 2	WHOLE	18.7	16.3	17.5[QC:7]
146[1]		WHOLE	16.7	16	16.35[QC:7]
175	Core 45 Composite	WHOLE	5.46	4.98	5.22
176		WHOLE	4.09	4.07	4.08
179	Core 46 Composite	WHOLE	4.44	4.01	4.225
180		WHOLE	4.46	4.98	4.72
Liquids: acid digest			**µg/mL**	**µg/mL**	**µg/mL**
204	Core 46 Composite	DL	0.995	---	0.995[QC:13]
Solids: fusion			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	5.64	11.7	8.67[QC:7,9]
176		WHOLE	10.2	9.84	10.02[QC:7]
179	Core 46 Composite	WHOLE	6.7	18.4	12.55[QC:8]
180		WHOLE	7.04	7.82	7.43
Solids: water digest			**µg/g**	**µg/g**	**µg/g**
175	Core 45 Composite	WHOLE	< 0.507	< 0.507	< 0.507[QC:7]
176		WHOLE	< 0.508	< 0.51	< 0.509[QC:7]
179	Core 46 Composite	WHOLE	< 0.508	< 0.509	< 0.5085
180		WHOLE	< 0.5	< 0.504	< 0.502[QC:7]

Note:

[1]Homogenization test sample

Table B2-37. Tank 241-T-104 Analytical Results: Zinc (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			µg/g	µg/g	µg/g
147[1]	46: 2	WHOLE	33.5	46.2	39.85[QC:7,9]
146[1]		WHOLE	24.8	23.8	24.3[QC:7]
175	Core 45 Composite	WHOLE	21	26	23.5[QC:7,9]
176		WHOLE	30.6	20.5	25.55[QC:7,9]
179	Core 46 Composite	WHOLE	21.2	18.6	19.9[QC:5,7]
180		WHOLE	26.8	23.5	25.15[QC:5,7]
Liquids: acid digest			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	3.12	---	3.12[QC:7]
Solids: fusion			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	265	152	208.5[QC:7,9]
176		WHOLE	177	145	161[QC:7]
179	Core 46 Composite	WHOLE	51.3	101	76.15[QC:6,7,9]
180		WHOLE	115	87.6	101.3[QC:6,7,9]
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	< 2.54	< 2.54	< 2.54[QC:7]
176		WHOLE	9.8	< 2.55	< 6.175[QC:7,9]
179	Core 46 Composite	WHOLE	< 2.54	< 2.54	< 2.54[QC:7]
180		WHOLE	< 2.5	< 2.52	< 2.51[QC:7]

Note:

[1]Homogenization test sample

Table B2-38. Tank 241-T-104 Analytical Results: Zirconium (ICP).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: acid digest			µg/g	µg/g	µg/g
147[1]	46: 2	WHOLE	87.2	75.7	81.45[QC:4,10]
146[1]		WHOLE	52.9	59	55.95[QC:4,10]
175	Core 45 Composite	WHOLE	35.3	42	38.65[QC:4,10]
176		WHOLE	58.3	48.1	53.2[QC:4,10]
179	Core 46 Composite	WHOLE	92.3	76.1	84.2[QC:4,10]
180		WHOLE	90.4	97.1	93.75[QC:4,10]
Liquids: acid digest			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	3.42	---	3.42[QC:4]
Solids: fusion			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	33.7	27.7	30.7[QC:4]
176		WHOLE	31.7	52.8	42.25[QC:4]
179	Core 46 Composite	WHOLE	34.8	44	39.4[QC:4,9]
180		WHOLE	33.6	41.4	37.5[QC:4,9]
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	2.23	2.59	2.41[QC:4]
176		WHOLE	2.69	2.7	2.695[QC:4]
179	Core 46 Composite	WHOLE	2.15	2.15	2.15[QC:4,7]
180		WHOLE	3.19	1.91	2.55[QC:4]

Note:

[1]Homogenization test sample

Table B2-39. Tank 241-T-104 Analytical Results: Chloride (IC).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	689	629	659[QC:2]
176		WHOLE	663	658	660.5[QC:2]
179	Core 46 Composite	WHOLE	664	729	696.5[QC:2]
180		WHOLE	665	659	662[QC:2]
Liquids			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	1,560	1,470	1,515[QC:4]

Table B2-40. Tank 241-T-104 Analytical Results: Fluoride (IC).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	8,950	8,720	8,835[QC:2]
176		WHOLE	8,290	8,480	8,385[QC:2]
179	Core 46 Composite	WHOLE	8,730	8,980	8,855[QC:2]
180		WHOLE	8,360	8,040	8,200[QC:2]
Liquids			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	4,340	4,050	4,195[QC:4,10]

Table B2-41. Tank 241-T-104 Analytical Results: Nitrate (IC).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	56,200	56,200	56,200[QC:2]
176		WHOLE	57,900	59,000	58,450[QC:2]
179	Core 46 Composite	WHOLE	59,800	59,800	59,800[QC:2]
180		WHOLE	59,100	56,200	57,650[QC:2]
Liquids			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	97,900	97,400	**97,650**[QC:2,4]

Table B2-42. Tank 241-T-104 Analytical Results: Nitrite (IC).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	4,070	3,990	4,030[QC:2]
176		WHOLE	4,120	4,140	4,130[QC:2]
179	Core 46 Composite	WHOLE	3,970	4,120	4,045[QC:2]
180		WHOLE	4,110	4,130	4,120[QC:2]
Liquids			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	6,140	6,030	6,085[QC:2,4]

Table B2-43. Tank 241-T-104 Analytical Results: Phosphate (IC).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	16,800	16,400	16,600[QC:2]
176		WHOLE	17,100	17,500	17,300[QC:2]
179	Core 46 Composite	WHOLE	18,300	19,100	18,700[QC:2]
180		WHOLE	18,500	18,800	18,650[QC:2]
Liquids			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	25,000	25,000	25,000[QC:4,10]

Table B2-44. Tank 241-T-104 Analytical Results: Sulfate (IC).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	3,930	3,830	3,880[QC:2]
176		WHOLE	3,870	3,970	3,920[QC:2]
179	Core 46 Composite	WHOLE	3,780	4,060	3,920[QC:2]
180		WHOLE	3,850	3,880	3,865[QC:2]
Liquids			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	4,190	4,330	4,260[QC:4]

Table B2-45. Tank 241-T-104 Analytical Results: Total Uranium (LF).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	896	864	880
176		WHOLE	965	836	900.5
179	Core 46 Composite	WHOLE	834	899	866.5
180		WHOLE	894	990	942

Table B2-46. Tank 241-T-104 Analytical Results: Arsenic (AA [As]).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	0.787	0.912	0.8495[QC:3,9]
176		WHOLE	0.751	0.662	0.7065[QC:3,8]
179	Core 46 Composite	WHOLE	0.714	0.706	0.71[QC:4,8]
180		WHOLE	0.668	0.589	0.6285[QC:4,8]
Solids: TCLP leachate			µg/mL	µg/mL	µg/mL
196	Core 45 Composite	WHOLE	0.015	0.016	0.0155[QC:4,8,10]
198		WHOLE	< 0.0125	0.417	< 0.21475

Table B2-47. Tank 241-T-104 Analytical Results: Selenium (AA [Se]).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	< 0.5	< 0.5	< 0.5[QC:10]
176		WHOLE	< 0.5	< 0.5	< 0.5[QC:10]
179	Core 46 Composite	WHOLE	< 0.5	< 0.5	< 0.5[QC:4,8,10]
180		WHOLE	< 0.5	< 0.25	<0.375[QC:4,8,10]
Solids: TCLP leachate			µg/mL	µg/mL	µg/mL
196	Core 45 Composite	WHOLE	0.021	0.019	0.02[QC:8]

Table B2-48. Tank 241-T-104 Analytical Results: Mercury (CVAA [Hg]).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: TCLP leachate AA method			µg/mL	µg/mL	µg/mL
196	Core 45 Composite	WHOLE	< 0.0025	< 0.0025	< 0.0025[QC:2,8]
Solids: CVAA method			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	< 0.125	0.127	< 0.126[QC:2]
176		WHOLE	< 0.125	< 0.125	< 0.125[QC:2]
179	Core 46 Composite	WHOLE	< 0.125	< 0.125	< 0.125[QC:2,4]
180		WHOLE	< 0.125	< 0.125	< 0.125[QC:2,8]

Table B2-49. Tank 241-T-104 Analytical Results: Ammonia (Distillation).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	< 1,330	< 1,330	< 1,330[QC:2]
176		WHOLE	< 800	< 800	< 800[QC:2]
179	Core 46 Composite	WHOLE	< 4,500	< 4,500	< 4,500[QC:2]
180		WHOLE	< 4,500	< 4,500	< 4,500[QC:2]

Table B2-50. Tank 241-T-104 Analytical Results: Cyanide (Spec [CN]).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	< 2	< 2	< 2[QC:2]
176		WHOLE	< 2	< 2	< 2[QC:2]
Solids			µg/mL	µg/mL	µg/mL
179	Core 46 Composite	WHOLE	< 2	< 2	< 2[QC:2]
180		WHOLE	< 2	< 2	< 2[QC:2]
Liquids			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	0.692	0.715	0.7035

Table B2-51. Tank 241-T-104 Analytical Results: Nitrite (Spectrophotometric).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	4,210	4,100	4,155[QC:2]
176		WHOLE	4,340	4,340	4,340[QC:2]
179	Core 46 Composite	WHOLE	4,110	4,470	4,290[QC:2]
180		WHOLE	4,160	4,170	4,165[QC:2]

Table B2-52. Tank 241-T-104 Analytical Results: pH Measurement (pH).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: water digest			unitless	unitless	unitless
175	Core 45 Composite	WHOLE	10	10	10[QC:2]
176		WHOLE	10.02	9.98	10[QC:2]
179	Core 46 Composite	WHOLE	10.02	10.02	10.02[QC:2]
180		WHOLE	10.05	9.92	9.985[QC:2]
Liquids: water digest			unitless	unitless	unitless
204	Core 46 Composite	DL	9.94	9.96	9.95[QC:4]

Table B2-53. Tank 241-T-104 Analytical Results: Bis(2-ethylhexyl) phthalate (SVOA).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids			µg/g	µg/g	µg/g
93-01809-E1	Core 45 Composite	WHOLE	1.2	---	1.2[QC:1]
93-01810-E1		WHOLE	0.95	---	0.95[QC:1]
93-01811-E1	Core 46 Composite	WHOLE	< 9.2	---	< 9.2[QC:1]
93-01812-E1		WHOLE	< 11	---	< 11[QC:1]

Table B2-54. Tank 241-T-104 Analytical Results: Dodecane (SVOA).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids			µg/g	µg/g	µg/g
93-01809-E1	Core 45 Composite	WHOLE	190	---	190[QC:1]
93-01810-E1		WHOLE	170	---	170[QC:1]
93-01811-E1	Core 46 Composite	WHOLE	67	---	67[QC:1]
93-01812-E1		WHOLE	120	---	120[QC:1]

Table B2-55. Tank 241-T-104 Analytical Results: Pentadecane (SVOA).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids			µg/g	µg/g	µg/g
93-01809-E1	Core 45 Composite	WHOLE	27	---	27[QC:1]
93-01810-E1		WHOLE	25	---	25[QC:1]
93-01811-E1	Core 46 Composite	WHOLE	13	---	13[QC:1]
93-01812-E1		WHOLE	18	---	18[QC:1]

Table B2-56. Tank 241-T-104 Analytical Results: Tetradecane (SVOA).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids			µg/g	µg/g	µg/g
93-01809-E1	Core 45 Composite	WHOLE	600	---	600[QC:1]
93-01810-E1		WHOLE	540	---	540[QC:1]
93-01811-E1	Core 46 Composite	WHOLE	330	---	330[QC:1]
93-01812-E1		WHOLE	440	---	440[QC:1]

Table B2-57. Tank 241-T-104 Analytical Results: Tridecane (SVOA).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids			µg/g	µg/g	µg/g
93-01809-E1	Core 45 Composite	WHOLE	700	---	700[QC:1]
93-01810-E1		WHOLE	630	---	630[QC:1]
93-01811-E1	Core 46 Composite	WHOLE	340	---	340[QC:1]
93-01812-E1		WHOLE	490	---	490[QC:1]

Table B2-58. Tank 241-T-104 Analytical Results: Non-Detected SVOA Analytes. (2 sheets)

Analyte	Detection Limit	Analyte	Detection Level
1,2,4-Trichlorobenzene	<11[QC:1]	Benzo(a)pyrene	<11[QC:1]
1,2-Dichlorobenzene	<11[QC:1]	Benzo(b)fluoranthene	<11[QC:1]
1,3-Dichlorobenzene	<11[QC:1]	Benzo(ghi)perylene	<11[QC:1]
1,4-Dichlorobenzene	<11[QC:1]	Benzo(k)fluoranthene	<11[QC:1]
2,4,5-Trichlorophenol	<53[QC:1]	Benzoic acid	<53[QC:1]
2,4,6-Trichlorophenol	<11[QC:1]	Benzyl alcohol	<11[QC:1]
2,4-Dichlorophenol	<11[QC:1]	Bis(2-chloroethoxy)methane	<11[QC:1]
2,4-Dimethylphenol	<11[QC:1]	Bis(2-chloroisopropyl) ether	<11[QC:1]
2,4-Dinitrophenol	<53[QC:1]	Bis(2-chloroethyl) ether	<11[QC:1]
2,4-Dinitrotoluene	<11[QC:1]	Butylbenzylphthalate	<11[QC:1]
2,6-Dinitrotoluene	<11[QC:1]	Chrysene	<11[QC:1]
2-Chloronaphthalene	<11[QC:1]	Di-n-butylphthalate	<11[QC:1]
2-Chlorophenol	<11[QC:1]	Di-n-octylphthalate	<11[QC:1]
2-Methylnaphthalene	<11[QC:1]	Dibenz[a,h]anthracene	<11[QC:1]
2-Methylphenol	<11[QC:1]	Dibenzofuran	<11[QC:1]
2-Nitroaniline	<53[QC:1]	Diethylphthalate	<11[QC:1]
2-Nitrophenol	<11[QC:1]	Dimethylphthalate	<11[QC:1]
3,3-Dichlorobenzidine	<21[QC:1]	Fluoranthene	<11[QC:1]
3-Nitroaniline	<53[QC:1]	Fluorene	<11[QC:1]
4,6-Dinitro-o-cresol	<53[QC:1]	Hexachlorobenzene	<11[QC:1]
4-Bromophenylphenyl ether	<11[QC:1]	Hexachlorobutadiene	<11[QC:1]
4-Chloro-3-methylphenol	<11[QC:1]	Hexachlorocyclopentadiene	<11[QC:1]
4-Chloroaniline	<11[QC:1]	Hexachloroethane	<11[QC:1]
4-Chlorophenylphenyl ether	<11[QC:1]	Indeno(1,2,3-cd)pyrene	<11[QC:1]
4-Methylphenol	<11[QC:1]	Isophorone	<11[QC:1]

Table B2-58. Tank 241-T-104 Analytical Results: Non-Detected SVOA Analytes. (2 sheets)

Analyte	Detection Limit	Analyte	Detection Level
4-Nitroaniline	<53[QC:1]	N-nitroso-di-n-dipropyla mine	<11[QC:1]
4-Nitrophenol	<53[QC:1]	N-nitrosodiphenylamine	<11[QC:1]
Acenaphthene	<11[QC:1]	Naphthalene	<11[QC:1]
Acenaphthylene	<11[QC:1]	Nitrobenzene	<11[QC:1]
Anthracene	<11[QC:1]	Pentachlorophenol	<53[QC:1]
Phenol	<11[QC:1]	Pyrene	<11[QC:1]
Benzo(a)anthracene	<11[QC:1]	Phenanthrene	<11[QC:1]

Table B2-59. Tank 241-T-104 Analytical Results: Acetone (VOA)

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids			µg/g	µg/g	µg/g
COR45K108	45: 1	WHOLE	< 4.4	---	< 4.4[QC:1]
COR45K110	45: 3	WHOLE	< 5.4	---	< 5.4[QC:1]
COR45K112	45: 5	WHOLE	< 5.8	---	< 5.8[QC:1]
COR45K114	45: 7	WHOLE	0.81	---	0.81[QC:1]
COR45K116	45: 9	WHOLE	< 4.6	---	< 4.6[QC:1]
COR46S2	46: 2	WHOLE	< 6.5	---	< 6.5[QC:1]
COR46K120	46: 3	WHOLE	2.1	---	2.1[QC:1]
COR46S4	46: 4	WHOLE	< 6	---	< 6[QC:1]
COR46K121	46: 5	WHOLE	< 5.2	---	< 5.2[QC:1]
COR46K122	46: 6	WHOLE	3.7	---	3.7[QC:1]
COR46K123	46: 7	WHOLE	< 4.6	---	< 4.6[QC:1]
COR46S8	46: 8	WHOLE	< 4.9	---	< 4.9[QC:1]
COR46S9	46: 9	WHOLE	< 6.8	---	< 6.8[QC:1]

Table B2-60. Tank 241-T-104 Analytical Results: Hexamethyl Disiloxane (VOA).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids			µg/g	µg/g	µg/g
COR45K108	45: 1	WHOLE	3.1	---	3.1[QC:1]
COR45K110	45: 3	WHOLE	4.5	---	4.5[QC:1]
COR45K112	45: 5	WHOLE	2.4	---	2.4[QC:1]
COR45K114	45: 7	WHOLE	3.5	---	3.5[QC:1]
COR45K116	45: 9	WHOLE	4.4	---	4.4[QC:1]
COR46K120	46: 3	WHOLE	2.6	---	2.6[QC:1]
COR46K121	46: 5	WHOLE	3.3	---	3.3[QC:1]
COR46K122	46: 6	WHOLE	5.2	---	5.2[QC:1]
COR46K123	46: 7	WHOLE	1.6	---	1.6[QC:1]
COR46S9	46: 9	WHOLE	8.1	---	8.1[QC:1]

Table B2-61. Tank 241-T-104 Analytical Results: Methoxytrimethyl Silane (VOA).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids			µg/g	µg/g	µg/g
COR45K108	45: 1	WHOLE	3.8	---	3.8[QC:1]
COR45K110	45: 3	WHOLE	9.5	---	9.5[QC:1]
COR45K112	45: 5	WHOLE	7.6	---	7.6[QC:1]
COR45K114	45: 7	WHOLE	12	---	12[QC:1]
COR45K116	45: 9	WHOLE	18	---	18[QC:1]
COR46S2	46: 2	WHOLE	11	---	11[QC:1]
COR46K120	46: 3	WHOLE	5.7	---	5.7[QC:1]
COR46S4	46: 4	WHOLE	17	---	17[QC:1]
COR46K121	46: 5	WHOLE	6.1	---	6.1[QC:1]
COR46K122	46: 6	WHOLE	4	---	4[QC:1]
COR46K123	46: 7	WHOLE	3	---	3[QC:1]
COR46S8	46: 8	WHOLE	13	---	13[QC:1]
COR46S9	46: 9	WHOLE	21	---	21[QC:1]

Table B2-62. Tank 241-T-104 Analytical Results: Methylenechloride (VOA).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids			µg/g	µg/g	µg/g
COR45K108	45: 1	WHOLE	< 2.2	---	< 2.2[QC:1]
COR45K110	45: 3	WHOLE	< 2.7	---	< 2.7[QC:1]
COR45K112	45: 5	WHOLE	< 2.9	---	< 2.9[QC:1]
COR45K114	45: 7	WHOLE	< 3	---	< 3[QC:1]
COR45K116	45: 9	WHOLE	< 2.3	---	< 2.3[QC:1]
COR46S2	46: 2	WHOLE	< 3.3	---	< 3.3[QC:1]
COR46K120	46: 3	WHOLE	0.61	---	0.61[QC:1]
COR46S4	46: 4	WHOLE	< 3	---	< 3[QC:1]
COR46K121	46: 5	WHOLE	0.39	---	0.39[QC:1]
COR46K122	46: 6	WHOLE	0.32	---	0.32[QC:1]
COR46K123	46: 7	WHOLE	0.4	---	0.4[QC:1]
COR46S8	46: 8	WHOLE	< 2.5	---	< 2.5[QC:1]
COR46S9	46: 9	WHOLE	< 3.4	---	< 3.4[QC:1]

Table B2-63. Tank 241-T-104 Analytical Results: Toluene (VOA).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids			µg/g	µg/g	µg/g
COR45K108	45: 1	WHOLE	0.55	---	0.55[QC:1]
COR45K110	45: 3	WHOLE	0.24	---	0.24[QC:1]
COR45K112	45: 5	WHOLE	0.3	---	0.3[QC:1]
COR45K114	45: 7	WHOLE	1.1	---	1.1[QC:1]
COR45K116	45: 9	WHOLE	0.62	---	0.62[QC:1]
COR46S2	46: 2	WHOLE	0.59	---	0.59[QC:1]
COR46K120	46: 3	WHOLE	0.69	---	0.69[QC:1]
COR46S4	46: 4	WHOLE	0.53	---	0.53[QC:1]
COR46K121	46: 5	WHOLE	0.47	---	0.47[QC:1]
COR46K122	46: 6	WHOLE	0.45	---	0.45[QC:1]
COR46K123	46: 7	WHOLE	0.43	---	0.43[QC:1]
COR46S8	46: 8	WHOLE	< 2.5	---	< 2.5[QC:1]
COR46S9	46: 9	WHOLE	0.52	---	0.52[QC:1]

Table B2-64. Tank 241-T-104 Analytical Results: Trimethyl Silanol (VOA).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids			µg/g	µg/g	µg/g
COR45K108	45: 1	WHOLE	6.8	---	6.8[QC:1]
COR45K110	45: 3	WHOLE	17	---	17[QC:1]
COR45K112	45: 5	WHOLE	9.6	---	9.6[QC:1]
COR45K114	45: 7	WHOLE	12	---	12[QC:1]
COR45K116	45: 9	WHOLE	20	---	20[QC:1]
COR46S2	46: 2	WHOLE	14	---	14[QC:1]
COR46K120	46: 3	WHOLE	18	---	18[QC:1]
COR46S4	46: 4	WHOLE	17	---	17[QC:1]
COR46K121	46: 5	WHOLE	20	---	20[QC:1]
COR46K122	46: 6	WHOLE	28	---	28[QC:1]
COR46K123	46: 7	WHOLE	10	---	10[QC:1]
COR46S8	46: 8	WHOLE	13	---	13[QC:1]
COR46S9	46: 9	WHOLE	31	---	31[QC:1]

Table B2-65. Tank 241-T-104 Analytical Results: Non-Detected VOA Analytes.

Analyte	Detection Limit	Analyte	Detection Level
1,1,1-Trichloroethane	<3.4[QC:1]	Chlorobenzene	<3.4[QC:1]
1,1,2,2-Tetrachloroethane	<3.4[QC:1]	Chloroethane	<3.4[QC:1]
1,1,2-Trichloroethane	<3.4[QC:1]	Chloroform	<3.4[QC:1]
1,1-Dichloroethane	<3.4[QC:1]	Chloromethane	<6.8[QC:1]
1,1-Dichloroethene	<3.4[QC:1]	Dibromochloromethane	<3.4[QC:1]
1,2-Dichloroethane	<3.4[QC:1]	Ethylbenzene	<3.4[QC:1]
1,2-Dichloroethylene	<3.4[QC:1]	Hexone	<6.8[QC:1]
1,2-Dichloropropane	<3.4[QC:1]	Styrene	<3.4[QC:1]
2-Hexanone	<6.8[QC:1]	Tetrachloroethene	<3.4[QC:1]
2-Butanone	<3.4[QC:1]	Trichloroethene	<3.4[QC:1]
Benzene	<3.4[QC:1]	Vinyl acetate	<6.8[QC:1]
Bromodichloromethane	<3.4[QC:1]	Vinyl chloride	<6.8[QC:1]
Bromoform	<3.4[QC:1]	Xylenes (total)	<3.4[QC:1]
Bromomethane	<6.8[QC:1]	cis-1,3-Dichloropropene	<3.4[QC:1]
Carbon disulfide	<3.4[QC:1]	trans-1,3-Dichloropropen e	<3.4[QC:1]
Carbon tetrachloride	<3.4[QC:1]		

Table B2-66. Tank 241-T-104 Analytical Results: Carbonate (TIC).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	< 500	< 500	< 500[QC:2]
176		WHOLE	< 500	< 500	< 500[QC:2]
179	Core 46 Composite	WHOLE	< 500	< 500	< 500[QC:2]
180		WHOLE	< 500	< 500	< 500[QC:2]

Table B2-67. Tank 241-T-104 Analytical Results: Total organic carbon (Furnace Oxidation).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: water digest			µg/g	µg/g	µg/g
175	Core 45 Composite	WHOLE	< 550	706	< 628[QC:2]
176		WHOLE	< 550	< 550	< 550[QC:2]
179	Core 46 Composite	WHOLE	< 550	< 550	< 550[QC:2]
180		WHOLE	< 550	< 550	< 550[QC:2]
Liquids: water digest			µg/mL	µg/mL	µg/mL
204	Core 46 Composite	DL	473	429	451[QC:2,3]

Table B2-68. Tank 241-T-104 Analytical Results: Americium-241 (GEA).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			µCi/g	µCi/g	µCi/g
146	46: 2	WHOLE	0.00816	0.00994	0.00905
147		WHOLE	0.0085	0.0108	0.00965
175	Core 45 Composite	WHOLE	0.0108	0.0125	0.01165[QC:2,4,8]
176		WHOLE	0.013	0.0168	0.0149
179	Core 46 Composite	WHOLE	0.0146	0.0145	0.01455
180		WHOLE	0.0137	0.0175	0.0156
Liquids: water digest			µCi/mL	µCi/mL	µCi/mL
204	Core 46 Composite	DL	< 9.450E-04	< 9.600E-04	< 9.525E-04

Table B2-69. Tank 241-T-104 Analytical Results: Cesium-137 (GEA).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			µCi/g	µCi/g	µCi/g
146	46: 2	WHOLE	0.222	0.232	0.227
147		WHOLE	0.222	0.22	0.221
175	Core 45 Composite	WHOLE	0.195	0.198	0.1965
176		WHOLE	0.193	0.188	0.1905
179	Core 46 Composite	WHOLE	0.199	0.201	0.2
180		WHOLE	0.21	0.209	0.2095
Liquids: water digest			µCi/mL	µCi/mL	µCi/mL
204	Core 46 Composite	WHOLE	0.0758	0.0808	0.0783

Table B2-70. Tank 241-T-104 Analytical Results: Cobalt-60 (GEA).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			µCi/g	µCi/g	µCi/g
146	46: 2	WHOLE	5.780E-04	5.990E-04	5.885E-04
147		WHOLE	5.200E-04	6.560E-04	5.880E-04
175	Core 45 Composite	WHOLE	< 2.270E-04	< 2.220E-04	< 2.245E-04
176		WHOLE	< 3.000E-04	< 2.430E-04	< 2.715E-04
179	Core 46 Composite	WHOLE	< 2.290E-04	< 2.810E-04	< 2.550E-04
180		WHOLE	< 2.950E-04	< 2.470E-04	< 2.710E-04
Liquids: water digest			µCi/mL	µCi/mL	µCi/mL
204	Core 46 Composite	DL	< 1.310E-04	< 1.100E-04	< 1.205E-04

Table B2-71. Tank 241-T-104 Analytical Results: Europium-154 (GEA).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			µCi/g	µCi/g	µCi/g
146	46: 2	WHOLE	0.00224	0.00263	0.002435
147		WHOLE	0.0023	0.00249	0.002395
175	Core 45 Composite	WHOLE	< 7.200E-04	< 7.700E-04	< 7.450E-04
176		WHOLE	0.00414	0.00471	0.004425
179	Core 46 Composite	WHOLE	0.00379	0.00329	0.00354
180		WHOLE	0.00475	0.00393	0.00434
Liquids: water digest			µCi/mL	µCi/mL	µCi/mL
204	Core 46 Composite	DL	< 3.470E-04	< 3.430E-04	< 3.450E-04

Table B2-72. Tank 241-T-104 Analytical Results: Europium-155 (GEA).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			µCi/g	µCi/g	µCi/g
146	46: 2	WHOLE	0.0051	0.005	0.00505
147		WHOLE	0.00375	0.00382	0.003785
175	Core 45 Composite	WHOLE	0.00295	0.00354	0.003245
176		WHOLE	0.00429	0.00361	0.00395
179	Core 46 Composite	WHOLE	0.00269	0.00318	0.002935
180		WHOLE	0.00401	0.00308	0.003545
Liquids: water digest			µCi/mL	µCi/mL	µCi/mL
204	Core 46 Composite	WHOLE	< 4.120E-04	< 3.970E-04	< 4.045E-04

Table B2-73. Tank 241-T-104 Analytical Results: Iodine-129 (I129).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			µCi/g	µCi/g	µCi/g
175	Core 45 Composite	WHOLE	< 0.012	< 0.0119	< 0.01195
176		WHOLE	< 0.0118	< 0.0118	< 0.0118
179	Core 46 Composite	WHOLE	< 0.0261	< 0.0149	< 0.0205
180		WHOLE	< 0.0464	< 0.0127	< 0.02955

Table B2-74. Tank 241-T-104 Analytical Results: Carbon-14 (C14).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			µCi/g	µCi/g	µCi/g
175	Core 45 Composite	WHOLE	---	< 4.500E-05	< 4.500E-05[QC:2,5]
176		WHOLE	< 4.500E-05	< 4.500E-05	< 4.500E-05[QC:5]
179	Core 46 Composite	WHOLE	< 4.500E-05	< 4.500E-05	< 4.500E-05[QC:5]
180		WHOLE	< 4.400E-05	< 4.400E-05	< 4.400E-05[QC:5]

Table B2-75. Tank 241-T-104 Analytical Results: Tritium (Liq. Scin.).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			µCi/g	µCi/g	µCi/g
175	Core 45 Composite	WHOLE	< 3.360E-04	< 3.360E-04	< 3.360E-04[QC:5]
176		WHOLE	< 3.370E-04	< 3.380E-04	< 3.375E-04[QC:5]
179	Core 46 Composite	WHOLE	< 3.360E-04	< 3.370E-04	< 3.365E-04[QC:5]
180		WHOLE	< 3.31	< 3.340E-04	< 1.65517[QC:5]

Table B2-76. Tank 241-T-104 Analytical Results: Selenium-79 (Se79).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			µCi/g	µCi/g	µCi/g
175	Core 45 Composite	WHOLE	< 1.730E-04	< 16,600	< 8,300[QC:6]
176		WHOLE	< 1.670E-04	< 1.750E-04	< 1.710E-04
179	Core 46 Composite	WHOLE	< 1.370E-04	< 1.410E-04	< 1.390E-04
180		WHOLE	< 1.320E-04	< 1.290E-04	< 1.305E-04

Table B2-77. Tank 241-T-104 Analytical Results: Technetium-99 (Te).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			µCi/g	µCi/g	µCi/g
175	Core 45 Composite	WHOLE	5.950E-04	5.630E-04	5.790E-04
176		WHOLE	< 4.710E-04	< 4.630E-04	< 4.670E-04
179	Core 46 Composite	WHOLE	< 7.230E-04	< 7.590E-04	< 7.410E-04
180		WHOLE	< 7.250E-04	< 7.380E-04	< 7.315E-04

Table B2-78. Tank 241-T-104 Analytical Results: Strontium-90 (Sr).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			µCi/g	µCi/g	µCi/g
175	Core 45 Composite	WHOLE	2.33	2.35	2.34[QC:3]
176		WHOLE	2.4	2.49	2.445
179	Core 46 Composite	WHOLE	2.72	2.76	2.74[QC:4]
180		WHOLE	2.98	3.02	3

Table B2-79. Tank 241-T-104 Analytical Results: Total Beta

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			µCi/g	µCi/g	µCi/g
175	Core 45 Composite	WHOLE	6.55	6.67	6.61[QC:4]
176		WHOLE	6.87	6.98	6.925[QC:4]
179	Core 46 Composite	WHOLE	7.74	7.59	7.665[QC:4]
180		WHOLE	9.22	9.13	9.175[QC:4]

Table B2-80. Tank 241-T-104 Analytical Results: Americium-241 (Alpha Spec).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			µCi/g	µCi/g	µCi/g
175	Core 45 Composite	WHOLE	0.0183	0.0204	0.01935[QC:2,4,8]
176		WHOLE	0.0163	0.0159	0.0161[QC:4,8]
179	Core 46 Composite	WHOLE	0.0159	0.0154	0.01565
180		WHOLE	0.017	0.019	0.018

Table B2-81. Tank 241-T-104 Analytical Results: Plutonium-238 (Alpha Spec).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			µCi/mL	µCi/mL	µCi/mL
175	Core 45 Composite	WHOLE	< 0.018	< 0.0179	< 0.01795[QC:2]
176		WHOLE	< 0.018	< 0.018	< 0.018[QC:2,8]
179	Core 46 Composite	WHOLE	< 0.0179	0.018	<0.01795[QC:4,6]
180		WHOLE	< 0.0179	< 0.0178	< 0.01785
Liquids: water digest			µCi/mL	µCi/mL	µCi/mL
204	Core 46 Composite	DL	< 9.010E-05	< 9.010E-05	< 9.010E-05[QC:8]

Table B2-82. Tank 241-T-104 Analytical Results: Plutonium-239/240 (Alpha Spec).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			µCi/g	µCi/g	µCi/g
175	Core 45 Composite	WHOLE	0.141	0.15	0.1455[QC:2,4]
176		WHOLE	0.152	0.142	0.147[QC:4,8]
179	Core 46 Composite	WHOLE	0.143	0.124	0.1335[QC:4,6]
180		WHOLE	0.136	0.13	0.133
Liquids: water digest			µCi/mL	µCi/mL	µCi/mL
204	Core 46 Composite	DL	0.00844	0.00943	0.008935[QC:8]

Table B2-83. Tank 241-T-104 Analytical Results: Neptunium-237 (Np237).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			µCi/g	µCi/g	µCi/g
175	Core 45 Composite	WHOLE	< 0.0216	< 0.0215	< 0.02155[QC:4]
176		WHOLE	< 0.0108	< 0.0108	< 0.0108[QC:4]
179	Core 46 Composite	WHOLE	< 0.0269	< 0.0108	< 0.01885[QC:4]
180		WHOLE	0.137	< 0.0213	< 0.07915

Table B2-84. Tank 241-T-104 Analytical Results: Pu238 to Pu ratio (Mass Spec.).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			%	%	%
93-1807-H1	45: 9	WHOLE	0.018	0.015	0.0165[QC:4]
93-1808-H1		WHOLE	0.044	0.03	0.037[QC:4]
93-1809-H1	Core 45 Composite	WHOLE	0.003	0.004	0.0035[QC:4]
93-1810-H1		WHOLE	0.004	0.004	0.004[QC:4]
93-1811-H1	Core 46 Composite	WHOLE	0.006	0.006	0.006[QC:4]
93-1812-H1		WHOLE	0.006	0.007	0.0065[QC:4]

Table B2-85. Tank 241-T-104 Analytical Results: Pu239 to Pu ratio (Mass Spec.).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			%	%	%
93-1807-H1	45: 9	WHOLE	98.0454	98.1677	98.1065[QC:4]
93-1808-H1		WHOLE	97.4645	97.577	97.5207[QC:4]
93-1809-H1	Core 45 Composite	WHOLE	96.9134	97.0094	96.9614[QC:4]
93-1810-H1		WHOLE	96.8341	96.8423	96.8382[QC:4]
93-1811-H1	Core 46 Composite	WHOLE	96.6298	96.6803	96.6551[QC:4]
93-1812-H1		WHOLE	96.5371	96.6492	96.5931[QC:4]

Table B2-86. Tank 241-T-104 Analytical Results: Pu240 to Pu ratio (Mass Spec.).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			%	%	%
93-1807-H1	45: 9	WHOLE	1.7948	1.7279	1.76135[QC:4]
93-1808-H1		WHOLE	2.3497	2.2204	2.28505[QC:4]
93-1809-H1	Core 45 Composite	WHOLE	3.0423	2.9444	2.99335[QC:4]
93-1810-H1		WHOLE	3.132	3.1254	3.1287[QC:4]
93-1811-H1	Core 46 Composite	WHOLE	3.3115	3.2622	3.28685[QC:4]
93-1812-H1		WHOLE	3.4061	3.3003	3.3532[QC:4]

Table B2-87. Tank 241-T-104 Analytical Results: Pu241 to Pu ratio (Mass Spec.).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			%	%	%
93-1807-H1	45: 9	WHOLE	0.044	0.037	0.0405[QC:4]
93-1808-H1		WHOLE	0.073	0.059	0.066[QC:4]
93-1809-H1	Core 45 Composite	WHOLE	0.036	0.032	0.034[QC:4]
93-1810-H1		WHOLE	0.027	0.028	0.0275[QC:4]
93-1811-H1	Core 46 Composite	WHOLE	0.038	0.039	0.0385[QC:4]
93-1812-H1		WHOLE	0.054	0.065	0.0595[QC:4]

Table B2-88. Tank 241-T-104 Analytical Results: Pu242 to Pu ratio (Mass Spec.).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			%	%	%
93-1807-H1	45: 9	WHOLE	0.097	0.053	0.075[QC:4]
93-1808-H1		WHOLE	0.069	0.114	0.0915[QC:4]
93-1809-H1	Core 45 Composite	WHOLE	0.005	0.011	0.008[QC:4]
93-1810-H1		WHOLE	0.003		0.003[QC:4]
93-1811-H1	Core 46 Composite	WHOLE	0.015	0.013	0.014[QC:4]

Table B2-89. Tank 241-T-104 Analytical Results: U234 to U ratio (Mass Spec.).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			%	%	%
93-1807-H1	45: 9	WHOLE	0.008	0.006	0.007[QC:4]
93-1808-H1		WHOLE	0.008	0.011	0.0095[QC:4]
93-1809-H1	Core 45 Composite	WHOLE	0.005	0.009	0.007[QC:4]
93-1810-H1		WHOLE	0.005	0.015	0.01[QC:4]
93-1811-H1	Core 46 Composite	WHOLE	0.006	0.006	0.006[QC:4]
93-1812-H1		WHOLE	0.005	0.007	0.006[QC:4]

Table B2-90. Tank 241-T-104 Analytical Results: U235 to U ratio (Mass Spec.).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			%	%	%
93-1807-H1	45: 9	WHOLE	0.6896	0.6973	0.69345[QC:4]
93-1808-H1		WHOLE	0.6996	0.7139	0.70675[QC:4]
93-1809-H1	Core 45 Composite	WHOLE	0.6813	0.6855	0.6834[QC:4]
93-1810-H1		WHOLE	0.6782	0.6835	0.68085[QC:4]
93-1811-H1	Core 46 Composite	WHOLE	0.6746	0.6686	0.6716[QC:4]
93-1812-H1		WHOLE	0.6654	0.6583	0.66185[QC:4]

Table B2-91. Tank 241-T-104 Analytical Results: U236 to U ratio (Mass Spec.).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			%	%	%
93-1807-H1	45: 9	WHOLE	0.006	0.005	0.0055[QC:4]
93-1808-H1		WHOLE	0.003	0.009	0.006[QC:4]
93-1809-H1	Core 45 Composite	WHOLE	0.007	0.009	0.008[QC:4]
93-1810-H1		WHOLE	0.004	0.005	0.0045[QC:4]
93-1811-H1	Core 46 Composite	WHOLE	0.006	0.007	0.0065[QC:4]
93-1812-H1		WHOLE	0.007	0.009	0.008[QC:4]

Table B2-92. Tank 241-T-104 Analytical Results: U238 to U ratio (Mass Spec.).

Sample Number	Sample Location	Sample Portion	Result	Duplicate	Mean
Solids: fusion			%	%	%
93-1807-H1	45: 9	WHOLE	99.2969	99.2912	99.294[QC:4]
93-1808-H1		WHOLE	99.2894	99.2659	99.2776[QC:4]
93-1809-H1	Core 45 Composite	WHOLE	99.3065	99.2959	99.3012[QC:4]
93-1810-H1		WHOLE	99.3122	99.2963	99.3042[QC:4]
93-1811-H1	Core 46 Composite	WHOLE	99.3128	99.3182	99.3155[QC:4]
93-1812-H1		WHOLE	99.3228	99.326	99.3244[QC:4]

Table B2-93. 1996 Evaluation of Tank Headspace Flammability.[1]

Vapor	Riser 8 Breather Vent	Riser 8	Dome Space Beneath Riser 8
TOC	0 ppmv	< 2 ppmv	4 ppmv
Flammability	0 percent of LFL	0 percent of LFL	0 percent of LFL
O_2	20.9 %	20.9 %	20.9 %
NH_3	0 ppmv	< 5 ppmv	50 ppmv

Note:

[1]WHC (1996)

Table B2-94. Physical Properties of 1979 Core Sample.[1]

Core Segment	Solids Received (cm)	Bulk Density (g/mL)	Percent Moisture	Drainable Liquid (mL)
1	0	0	---	---
2	35.6	1.39	57.0	120
3	40.6	1.27	59.0	150
4	40.6	1.35	58.0	120
5	43.2	1.36	61.0	150
6	45.7	1.35	62.0	125
7	45.7	1.28	64.0	125
8	48.3	1.28	62.0	90
9	50.8	1.30	61.0	70
Composite	n/a	1.31	62.0	n/a

Notes:

n/a = not applicable

[1]Horton (1979)

Table B2-95. Chemical Characteristics of Composite of 1979 Core Sample.[1]

Component	Water Soluble (weight percent)	Water Insoluble (weight percent)
Aluminum	NR	1.2
Bismuth	BDL	1.3
Carbonate	0.12	NR
Chromium	0.02	0.1
Chloride	0.12	NR
Fluoride	0.4	1.6
Iron	NR	0.2
Mercury	NR	ID
Lanthanum	NR	ID
Manganese	NR	0.01
Nickel	0.0004	1.3
Lead	BDL	NR
Nitrate	6.9	< 1.0
Sodium	13.0	4.3
Hydroxide	pH 8.0	NR
Phosphate	1.4	7.8
Sulfate	BDL	BDL
Silicate	ID	0.8
Cadmium	NR	0.003
TOC	0.00290 g/g	0.102 g/g
^{239}Pu	1.12E-10 g/g	4.06E-06 g/g
^{241}Am	NR	2.70E-07 g/g
U^{6+}	2.64E-06 g/g	7.40E-05 g/g
$^{89/90}Sr$	7.47E-04 μCi/g	5.0 μCi/g
^{137}Cs	0.511 μCi/g	1.30 μCi/g

Notes:

NR = Not reported
ID = Incomplete data
BDL = Below detection limit

[1]Horton (1979)

B3.0 ASSESSMENT OF CHARACTERIZATION RESULTS

The purpose of this chapter is to discuss the overall quality and consistency of the current sampling results for tank 241-T-104, and to present the results of the calculation of an analytical-based mean concentration for the tank.

This section also evaluates sampling and analysis factors that may impact interpretation of the data. These factors are used to assess the overall quality and consistency of the data and to identify any limitations in the use of the data.

B3.1 FIELD OBSERVATIONS

The sampler for segment 1 for core 46 was empty and segment 1 of core 45 contained only a small amount of sample. This was most likely because of a mismeasurement of the height of the waste prior to sampling and not because of any failure of the sampling process itself. the remainder of the segments for both cores exhibited very good recovery. All samples but one (segment 7 of core 46) which contained drainable liquids were contaminated with hydrostatic head fluid (normal paraffin hydrocarbon). This complicated the SVOA and VOA analyses in that a cleanup procedure had to be performed prior to analysis by gas chromatography.

B3.2 QUALITY CONTROL ASSESSMENT

The quality control assessment of the 1992 analytical results included an evaluation of the completeness of the chain of custody forms, performance of the analyses within the required time limits, initial and continuing calibration of analytical and laboratory instruments, performance of analysis-specific quality control tests i.e., serial dilutions, appropriate standard recoveries, spike recoveries, duplicate analyses, and blanks that were performed in conjunction with the chemical analyses. All the pertinent quality control tests were conducted on the 1992 core samples, allowing a full assessment regarding the accuracy and precision of the data (Pool 1994). Hill et al. (1991) established the specific criteria for all analytes. Sample and duplicate pairs that had one or more QC results outside the specified criteria were identified by footnotes in the data summary tables. Nearly all analytes exhibited one or more quality control discrepancies, ranging from excessive holding times, to standard or spike recoveries outside the limits. A qualitative judgment was made for these discrepancies, based on the requirements of Hill et al. (1991), and further guided by Silvers (1991), Smith (1992), and Jones (1993). A large majority of the data that exhibited qualifications were deemed "estimated." These qualifications impact the data very little. Of more serious impact were the qualifications of some analytes as "rejected." The following discussion is limited to those analytes that exhibited "rejected" analytical results.

All ICP analytical results for bismuth, cerium, lanthanum, phosphorus, strontium, sulfur, tin, and zirconium and one result (TCLP leachate of sample 196) for silver were rejected because of lack of initial or continuing calibration verification. The analytical results for silver in six samples (acid digests of samples 146, 147, 175, 176, 179, and 180) were rejected for poor standard or spike recoveries. The silver results of three of those samples and one other sample were also rejected because of interference check samples (acid digests of samples 146, 147, 176, and TCLP leachate of sample 196).

The IC analyses of one sample for fluoride and one for phosphate were rejected for incorrect recovery of a matrix spike (sample 204). The ICP analytical results for two selenium samples were rejected because of poor standard recoveries (samples 175 and 176).

Instrument calibration was the cause of the rejection of the results from two samples for ^{238}Pu (samples 175 and 176), failure of matrix spikes or tracers caused the rejection of the results from one sample for ^{241}Am (sample 176), and from two samples for ^{238}Pu, $^{239/240}$Pu (sample 176 and 204), and preparation blank contamination caused the rejection of one sample for ^{238}Pu, $^{239/240}$Pu (sample 179). Total alpha results for six samples were rejected because of a lack of documentation for initial calibration and matrix spikes (samples 93-1807 through 93-1812).

In summary, the vast majority of the QC results were within the boundaries specified in the applicable documents. Other than for the "rejected" data, the discrepancies mentioned here and footnoted in the data summary tables should not impact either the validity or the use of the data. In addition, upon examination of the plutonium and total alpha results, the rejected data appear to be consistent with other non-rejected data.

B3.3 DATA CONSISTENCY CHECKS

Comparisons of different analytical methods can help to assess the consistency and quality of the data. Several comparisons were possible with the data set provided by the two core samples, including a comparison of phosphorous as analyzed by ICP with phosphate as analyzed by IC, a comparison of weight percent water by TGA with the weight percent water by gravimetry, and comparisons of the total alpha and beta activities with the sum of the alpha- and beta-emitting radionuclides. In addition, mass and charge balances were calculated to help assess the overall data consistency.

B3.3.1 Comparison of Results from Different Analytical Methods

The following data consistency checks compare the results from two different analytical methods. Agreement between the two methods strengthens the credibility of both results, whereas poor agreement may bring the reliability of the data into question. All analytical mean results were taken from tables in Section B2.0.

The analytical phosphorus mean result as determined by ICP on the water digested sample was 6,410 μg/g, which converts to 19,600 μg/g of phosphate. This compares well with the IC phosphate mean result of 17,800 μg/g. The ratio between these two phosphate results was 0.91. The analytical phosphorus mean result as determined by ICP on the fusion digested sample was 24,700 μg/g, which converts to 75,600 μg/g of phosphate. Assuming the analysis was representative of the true concentrations of phosphorus, it is possible that much of the phosphate is water insoluble. The concentration of the phosphate in the drainable liquid sample was 25,000 μg/mL (22,700 μg/g), which accounts for approximately half of the total equivalent phosphate.

The analytical sulfur mean result as determined by ICP on the acid digestion was 1,280 μg/g. This is equivalent to 3,830 μg/g sulfate. The sulfate results as measured by IC was 3,900 μg/g. The ratio of equivalent sulfate to sulfate was 0.98, a very close agreement. This is an indication that much if not all of the sulfate is water soluble.

The mean weight percent water results, as determined by TGA, for cores 45 and 46 composites were 67.1, 69.55, 64.15, and 69.55 percent respectively. This compared well with the gravimetric results for the same samples of 70.35, 70.3, 70.5, and 70.85 percent, respectively. An informal examination of the segment data for percent water by TGA and gravimetry reveal a similar agreement.

Total alpha and total beta activities can be compared to the sums of the activities of the alpha and beta emitters. The sludge mean gross alpha activity was 0.109 μCi/g. The sum of the activities of ^{241}Am and $^{239/240}$Pu was 0.157 μCi/g. The ratio of gross alpha activity to the sum of the activities of the alpha emitters was 0.69. Total beta activity was 7.59 μCi/g. The sum of the activities of the beta emitters (^{90}Sr and ^{137}Cs) was 7.77 μCi/g. The ratio of total beta to the sum of the activities of the beta emitters was 0.98. The activity of ^{90}Sr was multiplied by 2 to account for the activity of ^{90}Y, which exists in secular equilibrium with ^{90}Sr and would have been counted in the total beta measurement and not counted in the ^{90}Sr measurement. The ^{90}Sr and ^{137}Cs results were multiplied by 1.42 and 1.51, respectively, to account for detector efficiencies that were calibrated to ^{60}Co. These results are summarized in Tables B3-1 and B3-2.

Table B3-1. Total Alpha Comparison.

Analyte	Concentration (μCi/g)
$^{239/240}$Pu	0.140
^{241}Am	0.0173
Sum of alpha emitters	0.1573
Gross alpha result	0.109

Table B3-2. Total Beta Comparison.

Analyte	Concentration (μCi/g)
^{90}Sr	2.63
^{137}Cs	0.199
Sum of beta emitters[1]	7.77
Gross beta result	7.59

Note:

[1]Calculated using the equation: 1.42 x 2 x ^{90}Sr +1.51 x ^{137}Cs. The coefficients 1.42 and 1.51 account for the detector efficiencies calibrated to ^{60}Co. Factor of 2 accounts for the activity of ^{90}Y which exists in secular equilibrium with ^{90}Sr.

B3.3.2 Mass and Charge Balance

The principal objective in performing a mass and charge balance is to determine if the measurements were self-consistent. In calculating the balances, the metals and anions listed in Table B3-6 that were detected at a level greater than 1,000 μg/g were considered. With the exception of sodium, all analytes listed in Table B3-3 are assumed to exist as hydroxide, oxide, or hydroxide precipitates. All positive charge was attributed to the sodium ion.

As discussed in Section B3.3.1, a large discrepancy exists between the mean concentration of equivalent phosphate as derived from the ICP phosphorus mean and the mean concentration of phosphate as measured by IC. It is assumed that some of the extra phosphate exists as insoluble precipitates of sodium, bismuth and iron. The soluble phosphate is listed in Table B3-4 as 'excess phosphate.' The concentrations of the cationic and anionic species in Tables B3-4 and B3-5, and the percent water, were ultimately used to calculate the mass balance.

The mass balance was calculated from the formula below. The factor 0.0001 is the conversion factor from μg/g to weight percent.

$$\begin{aligned}\text{Mass balance} &= \%\ \text{water} + 0.0001 \times \{\text{total analyte concentration}\} \\ &= \%\ \text{water} + 0.0001 \times \{[Al(OH)_3] + [BiPO_4] + [CaO] + [FePO_4] + [SiO_2] \\ &\quad + [Na_3PO_4] + [Na^+] + [F^-] + [NO_3^-] + [NO_2^-] + [PO_4^{3-}] + [SO_4^{2-}]\}\end{aligned}$$

The total of the analyte concentrations calculated from the above equation is 1,010,000 μg/g. The mean weight percent water obtained from thermogravimetric analysis reported in Table B3-6 is 70.5 percent, or 705,000 μg/g. The mass balance resulting from adding the percent water to the total analyte concentration is 98.7 percent (Table B3-5).

The following equations demonstrate the derivation of total cations and total anions. The charge balance is the ratio of these two values. To derive the results as shown in the equations, all concentrations must be expressed in μg/g.

<u>Total cations</u> $\mu eq/g = [Na^+]/23.0 = 2{,}013\ \mu eq/g$

<u>Total anions</u> $\mu eq/g = [F^-]/19.0 + [NO_3^-]/62.0 + [NO_2^-]/46.0 + [PO_4^{3-}]/31.7 + [SO_4^{2-}]/48.1 = 2{,}121\ \mu eq/g.$

The charge balance obtained by dividing the sum of the positive charge by the sum of the negative charge was 0.95.

In summary, the above calculations yield reasonable results for the charge balance and the mass balance. The results for the mass balance were close to 100 percent.

Table B3-3. Cation Mass and Charge Data.

Analyte	Concentration μg/g	Assumed Species	Concentration of Assumed Species μg/g	Charge μeq/g
Aluminum	16,200	$Al(OH)_3$	46,800	0
Bismuth	18,900	$BiPO_4$	27,500	0
Calcium	1,450	CaO	2,030	0
Iron	9,020	$FePO_4$	24,300	0
Silicon	6,520	SiO_2	14,000	0
Sodium	64,500	Na_3PO_4	42,800	0
		Na^+	46,500	2,013
Total			189,900	2,013

Table B3-4. Anion Mass and Charge Data.

Analyte	Concentration µg/g	Assumed Species	Concentration of Assumed Species µg/g	Charge µeq/g
Fluoride	8,570	F^-	8,570	451
Nitrate	58,000	NO_3^-	58,000	935
Nitrite	4,240	NO_2^-	4,240	92
Excess Phosphate	17,800	PO_4^{3-}	17,800	562
Sulfate	3,900	SO_4^{2-}	3,900	81
Total			92,500	2,121

Table B3-5. Mass Balance Totals.

Totals	Concentrations µg/g	Charge µeq/g
Cation total from Table B3-3	189,900	2,013
Anion total from Table B3-4	92,500	-2,121
Weight percent water	705,000	---
Mass balance total	987,000	---
Charge balance total	---	-108

B3.4 CALCULATION OF ANALYTICAL BASED MEANS AND INVENTORY

The statistics in this section were calculated using analytical data from the most recent core sampling event of tank 241-T-104. Analysis of variance (ANOVA) techniques were used to estimate the mean, and calculate confidence limits on the mean, for each analyte that had all results above the detection limit.

The results given below are ANOVA estimates based on the data from cores 45 and 46 of tank 241-T-104. In the laboratory, two core composite samples were formed from homogenized segment samples. For analytes having all values above the detection limit, an estimate of the mean concentration and a confidence interval on the mean concentration were

calculated. The estimates are given in Table B3-6. Some analytes had a lower confidence limit less than zero. Because an actual concentration of less than zero is not possible, this lower limit was reported as zero whenever this occurred.

Table B3-6. Tank Concentration From Composite Samples. (4 Sheets)

Analyte	$\bar{y}$	$\hat{\sigma}^2(\bar{y})$	df	95% LL	95% UL
METALS	µg/g	µg/g		µg/g	µg/g
ICP.a.Al	16,200	1.41E+06	1	1,150	31,300
ICP.a.B	15.6	2.32	1	0	35.0
ICP.a.Ba	7.64	0.0756	1	4.15	11.1
ICP.a.Bi	18,900	1.22E+05	1	14,400	23,300
ICP.a.Ca	262	1380	1	0	734
ICP.a.Cd	1.69	6,380	1	0.678	2.71
ICP.a.Ce	194	92.6	1	71.8	316
ICP.a.Cr	901	863	1	527	1,270
ICP.a.Cu	12.5	0.13	1	7.86	17.0
ICP.a.Fe	9,020	76,300	1	5,510	12,500
ICP.a.K	89.0	2.85	1	67.6	110
ICP.a.Mg	103	158	1	53.1	154
ICP.a.Mn	30.6	0.413	1	22.4	38.8
ICP.a.Na	64,500	5.18E+06	1	35,600	93,400
ICP.a.Ni	11.3	3.77	1	0	36.0
ICP.a.P	24,000	2.76E+05	1	17,300	30,700
ICP.a.Pb	49.8	82.6	1	0	165
ICP.a.S	1,280	543	1	980	1,570
ICP.a.Si	1,020	21,300	1	0	2,870
ICP.a.Sn	11.6	1.10	1	0	24.9
ICP.a.Sr	96.8	26.0	1	32.0	162
ICP.a.Ti	4.56	0.067	1	1.27	7.85

Table B3-6. Tank Concentration From Composite Samples. (4 Sheets)

Analyte	$\bar{y}$	$\hat{\sigma}^2(\bar{y})$	df	95% LL	95% UL
ICP.a.Zn	23.5	2.00	1	5.55	41.5
ICP.a.Zr	67.5	463	1	0	341
ICP.f.Al	15,600	3.56E+06	1	0	39,600
ICP.f.Ba	8.58	0.0434	1	5.93	11.2
ICP.f.Bi	17,400	1.21E+06	1	3,370	31,300
ICP.f.Ca	1,450	5.89E+05	1	0	11,200
ICP.f.Ce	160	195	1	0	337
ICP.f.Cr	867	365	1	624	1,110
ICP.f.Cu	51.0	174	1	0	218
ICP.f.Fe	8,840	3.80E+05	1	1,010	16,700
ICP.f.Mg	140	436	1	0	406
ICP.f.Mn	61.8	6.42	1	29.6	94.0
ICP.f.Na	62,100	1.63E+06	1	45,800	78,300
ICP.f.P	24,700	4.57E+06	1	0	51,800
ICP.f.S	1,270	977	1	869	1,660
ICP.f.Si	6,520	33,300	1	4,200	8,830
ICP.f.Sr	99.1	13.4	1	52.6	146
ICP.f.Ti	9.67	2.07	1	0	280
ICP.f.Zn	137	2310	1	0	747
ICP.f.Zr	37.5	8.18	1	1.12	73.8
ICP.w.Al	158	163	1	0	320
ICP.w.B	11.5	0.391	1	3.53	194
ICP.w.Bi	168	195	1	0	346
ICP.w.Ca	171	141	1	20.5	322
ICP.w.Cr	144	21.4	1	85.1	203
ICP.w.Fe	80.8	33.5	1	7.22	154

Table B3-6. Tank Concentration From Composite Samples. (4 Sheets)

Analyte	$\bar{y}$	$\hat{\sigma}^2(\bar{y})$	df	95% LL	95% UL
ICP.w.K	35.9	1.53	1	20.2	51.6
ICP.w.Mg	6.06	1.76	1	0	22.9
ICP.w.Na	46,500	1.03E+06	1	33,600	59,400
ICP.w.P	6,410	45,700	1	3,690	9,120
ICP.w.S	1,280	319	1	1,060	1,510
ICP.w.Si	167	17.3	1	11.4	220
ICP.w.Sr	1.17	0.0268	1	0	3.25
ICP.w.Zr	2.45	0.0216	1	0.586	4.32
ANIONS	**µg/g**	**µg/g**		**µg/g**	**µg/g**
IC.w.Cl	670	105	1	539	800
IC.w.F	8,570	26,900	1	6,490	10,700
IC.w.NO_2	4,080	652	1	3,760	4,410
Spec.w.NO_2	4,240	2,170	1	3,650	4,830
IC.w.NO_3	58,000	5.67E+05	1	48,500	67,600
IC.w.PO_4	17,800	7.44E+05	1	6,850	28,800
IC.w.SO_4	3,900	971	1	3,500	42,900
RADIONUCLIDES[1]	**µCi/g**	**µCi/g**		**µCi/g**	**µCi/g**
GEA.f.^{241}Am	0.0142	8.10E-07	1	0.00274	0.0256
GEA.f.^{137}Cs	0.199	3.16E-05	1	0.128	0.271
GEA.f.^{155}Eu	0.00342	4.69E-08	1	6.68E-04	0.00617
f.Gross.alpha	0.109	2.26E-05	1	0.0486	0.169
f.Gross.beta	7.59	0.683	1	0	18.1
^{241}Am	0.0173	7.38E-07	1	0.00636	0.0282
$^{239/240}$Pu	0.140	0.00650	1	0.057	0.222
^{239}Pu	96.8%	0.0190%	1	95.0%	98.5%
^{240}Pu	3.19%	0.0168%	1	1.55%	4.84%

Table B3-6. Tank Concentration From Composite Samples. (4 Sheets)

Analyte	$\bar{y}$	$\hat{\sigma}^2(\bar{y})$	df	95% LL	95% UL
^{241}Pu	0.0399%	8.33E-05%	1	0%	0.156%
^{90}Sr	2.63	0.0570	1	0	5.66
U	897 μg/g	394	1	645	1,150
^{234}U	0.00725%	1.56E-06%	1	0	0.0231%
^{235}U	0.674%	5.93E-05%	1	0.577%	0.772%
^{236}U	0.00675%	6.88E-07%	1	0%	0.0173%
^{238}U	99.3%	7.42E-05%	1	99.2%	99.4%
Physical Properties					
Percent.H20	70.5	0.0400	1	68.0	73.1

Notes: LL = lower limit
UL = upper limit
df = degrees of freedom
f = fusion digestion
a = acid digestion
w = water digestion

[1]Pu isotope values are given in weight percent of total Pu. U isotope values are given in weight percent of total U.

The statistical model that describes the structure of the core composite data is

$$y_{ijk} = \mu + S_i + C_{ij} + A_{ijk},$$
$$i = 1, \ldots a,\ j = 1, \ldots b_i,\ k = 1, \ldots n_{ij},$$

where

y_{ijk} = laboratory results from the kth duplicate of the jth composite of the ith core from the tank,

μ = the grand mean of all the data,

S_i = the effect of the ith core (spatial effect),

C_{ij} = the effect of the jth composite sample from the ith core,

A_{ijk} = the analytical error associated with the kth duplicate in the jth composite from the ith core,

a = the number of cores,

b_i = the number of composite samples in the ith core, and

n_{ij} = the number of analytical results from the jth composite sample in the ith core.

For cores 45 and 46 there are two core composite samples (i.e., $b_i = 2$).

The variables S_i and C_{ij} are random effects. It is assumed that S_i, C_{ij}, and A_{ijk} are each distributed normally with mean zero and variances of $\sigma^2(S)$, $\sigma^2(C)$, and $\sigma^2(A)$, respectively. Estimates of $\sigma^2(S)$, $\sigma^2(C)$, and $\sigma^2(A)$ were obtained using Restricted Maximum Likelihood Estimation (REML). This method applied to variance component estimation is described by Harville (1977). The REML estimates were obtained using the statistics program S-Plus[1] (Statistical Sciences 1993).

The mean concentration of each analyte of interest in the tank was calculated using the following equation:

where

$$\bar{y} = \frac{1}{a}\sum_{i=1}^{a}\bar{y}_{i++} = \frac{1}{a}\sum_{i=1}^{a}\frac{\sum_{j=1}^{b_i}\sum_{k=1}^{n_{ij}} y_{ijk}}{n_{i+}} = \frac{1}{a}\sum_{i=1}^{a}\frac{\sum_{j=1}^{b_i}\sum_{k=1}^{n_{ij}}\left(\mu + S_i + C_{ij} + A_{ijk}\right)}{n_{i+}}.$$

$$\bar{y}_{i++} = \frac{\sum_{j=1}^{b_i}\sum_{k=1}^{n_{ij}} y_{ijk}}{n_{i+}} \quad \text{and} \quad n_{i+} = \sum_{j=1}^{b_i} n_{ij}.$$

This mean gives the results from each core the same weight regardless of the unbalance that may exist for a particular analyte.

[1]Trademark of Statistical Sciences, Seattle, Washington.

The variance of $\bar{y}$ is

$$V(\bar{y}) = C_1\sigma^2(S) + C_2\sigma^2(C) + C_3\sigma^2(A)$$

where

$$C_1 = \frac{1}{a}, \quad C_2 = \frac{1}{a^2}\sum_{i=1}^{a}\left[\frac{1}{n_{i+}}\right]^2\left[\sum_{j=1}^{b_i} n_{ij}^2\right], \quad C_3 = \frac{1}{a^2}\sum_{i=1}^{a}\left[\frac{1}{n_{i+}}\right].$$

Using $\hat{\sigma}^2(S)$, $\hat{\sigma}^2(C)$, and $\hat{\sigma}^2(A)$ (REML variance component estimates), an estimated variance of $\bar{y}$ is

$$\hat{\sigma}^2(\bar{y}) = C_1\hat{\sigma}^2(S) + C_2\hat{\sigma}^2(C) + C_3\hat{\sigma}^2(A).$$

The approximate degrees of freedom used for $\hat{\sigma}^2(\bar{y})$ is the number of cores with data minus one.

The lower and upper 95% limits (95% LL and 95% UL respectively) on the mean concentration are

$$95\%\ LL = \bar{y} - t_{.025}\sqrt{\hat{\sigma}^2(\bar{y})} \quad \text{and} \quad 95\%\ UL = \bar{y} + t_{.025}\sqrt{\hat{\sigma}^2(\bar{y})}$$

where $t_{0.025}$ is the 0.025 quantile from a Student's t-distribution with one degree of freedom ($t_{0.025}=12.706$) for a one-sided 95 percent confidence interval.

Core recoveries for the two core samples (cores 45 and 46) taken from tank 241-T-104 were very good. The segment recoveries for each core are shown in Table B3-7. For both core samples there was nearly 100% segment recovery for most segments. Based on waste levels, segment 1 of each core was expected to be a partial segment with, at most, 6.4 cm (2.5 in.) of sample. Therefore, the expected recovery for segment 1 was only about 13%. Because sample recovery was high, any bias (due to incomplete recovery) in the results given in Table B3-6 should be minimal.

Table B3-7. Tank 241-T-104 Core Recoveries.

Core	Segment Number								
	1	2	3	4	5	6	7	8	9
45	5%	90%	100%	75%	95%	75%	94%	100%	100%.
46	0%	100%	60%	100%	100%	65%	98%	90%	100%

Sample-based inventory estimates can be calculated by multiplying the means in Table B3-6 by an estimate of the total sludge mass. Some analytes had data from fusion, acid, and water digestions. In such cases, the fusion digestion results were generally used to calculate the inventory because fusion digestion usually results in more complete dissolution than acid digestion. Acid digestion results should be used for potassium because the fusion digestion was performed by fusing the sample with potassium hydroxide. Acid digestion results should also be used for boron, cadmium, lead, and tin because the higher dilutions of the fusion digestion resulted in high detection limits for these analytes.

The volume of the sludge in tank 241-T-104 at the time of sampling was 1,673 kL (442 kgal). The samples that were recovered had density measurements that ranged from 1.24 g/mL to 1.42 g/mL with an average of 1.285 g/mL. Using the average density and the estimated sludge volume, an estimate of the total mass of sludge is 2.15×10^6 kg. The inventory values (with the exception of the Pu and U isotopic results) can be calculated by multiplying the mean concentration values in Table B3-6 by this number. For the Pu and U isotopic results given as percent of total Pu or U, the percentage results need to be ratioed to the $^{239/240}Pu$ or total U results to calculate concentration as μCi/g or μg/g before multiplying by the mass of the sludge.

Since the time of core sampling, saltwell liquid has been removed from the tank. Because solids have not been removed from the tank and because the core composite used to generate the concentrations in Table B3-6 did not include drainable liquids in the core samples, the present tank sludge inventory should be close to that calculated in the manner described in the previous paragraph. To provide a lower bound on the tank inventory, one can assume that the saltwell liquid pumped has the same composition as the drainable liquid that was analyzed, calculate the inventory of waste pumped from the tank (by multiplying the drainable liquid concentrations by the 317 kL pumped), and subtract this amount from the initial tank inventory.

B4.0 APPENDIX B REFERENCES

DeLorenzo, D. S., J. H. Rutherford, D. J. Smith, D. B. Hiller, K. W. Johnson, 1994, *Tank Characterization Reference Guide*, WHC-SD-WM-TI-648, Rev. 0A, Westinghouse Hanford Company, Richland, Washington.

Dukelow, G. T., J. W. Hunt, H. Babad, and J. E. Meacham, 1995, *Tank Safety Screening Data Quality Objective*, WHC-SD-WM-SP-004, Rev. 2, Westinghouse Hanford Company, Richland, Washington.

Harville, D. A., 1977, "Maximum Likelihood Approaches to Variance Component Estimation and to Related Problems," *Journal of the American Statistical Association*, 72:358, pp. 324-340.

Hill, J. G., W. I. Winters, B. C. Simpson, J. W. Buck, P. J. Chamberlain, and V. L. Hunter, 1991, *Waste Characterization Plan for the Hanford Site Single-Shell Tanks*, WHC-EP-0210, Rev. 3, Westinghouse Hanford Company, Richland, Washington.

Horton, J. E., 1979, *Physical and Chemical Characterization of Tank 104-T*, (internal letter 65124-79-017 to D. J. Flesher, November 13), Rockwell Hanford Operations, Richland, Washington.

Jones, T. E., 1993, *Pacific Northwest Laboratory Single-Shell Tank Waste Characterization Project (16021) and Single-Shell Tank Safety Analysis Project (19091) Technical Project Plan* , Pacific Northwest Laboratory Richland, Washington.

Pool, K. N., 1994, *Single-Shell Tank Waste Characterization Tank 241-T-104, Cores 45 and 46*, WHC-SD-WM-DP-032, Rev. 0A, Westinghouse Hanford Company, Richland, Washington.

Silvers, K. L., 1991, *Sampling and Analysis of Ten Single-Shell Tanks, Statement of Work*, WHC-SOW-91-0006, Rev. 1, Westinghouse Hanford Company, Richland, Washington.

Smith, H. E., 1992, *Technical Project Plan - Response to WHC-SOW-91-0006 for the 222-S Analytical Laboratory*, WHC-SD-CP-TP-070, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

Statistical Sciences, 1993, *S-PLUS Reference Manual Version 3.2*, StatSci, a division of MathSoft, Inc., Seattle, Washington.

WHC, 1996, *T-104 Riser Preparation*, Work Package WS-95-00291, Westinghouse Hanford Company, Richland, Washington.

This page left blank intentionally.

APPENDIX C

STATISTICAL ANALYSIS FOR ISSUE RESOLUTION

This page intentionally left blank.

APPENDIX C

STATISTICAL ANALYSIS FOR ISSUE RESOLUTION

In Appendix C, the analyses required for the applicable data quality objective (DQO) reports for tank 241-T-104 are performed. Specifically, statistical and other numerical manipulations required in the DQO reports are performed and documented in this appendix. The analyses required for tank 241-T-104 are documented in the following sections:

- **Section C1**: Statistical analysis supporting the Safety Screening DQO (Dukelow et al. 1995). Specifically, confidence intervals were needed to support the plutonium (criticality) threshold limit.
- **Section C2**: References for Appendix C.

C1.0 STATISTICS FOR SAFETY SCREENING DQO

The safety screening DQO (Dukelow et al. 1995) defines acceptable decision confidence limits in terms of one-sided 95 percent confidence intervals on the mean for each subsample. In this appendix, one-sided confidence limits supporting the safety screening DQO are calculated for tank 241-T-104. All data considered in this section are taken from the final laboratory data package for the 1992 core sampling event for tank 241-T-104 (Pool 1994).

Confidence intervals were computed for each sample number from tank 241-T-104 analytical data. The sample numbers and confidence intervals are provided in Table C1-1.

The upper limit (UL) of a one-sided 95 percent confidence interval for the mean is

$$\hat{\mu} + t_{(n-1,0.95)} * \sqrt{\frac{\hat{\sigma}^2}{n}}$$

where $\hat{\mu}$ is the arithmetic mean of the data, n is the number of observations, $\hat{\sigma}^2$ is the estimate of the variance of the data, and $t_{(n-1,0.95)}$ is a quantile from Student's t distribution with $n-1$ degrees of freedom and 0.95 confidence.

For the tank 241-T-104 data (per sample number), n is two and $t_{(1,0.95)}$ is 6.314.

The upper limit of the one-sided 95 percent confidence interval for each sample number based on the total alpha data is listed in Table C1-1. Each confidence interval can be used to make the following statement. If the upper limit is less than 47.7 μCi/g, then one would reject the null hypothesis that the total alpha is greater than or equal to 47.7 μCi/g at the 0.05 level of significance. The upper limit of 47.7 μCi/g was calculated from the 1 g/L plutonium limit, using a measured density of 1.29 g/mL (Pool 1994), and assuming that all the plutonium is ^{239}Pu.

Table C1-1. One-Sided 95 Percent Confidence Interval Upper Limits for Total Alpha for Tank 241-T-104.

Sample Number	Sample Location	Sample Portion	$\hat{\mu}$ (μCi/g)	$\hat{\sigma}^2/n$	UL (μCi/g)
175	Core 45 composite	WHOLE	0.102	1.00E-06	0.108
176		WHOLE	0.1065	2.50E-07	0.110
179	Core 46 composite	WHOLE	0.118	9.00E-06	0.137
180		WHOLE	0.1095	2.50E-07	0.113

Note:

UL = Upper limit

Confidence intervals were not performed on the differential scanning calorimetry (DSC) data, because no exotherms were detected.

C2.0 APPENDIX C REFERENCES

Dukelow, G. T., J. W. Hunt, H. Babad, and J. E Meacham, 1995, *Tank Safety Screening Data Quality Objective*, WHC-SD-WM-SP-004, Rev. 2, Westinghouse Hanford Company, Richland, Washington.

Pool, K. N., 1994, *Single-Shell Tank Waste Characterization Tank 241-T-104, Cores 45 and 46*, WHC-SD-WM-DP-032, Rev. 0-A, Westinghouse Hanford Company, Richland, Washington.

APPENDIX D

EVALUATION TO ESTABLISH BEST-BASIS INVENTORY FOR TANK 241-T-104

This page intentionally left blank.

APPENDIX D

EVALUATION TO ESTABLISH BEST-BASIS INVENTORY FOR TANK 241-T-104

An effort is underway to provide waste inventory estimates that will serve as standard characterization source terms for the various waste management activities (Hodgson and LeClair 1996). As part of this effort, an evaluation of available chemical information for tank 241-T-104 was performed, and a best-basis inventory was established. This work, detailed in the following sections, follows the methodology that was established by the standard inventory task.

D1.0 CHEMICAL INFORMATION SOURCES

The data package for single-shell tank 241-T-104 (Pool 1994) provided characterization results from the most recent core sampling event for this tank; the results are presented in Appendix B. Two core samples were obtained and analyzed. Jensen et al. (1994) summarizes the results from the statistical analysis of data from two core composites. Estimates of the spatial variance, compositing variance, and the spatial variance for the core composite data were provided. Both the analytical and systematic error of the tank 241-T-104 core samples were presented. Mean concentrations and confidence intervals are presented in Appendix B.

Component inventories at the time of sampling were calculated by multiplying the mean concentration of an analyte (presented in Table B3-6) by the density of the waste (1.29 g/mL) and the volume of the sludge at the time of sampling (1,673 kL [442 kgal]). Sample-based inventories listed in Tables D2-1 and D2-2 are derived from the mean concentrations in Table B3-6 and the Hanford defined waste (HDW) model developed at Los Alamos National Laboratory (Agnew et al. 1996b). The HDW model (Agnew et al. 1996b) provides tank content estimates, in terms of component concentrations and inventories. The HDW model estimated the tank inventory using the total waste volume of 1,684 kL (445 kgal), consisting of 1,673 kL (442 kgal) of sludge and 11.4 kL (3 kgal) of supernate, reported by Hanlon (1992) at the time of sampling and prior to the start of saltwell pumping. The sampling-based inventory is based upon the sludge volume (1,673 kL [442 kgal]) only. The supernatant contributes a small amount to the total tank inventory.

Table D2-1. Sample- and Historical Tank Content-Based Inventory Estimates for Nonradioactive Components. (2 sheets)

Analyte	Sample Inventory Estimate (kg)	HDW[1] Inventory Estimate (kg)	Analyte	Sample Inventory Estimate (kg)	HDW[1] Inventory Estimate (kg)
Al	33,500	31,700	Ni	22,600	126
Ag	NR	NR	NO_2	8,770	17,300
As	NR	NR	NO_3	125,000	41,200
Ba	18.4	NR	OH	NR	84,200
Be	NR	NR	oxalate	NR	0.0036
Bi	37,400	20,300	Pb	NR	0.87
Ca	3,120	3,900	Pd	NR	NR
Ce	344	NR	P as PO_4	162,000	170,000
Cd	3.63	NR	Pt	NR	NR
Cl	1,440	847	Rh	NR	NR
Co	NR	NR	Ru	NR	NR
Cr	1,860	371	Sb	NR	NR
Cr^{+3}	NR	371	Se	NR	NR
Cr^{+6}	NR	NR	Si	14,000	2,630
Cs	NR	NR	SO_4	8,390	7,930
Cu	110	NR	Sr	213	0.0014
F	18,400[3]	5,760	Te	NR	NR
Fe	19,000	22,400	CO_3	NR	5,970
FeCN/CN	NR	NR	Th	NR	NR
formate	NR	NR	Tl	NR	NR
Hg	NR	26.2	TOC	NR	NR
K	191	205	U_{TOTAL}	1,930	254
La	NR	0.0066	V	NR	NR
Mg	303	NR	W	NR	NR
Mn	133	0.99	Zn	295	NR

Table D2-1. Sample- and Historical Tank Content-Based Inventory Estimates for Nonradioactive Components. (2 sheets)

Analyte	Sample Inventory Estimate (kg)	HDW[1] Inventory Estimate (kg)	Analyte	Sample Inventory Estimate (kg)	HDW[1] Inventory Estimate (kg)
Mo	NR	NR	Zr	80.6	1,280
Na	134,000	159,000	H_2O (wt%)	70.5	72.7
Nd	NR	NR	density (kg/L)	1.29	1.25
NH_3	NR	15.5			

Notes:

HDW = Hanford Defined Waste
NR = Not reported

[1]Agnew et al. (1996b)

Table D2-2. Sample- and Historical Tank Content-Based Inventory Estimates for Radioactive Components.

Analyte	Sample Inventory Estimate (Ci)	HDW[1] Inventory Estimate (Ci)	Analyte	Sample Inventory Estimate (Ci)	HDW[1] Inventory Estimate (Ci)
^{14}C	NR	NR	^{237}Np	NR	NR
^{90}Sr	5,650	930	$^{239/240}Pu$	300	27
^{99}Tc	NR	NR	^{241}Am	37.2	NR
^{129}I	NR	NR	Total α	234	NR
^{137}Cs	428	38,100	Total β	16,300	NR
^{155}Eu	7.35	NR			

Notes:

HDW = Hanford Defined Waste
NR = Not reported

[1]Agnew et al. (1996b)

Since the time of core sampling, saltwell liquid has been removed from the tank. Because solids have not been removed from the tank and because the core composite used to generate the concentrations in Table B3-6 did not include drainable liquids recovered from the core samples, the present tank sludge inventory should be close to that calculated in the manner described above. To provide a lower bound on the tank inventory, one could assume that the saltwell liquid pumped has the same composition as the drainable liquid that was analyzed, calculate the inventory of waste pumped from the tank (by multiplying the drainable liquid concentrations by the 317 kL (83.8 kgal) pumped as of September 30, 1996), and subtracting this amount from the initial tank inventory.

D2.0 COMPARISON OF COMPONENT INVENTORY VALUES

Sample-based inventories derived from analytical concentration data and HDW model inventories are compared in Tables D2-1 and D2-2. The sludge volume used to generate the sample-based inventory is 1,673 kL (442 kgal) (Hanlon 1992). The HDW model included the 11.4 kL (3 kgal) of supernate present prior to saltwell pumping, for a total tank waste volume of 1,684 kL (445 kgal) (Hanlon 1992). The mean sludge density, which includes interstitial liquid, used to calculate the sample-based component inventories is 1.29 g/mL (the mean of the values in Table B2-4). The means from the ICP fusion digestion analyses were used for aluminum, beryllium, bismuth, cerium, chromium, iron, phosphorus, silicon, magnesium, manganese, and sodium. The ICP acid digestion means were used for cadmium, nickel, and potassium and the IC water digestion means were used for chloride, fluoride, nitrite, and nitrate. The HDW model density for the sludge and total waste is estimated to be 1.25 g/mL (approximately 3 percent less than the measured density). Note the significant differences between the sample-based and HDW model inventories for several of the bulk components, e.g., bismuth, fluoride, nitrate, nitrite, uranium, zirconium, and silicon.

D3.0 REVIEW AND EVALUATION OF COMPONENT INVENTORIES

The following evaluation of tank contents is performed to identify potential errors and/or missing information that would influence the sample-based and HDW model component inventories.

D3.1 PROCESS KNOWLEDGE

Tank 241-T-104 began receiving first cycle decontamination (1C) waste in March 1946 and was filled in August 1946. There was no cascading at this time. Nearly 3,400 kL (900 kgal) of 1C waste was received by tank 241-T-104 in a series of additions in 1948 and

1949 (Jungfleisch 1984). The tank was already full, so this waste all cascaded to tanks 241-T-105 and 241-T-106. Since it was the primary tank in the cascade, most of the solids in the 1C waste settled in tank 241-T-104. When the supernate was removed from the tanks in the cascade and sent to cribs in 1953, tank 241-T-104 held 1,410 kL (372 kgal) of solids (Anderson 1990). A discrepancy in the historical records is found here. Up to this time, 5,360 kL (1,440 kgal) of waste additions (all pre-1951 1C) to tank 241-T-104 are documented (Jungfleisch 1984). For 5,360 kL of waste to deposit 1,410 kL of solids in a tank, the waste stream must be at least 26 percent solids. Pre-1951 1C waste, however, is expected to be only about 13.7 percent solids (Agnew et al. 1996a). Agnew, et al. (1996a) estimates a slightly larger waste addition volume of 6,386 kL (1,687 kgal), though not enough to account for all the solids estimated by Anderson (1990).

In 1954, a series of additions of 1C waste to tank 241-T-104 brought 3,900 kL (1,030 kgal) of waste into the tank (Jungfleisch 1984). (Agnew, et al. [1996a] estimates a volume of 6,711 kL [1,773 kgal].) This 1C waste included coating waste and stack drainage that were combined with 1C waste after May 1951 (Agnew et al. 1996a). Coating waste was produced from the dissolution of aluminum fuel cladding in a sodium nitrate-sodium hydroxide solution. Much of this waste was cascaded to tank 241-T-105; some of the waste was pumped to other tanks. This was the last time tank 241-T-104 received waste. A supernate transfer out of the tank brought the volume to 1,830 kL (483 kgal). Saltwell pumping and settling of the waste brought the tank to its current waste volume of 1,408 kL (372 kgal). Table D3-1 uses transaction records to present an estimate of the total volume of waste that has been received by tank 241-T-104 (Jungfleisch 1984). These volumes differ somewhat from the estimates of Agnew et al. (1996a) which were presented in Appendix A (Table A3-1).

Table D3-1. Estimated Total Volume of Waste Types Received By Tank 241-T-104.[1]

Waste Type	Estimated Volume[2]
1C 1944 to 1951	5,360 kL (1,415 kgal)
1C 1951 to 1956[3]	3,900 kL (1,030 kgal)

Notes:

[1]Jungfleisch (1984)

[2]Total volume is greater than 2,010 kL (530 kgal) because waste was routinely pumped from tank 241-T-104 and also cascaded to tank 241-T-105.

[3]Coating waste and stack drainage were added to 1C waste after May 1951.

D3.2 HISTORICAL ESTIMATION OF THE CONTENTS OF TANK 241-T-104

A preliminary estimate of the waste constituents in tank 241-T-104 can be developed by reviewing historical data for the tank. This section uses the process history of the tank and past sampling efforts to develop an estimation of the contents of tank 241-T-104.

D3.3 PROCESS HISTORY ESTIMATION

Section D3.1 describes the history of tank 241-T-104 as repeated filling of the tank with 1C decontamination waste and cascading to tank 241-T-105 or pumping of the supernate. There is no record of any waste type other than 1C waste being received by the tank. However, the composition of 1C waste varied. As discussed in Section D3.1, coating waste and stack drainage were included in 1C waste after May 1951.

D3.4 CONTRIBUTING WASTE TYPES

Waste volumes (kgal)	Agnew et al. (1996b):	1946 through 1956, 1C, 13,100kL (3,460 kgal)
	Hill et al. (1995):	1C

Note: 1C, first-cycle decontamination bismuth phosphate waste, that includes bismuth phosphate cladding waste (CW).

In the bismuth phosphate process, the 1C waste stream was neutralized with aluminum cladding waste. This neutralized waste stream, which contains approximately 7 percent CW, also is commonly referred to as 1C. Cascade overflows from tank 241-T-104 to tanks 241-T-105 and 241-T-106. Tables D2-1 and D2-2 compare sampling inventory estimates with HDW inventory estimates.

D3.5 TECHNICAL FLOWSHEET INFORMATION

Technical flowsheet (Kupfer et al. 1997) information for the bismuth phosphate 1C stream, which includes bismuth phosphate CW, is provided in Table D3-2. The comparative HDW model defined 1C waste stream is also provided in Table D3-2. The HDW model 1C defined waste stream appears to be a "second generation" flowsheet waste stream, derived by Jungfleisch (1984) for an earlier modeling effort (the Tracks Radioactive Components model).

Table D3-2. Technical Flowsheet and Los Alamos National Laboratory Defined Waste Streams (Hanford Defined Waste Model).

Analyte	Flowsheet[1] 1C[2] (M)	Defined Waste 1C[3] (M)
NO_3	1.44	0.588
NO_2	0.0577	0.174
SO_4	0.0631	0.062
Bi	0.0115	0.014
Fe	0.0315	0.046
Si	0.0312	0.038
U	0.000963	0.0008
Al	0.0826	0.233
$Cr^{+3/+6}$	0.00306	0.0062
Ce	0.000193	0
PO_4	0.258	0.334
Zr	0.000296	0.004
F	0.170	0.228
Na	2.17	2.17

Notes:

[1]This flowsheet stream includes Bismuth phosphate cladding waste in the 1C bismuth phosphate waste.

[2]Bismuth phosphate process flowsheet.

[3]Agnew et al. (1996b).

D3.6 EVALUATION OF COMPONENT INVENTORIES

Reference inventories of certain components in tank 241-T-104 were estimated using an engineering assessment that is based on a set of simplified assumptions. The inventories were then compared with the tank 241-T-104 sample-based inventories and the HDW model inventories. The assumptions and observations for the engineering assessment were based on best technical judgement pertaining to parameters that can significantly influence tank inventories. These parameters include: 1) correct prediction of contributing waste types and correct relative proportions of the waste types; 2) accurate predictions of model flowsheet

conditions, fuel processed, and waste volumes; 3) accurate prediction of partitioning of components; 4) accurate predictions of physical parameters such as density, percent solids, void fraction (porosity), etc. By using this evaluation, the assumptions can be modified as necessary to provide a basis for identifying potential errors and/or missing information that could influence the sampling- and model-based inventories. Following are the simplified assumptions and observations used for the evaluation.

- Components listed in the technical flowsheets summarized in Kupfer et al. (1997) and Table D3-2 were used for the evaluation.

- Tank waste mass is calculated using the tank volume listed in Hanlon (1992) prior to the start of saltwell pumping.

- All bismuth, iron, silicon, cerium, and uranium precipitate as water insoluble components. These assumptions are based on known chemistry of the components in alkaline solutions. Chromium was assumed to precipitate as $Cr(OH)_3$ or $Cr_2O_3(XH_2O)$ in alkaline media.

- Sodium, nitrate, nitrite, phosphate, sulfate, aluminum, and fluoride are assumed to partition between the liquid and solid phases based on known chemical solubilities and properties of compounds in alkaline solutions.

- No radiolysis of nitrate to nitrite and no additions of nitrite to the waste for corrosion purposes are factored in this independent assessment.

- Only the 1C bismuth phosphate waste streams which includes bismuth phosphate CW, contributed to solids formation.

D3.6.1 Solids Concentration Factor and Partition Factors for First Cycle Bismuth Phosphate Waste in Tank 241-T-104

One method for estimating a component inventory for a particular waste type in a tank (e.g., 1C waste) is to derive a concentration factor (CF) for that component. This approach was used to estimate inventories in tank 241-T-104. Concentration factors are a means of reconciling process-based information and sample-based information for particular waste types. The CF is derived by dividing the concentration of a component found in the tank samples by the concentration of that component in the neutralized process waste stream (i.e., flowsheet concentrations in Table D3-2). The CF for components of a defined waste are best determined if the tank contains only one waste type (e.g., only 1C waste in tank 241-T-104) and when abundant representative analytical data are available. The relative concentrations of components expected to precipitate essentially 100 percent to the waste solids (e.g., bismuth, iron, and uranium) should be approximately proportional to the respective flowsheet concentrations for those components; i.e., these components should exhibit nearly the same CFs. If this is the case, it can generally be concluded that the sample data are consistent

with the flowsheet basis, and thus, are quite representative of the tank contents. Since the CFs are often consistent for the same waste type in different tanks, inventories for components in tanks that do not have samples can be estimated if it is known that the defined waste is indeed present in the tank, and the volume of the defined waste is known or can be predicted.

It was noted in Assumption 3 that this evaluation assumes bismuth as well as iron, silicon, uranium, cerium, and chromium precipitate nearly 100 percent from the neutralized waste. The assumption for bismuth is based on sludge and supernatant analyses performed on typical Hanford Site tank wastes and is consistent with known chemistry for bismuth phosphate and for bismuth in alkaline solutions. The following procedure is used to calculate the CF for bismuth in tank 241-T-104. From Table D2-1, the analytical-based inventory for bismuth is 33,000 kg, which corresponds to a bismuth concentration in the solids of 0.107 M. The flowsheet concentration for bismuth is 0.0115 M (Table D3-2). The CF_{Bi} is:

$$\frac{0.107 \text{ moles Bi/L}}{0.0115 \text{ moles Bi/L}} = 9.3$$

The silicon and cerium that are expected to fully precipitate from 1C waste have CFs of 9.6 and 7.6, respectively, for tank 241-T-104. This variation for precipitated components is considered to be quite small and provides a high degree of confidence that the tank sample is representative of waste produced by the 1C flowsheet. However, the CFs for iron and uranium are approximately 7 and 5, respectively, which could indicate some partitioning of these components (see Section D3.7.2).

The CFs can be quite different for different waste types. For example, the CF based on bismuth for the bismuth phosphate process 224 waste is 95, and for second-cycle bismuth phosphate waste the CF is approximately 20.

Once the CFs for fully precipitated components for a waste type are determined, the sample analysis can be used to establish how other components such as sulfate or phosphate partition between solids and supernatants. Concentration factors for components not expected to precipitate 100 percent can be ratioed to CF_{Bi} to obtain the partitioning factors (PFs) for those components. The PF for any component N, defined as CF_N/CF_{Bi}, is the fraction of N partitioned to the sludge.

Thus the PF for phosphate (tank 241-T-104) is:

$$\frac{CF_{PO4}}{CF_{Bi}} = \frac{4.0}{9.3} = 0.43$$

Using this method, the estimated PFs for other components for 1C waste based on tank 241-T-104 are as follows when using a CF of 9.3 for fully precipitated components:

Na:	0.17	Al:	0.97	SO_4:	0.09	PO_4:	0.43
NO_3:	0.09	NO_2:	0.21	F:	0.37		

Several anomalies are seemingly apparent, however, when considering Assumptions 3 and 4 defined earlier in Section D3.7. The PF for aluminum is surprisingly high; i.e., based on the analytical data, it could be concluded that this component is essentially fully precipitated. As noted earlier, it was also unexpected that both iron and uranium apparently partition between the solids and supernatant. Possible explanations for these unexpected conclusions are summarized in Section D3.7.2.

The calculated CFs and PFs for tank 241-T-104 provide significant confidence that the analytical data for the tank is quite representative of the tank contents and could be used as a basis for component inventories. This is substantiated by the following:

- CFs for components in tank 241-T-104 that are expected to fully precipitate are quite consistent, which indicates that the sample likely represents the 1C flowsheet basis (Table D3-32) for the waste.

- The PFs indicate reasonable partitioning of components based on experience and knowledge of the typical chemical behavior of the components in alkaline media.

D3.6.2 Inventory of Components Assumed to Precipitate 100 Percent

The following calculations provide estimates (rounded) of tank 241-T-104 inventories for components assumed to precipitate 100 percent based on a bismuth CF of 9.3.

Fe: $0.032 \text{ moles Fe}/L_{1C} \times 9.3_{CF(1C)} \times 442 \text{ kgal} \times 3{,}785 \text{ L/kga} \times 55.85 \text{ g/mole Fe} \times \text{kg}/1{,}000 \text{ g} = 27{,}800 \text{ kg}$

Similarly,

Si: 13,680 kg

Zr: 420 kg

Ce: 420 kg

U: 3,580 kg

Cr: 2,490 kg

Estimated inventories from this evaluation for components assumed to fully precipitate are compared with sample and HDW model-based inventories in Table D3-3. Observations regarding these inventories are provided by component in the following text.

Waste composition estimates for some tanks also can be developed from process flowsheets, fuel production, and waste transaction records. Tank 241-T-104, as the first tank in a three-tank cascade, is known to have received 1C and CW waste from T Plant from the first quarter of 1945 through the third quarter of 1954. The composition of this waste can be estimated from a spreadsheet analysis of the bismuth phosphate flowsheet, T Plant fuel production records, and waste status and transaction record summaries (WSTRSs) for this tank. Altogether, tank 241-T-104 received 13,096 kL (3,460 kgal) of 1C and CW waste from T Plant. The equivalent metric tons of uranium (MTU) can be estimated by multiplying the MTUs processed each quarter by the total fraction of 1C/CW waste sent to tank 241-T-104. Based on this approach, tank 241-T-104 received 978.14 MTUs of equivalent 1C and CW waste. For insoluble components such as bismuth, cerium, iron, silicon, and zirconium and semi-soluble components such as aluminum, chromium, and phosphate, these values can be easily converted into equivalent waste inventory estimates for the three tank cascade. The results are summarized in Table D3-4, together with sample- and HDW model-derived estimates for tank 241-T-104.

Table D3-3. Comparison of Selected Component Inventory Estimates for Tank 241-T-104 Waste.

Component	This Evaluation (kg)[1]	Sample-Based (kg)	HDW Model (kg)
Bi	37,400	37,400	20,300
Ce	420	344	NR
Cr	2,490	1,860	371
Si	13,680	14,000	2,630
Fe	27,800	19,000	22,400
U	3,580	1,930	254
Zr	420	80.6	1,280

Notes:

NR = Not reported.

[1]Based on assumptions defined in Section D3.7 and calculations in Section D3.7.1.

Table D3-4. Comparisons Based on Fuel Production.

Components	1C/CW Waste Sent to Tanks 241-T-104/T-105/ T-106 (kg)	Tank 241-T-104 Sample Inventory (kg)	Tank 241-T-104 HDW Model Inventory (kg)
Al	32,278	33,500	31,700
Bi	35,213	37,400	20,300
Ce	390	344	NR
Cr	2,348	1,860	371
Fe	25,431	19,000	22,400
Si	12,911	14,000	7,930
PO_4	353,109	162,000	170,000
Zr	391	80.6	1,280

Note:

HDW = Hanford defined waste

Bismuth. The bismuth inventory based on the core sample data is almost twice that predicted by the HDW model. The 1C defined waste from the HDW model does not differ significantly from the 1C flowsheet basis given in Table D3-2. Although the HDW model assumes that only 73 percent of the bismuth in the 1C waste stream precipitates, this does not account for all of the discrepancy. The CFs for other components that are expected to fully precipitate are quite consistent with those for bismuth, which indicates that the sample is likely representative of the waste produced by the bismuth phosphate process 1C flowsheet. Examination of process flowsheets, fuel production records, and waste transaction records provides evidence that less than 37,400 kg of bismuth may be in the tank. This agrees well with the sample inventory and the sample based inventory is considered to be the best basis for bismuth.

Chromium. This inventory assessment predicts the total chromium content to be fairly close to that based on the sample analysis. However, these values are approximately 5 to 7 times higher than those predicted by the HDW model. The HDW model assumes that none of the chromium precipitated in the 1C stream (i.e., the only chromium contribution to the solids is from the interstitial liquids associated with the solids). Additionally, because the chromium was added primarily as chromium (III) in the bismuth phosphate process, it is expected that the majority of the chromium will precipitate as $Cr(OH)_3$ or $Cr_2O_3(XH_2O)$.

Iron. The iron inventory predicted by this assessment is approximately 45 percent higher than the sample-based inventory. This assessment assumed that the iron would fully precipitate; however, some parititioning is likely either by loss as fine particles or (less likely) approximately 30 percent of the iron is soluble. The sample-based inventory is thus considered the best basis. The HDW inventory is slightly less than that for the sample-based inventory, although it assumes that approximately 96 percent of the iron precipitates.

Aluminum. The sample-based inventory and HDW model estimate are comparable. This assessment assumed that some aluminum would partition to the supernatant; however, the sample-based inventory for tank 241-T-104 indicates that essentially all of the aluminum precipitates. It is not surprising that most of the aluminum in 1C waste would partition to the solids. There is historical evidence that wastes from the bismuth phosphate process were made alkaline to an approximate pH of only 9, which would promote precipitation of the metal hydroxide. If the waste was neutralized to a higher pH (e.g., 12), there is significant dissolution of the hydroxide with conversion to soluble sodium aluminate.

Sodium. Based on the sample analysis of tank 241-T-104, approximately 17 percent of the sodium partitions to the solids. This is somewhat lower than observed for tank 241-BX-112, which also contains 1C waste, which may indicate that some B saltcake is present in tank 241-BX-112 as predicted by the HDW model.

Silicon. The silicon inventory predicted by this assessment is approximately equal to the sample-based inventory. The silicon inventory was estimated based on the CF for bismuth. As previously mentioned, the CFs for components expected to fully precipitate should be approximately the same if the samples are representative of the waste results from the 1C bismuth phosphate process. It is concluded in the assessment that the sample-based inventory is reasonably close to the predicted inventory. The HDW model-based inventory is significantly lower than the sample-based inventory. The apparent explanation is that this assessment assumes that all silicon precipitates, while the HDW model assumes that only approximately 10 percent of the silicon precipitates.

Fluoride. The sample-based inventory for fluoride is approximately three times higher than the HDW model inventory. The analytical data show that a major portion of the fluoride is partitioned to the solids. This is consistent with analyses for tank 241-BX-112. The HDW model assumes that no fluoride precipitates with the solids although some remains with the interstitial liquid associated with the solids.

Uranium. The uranium inventory predicted by this assessment is approximately twice the sample-based inventory. As stated previously, it is concluded that some of the uranium partitions to the supernatant and interstitial liquid, likely as soluble uranate, but most remains with the solids. The sample-based inventory is approximately eight times higher than the HDW model-based inventory. The HDW model assumes that no uranium precipitates but that some is associated with the solids in the interstitial liquid.

Nitrate. The sample-based inventory is approximately three times higher than predicted by the HDW model. It is surprising that the analytical-based inventory for nitrate is three times higher than that predicted by the HDW model.

Nitrite. The sample-based inventory for nitrite is approximately two times higher than predicted by the HDW model. The sample-based inventory indicates that 21 percent of the nitrite added in the 1C bismuth phosphate process partitioned to the solids. This partitioning was expected based on the high solubility of nitrite in the alkaline solutions.

Phosphate. The sample-based inventory for phosphate is within 3 percent of that predicted by the HDW model. Analytical data indicate that a significant portion of the phosphate in 1C waste partitions to the solids. The HDW model also assumes that much of the phosphate partitions.

Sulfate. The HDW model-based inventory is approximately equal to that based on the samples. The sample-based inventory for sulfate indicates that less than ten percent of the sulfate in 1C waste partitions to the solids. The HDW model predicts that all sulfate will remain soluble and will be present only in the interstitial liquids associated with the solids.

D4.0 DEFINE THE BEST-BASIS AND ESTABLISH COMPONENT INVENTORIES

Information about chemical, radiological, and/or physical properties is used to perform safety analyses, engineering evaluations, and risk assessment activities associated with waste management activities, as well as regulatory issues. These activities include overseeing tank farm operations and identifying, monitoring, and resolving safety issues associated with these operations and with the tank wastes. Disposal activities involve designing equipment, processes, and facilities for retrieving wastes and processing them into a form that is suitable for long-term storage. Chemical and radiological inventory information is generally derived using three approaches: 1) component inventories are estimated using the results of sample analyses; 2) component inventories are predicted using the HDW model based on process knowledge and historical information; or 3) a tank-specific process estimate is made based on process flowsheets, reactor fuel data, essential material usage, and other operating data. Not surprisingly, the information derived from these different approaches is often inconsistent.

An effort is underway to provide waste inventory estimates that will serve as the standard characterization for the various waste management activities (Hodgson and LeClair 1996). As part of this effort, an evaluation of available chemical information for tank 241-T-104 was performed, including the following:

- Data from two 1992 core samples
- An inventory estimate generated by the HDW model (Agnew et al. 1996b)
- Evaluation of the 1C/CW flowsheet and MTU comparisons.

Based on this evaluation, a best-basis inventory was developed. In general, the sample-based TCR results were preferred when they were reasonable and consistent with other results.

The best-basis inventory for tank 241-T-104 is presented in Tables D4-1 and D4-2.

Table D4-1. Best-Basis Inventory Estimates for Nonradioactive Components in Tank 241-T-104 (November 19, 1996).[1] (2 Sheets)

Analyte	Total Inventory (kg)	Basis (S, M, or E)
Al	33,500	S
Bi	37,400	S
Ca	3,120	S
Cl	1,440	S
TIC as CO_3	5,970	M_H
Cr	1,860	S
F	18,400	S
Fe	19,000	S
Hg	26.2	M_H
K	191	S
La	0.0066	M_H
Mn	133	S
Na	134,000	S
Ni	22,600	S
NO_2	8,770	S
NO_3	125,000	S
OH	NR	
Pb	0.87	M_H
P as PO_4^2	162,000	S
Si	14,000	S
S as SO_4	8,390	S
Sr	213	S

Table D4-1. Best-Basis Inventory Estimates for Nonradioactive Components in Tank 241-T-104 (November 19, 1996).[1] (2 Sheets)

Analyte	Total Inventory (kg)	Basis (S, M, or E)
TOC	NR	
U_{TOTAL}	1,930	S
Zr	80.6	S

Notes:

S = Sample-based
M_H = Hanford Defined Waste model-based
E = Engineering assessment-based
NR = Not reported

[1]Based on 1992 core sample (see Appendix B)
[2]ICP much higher than IC

Table D4-2. Best-Basis Inventory Estimates for Radioactive Components in Tank 241-T-104 (November 19, 1996).[1]

Analyte	Total Inventory (Ci)	Basis (S, M_H, or E)
^{90}Sr	5,650	S
^{137}Cs	428	S
^{155}Eu	7.35	S
^{234}U	0.140 kg	S
^{235}U	13.0 kg	S
^{236}U	0.130 kg	S
^{238}U	1920 kg	S
^{239}Pu	269	S
^{240}Pu	32.5	S
^{241}Am	30.5	S
^{241}Pu	184	S

Notes:

S = Sample-based
M_H = Hanford Defined Waste model-based
E = Engineering assessment-based

[1]Based on 1992 core sample (see Appendix B)

D5.0 APPENDIX D REFERENCES

Agnew, S. F., R. A. Corbin, T. B. Duran, K. A. Jurgensen, T. P. Ortiz, and B. L. Young, 1996a, *Waste Status and Transaction Record Summary for the Northwest Quadrant*, WHC-SD-WM-TI-669, Rev. 1, Westinghouse Hanford Company, Richland, Washington.

Agnew, S. F., J. Boyer, R. A. Corbin, T. B. Duran, J. R. FitzPatrick, K. A. Jurgensen, T. P. Ortiz, and B. L. Young, 1996b, *Hanford Tank Chemical and Radionuclide Inventories: HDW Model Rev. 3*, Los Alamos National Laboratory, Los Alamos, New Mexico.

Anderson, J. D., 1990, *A History of the 200 Area Farms*, WHC-MR-0132, Westinghouse Hanford Company, Richland, Washington.

Hanlon, B. M., 1992, *Tank Farm Surveillance and Waste Status Summary Report for September 1992*, WHC-EP-0182-54, Westinghouse Hanford Company, Richland, Washington.

Hill, J. G., G. S. Anderson, and B. C. Simpson, 1995, *The Sort on Radioactive Waste Type Model: A Method to Sort Single-Shell Tanks into Characteristic Groups*, PNL-9814, Rev. 2, Pacific Northwest National Laboratory, Richland, Washington.

Hodgson, K. M, and M. D. LeClair, 1996, *Work Plan for Defining a Standard Inventory Estimate for Wastes Stored in Hanford Site Underground Tanks*, WHC-SD-WM-WP-311, Rev. 1, Lockheed Martin Hanford Corporation, Richland, Washington.

Jensen, L., R. D. Cromar, and S. R. Wilmarth, 1994, *Statistical Characterization Report for Single-Shell Tank 241-T-104*, WHC-SD-WM-TI-658, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

Jungfleisch, F. M., 1984, *TRAC: Preliminary Estimation of the Waste Inventories in Hanford Tanks Through 1980, Transaction File*, SD-WM-TI-057, Rev. 0, Rockwell Hanford Operations, Richland, Washington.

Kupfer, M. J., A. L. Boldt, B. A. Higley, K. M. Hodgson, L. W. Shelton, R. A. Watrous, S. L. Lambert, D. E. Place, R. M. Orme, G. L. Borsheim, N. G. Colton, M. D. LeClair, R. T. Winward, and W. W. Schulz, 1997, *Standard Inventories of Chemical and Radionuclides in Hanford Site Tank Wastes*, HNF-SD-WM-TI-740, Rev. 0, Lockheed Martin Hanford Corporation, Richland, Washington.

Pool, K. N., 1994, *Single-Shell Tank Waste Characterization Tank 241-T-104, Cores 45 and 46*, WHC-SD-WM-DP-032, Rev. 0A, Westinghouse Hanford Company, Richland, Washington.

APPENDIX E

BIBLIOGRAPHY FOR TANK 241-T-104

This page intentionally left blank.

APPENDIX E

BIBLIOGRAPHY FOR TANK 241-T-104

Appendix E provides a bibliography of information that supports the characterization of tank 241-T-104. This bibliography represents an in-depth literature search of all known information sources that provide sampling, analysis, surveillance, and modeling information, as well as processing occurrences associated with tank 241-T-104 and its respective waste types.

The references in this bibliography are separated into three broad categories containing references broken down into subgroups. These categories and their subgroups are listed below.

I. NON-ANALYTICAL DATA

- Ia. Models/Waste Type Inventories/Campaign Information
- Ib. Fill History/Waste Transfer Records
- Ic. Surveillance/Tank Configuration
- Id. Sample Planning/Tank Prioritization
- Ie. Data Quality Objectives/Customers of Characterization Data

II. ANALYTICAL DATA - SAMPLING OF TANK WASTE AND WASTE TYPES

- IIa. Sampling of tank 241-T-104

III. COMBINED ANALYTICAL/NON-ANALYTICAL DATA

- IIIa. Inventories using both Campaign and Analytical Information
- IIIb. Compendium of Existing Physical and Chemical Documented Data Sources

This bibliography is broken down into the appropriate sections of material to use, with an annotation at the end of each reference describing the information source. Where possible, a reference is provided for information sources. A majority of the information listed below may be found in the Westinghouse Hanford Company Tank Characterization Resource Center.

I. NON-ANALYTICAL DATA

Ia. Models/Waste Type Inventories/Campaign Information

Anderson, J. D., 1990, *A History of the 200 Area Tank Farms*, WHC-MR-0132, Westinghouse Hanford Company, Richland, Washington.

- Document contains single-shell tank fill history and primary campaign/waste type information up to 1981.

Jungfleisch, F. M. and B. C. Simpson, 1993, *Preliminary Estimation of the Waste Inventories in Hanford Tanks Through 1980*, WHC-SD-WM-TI-057, Rev. 0A, Westinghouse Hanford Company, Richland, Washington.

- A model based on process knowledge and radioactive decay estimations using ORIGEN for different compositions of process waste streams assembled for total, solution, and solids compositions per tank. Assumptions about waste/waste types and solubility parameters/constraints are also given.

Schneider, K. J., 1951, *Flow Sheet and Flow Diagrams of Precipitation Separations Process*, HW-23043, General Electric Company, Richland, Washington.

- Document contains compositions of first concentration cycle waste before transfer to 200 East Area waste tanks.

Ib. Fill History/Waste Transfer Records

Agnew, S. F., R. A. Corbin, T. B. Duran, K. A. Jurgensen, T. P. Ortiz, and B. L. Young, 1996, *Waste Status and Transaction Record Summary for the Northwest Quadrant of the Hanford 200 East Area*, WHC-SD-WM-TI-669, Rev. 1, Los Alamos National Laboratory, Los Alamos, New Mexico.

- Document contains spreadsheets depicting all available data on tank additions/transfers.

Anderson, J. D., 1990, *A History of the 200 Area Tank Farms*, WHC-MR-0132, Westinghouse Hanford Company, Richland, Washington.

- Document contains single-shell tank fill history and primary campaign/waste type information up to 1981.

Wicks, J. H., 1996, *Saltwell Pumping of Tank 241-T-104*, (internal letter 9651183 to A. B. Sidpara, March 15), Westinghouse Hanford Company, Richland, Washington.

- Document states intention to pump the saltwell of tank 2451-T-104, and lists some of the flammable gas safeguards in place.

Ic. Surveillance/Tank Configuration

Alstad, A. T., 1993, *Riser Configuration Document for Single-Shell Waste Tanks*, WHC-SD-RE-TI-053, Rev. 9, Westinghouse Hanford Company, Richland, Washington.

- Document shows tank riser locations in relation to tank aerial view as well as a description of riser and its contents.

Kummerer, M., 1992, *Near Term Safety Study of Interim Stabilization of Watch List Tanks*, WHC-SD-WM-RPT-044, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

- The document estimates the expected tank inventories after interim stabilization and compares them against Watch List criteria.

Kummerer, M., 1995, *Topical Report on Heat Removal Characteristics of Waste Storage Tanks*, WHC-SD-WM-SARR-010, Rev. 1, Westinghouse Hanford Company, Richland, Washington.

- Document estimates the expected tank heat content based on tank temperatures.

Lipnicki, J., 1996, *Waste Tank Risers Available for Sampling*, WHC-SD-WM-TI-710, Rev. 3, Westinghouse Hanford Company, Richland, Washington.

- Document gives an assessment of all riser locations for each tank; however, not all tanks are included/completed. Also included is an estimate of what risers are available for sampling.

Tran, T. T., 1993, *Thermocouple Status Single-Shell and Double-Shell Waste Tanks*, WHC-SD-WM-TI-533, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

- Document contains information about the thermocouple status in single- and double-shell tanks.

Id. Sample Planning/Tank Prioritization

Brown, T. M., J. W. Hunt, and T. J. Kunthara, 1996, *Tank Waste Characterization Basis*, WHC-SD-WM-TA-164, Rev. 2, Westinghouse Hanford Company, Richland, Washington.

- Document that summarizes the technical basis for characterizing the waste in the tanks and assigns a priority number to each tank.

Creed, R. F., *Test Plan for Carbonylation of 241-T-104 Waste Materials*, WHC-SD-WM-TP-194, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

- Document describes the process of carbonylation as a method of pretreating waste to remove iron and nickel.

Grimes, G. W., 1977, *Hanford Long-Term Defense High-Level Waste Management Program Waste Sampling and Characterization Plan*, RHO-CD-137, Rockwell Hanford Operations, Richland, Washington.

- Early characterization planning document.

Hill, J. G., W. I. Winters, B. C. Simpson, J. W. Buck, P. J. Chamberlain, and V. L. Hunter, 1991, *Waste Characterization Plan for the Hanford Single-Shell Tanks*, WHC-EP-0210, Rev. 3, Westinghouse Hanford Company, Richland, Washington.

- Document provides sampling and analysis requirements for several single-shell tanks, including tank 241-T-104.

Kelly, S. E., 1991, *Single and Double Shell Tanks for Push Mode Sampling (Rev. 1)*, (internal letter 72200-91-016 to N. W. Kirch, March 19), Westinghouse Hanford Company, Richland, Washington.

- Letter provides an assessment of tanks based on waste types, waste groupings, photographs of the waste surface, and previous waste sampling information, and lists tanks for a which a high percent recovery could be expected with the push mode core sampling method.

Jones, T. E., 1992, *Pacific Northwest Laboratory Single-Shell Tank Waste Characterization Project (16021) and Single-Shell Tank Safety Analysis Project (19091) Technical Project Plan* , Pacific Northwest National Laboratory Richland, Washington.

- Document provides Pacific Northwest Laboratory 325 Laboratory plans for analyzing core samples from several single-shell tanks, including tank 241-T-104, in response to Silvers (1991) below.

Silvers, K. L., 1991, *Sampling and Analysis of Ten Single-Shell Tanks, Statement of Work*, WHC-SOW-91-0006, Rev. 1, Westinghouse Hanford Company, Richland, Washington.

- Document provides request to laboratories to perform tank core sample analyses in accordance with Hill, et al. (1991) above.

Smith, H. E., 1992, *Technical Project Plan - Response to WHC-SOW-91-0006 for the 222-S Analytical Laboratory*, WHC-SD-CP-TP-070, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

- Document provides Westinghouse Hanford Company 222-S Laboratory plans for analyzing core samples from several single-shell tanks, including tank 241-T-104, in response to Silvers (1991) above.

Winkelman, W. D., J. W. Hunt, and L. J. Fergestrom, 1996, *FY 1997 Tank Waste Analysis Plan*, WHC-SD-WM-PLN-120, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

- Document contains Tri-Party Agreement (see Ecology et al. 1993 listing in Section 5.0) requirement-driven TWRS Characterization Program information and a list of tanks addressed in fiscal year 1997.

Ie. Data Quality Objectives (DQO) and Customers of Characterization Data

Dukelow, G. T., J. W. Hunt, H. Babad, and J. E. Meacham, 1995, *Tank Safety Screening Data Quality Objective*, WHC-SD-WM-SP-004, Rev. 2, Westinghouse Hanford Company, Richland, Washington.

- Most recent version of DQO used to determine if tanks are under safe operating conditions.

Hodgson, K. M, and M. D. LeClair, 1996, *Work Plan for Defining a Standard Inventory Estimate for Wastes Stored in Hanford Site Underground Tanks*, WHC-SD-WM-WP-311, Rev. 1, Westinghouse Hanford Company, Richland, Washington.

- Defines method for selecting data and method for best-basis inventory.

Kupfer, M. J., W. W. Schultz, G. L. Borsheim, S. J. Eberlein, B. C. Simpson, and J. T. Slankas, 1994, *Strategy for Sampling Hanford Site Tank Wastes for Development of Disposal Technology*, WHC-SD-WM-TA-154, Westinghouse Hanford Company, Richland, Washington.

- Document provides basis for selection of tanks for disposal needs.

Slankas, T. J., M. J. Kupfer, and W. W. Schulz, 1995, *Data Needs and Attendant Data Quality Objectives for Tank Waste Pretreatment and Disposal*, WHC-SD-WM-DQO-022, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

- Documents the needs of the pretreatment function within TWRS.

II. ANALYTICAL DATA - SAMPLING OF TANK WASTE AND WASTE TYPES

IIa. Sampling of tank 241-T-104

Horton, J. E., 1979, *Physical and Chemical Characterization of Tank 104-T*, (internal letter 65124-79-017 to D. J. Flesher, November 13), Rockwell Hanford Operations, Richland, Washington.

- Internal letter provides analyses of core sample from 1979 sampling event. These results are also summarized in Mitchell (1980) and Bratzel (1980) below.

Mitchell, M. E., 1980, *Radionuclide Data on Radioactive Waste Tank Samples*, (internal letter 65453-080-133 to J. R. Wetch, April 22), Rockwell Hanford Operations, Richland, Washington.

- Internal letter summarizes results of radionuclide analyses for sludge samples including those from the 1979 core sample from tank 241-T-104 documented in Horton (1979) above.

Pool, K. N., 1994, *Single-Shell Tank Waste Characterization Tank 241-T-104, Cores 45 and 46*, WHC-SD-WM-DP-032, Rev. 0-A, Westinghouse Hanford Company, Richland, Washington.

- Document contains sample analyses from 1992 tank 241-T-104 core sampling event.

WHC, 1996, *T-104 Riser Preparation*, Work Package WS-95-00291, Westinghouse Hanford Company, Richland, Washington.

- Work package contains results of tank headspace measurements made in February 1996. Vapor measurements made were flammability, total organic carbon, oxygen, and ammonia.

III. COMBINED ANALYTICAL/NON-ANALYTICAL DATA

IIIa. Inventories from Campaign and Analytical Information

Agnew, S. F., J. Boyer, R. A. Corbin, T. B. Duran, J. R. Fitzpatrick, K. A. Jurgensen, T. P. Ortiz, and B. L. Young, 1996, *Hanford Tank Chemical and Radionuclide Inventories: HDW Rev. 3*, LA-UR-96-858, Rev. 0, Los Alamos National Laboratory, Los Alamos, New Mexico.

- Document contains waste type summaries as well as primary chemical compound/analyte and radionuclide estimates for sludge, supernatant, and solids.

Allen, G. K., 1976, *Estimated Inventory of Chemicals Added to Underground Waste Tanks, 1944 - 1975*, ARH-CD-601B, Atlantic Richfield Hanford Company, Richland, Washington.

- Document contains major components for waste types, and some assumptions. Purchase record are used to estimate chemical inventories.

Allen, G. K., 1975, *Hanford Liquid Waste Inventory As Of September 30, 1974*, ARH-CD-229, Atlantic Richfield Hanford Company, Richland, Washington.

- Document contains major components for waste types, and some assumptions.

Brevick, C. H., L. A. Gaddis, and E. D. Johnson, 1996, *Historical Tank Content Estimate for the Northwest Quadrant of the Hanford 200 Areas*, WHC-SD-MW-ER-351, Rev. 1, Westinghouse Hanford Company, Richland, Washington.

- Document contains summary information from the supporting document as well as in-tank photo collages and the solid composite inventory estimates Rev. 0 and Rev. 0A.

Brevick, C. H., L. A. Gaddis, and W. W. Pickett, 1995, *Supporting Document for the Historical Tank Content Estimate for T Tank Farm*, WHC-SD-WM-ER-320, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

- Document contains summary tank farm and tank write-ups on historical data and solid inventory estimates as well as appendices for the data. The appendices contain the following information: Appendix C - Level History AutoCAD sketch; Appendix D - Temperature Graphs; Appendix E - Surface Level Graph; Appendix F, pg F-1 - Cascade/ Drywell Chart; Appendix G - Riser Configuration Drawing and Table; Appendix I - In-Tank Photos; and Appendix K - Tank Layer Model Bar Chart and Spreadsheet.

Hartley, S. A., G. Chen, C. A. Lopresti, T. A. Ferryman, A. M. Liebetrau, K. M. Remund, and S. A. Allen, 1996, *A Comparison of Historical Tank Content Estimates (HTCE) Model, Rev. 3, and Sample-Based Estimates*, PNNL-11429, Pacific Northwest National Laboratory, Richland, Washington.

- Document presents the results of a statistical comparison between sampling-based tank inventory estimates and those developed using the Hanford Defense Waste model.

Hill, J. G., G. S. Anderson, and B. C. Simpson, 1995, *The Sort of Radioactive Waste Type Model: A Method to Sort Single-Shell Tanks into Characteristic Groups*, PNL-9814, Rev. 2, Pacific Northwest National Laboratory, Richland, Washington.

- Document describes a method of grouping single-shell tanks according to the amounts and types of wastes each received.

Remund, K. M., and B. C. Simpson, 1996, *Hanford Waste Tank Grouping Study*, PNNL-11433, Pacific Northwest National Laboratory, Richland, Washington.

- Document summarizes Hanford Tank Grouping Study efforts in fiscal year 1996. Tanks are grouped into classes with similar waste properties using analytical data.

Schmittroth, F. A., 1995, *Inventories for Low-Level Tank Waste*, WHC-SD-WM-RPT-164, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

- Document presents tank waste inventory estimates for tanks containing low-level wastes.

Shelton, L. W., 1996, *Chemical and Radionuclide Inventory for Single and Double Shell Tanks*, (internal letter 74A20-96-30 to D. J. Washnefelder, February 28), Westinghouse Hanford Company, Richland, Washington.

- Letter contains a tank inventory estimate based on analytical information.

Shelton, L. W., 1995, *Chemical and Radionuclide Inventory for Single and Double Shell Tanks*, (internal letter 75520-95-007 to R. M. Orme, August 8), Westinghouse Hanford Company, Richland, Washington.

- Letter contains a tank inventory estimate based on analytical information.

Shelton, L. W., 1995, *Radionuclide Inventories for Single and Double Shell Tanks*, (internal letter 71320-95-002 to F. M. Coony, February 14), Westinghouse Hanford Company, Richland, Washington.

- Letter contains a tank inventory estimate based on analytical information.

IIIb. Compendium of data from other sources physical and chemical

Agnew, S. F., and J. G. Watkin, 1994, *Estimation of Limiting Solubilities for Ionic Species in Hanford Waste Tank Supernates*, LAUR-94-3590, Los Alamos National Laboratory, Los Alamos, New Mexico.

- Document gives solubility ranges used for key chemical and radionuclide components based on supernatant sample analyses.

Bratzel, D. R., 1980, *Evaluation of Waste Storage Tank Physical and Chemical Characterization Data*, (internal letter 65453-80-265, to J. M. Jungfleisch, September 18), Rockwell Hanford Operations, Richland, Washington.

- Internal letter summarizes results of radionuclide analyses for sludge samples including those from the 1979 core sample from tank 241-T-104 documented in Horton (1979) above.

Brevick, C. H., L. A. Gaddis, and E. D. Johnson, 1995, *Tank Waste Source Term Inventory Validation, Vols. I & II.*, WHC-SD-WM-ER-400, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

- Document contains a quick reference to sampling information in spreadsheet or graphical form for 23 chemicals and 11 radionuclides for all the tanks.

Colton, N. G., 1996, *Status Report: Pretreatment Chemistry Evaluation - Wash and Leach Factors for the Single-Shell Tank Waste Inventory*, PNNL-11290, Pacific Northwest National Laboratory, Richland, Washington.

- Document summarizes results of washing and leach studies performed on tank wastes, including tank 241-T-104, in support of tank waste pretreatment development.

Hanlon, B. M., 1996, *Waste Tank Summary Report for Month Ending September, 1996*, WHC-EP-0182-102, Westinghouse Hanford Company, Richland, Washington.

- These documents contain a monthly summary of fill volumes, Watch List tanks, occurrences, integrity information, equipment readings, equipment status, tank location, and other miscellaneous tank information.

Harmon, H. D., 1992, *Evaluation of High Total Organic Carbon Results in 1979 Data from Tanks 241-TY-106 and 241-T-104*, (letter 9253912 to R. E. Gerton, U. S. Department of Energy, Richland Operations Office, June 8), Westinghouse Hanford Company, Richland, Washington.

- Letter cites evaluation performed in Winters (1992) below and states that the 1970 analyses of tank 241-TY-106 and 241-T-104 core samples incorrectly indicated that the tanks belonged on the Organic Watch List.

Hodgson, K. M., *Evaluation of Hanford Tanks for Trapped Gas*, WHC-SD-WM-ER-526, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

- Document reports the evaluations of the high-level waste storage tanks for trapped flammable gas, following the methodology given in *Methodology for Flammable Gas Evaluations*, WHC-SD-WM-TI-724, Rev. 1. The evaluations estimate the headspace concentrations of flammable gases as a percentage of the lower flammability limit.

Husa, E. I., 1993, *Hanford Site Waste Storage Tank Information Notebook*, WHC-EP-0625, Westinghouse Hanford Company, Richland, Washington.

- Document contains in-tank photos as well as summaries on the tank description, leak detection system, and tank status.

Husa, E. I., 1995, *Hanford Waste Tank Preliminary Dryness Evaluation*, WHC-SD-WM-TI-703, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

- Document gives assessment of relative dryness between tanks.

Jensen, L., R. D. Cromar, and S. R. Wilmarth, 1994, *Statistical Characterization Report for Single-Shell Tank 241-T-104*, WHC-SD-WM-TI-658, Rev. 0, Westinghouse Hanford Company, Richland, Washington.

- Document contains the statistical analysis of data from two core samples obtained from tank 241-T-104 in 1992.

Jungfleisch, F. M., 1980, *Hanford High-Level Defense Waste Characterization - A Status Report*, RHO-CD-1019, Rockwell Hanford Operations, Richland, Washington.

- Document provides status of the characterization effort and provides core sample analytical results, including results of the 1979 core sample from tank 241-T-104 documented in Horton (1979) above.

Klem, M. J., 1990, *Total Organic Concentration of Single-Shell Tank Waste*, (internal letter 82316-90-032 to R. E. Raymond, April 27), Westinghouse Hanford Company, Richland, Washington.

- Letter summarizes total organic carbon concentrations for a number of single-shell tanks, including tank 241-T-104.

Richardson, D. C., 1993, *Total Inorganic Carbon Content Tank 241-T-104*, (letter 9350907 to R. E. Gerton, U. S. Department of Energy, Richland Operations Office, February 15), Westinghouse Hanford Company, Richland, Washington.

- Letter provides to DOE-RL and evaluation of tank 241-T-104 total organic carbon results and provides justification for not including the tank on the Organic Watch List.

Van Vleet, R. J., 1993, *Radionuclide and Chemical Inventories for the Single-Shell Tanks*, WHC-SD-WM-TI-565, Rev. 1, Westinghouse Hanford Company, Richland, Washington.

- Document provides an estimate of radionuclide and chemical concentrations for each single-shell tank using sampling data and TRAC model estimates.

Winters, W. I., 1992, *Evaluation of High Total Organic Carbon (TOC) Results on 1979 Data Reports from Tanks TY-106 and T-104*, (internal letter 12200-A092-034 to J. D. Hopkins, April 24), Westinghouse Hanford Company, Richland, Washington.

- Letter evaluates high total organic carbon results reported for tank 241-T-104 core samples taken in 1979 and tank 241-TY-106 core samples and concludes that the data are questionable. These conclusions were transmitted from Westinghouse Hanford Company to the U. S. Department of Energy, Richland Operations Office in Harmon (1992) above.

9713530.2902

DISTRIBUTION SHEET

To	From	Page 1 of 4
Distribution	Data Assessment and Interpretation	Date 02/03/97
Project Title/Work Order		EDT No. N/A
Tank Characterization Report for Single-Shell Tank 241-T-104, HNF-SD-WM-ER-372, Rev. 1		ECN No. ECN-635429

Name	MSIN	Text With All Attach.	Text Only	Attach./ Appendix Only	EDT/ECN Only
OFFSITE					
Sandia National Laboratory P.O. Box 5800 MS-0744, Dept. 6404 Albuquerque, NM 87815					
D. Powers		X			
Nuclear Consulting Services Inc. P. O. Box 29151 Columbus, OH 43229-01051					
J. L. Kovach		X			
Chemical Reaction Sub-TAP P.O. Box 271 Lindsborg, KS 67456					
B. C. Hudson		X			
Tank Characterization Panel Senior Technical Consultant Contech 7309 Indian School Road Albuquerque, NM 87110					
J. Arvisu		X			
SAIC 20300 Century Boulevard, Suite 200-B Germantown, MD 20874					
H. Sutter		X			
555 Quince Orchard Rd., Suite 500 Gaithersburg, MD 20878					
P. Szerszen		X			

9713530.2903

DISTRIBUTION SHEET

To	From	Page 2 of 4
Distribution	Data Assessment and Interpretation	Date 02/03/97
Project Title/Work Order		EDT No. N/A
Tank Characterization Report for Single-Shell Tank 241-T-104, HNF-SD-WM-ER-372, Rev. 1		ECN No. ECN-635429

Name	MSIN	Text With All Attach.	Text Only	Attach./ Appendix Only	EDT/ECN Only
Los Alamos Laboratory CST-14 MS-J586 P. O. Box 1663 Los Alamos, NM 87545					
S. F. Agnew		X			
Los Alamos Technical Associates					
T. T. Tran	B1-44	X			
Ogden Environmental 101 East Wellsian Way Richland, WA 99352					
R. J. Anema		X			
CH2M Hill P. O. Box 91500 Bellevue, WA 98009-2050					
M. McAfee		X			
Tank Advisory Panel 102 Windham Road Oak Ridge, TN 37830					
D. O. Campbell		X			
ONSITE					
Department of Energy - Richland Operations					
J. F. Thompson	S7-54	X			
W. S. Liou	S7-54	X			
J. A. Poppiti	S7-54	X			
N. W. Willis	S7-54	X			

9713530.2904

DISTRIBUTION SHEET

To	From	Page 3 of 4
Distribution	Data Assessment and Interpretation	Date 02/03/97
Project Title/Work Order		EDT No. N/A
Tank Characterization Report for Single-Shell Tank 241-T-104, HNF-SD-WM-ER-372, Rev. 1		ECN No. ECN-635429

Name	MSIN	Text With All Attach.	Text Only	Attach./ Appendix Only	EDT/ECN Only
DE&S Hanford, Inc.					
R. J. Cash	S7-14	X			
W. L. Cowley	R2-54	X			
G. L. Dunford	A2-34	X			
G. D. Johnson	S7-14	X			
J. E. Meacham	S7-14	X			
Fluor Daniel Northwest					
J. L. Stroup	S3-09	X			
Lockheed Martin Hanford, Corp.					
K. M. Hodgson	H0-34	X			
T. J. Kelley	S7-21	X			
N. W. Kirch	R2-11	X			
L. M. Sasaki	R2-12	X			
B. C. Simpson	R2-12	X			
ERC (Environmental Resource Center)	R1-51	X			
Tank Characterization Resource Center	R2-12	5			
Lockheed Martin Services, Inc.					
B. G. Lauzon	R1-08	X			
Central Files	A3-88	X			
EDMC	H6-08	X			
Numatec Hanford Corporation					
J. S. Hertzel	H5-61	X			
D. L. Lamberd	H5-61	X			
Pacific Northwest Laboratory					
J. R. Gormsen	K7-28	X			
A. F. Noonan	K9-91	X			
Rust Federal Services of Hanford, Inc.					
C. T. Narquis	T6-16	X			

9713530.2905

DISTRIBUTION SHEET

To	From	Page 4 of 4
Distribution	Data Assessment and Interpretation	Date 02/03/97
Project Title/Work Order		EDT No. N/A
Tank Characterization Report for Single-Shell Tank 241-T-104, HNF-SD-WM-ER-372, Rev. 1		ECN No. ECN-635429

Name	MSIN	Text With All Attach.	Text Only	Attach./ Appendix Only	EDT/ECN Only
SGN Eurisys Services Corp.					
D. B. Engelman	L6-37	X			

A-6000-135 (01/93) WEF067